

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other

2. NAME OF OPERATOR
Amoco Production Company

3. ADDRESS OF OPERATOR
501 Airport Drive, Farmington, NM 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 990' FNL x 1580' FWL
AT TOP PROD. INTERVAL: Same
AT TOTAL DEPTH: Same


16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

(other) Spud and Set Casing

SUBSEQUENT REPORT OF:



5. LEASE
SF-078926

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
Gallegos Canyon Unit

8. FARM OR LEASE NAME

9. WELL NO.
164E

10. FIELD OR WILDCAT NAME
Basin Dakota

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
NE/4, NW/4, Section 35, T29N, R13W

12. COUNTY OR PARISH
San Juan

13. STATE
New Mexico

14. API NO.
30-045-24958

15. ELEVATIONS (SHOW DF, KDB, AND WD)
5853' G.L.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Spudded a 12-1/4" hole on 1-3-82 and drilled to 325'. Set 8-5/8" 24 pound surface casing at 320' on 1-4-82, and cemented with 300 sx of Class "B" neat cement containing 2% CaCl₂. Good cement was circulated to the surface. Drilled a 7-7/8" hole to a TD of 6436'. Set 4-1/2" 10.5 pound production casing at 6436', on 1-13-82, and cemented in two stages as follows:

1) Cement with 340 sx of Class "B" neat cement containing 50:50 POZ, 6% gel, 2 pound medium tuf plug per sack, and .8% fluid loss additive. This was tailed in with 100 sx of Class "B" neat cement.

2) Cement with 1050 sx of Class "B" neat cement containing 65:35 POZ, 6% gel, 2 pound medium tuf plug per sack, and .8% fluid loss additive. This was tailed (over)

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED _____ TITLE Dist. Admin. Supv. DATE

JAN 25 1982

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____ DATE _____

ACCEPTED FOR RECORD

FEB 2 1982

*See Instructions on Reverse Side

NMOCC

FARMINGTON DISTRICT
BY _____

Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.

(Continued)

in with 100 sx of Class "B" neat cement. No cement was circulated to the surface. Cement top is 1200' below the surface.

The DV tool was set at 4584'.

The rig was released on 1-14-82.