

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☒ gas well ☐ other ☐

2. NAME OF OPERATOR
SUPRON ENERGY CORPORATION

3. ADDRESS OF OPERATOR
P.O. Box 808, Farmington, New Mexico 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: *1650 ft./S ; 990 ft./E line*
AT TOP PROD. INTERVAL: *Same as above*
AT TOTAL DEPTH: *Same as above*

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:

☒
☐
☐
☐
☐
☐
☐
☐

5. LEASE

SF 080724 A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Zachry

9. WELL NO.

28

10. FIELD OR WILDCAT NAME

Wildcat Gallup

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

Sec. 35, T-29N, R-10W, N.M.P.M.

12. COUNTY OR PARISH

San Juan

13. STATE


New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)

5780 ft. R.K.B.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)



17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- Spudded 12 1/4" surface hole at 4:00 p.m. 11-21-81.*
- Drilled surface hole to total depth of 319 ft. R.K.B.*
- Ran 7 joints of 9-5/8", 32.00#, H-40 casing and set @ 305 ft. R.K.B.*
- Cemented w/275 sacks of class "B" w/3% calcium chloride. Plug down at 11:00 p.m. 11-21-81. Cement circulated to the surface.*
- Waited on cement for 12 hours.*
- Pressure-tested casing to 1000 PSI for 15 minutes. Held OK.*

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED *Kenneth E. Roddy* TITLE *Production Supt.* DATE *November 25, 1981*
Kenneth E. Roddy

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____
CONDITIONS OF APPROVAL, IF ANY:

DATE
ACCEPTED FOR RECORD

NOV 30 1981

*See Instructions on Reverse Side

FARMINGTON DISTRICT

BY

MMOCC