



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Farmington District Office
1235 La Plata Highway
Farmington, New Mexico 87401

IN REPLY REFER TO:

Attachment to Notice of

Re: Sidetrack

Intention to Workover

Well: 7 E. E. Elliott B

CONDITIONS OF APPROVAL

1. Spot a cement plug from 6188' to 6088' plus 50 linear feet excess cement inside the 4 1/2" casing. (Gallup top @ 6138', 12 sks.)
2. Place a cement plug from 4923' to 4823' inside and outside the 4 1/2" casing plus 50 linear feet excess cement. (CBL will determine if perforating the 4 1/2" casing is necessary--7.0" casing shoe at 4873')
3. Place a cement plug from 4330' to 4230' inside and outside the 4 1/2" casing plus 50 linear feet excess cement. (CBL will determine if perforating the 4 1/2" casing is necessary--Mesaverde top @ 4280')
4. Spot a 100 ' cement plug at the top of the 4 1/2" casing cut off. (50' of cement in the 4 1/2" csg. and 50' of cement in the 7.0" csg.)
5. **Mike Flaniken** with the Farmington District Office is to be notified at least 24 hours before the workover operations commence (505) 599-8907.