

(SUBMIT IN TRIPLICATE)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

Land Office Santa Fe

Lease No. SF 078214

Unit E/2, Sec. 28, T-30N,  
R-13W, N.M.P.M. San Juan  
County, New Mexico

SUNDRY NOTICES AND REPORTS ON WELLS

NOTICE OF INTENTION TO DRILL.....	SUBSEQUENT REPORT OF WATER SHUT-OFF.....	<input checked="" type="checkbox"/>
NOTICE OF INTENTION TO CHANGE PLANS.....	SUBSEQUENT REPORT OF SHOOTING OR ACIDIZING.....	<input type="checkbox"/>
NOTICE OF INTENTION TO TEST WATER SHUT-OFF.....	SUBSEQUENT REPORT OF ALTERING CASING.....	<input type="checkbox"/>
NOTICE OF INTENTION TO RE-DRILL OR REPAIR WELL.....	SUBSEQUENT REPORT OF RE-DRILLING OR REPAIR.....	<input type="checkbox"/>
NOTICE OF INTENTION TO SHOOT OR ACIDIZE.....	SUBSEQUENT REPORT OF ABANDONMENT.....	<input type="checkbox"/>
NOTICE OF INTENTION TO PULL OR ALTER CASING.....	SUPPLEMENTARY WELL HISTORY.....	<input type="checkbox"/>
NOTICE OF INTENTION TO ABANDON WELL.....		

(INDICATE ABOVE BY CHECK MARK NATURE OF REPORT, NOTICE, OR OTHER DATA)

October 8, 1963

Well No. 8/ McCord is located 1155 ft. from N line and 920 ft. from E line of sec. 28

NE/4, NE/4, Sec. 28  
( $\frac{1}{4}$  Sec. and Sec. No.)

30-N  
(Twp.)

13-W  
(Range)

N.M.P.M.  
(Meridian)

Basin Dakota  
(Field)

San Juan  
(County or Subdivision)


New Mexico  
(State or Territory)

The elevation of the derrick floor above sea level is 5723 ft. Ungraded ground level.

DETAILS OF WORK

(State names of and expected depths to objective sands; show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work)

1. Spudded 12-1/4" surface hole 12:30 A.M. 10/6/63. Drilled to T.D. of 265 ft.
2. Ran 8 jts., 8-5/8", 24.0#, J-55 casing as surface casing. Landed at 262 ft. R.K.B. Cemented w/150 sx regular w/2% Calcium Chloride. Cement circulated to surface. Plug down 11:30 P.M. 10/6/63.
3. Nippled up. Pressure test casing to 1000 psi for 30 min. OK.
4. Drilled out from under surface w/7-7/8" hole on 10/7/63.



I understand that this plan of work must receive approval in writing by the Geological Survey before operations may be commenced.

Company SOUTHERN UNION PRODUCTION COMPANY

Address P. O. Box 808

Farmington, New Mexico

By Gilbert D. Moland, Jr.  
Drilling Superintendent

Title