

17. NU flow-back manifold. Begin immediate flow-back on $\frac{1}{4}$ " Choke (minimum of 12-Hrs), switch to $\frac{1}{2}$ " Choke, minimum total flow-back time of 36-Hrs. ND Frac valve.
18. TIH w/ 3-7/8" mill on tbg and CO SD, from Menefee/MV Frac, and DO CIBP @ 4500'.
19. Cont. TIH w/ 3-7/8" mill on tbg and CO SD, from Point Lookout/MV Frac, to PBTD.
20. TOOH w/ mill and string float on tbg.
21. TIH w/ expendable check, 1-Jt 2-3/8" tbg, 'P' Nipple on 2-3/8" production tbg, land tbg hanger, secure lock-downs.
22. NU WH. Pump 5-Bbls of 1% KCl wtr down tbg, drop ball, and pump out expendable check.
23. RD and MO Big 'A' daylight completion rig.