

GENERAL INFORMATION

I. The following tubular goods have been assigned to the well.

<u>Description</u>	<u>Approximate Gross Measurement (feet)</u>	<u>Availability</u>
	<u>Surface Casing</u>	
13-3/8-inch O.D., 54.5-pound, K-55, 8 round thread, ST&C casing	350	Warehouse Stock
	<u>Intermediate Casing</u>	
8-5/8-inch O.D., 36-pound, L-80 buttress thread casing	6,400	Warehouse Stock
	<u>Production Casing</u>	
5-1/2-inch O.D., 23-pound, Soo-90, 8 round thread, LT&C casing	6,800	Warehouse Stock
5-1/2-inch O.D., 20-pound, L-80, 8 round thread, LT&C casing	<u>6,400</u>	Warehouse Stock
Total	13,200	
	<u>Production Tubing</u>	
2-7/8-inch O.D., 6.5-pound, C-75 Hydril CS tubing	13,200	Warehouse Stock

II. All ram type preventers will have hand wheels installed and operative at the time the preventers are installed. Pipe rams will be worked each day and blind rams will be worked each time the drill pipe is out of the hole.

III. Well responsibility: E. G. Mickel