

UNITED STATES  
DEPARTMENT OF THE INTERIOR

(Other Instructions on  
Reverse Side)

GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

20-045-23364

5. LEASE DESIGNATION AND SERIAL NO.  
USA SF 078201

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME  
Florance

9. WELL NO.  
115

10. FIELD AND POOL, OR WILDCAT  
Blanco Pictured Cliff Ex

11. SEC., T., R., M., OR BLE.  
AND SURVEY OR AREA  
Sec. 10, T30N, R9W

12. COUNTY OR PARISH  
San Juan

13. STATE  
New Mexico

1a. TYPE OF WORK  
DRILL ☒ DEEPEN ☐ PLUG BACK ☐

b. TYPE OF WELL  
OIL WELL ☐ GAS WELL ☒ OTHER ☐  
SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR  
TENNECO OIL COMPANY

3. ADDRESS OF OPERATOR  
720 SOUTH COLORADO BLVD., DENVER, CO 80222

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)  
At surface 790' FSL and 1025' FWL

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE  
See point 1B Surface Use Plan

15. DISTANCE FROM PROPOSED LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT.  
(Also to nearest drlg. unit line, if any)

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT.

21. ELEVATIONS (Show whether DF, RT, GR, etc.)  
6274' G.L.

22. APPROX. DATE WORK WILL START  
February 1, 1979

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
11"	8-5/8"	24#	+ 200'	Circulate to surface.
7-7/8"	5-1/2"	15.5#	+ 3100'	Cement column behind casing.

- The geological name of the surface formation is San Jose Eocene.
- Estimated Formation Tops  
Pictured Cliffs + 2900' Possible oil and gas producer.
- Run 8-5/8" OD, K-55 ST&C new casing to + 200' and circulate cement shoe, float collar and centralizers across zones of interst. Cement thorough the shoe with sufficient volume to yield a + 1000' column of cement behind the casing.
- Blowout Preventors: Hydraulic, double ram 10". One set of rams will be provided for each size drill pipe in the hole. One set of blind rams at all times. Fill line will be 2", Kill line will be 2", choke relief line will be 2" with variable choke. BOPs will be installed, tested and in working order before drilling below surface casing and shall be maintained ready for use until drilling operations are completed. BOPs, drills and tests will be recorded in the IADC Drilling Report. They shall be checked every 24 hours. All rig equipment will be tested to above BOE ratings.
- Use of spud mud 0-200'; and low solids 200' - T.D.
- Auxiliary Equipment
  - Kelly cock will be in use at all times.
  - Stabbing valve to fit drill pipe will be present on floor at all times.
  - Mud monitoring will be visual, no abnormal pressures are anticipated in this area.
  - Floats at bits.
  - Drill string safety valve(s) to fit all pipe in the drill string will be maintained on the rig floor while drilling operations are in progress.
  - Rotating head will be used while drilling with gas.
- No coring is planned. GR/FDC/CNL/Caliper. Surveys will be taken from 2000' above T.D. to T.D. SP/Induction/SN/GR taken from T.D. to surface.
- No abnormal pressures or temperatures are anticipated. See point #5 for blowout prevention equipment.
- The drilling of this well will take approximately five days. The gas is not yet contracted.



JAN 19 1979

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED D. D. Meyer TITLE Div. Production Manager DATE 1/8/79  
(This space for Federal or State office use)

OKAL PERMIT NO. APPROVAL DATE

NEW MEXICO OIL CONSERVATION COMMISSION  
WELL LOCATION AND ACREAGE DEDICATION PLAT

USA SF 078201

Form C-102  
Supersedes C-128  
Effective 1-1-65

All distances must be from the outer boundaries of the Section.


Operator <b>TENNECO OIL COMPANY</b>			Lease <b>FLORANCE</b>		Well No. <b>115</b>
Unit Letter <b>M</b>	Section <b>10</b>	Township <b>30N</b>	Range <b>9W</b>	County <b>SAN JUAN</b>	
Actual Footage Location of Well: <b>79C</b> feet from the <b>South</b> line and <b>1025</b> feet from the <b>West</b> line					
Ground Level Elev. <b>6274</b>	Producing Formation <b>Pictured Cliffs</b>		Pool <b>BLANCO - PC EXT</b>	Dedicated Acreage: <b>160</b> Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☐ Yes ☐ No If answer is "yes," type of consolidation \_\_\_\_\_

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) \_\_\_\_\_

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Name J.A. Rush  
Position Environmental Coordinator  
Company Tenneco Oil Company  
Date January 10, 1979

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

Date Surveyed October 31, 1978  
Registered Professional Engineer and/or Land Surveyor  
Frederick B. Kerr, Jr.  
Certification No. 3950

1. Existing Roads

A. Proposed Well Site Location:

The proposed well site location was surveyed and staked by a registered land surveyor and is located 790' FSL and 1025' FWL, Section 10, Township 30N, Range 9W, San Juan County, NM . (See Surveyors Plat).

B. Planned Access Route: The planned access route begins in Blanco, NM and goes north 2 miles to a 3-way junction which then turns east. Proceed on this turning north after 1.0 mile and continue on this road for approximately 2.5 miles when the road turns east for 1.0 mile and north. Go 2.5 miles to the junction of a gravel road which goes

C. Access Road Labelled: /southeasterly 0.5 mile. This begins the new /road section of 1200' to the well site  
Color Code: Red - Improved Surface /location. (See exhibit II).  
Blue - New Access Road

D. Not applicable - the proposed well is a development well.

E. The proposed well is a development well. See Exhibit II for existing roads within a one mile radius.

F. Existing Road Maintenance or Improvement Plan:  
The existing roads will require minimal maintenance.

2. Planned Access Roads

(All roads are existing roads.)

A. Width:  
The average width of the road is                feet.

B. Maximum Grades:  
The maximum grades will be six percent.

C. Turnouts:  
There are no turnouts planned as sight distance is sufficient.

D. Drainage Design:  
The road is center crowned to allow drainage. The road is flat primarily.

E. Culverts Use Major Cuts and Fills:  
Approximately a 15' cut will be needed on the NW corner of the location and a 7' cut on the NE corner. Also a water bar diversion will be needed along the north side of the location. No culverts will be needed.

F. Surfacing Material:  
Native soil has been wetted, bladed and compacted to make the road surface, which is existing.

2. Planned Access Roads (Cont'd)

- G. Gates, Cattleguards, Fence Cuts:  
A 16' cattleguard will be needed where the 1200' new road goes through the fence.
- H. New Roads Centerlined Flagged:  
Existing Roads.

3. Location of Existing Wells

The proposed well is a development well. Exhibit III shows existing wells within a one mile radius.

- A. Water Wells: None.
- B. Abandoned Wells: None.
- C. Temporarily Abandoned Wells: None.
- D. Disposal Wells: None.
- E. Drilling Wells: See Exhibit III.
- F. Producing Wells: See Exhibit III.
- G. Shut-In Wells: None.
- H. Injection Wells: None.
- I. Monitoring or Observation Wells: None.

4. Location of Existing and/or Proposed Facilities

- A. Existing facilities within one mile owned or controlled by Lessee/Operator:

See Exhibit III.

- (1) Tank batteries - n/a.
- (2) Production facilities - See Exhibit III.
- (3) Oil Gathering Lines - n/a.
- (4) Gas Gathering Lines - n/a.
- (5) Injection Lines - n/a.
- (6) Disposal Lines - n/a.

- B. New facilities in the event of production:

- (1) New facilities will be within the dimensions of the drill pad.
- (2) Dimensions are shown on Exhibit IV.
- (3) Construction Materials/Methods:  
Construction materials will be native to the site.  
Facilities will consist of a well pad.
- (4) Protection of Wildlife/Livestock:  
Facilities will be fenced as needed.

4. Location of Existing and/or Proposed Facilities (Cont'd)

B. New facilities in the event of production: (cont'd)

(5) Facilities will consist of a wellhead, tank and production unit.

C. Rehabilitation of Disturbed Areas:

Following the completion of construction, those areas required for continued production will be graded to provide drainage and minimize erosion. Those areas unnecessary for use will be graded to blend with surrounding topography per BLM recommendations.

5. Location and Type of Water Supply

A. Location and type of water supply:

Water will be hauled from a private source.

B. Water Transportation System:

Water trucks will be used.

C. Water wells:

N/A.

6. Source of Construction Materials

A. Materials:

Construction materials will consist of soil native to the site. Any topsoil, if present, will be stripped and stockpiled as needed.

B. Land Ownership;

The planned site and access road is on federal land administered by the Bureau of Land Management.

C. Materials Foreign to the Site:

N/A.

D. Access Roads:

No additional roads will be required.

7. Methods for Handling Waste Disposal

A. Cuttings:

Cuttings will be contained in the reserve pit.

B. Drilling Fluids:

Drilling fluids will be retained in the reserve pit.

C. Produced Fluids:

Produced fluids, including produced water will be collected in the reserve pit. Any small amount of hydrocarbon that may be produced during testing will be retained in the reserve pit. Prior to clean up operations, the hydrocarbon material will be skimmed.

7. Methods for Handling Waste Disposal (Cont'd)

- D. Sewage:  
Sanitary facilities for sewage disposal will consist of at least one pit toilet, during the driller operations. The pit will be backfilled immediately following completion of the drilling operation.
- E. Garbage:  
There probably will not be much putrescible garbage to dispose of. However, it will be disposed of along with the refuse in a constructed burn pit, which will be fenced. The small amount of refuse will be burned and the pit will be covered with a minimum 36 inch cover upon completion.
- F. Clean-Up of Well Site:  
Upon the release of the drilling rig, the surface of the drilling pad will be prepared to accommodate a completion rig, if testing indicates potential productive zones. In either case, the "mouse hole" and "rat hole" will be covered to eliminate a potential hazard to livestock. The reserve pit will be fenced to prevent entry of livestock until the pit is backfilled. Reasonable clean up will be performed prior to final restoration of the site.

8. Ancillary Facilities

None required.

9. Well Site Layout

- A. See Exhibit IV.
- B. Location of pits, etc. See Exhibit IV.
- C. Rig orientation etc. See Exhibit IV.
- D. Lining of pits:  
Pits will not be lined. They will be covered with a fine mesh netting, if necessary, for the protection of wildlife if fluids are found to be toxic.

10. Plans for Restoration of Surface

- A. Reserve pit clean up:  
The pit will be fenced prior to rig release and shall be maintained until clean up. Prior to backfilling any hydrocarbon material on the pit surface will be removed. The fluids and solids contained in the pit shall be backfilled with soil excavated from the site and with soil adjacent to the reserve pit. The restored surface of the reserve pit will be contoured as needed to minimize erosion. The reserve pit area will be seeded per BLM recommendations during the appropriate season following final restoration of the site.

10. Plans for Restoration of Surface (Cont'd)

- B. Restoration Plans - Production Developed:  
The reserve pit will be backfilled and restored as described under Item A. In addition, those disturbed areas not required for production will be graded to blend with the surrounding topography, and seeded, per BLM recommendations. The portion of the drill pad required for production and turning areas will be graded to minimize erosion and provide access to production facilities under inclement conditions. Following depletion and abandonment of the site, restoration procedures will be those under Item C. below.
- C. Restoration Plan - No Production Developed:  
The reserve pit will be restored as described above. With no production developed, the entire surface disturbed by construction of the drilling pad will be restored. The site will be contoured to blend with the surrounding topography. The site will be seeded according to BLM recommendations. If the new access road is not required for other development plans, it will be obliterated and restored and seeded per BLM recommendations.
- D. Rehabilitation Time Table:  
Upon completion of operations the initial clean up of the well site will be performed. Final restoration of the site will be performed as soon as possible according to procedural guidelines published by the USGS and BLM. Seeding of the disturbed areas which are no longer required will be performed during the appropriate season, following final restoration.

11. Other Information

- A. Surface Description:  
The area is relatively flat and has cedar/juniper trees throughout the proposed area. The soil is a sandy silt type.
- B. Surface Use Activities:  
The surface is federally owned and managed by the BLM. The predominant surface use is mineral exploration and production.
- C. Proximity of Water, Dwellings and Historical Sites:
  - 1. Water:  
There are no reservoirs or streams in the immediate area.
  - 2. Occupied Dwellings:  
There are no occupied dwellings or buildings in the area.
  - 3. Sites:  
An archeological reconnaissance has been performed for this location and clearance has been granted.

12. Operator's Field Representative

Donald S. Barnes  
Division Drilling Engineer  
Tenneco Oil Company  
720 South Colorado Blvd.  
Penthouse  
Denver, CO 80222  
(303) 758-7130 Ext. 212


13. Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions as they actually exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the proposed work performed by Tenneco Oil Company and its contractors and subcontractors will conform to this plan.

Date: 1-12-79

D. D. Myers  
D. D. Myers  
Division Production Manager





All valves 2"

All BOPs, flanges, spools, valves, & lines must be series 900 or 3000 psi working press.


Choke manifold must be at ground level and extended out from under substructure.

TENNECO OIL COMPANY

REQUIRED MINIMUM BLOWOUT PREVENTOR

HOCKUP

Denver, Colorado



INTERIOR-GEOLOGICAL SURVEY WASHINGTON D.C. 20540  
1:50,000 Scale  
BLANCO 42 MI

**ROAD CLASSIFICATION**  
 Medium duty ——— Light duty ———  
 Unimproved dirt .....  
 U.S. Route (S) State Route (S)


Mapped, edited, and published by USGS and USCG  
 Control by USCG and USCG  
 East half completed in 1959  
 dated 1954. First published  
 methods from aerial photography  
 field checked 1954

Polyconic projection 1927 North American datum  
 10,000 foot grid based on New Mexico coordinate system,  
 west and central zones  
 1000 meter Universal Transverse Mercator grid ticks,  
 zone 13 shown in blue

**Vicinity Map for Exhibit II**  
**TENNECO OIL COMPANY #115 FLORENCE**  
**790'FSL 1025'FWL Sec 10-T30N-R9W**  
**SAN JUAN COUNTY, NEW MEXICO**

AZTEC, N. MEX

UTM GRID AND 1959 MAGNETIC NORTH  
 DECLINATION AT CENTER OF SHEET



TENNECO OIL COMPANY

CALCULATION SHEET

COMPANY

SUBJECT

LOCATION

Drilling Well Site Layout - Florance 115

Sw/Sw Sec 10, T30N, R9W San Juan

BY

DATE

Exhibit IV

1/79

