

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒
well well other

2. NAME OF OPERATOR

El Paso Natural Gas Company

3. ADDRESS OF OPERATOR

Box 289, Farmington, New Mexico 87401

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 1720'S, 1630'E

AT TOP PROD. INTERVAL:

AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

☒
☐
☐
☐
☐
☐
☐
☐

5. LEASE

NM 04240

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Kelly

9. WELL NO.

* 2 A (PM)

10. FIELD OR WILDCAT NAME

Blanco Mesa Verde, Blanco PC

11. SEC., T., R., M., OR BLK. AND SURVEY OR

AREA Sec. 35, T-30-N, R-10-W
N.M.P.M.

12. COUNTY OR PARISH 13. STATE

San Juan

New Mexico

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)

6147' GL

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

- 18-80: PBSD 5421'. Tested casing to 3500#, OK. Perfed P.L. 4898,4903,4908,4924,4929, 4935,4940,4945,4950,4962,4968,4974,4980,4992,5006,5013,5020,5080,5133,5194,5250, 5257,5281' W/1 SPZ. Fraced w/76,670# 20/40 sand, 151,420 gal. wtr. Flushed w/ 6790 gal. wtr.
- 19-80: Perfed Men. & C.H. 4204,4274,4280,4302,4309,4316,4324,4351,4372,4380,4388,4396, 4404,4412,4420,4624,4641,4650,4742,4762,4770,4778' w/1 SPZ. Fraced w/91,600# 20/40 sand, 176,360 gal. wtr. Flushed w/ 6180 gal. wtr.
- Perfed P.C. 2657-2680,2700-2714,2718-2730,2740-2750' W/16 SPZ. Fraced w/ 60,530# 10/20 sand, 65,420 gal. wtr. Dropped 3 sets of 16 balls each. Flushed w/4590 gal. wtr.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct


SIGNED J. Bruce TITLE Drilling Clerk DATE January 22, 1980

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

NMOCC

*See Instructions on Reverse Side



JAN 31 '80

BY _____
DISTRICT