

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☐ gas well ☒ other

2. NAME OF OPERATOR

MESA PETROLEUM CO.

3. ADDRESS OF OPERATOR 1660 Lincoln
2800 Lincoln Center, Denver, Colo. 80264

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE: 950'N & 1550'E

AT TOP PROD. INTERVAL: same

AT TOTAL DEPTH: same

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

(other)

CHANGE PLANS

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE
078204-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

TRIEB

9. WELL NO.

2E

10. FIELD OR WILDCAT NAME

BLANCO MV. BASIN DAKOTA

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

33-30N-10W

12. COUNTY OR PARISH

SAN JUAN

13. STATE

NEW MEXICO

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)
6107

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*


Change plans from mud drilled, to mud drilled to 2900' \pm , then air drilled to 7200' \pm .

* Intermediate casing to be 7", 20# K-55 new, set at 2900' \pm , and cemented w/ 200 sks 65-35 Pozmix + 2% gel followed by 200 sks class "B" + 2% CaCl₂.

Hole then air drilled to TD.

Liner to be run from 2700' \pm to TD 4 1/2" 10.5# K-55 new casing. Cement to be 500 sks 50-50 Poz + 2% gel + 0.6% HALAD-9.

* Cement is to cover the o/g



Subsurface Safety Valve: Manu. and Type

18. I hereby certify that the foregoing is true and correct

SIGNED

JOHN ALEXANDER

TITLE

AGENT

DATE

May 8, 1980

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

NMOCC