



NEW MEXICO ENERGY, MINERALS & NATURAL RESOURCES DEPARTMENT

OIL CONSERVATION DIVISION
AZTEC DISTRICT OFFICE
1000 RIO BRAZOS ROAD
AZTEC NM 87410
(505) 334-6178 FAX: (505) 334-6170
[http://www.nm.us/ocd/District III/3distric.htm](http://www.nm.us/ocd/District%20III/3distric.htm)

This form is not to
be used for reporting
packer leakage tests
in Southeast New Mexico

RECEIVED
DEC - 8 1999

Page 1
Revised 11/16/98

NORTHWEST NEW MEXICO PACKER-LEAKAGE TEST

Operator Phillips Petroleum 017654 Lease Name San Juan 32-8 Unit Well No 12A

Location of Well: Unit Letter E Sec 21 Twp 31N Rge 8W API # 30-0 45-10781

| | NAME OF RESERVOIR OR POOL | TYPE OF PROD. (Oil or Gas) | METHOD OF PROD. (Flow or Art. Lift) | PROD. MEDIUM (Tbg. or Csg.) |
|------------------|---------------------------|-------------------------------|--|--------------------------------|
| Upper Completion | Mesaverde | gas | flowing | tubing |
| Lower Completion | Dakota | gas | flowing | tubing |

PRE-FLOW SHUT-IN PRESSURE DATA

| | | | | |
|------------------|--------------------------------|----------------------------------|-----------------------|-------------------------------|
| Upper Completion | Hour, date shut-in 11/15/99 | Length of time shut-in 3 days | SI press. Psig 174 | Stabilized? (Yes or No) no |
| Lower Completion | Hour, date shut-in 11/15/99 | Length of time shut-in 3 days | SI press. Psig 887 | Stabilized? (Yes or No) no |

FLOW TEST NO. 1

| Commenced at (hour, date)* | | | | Zone producing (Upper or Lower): | |
|----------------------------|-----------------------|------------------|------------------|----------------------------------|------------------------|
| TIME (hour, date) | LAPSED TIME SINCE* | PRESSURE | | PROD. ZONE TEMP. | REMARKS |
| | | Upper Completion | Lower Completion | | |
| 11/19/99 | 24 hrs | 178 | 111 | | Upper SI: flowed lower |
| 11/20/99 | 48 hrs | 182 | 108 | | Upper SI: flowed lower |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Production rate during test

Oil: _____ BOPD based on _____ Bbls. in _____ Hours _____ Grav. _____ GOR _____

Gas: _____ MCFPD; Tested thru (Orifice or Meter): _____

MID-TEST SHUT-IN PRESSURE DATA

| | | | | |
|------------------|--------------------|------------------------|----------------|-------------------------|
| Upper Completion | Hour, date shut-in | Length of time shut-in | SI press psig | Stabilized? (Yes or No) |
| Lower Completion | Hour, date shut-in | Length of time shut-in | SI press. psig | Stabilized? (Yes or No) |

(Continue on reverse side)

| Commenced at (hour, date)** | | | Zone producing (Upper or Lower): | | |
|-----------------------------|------------------------|------------------|----------------------------------|------------|---------|
| TIME (hour, date) | LAPSED TIME Since** | PRESSURE | | PROD. ZONE | REMARKS |
| | | Upper Completion | Lower Completion | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

Production rate during test

Oil: _____ BOPD based on _____ Bbls. in _____ Hours. _____ Grav. _____ GOR _____

Gas: _____ MCFPD: Tested thru (Office or Meter): _____

Remarks: _____

I hereby certify that the information herein contained is true and complete to the bes of my knowledge.

Approved _____ 19____ Operator _____ Phillips Petroleum Company

New Mexico Oil Conservation Division

By Jim Kennedy Jim Kennedy

By _____ Title _____ Well Tester

Title _____ Date _____ 11/24/99

NORTHWEST NEW MEXICO PACKER LEAKAGE TEST INSTRUCTIONS

1. A packer leakage test shall be commenced on each multiply completed well within seven days after actual completion of the well, and annually thereafter as prescribed by the order authorizing the multiple completion. Such tests shall also be commenced on all multiple completions within seven days following recompletion and/or chemical or fracture treatment, and whenever remedial work has been done on a well during which the packer or the tubing have been disturbed. Tests shall also be taken at any time that communication is suspected or when requested by the Division.
2. At least 72 hours prior to the commencement of any packer leakage test, the operator shall notify the Division in writing of the exact time the test is to be commenced. Offset operators shall also be so notified.
3. The packer leakage test shall commence when both zones of the dual completion are shut-in for pressure stabilization. Both zones shall remain shut-in until the well-head pressure in each has stabilized, provided however, that they need not remain shut-in more than seven days.
4. For Flow Test No. 1, one zone of the dual completion shall be produced at the normal rate of production while the other zone remains shut-in. Such test shall be continued for seven days in the case of a gas well and for 24 hours in the case of an oil well. Note: if, on an initial packer leakage test, a gas well is being flowed to the atmosphere due to the lack of a pipeline connection the flow period shall be three hours.
5. Following completion of Flow Test No. 1, the well shall again be shut-in, in accordance with Paragraph 3 above.
6. Flow Test No. 2 shall be conducted even though no leak was indicated during Flow Test No. 1. Procedure for Flow Test no. 2 is to be the same as for Flow Test No. 1 except

that the previously produced zone shall remain shut-in while the zone which was previously shut-in is produced.

7. Pressures for gas-zone tests must be measured on each zone with a deadweigh pressure gauge at time intervals as follows: 3 hours tests: immediately prior to the beginning of each flow-period, at fifteen-minute intervals during the first hour thereof and at hourly intervals thereafter, including one pressure measurement immediately prior to the beginning of each flow period, at least one time during each flow perio (at approximately the midway point) and immediately prior to the conclusion of each flow period. Other pressures may be taken as desired, or may be requested on well which have previously shown questionable test date.

24-hour oil zone tests: all pressures, throughout the entire test, shall b continuously measured and recorded with recording pressure gauges the accurac of which must be checked at least twice, once at the beginning and once at the en of each test, with a deadweight pressure gauge. If a well is a gas-oil or an oil-ga dual completion, the recording gauge shall be required on the oil zone only, wit deadweight pressures as required above being taken on the gas zone.

8. The result s of the above-described tests shall be filed in triplicate within 15 day after completion of the test. Tests shall be filed with the Aztec District Office of th New Mexico oil Conservation Division on northwest new Mexico packer leakage Te Form Revised 11-16-98 with all deadweight pressures indicated thereon as well a the flowing temperatures (gas zones only) and gravity and GOR (oil zones only).