Form 3160-5 (June 1990)

UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT** SUNDRY NOTICES AND REPORT ON WELLS.

FC	ORM AP	PRO	VED	
Budget	Bureau	No.	1004-01	135

Expires: March 31, 1993

SUNDRY NOTIC	5. Lease Designation and Serial No. SF-078387-A		
Do not use this form for proposal Use "APPLICATION Fo	ls to drill or to deepen or reentry to a di OR PERMIT" - for such proposals.	ifferent reservoir	6. If Indian, Allottee or Tribe Name
	- ron TATA	MATON, WIN	o. a molan, Allottee of The Name
	U70 1744	¥111 × 112 × 111 × 112 × 111 × 112 ×	7. If Unit or CA, Agreement Designation
1. Type of Well Gas			8. Well Name and No.
Oil Gas Well X Well Othe	er		Kernaghan B 8
2. Name of Operator	Attention:		9. API Well No.
Amoco Production Company	Patty Haefele		3004527351
3. Address and Telephone No.			10. Field and Pool, or Exploratory Area
P.O. Box 800, Denver, Colorado 80201	Basin Fruitland Coal		
4. Location of Well (Footage, Sec., T., R., M., or Survey Descrip			11. County or Parish, State
1140' FSL & 1700' FWL		R8W Unit B	San Juan, New Mexico
12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF I	NOTICE, REPORT FACTION	OR OTHER DATA
THE OF CODMISSION	TIPE OI	FACTION	
X Notice of Intent	☐ Abandonment ☐ Recompletion	☐ Change	
Notice of littlefit	Plugging Back		nstruction utine Fracturing
Subsequent Report	☐ Casing Repair ☐ Altering Casing	☐ Water S	Shut-off sion to Injection
Final Abandannant Maties		. 🔲 Dispose	· Water
Final Abandonment Notice		(Note: Report results Recompletion Report a	of multiple completion on Well Completion or and Log Form)
 Describe Proposed or Completed Operations (Cle work. If well is directionally drilled, give subsurface 	arly state all pertinent details, and g	ive pertinent dates, ir	cluding estimated date of starting any proposes
Amoco Production Company requests permi	ission to clean out this open i		CCI 2 DUV. DIST. 3
14. I hereby certify that the foregoing is true and correct			
Signed Patty Haefele	Title	Staff Assistant	Date <u>10/10/96</u>
(This space for Federal or State office use)			
Approved byConditions of approval, if any:	Title		APPROVED
Title 18 U.S.C. Section 1001, makes it a crime for any person kr or representations as to any matter within its jurisdiction	nowingly and willfully to make to any depar	tment or agency of the U	nited States any false, fictitious, or fraudulent statement
	* See Instructions on Revers	7	S/Dusne W. Spencer DISTRICT MANAGER

SJOET Well Work Procedure

Kernaghan	В	8
Version:		

#1

Date: October 10, 1996
Budget: Expense/Well Repair

Repair Type:

Cleanout

Objectives:

- 1. TOOH with existing 4 1/2" tubing and LD.
- 2. TIH with work string to cleanout well to TD.
- 3. Stabilize open hole, slightly surging well if necessary, and flowtest.
- 4. TOOH with work string and TIH with 3 1/2" tubing and flowback.
- 5. Change tubing head and casing valves to full opening.

Pertinent Information:

Location: 11

1140' FSL x 1700' FWL; 33-T31N, R08W

Horizon:

FT

County:

San Juan

API#: Engr: 30-045-27351 R. DeHerrera

State: Lease: New Mexico SF-078387-A

Phone:

H-(303)439-7893

Well Flac:

703041

W-(303)830-4946

Economic Information:

APC WI:

50%

Prod. Before Repair:

3250 MCFD

Estimated Cost:

\$75,000

Anticipated Prod.:

4250 MCFD

Payout:

3 Months

Prod. Before Repair

Max Cost -12 Mo. P.O.

\$276,602

Anticipated Prod.:

PV15

Max Cost PV15:

Note: Economics will be run on all projects that have a payout exceeding ONE year.

Formation Tops: (Estimated formation tops)

3070'

Nacimento:

MesaVerde:

Ojo Alamo:

Point Lookout:

Kirtland Shale:

Mancos Shale:

Fruitland:

Gallup:

Pictured Cliffs:

Graneros:

Lewis Shale:

Dakota:

Cliff House

Morrison:

Bradenhead Test Information:

Test Date:

Tubing:

Casing:

BH:

Time BH CSG INT CSG
5 min
10 min
15 min

Comments:

Orig. Comp. 8/89 TD= 3235' Page 2 of 2

HIGH VOLUME WELL--DO NOT PROCEED UNTIL YOU ARE CERTAIN THAT ALL PRECAUTIONS HAVE BEEN TAKEN. CALL ME AT NUMBERS LISTED BELOW IF IN DOUBT.

- 1. MIRURT complete with 3.500" drill pipe, 4.750" drill collars and air package.
- 2. ND tree, rig up BOP's w/cavitation capability complete with venturis on blooic lines. Test BOE. Set pump-through plug in 2.75" "f" nipple at 3000". With additional joints of 4 1/2" tubing, tag fill depth. TOOH with 4 1/2" tubing, laying it down. NOTE: SHOULD IT BECOME APPARENT THAT YOU CAN NOT SAFELY PULL THE TUBING WITHOUT ASSISTANCE FROM A SNUBBING UNIT; CALL ONE OUT AND RIG UP. Change pipe rams to permit running the 3.500" drill pipe.
- 3. Pick up a 6.250" mill tooth bit, 3.500" drill pipe, and 4.750" drill collars and clean out fill to total depth (3235') using air and foam. Rotate and reciprocate on bottom until hole is clean. POOH with drill pipe so bottom of tubing is above 7" casing shoe at 3052'.
- 4. Flow test well up both tubing and casing for 1 hour through 3/4" choke and record pressures every 10 minutes. Shut well in and wait for 4 hours, record pressures every 10 minutes for first hour then every hour following.
- 5. TIH with tubing and check to determine amount of fill and how difficult it is to clean up. Repeat clean out, flow test, and shut in if necessary and stabilize hole as quickly as possible to allow running tubing. Once hole is stabilized, proceed to next step. Slight surging of the well may be necessary to stabilize open hole.
- 6. Lay down drill string, change pipe rams as necessary to run the 3 1/2" tubing string. Pick up a 3 1/2" Closed End Half Mule shoe, 10' perforated sub, profile nipple and 3 1/2" tubing. Install profile nipple with retrievable plug in place and run in with the 3 1/2" tubing. Land tubing at 3180'. Profile nipple needs to be at the bottom of the tubing just above the perforated sub assembly.
- 7. ND BOE, NU tree and RDMORT. Tie well back into surface equipment, retrieve plug and bring well on line slowly in an attempt to minimize any cavitation effect. Turn over to production.

Dependent on speed of hole stabilization, I estimate this procedure to require approximately 5 days and to cost approximately \$75,000.

Tubing Head Replacement

This can be completed any time during the workover. Many of the high rate fruitland coal wells are produced through the tubing string and the tubing/casing annulus. The 7 1/16" 3000# x 11" 3000# tubing heads on the wells were outfitted with flanged 2 1/8" casing valves. The threaded outlet in the head is 1 1/2" in diameter. We need an additional head with the outlets full opening and the ability to accommodate full opening casing valves. FMC is aware of our plans and is scrambling to accommodate this request.

If problems are encountered, please contact:

Robert DeHerrera (W) (303)830-4946 (H) (303)439-7893