

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240

DISTRICT II
811 South Frist, Artesia, NM 88210

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV
2040 South Pacheco, Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-101

OIL CONSERVATION DIVISION

2040 South Pacheco

Santa Fe, NM 87505

Revised March 25, 1999
Instructions on back
Submit to Appropriate District Office
State Lease - 6 Copies
Fee Lease - 5 Copies
AMENDED REPORT

APPLICATION FOR PERMIT TO DRILL, RE-ENTER, DEEPEN, PLUG BACK, OR ADD A ZONE

1 Operator Name and Address FOUR STAR OIL AND GAS COMPANY 3300 N. Butler Ave. Ste 100 Farmington NM 87401				2 OGRD Number 131994
4 Property Code 17713	5 Property Name NEW MEXICO COM			6 Well No. 1-C

7 Surface Location									
Ul or lot no.	Section	Township	Range	Lot.Idn	Feet From The	North/South Line	Feet From The	East/West Line	County
C	36	T30N	R10W		1085	NORTH	2155	WEST	SAN JUAN

8 Proposed Bottom Hole Location If Different From Surface									
Ul or lot no.	Section	Township	Range	Lot.Idn	Feet From The	North/South Line	Feet From The	East/West Line	County
9 Proposed Pool 1 BLANCO MESA VERDE									
10 Proposed Pool 2									

11 Work Type Code N	12 WellType Code G	13 Rotary or C.T. R	14 Lease Type Code S	15 Ground Level Elevation 5930' GR
16 Multiple N	17 Proposed Depth 4950'	18 Formation MESA VERDE	19 Contractor BEAR CAT	20 Spud Date

21 Proposed Casing and Cement Program					
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
12-1/4"	8-5/8"	32#	350'	260 SXS	SURFACE
7-7/8"	5-1/2"	15.5#	4950'	480 SXS	SURFACE

22 Describe the proposed program. If this application is to DEEPEN or PLUG BACK give the data on the present productive zone and proposed new productive zone. Describe the blowout prevention program, if any. Use additional sheets if necessary.

22 FOUR STAR OIL AND GAS CO. PROPOSES TO DRILL THIS DEVELOPMENT WELL TO A DEPTH OF 4950'. THIS WELL WILL TEST THE PRODUCTIVITY

23 OF THE MESA VERDE FORMATION. IF THE WELL IS UNPRODUCTIVE, IT WILL BE PLUGGED AND ABANDONED AS PER STATE REQUIREMENTS.

24

25 BOND COVERAGE FOR THIS WELL IS PROVIDED BY BOND NO. K02907914-C4073(NATION WIDE BLM BOND)& BOND NO. K02907914-F4072

26 (NATION WIDE BIA BOND)

27

28 A THREATENED -ENDANGERED SPECIES SURVEY AND ARCHAEOLOGICAL SURVEY WERE PERFORMED AS REQUIRED.

23 I hereby certify that the rules and regulations of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief.

Signature Arthur D. Archibeque

Printed Name Arthur D. Archibeque

Title Eng. Assistant

Date 07/12/2000 Telephone 325-4397

OIL CONSERVATION DIVISION	
Approved By: <u>[Signature]</u>	
Title: <u>DEPUTY OIL & GAS INSPECTOR, DIST. IV</u>	
Approval Date: <u>7-21-00</u>	Expiration Date: <u>JUL 21 2001</u>
Conditions of Approval: Attached <input type="checkbox"/>	

District I
PO Box 1980, Hobbs, NM 88241-1980

State of New Mexico
Energy, Minerals & Natural Resources Department

Form C-102
Revised February 21, 1994

District II
PO Drawer CO, Artesia, NM 88211-0719

OIL CONSERVATION DIVISION
PO Box 2088
Santa Fe, NM 87504-2088

Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

District III
1000 Rio Brazos Rd., Aztec, NM 87410

District IV
PO Box 2088, Santa Fe, NM 87504-2088

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-045-30304		Pool Code 72319	Pool Name BLANCO MESAVERDE
Property Code 17713	Property Name NEW MEXICO COM		Well Number 1C
OGAIC No. 131994	Operator Name FOUR STAR OIL & GAS COMPANY		Elevation 5930'

10 Surface Location




UL or lot no.	Section	Township	Range	Lot 10n	Feet from the	North/South line	Feet from the	East/West line	County
C	36	30N	10W		1085	NORTH	2155	WEST	SAN JUAN

11 Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot 10n	Feet from the	North/South line	Feet from the	East/West line	County

12 Dedicated Acres 320 w/2	13 Joint or Infill I	14 Consolidation Code	15 Order No.
--------------------------------------	--------------------------------	-----------------------	--------------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

	17 OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief. <u>Arthur D. Archibez</u> Signature <u>Arthur D. Archibez</u> Printed Name <u>Engineer Assistant</u> Title <u>6/14/2000</u> Date
	18 SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. <u>JUNE 8, 2000</u> Date of Survey <u>NEALE G. EDWARDS</u> Signature and Seal of Professional Surveyor  Certificate No. <u>6857</u>
	



DRILLING PROGRAM

OPERATOR: FOUR STAR OIL & GAS Co.
LEASE NAME: NEW MEXICO COM 1C
LOCATION: 1085' FNL- 2155' FWL SEC. 36 30N-10W SAN JUAN COUNTY, NEW MEXICO

1. ESTIMATED TOPS OF GEOLOGIC MARKERS.

THE ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS ARE AS FOLLOWS:

<u>FORMATION</u>	<u>DEPTH</u>	<u>SUBSEA</u>
MESA VERDE		1725
T.D.	4950'	4360'

2. ESTIMATED DEPTHS OF ANTICIPATED OIL, GAS, WATER, OR OTHER MINERAL BEARING ZONES.

<u>FORMATION</u>	<u>DEPTH</u>	<u>SUBSTANCE</u>
MESA VERDE	4400'	GAS
T.D.	4950'	--

IF ANY UNEXPECTED WATER OR MINERAL BEARING ZONES ARE ENCOUNTERED DURING DRILLING, THEY WILL BE REPORTED, EVALUATED, AND PROTECTED AS CIRCUMSTANCES AND REGULATIONS REQUIRE.

3. BOP EQUIPMENT.

TEXACO'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL EQUIPMENT ARE AS FOLLOWS:

RAM TYPE: HYDRAULIC DOUBLE, 3000 PSI W.P.

RAM TYPE PREVENTERS AND ASSOCIATED EQUIPMENT SHALL BE TESTED TO APPROVED STACK WORKING PRESSURE IF ISOLATED BY TEST PLUG OR TO 70 PERCENT OF INTERNAL YIELD PRESSURE OF CASING. PRESSURE SHALL BE MAINTAINED FOR AT LEAST 10 MINUTES OR UNTIL REQUIREMENTS OF TEST ARE MET, WHICHEVER IS LONGER. IF A TEST PLUG IS UTILIZED, NO BLEED-OFF PRESSURE IS ACCEPTABLE. FOR A TEST NOT UTILIZING A TEST PLUG, IF A DECLINE IN PRESSURE OF MORE THAN 10 PERCENT IN 30 MINUTES OCCURS, THE TEST SHALL BE CONSIDERED TO HAVE FAILED. VALVE ON CASING HEAD BELOW TEST PLUG SHALL BE OPEN DURING TEST OF BOP STACK.

ANNULAR TYPE PREVENTERS (IF USED) SHALL BE TESTED TO 50 PERCENT OF RATED WORKING PRESSURE. PRESSURE SHALL BE MAINTAINED AT LEAST 10 MINUTES OR UNTIL PROVISIONS OF TEST ARE MET, WHICHEVER IS LONGER.

AS A MINIMUM, THE ABOVE TEST SHALL BE PERFORMED:

- A. WHEN INITIALLY INSTALLED;
- B. WHENEVER ANY SEAL SUBJECT TO TEST PRESSURE IS BROKEN
- C. FOLLOWING RELATED REPAIRS; AND
- D. AT 30 DAY INTERVALS

VALVES SHALL BE TESTED FROM WORKING PRESSURE SIDE DURING BOPE TESTS WITH ALL DOWNSTREAM VALVES OPEN.

WHEN TESTING THE KILL LINE VALVE(S), THE CHECK VALVE SHALL BE HELD OPEN OR THE BALL REMOVED.