

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lessee Designation and Serial No.

NM 28277

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

ARBOLES 20 A #1Y

9. API Well No.

30-039-23562

10. Field and Pool, or Exploratory Area

BASIN FRUITLAND COAL

11. County or Parish, State

RIO ARRIBA COUNTY, NM

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT-" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator


VASTAR RESOURCES, INC.

3. Address and Telephone No.

1816 E. MOJAVE ST., FARMINGTON, NM 87401 (505) 599-4300

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1525' FSL, 750' FWL, SECTION 20, T32N, R4W



12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other REENTRY OPERATIONS

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well " " Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The following re-entry and Fruitland Coal sidetrack was performed from 8-8-00 to 8-31-00:

Drill out cement plugs from surface to 223', 1702' to 2132', and partially into 3rd plug from 3135' to 3802' (did not drill cement from 3802' to cement retainer at 3980'). Set 7" whipstock at 3780' and milled window in 7" casing with top of window at 3764' and bottom of window at 3772'. Drill 6-1/4" Fruitland Coal sidetrack to 4210' TD. Ran 5-1/2" 15.50# L-80 Hydril 511 Flush Joint liner and hung in hole (uncemented) from 3570' to 4210' TD. ND BOP, NU Wellhead, RD.

cc: BLM, Farmington (Or + 3)

N. Hall

Well File

14. I hereby certify that the foregoing is true and correct

Signed CW King

Title Engineer 505 599 4308

ACCEPTED FOR RECORD

(This space for Federal or State official use)

Approved by _____

Title _____

Date DEC 07 2000

Conditions of approval, if any:

FARMINGTON FIELD OFFICE
BY [Signature]

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side