

## **DRILLING PROGRAM**

Coho "6" Federal No.1

Page 2

### **9. Abnormal Conditions, Pressures, Temperatures, & Potential Hazards:**

No abnormal pressures or temperatures are anticipated. The estimated bottom hole temperature is 135 °F and the estimated bottom hole pressure is 3500 psi. There are no known problems with H<sub>2</sub>S or water flows in this immediate area.

### **10. Anticipated Starting Date and Duration of Operations:**

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is August 24, 1993. Once spudded, the drilling operation should be completed in approximately 20 days. If the well is productive, an additional 30 days will be required for completion and testing before permanent facilities are installed.

RECEIVED

SEP 17 1993

OFFICE