

|                                              |                                                          |                                   |
|----------------------------------------------|----------------------------------------------------------|-----------------------------------|
| Well Name: CORRAL BLUFF 11_14<br>FEDERAL COM | Well Location: T25S / R29E / SEC 11 /<br>NENE /          | County or Parish/State:           |
| Well Number: 312H                            | Type of Well: OIL WELL                                   | Allottee or Tribe Name:           |
| Lease Number: NMNM15303                      | Unit or CA Name:                                         | Unit or CA Number:                |
| US Well Number: 3001548029                   | Well Status: Approved Application for<br>Permit to Drill | Operator: OXY USA<br>INCORPORATED |

Notice of Intent

Sundry ID: 2713604

|                                                |                              |
|------------------------------------------------|------------------------------|
| Type of Submission: Notice of Intent           | Type of Action: APD Change   |
| Date Sundry Submitted: 02/01/2023              | Time Sundry Submitted: 11:59 |
| Date proposed operation will begin: 05/01/2023 |                              |

**Procedure Description:** The new drill plan and C-102 are attached. The old pool was the [96473] PIERCE CROSSING; BONE SPRING, EAST. The new pool is the [98220] PURPLE SAGE WOLFCAMP (GAS). The old BHL was 20 FSL, 1040 FEL, SECTION 14, T25S, R29E. The new BHL is 20 FSL, 1350 FEL, SECTION 14, T25S, R29E. The old HSU was 640 acres, the new HSU is 1280 acres.

NOI Attachments

Procedure Description

- IP8631WEL03NM\_C102\_CORRAL\_BLUFF\_11\_14\_FED\_COM\_312H\_FLAT\_20230201115902.pdf
- CorralBluff11\_14FedCom312H\_TNSWedge461\_5.500in\_20.00\_\_P110CY\_20230201115902.pdf
- CorralBluff11\_14FedCom312H\_TNSWedge441\_5.500in\_20.00\_\_P110CY\_20230201115901.pdf
- CorralBluff11\_14FedCom312H\_H2S2\_20230201115852.pdf
- CorralBluff11\_14FedCom312H\_SpudRigData\_20230201115853.pdf
- CorralBluff11\_14FedCom312H\_FlexHoseCert\_20230201115853.pdf
- CorralBluff11\_14FedCom312H\_TNSWedge425\_5.500in\_20.00\_\_P110CY\_20230201115853.pdf
- CorralBluff11\_14FedCom312H\_DrillPlan\_20230201115850.pdf
- CorralBluff11\_14FedCom312H\_H2SEmerContact\_20230201115852.pdf

|                                                     |                                                                 |                                                        |                                |
|-----------------------------------------------------|-----------------------------------------------------------------|--------------------------------------------------------|--------------------------------|
| <b>Well Name:</b> CORRAL BLUFF 11_14<br>FEDERAL COM |                                                                 | <b>Well Location:</b> T25S / R29E / SEC 11 /<br>NENE / | <b>County or Parish/State:</b> |
| <b>Well Number:</b> 312H                            | <b>Type of Well:</b> OIL WELL                                   |                                                        | <b>Allottee or Tribe Name:</b> |
| <b>Lease Number:</b> NMNM15303                      | <b>Unit or CA Name:</b>                                         | <b>Unit or CA Number:</b>                              |                                |
| <b>US Well Number:</b> 3001548029                   | <b>Well Status:</b> Approved Application for<br>Permit to Drill | <b>Operator:</b> OXY USA<br>INCORPORATED               |                                |

CorralBluff11\_14FedCom312H\_13inADAPT\_10.75in\_7.625in\_10x10\_20230201115848.pdf

CorralBluff11\_14FedCom312H\_BOP\_20230201115848.pdf

CorralBluff11\_14FedCom312H\_DirectPlan\_20230201115847.pdf

CorralBluff11\_14FedCom312H\_DirectPlot\_20230201115848.pdf

CorralBluff11\_14FedCom312H\_ChkManifolds\_20230201115848.pdf

CorralBluff11\_14FedCom312H\_CsgCriteria\_20230201115847.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

|                                                       |                                         |
|-------------------------------------------------------|-----------------------------------------|
| <b>Operator Electronic Signature:</b> STEPHEN JANACEK | <b>Signed on:</b> FEB 01, 2023 11:59 AM |
| <b>Name:</b> OXY USA INCORPORATED                     |                                         |
| <b>Title:</b> Regulatory Engineer                     |                                         |
| <b>Street Address:</b> 5 Greenway Plaza, Suite 110    |                                         |
| <b>City:</b> Houston                                  | <b>State:</b> TX                        |
| <b>Phone:</b> (713) 497-2417                          |                                         |
| <b>Email address:</b> stephen_janacek@oxy.com         |                                         |

Field

|                             |               |             |
|-----------------------------|---------------|-------------|
| <b>Representative Name:</b> |               |             |
| <b>Street Address:</b>      |               |             |
| <b>City:</b>                | <b>State:</b> | <b>Zip:</b> |
| <b>Phone:</b>               |               |             |
| <b>Email address:</b>       |               |             |

BLM Point of Contact

|                                      |                                                |
|--------------------------------------|------------------------------------------------|
| <b>BLM POC Name:</b> KEITH P IMMATTY | <b>BLM POC Title:</b> ENGINEER                 |
| <b>BLM POC Phone:</b> 5759884722     | <b>BLM POC Email Address:</b> KIMMATTY@BLM.GOV |
| <b>Disposition:</b> Approved         | <b>Disposition Date:</b> 04/13/2023            |
| <b>Signature:</b> KEITH IMMATTY      |                                                |

District I  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720  
District II  
811 S. First St., Artesia, NM 88210  
Phone: (505) 748-1283 Fax: (575) 748-9720  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

☒ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

|                                         |                                                          |                                                      |
|-----------------------------------------|----------------------------------------------------------|------------------------------------------------------|
| <sup>1</sup> API Number<br>30-015-48029 | <sup>2</sup> Pool Code<br>98220                          | <sup>3</sup> Pool Name<br>PURPLE SAGE WOLFCAMP (GAS) |
| <sup>4</sup> Property Code<br>329731    | <sup>5</sup> Property Name<br>CORRAL BLUFF 11_14 FED COM | <sup>6</sup> Well Number<br>312H                     |
| <sup>7</sup> OGRID No.<br>16696         | <sup>8</sup> Operator Name<br>OXY USA INC.               | <sup>9</sup> Elevation<br>3069.7' (NAVD 88)          |


<sup>10</sup> Surface Location

|                    |               |                 |              |         |                     |                           |                      |                        |                |
|--------------------|---------------|-----------------|--------------|---------|---------------------|---------------------------|----------------------|------------------------|----------------|
| UL or lot no.<br>A | Section<br>11 | Township<br>25S | Range<br>29E | Lot Idn | Feet from the<br>74 | North/South line<br>NORTH | Feet from the<br>363 | East/West line<br>EAST | County<br>EDDY |
|--------------------|---------------|-----------------|--------------|---------|---------------------|---------------------------|----------------------|------------------------|----------------|

<sup>11</sup> Bottom Hole Location If Different From Surface

|                                       |                                    |                                  |                         |         |                     |                           |                       |                        |                |
|---------------------------------------|------------------------------------|----------------------------------|-------------------------|---------|---------------------|---------------------------|-----------------------|------------------------|----------------|
| UL or lot no.<br>O                    | Section<br>14                      | Township<br>25S                  | Range<br>29E            | Lot Idn | Feet from the<br>20 | North/South line<br>SOUTH | Feet from the<br>1350 | East/West line<br>EAST | County<br>EDDY |
| <sup>12</sup> Dedicated Acres<br>1280 | <sup>13</sup> Joint or Infill<br>y | <sup>14</sup> Consolidation Code | <sup>15</sup> Order No. |         |                     |                           |                       |                        |                |

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



# **OXY**

**PRD NM DIRECTIONAL PLANS (NAD 1983)**

**Corral Bluff 11\_14**

**Corral Bluff 11\_14 Fed Com 312H**

**Wellbore #1**

**Plan: Permitting Plan**

## **Standard Planning Report**

**06 December, 2022**

# OXY

## Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | HOPSPP                              | <b>Local Co-ordinate Reference:</b> | Well Corral Bluff 11_14 Fed Com 312H |
| <b>Company:</b>  | ENGINEERING DESIGNS                 | <b>TVD Reference:</b>               | RKB=26.5' @ 3096.20ft                |
| <b>Project:</b>  | PRD NM DIRECTIONAL PLANS (NAD 1983) | <b>MD Reference:</b>                | RKB=26.5' @ 3096.20ft                |
| <b>Site:</b>     | Corral Bluff 11_14                  | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | Corral Bluff 11_14 Fed Com 312H     | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Permitting Plan                     |                                     |                                      |

|                    |                                     |                      |                             |
|--------------------|-------------------------------------|----------------------|-----------------------------|
| <b>Project</b>     | PRD NM DIRECTIONAL PLANS (NAD 1983) |                      |                             |
| <b>Map System:</b> | US State Plane 1983                 | <b>System Datum:</b> | Mean Sea Level              |
| <b>Geo Datum:</b>  | North American Datum 1983           |                      |                             |
| <b>Map Zone:</b>   | New Mexico Eastern Zone             |                      | Using geodetic scale factor |

|                       |     |                    |                 |            |             |
|-----------------------|-----|--------------------|-----------------|------------|-------------|
| Site                  |     | Corral Bluff 11_14 |                 |            |             |
| Site Position:        |     | Northing:          | 419,542.96 usft | Latitude:  | 32.152848   |
| From:                 | Map | Easting:           | 657,232.81 usft | Longitude: | -103.958842 |
| Position Uncertainty: |     | 1.00 ft            | Slot Radius:    | 13.200 in  |             |

| Well                 |       | Corral Bluff 11_14 Fed Com 312H |                     |                |               |             |
|----------------------|-------|---------------------------------|---------------------|----------------|---------------|-------------|
| Well Position        | +N/-S | 0.00 ft                         | Northing:           | 419,152.52 usf | Latitude:     | 32.151742   |
|                      | +E/-W | 0.00 ft                         | Easting:            | 660,656.95 usf | Longitude:    | -103.947782 |
| Position Uncertainty |       | 1.00 ft                         | Wellhead Elevation: | ft             | Ground Level: | 3,069.70 ft |
| Grid Convergence:    |       | 0.21 °                          |                     |                |               |             |

|                  |                   |                    |                        |                      |                            |
|------------------|-------------------|--------------------|------------------------|----------------------|----------------------------|
| <b>Wellbore</b>  | Wellbore #1       |                    |                        |                      |                            |
| <b>Magnetics</b> | <b>Model Name</b> | <b>Sample Date</b> | <b>Declination (°)</b> | <b>Dip Angle (°)</b> | <b>Field Strength (nT)</b> |
|                  | HDGM_FILE         | 12/9/2019          | 6.78                   | 59.80                | 47,820.50000000            |

|                          |                              |                   |                      |                      |
|--------------------------|------------------------------|-------------------|----------------------|----------------------|
| <b>Design</b>            | Permitting Plan              |                   |                      |                      |
| <b>Audit Notes:</b>      |                              |                   |                      |                      |
| <b>Version:</b>          | <b>Phase:</b>                | PROTOTYPE         | <b>Tie On Depth:</b> | 0.00                 |
| <b>Vertical Section:</b> | <b>Depth From (TVD) (ft)</b> | <b>+N/-S (ft)</b> | <b>+E/-W (ft)</b>    | <b>Direction (°)</b> |
|                          | 0.00                         | 0.00              | 0.00                 | 185.06               |

|                                 |                      |                          |                               |                                    |
|---------------------------------|----------------------|--------------------------|-------------------------------|------------------------------------|
| <b>Plan Survey Tool Program</b> | <b>Date</b>          | 12/6/2022                |                               |                                    |
| <b>Depth From (ft)</b>          | <b>Depth To (ft)</b> | <b>Survey (Wellbore)</b> | <b>Tool Name</b>              | <b>Remarks</b>                     |
| 1                               | 0.00                 | 20,698.30                | Permitting Plan (Wellbore #1) | B001Mb_MWD+HRGM<br>OWSG MWD + HRGM |

|                            |                        |                    |                            |                   |                   |                              |                             |                            |                |                    |
|----------------------------|------------------------|--------------------|----------------------------|-------------------|-------------------|------------------------------|-----------------------------|----------------------------|----------------|--------------------|
| <b>Plan Sections</b>       |                        |                    |                            |                   |                   |                              |                             |                            |                |                    |
| <b>Measured Depth (ft)</b> | <b>Inclination (°)</b> | <b>Azimuth (°)</b> | <b>Vertical Depth (ft)</b> | <b>+N/-S (ft)</b> | <b>+E/-W (ft)</b> | <b>Dogleg Rate (°/100ft)</b> | <b>Build Rate (°/100ft)</b> | <b>Turn Rate (°/100ft)</b> | <b>TFO (°)</b> | <b>Target</b>      |
| 0.00                       | 0.00                   | 0.00               | 0.00                       | 0.00              | 0.00              | 0.00                         | 0.00                        | 0.00                       | 0.00           |                    |
| 4,210.00                   | 0.00                   | 0.00               | 4,210.00                   | 0.00              | 0.00              | 0.00                         | 0.00                        | 0.00                       | 0.00           |                    |
| 5,210.01                   | 10.00                  | 271.50             | 5,204.94                   | 2.28              | -87.02            | 1.00                         | 1.00                        | 0.00                       | 271.50         |                    |
| 9,815.10                   | 10.00                  | 271.50             | 9,740.06                   | 23.21             | -886.42           | 0.00                         | 0.00                        | 0.00                       | 0.00           |                    |
| 10,719.29                  | 90.11                  | 179.71             | 10,307.36                  | -551.33           | -983.65           | 10.00                        | 8.86                        | -10.15                     | -91.75         |                    |
| 20,698.30                  | 90.11                  | 179.71             | 10,288.20                  | -10,530.18        | -932.47           | 0.00                         | 0.00                        | 0.00                       | 0.00           | PBHL (Corral Bluff |

# OXY

## Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | HOPSPP                              | <b>Local Co-ordinate Reference:</b> | Well Corral Bluff 11_14 Fed Com 312H |
| <b>Company:</b>  | ENGINEERING DESIGNS                 | <b>TVD Reference:</b>               | RKB=26.5' @ 3096.20ft                |
| <b>Project:</b>  | PRD NM DIRECTIONAL PLANS (NAD 1983) | <b>MD Reference:</b>                | RKB=26.5' @ 3096.20ft                |
| <b>Site:</b>     | Corral Bluff 11_14                  | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | Corral Bluff 11_14 Fed Com 312H     | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Permitting Plan                     |                                     |                                      |

| Planned Survey      |                 |             |                     |            |            |                       |                       |                      |                     |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 0.00                | 0.00            | 0.00        | 0.00                | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 100.00              | 0.00            | 0.00        | 100.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 200.00              | 0.00            | 0.00        | 200.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 300.00              | 0.00            | 0.00        | 300.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 400.00              | 0.00            | 0.00        | 400.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 500.00              | 0.00            | 0.00        | 500.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 600.00              | 0.00            | 0.00        | 600.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 700.00              | 0.00            | 0.00        | 700.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 800.00              | 0.00            | 0.00        | 800.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 900.00              | 0.00            | 0.00        | 900.00              | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,000.00            | 0.00            | 0.00        | 1,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,100.00            | 0.00            | 0.00        | 1,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,200.00            | 0.00            | 0.00        | 1,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,300.00            | 0.00            | 0.00        | 1,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,400.00            | 0.00            | 0.00        | 1,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,500.00            | 0.00            | 0.00        | 1,500.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,600.00            | 0.00            | 0.00        | 1,600.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,700.00            | 0.00            | 0.00        | 1,700.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,800.00            | 0.00            | 0.00        | 1,800.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 1,900.00            | 0.00            | 0.00        | 1,900.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,000.00            | 0.00            | 0.00        | 2,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,100.00            | 0.00            | 0.00        | 2,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,200.00            | 0.00            | 0.00        | 2,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,300.00            | 0.00            | 0.00        | 2,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,400.00            | 0.00            | 0.00        | 2,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,500.00            | 0.00            | 0.00        | 2,500.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,600.00            | 0.00            | 0.00        | 2,600.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,700.00            | 0.00            | 0.00        | 2,700.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,800.00            | 0.00            | 0.00        | 2,800.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 2,900.00            | 0.00            | 0.00        | 2,900.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,000.00            | 0.00            | 0.00        | 3,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,100.00            | 0.00            | 0.00        | 3,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,200.00            | 0.00            | 0.00        | 3,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,300.00            | 0.00            | 0.00        | 3,300.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,400.00            | 0.00            | 0.00        | 3,400.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,500.00            | 0.00            | 0.00        | 3,500.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,600.00            | 0.00            | 0.00        | 3,600.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,700.00            | 0.00            | 0.00        | 3,700.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,800.00            | 0.00            | 0.00        | 3,800.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 3,900.00            | 0.00            | 0.00        | 3,900.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 4,000.00            | 0.00            | 0.00        | 4,000.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 4,100.00            | 0.00            | 0.00        | 4,100.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 4,200.00            | 0.00            | 0.00        | 4,200.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 4,210.00            | 0.00            | 0.00        | 4,210.00            | 0.00       | 0.00       | 0.00                  | 0.00                  | 0.00                 | 0.00                |
| 4,300.00            | 0.90            | 271.50      | 4,300.00            | 0.02       | -0.71      | 0.04                  | 1.00                  | 1.00                 | 0.00                |
| 4,400.00            | 1.90            | 271.50      | 4,399.97            | 0.08       | -3.15      | 0.20                  | 1.00                  | 1.00                 | 0.00                |
| 4,500.00            | 2.90            | 271.50      | 4,499.88            | 0.19       | -7.34      | 0.46                  | 1.00                  | 1.00                 | 0.00                |
| 4,600.00            | 3.90            | 271.50      | 4,599.70            | 0.35       | -13.26     | 0.82                  | 1.00                  | 1.00                 | 0.00                |
| 4,700.00            | 4.90            | 271.50      | 4,699.40            | 0.55       | -20.93     | 1.30                  | 1.00                  | 1.00                 | 0.00                |
| 4,800.00            | 5.90            | 271.50      | 4,798.96            | 0.79       | -30.34     | 1.88                  | 1.00                  | 1.00                 | 0.00                |
| 4,900.00            | 6.90            | 271.50      | 4,898.33            | 1.09       | -41.48     | 2.58                  | 1.00                  | 1.00                 | 0.00                |
| 5,000.00            | 7.90            | 271.50      | 4,997.50            | 1.42       | -54.36     | 3.38                  | 1.00                  | 1.00                 | 0.00                |
| 5,100.00            | 8.90            | 271.50      | 5,096.43            | 1.81       | -68.96     | 4.28                  | 1.00                  | 1.00                 | 0.00                |
| 5,200.00            | 9.90            | 271.50      | 5,195.08            | 2.23       | -85.29     | 5.30                  | 1.00                  | 1.00                 | 0.00                |
| 5,210.01            | 10.00           | 271.50      | 5,204.94            | 2.28       | -87.02     | 5.41                  | 1.00                  | 1.00                 | 0.00                |

# OXY

## Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | HOPSPP                              | <b>Local Co-ordinate Reference:</b> | Well Corral Bluff 11_14 Fed Com 312H |
| <b>Company:</b>  | ENGINEERING DESIGNS                 | <b>TVD Reference:</b>               | RKB=26.5' @ 3096.20ft                |
| <b>Project:</b>  | PRD NM DIRECTIONAL PLANS (NAD 1983) | <b>MD Reference:</b>                | RKB=26.5' @ 3096.20ft                |
| <b>Site:</b>     | Corral Bluff 11_14                  | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | Corral Bluff 11_14 Fed Com 312H     | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Permitting Plan                     |                                     |                                      |

| Planned Survey      |                 |             |                     |            |            |                       |                       |                      |                     |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 5,300.00            | 10.00           | 271.50      | 5,293.56            | 2.69       | -102.64    | 6.38                  | 0.00                  | 0.00                 | 0.00                |
| 5,400.00            | 10.00           | 271.50      | 5,392.04            | 3.14       | -120.00    | 7.45                  | 0.00                  | 0.00                 | 0.00                |
| 5,500.00            | 10.00           | 271.50      | 5,490.53            | 3.60       | -137.36    | 8.53                  | 0.00                  | 0.00                 | 0.00                |
| 5,600.00            | 10.00           | 271.50      | 5,589.01            | 4.05       | -154.72    | 9.61                  | 0.00                  | 0.00                 | 0.00                |
| 5,700.00            | 10.00           | 271.50      | 5,687.49            | 4.51       | -172.07    | 10.69                 | 0.00                  | 0.00                 | 0.00                |
| 5,800.00            | 10.00           | 271.50      | 5,785.97            | 4.96       | -189.43    | 11.77                 | 0.00                  | 0.00                 | 0.00                |
| 5,900.00            | 10.00           | 271.50      | 5,884.45            | 5.42       | -206.79    | 12.85                 | 0.00                  | 0.00                 | 0.00                |
| 6,000.00            | 10.00           | 271.50      | 5,982.93            | 5.87       | -224.15    | 13.92                 | 0.00                  | 0.00                 | 0.00                |
| 6,100.00            | 10.00           | 271.50      | 6,081.41            | 6.32       | -241.51    | 15.00                 | 0.00                  | 0.00                 | 0.00                |
| 6,200.00            | 10.00           | 271.50      | 6,179.89            | 6.78       | -258.87    | 16.08                 | 0.00                  | 0.00                 | 0.00                |
| 6,300.00            | 10.00           | 271.50      | 6,278.37            | 7.23       | -276.23    | 17.16                 | 0.00                  | 0.00                 | 0.00                |
| 6,400.00            | 10.00           | 271.50      | 6,376.85            | 7.69       | -293.59    | 18.24                 | 0.00                  | 0.00                 | 0.00                |
| 6,500.00            | 10.00           | 271.50      | 6,475.33            | 8.14       | -310.95    | 19.32                 | 0.00                  | 0.00                 | 0.00                |
| 6,600.00            | 10.00           | 271.50      | 6,573.81            | 8.60       | -328.31    | 20.39                 | 0.00                  | 0.00                 | 0.00                |
| 6,700.00            | 10.00           | 271.50      | 6,672.29            | 9.05       | -345.67    | 21.47                 | 0.00                  | 0.00                 | 0.00                |
| 6,800.00            | 10.00           | 271.50      | 6,770.77            | 9.51       | -363.02    | 22.55                 | 0.00                  | 0.00                 | 0.00                |
| 6,900.00            | 10.00           | 271.50      | 6,869.26            | 9.96       | -380.38    | 23.63                 | 0.00                  | 0.00                 | 0.00                |
| 7,000.00            | 10.00           | 271.50      | 6,967.74            | 10.42      | -397.74    | 24.71                 | 0.00                  | 0.00                 | 0.00                |
| 7,100.00            | 10.00           | 271.50      | 7,066.22            | 10.87      | -415.10    | 25.79                 | 0.00                  | 0.00                 | 0.00                |
| 7,200.00            | 10.00           | 271.50      | 7,164.70            | 11.32      | -432.46    | 26.86                 | 0.00                  | 0.00                 | 0.00                |
| 7,300.00            | 10.00           | 271.50      | 7,263.18            | 11.78      | -449.82    | 27.94                 | 0.00                  | 0.00                 | 0.00                |
| 7,400.00            | 10.00           | 271.50      | 7,361.66            | 12.23      | -467.18    | 29.02                 | 0.00                  | 0.00                 | 0.00                |
| 7,500.00            | 10.00           | 271.50      | 7,460.14            | 12.69      | -484.54    | 30.10                 | 0.00                  | 0.00                 | 0.00                |
| 7,600.00            | 10.00           | 271.50      | 7,558.62            | 13.14      | -501.90    | 31.18                 | 0.00                  | 0.00                 | 0.00                |
| 7,700.00            | 10.00           | 271.50      | 7,657.10            | 13.60      | -519.26    | 32.26                 | 0.00                  | 0.00                 | 0.00                |
| 7,800.00            | 10.00           | 271.50      | 7,755.58            | 14.05      | -536.62    | 33.33                 | 0.00                  | 0.00                 | 0.00                |
| 7,900.00            | 10.00           | 271.50      | 7,854.06            | 14.51      | -553.97    | 34.41                 | 0.00                  | 0.00                 | 0.00                |
| 8,000.00            | 10.00           | 271.50      | 7,952.54            | 14.96      | -571.33    | 35.49                 | 0.00                  | 0.00                 | 0.00                |
| 8,100.00            | 10.00           | 271.50      | 8,051.02            | 15.42      | -588.69    | 36.57                 | 0.00                  | 0.00                 | 0.00                |
| 8,200.00            | 10.00           | 271.50      | 8,149.51            | 15.87      | -606.05    | 37.65                 | 0.00                  | 0.00                 | 0.00                |
| 8,300.00            | 10.00           | 271.50      | 8,247.99            | 16.33      | -623.41    | 38.73                 | 0.00                  | 0.00                 | 0.00                |
| 8,400.00            | 10.00           | 271.50      | 8,346.47            | 16.78      | -640.77    | 39.80                 | 0.00                  | 0.00                 | 0.00                |
| 8,500.00            | 10.00           | 271.50      | 8,444.95            | 17.23      | -658.13    | 40.88                 | 0.00                  | 0.00                 | 0.00                |
| 8,600.00            | 10.00           | 271.50      | 8,543.43            | 17.69      | -675.49    | 41.96                 | 0.00                  | 0.00                 | 0.00                |
| 8,700.00            | 10.00           | 271.50      | 8,641.91            | 18.14      | -692.85    | 43.04                 | 0.00                  | 0.00                 | 0.00                |
| 8,800.00            | 10.00           | 271.50      | 8,740.39            | 18.60      | -710.21    | 44.12                 | 0.00                  | 0.00                 | 0.00                |
| 8,900.00            | 10.00           | 271.50      | 8,838.87            | 19.05      | -727.57    | 45.20                 | 0.00                  | 0.00                 | 0.00                |
| 9,000.00            | 10.00           | 271.50      | 8,937.35            | 19.51      | -744.92    | 46.27                 | 0.00                  | 0.00                 | 0.00                |
| 9,100.00            | 10.00           | 271.50      | 9,035.83            | 19.96      | -762.28    | 47.35                 | 0.00                  | 0.00                 | 0.00                |
| 9,200.00            | 10.00           | 271.50      | 9,134.31            | 20.42      | -779.64    | 48.43                 | 0.00                  | 0.00                 | 0.00                |
| 9,300.00            | 10.00           | 271.50      | 9,232.79            | 20.87      | -797.00    | 49.51                 | 0.00                  | 0.00                 | 0.00                |
| 9,400.00            | 10.00           | 271.50      | 9,331.27            | 21.33      | -814.36    | 50.59                 | 0.00                  | 0.00                 | 0.00                |
| 9,500.00            | 10.00           | 271.50      | 9,429.75            | 21.78      | -831.72    | 51.67                 | 0.00                  | 0.00                 | 0.00                |
| 9,600.00            | 10.00           | 271.50      | 9,528.24            | 22.23      | -849.08    | 52.74                 | 0.00                  | 0.00                 | 0.00                |
| 9,700.00            | 10.00           | 271.50      | 9,626.72            | 22.69      | -866.44    | 53.82                 | 0.00                  | 0.00                 | 0.00                |
| 9,800.00            | 10.00           | 271.50      | 9,725.20            | 23.14      | -883.80    | 54.90                 | 0.00                  | 0.00                 | 0.00                |
| 9,815.10            | 10.00           | 271.50      | 9,740.06            | 23.21      | -886.42    | 55.06                 | 0.00                  | 0.00                 | 0.00                |
| 9,900.00            | 12.89           | 230.09      | 9,823.41            | 17.32      | -901.08    | 62.23                 | 10.00                 | 3.40                 | -48.78              |
| 10,000.00           | 20.67           | 207.58      | 9,919.17            | -5.54      | -917.85    | 86.47                 | 10.00                 | 7.78                 | -22.51              |
| 10,100.00           | 29.76           | 197.68      | 10,009.59           | -44.93     | -933.59    | 127.10                | 10.00                 | 9.10                 | -9.91               |
| 10,200.00           | 39.27           | 192.17      | 10,091.90           | -99.66     | -947.84    | 182.87                | 10.00                 | 9.51                 | -5.50               |
| 10,300.00           | 48.96           | 188.55      | 10,163.62           | -168.06    | -960.15    | 252.10                | 10.00                 | 9.68                 | -3.62               |
| 10,400.00           | 58.72           | 185.87      | 10,222.57           | -248.07    | -970.16    | 332.67                | 10.00                 | 9.76                 | -2.68               |
| 10,500.00           | 68.53           | 183.70      | 10,266.94           | -337.23    | -977.55    | 422.14                | 10.00                 | 9.81                 | -2.17               |
| 10,600.00           | 78.36           | 181.81      | 10,295.40           | -432.86    | -982.11    | 517.80                | 10.00                 | 9.83                 | -1.89               |



# OXY

## Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | HOPSPP                              | <b>Local Co-ordinate Reference:</b> | Well Corral Bluff 11_14 Fed Com 312H |
| <b>Company:</b>  | ENGINEERING DESIGNS                 | <b>TVD Reference:</b>               | RKB=26.5' @ 3096.20ft                |
| <b>Project:</b>  | PRD NM DIRECTIONAL PLANS (NAD 1983) | <b>MD Reference:</b>                | RKB=26.5' @ 3096.20ft                |
| <b>Site:</b>     | Corral Bluff 11_14                  | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | Corral Bluff 11_14 Fed Com 312H     | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Permitting Plan                     |                                     |                                      |

| Planned Survey      |                 |             |                     |            |            |                       |                       |                      |                     |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 10,700.00           | 88.21           | 180.04      | 10,307.08           | -532.03    | -983.69    | 616.73                | 10.00                 | 9.85                 | -1.76               |
| 10,719.29           | 90.11           | 179.71      | 10,307.36           | -551.33    | -983.65    | 635.94                | 10.00                 | 9.85                 | -1.74               |
| 10,800.00           | 90.11           | 179.71      | 10,307.20           | -632.03    | -983.24    | 716.29                | 0.00                  | 0.00                 | 0.00                |
| 10,900.00           | 90.11           | 179.71      | 10,307.01           | -732.03    | -982.72    | 815.86                | 0.00                  | 0.00                 | 0.00                |
| 11,000.00           | 90.11           | 179.71      | 10,306.82           | -832.03    | -982.21    | 915.42                | 0.00                  | 0.00                 | 0.00                |
| 11,100.00           | 90.11           | 179.71      | 10,306.63           | -932.03    | -981.70    | 1,014.98              | 0.00                  | 0.00                 | 0.00                |
| 11,200.00           | 90.11           | 179.71      | 10,306.44           | -1,032.02  | -981.18    | 1,114.55              | 0.00                  | 0.00                 | 0.00                |
| 11,300.00           | 90.11           | 179.71      | 10,306.24           | -1,132.02  | -980.67    | 1,214.11              | 0.00                  | 0.00                 | 0.00                |
| 11,400.00           | 90.11           | 179.71      | 10,306.05           | -1,232.02  | -980.16    | 1,313.67              | 0.00                  | 0.00                 | 0.00                |
| 11,500.00           | 90.11           | 179.71      | 10,305.86           | -1,332.02  | -979.65    | 1,413.24              | 0.00                  | 0.00                 | 0.00                |
| 11,600.00           | 90.11           | 179.71      | 10,305.67           | -1,432.02  | -979.13    | 1,512.80              | 0.00                  | 0.00                 | 0.00                |
| 11,700.00           | 90.11           | 179.71      | 10,305.48           | -1,532.02  | -978.62    | 1,612.36              | 0.00                  | 0.00                 | 0.00                |
| 11,800.00           | 90.11           | 179.71      | 10,305.28           | -1,632.02  | -978.11    | 1,711.93              | 0.00                  | 0.00                 | 0.00                |
| 11,900.00           | 90.11           | 179.71      | 10,305.09           | -1,732.01  | -977.59    | 1,811.49              | 0.00                  | 0.00                 | 0.00                |
| 12,000.00           | 90.11           | 179.71      | 10,304.90           | -1,832.01  | -977.08    | 1,911.05              | 0.00                  | 0.00                 | 0.00                |
| 12,100.00           | 90.11           | 179.71      | 10,304.71           | -1,932.01  | -976.57    | 2,010.62              | 0.00                  | 0.00                 | 0.00                |
| 12,200.00           | 90.11           | 179.71      | 10,304.52           | -2,032.01  | -976.06    | 2,110.18              | 0.00                  | 0.00                 | 0.00                |
| 12,300.00           | 90.11           | 179.71      | 10,304.32           | -2,132.01  | -975.54    | 2,209.74              | 0.00                  | 0.00                 | 0.00                |
| 12,400.00           | 90.11           | 179.71      | 10,304.13           | -2,232.01  | -975.03    | 2,309.31              | 0.00                  | 0.00                 | 0.00                |
| 12,500.00           | 90.11           | 179.71      | 10,303.94           | -2,332.00  | -974.52    | 2,408.87              | 0.00                  | 0.00                 | 0.00                |
| 12,600.00           | 90.11           | 179.71      | 10,303.75           | -2,432.00  | -974.00    | 2,508.44              | 0.00                  | 0.00                 | 0.00                |
| 12,700.00           | 90.11           | 179.71      | 10,303.56           | -2,532.00  | -973.49    | 2,608.00              | 0.00                  | 0.00                 | 0.00                |
| 12,800.00           | 90.11           | 179.71      | 10,303.36           | -2,632.00  | -972.98    | 2,707.56              | 0.00                  | 0.00                 | 0.00                |
| 12,900.00           | 90.11           | 179.71      | 10,303.17           | -2,732.00  | -972.47    | 2,807.13              | 0.00                  | 0.00                 | 0.00                |
| 13,000.00           | 90.11           | 179.71      | 10,302.98           | -2,832.00  | -971.95    | 2,906.69              | 0.00                  | 0.00                 | 0.00                |
| 13,100.00           | 90.11           | 179.71      | 10,302.79           | -2,932.00  | -971.44    | 3,006.25              | 0.00                  | 0.00                 | 0.00                |
| 13,200.00           | 90.11           | 179.71      | 10,302.60           | -3,031.99  | -970.93    | 3,105.82              | 0.00                  | 0.00                 | 0.00                |
| 13,300.00           | 90.11           | 179.71      | 10,302.40           | -3,131.99  | -970.41    | 3,205.38              | 0.00                  | 0.00                 | 0.00                |
| 13,400.00           | 90.11           | 179.71      | 10,302.21           | -3,231.99  | -969.90    | 3,304.94              | 0.00                  | 0.00                 | 0.00                |
| 13,500.00           | 90.11           | 179.71      | 10,302.02           | -3,331.99  | -969.39    | 3,404.51              | 0.00                  | 0.00                 | 0.00                |
| 13,600.00           | 90.11           | 179.71      | 10,301.83           | -3,431.99  | -968.88    | 3,504.07              | 0.00                  | 0.00                 | 0.00                |
| 13,700.00           | 90.11           | 179.71      | 10,301.64           | -3,531.99  | -968.36    | 3,603.63              | 0.00                  | 0.00                 | 0.00                |
| 13,800.00           | 90.11           | 179.71      | 10,301.44           | -3,631.99  | -967.85    | 3,703.20              | 0.00                  | 0.00                 | 0.00                |
| 13,900.00           | 90.11           | 179.71      | 10,301.25           | -3,731.98  | -967.34    | 3,802.76              | 0.00                  | 0.00                 | 0.00                |
| 14,000.00           | 90.11           | 179.71      | 10,301.06           | -3,831.98  | -966.82    | 3,902.32              | 0.00                  | 0.00                 | 0.00                |
| 14,100.00           | 90.11           | 179.71      | 10,300.87           | -3,931.98  | -966.31    | 4,001.89              | 0.00                  | 0.00                 | 0.00                |
| 14,200.00           | 90.11           | 179.71      | 10,300.68           | -4,031.98  | -965.80    | 4,101.45              | 0.00                  | 0.00                 | 0.00                |
| 14,300.00           | 90.11           | 179.71      | 10,300.48           | -4,131.98  | -965.29    | 4,201.02              | 0.00                  | 0.00                 | 0.00                |
| 14,400.00           | 90.11           | 179.71      | 10,300.29           | -4,231.98  | -964.77    | 4,300.58              | 0.00                  | 0.00                 | 0.00                |
| 14,500.00           | 90.11           | 179.71      | 10,300.10           | -4,331.98  | -964.26    | 4,400.14              | 0.00                  | 0.00                 | 0.00                |
| 14,600.00           | 90.11           | 179.71      | 10,299.91           | -4,431.97  | -963.75    | 4,499.71              | 0.00                  | 0.00                 | 0.00                |
| 14,700.00           | 90.11           | 179.71      | 10,299.72           | -4,531.97  | -963.23    | 4,599.27              | 0.00                  | 0.00                 | 0.00                |
| 14,800.00           | 90.11           | 179.71      | 10,299.52           | -4,631.97  | -962.72    | 4,698.83              | 0.00                  | 0.00                 | 0.00                |
| 14,900.00           | 90.11           | 179.71      | 10,299.33           | -4,731.97  | -962.21    | 4,798.40              | 0.00                  | 0.00                 | 0.00                |
| 15,000.00           | 90.11           | 179.71      | 10,299.14           | -4,831.97  | -961.70    | 4,897.96              | 0.00                  | 0.00                 | 0.00                |
| 15,100.00           | 90.11           | 179.71      | 10,298.95           | -4,931.97  | -961.18    | 4,997.52              | 0.00                  | 0.00                 | 0.00                |
| 15,200.00           | 90.11           | 179.71      | 10,298.76           | -5,031.96  | -960.67    | 5,097.09              | 0.00                  | 0.00                 | 0.00                |
| 15,300.00           | 90.11           | 179.71      | 10,298.56           | -5,131.96  | -960.16    | 5,196.65              | 0.00                  | 0.00                 | 0.00                |
| 15,400.00           | 90.11           | 179.71      | 10,298.37           | -5,231.96  | -959.64    | 5,296.21              | 0.00                  | 0.00                 | 0.00                |
| 15,500.00           | 90.11           | 179.71      | 10,298.18           | -5,331.96  | -959.13    | 5,395.78              | 0.00                  | 0.00                 | 0.00                |
| 15,600.00           | 90.11           | 179.71      | 10,297.99           | -5,431.96  | -958.62    | 5,495.34              | 0.00                  | 0.00                 | 0.00                |
| 15,700.00           | 90.11           | 179.71      | 10,297.80           | -5,531.96  | -958.11    | 5,594.90              | 0.00                  | 0.00                 | 0.00                |
| 15,800.00           | 90.11           | 179.71      | 10,297.60           | -5,631.96  | -957.59    | 5,694.47              | 0.00                  | 0.00                 | 0.00                |
| 15,900.00           | 90.11           | 179.71      | 10,297.41           | -5,731.95  | -957.08    | 5,794.03              | 0.00                  | 0.00                 | 0.00                |
| 16,000.00           | 90.11           | 179.71      | 10,297.22           | -5,831.95  | -956.57    | 5,893.60              | 0.00                  | 0.00                 | 0.00                |



# OXY

## Planning Report

|                  |                                     |                                     |                                      |
|------------------|-------------------------------------|-------------------------------------|--------------------------------------|
| <b>Database:</b> | HOPSPP                              | <b>Local Co-ordinate Reference:</b> | Well Corral Bluff 11_14 Fed Com 312H |
| <b>Company:</b>  | ENGINEERING DESIGNS                 | <b>TVD Reference:</b>               | RKB=26.5' @ 3096.20ft                |
| <b>Project:</b>  | PRD NM DIRECTIONAL PLANS (NAD 1983) | <b>MD Reference:</b>                | RKB=26.5' @ 3096.20ft                |
| <b>Site:</b>     | Corral Bluff 11_14                  | <b>North Reference:</b>             | Grid                                 |
| <b>Well:</b>     | Corral Bluff 11_14 Fed Com 312H     | <b>Survey Calculation Method:</b>   | Minimum Curvature                    |
| <b>Wellbore:</b> | Wellbore #1                         |                                     |                                      |
| <b>Design:</b>   | Permitting Plan                     |                                     |                                      |

| Planned Survey      |                 |             |                     |            |            |                       |                       |                      |                     |
|---------------------|-----------------|-------------|---------------------|------------|------------|-----------------------|-----------------------|----------------------|---------------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 16,100.00           | 90.11           | 179.71      | 10,297.03           | -5,931.95  | -956.05    | 5,993.16              | 0.00                  | 0.00                 | 0.00                |
| 16,200.00           | 90.11           | 179.71      | 10,296.84           | -6,031.95  | -955.54    | 6,092.72              | 0.00                  | 0.00                 | 0.00                |
| 16,300.00           | 90.11           | 179.71      | 10,296.64           | -6,131.95  | -955.03    | 6,192.29              | 0.00                  | 0.00                 | 0.00                |
| 16,400.00           | 90.11           | 179.71      | 10,296.45           | -6,231.95  | -954.52    | 6,291.85              | 0.00                  | 0.00                 | 0.00                |
| 16,500.00           | 90.11           | 179.71      | 10,296.26           | -6,331.95  | -954.00    | 6,391.41              | 0.00                  | 0.00                 | 0.00                |
| 16,600.00           | 90.11           | 179.71      | 10,296.07           | -6,431.94  | -953.49    | 6,490.98              | 0.00                  | 0.00                 | 0.00                |
| 16,700.00           | 90.11           | 179.71      | 10,295.88           | -6,531.94  | -952.98    | 6,590.54              | 0.00                  | 0.00                 | 0.00                |
| 16,800.00           | 90.11           | 179.71      | 10,295.68           | -6,631.94  | -952.46    | 6,690.10              | 0.00                  | 0.00                 | 0.00                |
| 16,900.00           | 90.11           | 179.71      | 10,295.49           | -6,731.94  | -951.95    | 6,789.67              | 0.00                  | 0.00                 | 0.00                |
| 17,000.00           | 90.11           | 179.71      | 10,295.30           | -6,831.94  | -951.44    | 6,889.23              | 0.00                  | 0.00                 | 0.00                |
| 17,100.00           | 90.11           | 179.71      | 10,295.11           | -6,931.94  | -950.93    | 6,988.79              | 0.00                  | 0.00                 | 0.00                |
| 17,200.00           | 90.11           | 179.71      | 10,294.92           | -7,031.93  | -950.41    | 7,088.36              | 0.00                  | 0.00                 | 0.00                |
| 17,300.00           | 90.11           | 179.71      | 10,294.72           | -7,131.93  | -949.90    | 7,187.92              | 0.00                  | 0.00                 | 0.00                |
| 17,400.00           | 90.11           | 179.71      | 10,294.53           | -7,231.93  | -949.39    | 7,287.48              | 0.00                  | 0.00                 | 0.00                |
| 17,500.00           | 90.11           | 179.71      | 10,294.34           | -7,331.93  | -948.87    | 7,387.05              | 0.00                  | 0.00                 | 0.00                |
| 17,600.00           | 90.11           | 179.71      | 10,294.15           | -7,431.93  | -948.36    | 7,486.61              | 0.00                  | 0.00                 | 0.00                |
| 17,700.00           | 90.11           | 179.71      | 10,293.96           | -7,531.93  | -947.85    | 7,586.17              | 0.00                  | 0.00                 | 0.00                |
| 17,800.00           | 90.11           | 179.71      | 10,293.76           | -7,631.93  | -947.34    | 7,685.74              | 0.00                  | 0.00                 | 0.00                |
| 17,900.00           | 90.11           | 179.71      | 10,293.57           | -7,731.92  | -946.82    | 7,785.30              | 0.00                  | 0.00                 | 0.00                |
| 18,000.00           | 90.11           | 179.71      | 10,293.38           | -7,831.92  | -946.31    | 7,884.87              | 0.00                  | 0.00                 | 0.00                |
| 18,100.00           | 90.11           | 179.71      | 10,293.19           | -7,931.92  | -945.80    | 7,984.43              | 0.00                  | 0.00                 | 0.00                |
| 18,200.00           | 90.11           | 179.71      | 10,293.00           | -8,031.92  | -945.28    | 8,083.99              | 0.00                  | 0.00                 | 0.00                |
| 18,300.00           | 90.11           | 179.71      | 10,292.80           | -8,131.92  | -944.77    | 8,183.56              | 0.00                  | 0.00                 | 0.00                |
| 18,400.00           | 90.11           | 179.71      | 10,292.61           | -8,231.92  | -944.26    | 8,283.12              | 0.00                  | 0.00                 | 0.00                |
| 18,500.00           | 90.11           | 179.71      | 10,292.42           | -8,331.92  | -943.75    | 8,382.68              | 0.00                  | 0.00                 | 0.00                |
| 18,600.00           | 90.11           | 179.71      | 10,292.23           | -8,431.91  | -943.23    | 8,482.25              | 0.00                  | 0.00                 | 0.00                |
| 18,700.00           | 90.11           | 179.71      | 10,292.04           | -8,531.91  | -942.72    | 8,581.81              | 0.00                  | 0.00                 | 0.00                |
| 18,800.00           | 90.11           | 179.71      | 10,291.84           | -8,631.91  | -942.21    | 8,681.37              | 0.00                  | 0.00                 | 0.00                |
| 18,900.00           | 90.11           | 179.71      | 10,291.65           | -8,731.91  | -941.69    | 8,780.94              | 0.00                  | 0.00                 | 0.00                |
| 19,000.00           | 90.11           | 179.71      | 10,291.46           | -8,831.91  | -941.18    | 8,880.50              | 0.00                  | 0.00                 | 0.00                |
| 19,100.00           | 90.11           | 179.71      | 10,291.27           | -8,931.91  | -940.67    | 8,980.06              | 0.00                  | 0.00                 | 0.00                |
| 19,200.00           | 90.11           | 179.71      | 10,291.08           | -9,031.90  | -940.16    | 9,079.63              | 0.00                  | 0.00                 | 0.00                |
| 19,300.00           | 90.11           | 179.71      | 10,290.88           | -9,131.90  | -939.64    | 9,179.19              | 0.00                  | 0.00                 | 0.00                |
| 19,400.00           | 90.11           | 179.71      | 10,290.69           | -9,231.90  | -939.13    | 9,278.75              | 0.00                  | 0.00                 | 0.00                |
| 19,500.00           | 90.11           | 179.71      | 10,290.50           | -9,331.90  | -938.62    | 9,378.32              | 0.00                  | 0.00                 | 0.00                |
| 19,600.00           | 90.11           | 179.71      | 10,290.31           | -9,431.90  | -938.10    | 9,477.88              | 0.00                  | 0.00                 | 0.00                |
| 19,700.00           | 90.11           | 179.71      | 10,290.12           | -9,531.90  | -937.59    | 9,577.45              | 0.00                  | 0.00                 | 0.00                |
| 19,800.00           | 90.11           | 179.71      | 10,289.92           | -9,631.90  | -937.08    | 9,677.01              | 0.00                  | 0.00                 | 0.00                |
| 19,900.00           | 90.11           | 179.71      | 10,289.73           | -9,731.89  | -936.57    | 9,776.57              | 0.00                  | 0.00                 | 0.00                |
| 20,000.00           | 90.11           | 179.71      | 10,289.54           | -9,831.89  | -936.05    | 9,876.14              | 0.00                  | 0.00                 | 0.00                |
| 20,100.00           | 90.11           | 179.71      | 10,289.35           | -9,931.89  | -935.54    | 9,975.70              | 0.00                  | 0.00                 | 0.00                |
| 20,200.00           | 90.11           | 179.71      | 10,289.16           | -10,031.89 | -935.03    | 10,075.26             | 0.00                  | 0.00                 | 0.00                |
| 20,300.00           | 90.11           | 179.71      | 10,288.96           | -10,131.89 | -934.51    | 10,174.83             | 0.00                  | 0.00                 | 0.00                |
| 20,400.00           | 90.11           | 179.71      | 10,288.77           | -10,231.89 | -934.00    | 10,274.39             | 0.00                  | 0.00                 | 0.00                |
| 20,500.00           | 90.11           | 179.71      | 10,288.58           | -10,331.89 | -933.49    | 10,373.95             | 0.00                  | 0.00                 | 0.00                |
| 20,600.00           | 90.11           | 179.71      | 10,288.39           | -10,431.88 | -932.98    | 10,473.52             | 0.00                  | 0.00                 | 0.00                |
| 20,698.30           | 90.11           | 179.71      | 10,288.20           | -10,530.18 | -932.47    | 10,571.38             | 0.00                  | 0.00                 | 0.00                |

OXY  
Planning Report

|           |                                     |                              |                                      |
|-----------|-------------------------------------|------------------------------|--------------------------------------|
| Database: | HOPSPP                              | Local Co-ordinate Reference: | Well Corral Bluff 11_14 Fed Com 312H |
| Company:  | ENGINEERING DESIGNS                 | TVD Reference:               | RKB=26.5' @ 3096.20ft                |
| Project:  | PRD NM DIRECTIONAL PLANS (NAD 1983) | MD Reference:                | RKB=26.5' @ 3096.20ft                |
| Site:     | Corral Bluff 11_14                  | North Reference:             | Grid                                 |
| Well:     | Corral Bluff 11_14 Fed Com 312H     | Survey Calculation Method:   | Minimum Curvature                    |
| Wellbore: | Wellbore #1                         |                              |                                      |
| Design:   | Permitting Plan                     |                              |                                      |

| Design Targets                                                                                                                |           |          |           |            |         |            |            |           |             |
|-------------------------------------------------------------------------------------------------------------------------------|-----------|----------|-----------|------------|---------|------------|------------|-----------|-------------|
| Target Name                                                                                                                   | Dip Angle | Dip Dir. | TVD       | +N/-S      | +E/-W   | Northing   | Easting    | Latitude  | Longitude   |
| - hit/miss target                                                                                                             | (°)       | (°)      | (ft)      | (ft)       | (ft)    | (usft)     | (usft)     |           |             |
| - Shape                                                                                                                       |           |          |           |            |         |            |            |           |             |
| PBHL (Corral Bluff<br>- plan hits target center<br>- Point                                                                    | 0.00      | 0.00     | 10,288.20 | -10,530.18 | -932.47 | 408,623.15 | 659,724.55 | 32.122807 | -103.950916 |
| FTP (Corral Bluff<br>- plan misses target center by 202.59ft at 10300.00ft MD (10163.62 TVD, -168.06 N, -960.15 E)<br>- Point | 0.00      | 0.00     | 10,307.20 | -27.55     | -986.34 | 419,124.97 | 659,670.69 | 32.151675 | -103.950969 |

| Formations     |                |                 |           |     |               |  |
|----------------|----------------|-----------------|-----------|-----|---------------|--|
| Measured Depth | Vertical Depth | Name            | Lithology | Dip | Dip Direction |  |
| (ft)           | (ft)           |                 |           | (°) | (°)           |  |
| 356.20         | 356.20         | RUSTLER         |           |     |               |  |
| 752.20         | 752.20         | SALADO          |           |     |               |  |
| 1,692.20       | 1,692.20       | CASTILE         |           |     |               |  |
| 3,245.20       | 3,245.20       | DELAWARE        |           |     |               |  |
| 3,248.20       | 3,248.20       | BELL CANYON     |           |     |               |  |
| 4,126.20       | 4,126.20       | CHERRY CANYON   |           |     |               |  |
| 5,555.52       | 5,545.20       | BRUSHY CANYON   |           |     |               |  |
| 7,051.24       | 7,018.20       | BONE SPRING     |           |     |               |  |
| 7,968.17       | 7,921.20       | BONE SPRING 1ST |           |     |               |  |
| 8,837.38       | 8,777.20       | BONE SPRING 2ND |           |     |               |  |
| 9,976.67       | 9,897.20       | BONE SPRING 3RD |           |     |               |  |
| 10,362.70      | 10,202.20      | WOLFCAMP        |           |     |               |  |

| Plan Annotations |                |                   |         |                           |  |
|------------------|----------------|-------------------|---------|---------------------------|--|
| Measured Depth   | Vertical Depth | Local Coordinates |         |                           |  |
| (ft)             | (ft)           | +N/-S             | +E/-W   | Comment                   |  |
| (ft)             | (ft)           | (ft)              | (ft)    |                           |  |
| 4,210.00         | 4,210.00       | 0.00              | 0.00    | Build 1°/100'             |  |
| 5,210.01         | 5,204.94       | 2.28              | -87.02  | Hold 10° Tangent          |  |
| 9,815.10         | 9,740.07       | 23.21             | -886.42 | KOP, Buid & Turn 10°/100' |  |
| 10,719.29        | 10,307.36      | -551.32           | -983.65 | Landing Point             |  |
| 20,698.29        | 10,288.20      | -10,530.17        | -932.47 | TD at 20698.29' MD        |  |



Project: PRD NM DIRECTIONAL PLANS (NAD 1983)  
 Site: Corral Bluff 11\_14  
 Well: Corral Bluff 11\_14 Fed Com 312H  
 Wellbore: Wellbore #1  
 Design: Permitting Plan

## PROJECT DETAILS: NM DIRECTIONAL PLANS (NAD 1983)

Geodetic System: US State Plane 1983  
 Datum: North American Datum 1983  
 Ellipsoid: GRS 1980  
 Zone: New Mexico Eastern Zone

System Datum: Mean Sea Level

## WELL DETAILS: Corral Bluff 11\_14 Fed Com 312H

| +N/-S | +E/-W | Northing  | 3069.70<br>Easting | Latitude  | Longitude   |
|-------|-------|-----------|--------------------|-----------|-------------|
| 0.00  | 0.00  | 419152.52 | 660656.95          | 32.151741 | -103.947782 |


## SECTION DETAILS

| MD       | Inc   | Azi    | TVD      | +N/-S     | +E/-W   | Dleg  | TFace  | V/Sect   | Annotation                 |
|----------|-------|--------|----------|-----------|---------|-------|--------|----------|----------------------------|
| 0.00     | 0.00  | 0.00   | 0.00     | 0.00      | 0.00    | 0.00  | 0.00   | 0.00     |                            |
| 4210.00  | 0.00  | 0.00   | 4210.00  | 0.00      | 0.00    | 0.00  | 0.00   | 0.00     | Build 1°/100'              |
| 5210.01  | 10.00 | 271.50 | 5204.94  | 2.28      | -87.02  | 1.00  | 271.50 | 5.41     | Hold 10° Tangent           |
| 9815.10  | 10.00 | 271.50 | 9740.06  | 23.21     | -886.42 | 0.00  | 0.00   | 55.06    | KOP, Build & Turn 10°/100' |
| 10719.29 | 90.11 | 179.71 | 10307.36 | -551.33   | -983.65 | 10.00 | -91.75 | 635.94   | Landing Point              |
| 20698.29 | 90.11 | 179.71 | 10288.20 | -10530.18 | -932.47 | 0.00  | 0.00   | 10571.38 | TD at 20698.29' MD         |



Azimuths to Grid North  
 True North: -0.21°  
 Magnetic North: 6.58°

Magnetic Field  
 Strength: 47820.5nT  
 Dip Angle: 59.80°  
 Date: 12/9/2019  
 Model: HDGM\_FILE



# Oxy USA Inc. - Corral Bluff 11\_14 Fed Com 312H

## Drill Plan

### 1. Geologic Formations

|                            |       |                                    |     |
|----------------------------|-------|------------------------------------|-----|
| TVD of Target (ft):        | 10307 | Pilot Hole Depth (ft):             |     |
| Total Measured Depth (ft): | 20698 | Deepest Expected Fresh Water (ft): | 356 |

### Delaware Basin

| Formation       | MD-RKB (ft) | TVD-RKB (ft) | Expected Fluids |
|-----------------|-------------|--------------|-----------------|
| Rustler         | 356         | 356          |                 |
| Salado          | 752         | 752          | Salt            |
| Castile         | 1692        | 1692         | Salt            |
| Delaware        | 3245        | 3245         | Oil/Gas/Brine   |
| Bell Canyon     | 3248        | 3248         | Oil/Gas/Brine   |
| Cherry Canyon   | 4126        | 4126         | Oil/Gas/Brine   |
| Brushy Canyon   | 5556        | 5545         | Losses          |
| Bone Spring     | 7051        | 7018         | Oil/Gas         |
| Bone Spring 1st | 7968        | 7921         | Oil/Gas         |
| Bone Spring 2nd | 8837        | 8777         | Oil/Gas         |
| Bone Spring 3rd | 9977        | 9897         | Oil/Gas         |
| Wolfcamp        | 10363       | 10202        | Oil/Gas         |
| Penn            |             |              | Oil/Gas         |
| Strawn          |             |              | Oil/Gas         |

\*H2S, water flows, loss of circulation, abnormal pressures, etc.

### 2. Casing Program

| Section      | Hole Size (in) | MD        |         | TVD       |         | Csg. OD (in) | Csg Wt. (ppf) | Grade   | Conn.     |
|--------------|----------------|-----------|---------|-----------|---------|--------------|---------------|---------|-----------|
|              |                | From (ft) | To (ft) | From (ft) | To (ft) |              |               |         |           |
| Surface      | 14.75          | 0         | 692     | 0         | 692     | 10.75        | 45.5          | J-55    | BTC       |
| Intermediate | 9.875          | 0         | 9715    | 0         | 9640    | 7.625        | 26.4          | L-80 HC | BTC       |
| Production   | 6.75           | 0         | 20698   | 0         | 10307   | 5.5          | 20            | P-110   | Wedge 461 |

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

\*Oxy requests the option to run production casing with DQX, TORQ DQW, Wedge 425, Wedge 461, and/or Wedge 441 connections to accommodate hole conditions or drilling operations.

| All Casing SF Values will meet or exceed those below |          |                 |                  |
|------------------------------------------------------|----------|-----------------|------------------|
| SF Collapse                                          | SF Burst | Body SF Tension | Joint SF Tension |
| 1.125                                                | 1.2      | 1.4             | 1.4              |

## Annular Clearance Variance Request

As per the agreement reached in the Oxy/BLM face-to-face meeting on Feb 22, 2018, Oxy requests permission to allow deviation from the 0.422" annular clearance requirement from Onshore Order #2 under the following conditions:

1. Annular clearance to meet or exceed 0.422" between intermediate casing ID and production casing coupling only on the first 500' overlap between both casings.
2. Annular clearance less than 0.422" is acceptable for the curve and lateral portions of the production open hole section.

|                                                                                                                                                     | Y or N |
|-----------------------------------------------------------------------------------------------------------------------------------------------------|--------|
| Is casing new? If used, attach certification as required in Onshore Order #1                                                                        | Y      |
| Does casing meet API specifications? If no, attach casing specification sheet.                                                                      | Y      |
| Is premium or uncommon casing planned? If yes attach casing specification sheet.                                                                    | Y      |
| Does the above casing design meet or exceed BLM's minimum standards?<br>If not provide justification (loading assumptions, casing design criteria). | Y      |
| Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?                   | Y      |
| Is well located within Capitan Reef?                                                                                                                | N      |
| If yes, does production casing cement tie back a minimum of 50' above the Reef?                                                                     |        |
| Is well within the designated 4 string boundary.                                                                                                    |        |
| Is well located in SOPA but not in R-111-P?                                                                                                         | N      |
| If yes, are the first 2 strings cemented to surface and 3 <sup>rd</sup> string cement tied back 500' into previous casing?                          |        |
| Is well located in R-111-P and SOPA?                                                                                                                | N      |
| If yes, are the first three strings cemented to surface?                                                                                            |        |
| Is 2 <sup>nd</sup> string set 100' to 600' below the base of salt?                                                                                  |        |
| Is well located in high Cave/Karst?                                                                                                                 | N      |
| If yes, are there two strings cemented to surface?                                                                                                  |        |
| (For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?                                                              |        |
| Is well located in critical Cave/Karst?                                                                                                             | N      |
| If yes, are there three strings cemented to surface?                                                                                                |        |

### 3. Cementing Program

| Section | Stage | Slurry:                   | Sacks | Yield<br>(ft <sup>3</sup> /ft) | Density<br>(lb/gal) | Excess: | TOC   | Placement  | Description                   |
|---------|-------|---------------------------|-------|--------------------------------|---------------------|---------|-------|------------|-------------------------------|
| Surface | 1     | Surface - Tail            | 579   | 1.33                           | 14.8                | 100%    | -     | Circulate  | Class C+Accel.                |
| Int.    | 1     | Intermediate 1S - Tail    | 534   | 1.65                           | 13.2                | 5%      | 5,806 | Circulate  | Class H+Accel., Disper., Salt |
| Int.    | 2     | Intermediate 2S - Tail BH | 897   | 1.71                           | 13.3                | 25%     | -     | Bradenhead | Class C+Accel.                |
| Prod.   | 1     | Production - Tail         | 867   | 1.38                           | 13.2                | 25%     | 9,215 | Circulate  | Class H+Ret., Disper., Salt   |

## Offline Cementing

Oxy requests a variance to cement the 9.625" and/or 7.625" intermediate casing strings offline in accordance to the approved variance, EC Tran 461365.

The summarized operational sequence will be as follows:

Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe).

Land casing.

Fill pipe with kill weight fluid, and confirm well is static.

If well Oxy requests a variance to cement the 9.625" and/or 7.625" intermediate casing strings offline in accordance to the approved variance, EC Tran 461365.

The summarized operational sequence will be as follows:

1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe).
2. Land casing.
3. Fill pipe with kill weight fluid, and confirm well is static.
  - a. If well is not static notify BLM and kill well.
  - b. Once well is static notify BLM with intent to proceed with nipple down and offline cementing.
4. Set and pressure test annular packoff.
5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange. If any barrier fails to test, the BOP stack will not be nipped down until after the cement job is completed.
6. Skid rig to next well on pad.
7. Confirm well is static before removing cap flange.
8. If well is not static notify BLM and kill well prior to cementing or nipping up for further remediation.
9. Install offline cement tool.
10. Rig up cement equipment.
  - a. Notify BLM prior to cement job.
11. Perform cement job.
12. Confirm well is static and floats are holding after cement job.
13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Oxy requests permission to adjust the CBL requirement after bradenhead cement jobs, on 7-5/8" intermediate casings, as per the agreement reached in the OXY/BLM meeting on September 5, 2019.

### Three string wells:

- CBL will be required on one well per pad
- If the pumped volume of cement is less than permitted in the APD, BLM will be notified and a CBL may be run
- Echometer will be used after bradenhead cement job to determine TOC before pumping top-out cement



#### 4. Pressure Control Equipment

| BOP installed and tested before drilling which hole? | Size?   | Min. Required WP | Type       |  | ✓ | Tested to:              | Deepest TVD Depth (ft) per Section: |
|------------------------------------------------------|---------|------------------|------------|--|---|-------------------------|-------------------------------------|
| 9.875" Hole                                          | 13-5/8" | 3M               | Annular    |  | ✓ | 70% of working pressure | 9640                                |
|                                                      |         | 3M               | Blind Ram  |  | ✓ | 250 psi / 3000 psi      |                                     |
|                                                      |         |                  | Pipe Ram   |  |   |                         |                                     |
|                                                      |         |                  | Double Ram |  | ✓ |                         |                                     |
|                                                      |         |                  | Other*     |  |   |                         |                                     |
| 6.75" Hole                                           | 13-5/8" | 5M               | Annular    |  | ✓ | 70% of working pressure | 10307                               |
|                                                      |         | 5M               | Blind Ram  |  | ✓ | 250 psi / 5000 psi      |                                     |
|                                                      |         |                  | Pipe Ram   |  |   |                         |                                     |
|                                                      |         |                  | Double Ram |  | ✓ |                         |                                     |
|                                                      |         |                  | Other*     |  |   |                         |                                     |

\*Specify if additional ram is utilized

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold.

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|   | Formation integrity test will be performed per Onshore Order #2.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |
|   | On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.                                                                                                                                                                                                                                                                                                                                                                                                                              |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|   | A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| Y | Are anchors required by manufacturer?                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |
|   | A multibowl or a unionized multibowl wellhead system will be employed. The wellhead and connection to the BOPE will meet all API 6A requirements. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. We will test the flange connection of the wellhead with a test port that is directly in the flange. We are proposing that we will run the wellhead through the rotary prior to cementing surface casing as discussed with the BLM on October 8, 2015.<br><br>See attached schematics. |

## BOP Break Testing Request

Oxy requests permission to adjust the BOP break testing requirements as per the agreement reached in the OXY/BLM meeting on September 5, 2019.

BOP break test under the following conditions:

- After a full BOP test is conducted
- When skidding to drill an intermediate section where ICP is set into the third Bone Spring or shallower.

If the kill line is broken prior to skid, two tests will be performed.

- 1) Wellhead flange, co-flex hose, kill line connections and upper pipe rams
- 2) Wellhead flange, HCR valve, check valve, upper pipe rams

If the kill line is not broken prior to skid, only one test will be performed.

- 1) Wellhead flange, co-flex hose, check valve, upper pipe rams

**Oxy will use Cameron ADAPT wellhead system that uses an OEC top flange connection. This connection has been fully vetted and verified by API to Spec 6A and carries an API monogram.**

## 5. Mud Program

| Section      | Depth - MD |         | Depth - TVD |         | Type                                   | Weight (ppg) | Viscosity | Water Loss |
|--------------|------------|---------|-------------|---------|----------------------------------------|--------------|-----------|------------|
|              | From (ft)  | To (ft) | From (ft)   | To (ft) |                                        |              |           |            |
| Surface      | 0          | 692     | 0           | 692     | Water-Based Mud                        | 8.6 - 8.8    | 40-60     | N/C        |
| Intermediate | 692        | 9715    | 692         | 9640    | Saturated Brine-Based or Oil-Based Mud | 8.0 - 10.0   | 35-45     | N/C        |
| Production   | 9715       | 20698   | 9640        | 10307   | Water-Based or Oil-Based Mud           | 9.5 - 12.5   | 38-50     | N/C        |

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times. The following is a general list of products: Barite, Bentonite, Gypsum, Lime, Soda Ash, Caustic Soda, Nut Plug, Cedar Fiber, Cotton Seed Hulls, Drilling Paper, Salt Water Clay, CACL2. Oxy will use a closed mud system.

|                                                         |                                |
|---------------------------------------------------------|--------------------------------|
| What will be used to monitor the loss or gain of fluid? | PVT/MD Totco/Visual Monitoring |
|---------------------------------------------------------|--------------------------------|

## 6. Logging and Testing Procedures

| Logging, Coring and Testing. |                                                                              |
|------------------------------|------------------------------------------------------------------------------|
| Yes                          | Will run GR from TD to surface (horizontal well – vertical portion of hole). |
|                              | Stated logs run will be in the Completion Report and submitted to the BLM.   |
| No                           | Logs are planned based on well control or offset log information.            |
| No                           | Drill stem test? If yes, explain                                             |
| No                           | Coring? If yes, explain                                                      |

| Additional logs planned | Interval    |
|-------------------------|-------------|
| No                      | Resistivity |
| No                      | Density     |
| Yes                     | CBL         |
| Yes                     | Mud log     |
| No                      | PEX         |

## 7. Drilling Conditions

| Condition                     | Specify what type and where? |
|-------------------------------|------------------------------|
| BH Pressure at deepest TVD    | 6700 psi                     |
| Abnormal Temperature          | No                           |
| BH Temperature at deepest TVD | 163°F                        |

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

|   |                   |
|---|-------------------|
| N | H2S is present    |
| Y | H2S Plan attached |

## 8. Other facets of operation

|                                                                                                                                                                                                                                                                                                                                                                                                                                 | Yes/No |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|
| Will the well be drilled with a walking/skidding operation? If yes, describe.<br>We plan to drill the 4 well pad in batch by section: all surface sections, intermediate sections and production sections. The wellhead will be secured with a night cap whenever the rig is not over the well.                                                                                                                                 | Yes    |
| Will more than one drilling rig be used for drilling operations? If yes, describe.<br>Oxy requests the option to contract a Surface Rig to drill, set surface casing, and cement for this well. If the timing between rigs is such that Oxy would not be able to preset surface, the Primary Rig will MIRU and drill the well in its entirety per the APD. Please see the attached document for information on the spudder rig. | Yes    |


**Total Estimated Cuttings Volume:** 1488 bbls

### Attachments

- ☒ Directional Plan
- ☒ H2S Contingency Plan
- ☒ Flex III Attachments
- ☒ Spudder Rig Attachment
- ☒ Premium Connection Specs

## 9. Company Personnel

| Name             | Title                        | Office Phone | Mobile Phone |
|------------------|------------------------------|--------------|--------------|
| Garrett Granier  | Drilling Engineer            | 713-513-6633 | 832-265-0581 |
| Derek Adam       | Drilling Engineer Supervisor | 713-366-5170 | 916-802-8873 |
| Casey Martin     | Drilling Superintendent      | 713-497-2530 | 337-764-4278 |
| Kevin Threadgill | Drilling Manager             | 713-366-5958 | 361-815-0788 |




**Notes:**

1. THIS IS A PROPOSAL DRAWING AND DIMENSIONS SHOWN ARE SUBJECT TO CHANGE DURING THE FINAL DESIGN PROCESS.


2. DIGITALLY ENABLED SOLUTIONS, CHOKES AND ESD'S AVAILABLE ON REQUEST

| CONFIDENTIAL      |                            |                                                                                                                 |                 |
|-------------------|----------------------------|-----------------------------------------------------------------------------------------------------------------|-----------------|
| SURFACE TREATMENT | DO NOT SCALE               | <br>A Schlumberger Company | SURFACE SYSTEMS |
| DRAWN BY          | D. GOTTUNG                 | DATE                                                                                                            | 2 Dec 21        |
| CHECKED BY        | D. GOTTUNG                 | DATE                                                                                                            | 2 Dec 21        |
| APPROVED BY       | D. GOTTUNG                 | DATE                                                                                                            | 2 Dec 21        |
| ESTIMATED WEIGHT  | 6515.617 LBS (2955.434 KG) | INTERNAL USE BOM                                                                                                |                 |
| SHEET             |                            | 4 of 4                                                                                                          | SD-053434-94-05 |
|                   |                            | REV                                                                                                             | 01              |

# 5/10M BOP Stack



# 10M Choke Panel




1. Choke Manifold Valve
2. Choke Manifold Valve
3. Choke Manifold Valve
4. Choke Manifold Valve
5. Choke Manifold Valve
6. Choke Manifold Valve
7. Choke Manifold Valve
8. PC – Power Choke
9. Choke Manifold Valve
10. Choke Manifold Valve
11. Choke Manifold Valve
12. LMC – Lower Manual Choke
13. UMC – Upper manual choke
15. Choke Manifold Valve
16. Choke Manifold Valve
17. Choke Manifold Valve
18. Choke Manifold Valve


21. Vertical Choke Manifold Valve



**\*All Valves 3" minimum**





## Gas Separator Routing Flex III Rigs



**Choke Manifold – Gas Separator (Top View)****Choke Manifold – Gas Separator (Side View)**

## OXY's Minimum Design Criteria

Burst, Collapse, and Tensile SF are calculated using Landmark's Stress Check (Casing Design) software. A sundry will be requested if any lesser grade or different size casing is substituted.

### 1) Casing Design Assumptions

#### a) Burst Loads

##### CSG Test (Surface)

- Internal: Displacement fluid + pressure required to comply with regulatory casing test pressures. This will comply with both Onshore Oil and Gas Order No. 2 and 19.15.16 of the OCD Rules.
- External: Pore pressure in open hole.

##### CSG Test (Intermediate)

- Internal: Displacement fluid + pressure required to comply with regulatory casing test pressures. This will comply with both Onshore Oil and Gas Order No. 2 and 19.15.16 of the OCD Rules.
- External: Mud Weight to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

##### CSG Test (Production)

- Internal:
  - For Drilling: Displacement fluid + pressure required to comply with regulatory casing test pressures. This will comply with both Onshore Oil and Gas Order No. 2 and 19.15.16 of the OCD Rules.
  - For Production: The design pressure test should be the greater of (1) the planned test pressure prior to stimulation down the casing. (2) the regulatory test pressure, and (3) the expected gas lift system pressure. The design test fluid should be the fluid associated with pressure test having the greatest pressure.
- External:
  - For Drilling: Mud Weight to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.
  - For Production: Mud base-fluid density to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

##### Gas Column (Surface)

- Internal: Assumes a full column of gas in the casing with a Gas/Oil Gradient of 0.1 psi/ft in the absence of better information. It is limited to the controlling pressure based on the fracture pressure at the shoe or the maximum expected pore pressure within the next drilling interval, whichever results in a lower surface pressure.
- External: Fluid gradient below TOC, pore pressure from the TOC to the Intermediate CSG shoe (if applicable), and MW of the drilling mud that was in the hole when the CSG was run from Intermediate CSG shoe to surface.

##### Bullheading (Surface / Intermediate)

- Internal: The string must be designed to withstand a pressure profile based on the fracture pressure at the casing shoe with a column of water above the shoe plus an additional surface pressure (in psi) of  $0.02 \times MD$  of the shoe to account for pumping friction pressure.
- External: Mud weight to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

**Gas Kick (Intermediate)**

- The string must be designed to at least a gas kick load case unless the rig is unable to detect a kick. For the gas kick load case, the internal pressure profile must be based on a minimum volume of 50 bbl or the minimum kick detection capability of the rig, whichever is greater, and a kick intensity of 2.0 ppg for Class 1, 1.0 ppg of Class 2, and 0.5 ppg for Class 3 and 4 wells.
- Internal: Influx depth of the maximum pore pressure of 0.55 "gas kick gravity" of gas to surface while drilling the next hole section.
- External: Mud weight to the TOC, cement mix water gradient below TOC, and pore pressure in open hole.

**Tubing Leak Near Surface While Producing (Production)**

- Internal: SITP plus a packer fluid gradient to the shoe or top of packer.
- External: Mud base-fluid density to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

**Tubing Leak Near Surface While Stimulating (Production)**

- Internal: Surface pressure or pressure-relief system pressure, whichever is lower plus packer fluid gradient.
- External: Mud base-fluid density to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

**Injection / Stimulation Down Casing (Production)**

- Internal: Surface pressure plus injection fluid gradient.
- External: Mud base-fluid density to TOC, cement mix water gradient (8.4 ppg) below TOC, and pore pressure in open hole.

**b) Collapse Loads****Lost Circulation (Surface / Intermediate)**

- Internal: Lost circulation at the TD of the next hole section, and the fluid level falls to a depth where the hydrostatic of the mud equals pore pressure at the depth of the lost circulation zone.
- External: MW of the drilling mud that was in the hole when the casing was run.

**Cementing (Surface / Intermediate / Production)**

- Internal: Displacement fluid density.
- External: Mud weight from TOC to surface and cement slurry weight from TOC to casing shoe.

**Full Evacuation (Production)**

- Internal: Full void pipe.
- External: MW of drilling mud in the hole when the casing was run.

**c) Tension Loads****Running Casing (Surface / Intermediate / Production)**

- Axial: Buoyant weight of the string plus the lesser of 100,000 lb or the string weight in air.

**Green Cement (Surface / Intermediate / Production)**

- Axial: Buoyant weight of the string plus cement plug bump pressure load.



Fluid Technology

Quality Document

## CERTIFICATE OF CONFORMITY

**Supplier** : CONTITECH RUBBER INDUSTRIAL KFT.  
**Equipment** : 6 pcs. Choke and Kill Hose with installed couplings  
**Type** : 3" x 10,67 m WP: 10000 psi  
**Supplier File Number** : 412638  
**Date of Shipment** : April. 2008  
**Customer** : Phoenix Beattie Co.  
**Customer P.o.** : 002491  
**Referenced Standards**  
**/ Codes / Specifications** : API Spec 16 C  
**Serial No.:** 52754,52755,52776,52777,52778,52782

## STATEMENT OF CONFORMITY

We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU

Signed : .....

A handwritten signature in black ink, appearing to read "Jack G. G.", written over a dotted line.

ContiTech Rubber  
Industrial Kft.  
Quality Control Dept.  
(1)

Date: 04. April. 2008

Position: Q.C. Manager

Coflex Hose Certification

Page: 1/1

|    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |      |
|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|
| 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 | 53 | 54 | 55 | 56 | 57 | 58 | 59 | 60 | 61 | 62 | 63 | 64 | 65 | 66 | 67 | 68 | 69 | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 | 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 | 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 | 101 | 102 | 103 | 104 | 105 | 106 | 107 | 108 | 109 | 110 | 111 | 112 | 113 | 114 | 115 | 116 | 117 | 118 | 119 | 120 | 121 | 122 | 123 | 124 | 125 | 126 | 127 | 128 | 129 | 130 | 131 | 132 | 133 | 134 | 135 | 136 | 137 | 138 | 139 | 140 | 141 | 142 | 143 | 144 | 145 | 146 | 147 | 148 | 149 | 150 | 151 | 152 | 153 | 154 | 155 | 156 | 157 | 158 | 159 | 160 | 161 | 162 | 163 | 164 | 165 | 166 | 167 | 168 | 169 | 170 | 171 | 172 | 173 | 174 | 175 | 176 | 177 | 178 | 179 | 180 | 181 | 182 | 183 | 184 | 185 | 186 | 187 | 188 | 189 | 190 | 191 | 192 | 193 | 194 | 195 | 196 | 197 | 198 | 199 | 200 | 201 | 202 | 203 | 204 | 205 | 206 | 207 | 208 | 209 | 210 | 211 | 212 | 213 | 214 | 215 | 216 | 217 | 218 | 219 | 220 | 221 | 222 | 223 | 224 | 225 | 226 | 227 | 228 | 229 | 230 | 231 | 232 | 233 | 234 | 235 | 236 | 237 | 238 | 239 | 240 | 241 | 242 | 243 | 244 | 245 | 246 | 247 | 248 | 249 | 250 | 251 | 252 | 253 | 254 | 255 | 256 | 257 | 258 | 259 | 260 | 261 | 262 | 263 | 264 | 265 | 266 | 267 | 268 | 269 | 270 | 271 | 272 | 273 | 274 | 275 | 276 | 277 | 278 | 279 | 280 | 281 | 282 | 283 | 284 | 285 | 286 | 287 | 288 | 289 | 290 | 291 | 292 | 293 | 294 | 295 | 296 | 297 | 298 | 299 | 300 | 301 | 302 | 303 | 304 | 305 | 306 | 307 | 308 | 309 | 310 | 311 | 312 | 313 | 314 | 315 | 316 | 317 | 318 | 319 | 320 | 321 | 322 | 323 | 324 | 325 | 326 | 327 | 328 | 329 | 330 | 331 | 332 | 333 | 334 | 335 | 336 | 337 | 338 | 339 | 340 | 341 | 342 | 343 | 344 | 345 | 346 | 347 | 348 | 349 | 350 | 351 | 352 | 353 | 354 | 355 | 356 | 357 | 358 | 359 | 360 | 361 | 362 | 363 | 364 | 365 | 366 | 367 | 368 | 369 | 370 | 371 | 372 | 373 | 374 | 375 | 376 | 377 | 378 | 379 | 380 | 381 | 382 | 383 | 384 | 385 | 386 | 387 | 388 | 389 | 390 | 391 | 392 | 393 | 394 | 395 | 396 | 397 | 398 | 399 | 400 | 401 | 402 | 403 | 404 | 405 | 406 | 407 | 408 | 409 | 410 | 411 | 412 | 413 | 414 | 415 | 416 | 417 | 418 | 419 | 420 | 421 | 422 | 423 | 424 | 425 | 426 | 427 | 428 | 429 | 430 | 431 | 432 | 433 | 434 | 435 | 436 | 437 | 438 | 439 | 440 | 441 | 442 | 443 | 444 | 445 | 446 | 447 | 448 | 449 | 450 | 451 | 452 | 453 | 454 | 455 | 456 | 457 | 458 | 459 | 460 | 461 | 462 | 463 | 464 | 465 | 466 | 467 | 468 | 469 | 470 | 471 | 472 | 473 | 474 | 475 | 476 | 477 | 478 | 479 | 480 | 481 | 482 | 483 | 484 | 485 | 486 | 487 | 488 | 489 | 490 | 491 | 492 | 493 | 494 | 495 | 496 | 497 | 498 | 499 | 500 | 501 | 502 | 503 | 504 | 505 | 506 | 507 | 508 | 509 | 510 | 511 | 512 | 513 | 514 | 515 | 516 | 517 | 518 | 519 | 520 | 521 | 522 | 523 | 524 | 525 | 526 | 527 | 528 | 529 | 530 | 531 | 532 | 533 | 534 | 535 | 536 | 537 | 538 | 539 | 540 | 541 | 542 | 543 | 544 | 545 | 546 | 547 | 548 | 549 | 550 | 551 | 552 | 553 | 554 | 555 | 556 | 557 | 558 | 559 | 560 | 561 | 562 | 563 | 564 | 565 | 566 | 567 | 568 | 569 | 570 | 571 | 572 | 573 | 574 | 575 | 576 | 577 | 578 | 579 | 580 | 581 | 582 | 583 | 584 | 585 | 586 | 587 | 588 | 589 | 590 | 591 | 592 | 593 | 594 | 595 | 596 | 597 | 598 | 599 | 600 | 601 | 602 | 603 | 604 | 605 | 606 | 607 | 608 | 609 | 610 | 611 | 612 | 613 | 614 | 615 | 616 | 617 | 618 | 619 | 620 | 621 | 622 | 623 | 624 | 625 | 626 | 627 | 628 | 629 | 630 | 631 | 632 | 633 | 634 | 635 | 636 | 637 | 638 | 639 | 640 | 641 | 642 | 643 | 644 | 645 | 646 | 647 | 648 | 649 | 650 | 651 | 652 | 653 | 654 | 655 | 656 | 657 | 658 | 659 | 660 | 661 | 662 | 663 | 664 | 665 | 666 | 667 | 668 | 669 | 670 | 671 | 672 | 673 | 674 | 675 | 676 | 677 | 678 | 679 | 680 | 681 | 682 | 683 | 684 | 685 | 686 | 687 | 688 | 689 | 690 | 691 | 692 | 693 | 694 | 695 | 696 | 697 | 698 | 699 | 700 | 701 | 702 | 703 | 704 | 705 | 706 | 707 | 708 | 709 | 710 | 711 | 712 | 713 | 714 | 715 | 716 | 717 | 718 | 719 | 720 | 721 | 722 | 723 | 724 | 725 | 726 | 727 | 728 | 729 | 730 | 731 | 732 | 733 | 734 | 735 | 736 | 737 | 738 | 739 | 740 | 741 | 742 | 743 | 744 | 745 | 746 | 747 | 748 | 749 | 750 | 751 | 752 | 753 | 754 | 755 | 756 | 757 | 758 | 759 | 760 | 761 | 762 | 763 | 764 | 765 | 766 | 767 | 768 | 769 | 770 | 771 | 772 | 773 | 774 | 775 | 776 | 777 | 778 | 779 | 780 | 781 | 782 | 783 | 784 | 785 | 786 | 787 | 788 | 789 | 790 | 791 | 792 | 793 | 794 | 795 | 796 | 797 | 798 | 799 | 800 | 801 | 802 | 803 | 804 | 805 | 806 | 807 | 808 | 809 | 810 | 811 | 812 | 813 | 814 | 815 | 816 | 817 | 818 | 819 | 820 | 821 | 822 | 823 | 824 | 825 | 826 | 827 | 828 | 829 | 830 | 831 | 832 | 833 | 834 | 835 | 836 | 837 | 838 | 839 | 840 | 841 | 842 | 843 | 844 | 845 | 846 | 847 | 848 | 849 | 850 | 851 | 852 | 853 | 854 | 855 | 856 | 857 | 858 | 859 | 860 | 861 | 862 | 863 | 864 | 865 | 866 | 867 | 868 | 869 | 870 | 871 | 872 | 873 | 874 | 875 | 876 | 877 | 878 | 879 | 880 | 881 | 882 | 883 | 884 | 885 | 886 | 887 | 888 | 889 | 890 | 891 | 892 | 893 | 894 | 895 | 896 | 897 | 898 | 899 | 900 | 901 | 902 | 903 | 904 | 905 | 906 | 907 | 908 | 909 | 910 | 911 | 912 | 913 | 914 | 915 | 916 | 917 | 918 | 919 | 920 | 921 | 922 | 923 | 924 | 925 | 926 | 927 | 928 | 929 | 930 | 931 | 932 | 933 | 934 | 935 | 936 | 937 | 938 | 939 | 940 | 941 | 942 | 943 | 944 | 945 | 946 | 947 | 948 | 949 | 950 | 951 | 952 | 953 | 954 | 955 | 956 | 957 | 958 | 959 | 960 | 961 | 962 | 963 | 964 | 965 | 966 | 967 | 968 | 969 | 970 | 971 | 972 | 973 | 974 | 975 | 976 | 977 | 978 | 979 | 980 | 981 | 982 | 983 | 984 | 985 | 986 | 987 | 988 | 989 | 990 | 991 | 992 | 993 | 994 | 995 | 996 | 997 | 998 | 999 | 1000 |
|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|

Back  
ContiTech Rubber  
Industrial Kft.  
Quality Control Dept.  
(2)



## Coflex Hose Certification

[illegible]

We hereby certify that these goods have been inspected by our Quality Management System, and to the best of our knowledge are found to conform to relevant industry standards within the requirements of the purchase order as issued to Phoenix Beattie Corporation.

05/23/08



Coflex Hose Certification

Form No 100/12

**Phoenix Beattie Corp**

11535 Brittmoore Park Drive  
Houston, TX 77041  
Tel: (832) 327-0141  
Fax: (832) 327-0148  
E-mail mail@phoenixbeattie.com  
www.phoenixbeattie.com

**Delivery Note**

|                                                                                                                      |             |                                                                                                                                       |        |             |   |
|----------------------------------------------------------------------------------------------------------------------|-------------|---------------------------------------------------------------------------------------------------------------------------------------|--------|-------------|---|
| <b>Customer Order Number</b>                                                                                         | 370-369-001 | <b>Delivery Note Number</b>                                                                                                           | 003078 | <b>Page</b> | 1 |
| <b>Customer / Invoice Address</b><br>HELMERICH & PAYNE INT'L DRILLING CO<br>1437 SOUTH BOULDER<br>TULSA, OK<br>74119 |             | <b>Delivery / Address</b><br>HELMERICH & PAYNE IDC<br>ATTN: JOE STEPHENSON - RIG 370<br>13609 INDUSTRIAL ROAD<br>HOUSTON, TX<br>77015 |        |             |   |

|                        |                                         |                                  |             |
|------------------------|-----------------------------------------|----------------------------------|-------------|
| <b>Customer Acc No</b> | <b>Phoenix Beattie Contract Manager</b> | <b>Phoenix Beattie Reference</b> | <b>Date</b> |
| H01                    | JJL                                     | 006330                           | 05/23/2008  |

| Item No | Beattie Part Number / Description                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty Ordered | Qty Sent | Qty To Follow |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----------|---------------|
| 1       | HP10CK3A-35-4F1<br>3" 10K 16C C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/<br>End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange<br>End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange<br>c/w BX155 Standard ring groove at each end<br>Suitable for H2S Service<br>Working pressure: 10,000psi<br>Test pressure: 15,000psi<br>Standard: API 16C Full specification<br>Armor Guarding: Included<br>Fire Rating: Not Included<br>Temperature rating: -20 Deg C to +100 Deg C | 1           | 1        | 0             |
| 2       | SECK3-HPF3<br>LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1<br>2 x 160mm ID Safety Clamps<br>2 x 244mm ID Lifting Collars & element C's<br>2 x 7ft Stainless Steel wire rope 3/4" OD<br>4 x 7.75t Shackles                                                                                                                                                                                                                                                                  | 1           | 1        | 0             |
| 3       | SC725-200CS<br>SAFETY CLAMP 200MM 7.25T C/S GALVANISED                                                                                                                                                                                                                                                                                                                                                                                                                         | 1           | 1        | 0             |

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.  
Returns may be subject to a handling charge.

Coflex Hose Certification

Fluid Technology

Quality Document

| QUALITY CONTROL<br>INSPECTION AND TEST CERTIFICATE                                                                                                    |           |                                      |                 | CERT. N°: 746                          |  |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|--------------------------------------|-----------------|----------------------------------------|--|
| PURCHASER: Phoenix Beattie Co.                                                                                                                        |           |                                      |                 | P.O. N°: 002491                        |  |
| CONTITECH ORDER N°: 412638                                                                                                                            |           | HOSE TYPE: 3" ID Choke and Kill Hose |                 |                                        |  |
| HOSE SERIAL N°: 52777                                                                                                                                 |           | NOMINAL / ACTUAL LENGTH: 10,67 m     |                 |                                        |  |
| W.P. 68,96 MPa 10000 psi                                                                                                                              |           | T.P. 103,4 MPa 15000 psi             |                 | Duration: 60 ~ min.                    |  |
| Pressure test with water at ambient temperature<br><br><p style="text-align: center;">See attachment. (1 page)</p>                                    |           |                                      |                 |                                        |  |
| ↑ 10 mm = 10 Min.<br>→ 10 mm = 25 MPa                                                                                                                 |           |                                      |                 |                                        |  |
| COUPLINGS                                                                                                                                             |           |                                      |                 |                                        |  |
| Type                                                                                                                                                  | Serial N° |                                      | Quality         | Heat N°                                |  |
| 3" coupling with<br>4 1/16" Flange end                                                                                                                | 917       | 913                                  | AISI 4130       | T7998A                                 |  |
|                                                                                                                                                       |           |                                      | AISI 4130       | 26984                                  |  |
| INFOCHIP INSTALLED                                                                                                                                    |           |                                      |                 | API Spec 16 C<br>Temperature rate: "B" |  |
| All metal parts are flawless                                                                                                                          |           |                                      |                 |                                        |  |
| WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT. |           |                                      |                 |                                        |  |
| Date:                                                                                                                                                 | Inspector |                                      | Quality Control |                                        |  |
| 04. April. 2008                                                                                                                                       |           |                                      |                 |                                        |  |

Coflex Hose Certification

Form No 100/12

**Phoenix Beattie Corp**

11535 Brittmoore Park Drive  
Houston, TX 77041  
Tel: (832) 327-0141  
Fax: (832) 327-0148  
E-mail mail@phoenixbeattie.com  
www.phoenixbeattie.com

**Delivery Note**

|                                                                                                                      |             |                                                                                                                                       |        |             |   |
|----------------------------------------------------------------------------------------------------------------------|-------------|---------------------------------------------------------------------------------------------------------------------------------------|--------|-------------|---|
| <b>Customer Order Number</b>                                                                                         | 370-369-001 | <b>Delivery Note Number</b>                                                                                                           | 003078 | <b>Page</b> | 2 |
| <b>Customer / Invoice Address</b><br>HELMERICH & PAYNE INT'L DRILLING CO<br>1437 SOUTH BOULDER<br>TULSA, OK<br>74119 |             | <b>Delivery / Address</b><br>HELMERICH & PAYNE IDC<br>ATTN: JOE STEPHENSON - RIG 370<br>13609 INDUSTRIAL ROAD<br>HOUSTON, TX<br>77015 |        |             |   |

|                        |                                         |                                  |             |
|------------------------|-----------------------------------------|----------------------------------|-------------|
| <b>Customer Acc No</b> | <b>Phoenix Beattie Contract Manager</b> | <b>Phoenix Beattie Reference</b> | <b>Date</b> |
| H01                    | JJL                                     | 006330                           | 05/23/2008  |

| Item No | Beattie Part Number / Description                                                                                                                                                                 | Qty Ordered | Qty Sent | Qty To Follow |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----------|---------------|
| 4       | SC725-132CS<br>SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS                                                                                                                                  | 1           | 1        | 0             |
| 5       | 00CERT-HYDRO<br>HYDROSTATIC PRESSURE TEST CERTIFICATE                                                                                                                                             | 1           | 1        | 0             |
| 6       | 00CERT-LOAD<br>LOAD TEST CERTIFICATES                                                                                                                                                             | 1           | 1        | 0             |
| 7       | 00FREIGHT<br>INBOUND / OUTBOUND FREIGHT<br>PRE-PAY & ADD TO FINAL INVOICE<br>NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING<br>THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT | 1           | 1        | 0             |

Phoenix Beattie Inspection Signature :

Received In Good Condition : Signature

Print Name

Date

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days.  
Returns may be subject to a handling charge.

**OXY USA Inc**  
**APD ATTACHMENT: SPUDDER RIG DATA**

**OPERATOR NAME / NUMBER:** OXY USA Inc

**1. SUMMARY OF REQUEST:**


Oxy USA respectfully requests approval for the following operations for the surface hole in the drill plan:

1. Utilize a spudder rig to pre-set surface casing for time and cost savings.

**2. Description of Operations**

1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
  - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
  - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
2. The wellhead will be installed and tested as soon as the surface casing is cut off and the WOC time has been reached.
3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
  - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. Spudder rig operations are expected to take 2-3 days per well on the pad.
5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
6. Drilling operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nipped up and tested on the wellhead before drilling operations resume on each well.
  - a. The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
  - b. The BLM will be contacted / notified 24 hours before the larger rig moves back on the pre-set locations.
7. Oxy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
8. Once the rig is removed, Oxy will secure the wellhead area by placing a guard rail around the cellar area.

# Spudder Rig Layout





# TenarisHydril Wedge 425®



| Coupling       | Pipe Body       |
|----------------|-----------------|
| Grade: P110-CY | Grade: P110-CY  |
| Body: White    | 1st Band: White |
| 1st Band: Grey | 2nd Band: Grey  |
| 2nd Band: -    | 3rd Band: -     |
| 3rd Band: -    | 4th Band: -     |
|                | 5th Band: -     |
|                | 6th Band: -     |

|                      |           |                 |              |       |         |
|----------------------|-----------|-----------------|--------------|-------|---------|
| Outside Diameter     | 5.500 in. | Wall Thickness  | 0.361 in.    | Grade | P110-CY |
| Min. Wall Thickness  | 87.50 %   | Pipe Body Drift | API Standard | Type  | Casing  |
| Connection OD Option | REGULAR   |                 |              |       |         |

## Pipe Body Data

| Geometry       |           |                  |             | Performance                  |              |
|----------------|-----------|------------------|-------------|------------------------------|--------------|
| Nominal OD     | 5.500 in. | Wall Thickness   | 0.361 in.   | Body Yield Strength          | 641 x1000 lb |
| Nominal Weight | 20 lb/ft  | Plain End Weight | 19.83 lb/ft | Min. Internal Yield Pressure | 12,640 psi   |
| Drift          | 4.653 in. | OD Tolerance     | API         | SMYS                         | 110,000 psi  |
| Nominal ID     | 4.778 in. |                  |             | Collapse Pressure            | 11,100 psi   |

## Connection Data

| Geometry             |           | Performance                |              | Make-Up Torques         |              |
|----------------------|-----------|----------------------------|--------------|-------------------------|--------------|
| Connection OD        | 5.777 in. | Tension Efficiency         | 90 %         | Minimum                 | 15,700 ft-lb |
| Connection ID        | 4.734 in. | Joint Yield Strength       | 577 x1000 lb | Optimum                 | 19,600 ft-lb |
| Make-up Loss         | 5.823 in. | Internal Pressure Capacity | 12,640 psi   | Maximum                 | 21,600 ft-lb |
| Threads per inch     | 3.77      | Compression Efficiency     | 90 %         |                         |              |
| Connection OD Option | Regular   | Compression Strength       | 577 x1000 lb | Operation Limit Torques |              |
|                      |           | Max. Allowable Bending     | 82 °/100 ft  | Operating Torque        | 29,000 ft-lb |
|                      |           | External Pressure Capacity | 11,100 psi   | Yield Torque            | 36,000 ft-lb |

## Notes

This connection is fully interchangeable with:  
TORQ® SFW™ - 5.5 in. - 0.361 in.  
Connections with Dopeless® Technology are fully compatible with the same connection in its Standard version

For the latest performance data, always visit our website: [www.tenaris.com](http://www.tenaris.com)

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information –if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at [www.tenaris.com](http://www.tenaris.com) . ©Tenaris 2021. All rights reserved.



# TenarisHydril Wedge 441®



| Coupling       | Pipe Body       |
|----------------|-----------------|
| Grade: P110-CY | Grade: P110-CY  |
| Body: White    | 1st Band: White |
| 1st Band: Grey | 2nd Band: Grey  |
| 2nd Band: -    | 3rd Band: -     |
| 3rd Band: -    | 4th Band: -     |
|                | 5th Band: -     |
|                | 6th Band: -     |

|                      |           |                |              |       |         |
|----------------------|-----------|----------------|--------------|-------|---------|
| Outside Diameter     | 5.500 in. | Wall Thickness | 0.361 in.    | Grade | P110-CY |
| Min. Wall Thickness  | 87.50 %   | Drift          | API Standard | Type  | Casing  |
| Connection OD Option | REGULAR   |                |              |       |         |

Pipe Body Data

| Geometry       |           |                  |             | Performance                  |              |
|----------------|-----------|------------------|-------------|------------------------------|--------------|
| Nominal OD     | 5.500 in. | Wall Thickness   | 0.361 in.   | Body Yield Strength          | 641 x1000 lb |
| Nominal Weight | 20 lb/ft  | Plain End Weight | 19.83 lb/ft | Min. Internal Yield Pressure | 12,640 psi   |
| Drift          | 4.653 in. | OD Tolerance     | API         | SMYS                         | 110,000 psi  |
| Nominal ID     | 4.778 in. |                  |             | Collapse Pressure            | 11,100 psi   |

Connection Data

| Geometry             |           | Performance                |              | Make-Up Torques         |              |
|----------------------|-----------|----------------------------|--------------|-------------------------|--------------|
| Connection OD        | 5.852 in. | Tension Efficiency         | 81.50 %      | Minimum                 | 15,000 ft-lb |
| Coupling Length      | 8.714 in. | Joint Yield Strength       | 522 x1000 lb | Optimum                 | 16,000 ft-lb |
| Connection ID        | 4.778 in. | Internal Pressure Capacity | 12,640 psi   | Maximum                 | 19,200 ft-lb |
| Make-up Loss         | 3.780 in. | Compression Efficiency     | 81.50 %      | Operation Limit Torques |              |
| Threads per inch     | 3.40      | Compression Strength       | 522 x1000 lb | Operating Torque        | 32,000 ft-lb |
| Connection OD Option | Regular   | Max. Allowable Bending     | 71 °/100 ft  | Yield Torque            | 38,000 ft-lb |
|                      |           | External Pressure Capacity | 11,100 psi   | Buck-On                 |              |
|                      |           |                            |              | Minimum                 | 19,200 ft-lb |
|                      |           |                            |              | Maximum                 | 20,700 ft-lb |

Notes

This connection is fully interchangeable with:  
Wedge 441® - 5.5 in. - 0.304 in.  
Connections with Dopeless® Technology are fully compatible with the same connection in its Standard version

For the latest performance data, always visit our website: [www.tenaris.com](http://www.tenaris.com)

Tenaris has issued this document for general information only, and the information in this document, including, without limitation, any pictures, drawings or designs ("Information") is not intended to constitute professional or any other type of advice or recommendation and is provided on an "as is" basis. No warranty is given. Tenaris has not independently verified any information –if any- provided by the user in connection with, or for the purpose of, the Information contained hereunder. The use of the Information is at user's own risk and Tenaris does not assume any responsibility or liability of any kind for any loss, damage or injury resulting from, or in connection with any Information contained hereunder or any use thereof. The Information in this document is subject to change or modification without notice. Tenaris's products and services are subject to Tenaris's standard terms and conditions or otherwise to the terms resulting from the respective contracts of sale or services, as the case may be, between petitioner and Tenaris. For more complete information please contact a Tenaris's representative or visit our website at [www.tenaris.com](http://www.tenaris.com) . ©Tenaris 2021. All rights reserved.





5.500" 20.00 lb/ft P110-CY

TenarisHydril Wedge 461™ Matched Strength



Special Data Sheet

TH DS-20.0359

12 August 2020

Rev 00

|                    |           |                |           |                      |                  |
|--------------------|-----------|----------------|-----------|----------------------|------------------|
| Nominal OD         | 5.500 in. | Wall Thickness | 0.361 in. | Grade                | P110-CY          |
| Min Wall Thickness | 87.5%     | Type           | CASING    | Connection OD Option | MATCHED STRENGTH |

Pipe Body Data

| Geometry                |              |                  | Performance  |                     |                |
|-------------------------|--------------|------------------|--------------|---------------------|----------------|
| Nominal OD              | 5.500 in.    | Nominal ID       | 4.778 in.    | Body Yield Strength | 641 x 1000 lbs |
| Nominal Weight          | 20.00 lbs/ft | Wall Thickness   | 0.361 in.    | Internal Yield      | 12640 psi      |
| Standard Drift Diameter | 4.653 in.    | Plain End Weight | 19.83 lbs/ft | SMYS                | 110000 psi     |
| Special Drift Diameter  | N/A          | OD Tolerance     | API          | Collapse Pressure   | 11110 psi      |

Connection Data

| Geometry             |                  | Performance            |                | Make-up Torques           |              |
|----------------------|------------------|------------------------|----------------|---------------------------|--------------|
| Matched Strength OD  | 6.050 in.        | Tension Efficiency     | 100%           | Minimum                   | 17000 ft-lbs |
| Make-up Loss         | 3.775 in.        | Joint Yield Strength   | 641 x 1000 lbs | Optimum                   | 18000 ft-lbs |
| Threads per in.      | 3.40             | Internal Yield         | 12640 psi      | Maximum                   | 21600 ft-lbs |
| Connection OD Option | MATCHED STRENGTH | Compression Efficiency | 100%           | Operational Limit Torques |              |
| Coupling Length      | 7.714 in.        | Compression Strength   | 641 x 1000 lbs | Operating Torque          | 32000 ft-lbs |
|                      |                  | Bending                | 92 °/100 ft    | Yield Torque              | 38000 ft-lbs |
|                      |                  | Collapse               | 11110 psi      | Buck-On Torques           |              |
|                      |                  |                        |                | Minimum                   | 21600 ft-lbs |
|                      |                  |                        |                | Maximum                   | 23100 ft-lbs |

Notes

\*If you need to use torque values that are higher than the maximum indicated, please contact a local Tenaris technical sales representative

**District I**  
1625 N. French Dr., Hobbs, NM 88240  
Phone:(575) 393-6161 Fax:(575) 393-0720  
**District II**  
811 S. First St., Artesia, NM 88210  
Phone:(575) 748-1283 Fax:(575) 748-9720  
**District III**  
1000 Rio Brazos Rd., Aztec, NM 87410  
Phone:(505) 334-6178 Fax:(505) 334-6170  
**District IV**  
1220 S. St Francis Dr., Santa Fe, NM 87505  
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico  
Energy, Minerals and Natural Resources  
Oil Conservation Division  
1220 S. St Francis Dr.  
Santa Fe, NM 87505

COMMENTS

Action 216130

COMMENTS

|                                                                    |                                                      |
|--------------------------------------------------------------------|------------------------------------------------------|
| Operator:<br>OXY USA INC<br>P.O. Box 4294<br>Houston, TX 772104294 | OGRID:<br>16696                                      |
|                                                                    | Action Number:<br>216130                             |
|                                                                    | Action Type:<br>[C-103] NOI Change of Plans (C-103A) |

COMMENTS

| Created By | Comment                       | Comment Date |
|------------|-------------------------------|--------------|
| dmcclure   | Defining well is 30-015-47212 | 6/14/2023    |

**District I**  
1625 N. French Dr., Hobbs, NM 88240  
Phone:(575) 393-6161 Fax:(575) 393-0720  
**District II**  
811 S. First St., Artesia, NM 88210  
Phone:(575) 748-1283 Fax:(575) 748-9720  
**District III**  
1000 Rio Brazos Rd., Aztec, NM 87410  
Phone:(505) 334-6178 Fax:(505) 334-6170  
**District IV**  
1220 S. St Francis Dr., Santa Fe, NM 87505  
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico  
Energy, Minerals and Natural Resources  
Oil Conservation Division  
1220 S. St Francis Dr.  
Santa Fe, NM 87505

CONDITIONS  
  
Action 216130

CONDITIONS

|                                                                    |                                                      |
|--------------------------------------------------------------------|------------------------------------------------------|
| Operator:<br>OXY USA INC<br>P.O. Box 4294<br>Houston, TX 772104294 | OGRID:<br>16696                                      |
|                                                                    | Action Number:<br>216130                             |
|                                                                    | Action Type:<br>[C-103] NOI Change of Plans (C-103A) |

CONDITIONS

|            |              |                |
|------------|--------------|----------------|
| Created By | Condition    | Condition Date |
| dmcclure   | NSL required | 6/14/2023      |