

Form 3160-3  
(June 2015)FORM APPROVED  
OMB No. 1004-0137  
Expires: January 31, 2018

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
**APPLICATION FOR PERMIT TO DRILL OR REENTER**

1a. Type of work: <input type="checkbox"/> DRILL <input type="checkbox"/> REENTER 1b. Type of Well: <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other 1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		5. Lease Serial No.  6. If Indian, Allottee or Tribe Name  7. If Unit or CA Agreement, Name and No.  8. Lease Name and Well No.  <div style="text-align: center; font-weight: bold; font-size: 1.2em;">[323150]</div>	
2. Name of Operator  <div style="text-align: center; font-weight: bold; font-size: 1.2em;">[215099]</div>		9. API Well No. <b>30-025-51923</b>	
3a. Address		3b. Phone No. (include area code)	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		10. Field and Pool, or Exploratory <b>[98094]</b>  11. Sec., T. R. M. or Blk. and Survey or Area	
14. Distance in miles and direction from nearest town or post office*		12. County or Parish  13. State	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)		16. No of acres in lease	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.		17. Spacing Unit dedicated to this well  20. BLM/BIA Bond No. in file	
21. Elevations (Show whether DF, KDB, RT, GL, etc.)		22. Approximate date work will start*	
23. Estimated duration		24. Attachments	
The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)			
1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).		4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification. 6. Such other site specific information and/or plans as may be requested by the BLM.	
25. Signature		Name (Printed/Typed)	
Title		Date	
Approved by (Signature)		Name (Printed/Typed)	
Title		Office	
Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.			
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.			

NGMP Rec 08/24/2023

SL

(Continued on page 2)



Approval Date: 05/30/2023

KZ

08/31/2023

\*(Instructions on page 2)

**District I**  
1625 N. French Dr., Hobbs, NM 88240  
Phone: (575) 393-6161 Fax: (575) 393-0720

**District II**  
811 S. First St., Artesia, NM 88210  
Phone: (575) 748-1283 Fax: (575) 748-9720

**District III**  
1000 Rio Brazos Road, Aztec, NM 87410  
Phone: (505) 334-6178 Fax: (505) 334-6170

**District IV**  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
OIL CONSERVATION DIVISION  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-102  
Revised August 1, 2011  
Submit one copy to appropriate  
District Office

☐ AMENDED REPORT

## WELL LOCATION AND ACREAGE DEDICATION PLAT

<sup>1</sup> API Number <b>30-025-51923</b>		<sup>2</sup> Pool Code <b>98094</b>	<sup>3</sup> Pool Name <b>Bobcat Draw; Upper Wolfcamp</b>	
<sup>4</sup> Property Code <b>323150</b>	<sup>5</sup> Property Name <b>RED HILLS UNIT</b>			<sup>6</sup> Well Number <b>20H</b>
<sup>7</sup> OGRID No. <b>215099</b>	<sup>8</sup> Operator Name <b>CIMAREX ENERGY CO.</b>			<sup>9</sup> Elevation <b>3347.6'</b>

<sup>10</sup>Surface Location

UL or lot no. B	Section 33	Township 25S	Range 33E	Lot Idn	Feet from the 453	North/South line NORTH	Feet from the 1620	East/West line EAST	County LEA
--------------------	---------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

<sup>11</sup> Bottom Hole Location If Different From Surface

UL or lot no. O	Section 4	Township 26S	Range 33E	Lot Idn	Feet from the 100	North/South line SOUTH	Feet from the 2024	East/West line EAST	County LEA
<sup>12</sup> Dedicated Acres 320		<sup>13</sup> Joint or Infill		<sup>14</sup> Consolidation Code		<sup>15</sup> Order No.			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

**NOTE:**

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00"

**SCALE**

DRAWN BY: R.J. 04-03-18  
REV: 1 02-12-20 T.L.L. (BHL MOVE)

**NAD 83 (SURFACE HOLE LOCATION)**  
LATITUDE = 32°05'34.93" (32.093037°)  
LONGITUDE = 103°34'26.34" (103.573983°)  
**NAD 27 (SURFACE HOLE LOCATION)**  
LATITUDE = 32°05'34.48" (32.092912°)  
LONGITUDE = 103°34'24.65" (103.573513°)  
**STATE PLANE NAD 83 (N.M. EAST)**  
N: 398411.63' E: 776492.11'  
**STATE PLANE NAD 27 (N.M. EAST)**  
N: 398354.02' E: 735305.59'

**NAD 83 (LP/FTP)**  
LATITUDE = 32°05'34.94" (32.093040°)  
LONGITUDE = 103°34'31.03" (103.575287°)  
**NAD 27 (LP/FTP)**  
LATITUDE = 32°05'34.50" (32.092915°)  
LONGITUDE = 103°34'29.34" (103.574817°)  
**STATE PLANE NAD 83 (N.M. EAST)**  
N: 398409.94' E: 776088.21'  
**STATE PLANE NAD 27 (N.M. EAST)**  
N: 398352.33' E: 734901.70'

**NAD 83 (BHL/LTP)**  
LATITUDE = 32°03'55.96" (32.065545°)  
LONGITUDE = 103°34'30.90" (103.575249°)  
**NAD 27 (BHL/LTP)**  
LATITUDE = 32°03'55.51" (32.065420°)  
LONGITUDE = 103°34'29.21" (103.574780°)  
**STATE PLANE NAD 83 (N.M. EAST)**  
N: 388407.50' E: 776170.25'  
**STATE PLANE NAD 27 (N.M. EAST)**  
N: 388350.14' E: 734983.26'

**17 OPERATOR CERTIFICATION**

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Amithy Crawford 8/24/2018  
Signature Date

Amithy Crawford  
Printed Name

E-mail Address \_\_\_\_\_

**LINE TABLE**

LINE	DIRECTION	LENGTH
L1	S89°59'45"W	2637.35'
L2	S90°00'00"W	403.97'

**18 SURVEYOR CERTIFICATION**

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

March 27, 2018  
Date of Survey  
Signature and Seal of Professional Surveyor:

**PAUL BUCHELE**  
NEW MEXICO  
23782  
02-13-20  
PROFESSIONAL SURVEYOR

Certificate Number: \_\_\_\_\_

● = SURFACE HOLE LOCATION  
◆ = LANDING POINT/FIRST TAKE POINT  
○ = BOTTOM HOLE LOCATION/LAST TAKE POINT  
▲ = SECTION CORNER LOCATED

Intent ☐ As Drilled ☐

API # <b>30-025-51923</b>	
Operator Name:	Property Name:
Well Number	

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
Latitude					Longitude				NAD

Is this well the defining well for the Horizontal Spacing Unit? ☐Is this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #	
Operator Name:	Property Name:
Well Number	


Estimated Formation Tops

Formation:	Top:	Formation:	Top:

# RED HILLS UNIT E2

## LEASE MAP

LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N89°58'47"E	599.45'





State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Electronically  
Via E-permitting

## NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

### Section 1 – Plan Description

Effective May 25, 2021

**I. Operator:** Cimarex Energy Company **OGRID:** 215099 **Date:** 08/3/2023

**II. Type:** ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: \_\_\_\_\_

**III. Well(s):** Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Red Hills Unit 20H		B, Sec 33 T25S, R33E	395 FNL/2350	FEL 2000	3000	4000

**IV. Central Delivery Point Name:** Red Hills 33-4 CDP Sales [See 19.15.27.9(D)(1) NMAC]

**V. Anticipated Schedule:** Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Red Hills Unit 20H		7/1/2024	1/1/2025	2/1/25	4/1/25	4/1/25

**VI. Separation Equipment:** ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

**VII. Operational Practices:** ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

**VIII. Best Management Practices:** ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

## **Section 2 – Enhanced Plan**

### **EFFECTIVE APRIL 1, 2022**

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

#### **IX. Anticipated Natural Gas Production:**

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

#### **X. Natural Gas Gathering System (NGGS):**

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

**XI. Map.** ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

**XII. Line Capacity.** The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

**XIII. Line Pressure.** Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

**XIV. Confidentiality:** ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

### **Section 3 - Certifications**

**Effective May 25, 2021**

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

***If Operator checks this box, Operator will select one of the following:***

**Well Shut-In.** ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

**Venting and Flaring Plan.** ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

### **Section 4 - Notices**


1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature: 
Printed Name: Sarah Jordan
Title: Regulatory Analyst
E-mail Address: sarah.jordan@coterra.com
Date: 8/3/23
Phone: 432/620-1909
<b>OIL CONSERVATION DIVISION</b> <b>(Only applicable when submitted as a standalone form)</b>
Approved By:
Title:
Approval Date:
Conditions of Approval:

***From State of New Mexico, Natural Gas Management Plan***

**VI. Separation Equipment:** Attach a complete description of how Operator will size separation equipment to optimize gas capture.

**XEC Standard Response**

Standard facility gas process flow begins at the inlet separator. These vessels are designed based off of forecasted rates and residence times in accordance with, and often greater than, API 12J. The separated gas is then routed to an additional separation vessel (ie sales scrubber) in order to extract liquids that may have carried over or developed due to the decrease in pressure. The sales scrubber is sized based on API 521. From the sales scrubber, the gas leaves the facility and enters the gas midstream gathering network.

## **Cimarex**

### **VII. Operational Practices**

Cimarex values the sustainable development of New Mexico's natural resources. Venting and flaring of natural gas is a source of waste in the industry, and Cimarex will ensure that its values are aligned with those of NMOCD. As such, Cimarex plans to take pointed steps to ensure compliance with Subsection A through F of 19.15.27.8 NMAC.

Specifically, below are the steps Cimarex will plan to follow under routine well commissioning and operations.

1. Capture or combust natural gas during drilling operations where technically feasible, using the best industry practices and control technologies.
  - a. All flares during these operations will be a minimum of 100ft away from the nearest surface-hole location.
2. All gas present during post-completion drill-out and flow back will be routed through separation equipment, and, if technically feasible, flare unsellable vapors rather than vent. Lastly, formal sales separator commissioning to process well-stream fluids and send gas to a gas flow line/collection system or use the gas for on-site fuel or beneficial usage, gas as soon as is safe and technically feasible.
3. Cimarex will ensure the flare or combustion equipment is properly sized to handle expected flow rates, ensure this equipment is equipped with an automatic or continuous ignition source, and ensure this equipment is designed for proper combustion efficiency.
4. If Cimarex must flare because gas is not meeting pipeline specifications, Cimarex will limit flaring to <60 days, analyze gas composition at least twice per week, and route gas into a gathering pipeline as soon as pipeline specifications are met.
5. Under routine production operations, Cimarex will not flare/vent unless:
  - a. Venting or flaring occurs due to an emergency or equipment malfunction.
  - b. Venting or flaring occurs as a result of unloading practices, and an operator is onsite (or within 30 minutes of drive time and posts contact information at the wellsite) until the end of unloading practice.
  - c. The venting or flaring occurs during automated plungerlift operations, in which case the Cimarex operator will work to optimize the plungerlift system to minimize venting/flaring.
  - d. The venting or flaring occurs during downhole well maintenance, in which case Cimarex will work to minimize venting or flaring operations to the extent that it does not pose a risk to safe operations.
  - e. The well is an exploratory well, the division has approved the well as an exploratory well, venting or flaring is limited to 12 months, as approved by the division, and venting/flaring does not cause Cimarex to breach its State-wide 98% gas capture requirement.
  - f. Venting or flaring occurs because the stock tanks or other low-pressure vessels are being gauged, sampled, or liquids are being loaded out.
  - g. The venting or flaring occurs because pressurized vessels are being maintained and are being blown-down or depressurized.
  - h. Venting or flaring occurs as a result of normal dehydration unit operations.

- i. Venting or flaring occurs as a result of bradenhead testing.
  - j. Venting or flaring occurs as a result of normal compressor operations, including general compressor operations, compressor engines and turbines.
  - k. Venting or flaring occurs as a result of a packer leakage test.
  - l. Venting or flaring occurs as a result of a production test lasting less than 24 hours unless otherwise approved by the division.
  - m. Venting or flaring occurs as a result of new equipment commissioning and is necessary to purge impurities from the pipeline or production equipment.
6. Cimarex will maintain its equipment in accordance with its Operations and Maintenance Program, to ensure venting or flaring events are minimized and that equipment is properly functioning.
7. Cimarex will install automatic tank gauging equipment on all production facilities constructed after May 25, 2021, to ensure minimal emissions from tank gauging practices.
8. By November 25, 2022, all Cimarex facilities equipped with flares or combustors will be equipped with continuous pilots or automatic igniters, and technology to ensure proper function, i.e. thermocouple, fire-eye, etc...
9. Cimarex will perform AVO (audio, visual, olfactory) facility inspections in accordance with NMOCD requirements. Specifically, Cimarex will:
  - a. Perform weekly inspections during the first year of production, and so long as production is greater than 60 MCFD.
  - b. If production is less than 60 MCFD, Cimarex will perform weekly AVO inspections when an operator is present on location, and inspections at least once per calendar month with at least 20 calendar days between inspections.
10. Cimarex will measure or estimate the volume of vented, flared or beneficially used natural gas, regardless of the reason or authorization for such venting or flaring.
11. On all facilities constructed after May 25, 2021, Cimarex will install metering where feasible and in accordance with available technology and best engineering practices, in an effort to measure how much gas could have been vented or flared.
  - a. In areas where metering is not technically feasible, such as low-pressure/low volume venting or flaring applications, engineering estimates will be used such that the methodology could be independently verified.
12. Cimarex will fulfill the division's requirements for reporting and filing of venting or flaring that exceeds 50 MCF in volume or last eight hours or more cumulatively within any 24-hour period.



## VIII. Best Management Practices to minimize venting during active and planned maintenance

Cimarex strives to ensure minimal venting occurs during active and planned maintenance activities. Below is a description of common maintenance practices, and the steps Cimarex takes to limit venting exposure.

- **Workovers:**
  - Always strive to kill well when performing downhole maintenance.
  - If vapors or trapped pressure is present and must be relieved then:
    - Initial blowdown to production facility:
      - Route vapors to LP flare if possible/applicable
    - Blowdown to portable gas buster tank:
      - Vent to existing or portable flare if applicable.
- **Stock tank servicing:**
  - Minimize time spent with thief hatches open.
  - When cleaning or servicing via manway, suck tank bottoms to ensure minimal volatiles exposed to atmosphere.
    - Connect vacuum truck to low pressure flare while cleaning bottoms to limit venting.
  - Isolate the vent lines and overflows on the tank being serviced from other tanks.
- **Pressure vessel/compressor servicing and associated blowdowns:**
  - Route to flare where possible.
  - Blow vessel down to minimum available pressure via pipeline, prior to venting vessel.
  - Preemptively changing anodes to reduce failures and extended corrosion related servicing.
  - When cleaning or servicing via manway, suck vessel bottoms to ensure minimal volatiles exposed to atmosphere.
- **Flare/combustor maintenance:**
  - Minimize downtime by coordinating with vendor and Cimarex staff travel logistics.
  - Utilizing preventative and predictive maintenance programs to replace high wear components before failure.
  - Because the flare/combustor is the primary equipment used to limit venting practices, ensure flare/combustor is properly maintained and fully operational at all times via routine maintenance, temperature telemetry, onsite visual inspections.

*The Cimarex expectation is to limit all venting exposure. Equipment that may not be listed on this document is still expected to be maintained and associated venting during such maintenance minimized.*

## PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

<b>OPERATOR'S NAME:</b>	<b>Cimarex</b>
<b>LEASE NO.:</b>	<b>NMNM005792</b>
<b>LOCATION:</b>	Section 33, T.25 S., R.33 E., NMPM
<b>COUNTY:</b>	Lea County, New Mexico

<b>WELL NAME &amp; NO.:</b>	Red Hills Unit 20H
<b>SURFACE HOLE FOOTAGE:</b>	453'/N & 1620'/E
<b>BOTTOM HOLE FOOTAGE:</b>	100'/S & 2024'/E

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input checked="" type="checkbox"/> Unit

### A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Bone Springs and Wolfcamp** formations. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

### B. CASING

- The **10-3/4** inch surface casing shall be set at approximately **1050** feet (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface. **Excess calculates to 24%. Additional cement maybe required.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8**

**hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing must be kept 1/3<sup>rd</sup> fluid filled to meet BLM minimum collapse requirement.**

- The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:
  - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Excess calculates to -11%. Additional cement maybe required.**

**Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**

- The minimum required fill of cement behind the 5-1/2 X 5 inch production casing is: Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

### C. PRESSURE CONTROL

1. **Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).**
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi**.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

**D. SPECIAL REQUIREMENT (S)****Unit Wells**

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

**Commercial Well Determination**

A commercial well determination shall be submitted after production has been established for at least six months. (This is not necessary for secondary recovery unit wells)

**GENERAL REQUIREMENTS**

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)  
689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.

- BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
  3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

**B. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.

- c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
  - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
  - c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - e. The results of the test shall be reported to the appropriate BLM office.



- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

#### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**ZS041223**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

# Operator Certification Data Report

07/31/2023



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Application Data

07/31/2023

APD ID: 10400060223

Submission Date: 04/21/2021

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 20H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data  
reflects the most  
recent changes  
[Show Final Text](#)

### Section 1 - General

APD ID: 10400060223

Tie to previous NOS? Y

Submission Date: 04/21/2021

BLM Office: Carlsbad

User: AMITHY CRAWFORD

Title: Regulatory Analyst

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM005792

Lease Acres:

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? Y

Permitting Agent? NO

APD Operator: CIMAREX ENERGY COMPANY

Operator letter of

### Operator Info

Operator Organization Name: CIMAREX ENERGY COMPANY

Operator Address: 6001 DEAUVILLE BLVD STE 300N

Zip: 79706

Operator PO Box:

Operator City: MIDLAND

State: TX

Operator Phone: (303)295-3995

Operator Internet Address: hknaults@cimarex.com

### Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: RED HILLS UNIT

Well Number: 20H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: BOBCAT DRAW;  
Upper WolfcampPool Name: BOBCAT DRAW;  
UPPER WOLFCAMP

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Is the proposed well in an area containing other mineral resources?** USEABLE WATER,NATURAL GAS,OIL**Is the proposed well in a Helium production area?** N**Use Existing Well Pad?** Y**New surface disturbance?** N**Type of Well Pad:** MULTIPLE WELL**Multiple Well Pad Name:** Red Hills Unit**Number:** W2E2-E**Well Class:** HORIZONTAL**Number of Legs:** 1**Well Work Type:** Drill**Well Type:** OIL WELL**Describe Well Type:****Well sub-Type:** INFILL**Describe sub-type:****Distance to town:** 23 Miles**Distance to nearest well:** 20 FT**Distance to lease line:** 453 FT**Reservoir well spacing assigned acres Measurement:** 320 Acres**Well plat:** Red\_Hills\_Unit\_Lease\_Plat\_20200812094721.pdf

Red\_Hills\_Unit\_20H\_C102\_20200824073034.pdf

**Well work start Date:** 11/30/2020**Duration:** 30 DAYS**Section 3 - Well Location Table****Survey Type:** RECTANGULAR**Describe Survey Type:****Datum:** NAD83**Vertical Datum:** NAVD88**Survey number:****Reference Datum:** GROUND LEVEL

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
SHL Leg #1	453	FNL	1620	FEL	25S	33E	33	Aliquot NWNE	32.093037	- 103.093037	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 0005792	3354	0	0	Y
KOP Leg #1	453	FNL	1620	FEL	25S	33E	33	Aliquot NWNE	32.093037	- 103.573983	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 0005792	- 8511	11898	11865	Y

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this
PPP Leg #1-1	453	FNL	2024	FEL	25S	33E	33	Aliquot NWNE	32.09304	- 103.575287	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 0005792	- 8856	12283	12210	Y
EXIT Leg #1	100	FSL	2024	FEL	26S	33E	4	Aliquot SWSE	32.065545	- 103.575249	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 89425	- 9021	22432	12375	Y
BHL Leg #1	100	FSL	2024	FEL	26S	33E	4	Aliquot SWSE	32.065545	- 103.575249	LEA	NEW MEXI CO	NEW MEXI CO	F	NMNM 89425	- 9021	22432	12375	Y



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

# Drilling Plan Data Report

07/31/2023

APD ID: 10400060223

Submission Date: 04/21/2021

Highlighted data  
reflects the most  
recent changes

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 20H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)

## Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
819025	RUSTLER	3608	920	920	ANHYDRITE, SANDSTONE	USEABLE WATER	N
819026	TOP SALT	2274	1334	1334	ANHYDRITE	NONE	N
819027	BASE OF SALT	-1284	4892	4892	ANHYDRITE	NONE	N
819028	BELL CANYON	-1311	4919	4919	SANDSTONE	NONE	N
819029	CHERRY CANYON	-2411	6019	6019	SANDSTONE	NONE	N
819030	BRUSHY CANYON	-3970	7578	7578	SANDSTONE	NONE	N
819031	BONE SPRING	-5439	9047	9047	LIMESTONE	NATURAL GAS, OIL	N
3787164	BONE SPRING 1ST	-6422	10030	10030	SANDSTONE	NATURAL GAS, OIL	N
3787165	BONE SPRING 2ND	-6622	10230	10230	SANDSTONE	NATURAL GAS, OIL	N
3787166	BONE SPRING 3RD	-7409	11017	11017	SANDSTONE	NATURAL GAS, OIL	N
3787167	WOLFCAMP	-8520	12128	12128	SHALE	NATURAL GAS, OIL	Y

## Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 22432

**Equipment:** A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

**Requesting Variance?** YES

**Variance request:** Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only. Cimarex requests a 5M annular variance for the 10M BOP system. See

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H

attached procedure

**Testing Procedure:** A multi-bowl wellhead system will be utilized. After running the 10-3/4" surface casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 10000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 10000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

**Choke Diagram Attachment:**

Red\_Hills\_Unit\_20H\_Choke\_10M\_20210421153145.pdf

**BOP Diagram Attachment:**

Red\_Hills\_Unit\_20H\_BOP\_10M\_20210421153152.pdf

---

**Pressure Rating (PSI):** 5M**Rating Depth:** 12523

**Equipment:** A BOP consisting of three rams, including one blind ram and two pipe rams and one annular preventer. An accumulator that meets the requirements in Onshore Order #2 for the pressure rating of the BOP stack. A rotating head may be installed as needed. A Kelly clock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

**Requesting Variance?** YES

**Variance request:** Co-flex line between the BOP and choke manifold. Certification for proposed co-flex hose is attached. The hose is not required by the manufacturer to be anchored. In the event the specific hose is not available, one of equal or higher rating will be used. Variance to include Hammer Union connections on lines downstream of the buffer tank only.

**Testing Procedure:** A multi-bowl wellhead system will be utilized. After running the 10-3/4" surface casing, a 13 5/8 BOP/BOPE system with a minimum working pressure of 5000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 5000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2. The multi-bowl wellhead will be installed by vendors representative. A copy of the installation instructions has been sent to the BLM field office. The wellhead will be installed by a third-party welder, monitored by the wellhead vendor representative. All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type. A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 5000 psi. The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater. The casing string utilizing steel body pack-off will be tested to 70% of casing burst. If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

**Choke Diagram Attachment:**

Red\_Hills\_Unit\_20H\_Choke\_5M\_20210421153217.pdf

**BOP Diagram Attachment:**

Red\_Hills\_Unit\_20H\_BOP\_5M\_20210421153226.pdf



**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Section 3 - Casing**

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	10.75	NEW	API	N	0	970	0	970	3354	2384	970	J-55	40.5	BUTT	3.76	7.45	BUOY	16.01	BUOY	16.01
2	INTERMEDIATE	9.875	7.625	NEW	API	N	0	12523	0	12326	3608	-8972	12523	L-80	29.7	BUTT	2.48	1.19	BUOY	1.81	BUOY	1.81
3	PRODUCTION	6.75	5.5	NEW	API	N	0	12532	0	12532	3608	-9178	12532	L-80	20	LT&C	1.37	1.21	BUOY	2.2	BUOY	2.2
4	PRODUCTION	6.75	5.0	NEW	API	N	12532	22432	12532	12375	-9178	-9021	9900	P-110	18	BUTT	1.67	1.69	BUOY	99.99	BUOY	99.99

**Casing Attachments****Casing ID:** 1      **String** SURFACE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Red\_Hills\_Unit\_20H\_Casing\_Assumptions\_20210421153506.pdf

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Casing Attachments****Casing ID:** 2      **String**      INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Red\_Hills\_Unit\_20H\_Casing\_Assumptions\_20210421153540.pdf

**Casing ID:** 3      **String**      PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Red\_Hills\_Unit\_20H\_Casing\_Assumptions\_20210421153616.pdf

**Casing ID:** 4      **String**      PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

Red\_Hills\_Unit\_20H\_Casing\_Assumptions\_20210421153451.pdf

**Section 4 - Cement**

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
PRODUCTION	Lead		0	0	0	0	0	0	0	0	0

SURFACE	Lead		0	970	325	1.72	13.5	559	42	Class C	Bentonite
SURFACE	Tail		0	970	156	1.34	14.8	209	42	Class C	LCM
INTERMEDIATE	Lead	4850	0	4850	786	1.88	12.9	1477	40	35:65 (POZ C)	Salt Bentonite

INTERMEDIATE	Lead	4850	4850	1252 3	591	3.64	10.3	2125	47	Tuned Light	LCM
INTERMEDIATE	Tail		4850	1252 3	198	1.3	14.2	257	47	Class C	Retarder
PRODUCTION	Lead		0	2243 2	1364	1.3	14.2	1773	25	50:50 (POZ H)	Salt, Bentonite, Fluid Loss, Dispersant, SMS

### Section 5 - Circulating Medium

**Mud System Type:** Closed**Will an air or gas system be Used?** NO**Description of the equipment for the circulating system in accordance with Onshore Order #2:****Diagram of the equipment for the circulating system in accordance with Onshore Order #2:**

**Describe what will be on location to control well or mitigate other conditions:** Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

**Describe the mud monitoring system utilized:** PVT/Pason/Visual Monitoring

### Circulating Medium Table

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	970	OTHER : Fresh Water	7.83	8.33							
970	1252 3	OTHER : Brine Diesel Emulsion- The Brine Emulsion is completely saturated brine fluid that ties diesel into itself to lower the weight of the fluid. The drilling fluid is completely salt saturated.	8.5	9							
1252 3	2243 2	OIL-BASED MUD	12	12.5							

## Section 6 - Test, Logging, Coring

**List of production tests including testing procedures, equipment and safety measures:**

No DST Planned

**List of open and cased hole logs run in the well:**

GAMMA RAY LOG,DIRECTIONAL SURVEY,COMPENSATED NEUTRON LOG,

**Coring operation description for the well:**

N/A

## Section 7 - Pressure

**Anticipated Bottom Hole Pressure:** 8043

**Anticipated Surface Pressure:** 5320

**Anticipated Bottom Hole Temperature(F):** 191

**Anticipated abnormal pressures, temperatures, or potential geologic hazards?** YES

**Describe:**

Lost circulation may be encountered in the Delaware mountain group. Abnormal pressure as well as hole stability issues may be encountered in the Wolfcamp.

**Contingency Plans geohazards description:**

Lost circulation material will be available, as well as additional drilling fluid along with the fluid volume in the drilling rig pit system. Drilling fluid can be mixed on location or mixed in vendor mud plant and trucked to location if needed. Sufficient barite will be available to maintain appropriate mud weight for the Wolfcamp interval.

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Contingency Plans geohazards****Hydrogen Sulfide drilling operations plan required?** YES**Hydrogen sulfide drilling operations**

Red\_Hills\_Unit\_W2E2\_E\_H2S\_Plan\_20210421154135.pdf

**Section 8 - Other Information****Proposed horizontal/directional/multi-lateral plan submission:**

Red\_Hills\_Unit\_Directional\_Survey\_AC\_Report\_20210421154158.pdf

Red\_Hills\_Unit\_20H\_Directional\_Survey\_20210421154212.pdf

**Other proposed operations facets description:****Other proposed operations facets attachment:**

Red\_Hills\_Unit\_20H\_Drilling\_Plan\_20210421154224.pdf

Red\_Hills\_Unit\_20H\_Gas\_Capture\_20210421154232.pdf


**Other Variance attachment:**

Red\_Hills\_Unit\_20H\_Multibowl\_Diagram\_20210421154249.pdf

Red\_Hills\_Unit\_W2E2\_E\_Flex\_Hose\_20210421154340.pdf


Red\_Hills\_Unit\_20H\_Well\_Control\_10M\_w\_5M\_annular\_Plan\_BLM\_Approved\_20210421154348.pdf

4" Choke Line:  
OPTIONAL: 4" Flex Hose may be  
used if approved in APD



## Drilling Operations Choke Manifold 10M Service


Choke Manifold Diagram  
m **Red Hills Unit #20H**  
Cimarex Energy Co. 33-  
25S-33E  
Lea Co., NM



## Drilling Operations Choke Manifold 5M Service

Choke Manifold Diagram  
m Red Hills Unit #20H  
Cimarex Energy Co. 33-  
25S-33E  
Lea Co., NM





Drilling 9-7/8" hole below  
10-3/4" Casing

Fill Line

Flowline

5000# (5M)  
BOP

Annular Preventer

SRR & A

Pipe Rams

Blind Rams

2" Minimum Kill Line

Kill Line

Drilling  
Spool

3" minimum choke line

Choke Line

2 Valves Minimum

(HCR Required)

2 Valves and a check valve

Wellhead  
Assembly

11" 5000 psi x 7-1/16" 10,000 psi  
Wellhead Assembly

Wellhead  
Assembly

13-5/8" 3000 psi x 11" 5000 psi  
Wellhead Assembly

13-5/8" 3000# psi x 13-3/8" SOW Casing Head

5000# BOP  
Red Hills Unit #20H  
Cimarex Energy Co.  
33-25S-33E  
Lea Co., NM

## Red Hills Unit 20H

### Casing Assumptions

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

## Red Hills Unit 20H

### Casing Assumptions

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

## Red Hills Unit 20H

### Casing Assumptions

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

## Red Hills Unit 20H

### Casing Assumptions

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

## Hydrogen Sulfide Drilling Operations Plan

## Red Hills Unit W2E2-E

Cimarex Energy Co. of Colorado

Sec. 33-25S-33E

Lea Co., NM

- 1 All Company and Contract personnel admitted on location must be trained by a qualified H<sub>2</sub>S safety instructor to the following:
  - A. Characteristics of H<sub>2</sub>S
  - B. Physical effects and hazards
  - C. Principal and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - D. Evacuation procedure, routes and first aid.
  - E. Proper use of safety equipment & life support systems
  - F. Essential personnel meeting Medical Evaluation criteria will receive additional training on the proper use of 30 minute pressure demand air packs.

H<sub>2</sub>S Detection and Alarm Systems:

  - A. H<sub>2</sub>S sensors/detectors to be located on the drilling rig floor, in the base of the sub structure/cellar area, on the mud pits in the shale shaker area. Additional H<sub>2</sub>S detectors may be placed as deemed necessary.
  - B. An audio alarm system will be installed on the derrick floor and in the top doghouse.
- 3 Windsock and/or wind streamers:
  - A. Windsock at mudpit area should be high enough to be visible.
  - B. Windsock on the rig floor and / or top doghouse should be high enough to be visible.
- 4 Condition Flags and Signs
  - A. Warning sign on access road to location.
  - B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H<sub>2</sub>S present in dangerous concentration). Only H<sub>2</sub>S trained and certified personnel admitted to location.
- 5 Well control equipment:
  - A. See exhibit "E-1"
- 6 Communication:
  - A. While working under masks chalkboards will be used for communication.
  - B. Hand signals will be used where chalk board is inappropriate.
  - C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.
- 7 Drillstem Testing:

No DSTs or cores are planned at this time.
- 8 Drilling contractor supervisor will be required to be familiar with the effects H<sub>2</sub>S has on tubular goods and other mechanical equipment.
- 9 If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas separator will be brought into service along with H<sub>2</sub>S scavengers if necessary.

H<sub>2</sub>S Contingency Plan  
**Red Hills Unit W2E2-E** Cimarex  
Energy Co. of Colorado  
Sec. 33-25S- 33E  
Lea Co., NM

**Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must:

- « Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- « Evacuate any public places encompassed by the 100 ppm ROE.
- « Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- « Use the "buddy system" to ensure no injuries occur during the 432-620-1975
- « Take precautions to avoid personal injury during this operation.
- « Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- « Have received training in the:
  - Detection of H<sub>2</sub>S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

**Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

**Characteristics of H<sub>2</sub>S and SO<sub>2</sub>**

Please see attached International Chemical Safety Cards.

**Contacting Authorities**

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).



H<sub>2</sub>S Contingency Plan Emergency Contact  
s Red Hills Unit W2E2-E  
**Cimarex Energy Co. of Colorado**  
Sec. 33- 25S- 33E  
Lea Co., NM

**Company Office**

Cimarex Energy Co. of Colorado	800-969-4789
Co. Office and After-Hours Menu	

**Key Personnel**

Name	Title	Office	Mobile
Larry Seigrist	Drilling Manager	432-620-1934	580-243-8485
Charlie Pritchard	Drilling Superintendent	432-620-1975	432-238-7084
Roy Shirley	Construction Superintendent		432-634-2136

**Artesia**

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
<b>Fire Department</b>	<b>575-746-2701</b>
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

**Carlsbad**

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
<b>Fire Department</b>	<b>575-887-3798</b>
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

**Santa Fe**

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
New Mexico Emergency Response Commission (Santa Fe) 24 Hrs	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635

**National**

National Emergency Response Center (Washington, D.C.)	800-424-8802
-------------------------------------------------------	--------------

**Medical**

Flight for Life - 4000 24th St.; Lubbock, TX	806-743-9911
Aerocare - R3, Box 49F; Lubbock, TX	806-747-8923
Med Flight Air Amb - 2301 Yale Blvd S.E., #D3; Albuquerque, NM	505-842-4433
SB Air Med Service - 2505 Clark Carr Loop S.E.; Albuquerque, NM	505-842-4949

**Other**

Boots & Coots IWC	800-256-9688	or	281-931-8884
Cudd Pressure Control	432-699-0139	or	432-563-3356
Halliburton	575-746-2757		
B.J. Services	575-746-3569		



## Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20 Anti-Collision Summary Report

Analysis Date-24hr Time: April 07, 2020 - 16:41

Client: Cimarex Energy

Field: NM Lea County (NAD 83)

Structure: Cimarex Red Hills 33-4 Unit #20H

Slot: New Slot

Well: Red Hills 33-4 Unit #20H

Borehole: Red Hills 33-4 Unit #20H

Scan MD Range: 0.00ft ~ 22432.14ft

Analysis Method: 3D Least Distance

Reference Trajectory: Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20 (Non-Def Plan)

Depth Interval: Every 10.00 Measured Depth (ft)

Rule Set: NAL Procedure: D&M AntiCollision Standard S002

Min Pts: All local minima indicated.

Version / Patch: 2.10.787.0

Database \ Project: us1153APP452.DIR.SLB.COM\DRILLING-NM Lea County 2.10

**Trajectory Error Model:** ISCWSA0 3-D 95.000% Confidence 2.7955 sigma, for subject well. For offset wells, error model version is specified with each well respectively.

### Offset Trajectories Summary

#### Offset Selection Criteria

Wellhead distance scan: Restricted within 63442.64 ft

Selection filters: Definitive Surveys - Definitive Plans - Definitive surveys exclude definitive plans

- All Non-Def Surveys when no Def-Survey is set in a borehole - All Non-Def Plans when no Def-Plan is set in a borehole

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		

Results highlighted: Sep-Factor separation <= 1.50 ft

Cimarex Red Hills Unit #100H  
Rev0 RM 11Sept19 (Non-Def Plan)

Fail Major

629.92	32.81	627.94	597.11	N/A	MAS = 10.00 (m)	0.00	0.00						Surface
629.92	32.81	627.92	597.11	47103.58	MAS = 10.00 (m)	26.00	26.00						WRP
228.92	42.10	200.19	186.82	8.48	OSF1.50	5190.00	5161.81						MinPt-CtCt
229.01	42.35	200.12	186.66	8.43	OSF1.50	5220.00	5191.50						MINPT-O-EOU
229.09	42.44	200.14	186.65	8.42	OSF1.50	5230.00	5201.40						MinPt-O-ADP
230.80	43.18	201.35	187.61	8.33	OSF1.50	5320.00	5290.46						MinPt-O-SF
258.06	78.89	204.81	179.17	4.99	OSF1.50	10210.00	10176.83	OSF<5.00					Enter Alert
258.07	93.32	195.20	164.75	4.21	OSF1.50	11820.00	11786.83						MinPts
263.46	80.62	209.05	182.84	4.99	OSF1.50	12180.00	12130.75	OSF>5.00					Exit Alert
176.93	50.89	142.34	126.04	5.37	OSF1.50	12550.00	12332.89						MinPt-O-SF
108.39	33.92	85.12	74.47	5.00	OSF1.50	12870.00	12374.72	OSF<5.00					Enter Alert
82.21	39.91	54.94	42.29	3.17	OSF1.50	13160.00	12375.00						MinPt-CtCt
85.97	86.01	27.97	-0.04	1.50	OSF1.50	14930.00	12375.00	OSF<1.50					Enter Minor
89.35	133.12	-0.05	-43.76	1.00	OSF1.50	16520.00	12375.00						Enter Major
101.97	313.46	-107.67	-211.50	0.48	OSF1.50	22432.14	12375.00				OSF<1.00		MinPts

Cimarex Red Hills 33-4 Unit  
#19H Rev0 RM 06Apr20 (Non-Def Plan)

Fail Minor

19.99	16.25	18.70	3.74	N/A	MAS = 4.95 (m)	0.00	0.00	CtCt<=15m<15.00					Enter Alert
19.99	16.25	18.70	3.74	21046.03	MAS = 4.95 (m)	26.00	26.00						WRP
19.93	20.02	6.15	-0.09	1.49	OSF1.50	2050.00	2050.00	OSF<1.50					Enter Minor
19.73	20.77	5.48	-1.01	1.42	OSF1.50	2130.00	2130.00						MinPt-CtCt
19.85	21.14	5.33	-1.29	1.40	OSF1.50	2170.00	2170.00						MINPT-O-EOU
19.92	21.23	5.34	-1.31	1.40	OSF1.50	2180.00	2180.00						MinPts
21.86	21.91	6.83	-0.04	1.50	OSF1.50	2260.00	2260.00	OSF>1.50					Exit Minor
88.84	27.82	69.86	61.02	4.95	OSF1.50	3030.00	3024.24	OSF>5.00					Exit Alert
445.02	102.18	376.48	342.85	6.60	OSF1.50	11898.16	11865.00						MinPts
444.85	101.94	376.48	342.91	6.61	OSF1.50	11940.00	11906.78						MinPt-O-ADP
413.09	95.44	349.04	317.66	6.58	OSF1.50	12640.00	12351.80						MinPt-O-SF
411.18	94.42	347.80	316.76	6.60	OSF1.50	12870.00	12374.72						MinPt-O-ADP
411.03	94.24	347.77	316.78	6.61	OSF1.50	12920.00	12375.00						MINPT-O-EOU
410.95	93.75	348.01	317.19	6.65	OSF1.50	13070.00	12375.00						MinPt-CtCt
410.95	124.39	327.59	286.56	4.99	OSF1.50	15830.00	12375.00	OSF<5.00					Enter Alert
410.95	311.12	203.11	99.83	1.98	OSF1.50	22432.14	12375.00						MinPts

Cimarex Red Hills 33-4 Unit  
#62H Rev0 RM 06Apr20 (Non-Def Plan)

Warning Alert

20.00	16.26	18.71	3.74	N/A	MAS = 4.96 (m)	0.00	0.00	CtCt<=15m<15.00					Enter Alert
20.00	16.26	18.71	3.74	42114.56	MAS = 4.96 (m)	26.00	26.00						WRP
20.00	16.26	9.75	3.74	2.09	MAS = 4.96 (m)	1490.00	1490.00						MinPts
20.07	16.26	9.64	3.81	2.06	MAS = 4.96 (m)	1520.00	1520.00						MINPT-O-EOU
20.15	16.26	9.67	3.88	2.03	MAS = 4.96 (m)	1530.00	1530.00						MinPt-O-SF
56.81	18.14	44.29	38.67	4.94	OSF1.50	1970.00	1970.00	OSF>5.00					Exit Alert
161.40	48.16	128.87	113.24	5.12	OSF1.50	5531.74	5500.00						MinPt-O-SF
417.16	93.23	354.58	323.93	6.78	OSF1.50	11898.16	11865.00						MinPts
411.49	87.47	352.75	324.02	7.14	OSF1.50	12470.00	12309.60						MinPt-O-ADP
411.38	87.34	352.73	324.04	7.15	OSF1.50	12490.00	12316.50						MINPT-O-EOU
410.94	85.60	353.45	325.34	7.29	OSF1.50	12870.00	12374.72						MinPt-CtCt
410.94	124.24	327.68	286.70	5.00	OSF1.50	15880.00	12375.00	OSF<5.00					Enter Alert
410.95	315.17	200.40	95.77	1.96	OSF1.50	22432.14	12375.00						MinPts

Cimarex Red Hills 33-4 Unit  
#103H Rev0 RM 06Apr20 (Non-Def Plan)

Warning Alert

712.25	32.81	710.97	679.44	N/A	MAS = 10.00 (m)	0.00	0.00						Surface
712.25	32.81	710.95	679.44	47057.43	MAS = 10.00 (m)	26.00	26.00						WRP
122.35	38.29	96.25	84.06	4.95	OSF1.50	4580.00	4558.15	OSF<5.00					Enter Alert
74.84	42.02	46.39	32.82	2.71	OSF1.50	4970.00	4944.10						MinPts
74.90	42.10	46.40	32.79	2.71	OSF1.50	4980.00	4953.99						MinPt-O-ADP
75.03	42.19	46.48	32.84	2.70	OSF1.50	4990.00	4963.89						MinPt-O-SF
144.07	44.16	114.20	99.91	5.00	OSF1.50	5540.00	5508.18	OSF>5.00					Exit Alert
171.55	52.39	138.19	119.16	5.00	OSF1.50	7170.00	7136.83	OSF<5.00					Enter Alert
171.55	80.91	117.18	90.64	3.21	OSF1.50	10600.00	10566.83						MinPts
240.74	73.57	191.26	167.16	4.97	OSF1.50	10930.00	10896.83	OSF>5.00					Exit Alert
1336.93	315.73	1126.02	1021.20	6.37	OSF1.50	22432.14	12375.00						MinPts

Cimarex Red Hills 33-4 Unit  
#102H Rev0 RM 06Apr20 (Non-Def Plan)

Warning Alert

692.32	32.81	691.03	659.51	N/A	MAS = 10.00 (m)	0.00	0.00						Surface
692.32	32.81	691.02	659.51	47849.10	MAS = 10.00 (m)	26.00	26.00						WRP
131.81	39.66	104.94	92.16	5.10	OSF1.50	4790.00	4765.97						MinPt-CtCt
131.86	39.82	104.88	92.04	5.08	OSF1.50	4810.00	4785.76						MinPts
132.78	40.27	105.50	92.51	5.03	OSF1.50	4860.00	4835.24						MinPt-O-SF

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status	
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major			
	230.06	69.95	182.99	160.10	5.00	OSF1.50	9550.00	9516.83	OSF<5.00			Enter Alert		
	230.06	73.33	180.74	156.73	4.76	OSF1.50	9950.00	9916.83				MinPts		
	237.87	72.71	188.97	165.16	4.97	OSF1.50	10060.00	10026.83	OSF>5.00			Exit Alert		
	1984.95	314.40	1774.92	1670.55	9.50	OSF1.50	22432.14	12375.00				MinPts		
	Cimarex Red Hills Unit #99H Rev0 RM 11Sept19 (Non-Def Plan)													Warning Alert
	609.93	32.81	607.95	577.12	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	609.93	32.81	607.94	577.12	52620.02	MAS = 10.00 (m)	26.00	26.00				WRP		
	192.09	38.91	165.49	153.18	7.72	OSF1.50	4770.00	4746.17				MinPt-CtCt		
	192.16	39.08	165.44	153.08	7.69	OSF1.50	4790.00	4765.97				MinPts		
	194.54	39.91	167.27	154.63	7.62	OSF1.50	4890.00	4864.93				MinPt-O-SF		
	505.54	87.66	446.44	417.88	8.82	OSF1.50	11820.00	11786.83				MinPts		
	505.71	87.73	446.56	417.98	8.81	OSF1.50	11840.00	11806.83				MinPt-O-SF		
	441.29	80.68	386.84	360.61	8.37	OSF1.50	13160.00	12375.00				MinPt-CtCt		
	442.58	134.17	352.47	308.41	5.00	OSF1.50	16320.00	12375.00	OSF<5.00			Enter Alert		
	445.35	316.47	233.72	128.89	2.11	OSF1.50	22432.14	12375.00				MinPts		
	Cimarex Red Hills Unit #101H Rev0 RM 11Sept19 (Non-Def Plan)													Warning Alert
	649.92	32.81	647.94	617.11	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	649.92	32.81	647.92	617.11	49427.68	MAS = 10.00 (m)	26.00	26.00				WRP		
	355.37	104.13	285.26	251.24	5.19	OSF1.50	11740.00	11706.83				MinPt-CtCt		
	355.38	104.20	285.22	251.18	5.19	OSF1.50	11750.00	11716.83				MinPts		
	413.95	95.79	349.43	318.16	6.59	OSF1.50	13170.00	12375.00				MinPt-O-SF		
	413.93	95.78	349.42	318.15	6.59	OSF1.50	13180.00	12375.00				MinPts		
	413.93	95.78	349.42	318.15	6.59	OSF1.50	13190.00	12375.00				MinPt-CtCt		
	415.06	125.95	330.43	289.10	5.00	OSF1.50	15770.00	12375.00	OSF<5.00			Enter Alert		
	418.30	313.57	208.59	104.73	2.00	OSF1.50	22432.14	12375.00				MinPts		
	Cimarex Red Hills Unit #75H Rev0 RM 11Sept19 (Non-Def Plan)													Warning Alert
		730.20	32.81	728.22	697.39	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
730.18		32.81	728.20	697.37	N/A	MAS = 10.00 (m)	26.00	26.00				WRP		
730.18		32.81	714.73	697.37	54.30	MAS = 10.00 (m)	2200.00	2200.00				MinPts		
730.23		32.81	714.73	697.43	53.85	MAS = 10.00 (m)	2220.00	2220.00				MINPT-O-EOU		
900.69		44.74	870.20	855.95	31.53	OSF1.50	5600.00	5567.67				MinPt-O-SF		
900.52		44.62	870.12	855.90	31.61	OSF1.50	5760.00	5726.96				MinPt-O-SF		
890.86		91.13	829.45	799.73	14.96	OSF1.50	11820.00	11786.83				MinPt-CtCt		
890.89		91.26	829.35	799.63	14.94	OSF1.50	11840.00	11806.83				MinPts		
891.80		91.46	830.17	800.34	14.92	OSF1.50	11898.16	11865.00				MinPt-O-SF		
865.39		84.80	808.19	780.59	15.64	OSF1.50	12630.00	12349.97				MinPt-O-SF		
856.71		83.41	800.45	773.30	15.74	OSF1.50	13130.00	12375.00				MinPt-O-ADP		
856.70		83.40	800.45	773.31	15.75	OSF1.50	13140.00	12375.00				MINPT-O-EOU		
856.70		83.38	800.45	773.32	15.75	OSF1.50	13150.00	12375.00				MinPt-CtCt		
858.17		259.04	684.82	599.13	5.00	OSF1.50	20760.00	12375.00	OSF<5.00			Enter Alert		
858.54		310.91	650.61	547.63	4.16	OSF1.50	22432.14	12375.00				MinPts		
Cimarex Red Hills 33-4 Unit #104H Rev0 RM 06Apr20 (Non-Def Plan)													Pass	
		732.18	32.81	730.89	699.37	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	
		732.18	32.81	730.88	699.37	46332.27	MAS = 10.00 (m)	26.00	26.00				WRP	
	310.71	80.72	256.35	229.99	5.86	OSF1.50	9540.00	9506.83				MinPt-CtCt		
	310.71	80.80	256.29	229.91	5.86	OSF1.50	9550.00	9516.83				MinPts		
	310.84	80.87	256.38	229.97	5.85	OSF1.50	9570.00	9536.83				MinPt-O-SF		
	2399.93	315.61	2189.09	2084.32	11.45	OSF1.50	22432.14	12375.00				MinPts		
Cimarex Red Hills 33-4 Unit #105H Rev0 RM 06Apr20 (Non-Def Plan)													Pass	
	752.12	32.81	750.83	719.31	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	752.12	32.81	750.82	719.31	46292.29	MAS = 10.00 (m)	26.00	26.00				WRP		
	397.37	76.98	345.54	320.39	7.87	OSF1.50	8840.00	8806.83				MinPt-CtCt		
	397.38	77.04	345.51	320.35	7.86	OSF1.50	8850.00	8816.83				MinPts		
	397.69	77.14	345.75	320.55	7.86	OSF1.50	8880.00	8846.83				MinPt-O-SF		
	3096.10	313.89	2886.41	2782.21	14.83	OSF1.50	22432.14	12375.00				MinPts		
Cimarex Red Hills 33-4 Unit #79H Rev0 RM 27Mar20 (Non-Def Plan)													Pass	
	633.54	32.81	632.26	600.74	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	633.53	32.81	632.24	600.72	N/A	MAS = 10.00 (m)	26.00	26.00				WRP		
	610.05	32.81	594.92	577.24	44.03	MAS = 10.00 (m)	2530.00	2529.27				MinPts		
	610.07	32.81	594.91	577.26	43.94	MAS = 10.00 (m)	2540.00	2539.20				MINPT-O-EOU		
	658.97	32.81	637.40	626.16	32.43	MAS = 10.00 (m)	4080.00	4063.34				MinPt-O-SF		
	844.79	42.49	816.03	802.29	30.70	OSF1.50	5531.74	5500.00				MinPt-O-SF		
	872.76	79.92	819.06	792.85	16.63	OSF1.50	10320.00	10286.83				MinPts		
	872.89	79.99	819.14	792.90	16.61	OSF1.50	10340.00	10306.83				MinPt-O-SF		
	1829.95	308.17	1624.08	1521.79	8.94	OSF1.50	22432.14	12375.00				MinPts		
	Cimarex Red Hills 33-4 Unit #78H Rev0 RM 27Mar20 (Non-Def Plan)													Pass
	653.44	32.81	652.15	620.63	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	653.42	32.81	652.14	620.62	N/A	MAS = 10.00 (m)	26.00	26.00				WRP		
	653.42	32.81	639.98	620.62	53.63	MAS = 10.00 (m)	2000.00	2000.00				MinPts		
	653.46	32.81	639.91	620.65	53.20	MAS = 10.00 (m)	2020.00	2020.00				MINPT-O-EOU		
	667.20	32.81	652.62	634.39	50.10	MAS = 10.00 (m)	2300.00	2299.98				MinPt-O-SF		
	1459.60	44.45	1429.53	1415.15	50.68	OSF1.50	5531.74	5500.00				MinPt-O-SF		
	1580.72	47.44	1548.67	1533.29	51.33	OSF1.50	6270.00	6236.83				MinPt-O-SF		
	1588.73	79.29	1535.44	1509.43	30.52	OSF1.50	10630.00	10596.83				MINPT-O-EOU		
	1588.81	79.39	1535.45	1509.42	30.49	OSF1.50	10650.00	10616.83				MinPt-O-ADP		
	1591.57	79.88	1537.89	1511.70	30.35	OSF1.50	10810.00	10776.83				MinPt-O-SF		
2062.25	317.17	1850.37	1745.08	9.79	OSF1.50	22432.14	12375.00				MinPts			
Cimarex Red Hills 33-4 Unit #77H Rev0 RM 27Mar20 (Non-Def Plan)													Pass	
	673.34	32.81	672.05	640.53	N/A	MAS = 10.00 (m)	0.00	0.00				Surface		
	673.32	32.81	672.03	640.51	N/A	MAS = 10.00 (m)	26.00	26.00				WRP		
	673.32	32.81	661.13	640.51	61.64	MAS = 10.00 (m)	1800.00	1800.00				MinPts		
	673.35	32.81	661.07	640.55	61.10	MAS = 10.00 (m)	1820.00	1820.00				MINPT-O-EOU		

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
708.82	32.81	694.85	676.01	55.81		MAS = 10.00 (m)	2300.00	2299.98				MinPt-O-SF	
1495.92	43.95	1466.19	1451.97	52.53		OSF1.50	5531.74	5500.00				MinPt-O-SF	
1589.50	45.21	1558.93	1544.29	54.24		OSF1.50	6070.00	6036.83				MinPt-O-SF	
1596.03	72.44	1547.31	1523.59	33.62		OSF1.50	9980.00	9946.83				MINPT-O-EQU	
1596.08	72.49	1547.32	1523.59	33.60		OSF1.50	9990.00	9956.83				MinPt-O-ADP	
1600.68	72.98	1551.60	1527.70	33.48		OSF1.50	10180.00	10146.83				MinPt-O-SF	
2528.00	316.76	2316.48	2211.33	12.01		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #76H Rev0 RM 27Mar20 (Non-Def Plan)													Pass
693.25	32.81	691.97	660.44	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
693.23	32.81	691.95	660.42	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
693.23	32.81	682.93	660.42	76.76		MAS = 10.00 (m)	1500.00	1500.00				MinPts	
693.26	32.81	682.87	660.45	75.96		MAS = 10.00 (m)	1520.00	1520.00				MINPT-O-EQU	
799.89	32.81	786.15	767.09	64.11		MAS = 10.00 (m)	2480.00	2479.55				MinPt-O-SF	
812.96	32.81	799.01	780.15	64.10		MAS = 10.00 (m)	2540.00	2539.20				MinPt-O-SF	
830.30	32.81	816.09	797.50	64.13		MAS = 10.00 (m)	2613.20	2611.77				MinPt-O-SF	
1584.82	43.78	1555.21	1541.04	55.90		OSF1.50	5531.74	5500.00				MinPt-O-SF	
1713.45	47.06	1681.65	1666.39	56.11		OSF1.50	6290.00	6256.83				MinPt-O-SF	
1721.20	66.68	1676.31	1654.51	39.45		OSF1.50	9580.00	9546.83				MinPts	
1731.08	67.59	1685.59	1663.49	39.14		OSF1.50	9850.00	9816.83				MinPt-O-SF	
2912.86	317.08	2701.05	2595.78	13.83		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #50H Rev0 RM 27Mar20 (Non-Def Plan)													Pass
1671.42	32.81	1670.13	1638.61	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
1671.42	32.81	1670.10	1638.61	50449.02		MAS = 10.00 (m)	26.00	26.00				WRP	
711.27	75.83	659.99	635.44	14.44		OSF1.50	10290.00	10256.83				MinPt-CtCt	
711.29	75.87	659.99	635.43	14.44		OSF1.50	10300.00	10266.83				MinPts	
711.88	75.99	660.50	635.89	14.42		OSF1.50	10340.00	10306.83				MinPt-O-SF	
1767.66	40.99	1739.91	1726.67	66.73		OSF1.50	12920.00	12375.00				MinPt-CtCt	
1771.98	312.08	1563.51	1459.92	8.55		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #82H Rev0 RM 06Apr20 (Non-Def Plan)													Pass
740.79	32.81	739.50	707.98	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
740.77	32.81	739.48	707.96	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
740.77	32.81	726.07	707.96	55.13		MAS = 10.00 (m)	2200.00	2200.00				MinPts	
740.82	32.81	726.01	708.01	54.68		MAS = 10.00 (m)	2220.00	2220.00				MINPT-O-EQU	
1116.05	50.32	1082.08	1065.73	34.18		OSF1.50	5531.74	5500.00				MinPt-O-SF	
1124.13	50.69	1089.91	1073.44	34.03		OSF1.50	5600.00	5567.67				MinPt-O-SF	
1142.80	76.77	1091.19	1066.03	22.68		OSF1.50	8870.00	8836.83				MINPT-O-EQU	
1142.82	76.80	1091.19	1066.02	22.67		OSF1.50	8880.00	8846.83				MinPt-O-ADP	
1143.73	77.08	1091.91	1066.65	22.61		OSF1.50	8960.00	8926.83				MinPt-O-SF	
3272.41	311.38	3064.41	2961.08	15.82		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #74H Rev0 RM 11Sept19 (Non-Def Plan)													Pass
750.24	32.81	748.26	717.43	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
750.21	32.81	748.24	717.41	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
750.21	32.81	734.82	717.41	55.79		MAS = 10.00 (m)	2200.00	2200.00				MinPts	
750.27	32.81	734.77	717.47	55.34		MAS = 10.00 (m)	2220.00	2220.00				MINPT-O-EQU	
1154.28	51.03	1119.60	1103.25	35.24		OSF1.50	5531.74	5500.00				MinPt-O-SF	
1162.72	51.40	1127.79	1111.32	35.23		OSF1.50	5600.00	5567.67				MinPt-O-SF	
1182.19	104.16	1112.09	1078.04	17.33		OSF1.50	11790.00	11756.83				MinPts	
1182.98	104.30	1112.79	1078.68	17.31		OSF1.50	11840.00	11806.83				MinPt-O-SF	
1278.99	97.80	1213.13	1181.19	19.53		OSF1.50	12770.00	12369.27				MinPt-O-SF	
1275.76	96.57	1210.72	1179.19	20.20		OSF1.50	13120.00	12375.00				MinPt-O-ADP	
1275.74	96.58	1210.72	1179.20	20.20		OSF1.50	13130.00	12375.00				MINPT-O-EQU	
1275.70	96.43	1210.75	1179.27	20.23		OSF1.50	13180.00	12375.00				MinPt-CtCt	
1276.94	310.96	1068.97	965.97	6.19		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #81H RM 06Apr20 (Non-Def Plan)													Pass
760.49	32.81	759.20	727.68	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
760.48	32.81	759.19	727.67	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
760.23	32.81	745.48	727.42	56.37		MAS = 10.00 (m)	2210.00	2210.00				MinPts	
760.29	32.81	745.43	727.48	55.92		MAS = 10.00 (m)	2230.00	2230.00				MINPT-O-EQU	
842.13	32.81	822.46	809.32	45.74		MAS = 10.00 (m)	3200.00	3192.48				MinPt-O-SF	
1118.43	48.41	1085.73	1070.02	35.56		OSF1.50	5600.00	5567.67				MinPt-O-SF	
1136.28	80.68	1082.06	1055.60	21.44		OSF1.50	9570.00	9536.83				MINPT-O-EQU	
1136.31	80.72	1082.07	1055.59	21.43		OSF1.50	9580.00	9546.83				MinPt-O-ADP	
1137.26	80.99	1082.83	1056.27	21.39		OSF1.50	9660.00	9626.83				MinPt-O-SF	
2623.28	43.54	2593.83	2579.74	93.09		OSF1.50	12690.00	12359.90				MinPt-O-SF	
2636.85	312.07	2428.38	2324.78	12.72		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #21H Rev0 RM 11Sept19 (Non-Def Plan)													Pass
770.24	32.81	768.26	737.43	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
770.22	32.81	768.24	737.41	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
770.22	32.81	754.83	737.41	57.29		MAS = 10.00 (m)	2200.00	2200.00				MinPts	
770.27	32.81	754.77	737.47	56.82		MAS = 10.00 (m)	2220.00	2220.00				MINPT-O-EQU	
799.53	32.81	782.16	766.73	51.81		MAS = 10.00 (m)	2630.00	2628.39				MinPt-O-SF	
1520.63	43.50	1490.97	1477.13	54.88		OSF1.50	5531.74	5500.00				MinPt-O-SF	
1707.30	50.19	1673.17	1657.10	53.08		OSF1.50	6790.00	6756.83				MinPt-O-SF	
1713.22	88.63	1653.48	1624.59	29.62		OSF1.50	11840.00	11806.83				MINPT-O-EQU	
1713.25	88.68	1653.48	1624.58	29.61		OSF1.50	11850.00	11816.83				MinPt-O-ADP	
1713.70	88.90	1653.77	1624.79	29.54		OSF1.50	11898.16	11865.00				MinPt-O-SF	
1695.18	81.85	1639.94	1613.31	31.80		OSF1.50	13160.00	12375.00				MinPt-CtCt	
1696.09	313.87	1486.18	1382.22	8.15		OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #80H Rev0 RM 06Apr20 (Non-Def Plan)													Pass
780.23	32.81	778.95	747.43	N/A		MAS = 10.00 (m)	0.00	0.00				Surface	
780.22	32.81	778.93	747.41	N/A		MAS = 10.00 (m)	26.00	26.00				WRP	
780.22	32.81	766.77	747.41	64.08		MAS = 10.00 (m)	2000.00	2000.00				MinPts	
780.39	32.81	766.59	747.58	62.25		MAS = 10.00 (m)	2060.00	2060.00				MINPT-O-EQU	
892.33	32.81	872.79	859.52	48.81		MAS = 10.00 (m)	3150.00	3142.99				MinPt-O-SF	
1178.42	48.40	1145.72	1130.02	37.48		OSF1.50	5600.00	5567.67				MinPt-O-SF	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
	1195.90	80.88	1141.55	1115.02	22.51	OSF1.50	9630.00	9596.83				MinPt-O-SF	
	1194.09	80.65	1139.85	1113.44	22.54	OSF1.50	9810.00	9776.83				MinPts	
	2644.59	312.26	2435.98	2332.32	12.75	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #47H Rev0 RM 27Aug18 (Non-Def Plan)													
	1593.10	32.81	1591.12	1560.29	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1593.10	32.81	1591.09	1560.29	52272.27	MAS = 10.00 (m)	26.00	26.00				WRP	
	870.57	44.38	840.12	826.19	31.18	OSF1.50	5720.00	5687.06				MinPt-O-SF	
	865.45	43.92	835.31	821.54	31.33	OSF1.50	5940.00	5906.83				MinPts	
	865.45	70.35	817.68	795.10	19.11	OSF1.50	9480.00	9446.83				MinPt-CtCt	
	865.46	70.40	817.67	795.07	19.09	OSF1.50	9490.00	9456.83				MinPts	
	865.79	70.49	817.93	795.30	19.07	OSF1.50	9520.00	9486.83				MinPt-O-SF	
	2576.76	39.53	2549.75	2537.23	102.86	OSF1.50	12980.00	12375.00				MinPt-CtCt	
	2585.95	312.55	2376.93	2273.40	12.48	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #48H Rev0 RM 27Aug18 (Non-Def Plan)													
	1613.06	32.81	1611.08	1580.25	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1613.06	32.81	1611.05	1580.25	51793.75	MAS = 10.00 (m)	26.00	26.00				WRP	
	1250.58	83.53	1194.03	1166.97	23.06	OSF1.50	9480.00	9446.83				MinPt-CtCt	
	1250.51	83.58	1194.02	1166.93	23.04	OSF1.50	9490.00	9456.83				MinPts	
	1251.35	83.79	1194.72	1167.56	23.03	OSF1.50	9550.00	9516.83				MinPt-O-SF	
	2737.02	50.30	2702.83	2686.72	84.90	OSF1.50	12980.00	12375.00				MinPt-CtCt	
	2750.12	314.94	2539.50	2435.18	13.17	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #51H Rev0 RM 27Mar20 (Non-Def Plan)													
	1691.41	32.81	1690.12	1658.60	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1691.41	32.81	1690.09	1658.60	49076.62	MAS = 10.00 (m)	26.00	26.00				WRP	
	1314.22	86.95	1255.71	1227.28	23.08	OSF1.50	9930.00	9896.83				MinPt-CtCt	
	1314.23	87.02	1255.67	1227.21	23.07	OSF1.50	9940.00	9906.83				MinPts	
	1316.48	87.34	1257.71	1229.15	23.02	OSF1.50	10040.00	10006.83				MinPt-O-SF	
	2401.05	57.40	2362.35	2343.64	64.15	OSF1.50	12920.00	12375.00				MinPt-CtCt	
	2407.48	315.68	2196.59	2091.80	11.48	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #52H Rev0 RM 27Mar20 (Non-Def Plan)													
	1711.41	32.81	1710.12	1678.60	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1711.41	32.81	1710.08	1678.60	48714.50	MAS = 10.00 (m)	26.00	26.00				WRP	
	1711.41	32.81	1698.02	1678.60	141.37	MAS = 10.00 (m)	1980.00	1980.00				MinPts	
	1711.62	32.81	1697.77	1678.81	136.13	MAS = 10.00 (m)	2060.00	2060.00				MINPT-O-EOU	
	1348.34	90.29	1287.59	1258.05	22.80	OSF1.50	10580.00	10546.83				MinPt-CtCt	
	1348.37	90.47	1287.50	1257.91	22.75	OSF1.50	10610.00	10576.83				MinPts	
	1348.42	90.50	1287.52	1257.92	22.74	OSF1.50	10620.00	10586.83				MinPt-O-SF	
	1893.99	67.80	1848.35	1826.18	42.68	OSF1.50	12780.00	12370.13				MinPt-O-SF	
	1905.67	317.38	1693.66	1588.29	9.04	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #49H Rev0 RM 27Aug18 (Non-Def Plan)													
	1633.07	32.81	1631.09	1600.26	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1633.07	32.81	1631.06	1600.26	49602.67	MAS = 10.00 (m)	26.00	26.00				WRP	
	1633.07	32.81	1622.14	1600.26	182.21	MAS = 10.00 (m)	1480.00	1480.00				MinPts	
	1633.09	32.81	1622.07	1600.29	180.32	MAS = 10.00 (m)	1500.00	1500.00				MINPT-O-EOU	
	1709.76	32.81	1693.83	1676.95	122.40	MAS = 10.00 (m)	2820.00	2816.42				MinPts	
	1714.93	36.71	1689.80	1678.22	73.97	OSF1.50	4560.00	4538.35				MINPT-O-EOU	
	1719.23	42.86	1690.00	1676.37	63.01	OSF1.50	5250.00	5221.19				MinPt-O-SF	
	1686.94	43.87	1657.04	1643.07	60.33	OSF1.50	5600.00	5567.67				MinPt-O-SF	
	1671.86	43.13	1642.44	1628.73	60.88	OSF1.50	5940.00	5906.83				MinPts	
	1671.85	69.58	1624.81	1602.28	37.06	OSF1.50	9480.00	9446.83				MinPt-CtCt	
	1671.86	69.65	1624.78	1602.23	37.03	OSF1.50	9490.00	9456.83				MINPT-O-EOU	
	1671.90	69.68	1624.76	1602.22	37.00	OSF1.50	9500.00	9466.83				MinPt-O-ADP	
	1677.28	70.14	1629.86	1607.14	36.87	OSF1.50	9690.00	9656.83				MinPt-O-SF	
	2949.24	53.87	2912.66	2895.37	85.19	OSF1.50	12970.00	12375.00				MinPt-CtCt	
	2965.51	321.38	2750.60	2644.13	13.92	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills 33-4 Unit #53H Rev0 RM 27Mar20 (Non-Def Plan)													
	1731.41	32.81	1730.12	1698.60	N/A	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	1731.41	32.81	1730.08	1698.60	47772.44	MAS = 10.00 (m)	26.00	26.00				WRP	
	1731.41	32.81	1721.16	1698.60	193.18	MAS = 10.00 (m)	1480.00	1480.00				MinPts	
	1731.48	32.81	1721.09	1698.67	190.17	MAS = 10.00 (m)	1510.00	1510.00				MINPT-O-EOU	
	1944.14	47.52	1912.03	1896.61	63.03	OSF1.50	5600.00	5567.67				MinPt-O-SF	
	2064.59	52.43	2029.20	2012.15	60.51	OSF1.50	6460.00	6426.83				MinPt-O-SF	
	2075.73	79.26	2022.46	1996.47	39.91	OSF1.50	10420.00	10386.83				MinPt-CtCt	
	2075.73	79.27	2022.45	1996.46	39.90	OSF1.50	10430.00	10396.83				MINPT-O-EOU	
	2075.73	79.28	2022.45	1996.46	39.90	OSF1.50	10440.00	10406.83				MinPt-O-ADP	
	2082.90	79.80	2029.28	2003.10	39.77	OSF1.50	10750.00	10716.83				MinPt-O-SF	
	2655.94	327.72	2437.03	2328.22	12.20	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit#36H Rev0 RM 27Aug18 (Non-Def Plan)													
	3143.18	32.81	3141.19	3110.37	307345.66	MAS = 10.00 (m)	0.00	0.00				Surface	Pass
	3143.18	32.81	3141.14	3110.37	46202.29	MAS = 10.00 (m)	26.00	26.00				WRP	
	2060.50	73.37	2010.53	1987.13	43.97	OSF1.50	9460.00	9426.83				MinPt-CtCt	
	2060.58	73.65	2010.43	1986.94	43.79	OSF1.50	9520.00	9486.83				MINPT-O-EOU	
	2060.66	73.73	2010.44	1986.93	43.74	OSF1.50	9540.00	9506.83				MinPt-O-ADP	
	2065.56	74.18	2015.06	1991.39	43.58	OSF1.50	9800.00	9766.83				MinPt-O-SF	
	3204.24	54.08	3167.53	3150.16	92.29	OSF1.50	12710.00	12362.66				MinPt-O-SF	
	3232.94	313.88	3023.02	2919.06	15.54	OSF1.50	22432.14	12375.00				MinPts	
Cimarex Red Hills Unit #5H (Offset) Gyro Off-12608ft (Def Survey)													
	3158.94	32.81	3156.96	3126.13	N/A	MAS = 10.00 (m)	0.00	0.00				MinPts	Pass
	3158.97	32.81	3156.95	3126.16	69354.77	MAS = 10.00 (m)	26.00	26.00				WRP	
	3161.25	32.81	3155.94	3128.44	948.11	MAS = 10.00 (m)	630.00	630.00				MINPT-O-EOU	
	3163.62	32.81	3155.75	3130.81	536.83	MAS = 10.00 (m)	1160.00	1160.00				MINPT-O-EOU	
	3166.08	32.81	3154.19	3133.28	318.17	MAS = 10.00 (m)	2030.00	2030.00				MinPts	

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Cl-Cl (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
3166.07	32.81	3153.92	3133.28	311.23		MAS = 10.00 (m)	2090.00	2090.00				MinPts	
2896.09	35.75	2871.52	2860.34	129.37		OSF1.50	5600.00	5567.67				MinPt-O-SF	
2888.34	34.20	2864.81	2854.14	135.27		OSF1.50	5880.00	5846.84				MinPt-O-ADP	
2888.29	34.16	2864.80	2854.15	135.51		OSF1.50	5890.00	5856.84				MINPT-O-EQU	
2888.25	34.04	2864.83	2854.21	135.98		OSF1.50	5910.00	5876.83				MinPt-CiCi	
2888.97	34.16	2865.46	2854.81	135.48		OSF1.50	6070.00	6036.83				MinPt-O-ADP	
2891.03	35.99	2866.30	2855.03	128.19		OSF1.50	6420.00	6386.83				MinPt-O-ADP	
2893.20	37.96	2867.17	2855.25	121.23		OSF1.50	6770.00	6736.83				MinPt-O-ADP	
2928.38	53.81	2891.79	2874.57	84.95		OSF1.50	9190.00	9156.83				MinPt-O-ADP	
2929.71	54.91	2892.41	2874.81	83.22		OSF1.50	9340.00	9306.83				MINPT-O-EQU	
2930.17	55.68	2892.35	2874.51	82.08		OSF1.50	9440.00	9406.83				MINPT-O-EQU	
2930.33	55.84	2892.39	2874.49	81.78		OSF1.50	9470.00	9436.83				MinPt-O-ADP	
2931.08	56.51	2892.70	2874.57	80.78		OSF1.50	9570.00	9536.83				MinPt-O-ADP	
2931.55	57.46	2892.52	2874.08	79.44		OSF1.50	9710.00	9676.83				MINPT-O-EQU	
2931.78	57.75	2892.57	2874.03	79.01		OSF1.50	9760.00	9726.83				MinPt-O-ADP	
2928.60	60.73	2887.38	2867.87	74.97		OSF1.50	10280.00	10246.83				MinPt-CiCi	
2928.69	61.01	2887.30	2867.68	74.58		OSF1.50	10330.00	10296.83				MINPT-O-EQU	
2928.88	61.24	2887.35	2867.64	74.26		OSF1.50	10370.00	10336.83				MinPt-O-ADP	
2928.19	65.30	2883.93	2862.89	69.53		OSF1.50	10990.00	10956.83				MinPt-CiCi	
2928.20	65.34	2883.92	2862.86	69.47		OSF1.50	11000.00	10966.83				MINPT-O-EQU	
2928.37	65.64	2883.90	2862.73	69.13		OSF1.50	11050.00	11016.83				MINPT-O-EQU	
2928.51	65.80	2883.93	2862.70	68.92		OSF1.50	11080.00	11046.83				MinPt-O-ADP	
2928.87	71.10	2880.67	2857.77	63.89		OSF1.50	11898.00	11865.00				MinPt-O-SF	
2443.22	64.68	2399.25	2378.55	58.94		OSF1.50	13780.00	12375.00				MinPt-CiCi	
2443.23	64.74	2399.22	2378.49	58.87		OSF1.50	13790.00	12375.00				MINPT-O-EQU	
2443.28	64.81	2399.23	2378.47	58.80		OSF1.50	13800.00	12375.00				MinPt-O-ADP	
2725.22	78.87	2671.98	2646.39	53.13		OSF1.50	14990.00	12375.00				MinPt-O-SF	
2734.13	79.12	2680.73	2655.01	53.12		OSF1.50	15010.00	12375.00				MinPt-O-SF	
8986.76	101.12	8918.69	8885.65	135.94		OSF1.50	22432.14	12375.00				TD	

Cimarex Red Hills Unit #37H  
Rev0 RM 27Aug18 (Non-Def  
Plan)

Pass

3163.07	32.81	3161.08	3130.27	290355.63		MAS = 10.00 (m)	0.00	0.00				Surface	
3163.07	32.81	3161.03	3130.27	46043.45		MAS = 10.00 (m)	26.00	26.00				WRP	
2530.45	76.01	2478.90	2454.43	51.65		OSF1.50	9460.00	9426.83				MinPt-CiCi	
2530.50	76.20	2478.83	2454.30	51.52		OSF1.50	9500.00	9466.83				MinPts	
2535.76	76.43	2483.95	2459.33	51.45		OSF1.50	9790.00	9756.83				MinPt-O-SF	
3529.08	61.85	3487.19	3467.23	88.37		OSF1.50	12780.00	12370.13				MinPt-O-SF	
3553.78	315.48	3342.81	3238.31	17.00		OSF1.50	22432.14	12375.00				MinPts	

Cimarex Red Hills Unit #16H  
MWD Final (Surcon Corrected)  
(Def Survey)

Pass

3069.30	32.81	3067.31	3036.49	204358.69		MAS = 10.00 (m)	0.00	0.00				Surface	
3069.28	32.81	3067.22	3036.47	39917.51		MAS = 10.00 (m)	26.00	26.00				WRP	
3053.15	32.81	3045.75	3020.35	562.45		MAS = 10.00 (m)	1260.00	1260.00				MinPts	
3053.90	32.81	3044.88	3021.09	434.12		MAS = 10.00 (m)	1620.00	1620.00				MINPT-O-EQU	
3054.93	32.81	3045.13	3022.12	390.63		MAS = 10.00 (m)	1800.00	1800.00				MINPT-O-EQU	
2684.98	35.56	2660.48	2649.41	121.13		OSF1.50	5600.00	5567.67				MinPt-O-SF	
2673.89	34.18	2650.31	2639.70	125.98		OSF1.50	5860.00	5826.84				MinPt-O-ADP	
2673.84	34.13	2650.30	2639.72	126.20		OSF1.50	5870.00	5836.84				MINPT-O-EQU	
2673.83	34.07	2650.32	2639.75	126.42		OSF1.50	5880.00	5846.84				MinPt-CiCi	
2805.91	52.55	2770.22	2753.36	83.17		OSF1.50	9390.00	9356.83				MinPt-O-SF	
2940.38	54.34	2903.50	2886.04	84.18		OSF1.50	9890.00	9856.83				MinPt-O-SF	
3077.68	55.56	3039.98	3022.12	86.11		OSF1.50	10280.00	10246.83				MinPt-O-SF	
3388.41	56.38	3350.16	3332.03	93.38		OSF1.50	10960.00	10926.83				MinPt-O-SF	
4235.92	53.17	4199.81	4182.74	124.05		OSF1.50	13070.00	12375.00				MinPt-CiCi	
4236.09	53.57	4199.72	4182.52	123.12		OSF1.50	13110.00	12375.00				MINPT-O-EQU	
4236.27	53.78	4199.75	4182.49	122.60		OSF1.50	13130.00	12375.00				MinPt-O-ADP	
4251.22	62.10	4209.16	4189.12	106.01		OSF1.50	13650.00	12375.00				MinPt-CiCi	
4250.58	66.80	4205.39	4183.78	98.31		OSF1.50	13890.00	12375.00				MinPt-CiCi	
4240.83	92.53	4178.48	4148.30	70.22		OSF1.50	14980.00	12375.00				MinPt-CiCi	
4241.43	98.06	4175.40	4143.37	66.18		OSF1.50	15190.00	12375.00				MinPt-CiCi	
4237.77	110.41	4163.50	4127.36	58.60		OSF1.50	15650.00	12375.00				MinPt-CiCi	
4238.52	112.56	4162.82	4125.96	57.47		OSF1.50	15750.00	12375.00				MINPT-O-EQU	
4239.24	113.42	4162.97	4125.82	57.03		OSF1.50	15790.00	12375.00				MinPt-O-ADP	
4246.31	119.62	4165.90	4126.69	54.12		OSF1.50	16020.00	12375.00				MinPt-O-ADP	
4249.54	142.96	4153.57	4106.58	45.19		OSF1.50	16820.00	12375.00				MinPt-CiCi	
4251.90	154.62	4148.16	4097.28	41.77		OSF1.50	17230.00	12375.00				MinPt-CiCi	
4253.03	157.96	4147.07	4095.08	40.88		OSF1.50	17370.00	12375.00				MINPT-O-EQU	
4257.82	177.83	4138.61	4079.99	36.30		OSF1.50	18030.00	12375.00				MinPt-CiCi	
4259.60	185.58	4135.28	4074.08	34.80		OSF1.50	18320.00	12375.00				MINPT-O-EQU	
4262.69	189.18	4135.91	4073.51	34.14		OSF1.50	18460.00	12375.00				MinPt-O-ADP	
4256.58	207.34	4117.71	4049.26	31.08		OSF1.50	19040.00	12375.00				MinPt-CiCi	
4257.25	209.31	4117.05	4047.95	30.79		OSF1.50	19130.00	12375.00				MINPT-O-EQU	
4258.00	210.17	4117.22	4047.83	30.66		OSF1.50	19170.00	12375.00				MinPt-O-ADP	
4263.33	216.10	4118.61	4047.23	29.85		OSF1.50	19340.00	12375.00				MinPt-CiCi	
4264.16	219.57	4117.12	4044.59	29.38		OSF1.50	19480.00	12375.00				MINPT-O-EQU	
4264.89	220.46	4117.26	4044.44	29.27		OSF1.50	19520.00	12375.00				MinPt-O-ADP	
4272.38	226.04	4121.03	4046.34	28.59		OSF1.50	19720.00	12375.00				MINPT-O-EQU	
4273.97	228.01	4121.30	4045.96	28.35		OSF1.50	19780.00	12375.00				MinPt-O-ADP	
4279.05	247.40	4113.46	4031.65	26.14		OSF1.50	20400.00	12375.00				MinPt-CiCi	
4279.59	253.95	4109.64	4025.65	25.47		OSF1.50	20620.00	12375.00				MinPt-CiCi	
4280.39	256.51	4108.73	4023.89	25.21		OSF1.50	20730.00	12375.00				MINPT-O-EQU	
4281.32	257.65	4108.89	4023.67	25.11		OSF1.50	20780.00	12375.00				MinPt-O-ADP	
4240.77	282.45	4051.81	3958.32	22.67		OSF1.50	21580.00	12375.00				MinPt-CiCi	
4241.46	284.48	4051.14	3956.97	22.51		OSF1.50	21670.00	12375.00				MINPT-O-EQU	
4242.39	285.50	4051.34	3956.80	22.43		OSF1.50	21720.00	12375.00				MinPt-O-ADP	
4251.07	292.08	4055.68	3958.98	21.97		OSF1.50	21950.00	12375.00				MinPts	
4276.21	304.80	4072.35	3971.41	21.17		OSF1.50	22432.14	12375.00				MinPt-O-SF	

Cimarex Red Hills Unit #17H  
MWD Final(Surcon Corrected)  
(Def Survey)

Pass

3089.25	32.81	3087.27	3056.45	416878.43	MAS = 10.00 (m)	0.00	0.00
3089.26	32.81	3087.22	3056.46	48703.14	MAS = 10.00 (m)	26.00	26.00
3090.17	32.81	3086.25	3057.37	1585.32	MAS = 10.00 (m)	470.00	470.00
2845.64	35.65	2821.13	2809.99	127.62	OSF1.50	5600.00	5567.67
2837.35	34.37	2813.69	2802.98	132.34	OSF1.50	5840.00	5806.86
2837.30	34.32	2813.67	2802.98	132.57	OSF1.50	5850.00	5816.85
2837.27	34.21	2813.72	2803.06	133.02	OSF1.50	5870.00	5836.84
2849.14	39.39	2822.14	2809.75	114.87	OSF1.50	7020.00	6986.83
2849.43	40.27	2821.84	2809.16	112.24	OSF1.50	7160.00	7126.83

Offset Trajectory	Separation			Allow Dev. (ft)	Sep. Fact.	Controlling Rule	Reference Trajectory		Risk Level			Alert	Status
	Ct-Ct (ft)	MAS (ft)	EOU (ft)				MD (ft)	TVD (ft)	Alert	Minor	Major		
2850.22	41.23	2822.00	2808.89	109.51		OSF1.50	7310.00	7276.83				MinPt-O-ADP	
2851.26	49.37	2817.61	2801.89	90.62		OSF1.50	8670.00	8636.83				MinPt-CtCt	
2851.30	50.73	2816.74	2800.57	88.08		OSF1.50	8870.00	8836.83				MinPt-CtCt	
2851.87	52.25	2816.30	2799.62	85.42		OSF1.50	9110.00	9076.83				MINPT-O-EQU	
2842.38	59.48	2801.98	2782.90	74.43		OSF1.50	10310.00	10276.83				MinPt-CtCt	
2842.70	60.37	2801.71	2782.33	73.30		OSF1.50	10440.00	10406.83				MINPT-O-EQU	
2844.94	63.20	2802.07	2781.74	69.94		OSF1.50	10890.00	10856.83				MinPt-O-ADP	
2849.82	69.42	2802.80	2780.40	63.58		OSF1.50	11900.00	11866.83				MinPts	
2848.72	68.28	2802.46	2780.43	64.63		OSF1.50	12070.00	12033.15				MinPt-O-ADP	
2848.47	67.98	2802.41	2780.48	64.92		OSF1.50	12110.00	12069.95				MINPT-O-EQU	
2847.97	66.79	2802.71	2781.18	66.19		OSF1.50	12320.00	12234.06				MinPt-O-SF	
2828.50	65.25	2784.25	2763.25	67.31		OSF1.50	12620.00	12348.08				MinPt-O-SF	
2820.22	64.78	2776.27	2755.44	67.63		OSF1.50	12910.00	12375.00				MinPt-O-SF	
2820.19	64.78	2776.25	2755.41	67.63		OSF1.50	12930.00	12375.00				MinPts	
2847.16	66.85	2801.85	2780.31	66.04		OSF1.50	13410.00	12375.00				MinPts	
2838.45	72.24	2789.54	2766.21	60.78		OSF1.50	13920.00	12375.00				MinPt-CtCt	
2845.68	92.47	2783.29	2753.21	47.27		OSF1.50	14990.00	12375.00				MinPt-CtCt	
2848.58	102.69	2779.38	2745.90	42.50		OSF1.50	15450.00	12375.00				MinPt-CtCt	
2849.48	112.75	2773.57	2736.73	38.64		OSF1.50	15860.00	12375.00				MinPt-CtCt	
2841.47	123.00	2758.72	2718.47	35.27		OSF1.50	16270.00	12375.00				MinPt-CtCt	
2842.00	124.68	2758.13	2717.32	34.79		OSF1.50	16350.00	12375.00				MINPT-O-EQU	
2842.53	125.29	2758.26	2717.24	34.62		OSF1.50	16380.00	12375.00				MinPt-O-ADP	
2851.88	138.53	2758.77	2713.34	31.36		OSF1.50	16850.00	12375.00				MinPt-CtCt	
2852.72	141.08	2757.91	2711.62	30.79		OSF1.50	16960.00	12375.00				MINPT-O-EQU	
2860.72	150.17	2759.87	2710.55	28.98		OSF1.50	17300.00	12375.00				MinPt-O-ADP	
2858.87	177.41	2739.86	2681.46	24.46		OSF1.50	18250.00	12375.00				MinPt-CtCt	
2859.70	180.06	2738.92	2679.64	24.10		OSF1.50	18360.00	12375.00				MINPT-O-EQU	
2860.71	181.24	2739.15	2679.48	23.95		OSF1.50	18410.00	12375.00				MinPt-O-ADP	
2866.10	186.87	2740.75	2679.23	23.26		OSF1.50	18600.00	12375.00				MINPT-O-EQU	
2866.88	187.79	2740.95	2679.08	23.15		OSF1.50	18640.00	12375.00				MinPt-O-ADP	
2863.80	213.79	2720.53	2650.00	20.29		OSF1.50	19520.00	12375.00				MinPt-CtCt	
2874.03	252.05	2705.27	2621.98	17.24		OSF1.50	20830.00	12375.00				MinPt-CtCt	
2874.96	254.81	2704.37	2620.16	17.06		OSF1.50	20940.00	12375.00				MINPT-O-EQU	
2875.20	258.81	2701.93	2616.39	16.79		OSF1.50	21060.00	12375.00				MinPt-CtCt	
2874.48	269.46	2694.12	2605.03	16.12		OSF1.50	21420.00	12375.00				MinPt-CtCt	
2878.08	288.00	2685.35	2590.07	15.09		OSF1.50	22050.00	12375.00				MinPt-CtCt	
2879.36	292.66	2683.53	2586.70	14.86		OSF1.50	22220.00	12375.00				MINPT-O-EQU	
2879.52	292.85	2683.56	2586.67	14.85		OSF1.50	22230.00	12375.00				MinPt-O-ADP	
2890.19	295.89	2692.22	2594.30	14.75		OSF1.50	22432.14	12375.00				MinPt-O-SF	

Cimarex Red Hills Unit #38H  
Rev1 RM 16Oct18 (Def Plan)

Pass

3183.03	32.81	3181.04	3150.22	286344.52	MAS = 10.00 (m)	0.00	0.00					Surface	
3183.03	32.81	3180.98	3150.22	46184.60	MAS = 10.00 (m)	26.00	26.00					WRP	
3183.03	32.81	3172.17	3150.22	358.34	MAS = 10.00 (m)	1460.00	1460.00					MinPts	
3183.14	32.81	3172.03	3150.33	348.49	MAS = 10.00 (m)	1510.00	1510.00					MINPT-O-EQU	
3146.74	32.81	3124.29	3113.93	153.94	MAS = 10.00 (m)	3700.00	3687.28					MinPt-O-SF	
2900.85	79.29	2847.22	2821.56	56.49	OSF1.50	9460.00	9426.83					MinPt-CtCt	
2900.89	79.48	2847.13	2821.41	56.38	OSF1.50	9500.00	9466.83					MinPts	
3802.00	67.97	3756.02	3734.02	86.37	OSF1.50	12740.00	12366.28					MinPt-O-SF	
3830.38	319.74	3616.56	3510.65	18.07	OSF1.50	22432.14	12375.00					MinPts	

Texaco G W Miller Federal N #1  
(Offset) Plugged Oil Blind Off-  
5258ft (Def Survey)

Pass

9494.66	32.81	9492.68	9461.85	N/A	MAS = 10.00 (m)	0.00	0.00					Surface	
9494.61	32.81	9492.63	9461.80	N/A	MAS = 10.00 (m)	20.00	20.00					MinPt-O-SF	
9494.61	32.81	9492.62	9461.80	N/A	MAS = 10.00 (m)	26.00	26.00					WRP	
9494.60	667.56	9048.91	8827.05	21.39	OSF1.50	2200.00	2200.00					MinPt-CtCt	
9760.22	1639.04	8666.85	8121.18	8.94	OSF1.50	5320.00	5290.46					MinPts	
9761.15	1639.40	8667.56	8121.75	8.94	OSF1.50	5330.00	5300.36					MinPt-O-SF	
9995.05	1158.26	9222.22	8836.79	12.93	OSF1.50	14960.00	12375.00					MinPt-O-SF	
7217.24	379.28	6963.72	6837.96	28.68	OSF1.50	21870.00	12375.00					MinPt-CtCt	
7219.13	383.29	6962.94	6835.83	28.39	OSF1.50	22040.00	12375.00					MINPT-O-EQU	
7238.74	405.94	6967.45	6832.75	26.87	OSF1.50	22432.14	12375.00					MinPts	





## Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20 Proposal Geodetic Report (Non-Def Plan)




<b>Report Date:</b>	April 07, 2020 - 04:40 PM	<b>Survey / DLS Computation:</b>	Minimum Curvature / Lubinski
<b>Client:</b>	Cimarex Energy	<b>Vertical Section Azimuth:</b>	179.529 ° (Grid North)
<b>Field:</b>	NM Lea County (NAD 83)	<b>Vertical Section Origin:</b>	0.000 ft, 0.000 ft
<b>Structure / Slot:</b>	Cimarex Red Hills 33-4 Unit #20H / New Slot	<b>TVD Reference Datum:</b>	RKB
<b>Well:</b>	Red Hills 33-4 Unit #20H	<b>TVD Reference Elevation:</b>	3373.600 ft above MSL
<b>Borehole:</b>	Red Hills 33-4 Unit #20H	<b>Seabed / Ground Elevation:</b>	3347.600 ft above MSL
<b>UWI / API#:</b>	Unknown / Unknown	<b>Magnetic Declination:</b>	6.545 °
<b>Survey Name:</b>	Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20	<b>Total Gravity Field Strength:</b>	998.4369mgn (9.80665 Based)
<b>Survey Date:</b>	April 06, 2020	<b>Gravity Model:</b>	GARM
<b>Tort / AHD / DDI / ERD Ratio:</b>	106.528 ° / 10737.586 ft / 6.317 / 0.868	<b>Total Magnetic Field Strength:</b>	47667.087 nT
<b>Coordinate Reference System:</b>	NAD83 New Mexico State Plane, Eastern Zone, US Feet	<b>Magnetic Dip Angle:</b>	59.684 °
<b>Location Lat / Long:</b>	N 32° 5' 34.93347", W 103° 34' 26.33825"	<b>Declination Date:</b>	April 06, 2020
<b>Location Grid N/E Y/X:</b>	N 398411.630 ftUS, E 776492.110 ftUS	<b>Magnetic Declination Model:</b>	HDGM 2020
<b>CRS Grid Convergence Angle:</b>	0.4035 °	<b>North Reference:</b>	Grid North
<b>Grid Scale Factor:</b>	0.99997243	<b>Grid Convergence Used:</b>	0.4035 °
<b>Version / Patch:</b>	2.10.787.0	<b>Total Corr Mag North-&gt;Grid North:</b>	6.1411 °
		<b>Local Coord Referenced To:</b>	Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [453' FNL, 1620' FEL]	0.00	0.00	181.84	0.00	0.00	0.00	0.00	N/A	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	100.00	0.00	302.00	100.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	200.00	0.00	302.00	200.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	300.00	0.00	302.00	300.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	400.00	0.00	302.00	400.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	500.00	0.00	302.00	500.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	600.00	0.00	302.00	600.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	700.00	0.00	302.00	700.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	800.00	0.00	302.00	800.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	900.00	0.00	302.00	900.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
Rustler	926.00	0.00	302.00	926.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1000.00	0.00	302.00	1000.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1100.00	0.00	302.00	1100.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1200.00	0.00	302.00	1200.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
Top of Salt	1260.00	0.00	302.00	1260.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1300.00	0.00	302.00	1300.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1400.00	0.00	302.00	1400.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1500.00	0.00	302.00	1500.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1600.00	0.00	302.00	1600.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1700.00	0.00	302.00	1700.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1800.00	0.00	302.00	1800.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	1900.00	0.00	302.00	1900.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	2000.00	0.00	302.00	2000.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	2100.00	0.00	302.00	2100.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
Nudge 2"/100' DLS	2200.00	0.00	302.00	2200.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
	2300.00	2.00	302.00	2299.98	-0.94	0.92	-1.48	2.00	398412.55	776490.63	N 32 5 34.94	W 103 34 26.36
	2400.00	4.00	302.00	2399.84	-3.75	3.70	-5.92	2.00	398415.33	776486.19	N 32 5 34.97	W 103 34 26.41
	2500.00	6.00	302.00	2499.45	-8.43	8.32	-13.31	2.00	398419.95	776478.80	N 32 5 35.02	W 103 34 26.49
	2600.00	8.00	302.00	2598.70	-14.97	14.77	-23.64	2.00	398426.40	776468.47	N 32 5 35.08	W 103 34 26.61
Hold Nudge	2613.20	8.26	302.00	2611.77	-15.97	15.76	-25.23	2.00	398427.39	776466.88	N 32 5 35.09	W 103 34 26.63
	2700.00	8.26	302.00	2697.67	-22.67	22.37	-35.81	0.00	398434.00	776456.30	N 32 5 35.16	W 103 34 26.75
	2800.00	8.26	302.00	2796.63	-30.39	29.99	-48.00	0.00	398441.62	776444.11	N 32 5 35.23	W 103 34 26.89
	2900.00	8.26	302.00	2895.59	-38.10	37.61	-60.19	0.00	398449.24	776431.93	N 32 5 35.31	W 103 34 27.03
	3000.00	8.26	302.00	2994.55	-45.82	45.23	-72.38	0.00	398456.85	776419.74	N 32 5 35.39	W 103 34 27.18
	3100.00	8.26	302.00	3093.51	-53.54	52.84	-84.56	0.00	398464.47	776407.55	N 32 5 35.46	W 103 34 27.32
	3200.00	8.26	302.00	3192.48	-61.25	60.46	-96.75	0.00	398472.09	776395.36	N 32 5 35.54	W 103 34 27.46
	3300.00	8.26	302.00	3291.44	-68.97	68.08	-108.94	0.00	398479.70	776383.17	N 32 5 35.61	W 103 34 27.60
	3400.00	8.26	302.00	3390.40	-76.69	75.69	-121.13	0.00	398487.32	776370.98	N 32 5 35.69	W 103 34 27.74
	3500.00	8.26	302.00	3489.36	-84.40	83.31	-133.32	0.00	398494.94	776358.79	N 32 5 35.77	W 103 34 27.88
	3600.00	8.26	302.00	3588.32	-92.12	90.93	-145.51	0.00	398502.55	776346.60	N 32 5 35.84	W 103 34 28.02
	3700.00	8.26	302.00	3687.28	-99.84	98.54	-157.70	0.00	398510.17	776334.41	N 32 5 35.92	W 103 34 28.16
	3800.00	8.26	302.00	3786.25	-107.55	106.16	-169.89	0.00	398517.79	776322.22	N 32 5 36.00	W 103 34 28.30
	3900.00	8.26	302.00	3885.21	-115.27	113.78	-182.08	0.00	398525.40	776310.04	N 32 5 36.07	W 103 34 28.45
	4000.00	8.26	302.00	3984.17	-122.99	121.39	-194.27	0.00	398533.02	776297.85	N 32 5 36.15	W 103 34 28.59
	4100.00	8.26	302.00	4083.13	-130.70	129.01	-206.46	0.00	398540.64	776285.66	N 32 5 36.22	W 103 34 28.73
	4200.00	8.26	302.00	4182.09	-138.42	136.63	-218.65	0.00	398548.25	776273.47	N 32 5 36.30	W 103 34 28.87
	4300.00	8.26	302.00	4281.05	-146.14	144.24	-230.84	0.00	398555.87	776261.28	N 32 5 36.38	W 103 34 29.01
	4400.00	8.26	302.00	4380.02	-153.85	151.86	-243.03	0.00	398563.49	776249.09	N 32 5 36.45	W 103 34 29.15
	4500.00	8.26	302.00	4478.98	-161.57	159.48	-255.22	0.00	398571.10	776236.90	N 32 5 36.53	W 103 34 29.29
	4600.00	8.26	302.00	4577.94	-169.29	167.09	-267.41	0.00	398578.72	776224.71	N 32 5 36.61	W 103 34 29.43
Base of Salt	4674.84	8.26	302.00	4652.00	-175.06	172.79	-276.53	0.00	398584.42	776215.59	N 32 5 36.66	W 103 34 29.54
	4700.00	8.26	302.00	4676.90	-177.00	174.71	-279.59	0.00	398586.34	776212.52	N 32 5 36.68	W 103 34 29.57
	4800.00	8.26	302.00	4775.86	-184.72	182.33	-291.78	0.00	398593.95	776200.33	N 32 5 36.76	W 103 34 29.71
	4900.00	8.26	302.00	4874.82	-192.44	189.94	-303.97	0.00	398601.57	776188.15	N 32 5 36.83	W 103 34 29.86
Lamar	4913.31	8.26	302.00	4888.00	-193.46	190.96	-305.60	0.00	398602.58	776186.52	N 32 5 36.84	W 103 34 29.87
Bell Canyon	4957.78	8.26	302.00	4932.00	-196.89	194.34	-311.02	0.00	398605.97	776181.10	N 32 5 36.88	W 103 34 29.94
	5000.00	8.26	302.00	4973.78	-200.15	197.56	-316.16	0.00	398609.18	776175.96	N 32 5 36.91	W 103 34 30.00
	5100.00	8.26	302.00	5072.75	-207.87	205.18	-328.35	0.00	398616.80	776163.77	N 32 5 36.99	W 103 34 30.14
	5200.00	8.26	302.00	5171.71	-215.59	212.79	-340.54	0.00	398624.42	776151.58	N 32 5 37.06	W 103 34 30.28
	5300.00	8.26	302.00	5270.67	-223.30	220.41	-352.73	0.00	398632.03	776139.39	N 32 5 37.14	W 103 34 30.42
	5400.00	8.26	302.00	5369.63	-231.02	228.03	-364.92	0.00	398639.65	776127.20	N 32 5 37.22	W 103 34 30.56
	5500.00	8.26	302.00	5468.59	-238.74	235.64	-377.11	0.00	398647.27	776115.01	N 32 5 37.29	W 103 34 30.70
Drop to Vertical 2"/100' DLS	5531.74	8.26	302.00	5500.00	-241.19	238.06	-380.98	0.00	398649.68	776111.14	N 32 5 37.32	W 103 34 30.75
	5600.00	6.90	302.00	5567.67	-246.02	242.83	-388.62	2.00	398654.46	776103.51	N 32 5 37.36	W 103 34 30.84
	5700.00	4.90	302.00	5667.13	-251.54	248.28	-397.33	2.00	398659.90	776094.79	N 32 5 37.42	W 103 34 30.94
	5800.00	2.90	302.00	5766.89	-255.19	251.88	-403.10	2.00	398663.51	776089.03	N 32 5 37.45	W 103 34 31.00
	5900.00	0.90	302.00	5866.83	-256.97	253.64	-405.91	2.00	398665.26	776086.22	N 32 5 37.47	W 103 34 31.04
Hold Vertical	5944.94	0.00	302.00	5911.77	-257.16	253.83	-406.21	2.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6000.00	0.00	302.00	5966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Cherry Canyon	6050.17	0.00	302.00	6017.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6100.00	0.00	302.00	6066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6200.00	0.00	302.00	6166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6300.00	0.00	302.00	6266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6400.00	0.00	302.00	6366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6500.00	0.00	302.00	6466.83	-257.16	253.83	-406.2					




Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	6600.00	0.00	302.00	6566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6700.00	0.00	302.00	6666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6800.00	0.00	302.00	6766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	6900.00	0.00	302.00	6866.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7000.00	0.00	302.00	6966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7100.00	0.00	302.00	7066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7200.00	0.00	302.00	7166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7300.00	0.00	302.00	7266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7400.00	0.00	302.00	7366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7500.00	0.00	302.00	7466.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Brushy Canyon	7523.17	0.00	302.00	7490.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7600.00	0.00	302.00	7566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7700.00	0.00	302.00	7666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7800.00	0.00	302.00	7766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	7900.00	0.00	302.00	7866.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8000.00	0.00	302.00	7966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8100.00	0.00	302.00	8066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8200.00	0.00	302.00	8166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8300.00	0.00	302.00	8266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8400.00	0.00	302.00	8366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8500.00	0.00	302.00	8466.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8600.00	0.00	302.00	8566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8700.00	0.00	302.00	8666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8800.00	0.00	302.00	8766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	8900.00	0.00	302.00	8866.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9000.00	0.00	302.00	8966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Bone Spring	9072.17	0.00	302.00	9039.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9100.00	0.00	302.00	9066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Leonard Shale	9127.17	0.00	302.00	9094.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9200.00	0.00	302.00	9166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9300.00	0.00	302.00	9266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Avalon Shale	9389.17	0.00	302.00	9356.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9400.00	0.00	302.00	9366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9500.00	0.00	302.00	9466.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9600.00	0.00	302.00	9566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9700.00	0.00	302.00	9666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Lower Avalon Shale	9764.17	0.00	302.00	9731.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9800.00	0.00	302.00	9766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	9900.00	0.00	302.00	9866.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10000.00	0.00	302.00	9966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
1st Bone Spring Sand	10069.17	0.00	302.00	10036.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10100.00	0.00	302.00	10066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10200.00	0.00	302.00	10166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
2nd Bone Spring Carb	10256.17	0.00	302.00	10223.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10300.00	0.00	302.00	10266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10400.00	0.00	302.00	10366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10500.00	0.00	302.00	10466.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
2nd Bone Spring Sand	10597.17	0.00	302.00	10564.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10600.00	0.00	302.00	10566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10700.00	0.00	302.00	10666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10800.00	0.00	302.00	10766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	10900.00	0.00	302.00	10866.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11000.00	0.00	302.00	10966.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
3rd Bone Spring Carb	11050.17	0.00	302.00	11017.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11100.00	0.00	302.00	11066.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11200.00	0.00	302.00	11166.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11300.00	0.00	302.00	11266.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11400.00	0.00	302.00	11366.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11500.00	0.00	302.00	11466.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11600.00	0.00	302.00	11566.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11700.00	0.00	302.00	11666.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
3rd Bone Spring Sand	11715.17	0.00	302.00	11682.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11800.00	0.00	302.00	11766.83	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
KOP - Build 12"/100' DLS	11898.16	0.00	302.00	11865.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
	11900.00	0.22	179.53	11866.83	-257.15	253.82	-406.21	12.00	398665.44	776085.92	N 32 5 37.47	W 103 34 31.04
	12000.00	12.22	179.53	11966.06	-246.34	243.01	-406.12	12.00	398654.63	776086.01	N 32 5 37.37	W 103 34 31.04
	12100.00	24.22	179.53	12060.87	-215.13	211.80	-405.86	12.00	398623.42	776086.26	N 32 5 37.06	W 103 34 31.04
	12200.00	36.22	179.53	12147.13	-164.89	161.56	-405.45	12.00	398573.18	776086.68	N 32 5 36.56	W 103 34 31.04
Wolfcamp	12283.73	46.27	179.53	12210.00	-109.76	106.43	-404.99	12.00	398518.06	776087.13	N 32 5 36.01	W 103 34 31.04
	12300.00	48.22	179.53	12221.05	-97.81	94.49	-404.90	12.00	398506.11	776087.23	N 32 5 35.90	W 103 34 31.04
	12400.00	60.22	179.53	12279.41	-16.83	13.51	-404.23	12.00	398425.14	776087.89	N 32 5 35.10	W 103 34 31.04
Wolfcamp Y Sand	12401.19	60.36	179.53	12280.00	-15.79	12.47	-404.22	12.00	398424.10	776087.90	N 32 5 35.09	W 103 34 31.04
Wolfcamp Y SS Target	12445.28	65.65	179.53	12300.00	23.47	-26.79	-403.90	12.00	398384.84	776088.22	N 32 5 34.70	W 103 34 31.04
Wolfcamp A1	12450.18	66.24	179.53	12302.00	27.95	-31.27	-403.86	12.00	398380.36	776088.26	N 32 5 34.65	W 103 34 31.04
	12500.00	72.22	179.53	12319.66	74.51	-77.83	-403.48	12.00	398333.80	776088.64	N 32 5 34.19	W 103 34 31.03
Build 4"/100' DLS	12523.16	75.00	179.53	12326.19	96.73	-100.05	-403.30	12				

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
	14800.00	90.00	179.53	12375.00	2369.30	-2372.54	-384.61	0.00	396039.16	776107.51	N 32 5 11.48	W 103 34 31.00
	14900.00	90.00	179.53	12375.00	2469.30	-2472.54	-383.79	0.00	395939.17	776108.33	N 32 5 10.49	W 103 34 31.00
	15000.00	90.00	179.53	12375.00	2569.30	-2572.53	-382.97	0.00	395839.17	776109.15	N 32 5 9.50	W 103 34 31.00
	15100.00	90.00	179.53	12375.00	2669.30	-2672.53	-382.15	0.00	395739.18	776109.97	N 32 5 8.52	W 103 34 31.00
	15200.00	90.00	179.53	12375.00	2769.30	-2772.53	-381.33	0.00	395639.18	776110.80	N 32 5 7.53	W 103 34 31.00
	15300.00	90.00	179.53	12375.00	2869.30	-2872.52	-380.50	0.00	395539.19	776111.62	N 32 5 6.54	W 103 34 31.00
	15400.00	90.00	179.53	12375.00	2969.30	-2972.52	-379.68	0.00	395439.20	776112.44	N 32 5 5.55	W 103 34 30.99
	15500.00	90.00	179.53	12375.00	3069.30	-3072.52	-378.86	0.00	395339.20	776113.26	N 32 5 4.56	W 103 34 30.99
	15600.00	90.00	179.53	12375.00	3169.30	-3172.51	-378.04	0.00	395239.21	776114.08	N 32 5 3.57	W 103 34 30.99
	15700.00	90.00	179.53	12375.00	3269.30	-3272.51	-377.21	0.00	395139.22	776114.91	N 32 5 2.58	W 103 34 30.99
	15800.00	90.00	179.53	12375.00	3369.30	-3372.51	-376.39	0.00	395039.22	776115.73	N 32 5 1.59	W 103 34 30.99
	15900.00	90.00	179.53	12375.00	3469.30	-3472.50	-375.57	0.00	394939.23	776116.55	N 32 5 0.60	W 103 34 30.99
	16000.00	90.00	179.53	12375.00	3569.30	-3572.50	-374.75	0.00	394839.24	776117.37	N 32 4 59.61	W 103 34 30.99
	16100.00	90.00	179.53	12375.00	3669.30	-3672.50	-373.93	0.00	394739.24	776118.19	N 32 4 58.62	W 103 34 30.98
	16200.00	90.00	179.53	12375.00	3769.30	-3772.49	-373.10	0.00	394639.25	776119.02	N 32 4 57.63	W 103 34 30.98
	16300.00	90.00	179.53	12375.00	3869.30	-3872.49	-372.28	0.00	394539.25	776119.84	N 32 4 56.64	W 103 34 30.98
	16400.00	90.00	179.53	12375.00	3969.30	-3972.49	-371.46	0.00	394439.26	776120.66	N 32 4 55.65	W 103 34 30.98
	16500.00	90.00	179.53	12375.00	4069.30	-4072.48	-370.64	0.00	394339.27	776121.48	N 32 4 54.66	W 103 34 30.98
	16600.00	90.00	179.53	12375.00	4169.30	-4172.48	-369.82	0.00	394239.27	776122.31	N 32 4 53.67	W 103 34 30.98
	16700.00	90.00	179.53	12375.00	4269.30	-4272.48	-368.99	0.00	394139.28	776123.13	N 32 4 52.68	W 103 34 30.98
	16800.00	90.00	179.53	12375.00	4369.30	-4372.47	-368.17	0.00	394039.29	776123.95	N 32 4 51.69	W 103 34 30.98
	16900.00	90.00	179.53	12375.00	4469.30	-4472.47	-367.35	0.00	393939.29	776124.77	N 32 4 50.70	W 103 34 30.97
	17000.00	90.00	179.53	12375.00	4569.30	-4572.47	-366.53	0.00	393839.30	776125.59	N 32 4 49.71	W 103 34 30.97
	17100.00	90.00	179.53	12375.00	4669.30	-4672.46	-365.71	0.00	393739.31	776126.42	N 32 4 48.72	W 103 34 30.97
	17200.00	90.00	179.53	12375.00	4769.30	-4772.46	-364.88	0.00	393639.31	776127.24	N 32 4 47.73	W 103 34 30.97
NMNIM0005792 - NMNIM089425 Crossing	17253.10	90.00	179.53	12375.00	4822.40	-4825.56	-364.45	0.00	393586.22	776127.67	N 32 4 47.21	W 103 34 30.97
	17300.00	90.00	179.53	12375.00	4869.30	-4872.46	-364.06	0.00	393539.32	776128.06	N 32 4 46.75	W 103 34 30.97
	17400.00	90.00	179.53	12375.00	4969.30	-4972.45	-363.24	0.00	393439.32	776128.88	N 32 4 45.76	W 103 34 30.97
	17500.00	90.00	179.53	12375.00	5069.30	-5072.45	-362.42	0.00	393339.33	776129.70	N 32 4 44.77	W 103 34 30.97
	17600.00	90.00	179.53	12375.00	5169.30	-5172.45	-361.59	0.00	393239.34	776130.53	N 32 4 43.78	W 103 34 30.96
	17700.00	90.00	179.53	12375.00	5269.30	-5272.44	-360.77	0.00	393139.34	776131.35	N 32 4 42.79	W 103 34 30.96
	17800.00	90.00	179.53	12375.00	5369.30	-5372.44	-359.95	0.00	393039.35	776132.17	N 32 4 41.80	W 103 34 30.96
	17900.00	90.00	179.53	12375.00	5469.30	-5472.44	-359.13	0.00	392939.36	776132.99	N 32 4 40.81	W 103 34 30.96
	18000.00	90.00	179.53	12375.00	5569.30	-5572.43	-358.31	0.00	392839.36	776133.81	N 32 4 39.82	W 103 34 30.96
	18100.00	90.00	179.53	12375.00	5669.30	-5672.43	-357.48	0.00	392739.37	776134.64	N 32 4 38.83	W 103 34 30.96
	18200.00	90.00	179.53	12375.00	5769.30	-5772.43	-356.66	0.00	392639.38	776135.46	N 32 4 37.84	W 103 34 30.96
	18300.00	90.00	179.53	12375.00	5869.30	-5872.42	-355.84	0.00	392539.38	776136.28	N 32 4 36.85	W 103 34 30.95
	18400.00	90.00	179.53	12375.00	5969.30	-5972.42	-355.02	0.00	392439.39	776137.10	N 32 4 35.86	W 103 34 30.95
	18500.00	90.00	179.53	12375.00	6069.30	-6072.42	-354.20	0.00	392339.39	776137.92	N 32 4 34.87	W 103 34 30.95
	18600.00	90.00	179.53	12375.00	6169.30	-6172.41	-353.37	0.00	392239.40	776138.75	N 32 4 33.88	W 103 34 30.95
	18700.00	90.00	179.53	12375.00	6269.30	-6272.41	-352.55	0.00	392139.41	776139.57	N 32 4 32.89	W 103 34 30.95
	18800.00	90.00	179.53	12375.00	6369.30	-6372.41	-351.73	0.00	392039.41	776140.39	N 32 4 31.90	W 103 34 30.95
	18900.00	90.00	179.53	12375.00	6469.30	-6472.40	-350.91	0.00	391939.42	776141.21	N 32 4 30.91	W 103 34 30.95
	19000.00	90.00	179.53	12375.00	6569.30	-6572.40	-350.09	0.00	391839.43	776142.04	N 32 4 29.92	W 103 34 30.94
	19100.00	90.00	179.53	12375.00	6669.30	-6672.40	-349.26	0.00	391739.43	776142.86	N 32 4 28.93	W 103 34 30.94
	19200.00	90.00	179.53	12375.00	6769.30	-6772.39	-348.44	0.00	391639.44	776143.68	N 32 4 27.94	W 103 34 30.94
	19300.00	90.00	179.53	12375.00	6869.30	-6872.39	-347.62	0.00	391539.44	776144.50	N 32 4 26.95	W 103 34 30.94
	19400.00	90.00	179.53	12375.00	6969.30	-6972.39	-346.80	0.00	391439.45	776145.32	N 32 4 25.97	W 103 34 30.94
	19500.00	90.00	179.53	12375.00	7069.30	-7072.38	-345.97	0.00	391339.46	776146.15	N 32 4 24.98	W 103 34 30.94
	19600.00	90.00	179.53	12375.00	7169.30	-7172.38	-345.15	0.00	391239.46	776146.97	N 32 4 23.99	W 103 34 30.94
	19700.00	90.00	179.53	12375.00	7269.30	-7272.38	-344.33	0.00	391139.47	776147.79	N 32 4 23.00	W 103 34 30.93
	19800.00	90.00	179.53	12375.00	7369.30	-7372.37	-343.51	0.00	391039.48	776148.61	N 32 4 22.01	W 103 34 30.93
	19900.00	90.00	179.53	12375.00	7469.30	-7472.37	-342.69	0.00	390939.48	776149.43	N 32 4 21.02	W 103 34 30.93
	20000.00	90.00	179.53	12375.00	7569.30	-7572.36	-341.86	0.00	390839.49	776150.26	N 32 4 20.03	W 103 34 30.93
	20100.00	90.00	179.53	12375.00	7669.30	-7672.36	-341.04	0.00	390739.50	776151.08	N 32 4 19.04	W 103 34 30.93
	20200.00	90.00	179.53	12375.00	7769.30	-7772.36	-340.22	0.00	390639.50	776151.90	N 32 4 18.05	W 103 34 30.93
	20300.00	90.00	179.53	12375.00	7869.30	-7872.35	-339.40	0.00	390539.51	776152.72	N 32 4 17.06	W 103 34 30.93
	20400.00	90.00	179.53	12375.00	7969.30	-7972.35	-338.58	0.00	390439.51	776153.54	N 32 4 16.07	W 103 34 30.93
	20500.00	90.00	179.53	12375.00	8069.30	-8072.35	-337.75	0.00	390339.52	776154.37	N 32 4 15.08	W 103 34 30.92
	20600.00	90.00	179.53	12375.00	8169.30	-8172.34	-336.93	0.00	390239.53	776155.19	N 32 4 14.09	W 103 34 30.92
	20700.00	90.00	179.53	12375.00	8269.30	-8272.34	-336.11	0.00	390139.53	776156.01	N 32 4 13.10	W 103 34 30.92
	20800.00	90.00	179.53	12375.00	8369.30	-8372.34	-335.29	0.00	390039.54	776156.83	N 32 4 12.11	W 103 34 30.92
	20900.00	90.00	179.53	12375.00	8469.30	-8472.33	-334.47	0.00	389939.55	776157.65	N 32 4 11.12	W 103 34 30.92
	21000.00	90.00	179.53	12375.00	8569.30	-8572.33	-333.64	0.00	389839.55	776158.48	N 32 4 10.13	W 103 34 30.92
	21100.00	90.00	179.53	12375.00	8669.30	-8672.33	-332.82	0.00	389739.56	776159.30	N 32 4 9.14	W 103 34 30.92
	21200.00	90.00	179.53	12375.00	8769.30	-8772.32	-332.00	0.00	389639.57	776160.12	N 32 4 8.15	W 103 34 30.91
	21300.00	90.00	179.53	12375.00	8869.30	-8872.32	-331.18	0.00	389539.57	776160.94	N 32 4 7.16	W 103 34 30.91
	21400.00	90.00	179.53	12375.00	8969.30	-8972.32	-330.35	0.00	389439.58	776161.76	N 32 4 6.17	W 103 34 30.91
	21500.00	90.00	179.53	12375.00	9069.30	-9072.31	-329.53	0.00	389339.58	776162.59	N 32 4 5.18	W 103 34 30.91
	21600.00	90.00	179.53	12375.00	9169.30	-9172.31	-328.71	0.00	389239.59	776163.41	N 32 4 4.20	W 103 34 30.91
	21700.00	90.00	179.53	12375.00	9269.30	-9272.31	-327.89	0.00	389139.60	776164.23	N 32 4 3.21	W 103 34 30.91
	21800.00	90.00	179.53	12375.00	9369.30	-9372.30	-327.07	0.00	389039.60	776165.05	N 32 4 2.22	W 103 34 30.91
	21900.00	90.00	179.53	12375.00	9469.30	-9472.30	-326.24	0.00	388939.61	776165.88	N 32 4 1.23	W 103 34 30.90
	22000.00	90.00	179.53	12375.00	9569.30	-9572.30	-325.42	0.00	388839.62	776166.70	N 32 4 0.24	W 103 34 30.90
	22100.00	90.00	179.53	1237								



Grid



True      Mag

	<b>CONTROLLED</b>
Plan ref	Cinnarex Road H114 13-4 Unit #20H Road RM 04Apr20
Drawing ref	
Copy number	of 5
Date	07-Apr-2020


Grid North

Tot Corr (M->G 6.141")

Mag Dec (6.545")

Grid Conv (0.403")

1	Client	
2	Client	
3	Office	
4	Office	
Copy number		for





## Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20 Proposal Geodetic Report (Non-Def Plan)



**Report Date:** April 07, 2020 - 04:40 PM  
**Client:** Cimarex Energy  
**Field:** NM Lea County (NAD 83)  
**Structure / Slot:** Cimarex Red Hills 33-4 Unit #20H / New Slot  
**Well:** Red Hills 33-4 Unit #20H  
**Borehole:** Red Hills 33-4 Unit #20H  
**UWI / API#:** Unknown / Unknown  
**Survey Name:** Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20  
**Survey Date:** April 06, 2020  
**Tort / AHD / DDI / ERD Ratio:** 106.528 ° / 10737.586 ft / 6.317 / 0.868  
**Coordinate Reference System:** NAD83 New Mexico State Plane, Eastern Zone, US Feet  
**Location Lat / Long:** N 32° 5' 34.93347", W 103° 34' 26.33825"  
**Location Grid N/E Y/X:** N 398411.630 ftUS, E 776492.110 ftUS  
**CRS Grid Convergence Angle:** 0.4035 °  
**Grid Scale Factor:** 0.99997243  
**Version / Patch:** 2.10.787.0

**Survey / DLS Computation:** Minimum Curvature / Lubinski  
**Vertical Section Azimuth:** 179.529 ° (Grid North)  
**Vertical Section Origin:** 0.000 ft, 0.000 ft  
**TVD Reference Datum:** RKB  
**TVD Reference Elevation:** 3373.600 ft above MSL  
**Seabed / Ground Elevation:** 3347.600 ft above MSL  
**Magnetic Declination:** 6.545 °  
**Total Gravity Field Strength:** 998.4369mgn (9.80665 Based)  
**Gravity Model:** GARM  
**Total Magnetic Field Strength:** 47667.087 nT  
**Magnetic Dip Angle:** 59.684 °  
**Declination Date:** April 06, 2020  
**Magnetic Declination Model:** HDGM 2020  
**North Reference:** Grid North  
**Grid Convergence Used:** 0.4035 °  
**Total Corr Mag North->Grid North:** 6.1411 °  
**Local Coord Referenced To:** Well Head

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [453' FNL, 1620' FEL]	0.00	0.00	181.84	0.00	0.00	0.00	0.00	N/A	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
Nudge 2"/100'	2200.00	0.00	302.00	2200.00	0.00	0.00	0.00	0.00	398411.63	776492.11	N 32 5 34.93	W 103 34 26.34
Hold Nudge	2613.20	8.26	302.00	2611.77	-15.97	15.76	-25.23	2.00	398427.39	776466.88	N 32 5 35.09	W 103 34 26.63
Drop to Vertical	5531.74	8.26	302.00	5500.00	-241.19	238.06	-380.98	0.00	398649.68	776111.14	N 32 5 37.32	W 103 34 30.75
2"/100' DLS	5944.94	0.00	302.00	5911.77	-257.16	253.83	-406.21	2.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
Hold Vertical	5944.94	0.00	302.00	5911.77	-257.16	253.83	-406.21	2.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
KOP - Build	11898.16	0.00	302.00	11865.00	-257.16	253.83	-406.21	0.00	398665.45	776085.92	N 32 5 37.47	W 103 34 31.04
12"/100' DLS	12523.16	75.00	179.53	12326.19	96.73	-100.05	-403.30	12.00	398311.58	776088.83	N 32 5 33.97	W 103 34 31.03
Build 4"/100'	12523.16	75.00	179.53	12326.19	96.73	-100.05	-403.30	12.00	398311.58	776088.83	N 32 5 33.97	W 103 34 31.03
DLS	12898.16	90.00	179.53	12375.00	467.46	-470.77	-400.25	4.00	397940.87	776091.87	N 32 5 30.30	W 103 34 31.03
Landing Point	12898.16	90.00	179.53	12375.00	467.46	-470.77	-400.25	4.00	397940.87	776091.87	N 32 5 30.30	W 103 34 31.03
Cimarex Red Hills 33-4 Unit #20H - PBHL [100' FSL, 2024' FEL]	22432.14	90.00	179.53	12375.00	10001.44	-10004.43	-321.87	0.00	388407.50	776170.25	N 32 3 55.96	W 103 34 30.90

**Survey Type:** Non-Def Plan

**Survey Error Model:** ISCWSA Rev 0 \*\*\* 3-D 95.000% Confidence 2.7955 sigma  
**Survey Program:**

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.000	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS-Depth Only	Red Hills 33-4 Unit #20H / Cimarex Red Hills 33-4 Unit #20H Rev0 RM 06Apr20
	1	26.000	22432.143	1/100.000	17.500	13.375		NAL_MWD_IFR1+MS	Red Hills 33-4 Unit #20H / Cimarex Red Hills 33-4 Unit #20H

**1. Geological Formations**

TVD of target 12,375

Pilot Hole TD N/A

MD at TD 22,432

Deepest expected fresh water

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Rustler	920	Useable Water	
Top of Salt	1334	N/A	
Base of Salt	4892	N/A	
Bell Canyon	4919	N/A	
Cherry Canyon	6019	N/A	
Brushy Canyon	7578	N/A	
Bone Spring	9047	Hydrocarbons	
Upper Avalon Shale	9338	Hydrocarbons	
1st Bone Spring	10030	Hydrocarbons	
2nd Bone Spring	10230	Hydrocarbons	
3rd Bone Spring	11017	Hydrocarbons	
Wolfcamp	12128	Hydrocarbons	

**2. Casing Program**

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Request Variance for 5-1/2" x 7-5/8" annular clearance. The portion that does not meet clearance will not be cemented

## Cimarex Energy Co., Red Hills Unit 20H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	Y
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	N

## Cimarex Energy Co., Red Hills Unit 20H

## 3. Cementing Program

Casing	# Sk	Wt. lb/gal	Yld ft <sup>3</sup> /sack	H <sub>2</sub> O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	325	13.50	1.72	9.15	15.5	Lead: Class C + Bentonite
	156	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Intermediate Stage 1	591	10.30	3.64	22.18		Lead: Tuned Light + LCM
	198	14.80	1.36	6.57	9.5	Tail: Class C + Retarder
Intermediate Stage 2	786	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
Production	1364	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

DV tool with possible annular casing packer as needed is proposed at a depth of +/- 4,850'.

Casing String	TOC	% Excess
Surface	0	42
Intermediate Stage 1	4850	47
Intermediate Stage 2	0	40
Production	12323	25

Cimarex request the ability to perform casing integrity tests after plug bump of cement job.

**4. Pressure Control Equipment**

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
BOP installed and tested before drilling which hole?	Size	Min Required WP	Type		Tested To
9 7/8	13 5/8	5M	Annular	X	5M
			Blind Ram		
			Pipe Ram	X	
			Double Ram	X	
			Other		
6 3/4	13 5/8	10M	Annular	X	50% of working pressure
			Blind Ram		10M
			Pipe Ram	X	
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

X	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?



## Cimarex Energy Co., Red Hills Unit 20H

**5. Mud Program**

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 970'	Fresh Water	7.83 - 8.33	28	N/C
970' to 12523'	Brine Diesel Emulsion	8.50 - 9.00	30-35	N/C
12523' to 22432'	OBM	12.00 - 12.50	50-70	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

The Brine Emulsion is completely saturated brine fluid that ties diesel into itself to lower the weight of the fluid. The drilling fluid is completely salt saturated.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---------------------------------------------------------	-----------------------------

**6. Logging and Testing Procedures**

Logging, Coring and Testing	
	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test?
	Coring?

Additional Logs Planned	Interval
-------------------------	----------

**7. Drilling Conditions**

Condition	
BH Pressure at deepest TVD	8043 psi
Abnormal Temperature	No

Hydrogen Sulfide (H<sub>2</sub>S) monitors will be installed prior to drilling out the surface shoe. If H<sub>2</sub>S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

	H <sub>2</sub> S is present
	H <sub>2</sub> S plan is attached

**8. Other Facets of Operation****9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 10-3/4" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 10000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 10000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 10000 psi.

All casing strings will be tested as per Onshore Order No.2 to at least 0.22 psi/ft or 1,500 whichever is greater and not to exceed 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.



District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
811 S. First St., Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy, Minerals and Natural Resources Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Submit Original  
to Appropriate  
District Office

## GAS CAPTURE PLAN

Date: 08/24/20

☒ Original Operator & OGRID No.: Cimarex Energy Co of Colorado- 162683  
☐ Amended - Reason for Amendment: \_\_\_\_\_

This Gas Capture Plan outlines actions to be taken by the Operator to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

*Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).*

### Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Red Hills Unit 20H	Pending	33-25S-33E	453'FNL & 1620' FEL	4000		

### Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if gas transporter system is in place. The gas produced from production facility is dedicated to Enlink and will be connected to Enlink low/high pressure gathering system located in Lea County, New Mexico. It will require (no additional feet) of pipeline to connect the facility to low/high pressure gathering system. Cimarex provides (periodically) to Enlink a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Cimarex and Enlink have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at EnLink Lobo Processing Plant located in Sec 30, BLk 29 Loving Co, TX. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

### Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on Enlink system at that time. Based on current information, it is Cimarex belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

### Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines




Red Hills Unit 20H

CACTUS FOR SERVICE  
WEARBUSHING  
IN CASING HEAD &  
CASING SPOOL

LEA CO., NM


Multi-bowl Wellhead Diagram



Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
14 3/4	0	970	970	10-3/4"	40.50	J-55	BT&C	3.76	7.45	16.01
9 7/8	0	12523	12326	7-5/8"	29.70	L-80	BT&C	2.48	1.19	1.81
6 3/4	0	12532	12532	5-1/2"	23.00	L-80	LT&C	1.37	1.21	2.20
6 3/4	12532	22432	12375	5"	18.00	P-110	BT&C	1.67	1.69	99.99
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet



Co-Flex Hose  
**Red Hills Unit W2E2-E**  
Cimarex Energy Co. 33-25S-  
33E  
Lea Co., NM



Co-  
Flex Hose Hydrostatic Test  
Red Hills Unit W2E2-E  
Cimarex Energy Co.  
33-25S-33E  
Lea Co., NM



## Midwest Hose & Specialty, Inc.

INTERNAL HYDROSTATIC TEST REPORT			
Customer:		P.O. Number:	
Oderco Inc		odyd-271	
HOSE SPECIFICATIONS			
Type: Stainless Steel Armor Choke & Kill Hose		Hose Length: 45'ft.	
I.D. 4 INCHES		O.D. 9 INCHES	
WORKING PRESSURE	TEST PRESSURE	BURST PRESSURE	
10,000 PSI	15,000 PSI	0 PSI	
COUPLINGS			
Stem Part No.		Ferrule No.	
OKC OKC		OKC OKC	
Type of Coupling: Swage-It			
PROCEDURE			
<u>Hose assembly pressure tested with water at ambient temperature.</u>			
TIME HELD AT TEST PRESSURE		ACTUAL BURST PRESSURE:	
15 MIN.		0 PSI	
Hose Assembly Serial Number: 79793		Hose Serial Number: OKC	
Comments:			
Date:	Tested:	Approved:	
3/8/2011	<i>A. Joins</i>	<i>Kevin</i>	



Midwest Hose  
& Specialty, Inc.


# Internal Hydrostatic Test Graph

March 3, 2011

Customer: Houston

Pick Ticket #: 94260

Hose Specifications		Verification	
<u>Hose Type</u>	<u>Length</u>	<u>Type of Fitting</u>	<u>Coupling Method</u>
C & K	45'	41/16 10K	Swage
<u>I.D.</u>	<u>O.D.</u>	<u>Die Size</u>	<u>Final O.D.</u>
4"	6.09"	6.38"	6.25"
<u>Working Pressure</u>	<u>Burst Pressure</u>	<u>Hose Serial #</u>	<u>Hose Assembly Serial #</u>
10000 PSI	Standard Safety Multiplier Applies	5544	79793



<u>Test Pressure</u>	<u>Time Held at Test Pressure</u>	<u>Actual Burst Pressure</u>	<u>Peak Pressure</u>
15000 PSI	11 Minutes		15483 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.


Tested By: Zac Mcconnell

Approved By: Kim Thomas

Co-  
Flex Hose Hydrostatic Test  
t Red Hills Unit W2E2-E  
Cimarex Energy Co.  
33-25S-33E  
Lea Co., NM



Co-Flex Hose  
Red Hills Unit W2E2-E  
Cimarex Energy Co. 33-25S-  
33E  
Lea Co., NM



## Midwest Hose & Specialty, Inc.

### Certificate of Conformity

Customer:

DEM

PO

ODYD-271

### SPECIFICATIONS

Sales Order

79793

Dated:

3/8/2011

We hereby certify that the material supplied  
for the referenced purchase order to be true  
according to the requirements of the purchase  
order and current industry standards

Supplier:  
Midwest Hose & Specialty, Inc.  
10640 Tanner Road  
Houston, Texas 77041

Comments:

Approved:

*James Garcia*

Date:

3/8/2011





Midwest Hose  
& Specialty, Inc.

Co-Flex Hose  
Red Hills Unit W2E2-E  
Cimarex Energy Co.  
33-25S-33E  
Lea Co., NM

## Specification Sheet Choke & Kill Hose

The Midwest Hose & Specialty Choke & Kill hose is manufactured with only premium components. The reinforcement cables, inner liner and cover are made of the highest quality material to handle the tough drilling applications of today's industry. The end connections are available with API flanges, API male threads, hubs, hammer unions or other special fittings upon request. Hose assembly is manufactured to API 7K. This assembly is wrapped with fire resistant vermiculite coated fiberglass insulation, rated at 2000 degrees with stainless steel armor cover.

<b>Working Pressure:</b>	5,000 or 10,000 psi working pressure
<b>Test Pressure:</b>	10,000 or 15,000 psi test pressure
<b>Reinforcement:</b>	Multiple steel cables
<b>Cover:</b>	Stainless Steel Armor
<b>Inner Tube:</b>	Petroleum resistant, Abrasion resistant
<b>End Fitting:</b>	API flanges, API male threads, threaded or butt weld hammer unions, unbolt and other special connections
<b>Maximum Length:</b>	110 Feet
<b>ID:</b>	2-1/2", 3", 3-1/2", 4"
<b>Operating Temperature:</b>	-22 deg F to +180 deg F (-30 deg C to +82 deg C)

P.O. Box 96558 - 1421 S.E. 29<sup>th</sup> St. Oklahoma City, OK 73143 \* (405) 670-6718 \* Fax: (405) 670-6816



---

# Cimarex 10M Well Control Plan

---

Version 1.0

---

BOPE Preventer Utilization

The table below displays all BHA components, drill pipe, casing, or open hole that could be present during a required shut in and the associated preventer component that would provide a barrier to flow. It is specific to the hole section that requires a 10M system. The mud system being utilized in the hole will always assumed to be the first barrier to flow. The below table, combined with the mud program, documents that two barriers to flow can be maintained at all times, independent of the rating of the annular preventer.

Drill String Element	OD	Preventer	RWP
4" Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4" HWDP Drillpipe	4"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
4.5" HWDP Drillpipe	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Drill Collars (including non-magnetic)	4.75-5.25"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
Production Casing	4.5"	Lower Ram 3 1/2" - 5 1/2" VBR* Upper Ram 3 1/2" - 5 1/2" VBR*	10M
ALL	0-13 5/8"	Annular	5M
Open Hole		Blind Rams	10M

\*VBR – Variable Bore Ram

Well Control Procedures

Proper well control response is highly specific to current well conditions and must be adapted based on environment as needed. The procedures below are given in “common” operating conditions to cover the basic and most necessary operations required during the wellbore construction. These include drilling ahead, tripping pipe, tripping BHA, running casing, and pipe out of the hole/open hole. In some of the procedures below, there will be a switch of control from the lesser RWP annular to the appropriate 10M RWP ram. The pressure at which this is done is variable based on overall well conditions that must be evaluated situationally. The pressure that control is switched may be equal to or less than the RWP but at no time will the pressure on the annular preventer exceed the RWP of the annular. The annular will be tested to 5,000 psi. This will be the RWP of the annular preventer.

Shutting In While Drilling

1. Sound alarm to alert crew
2. Space out drill string
3. Shut down pumps
4. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

9. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

***Shutting In While Tripping***

1. Sound alarm and alert crew
2. Install open, full open safety valve and close valve
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

***Shutting In While Running Casing***

1. Sound alarm and alert crew
2. Install circulating swedge. Close high pressure, low torque valves.
3. Shut in uppermost BOPE preventer (typically the annular preventer) and open HCR.
4. Verify well is shut-in and flow has stopped
5. Notify supervisory personnel
6. Record data (SIDP, SICP, Pit Gain, and Time)
7. Hold Pre-job safety meeting and discuss kill procedure
8. If pressure is anticipated to climb to the RWP of the annular preventer during kill procedure, swap control of the well to the upper pipe ram

***Shutting in while out of hole***

1. Sound alarm
2. Shut-in well: close blind rams
3. Verify well is shut-in and monitor pressures
4. Notify supervisory personnel
5. Record data (SIDP, SICP, Pit Gain, and Time)
6. Hold Pre-job safety meeting and discuss kill procedure

***Shutting in prior to pulling BHA through stack***

1. Prior to pulling last joint of drill pipe thru the stack space out and check flow. If flowing see steps below.
2. Sound alarm and alert crew
3. Install open, full open safety valve and close valve
4. Shut in upper pipe ram and open HCR.

5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

***Shutting in while BHA is in the stack and ram preventer and combo immediately available***

1. Sound alarm and alert crew
2. Stab Crossover and install open, full open safety valve and close valve
3. Space out drill string with upset just beneath the compatible pipe ram.
4. Shut in upper compatible pipe ram and open HCR.
5. Verify well is shut-in and flow has stopped
6. Notify supervisory personnel
7. Record data (SIDP, SICP, Pit Gain, and Time)
8. Hold pre-job safety meeting and discuss kill procedure

***Shutting in while BHA is in the stack and no ram preventer or combo immediately available***

1. Sound alarm and alert crew
2. If possible pick up high enough, to pull string clear and follow "Open Hole" scenario
3. If not possible to pick up high enough:
  1. Stab Crossover, make up one joint/stand of drill pipe, and install open, full open safety valve and close valve
4. Space out drill string with upset just beneath the compatible pipe ram.
5. Shut in upper compatible pipe ram and open HCR.
6. Verify well is shut-in and flow has stopped
7. Notify supervisory personnel
8. Record data (SIDP, SICP, Pit Gain, and Time)
9. Hold pre-job safety meeting and discuss kill procedure



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## SUPO Data Report

07/31/2023

APD ID: 10400060223

Submission Date: 04/21/2021

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 20H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data  
reflects the most  
recent changes

[Show Final Text](#)

### Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

Red\_Hills\_Unit\_W2E2\_E\_Existing\_Access\_Road\_20200812095334.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? YES

#### ROW ID(s)

ID:

Do the existing roads need to be improved? NO

Existing Road Improvement Description:

Existing Road Improvement Attachment:

### Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

### Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H

Red\_Hills\_Unit\_W2E2\_\_E\_One\_Mile\_Radius\_20200812095543.pdf

**Section 4 - Location of Existing and/or Proposed Production Facilities****Submit or defer a Proposed Production Facilities plan?** SUBMIT

**Production Facilities description:** 2- 550 X 450 pads were staked with the BLM for construction and use as a central tank batteries (CTB), please see Exhibit F. Batteries have been previously approved in the Red Hill Unit 99H APD. Roads have all been previously approved in the Red Hills Unit 99H APD. Power ROW has been submitted. Bulklines have been previously approved in the Red hills Unit 99H APD.

**Production Facilities map:**

Red\_Hills\_Unit\_\_Zone\_1\_West\_CTB\_Btty\_Layout\_20200708120443.pdf

Red\_Hills\_Unit\_\_Zone\_2\_West\_CTB\_Btty\_Layout\_20200708120436.pdf

Red\_Hills\_Unit\_20H\_SUPO\_20210820082757.pdf

**Section 5 - Location and Types of Water Supply****Water Source Table****Water source type:** MUNICIPAL

**Water source use type:** SURFACE CASING  
INTERMEDIATE/PRODUCTION CASING

**Source latitude:** **Source longitude:****Source datum:****Water source permit type:** WATER RIGHT**Permit Number:****Water source transport method:** TRUCKING**Source land ownership:** FEDERAL**Source transportation land ownership:** FEDERAL**Water source volume (barrels):** 5000**Source volume (acre-feet):** 0.64446548**Source volume (gal):** 210000**Water source and transportation**

Red\_Hills\_Unit\_W2E2\_\_E\_Drilling\_Source\_Water\_20200812095811.pdf

**Water source comments:****New water well?** N

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**New Water Well Info****Well latitude:****Well Longitude:****Well datum:****Well target aquifer:****Est. depth to top of aquifer(ft):****Est thickness of aquifer:****Aquifer comments:****Aquifer documentation:****Well depth (ft):****Well casing type:****Well casing outside diameter (in.):****Well casing inside diameter (in.):****New water well casing?****Used casing source:****Drilling method:****Drill material:****Grout material:****Grout depth:****Casing length (ft.):****Casing top depth (ft.):****Well Production type:****Completion Method:****Water well additional information:****State appropriation permit:****Additional information attachment:****Section 6 - Construction Materials****Using any construction materials:** YES**Construction Materials description:** Caliche will be obtained from the actual well site if available. If not available onsite caliche will be obtained for a pit located in Sec 6, 26S, 34E, NWNE.**Construction Materials source location****Section 7 - Methods for Handling****Waste type:** DRILLING**Waste content description:** Drilling Fluids, drill cuttings, water and other waste produced from the well during drilling operations**Amount of waste:** 15000 barrels**Waste disposal frequency :** Weekly**Safe containment description:** N/A**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** COMMERCIAL**Disposal type description:****Disposal location description:** Haul to R360 Environmental Solutions, 4507 Carlsbad Hwy, Hobbs, NM 88240



**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Waste type:** SEWAGE**Waste content description:** Human Waste**Amount of waste:** 300 gallons**Waste disposal frequency :** Weekly**Safe containment description:** Waste will be properly contained and disposed of properly at a state approved disposal facility.**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** PRIVATE**Disposal type description:****Disposal location description:** A licensed 3rd party contractor will be used to haul and dispose human waste to City of Toyah TX waste water facility.**Waste type:** GARBAGE**Waste content description:** Garbage and trash produced during drilling and completion operations**Amount of waste:** 32500 pounds**Waste disposal frequency :** Weekly**Safe containment description:** N/A**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** COMMERCIAL**Disposal type description:****Disposal location description:** A licensed 3rd party hauls trash to Lea County Landfill

### Reserve Pit

**Reserve Pit being used?** NO**Temporary disposal of produced water into reserve pit?** NO**Reserve pit length (ft.)**      **Reserve pit width (ft.)****Reserve pit depth (ft.)**      **Reserve pit volume (cu. yd.)****Is at least 50% of the reserve pit in cut?****Reserve pit liner****Reserve pit liner specifications and installation description**

### Cuttings Area

**Cuttings Area being used?** NO**Are you storing cuttings on location?** N

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Description of cuttings location****Cuttings area length (ft.)****Cuttings area width (ft.)****Cuttings area depth (ft.)****Cuttings area volume (cu. yd.)****Is at least 50% of the cuttings area in cut?****WCuttings area liner****Cuttings area liner specifications and installation description****Section 8 - Ancillary****Are you requesting any Ancillary Facilities?:** N**Ancillary Facilities****Comments:****Section 9 - Well Site****Well Site Layout Diagram:**

Red\_Hills\_Unit\_pad\_3\_W2E2\_E\_Wellsite\_Pad\_Info\_20200812100947.docx

Red\_Hills\_Unit\_20H\_Wellsite\_Layout\_20210820083212.pdf

**Comments:** Well Pad is 500' by 560' with a 100' x 250' satellite pad on the south. This well pad has wells Red Hills Unit 19H 20H 62H 63H 64H 65H 66H 67H 68H 69H 70H 71H 72H 73H**Section 10 - Plans for Surface****Type of disturbance:** New Surface Disturbance**Multiple Well Pad Name:** Red Hills Unit**Multiple Well Pad Number:** W2E2-E**Recontouring**

Red\_Hills\_Unit\_W2E2\_E\_Interim\_Reclamation\_20210820084342.pdf

**Drainage/Erosion control construction:** To control and prevent potentially contaminated precipitation from leaving the pad site, a perimeter berm and settlement pond will be installed. Contaminated water will be removed from pond, stored in waste tanks, and disposed of at a state approved facility. Standing water or puddles will not be allowed. Drainage ditches would be established and maintained on the pad and along access roads to divert water away from operations. Natural drainage areas disturbed during construction would be re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured to near original condition prior to construction. Erosion Control Best Management Practices would be used where necessary and consist of seeding, fiber rolls, water bars, silt fences, and temporary diversion dikes. Areas disturbed during construction that are no longer needed for operations would be obliterated, re-contoured, and reclaimed to near original condition to re-establish natural drainage.

**Drainage/Erosion control reclamation:** All disturbed and re-contoured areas would be reseeded according to specifications. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage.

Operator Name: CIMAREX ENERGY COMPANY

Well Name: RED HILLS UNIT

Well Number: 20H

<b>Well pad proposed disturbance (acres):</b> 6.69	<b>Well pad interim reclamation (acres):</b> 3	<b>Well pad long term disturbance (acres):</b> 3.69
<b>Road proposed disturbance (acres):</b> 4.034	<b>Road interim reclamation (acres):</b> 0	<b>Road long term disturbance (acres):</b> 4.034
<b>Powerline proposed disturbance (acres):</b> 0.12	<b>Powerline interim reclamation (acres):</b> 0	<b>Powerline long term disturbance (acres):</b> 0.12
<b>Pipeline proposed disturbance (acres):</b> 7.028	<b>Pipeline interim reclamation (acres):</b> 0	<b>Pipeline long term disturbance (acres):</b> 7.028
<b>Other proposed disturbance (acres):</b> 0	<b>Other interim reclamation (acres):</b> 0	<b>Other long term disturbance (acres):</b> 0
<b>Total proposed disturbance:</b> 17.872	<b>Total interim reclamation:</b> 3	<b>Total long term disturbance:</b> 14.872

**Disturbance Comments:**

**Reconstruction method:** After well plugging, all disturbed areas would be returned to the original contour or a contour that blends with the surrounding landform including roads unless the surface owner requests that they be left intact. In consultation with the surface owners it will be determined if any gravel or similar materials used to reinforce an area are to be removed, buried, or left in place during final reclamation. Salvaged topsoil, if any, would be re-spread evenly over the surfaces to be re-vegetated. As necessary, the soil surface would be prepared to provide a seedbed for re-establishment of desirable vegetation. Site preparation may include gouging, scarifying, dozer track-walking, mulching, or fertilizing. Reclamation, Re-vegetation, and Drainage: All disturbed and re-contoured areas would be reseeded using techniques outlined under Phase I and II of this plan or as specified by the land owner. Approved seed mixtures would be certified weed free and consist of grasses, forbs, or shrubs similar to the surrounding area. Compacted soil areas may need to be obliterated and reclaimed to near natural conditions by re-contouring all slopes to facilitate and re-establish natural drainage.

**Topsoil redistribution:** The original stock piled topsoil, if any, will be spread evenly over the areas being reclaimed and the original landform will be restored for all disturbed areas including well pad, production facilities, roads, pipelines, and power line corridors as close as possible to the original topography. The location will then be seeded.

**Soil treatment:** The soil surface would be prepared to provide a seedbed for reestablishment of desirable vegetation. Establish control of erosion and invasion of non-native plants to reestablish plant community.

**Existing Vegetation at the well pad:** N/A

**Existing Vegetation at the well pad**

**Existing Vegetation Community at the road:** N/A

**Existing Vegetation Community at the road**

**Existing Vegetation Community at the pipeline:** N/A

**Existing Vegetation Community at the pipeline**

**Existing Vegetation Community at other disturbances:** N/A

**Existing Vegetation Community at other disturbances**

**Non native seed used?** N

**Non native seed description:**

**Seedling transplant description:**

**Will seedlings be transplanted for this project?** N

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Seedling transplant description****Will seed be harvested for use in site reclamation?** N**Seed harvest description:****Seed harvest description attachment:****Seed****Seed Table****Seed Summary****Total pounds/Acre:****Seed Type****Pounds/Acre****Seed reclamation****Operator Contact/Responsible Official****First Name:** Amithy**Last Name:** Crawford**Phone:** (432)620-1909**Email:** acrawford@cimarex.com**Seedbed prep:****Seed BMP:****Seed method:****Existing invasive species?** N**Existing invasive species treatment description:****Existing invasive species treatment****Weed treatment plan description:** N/A**Weed treatment plan****Monitoring plan description:** N/A**Monitoring plan****Success standards:** N/A**Pit closure description:** N/A**Pit closure attachment:****Section 11 - Surface**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Disturbance type:** WELL PAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Surface use plan certification:** YES

**Surface use plan certification document:**

**Surface access agreement or bond:** AGREEMENT

**Surface Access Agreement Need description:** NA

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

**Disturbance type:** PIPELINE

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Surface use plan certification:** YES

**Surface use plan certification document:**

**Surface access agreement or bond:** AGREEMENT

**Surface Access Agreement Need description:** NA

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

**Disturbance type:** TRANSMISSION LINE

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Surface use plan certification:** YES

**Surface use plan certification document:**

**Surface access agreement or bond:** AGREEMENT

**Surface Access Agreement Need description:** NA

**Surface Access Bond BLM or Forest Service:**

**BLM Surface Access Bond number:**

**USFS Surface access bond number:**

**Disturbance type:** NEW ACCESS ROAD

**Describe:**

**Surface Owner:** BUREAU OF LAND MANAGEMENT,PRIVATE OWNERSHIP

**Other surface owner description:**

**BIA Local Office:**

**BOR Local Office:**

**COE Local Office:**

**DOD Local Office:**

**NPS Local Office:**

**State Local Office:**

**Military Local Office:**

**USFWS Local Office:**

**Other Local Office:**

**USFS Region:**

**USFS Forest/Grassland:**

**USFS Ranger District:**

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Surface use plan certification:** YES**Surface use plan certification document:****Surface access agreement or bond:** AGREEMENT**Surface Access Agreement Need description:** NA**Surface Access Bond BLM or Forest Service:****BLM Surface Access Bond number:****USFS Surface access bond number:**

### Section 12 - Other

**Right of Way needed?** Y**Use APD as ROW?** Y**ROW Type(s):** 281001 ROW - ROADS,288100 ROW – O&G Pipeline,289001 ROW- O&G Well Pad,FLPMA (Powerline)


### ROW

**SUPO Additional Information:****Use a previously conducted onsite?** Y**Previous Onsite information:** Location was moved 18 ft. south due to pipeline to north. V-Door West. Top soil East. Interim reclamation: All sides. Access road at NE corner, west, to the proposed #3 Super Pad (Following existing pipeline). Pad size is 500' (E/W) x 560' (N/S).

### Other SUPO





**LEGEND:**

**PROPOSED LOCATION**




**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33-4 W2E2-E**  
NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	A.H., A.G.	03-27-18	SCALE
DRAWN BY	R.J.	04-04-18	1 : 100,000
<b>PUBLIC ACCESS ROAD MAP</b>		<b>EXHIBIT B</b>	

**LEGEND:**

● EXISTING WELLS


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33-4 W2E2-E**  
**NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., A.G.	03-27-18	SCALE
DRAWN BY	R.J.	04-04-18	1 : 36,000
<b>1 MILE RADIUS MAP</b>			<b>EXHIBIT E</b>



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

**NOTES:**

- Contours shown at 2' intervals.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
- Topsoil stockpile to be seeded in place prior to reclamation.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 ONE 1 WEST CTB**  
**NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	S.F.	06-02-17	1" = 80'
<b>LOCATION LAYOUT</b>		<b>EXHIBIT F</b>	



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,140 Cu. Yds.
REMAINING LOCATION	7,910 Cu. Yds.
<b>TOTAL CUT</b>	<b>11,050 Cu. Yds.</b>
<b>FILL</b>	<b>7,910 Cu. Yds.</b>
EXCESS MATERIAL	3,140 Cu. Yds.
TOPSOIL	3,140 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.301
FLOW LINE CONNECTION AREA DISTURBANCE	NA	±0.436
30' WIDE ACCESS ROAD "A" R-O-W DISTURBANCE	±79.80'	±0.055
30' WIDE ACCESS ROAD "B" R-O-W DISTURBANCE	±79.92'	±0.055
30' WIDE POWER LINE R-O-W DISTURBANCE	±109.91'	±0.076
<b>TOTAL</b>		<b>±6.868</b>

REV: 1 08-24-17 C.I. (RE-ROUTE)

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**


**RED HILLS UNIT 33 ONE 1 WEST CTB**  
**NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	S.F.	06-02-17	AS SHOWN
<b>TYPICAL CROSS SECTIONS</b>		<b>EXHIBIT F</b>	





REV: 1 08-24-17 C.I. (ACCESS ROAD RE-ROUTE, FLOW LINE CONNECTION AREA MOVE)

**NOTES:**

- Underground utilities shown on this sheet are for visualization purposes only, actual locations to be determined prior to construction.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 □ ONE 1 WEST CTB**  
**NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	S.F.	06-02-17	1" = 100'
ARCHAEOLOGICAL SURVEY BOUNDARY			<b>EXHIBIT F</b>




FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION

BEGINNING AT A POINT IN THE NW 1/4 NW 1/4 OF SECTION 33, T25S, R33E, N.M.P.M., WHICH BEARS S54°11'34"E 1481.40' FROM THE NORTHWEST CORNER OF SAID SECTION 33, THENCE N89°58'17"E 180.00'; THENCE S00°01'43"E 50.00'; THENCE S89°58'18"W 130.00'; THENCE S00°01'43"E 200.00'; THENCE S89°58'17"W 50.00'; THENCE N00°01'43"W 250.00' TO THE POINT OF BEGINNING. CONTAINS 0.436 ACRES MORE OR LESS.



CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 61736-A

Sheet 1 of 2

REV: 1 08-24-17 C.I. (FLOW LINE CONNECTION SUA MOVE)

NOTES:  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



CIMAREX ENERGY CO.

RED HILLS UNIT 33 □ ONE 1 WEST CTB  
SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	B.D.H.	06-06-17	1" = 1000'
FLOW LINE CONNECTION EXHIBIT F			



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING AT THE INTERSECTION OF J-1/ORLA ROAD AND PIPELINE ROAD TO THE EAST (LOCATED AT NAD83 LATITUDE N32.064964° AND LONGITUDE W103.674262°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY, THEN NORTHWESTERLY DIRECTION APPROXIMATELY 2.1 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE RED HILLS UNIT E2E2; FOLLOW ROAD FLAGS IN AN SOUTHEASTERLY, THEN EASTERLY DIRECTION FOR APPROXIMATELY 629' TO THE BEGINNING OF THE PROPOSED ACCESS "A" TO THE NORTH; FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 80' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND PIPELINE ROAD TO THE EAST (LOCATED AT NAD 83 LATITUDE N32.064964° AND LONGITUDE W103.674262°), TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 7.2 MILES.

REV: 01 08-24-17 L.W. (ROAD RE-ROUTE)

### CIMAREX ENERGY CO.

RED HILLS UNIT 33 □ ONE 1 WEST CTB  
NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO


### UELS, LLC

Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



SURVEYED BY	C.J., A.H.	05-05-17	
DRAWN BY	D	05-26-17	
ROAD DESCRIPTION		EXHIBIT F	



**LEGEND:**

**PROPOSED LOCATION**




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 ONE 1 WEST CTB**  
**NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	C.J., A.H.	05-05-17	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.	05-26-17	1 : 100,000
<b>PUBLIC ACCESS ROAD MAP</b>		<b>EXHIBIT B</b>	

**NOTES:**

- Contours shown at 2' intervals.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
- Topsoil stockpile to be seeded in place prior to reclamation.


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 ZONE 2 WEST CTB**  
**E 1/2 NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	S.F.	06-02-17	1" = 80'
<b>LOCATION LAYOUT</b>		<b>EXHIBIT F</b>	



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,120 Cu. Yds.
REMAINING LOCATION	4,790 Cu. Yds.
<b>TOTAL CUT</b>	<b>7,910 Cu. Yds.</b>
<b>FILL</b>	<b>4,790 Cu. Yds.</b>
EXCESS MATERIAL	3,120 Cu. Yds.
TOPSOIL	3,120 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS		
	DISTANCE	ACRES
WELL SITE DISTURBANCE	NA	±6.273
FLOW LINE CONNECTION AREA DISTURBANCE	NA	±0.436
30' WIDE ACCESS ROAD "A" R-O-W DISTURBANCE	±79.97'	±0.055
30' WIDE ACCESS ROAD "B" R-O-W DISTURBANCE	±79.85'	±0.055
30' WIDE POWER LINE R-O-W DISTURBANCE	±1,563.59'	±1.077
<b>TOTAL</b>		<b>±7.896</b>

REV: 1 08-24-17 C.I. (RE-ROUTE)

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 ZONE 2 WEST CTB**  
**E 1/2 NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	S.F.	06-02-17	AS SHOWN
<b>TYPICAL CROSS SECTIONS</b>		<b>EXHIBIT F</b>	




**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



750' X 650' Archaeological Survey Boundary

Proposed Flow Line Connection Area

Topsoil Stockpile



Proposed Access Road "B"

Proposed Access Road "A"

Proposed Access Road For the Red Hills Unit E2E2 Well Pad

REV: 1 08-24-17 C.I. (ACCESS ROAD RE-ROUTE, FLOW LINE CONNECTION AREA MOVE)

**NOTES:****CIMAREX ENERGY CO.**


**RED HILLS UNIT 33 ZONE 2 WEST CTB**  
**E 1/2 NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017

<b>SURVEYED BY</b>	C.J., A.H., P.R.	05-04-17	<b>SCALE</b>
<b>DRAWN BY</b>	S.F.	06-02-17	1" = 100'
<b>ARCHAEOLOGICAL SURVEY BOUNDARY</b>			<b>EXHIBIT F</b>






LINE TABLE		
LINE	DIRECTION	LENGTH
L1	S00°01'43"E	50.00'
L2	S89°58'17"W	130.00'
L3	S00°01'43"E	200.00'
L4	S89°58'17"W	50.00'
L5	N00°01'43"W	250.00'
L6	N89°58'17"E	180.00'


POINT OF BEGINNING BEARS S33°29'31"W 1040.14' FROM THE NORTH 1/4 CORNER OF SECTION 33, T25S, R33E, N.M.P.M.

FLOW LINE CONNECTION SURFACE USE AREA DESCRIPTION

BEGINNING AT A POINT IN THE NE 1/4 NW 1/4 OF SECTION 33, T25S, R33E, N.M.P.M., WHICH BEARS S33°29'31"W 1040.14' FROM THE NORTH 1/4 CORNER OF SAID SECTION 33, THENCE S00°01'43"E 50.00'; THENCE S89°58'17"W 130.00'; THENCE S00°01'43"E 200.00'; THENCE S89°58'17"W 50.00'; THENCE N00°01'43"W 250.00'; THENCE N89°58'17"E 180.00' TO THE POINT OF BEGINNING. CONTAINS 0.436 ACRES MORE OR LESS.



CERTIFICATE  
THIS IS TO CERTIFY THAT THIS EASEMENT PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY; THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO; AND THAT IT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



▲ = SECTION CORNERS LOCATED.

FILE: 61747-A

Sheet 1 of 2

REV: 1 08-24-17 C.I. (FLOW LINE CONNECTION SUA MOVE)

NOTES:  
• Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00"



CIMAREX ENERGY CO.

RED HILLS UNIT 33 ZONE 2 WEST CTB  
SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

SURVEYED BY	C.J., A.H., P.R.	05-04-17	SCALE
DRAWN BY	B.D.H.	06-07-17	1" = 1000'
FLOW LINE CONNECTION		EXHIBIT F	



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

BEGINNING AT THE INTERSECTION OF J-1/ORLA ROAD AND PIPELINE ROAD TO THE EAST (LOCATED AT NAD83 LATITUDE N32.064964° AND LONGITUDE W103.674262°) PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 5.0 TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY, THEN NORTHEASTERLY, THEN NORTHWESTERLY DIRECTION APPROXIMATELY 2.1 MILES TO THE BEGINNING OF THE PROPOSED ACCESS FOR THE RED HILLS UNIT E2E2; FOLLOW ROAD FLAGS IN A SOUTHEASTERLY DIRECTION THEN EASTERLY DIRECTION FOR APPROXIMATELY 1,809' TO THE PROPOSED ACCESS "A"; FOLLOW ROAD FLAGS IN A NORTHERLY DIRECTION APPROXIMATELY 80' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM THE INTERSECTION OF J-1/ORLA ROAD AND PIPELINE ROAD TO THE SOUTH (LOCATED AT NAD83 LATITUDE N32.064964° AND LONGITUDE W103.674262°) TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 7.5 MILES.

REV: 01 08-24-17 L.W. (ROAD RE-ROUTE)

### CIMAREX ENERGY CO.


RED HILLS UNIT 33 ZONE 2 WEST CTB  
E 1/2 NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

UELS, LLC

Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



SURVEYED BY	C.J., A.H.	05-05-17	
DRAWN BY			
ROAD DESCRIPTION		EXHIBIT F	

**LEGEND:**

**PROPOSED LOCATION**



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33 ZONE 2 WEST CTB  
E 1/2 NW 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO**

<b>SURVEYED BY</b>	C.J., A.H.	05-05-17	<b>SCALE</b>
<b>DRAWN BY</b>	V.L.D.V.L.D.	05-26-17	1 : 100
<b>PUBLIC ACCESS ROAD MAP</b>		<b>EXHIBIT B</b>	



## **Cimarex Red Hills Unit 20H Surface Use Plan**

Upon approval of the Application for Permit to Drill (APD) the following surface use plan of operations will be followed and carried out. The surface use plan outlines the proposed surface disturbance. If any other disturbance is needed after the APD is approved, a BLM sundry notice or right of way application will be submitted for approval prior to any additional surface disturbance.

### **Existing Roads**

- Directions to location - Exhibit A.
- Public access route - Exhibit B.
- Existing access road for the proposed project. Please see Exhibit B and C.
- Cimarex Energy will:
  - Improve and/or maintain existing road(s) condition the same as or better than before the operations began.
  - Provide plans for improvement and /or maintenance of existing roads if requested.
  - Repair or replace damaged or deteriorated structures as needed. Including cattle guards and culverts.
  - Prevent and abate fugitive dust as needed, whether created by vehicular traffic, equipment operations, or other events.
  - Obtain written BLM approval prior to the application of surfactants, binding agents, or other dust suppression chemicals on the roadways.
- The maximum width of the driving surface will be 18'. The road will be crowned and ditched with a 2% slope from the tip of the crown to the edge of the driving surface. The ditches will be 1' deep with 3:1 slopes. The driving surface will be made of 6" rolled and compacted caliche.

### **New or Reconstructed Access Roads**

Cimarex Energy plans to construct a new off-lease access road

- Road has been previously approved in the Red Hills Unit 99H

### **Well Radius Map**

Please see Exhibit E for wells within one mile or proposed well SHL and BHL.

### **Proposed or Existing Production Facility**

An existing battery will be utilized for the project if the well is productive.

- Red Hills Unit West CTB 1 & 2
  - Battery Pad diagram - Exhibit F
  - Battery will not require an expansion in order to accommodate additional production equipment for the project.
  - Battery Pad location previously approved
    - APD: Red Hills Unit 16H.

### **Gas Pipeline Specifications**

- No new gas pipelines are required for this project.

### **Salt Water Disposal Specifications**

- No new SWD pipelines are required for this project.

### **Power Lines**

- ROW Application has been submitted for powerline route

## Cimarex Red Hills Unit 20H Surface Use Plan

### Well Site Location

- Proposed well pad/location layout - Exhibit J.
- Proposed Rig layout - Exhibit K
  - The rig layout, including V-door and flare line may change depending on rig availability. The pad dimensions and orientation will remain the same. No additional disturbance is anticipated if a rig layout change is necessary to accommodate the drilling rig. If additional disturbance is required a sundry notice will be submitted to the BLM for approval.
  - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in the steel containment pits.
  - Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- Archeological boundary - Exhibit L
- Multi well pad: Red Hills Unit 19H 20H 62H-73H
- Pad Size: 500 x 560
- Construction Material
  - If possible, native caliche will be obtained from the excavation of drill site. The primary way of obtaining caliche will be by "turning over" the location. This means caliche will be obtained from the actual well site. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2,400 cu yds is the max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:
    - The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
    - An approximate 120' x 120' area is used within the proposed well site to remove caliche.
    - Subsoil is removed and piled alongside the 120' x 120' area within the pad site.
    - When caliche is found, material will be stockpiled within the pad site to build the location and road.
    - Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
    - Once well is drilled, the stockpiled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stockpiled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in Exhibit J - Layout Diagram.
    - In the event that no caliche is found onsite, caliche will be hauled in from BLM-approved caliche pit in Sec 3 26S 33E or .
  - Mud pits in the closed circulation system will be steel pits and the cuttings will be stored in steel containment pits.
- Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements. Exhibit P: Interim Reclamation Diagram.
- There are no known dwellings within 1.5 miles of this location.

### Bulklines

Well pad will utilize previously approved bulklines. Bulklines were approved in the Red Hills Unit 99H APD.

### Water Resources

No temporary fresh water pipelines are proposed for this project.

**Cimarex Red Hills Unit 20H****Surface Use Plan****Methods of Handling Waste**

- Drilling fluids, produced oil, and water from the well during drilling and completion operations will be stored safely and disposed of properly in a NMOCD approved disposal facility.
- Garbage and trash produced during drilling and completion operations will be collected in a trash container and disposed of properly at a state approved disposal facility. All trash on and around well site will be collected for disposal.
- Human waste and grey water will be contained and disposed of properly at a state approved disposal site.
- After drilling and completion operations, trash, chemicals, salts, frac sand and other waste will be removed and disposed of properly at a state approved disposal site.
- The well will be drilled utilizing a closed loop system. Drill cuttings will be properly disposed of into steel tanks and taken to an NMOCD approved disposal facility.

**Ancillary Facilities**

No camps or airstrips to be constructed.

**Interim and Final Reclamation**

- Rehabilitation of the location will start in a timely manner after all proposed drilling wells have been drilled from the pad or if drilling operations have ceased as outlined below:
  - No approved or pending drill permits for wells located on the drill pad
  - No drilling activity for 5 years from the drill pad
- Surfacing materials will be removed and returned to a mineral pit or recycled to repair or build roads and well pads.
- Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.
- Exhibit P illustrates the proposed Surface Reclamation plans after cessation of drilling operations as outlined above.
  - The areas of the location not essential to production facilities and operations will be reclaimed and seeded per BLM requirements.
- Operator will amend the surface reclamation plan if well is a dry hole and/or a single well pad.

**Surface Ownership**

- The wellsite is on surface owned by Dinwiddie Cattle Co.
- A copy of Surface Use Agreement has been given to the surface owner.
- The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.

**Cultural Resource Survey - Archeology**

- Cultural Resources Survey will be conducted for the entire project as proposed in the APD and submitted to the BLM for review and approval.

**On Site Notes and Information**

Onsite Date: 3/20/2018

BLM Personnel on site: Jeff Robertson


Cimarex Energy personnel on site: Barry Hunt

Pertinent information from onsite:



# Drilling Water Route & Source Map Fresh Water- Trucked

Drilling Water Route #1  
Red Hills Unit 76H  
Cimarex Energy Co  
33-25S-33E  
Lea Cty, NM



Google earth

© 2017 Google

Released to Imaging: 8/31/2023 3:03:01 PM



# Drilling Water Route & Source Map Fresh Water- Trucked

Drilling Water Route #2  
Red Hills Unit 76H  
Cimarex Energy Co  
33-25S 33E  
Lea Cty, NM

Red Hills Unit E2E2

Turn right

Sharp left

Turn right to stay on Battle A

Turn right onto Battle Axe Rd/J-2



Turn right onto Battle Axe Rd/J-2

Turn left onto Battle Axe Rd/J-1 J-2

Continue onto J-1/Orla Rd

Lindsey FW Station 10 Blk 55 T1 T&P RR Co  
Head northeast on RM 652 E toward Private Rd 3030


## Legend

-  Lindsey FW Station 10 Blk 55 T1 T&P RR Co
-  Red Hills Unit E2E2

Google earth

5 mi





## NOTES:

- Contours shown at 2' intervals.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)
- Underground utilities shown on this sheet are for visualization purposes only, actual locations to be determined prior to construction.
- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD83)

## CIMAREX ENERGY CO.


RED HILLS UNIT 33-4 W2E2-E  
NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO



UELS, LLC  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

SURVEYED BY	A.H., A.G.	03-27-18	SCALE
DRAWN BY	R.J.	04-03-18	1" = 80'
LOCATION LAYOUT			EXHIBIT J

X-Section  
Scale  
1" = 100'



APPROXIMATE EARTHWORK QUANTITIES	
(4") TOPSOIL STRIPPING	3,860 Cu. Yds.
REMAINING LOCATION	8,420 Cu. Yds.
<b>TOTAL CUT</b>	<b>12,280 Cu. Yds.</b>
<b>FILL</b>	<b>8,420 Cu. Yds.</b>
EXCESS MATERIAL	3,860 Cu. Yds.
TOPSOIL	3,860 Cu. Yds.
<b>EXCESS UNBALANCE</b> (After Interim Rehabilitation)	<b>0 Cu. Yds.</b>

APPROXIMATE SURFACE DISTURBANCE AREAS	
	ACRES
WELL SITE DISTURBANCE	±7.496

REV: 1 07-01-21 Z.T. (ADD SATELLITE PAD)

**NOTES:**

- Fill quantity includes 5% for compaction.
- Cut/Fill slopes 1 1/2:1 (Typ. except where noted)

**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33-4 W2E2-E**  
**NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**

SURVEYED BY	A.H., A.G.	03-27-18	SCALE
DRAWN BY	R.J.	04-03-18	AS SHOWN
<b>TYPICAL CROSS SECTIONS</b>		<b>EXHIBIT J</b>	



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017





- Contours shown at 2' intervals.

**CIMAREX ENERGY CO.**

## RED HILLS UNIT 20H


453' FNL 1620' FEL

NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.  
LEA COUNTY, NEW MEXICO

<b>SURVEYED BY</b>	A.H., A.G.	03-27-18	<b>SCALE</b>
<b>DRAWN BY</b>	R.J.	04-03-18	1" = 80'
<b>TYPICAL RIG LAYOUT</b>			<b>EXHIBIT K</b>



**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017

**NOTES:**

- Basis of Bearings is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD83)


**CIMAREX ENERGY CO.**

**RED HILLS UNIT 33-4 W2E2-E**  
**NW 1/4 NE 1/4, SECTION 33, T25S, R33E, N.M.P.M.**  
**LEA COUNTY, NEW MEXICO**


SURVEYED BY	A.H., A.G.	03-27-18	SCALE
DRAWN BY	R.J.	04-03-18	1" = 100'
ARCHAEOLOGICAL SURVEY BOUNDARY			<b>EXHIBIT L</b>



**UELS, LLC**  
 Corporate Office \* 85 South 200 East  
 Vernal, UT 84078 \* (435) 789-1017



Pad will be reclaimed after cessation of drilling operations.  
Please see Surface Use Plan for pad reclamation plans.





U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## PWD Data Report

07/31/2023

**APD ID:** 10400060223

**Submission Date:** 04/21/2021

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Well Type:** OIL WELL

**Well Work Type:** Drill

### Section 1 - General

Would you like to address long-term produced water disposal? NO

### Section 2 - Lined

Would you like to utilize Lined Pit PWD options? N

**Produced Water Disposal (PWD) Location:**

**PWD surface owner:**

**PWD disturbance (acres):**

**Lined pit PWD on or off channel:**

**Lined pit PWD discharge volume (bbl/day):**

**Lined pit**

**Pit liner description:**

**Pit liner manufacturers**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal**

**Lined pit precipitated solids disposal schedule:**

**Lined pit precipitated solids disposal schedule**

**Lined pit reclamation description:**

**Lined pit reclamation**

**Leak detection system description:**

**Leak detection system**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Lined pit Monitor description:**

**Lined pit Monitor**

**Lined pit: do you have a reclamation bond for the pit?**

**Is the reclamation bond a rider under the BLM bond?**

**Lined pit bond number:**

**Lined pit bond amount:**

**Additional bond information**

### Section 3 - Unlined

**Would you like to utilize Unlined Pit PWD options?** N

**Produced Water Disposal (PWD) Location:**

**PWD disturbance (acres):**

**PWD surface owner:**

**Unlined pit PWD on or off channel:**

**Unlined pit PWD discharge volume (bbl/day):**

**Unlined pit**

**Precipitated solids disposal:**

**Describe precipitated solids disposal:**

**Precipitated solids disposal**

**Unlined pit precipitated solids disposal schedule:**

**Unlined pit precipitated solids disposal schedule**

**Unlined pit reclamation description:**

**Unlined pit reclamation**

**Unlined pit Monitor description:**

**Unlined pit Monitor**

**Do you propose to put the produced water to beneficial use?**

**Beneficial use user**

**Estimated depth of the shallowest aquifer (feet):**

**Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?**

**TDS lab results:**

**Geologic and hydrologic**

**State**

**Unlined Produced Water Pit Estimated**

**Unlined pit: do you have a reclamation bond for the pit?**

**Operator Name:** CIMAREX ENERGY COMPANY**Well Name:** RED HILLS UNIT**Well Number:** 20H**Is the reclamation bond a rider under the BLM bond?****Unlined pit bond number:****Unlined pit bond amount:****Additional bond information****Section 4 -****Would you like to utilize Injection PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Injection PWD discharge volume (bbl/day):****Injection well mineral owner:****Injection well type:****Injection well number:****Injection well name:****Assigned injection well API number?****Injection well API number:****Injection well new surface disturbance (acres):****Minerals protection information:****Mineral protection****Underground Injection Control (UIC) Permit?****UIC Permit****Section 5 - Surface****Would you like to utilize Surface Discharge PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Surface discharge PWD discharge volume (bbl/day):****Surface Discharge NPDES Permit?****Surface Discharge NPDES Permit attachment:****Surface Discharge site facilities information:****Surface discharge site facilities map:****Section 6 -****Would you like to utilize Other PWD options?** N**Produced Water Disposal (PWD) Location:****PWD surface owner:****PWD disturbance (acres):****Other PWD discharge volume (bbl/day):**

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Other PWD type description:**

**Other PWD type**

**Have other regulatory requirements been met?**

**Other regulatory requirements**



U.S. Department of the Interior  
BUREAU OF LAND MANAGEMENT

## Bond Info Data

07/31/2023

**APD ID:** 10400060223

**Submission Date:** 04/21/2021

Highlighted data  
reflects the most  
recent changes  
[Show Final Text](#)

**Operator Name:** CIMAREX ENERGY COMPANY

**Well Name:** RED HILLS UNIT

**Well Number:** 20H

**Well Type:** OIL WELL

**Well Work Type:** Drill

### Bond

**Federal/Indian APD:** FED

**BLM Bond number:** NMB001188

**BIA Bond number:**

**Do you have a reclamation bond?** NO

**Is the reclamation bond a rider under the BLM bond?**

**Is the reclamation bond BLM or Forest Service?**

**BLM reclamation bond number:**

**Forest Service reclamation bond number:**

**Forest Service reclamation bond**

**Reclamation bond number:**

**Reclamation bond amount:**

**Reclamation bond rider amount:**

**Additional reclamation bond information**



**District I**

1625 N. French Dr., Hobbs, NM 88240  
Phone:(575) 393-6161 Fax:(575) 393-0720

**District II**

811 S. First St., Artesia, NM 88210  
Phone:(575) 748-1283 Fax:(575) 748-9720

**District III**

1000 Rio Brazos Rd., Aztec, NM 87410  
Phone:(505) 334-6178 Fax:(505) 334-6170

**District IV**

1220 S. St Francis Dr., Santa Fe, NM 87505  
Phone:(505) 476-3470 Fax:(505) 476-3462

**State of New Mexico**  
**Energy, Minerals and Natural Resources**  
**Oil Conservation Division**  
**1220 S. St Francis Dr.**  
**Santa Fe, NM 87505**

CONDITIONS

Action 257023

**CONDITIONS**

Operator: CIMAREX ENERGY CO. 6001 Deauville Blvd Midland, TX 79706	OGRID: 215099
	Action Number: 257023
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

**CONDITIONS**

Created By	Condition	Condition Date
pkautz	Will require a File As Drilled C-102 and a Directional Survey with the C-104	8/31/2023
pkautz	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	8/31/2023
pkautz	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	8/31/2023
pkautz	Cement is required to circulate on both surface and intermediate1 strings of casing	8/31/2023
pkautz	IF ON ANY STRING CEMENT DOES NOT CIRCULATE, A RCBL MUST BE RUN ON THAT STRING OF CASING.	8/31/2023