

Form 3160-3
(June 2015)FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☐ DRILL ☐ REENTER 1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Other 1c. Type of Completion: ☐ Hydraulic Fracturing ☐ Single Zone ☐ Multiple Zone		5. Lease Serial No. 6. If Indian, Allottee or Tribe Name 7. If Unit or CA Agreement, Name and No. 8. Lease Name and Well No.
2. Name of Operator		9. API Well No. 30-015-54383
3a. Address	3b. Phone No. (include area code)	10. Field and Pool, or Exploratory
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface At proposed prod. zone		11. Sec., T. R. M. or Blk. and Survey or Area
14. Distance in miles and direction from nearest town or post office*		12. County or Parish
13. State		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No of acres in lease	17. Spacing Unit dedicated to this well
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. in file
21. Elevations (Show whether DF, KDB, RT, GL, etc.)	22. Approximate date work will start*	23. Estimated duration
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM. |
|---|---|

25. Signature	Name (Printed/Typed)	Date
Title		
Approved by (Signature)	Name (Printed/Typed)	Date
Title		
Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
 Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)



Additional Operator Remarks

Location of Well

0. SHL: SESE / 455 FSL / 606 FEL / TWSP: 24S / RANGE: 30E / SECTION: 14 / LAT: 32.21189 / LONG: -103.844923 (TVD: 0 feet, MD: 0 feet)

PPP: SWSE / 100 FSL / 1430 FEL / TWSP: 24S / RANGE: 30E / SECTION: 14 / LAT: 32.210911 / LONG: -103.847591 (TVD: 11320 feet, MD: 11800 feet)

BHL: LOT 2 / 200 FNL / 1430 FEL / TWSP: 24S / RANGE: 30E / SECTION: 2 / LAT: 32.253589 / LONG: -103.847571 (TVD: 11635 feet, MD: 27581 feet)

BLM Point of Contact

Name: Priscilla Perez

Title: Legal Instruments Examiner

Phone: (575) 234-5934

Email: pperez@blm.gov

District I

1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

District III

1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102

Revised August 1, 2011

Submit one copy to appropriate

District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-015- 54383	² Pool Code 98220	³ Pool Name Purple Sage; Wolfcamp
⁴ Property Code 325598	⁵ Property Name Poker Lake 23 DTD Federal Com	⁶ Well Number 107H
⁷ OGRID No. 373075	⁸ Operator Name XTO PERMIAN OPERATING, LLC	⁹ Elevation 3,443'

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	14	24 S	30 E		455	SOUTH	606	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
2	2	24 S	30 E		200	NORTH	1,430	EAST	EDDY

¹² Dedicated Acres 960	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--------------------------------------	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

16 SHL (NAD83 NME) Y = 441,162.8 X = 692,390.5 LAT. = 32.211890 "N LONG. = 103.844923 "W FTP (NAD83 NME) Y = 440,803.1 X = 691,567.0 LAT. = 32.210911 "N LONG. = 103.847591 "W CORNER COORDINATES (NAD83 NME) <table border="0"> <tr><td>A - Y = 440,695.8 N</td><td>X = 690,318.7 E</td></tr> <tr><td>B - Y = 443,332.7 N</td><td>X = 690,316.5 E</td></tr> <tr><td>C - Y = 445,969.1 N</td><td>X = 690,314.3 E</td></tr> <tr><td>D - Y = 448,606.1 N</td><td>X = 690,296.3 E</td></tr> <tr><td>E - Y = 451,241.1 N</td><td>X = 690,278.3 E</td></tr> <tr><td>F - Y = 453,878.5 N</td><td>X = 690,267.5 E</td></tr> <tr><td>G - Y = 456,518.6 N</td><td>X = 690,256.7 E</td></tr> <tr><td>H - Y = 440,703.6 N</td><td>X = 691,657.9 E</td></tr> <tr><td>I - Y = 443,341.5 N</td><td>X = 691,655.2 E</td></tr> <tr><td>J - Y = 445,982.8 N</td><td>X = 691,652.3 E</td></tr> <tr><td>K - Y = 448,617.4 N</td><td>X = 691,633.4 E</td></tr> <tr><td>L - Y = 451,254.5 N</td><td>X = 691,614.2 E</td></tr> <tr><td>M - Y = 453,892.0 N</td><td>X = 691,604.4 E</td></tr> <tr><td>N - Y = 456,529.5 N</td><td>X = 691,594.5 E</td></tr> </table> SHL (NAD27 NME) Y = 441,103.7 X = 651,206.8 LAT. = 32.211766 "N LONG. = 103.844437 "W FTP (NAD27 NME) Y = 440,744.0 X = 650,383.2 LAT. = 32.210787 "N LONG. = 103.847105 "W CORNER COORDINATES (NAD27 NME) <table border="0"> <tr><td>A - Y = 440,636.8 N</td><td>X = 649,135.0 E</td></tr> <tr><td>B - Y = 443,273.6 N</td><td>X = 649,132.9 E</td></tr> <tr><td>C - Y = 445,909.9 N</td><td>X = 649,130.8 E</td></tr> <tr><td>D - Y = 448,546.9 N</td><td>X = 649,112.8 E</td></tr> <tr><td>E - Y = 451,181.8 N</td><td>X = 649,094.9 E</td></tr> <tr><td>F - Y = 453,819.1 N</td><td>X = 649,084.2 E</td></tr> <tr><td>G - Y = 456,459.1 N</td><td>X = 649,073.5 E</td></tr> <tr><td>H - Y = 440,644.6 N</td><td>X = 650,474.1 E</td></tr> <tr><td>I - Y = 443,282.4 N</td><td>X = 650,471.5 E</td></tr> <tr><td>J - Y = 445,923.7 N</td><td>X = 650,468.7 E</td></tr> <tr><td>K - Y = 448,558.1 N</td><td>X = 650,449.9 E</td></tr> <tr><td>L - Y = 451,195.2 N</td><td>X = 650,430.8 E</td></tr> <tr><td>M - Y = 453,832.6 N</td><td>X = 650,421.1 E</td></tr> <tr><td>N - Y = 456,470.0 N</td><td>X = 650,411.3 E</td></tr> </table>	A - Y = 440,695.8 N	X = 690,318.7 E	B - Y = 443,332.7 N	X = 690,316.5 E	C - Y = 445,969.1 N	X = 690,314.3 E	D - Y = 448,606.1 N	X = 690,296.3 E	E - Y = 451,241.1 N	X = 690,278.3 E	F - Y = 453,878.5 N	X = 690,267.5 E	G - Y = 456,518.6 N	X = 690,256.7 E	H - Y = 440,703.6 N	X = 691,657.9 E	I - Y = 443,341.5 N	X = 691,655.2 E	J - Y = 445,982.8 N	X = 691,652.3 E	K - Y = 448,617.4 N	X = 691,633.4 E	L - Y = 451,254.5 N	X = 691,614.2 E	M - Y = 453,892.0 N	X = 691,604.4 E	N - Y = 456,529.5 N	X = 691,594.5 E	A - Y = 440,636.8 N	X = 649,135.0 E	B - Y = 443,273.6 N	X = 649,132.9 E	C - Y = 445,909.9 N	X = 649,130.8 E	D - Y = 448,546.9 N	X = 649,112.8 E	E - Y = 451,181.8 N	X = 649,094.9 E	F - Y = 453,819.1 N	X = 649,084.2 E	G - Y = 456,459.1 N	X = 649,073.5 E	H - Y = 440,644.6 N	X = 650,474.1 E	I - Y = 443,282.4 N	X = 650,471.5 E	J - Y = 445,923.7 N	X = 650,468.7 E	K - Y = 448,558.1 N	X = 650,449.9 E	L - Y = 451,195.2 N	X = 650,430.8 E	M - Y = 453,832.6 N	X = 650,421.1 E	N - Y = 456,470.0 N	X = 650,411.3 E	SECTION 2 LOT 2 - 40.23 ACRES GRID AZ. = 359°45'50" HORIZ. DIST. = 15,525.80' GRID AZ. = 246°24'20" HORIZ. DIST. = 898.66' LOT ACREAGE TABLE SEC. 34 SEC. 35 T23S R30E G SEC. 36 SEC. 3 SEC. 2 SEC. 11 SEC. 10 SEC. 11 T24S R30E SEC. 12 SEC. 15 SEC. 14 SEC. 13 SEC. 22 SEC. 23 SEC. 24 LOT 2 LOT 1 LOT 3 LOT 4 LOT 5 LOT 6 LOT 7 LOT 8 LOT 9 LOT 10 LOT 11 LOT 12 LOT 13 LOT 14 LOT 15 LOT 16 LOT 17 LOT 18 LOT 19 LOT 20 LOT 21 LOT 22 LOT 23 LOT 24 LOT 25 LOT 26 LOT 27 LOT 28 LOT 29 LOT 30 LOT 31 LOT 32 LOT 33 LOT 34 LOT 35 LOT 36 LOT 37 LOT 38 LOT 39 LOT 40 LOT 41 LOT 42 LOT 43 LOT 44 LOT 45 LOT 46 LOT 47 LOT 48 LOT 49 LOT 50 LOT 51 LOT 52 LOT 53 LOT 54 LOT 55 LOT 56 LOT 57 LOT 58 LOT 59 LOT 60 LOT 61 LOT 62 LOT 63 LOT 64 LOT 65 LOT 66 LOT 67 LOT 68 LOT 69 LOT 70 LOT 71 LOT 72 LOT 73 LOT 74 LOT 75 LOT 76 LOT 77 LOT 78 LOT 79 LOT 80 LOT 81 LOT 82 LOT 83 LOT 84 LOT 85 LOT 86 LOT 87 LOT 88 LOT 89 LOT 90 LOT 91 LOT 92 LOT 93 LOT 94 LOT 95 LOT 96 LOT 97 LOT 98 LOT 99 LOT 100 LOT 101 LOT 102 LOT 103 LOT 104 LOT 105 LOT 106 LOT 107 LOT 108 LOT 109 LOT 110 LOT 111 LOT 112 LOT 113 LOT 114 LOT 115 LOT 116 LOT 117 LOT 118 LOT 119 LOT 120 LOT 121 LOT 122 LOT 123 LOT 124 LOT 125 LOT 126 LOT 127 LOT 128 LOT 129 LOT 130 LOT 131 LOT 132 LOT 133 LOT 134 LOT 135 LOT 136 LOT 137 LOT 138 LOT 139 LOT 140 LOT 141 LOT 142 LOT 143 LOT 144 LOT 145 LOT 146 LOT 147 LOT 148 LOT 149 LOT 150 LOT 151 LOT 152 LOT 153 LOT 154 LOT 155 LOT 156 LOT 157 LOT 158 LOT 159 LOT 160 LOT 161 LOT 162 LOT 163 LOT 164 LOT 165 LOT 166 LOT 167 LOT 168 LOT 169 LOT 170 LOT 171 LOT 172 LOT 173 LOT 174 LOT 175 LOT 176 LOT 177 LOT 178 LOT 179 LOT 180 LOT 181 LOT 182 LOT 183 LOT 184 LOT 185 LOT 186 LOT 187 LOT 188 LOT 189 LOT 190 LOT 191 LOT 192 LOT 193 LOT 194 LOT 195 LOT 196 LOT 197 LOT 198 LOT 199 LOT 200 LOT 201 LOT 202 LOT 203 LOT 204 LOT 205 LOT 206 LOT 207 LOT 208 LOT 209 LOT 210 LOT 211 LOT 212 LOT 213 LOT 214 LOT 215 LOT 216 LOT 217 LOT 218 LOT 219 LOT 220 LOT 221 LOT 222 LOT 223 LOT 224 LOT 225 LOT 226 LOT 227 LOT 228 LOT 229 LOT 230 LOT 231 LOT 232 LOT 233 LOT 234 LOT 235 LOT 236 LOT 237 LOT 238 LOT 239 LOT 240 LOT 241 LOT 242 LOT 243 LOT 244 LOT 245 LOT 246 LOT 247 LOT 248 LOT 249 LOT 250 LOT 251 LOT 252 LOT 253 LOT 254 LOT 255 LOT 256 LOT 257 LOT 258 LOT 259 LOT 260 LOT 261 LOT 262 LOT 263 LOT 264 LOT 265 LOT 266 LOT 267 LOT 268 LOT 269 LOT 270 LOT 271 LOT 272 LOT 273 LOT 274 LOT 275 LOT 276 LOT 277 LOT 278 LOT 279 LOT 280 LOT 281 LOT 282 LOT 283 LOT 284 LOT 285 LOT 286 LOT 287 LOT 288 LOT 289 LOT 290 LOT 291 LOT 292 LOT 293 LOT 294 LOT 295 LOT 296 LOT 297 LOT 298 LOT 299 LOT 300 LOT 301 LOT 302 LOT 303 LOT 304 LOT 305 LOT 306 LOT 307 LOT 308 LOT 309 LOT 310 LOT 311 LOT 312 LOT 313 LOT 314 LOT 315 LOT 316 LOT 317 LOT 318 LOT 319 LOT 320 LOT 321 LOT 322 LOT 323 LOT 324 LOT 325 LOT 326 LOT 327 LOT 328 LOT 329 LOT 330 LOT 331 LOT 332 LOT 333 LOT 334 LOT 335 LOT 336 LOT 337 LOT 338 LOT 339 LOT 340 LOT 341 LOT 342 LOT 343 LOT 344 LOT 345 LOT 346 LOT 347 LOT 348 LOT 349 LOT 350 LOT 351 LOT 352 LOT 353 LOT 354 LOT 355 LOT 356 LOT 357 LOT 358 LOT 359 LOT 360 LOT 361 LOT 362 LOT 363 LOT 364 LOT 365 LOT 366 LOT 367 LOT 368 LOT 369 LOT 370 LOT 371 LOT 372 LOT 373 LOT 374 LOT 375 LOT 376 LOT 377 LOT 378 LOT 379 LOT 380 LOT 381 LOT 382 LOT 383 LOT 384 LOT 385 LOT 386 LOT 387 LOT 388 LOT 389 LOT 390 LOT 391 LOT 392 LOT 393 LOT 394 LOT 395 LOT 396 LOT 397 LOT 398 LOT 399 LOT 400 LOT 401 LOT 402 LOT 403 LOT 404 LOT 405 LOT 406 LOT 407 LOT 408 LOT 409 LOT 410 LOT 411 LOT 412 LOT 413 LOT 414 LOT 415 LOT 416 LOT 417 LOT 418 LOT 419 LOT 420 LOT 421 LOT 422 LOT 423 LOT 424 LOT 425 LOT 426 LOT 427 LOT 428 LOT 429 LOT 430 LOT 431 LOT 432 LOT 433 LOT 434 LOT 435 LOT 436 LOT 437 LOT 438 LOT 439 LOT 440 LOT 441 LOT 442 LOT 443 LOT 444 LOT 445 LOT 446 LOT 447 LOT 448 LOT 449 LOT 450 LOT 451 LOT 452 LOT 453 LOT 454 LOT 455 LOT 456 LOT 457 LOT 458 LOT 459 LOT 460 LOT 461 LOT 462 LOT 463 LOT 464 LOT 465 LOT 466 LOT 467 LOT 468 LOT 469 LOT 470 LOT 471 LOT 472 LOT 473 LOT 474 LOT 475 LOT 476 LOT 477 LOT 478 LOT 479 LOT 480 LOT 481 LOT 482 LOT 483 LOT 484 LOT 485 LOT 486 LOT 487 LOT 488 LOT 489 LOT 490 LOT 491 LOT 492 LOT 493 LOT 494 LOT 495 LOT 496 LOT 497 LOT 498 LOT 499 LOT 500 LOT 501 LOT 502 LOT 503 LOT 504 LOT 505 LOT 506 LOT 507 LOT 508 LOT 509 LOT 510 LOT 511 LOT 512 LOT 513 LOT 514 LOT 515 LOT 516 LOT 517 LOT 518 LOT 519 LOT 520 LOT 521 LOT 522 LOT 523 LOT 524 LOT 525 LOT 526 LOT 527 LOT 528 LOT 529 LOT 530 LOT 531 LOT 532 LOT 533 LOT 534 LOT 535 LOT 536 LOT 537 LOT 538 LOT 539 LOT 540 LOT 541 LOT 542 LOT 543 LOT 544 LOT 545 LOT 546 LOT 547 LOT 548 LOT 549 LOT 550 LOT 551 LOT 552 LOT 553 LOT 554 LOT 555 LOT 556 LOT 557 LOT 558 LOT 559 LOT 560 LOT 561 LOT 562 LOT 563 LOT 564 LOT 565 LOT 566 LOT 567 LOT 568 LOT 569 LOT 570 LOT 571 LOT 572 LOT 573 LOT 574 LOT 575 LOT 576 LOT 577 LOT 578 LOT 579 LOT 580 LOT 581 LOT 582 LOT 583 LOT 584 LOT 585 LOT 586 LOT 587 LOT 588 LOT 589 LOT 590 LOT 591 LOT 592 LOT 593 LOT 594 LOT 595 LOT 596 LOT 597 LOT 598 LOT 599 LOT 600 LOT 601 LOT 602 LOT 603 LOT 604 LOT 605 LOT 606 LOT 607 LOT 608 LOT 609 LOT 610 LOT 611 LOT 612 LOT 613 LOT 614 LOT 615 LOT 616 LOT 617 LOT 618 LOT 619 LOT 620 LOT 621 LOT 622 LOT 623 LOT 624 LOT 625 LOT 626 LOT 627 LOT 628 LOT 629 LOT 630 LOT 631 LOT 632 LOT 633 LOT 634 LOT 635 LOT 636 LOT 637 LOT 638 LOT 639 LOT 640 LOT 641 LOT 642 LOT 643 LOT 644 LOT 645 LOT 646 LOT 647 LOT 648 LOT 649 LOT 650 LOT 651 LOT 652 LOT 653 LOT 654 LOT 655 LOT 656 LOT 657 LOT 658 LOT 659 LOT 660 LOT 661 LOT 662 LOT 663 LOT 664 LOT 665 LOT 666 LOT 667 LOT 668 LOT 669 LOT 670 LOT 671 LOT 672 LOT 673 LOT 674 LOT 675 LOT 676 LOT 677 LOT 678 LOT 679 LOT 680 LOT 681 LOT 682 LOT 683 LOT 684 LOT 685 LOT 686 LOT 687 LOT 688 LOT 689 LOT 690 LOT 691 LOT 692 LOT 693 LOT 694 LOT 695 LOT 696 LOT 697 LOT 698 LOT 699 LOT 700 LOT 701 LOT 702 LOT 703 LOT 704 LOT 705 LOT 706 LOT 707 LOT 708 LOT 709 LOT 710 LOT 711 LOT 712 LOT 713 LOT 714 LOT 715 LOT 716 LOT 717 LOT 718 LOT 719 LOT 720 LOT 721 LOT 722 LOT 723 LOT 724 LOT 725 LOT 726 LOT 727 LOT 728 LOT 729 LOT 730 LOT 731 LOT 732 LOT 733 LOT 734 LOT 735 LOT 736 LOT 737 LOT 738 LOT 739 LOT 740 LOT 741 LOT 742 LOT 743 LOT 744 LOT 745 LOT 746 LOT 747 LOT 748 LOT 749 LOT 750 LOT 751 LOT 752 LOT 753 LOT 754 LOT 755 LOT 756 LOT 757 LOT 758 LOT 759 LOT 760 LOT 761 LOT 762 LOT 763 LOT 764 LOT 765 LOT 766 LOT 767 LOT 768 LOT 769 LOT 770 LOT 771 LOT 772 LOT 773 LOT 774 LOT 775 LOT 776 LOT 777 LOT 778 LOT 779 LOT 780 LOT 781 LOT 782 LOT 783 LOT 784 LOT 785 LOT 786 LOT 787 LOT 788 LOT 789 LOT 790 LOT 791 LOT 792 LOT 793 LOT 794 LOT 795 LOT 796 LOT 797 LOT 798 LOT 799 LOT 800 LOT 801 LOT 802 LOT 803 LOT 80
A - Y = 440,695.8 N	X = 690,318.7 E																																																								
B - Y = 443,332.7 N	X = 690,316.5 E																																																								
C - Y = 445,969.1 N	X = 690,314.3 E																																																								
D - Y = 448,606.1 N	X = 690,296.3 E																																																								
E - Y = 451,241.1 N	X = 690,278.3 E																																																								
F - Y = 453,878.5 N	X = 690,267.5 E																																																								
G - Y = 456,518.6 N	X = 690,256.7 E																																																								
H - Y = 440,703.6 N	X = 691,657.9 E																																																								
I - Y = 443,341.5 N	X = 691,655.2 E																																																								
J - Y = 445,982.8 N	X = 691,652.3 E																																																								
K - Y = 448,617.4 N	X = 691,633.4 E																																																								
L - Y = 451,254.5 N	X = 691,614.2 E																																																								
M - Y = 453,892.0 N	X = 691,604.4 E																																																								
N - Y = 456,529.5 N	X = 691,594.5 E																																																								
A - Y = 440,636.8 N	X = 649,135.0 E																																																								
B - Y = 443,273.6 N	X = 649,132.9 E																																																								
C - Y = 445,909.9 N	X = 649,130.8 E																																																								
D - Y = 448,546.9 N	X = 649,112.8 E																																																								
E - Y = 451,181.8 N	X = 649,094.9 E																																																								
F - Y = 453,819.1 N	X = 649,084.2 E																																																								
G - Y = 456,459.1 N	X = 649,073.5 E																																																								
H - Y = 440,644.6 N	X = 650,474.1 E																																																								
I - Y = 443,282.4 N	X = 650,471.5 E																																																								
J - Y = 445,923.7 N	X = 650,468.7 E																																																								
K - Y = 448,558.1 N	X = 650,449.9 E																																																								
L - Y = 451,195.2 N	X = 650,430.8 E																																																								
M - Y = 453,832.6 N	X = 650,421.1 E																																																								
N - Y = 456,470.0 N	X = 650,411.3 E																																																								



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

06/09/2022

APD ID: 10400080747

Submission Date: 10/11/2021

Highlighted data
reflects the most
recent changes

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE 23 DTD FEDERAL COM

Well Number: 107H

Well Type: CONVENTIONAL GAS WELL

Well Work Type: Drill

[Show Final Text](#)

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
7648450	QUATERNARY	3443	0	0	ALLUVIUM	USEABLE WATER	N
7648451	RUSTLER	2973	470	470	SANDSTONE	USEABLE WATER	N
7648452	TOP SALT	2603	840	840	SALT	NONE	N
7648453	BASE OF SALT	-417	3860	3860	SALT	NONE	N
7648454	DELAWARE	-637	4080	4080	SANDSTONE, SILTSTONE	NATURAL GAS, OIL, USEABLE WATER	N
7648455	BONE SPRING	-4517	7960	7960	LIMESTONE, SANDSTONE	NATURAL GAS, OIL, USEABLE WATER	N
7648456	WOLFCAMP	-7817	11260	11260	LIMESTONE, SANDSTONE, SILTSTONE	NATURAL GAS, OIL, USEABLE WATER	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 10M

Rating Depth: 11320

Equipment: Once the permanent WH is installed on the 11-3/4 casing, the blow out preventer equipment (BOP) will consist of a 13-5/8 minimum 10M Hydril and a 13-5/8 minimum 10M 3-Ram BOP. In any instance where 10M BOP is required by BLM, XTO requests a variance to utilize 5M annular with 10M ram preventers (a common BOP configuration, which allows use of 10M rams in unlikely event that pressures exceed 5M). Also a variance is requested to test the 5M annular to 70% of working pressure at 3500 psi.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors. A variance is requested to ONLY test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken. Based on discussions with the BLM on February 27th 2020, we will request permission to ONLY retest broken pressure seals if the following conditions are met: 1. After a full BOP test is conducted on the first well on the pad (First well will be the deepest Intermediate) 2. When skidding to drill an intermediate section does not penetrate into the Wolfcamp 3. Full BOP test will be required prior to drilling the production hole. Permanent Wellhead – Multibowl System A. Starting Head: 13-5/8" 10M top flange x 11-3/4" SOW bottom B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange
· Wellhead will be installed by manufacturer's

Operator Name: XTO PERMIAN OPERATING LLC**Well Name:** POKER LAKE 23 DTD FEDERAL COM**Well Number:** 107H

representatives. · Manufacturer will monitor welding process to ensure appropriate temperature of seal.
 Operator will test the 7-5/8" casing per BLM Onshore Order 2 · Wellhead Manufacturer representative will not be present for BOP test plug installation

Testing Procedure: All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 70% of the working pressure. When nipping up on the 11-3/4", 10M bradenhead and flange, the BOP test will be limited to 7500 psi. All BOP tests will include a low pressure test as per BLM regulations. The 10M BOP diagrams are attached. Blind rams will be functioned tested each trip, pipe rams will be functioned tested each day.

Choke Diagram Attachment:

PLU_23_DTD_10MCM_20210803061532.pdf

BOP Diagram Attachment:

PLU_23_DTD_5M10MBOP_20210803061538.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	12.25	9.625	NEW	API	N	0	740	0	740	3442	2702	740	J-55	40	BUTT	7.68	1.31	DRY	21.28	DRY	21.28
2	INTERMEDIATE	8.75	7.625	NEW	API	Y	0	11320	0	11320	3329	-7878	11320	HCL-80	29.7	OTHER - Flush Joint	1.89	1.61	DRY	2.08	DRY	2.08
3	PRODUCTION	6.75	5.5	NEW	API	Y	0	27259	0	11320	3329	-7878	27259	P-110	23	OTHER - Semi-Flush	2.15	1.21	DRY	4.72	DRY	4.72

Casing Attachments

Operator Name: XTO PERMIAN OPERATING LLC**Well Name:** POKER LAKE 23 DTD FEDERAL COM**Well Number:** 107H**Casing Attachments****Casing ID:** 1 **String** SURFACE**Inspection Document:****Spec Document:****Tapered String Spec:****Casing Design Assumptions and Worksheet(s):**

PLU_23_DTD_107H_csg_20211004090137.pdf

Casing ID: 2 **String** INTERMEDIATE**Inspection Document:****Spec Document:****Tapered String Spec:**

PLU_23_DTD_107H_csg_20211004090205.pdf

Casing Design Assumptions and Worksheet(s):

PLU_23_DTD_107H_csg_20211004090226.pdf

Casing ID: 3 **String** PRODUCTION**Inspection Document:****Spec Document:****Tapered String Spec:**

PLU_23_DTD_107H_csg_20211004090335.pdf

Casing Design Assumptions and Worksheet(s):

PLU_23_DTD_107H_csg_20211004090339.pdf

Section 4 - Cement

Operator Name: XTO PERMIAN OPERATING LLC**Well Name:** POKER LAKE 23 DTD FEDERAL COM**Well Number:** 107H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	740	290	1.87	12.9	542.3	100	EconoCem-HLTRRC	None

INTERMEDIATE	Lead		0	1057 1	830	2.77	10.5	2299. 1	30	Class C	None - See Cement Attachment
INTERMEDIATE	Tail		0	1057 1	710	1.33	14.8	944.3	30	Class C	None - See Cement Attachment
PRODUCTION	Lead		1037 1	2725 9	20	2.69	11.5	53.8	100	NeoCem	None
PRODUCTION	Tail		1037 1	2725 9	1180	1.51	13.2	1781. 8	100	Versacem	None

Section 5 - Circulating Medium

Mud System Type: Closed**Will an air or gas system be Used?** NO**Description of the equipment for the circulating system in accordance with Onshore Order #2:****Diagram of the equipment for the circulating system in accordance with Onshore Order #2:****Describe what will be on location to control well or mitigate other conditions:** The necessary mud products for weight addition and fluid loss control will be on location at all times.

Describe the mud monitoring system utilized: Spud with fresh water/native mud and set 11-3/4" surface casing, isolating the fresh water aquifer. Drill out from under 11-3/4 surface casing with a brine/oil direct emulsion mud system. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	740	SPUD MUD	8.7	9.2							

Operator Name: XTO PERMIAN OPERATING LLC**Well Name:** POKER LAKE 23 DTD FEDERAL COM**Well Number:** 107H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
740	1057 1	OTHER : Brine / Cut Brine / Direct Emulsion	9.7	10.2							
1057 1	2725 9	OTHER : Cut Brine / WBM / OBM	11.5	12							The necessary mud products for weight addition and fluid loss control will be on location at all times.

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Mud Logger: Mud Logging Unit (2 man) below intermediate casing. Open hole logging will not be done on this well.

List of open and cased hole logs run in the well:

CEMENT BOND LOG, DIRECTIONAL SURVEY,

Coring operation description for the well:

No Coring Operations for Well

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 6769

Anticipated Surface Pressure: 4209

Anticipated Bottom Hole Temperature(F): 170

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

PLU_23_DTD_H2S_Dia_20210803062628.pdf

PLU_23_DTD_H2S_Plan_20210803062634.pdf

Operator Name: XTO PERMIAN OPERATING LLC

Well Name: POKER LAKE 23 DTD FEDERAL COM

Well Number: 107H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

PLU_23_DTD_107H_DD_20211004090544.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

PLU_23_DTD_107H_cmt_20211004090549.pdf

Other Variance attachment:


PLU_23_DTD_BOP_Break_20210803062742.pdf

PLU_23_DTD_FH_20210803062714.pdf

PLU_23_DTD_MBS_20210803062722.pdf


PLU_23_DTD_OFCV_20210803062728.pdf

PLU_23_DTD_Spud_20210803062736.pdf



10M Choke Manifold Diagram
XTO

**Drilling Operations
Choke Manifold
10M Service**



[illegible]

TO the Editor of the LM the volume of the limited to the intermediate and the
 following table of the LM the volume of the limited to the intermediate and the


TO receive information. Official Lead will conduct data analysis and remove trace of the information from the traceable LM will be located and the record will be made and the TOC term will be cleared.

[illegible]

XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

Description of Operations:

1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
 - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
2. The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached.
3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. Spudder rig operations are expected to take 2-3 days per well on the pad.
5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
6. Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nipped up and tested on the wellhead before drilling operations resume on each well.
 - a. The larger rig will move back onto the location within 180 days from the point at which the wells are secured and the spudder rig is moved off location.
 - b. The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations
7. XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
8. Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area.



GATES E & S NORTH AMERICA, INC
DU-TEX
134 44TH STREET
CORPUS CHRISTI, TEXAS 78405

PHONE: 361-887-9807
FAX: 361-887-0812
EMAIL: crpe@s@gates.com
WEB: www.gates.com


GRADE D PRESSURE TEST CERTIFICATE


Customer :	AUSTIN DISTRIBUTING	Test Date:	6/8/2014
Customer Ref. :	PENDING	Hose Serial No.:	D-060814-1
Invoice No. :	201709	Created By:	NORMA
Product Description:	FD3.042.0R41/16.5KFLGE/E LE		
End Fitting 1 :	4 1/16 in.5K FLG	End Fitting 2 :	4 1/16 in.5K FLG
Gates Part No. :	4774-6001	Assembly Code :	L33090011513D-060814-1
Working Pressure :	5,000 PSI	Test Pressure :	7,500 PSI


Gates E & S North America, Inc. certifies that the following hose assembly has been tested to the Gates Oilfield Roughneck Agreement/Specification requirements and passed the 15 minute hydrostatic test per API Spec 7K/Q1, Fifth Edition, June 2010, Test pressure 9.6.7 and per Table 9 to 7,500 psi in accordance with this product number. Hose burst pressure 9.6.7.2 exceeds the minimum of 2.5 times the working pressure per Table 9.

Quality:	QUALITY	Technical Supervisor :	PRODUCTION
Date :	6/8/2014	Date :	6/8/2014
Signature :		Signature :	

Form PTC - 01 Rev.0 2







ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.

CACTUS WELLHEAD LLC			ALL DIMENSIONS APPROXIMATE		
20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead With 1 1" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers			XTO ENERGY INC ICARUS PAD		
DRAWN	DLE	18JAN21			
APPRV					
DRAWING NO.	HBE0000479				

XTO Permian Operating, LLC Offline Cementing Variance Request

XTO requests the option to cement the surface and intermediate casing strings offline as a prudent batch drilling efficiency of acreage development.


1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
2. Land casing with mandrel
3. Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static
4. Set annular packoff shown below and pressure test to confirm integrity of the seal. Pressure ratings of wellhead components and valves is 5,000 psi.
5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange.
 - a. If any barrier fails to test, the BOP stack will not be nipped down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified.




Annular packoff with both external and internal seals

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

6. Skid rig to next well on pad.
7. Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, casing outlet valves will provide access to both the casing ID and annulus. Rig or third party pump truck will kill well prior to cementing or nipping up for further remediation.
 - a. Well Control Plan
 - i. The Drillers Method will be the primary well control method to regain control of the wellbore prior to cementing, if wellbore conditions do not permit the drillers method other methods of well control may be used
 - ii. Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID
 - iii. A high pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - iv. Once influx is circulated out of the hole, kill weight mud will be circulated
 - v. Well will be confirmed static
 - vi. Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence
8. Install offline cement tool
9. Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request

Wellhead diagram during offline cementing operations

10. Circulate bottoms up with cement truck
 - a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - b. Max anticipated time before circulating with cement truck is 6 hrs
11. Perform cement job taking returns from the annulus wellhead valve
12. Confirm well is static and floats are holding after cement job
13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

Onshore Oil and Gas Order (OOGO) No. 2, Drilling Operations, Sections III.A.2.i.iv.B states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. OOGO No. 2, Section I.D.2 states, "Some situation may exist either on a well-by-well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO Energy feels the break testing the BOPE is such a situation. Therefore, as per OOGO No. 2, Section IV., XTO Energy submits this request for the variance.

Supporting Documentation

OOGO No. 2 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time there have been significant changes in drilling technology. BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since OOGO No. 2 was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. OOGO No. 2 recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, *Well Control Equipment Systems for Drilling Wells* (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states “A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component.” See Table C.4 below for reference.

62

API STANDARD 53

Table C.4—Initial Pressure Testing, Surface BOP Stacks

Component to be Pressure Tested	Pressure Test—Low Pressure ^{ac} psig (MPa)	Pressure Test—High Pressure ^{ac}	
		Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket
Annular preventer ^b	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.
Fixed pipe, variable bore, blind, and BSR preventers ^{bd}	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	ITP
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2.41)	RWP of side outlet valve or wellhead system, whichever is lower	ITP
Choke manifold—upstream of chokes ^e	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower	ITP
Choke manifold—downstream of chokes ^e	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or MASP for the well program, whichever is lower	
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	MASP for the well program	

^a Pressure test evaluation periods shall be a minimum of five minutes.

No visible leaks.

The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended test pressure.

^b Annular(s) and VBR(s) shall be pressure tested on the largest and smallest OD drill pipe to be used in well program.

^c For pad drilling operations, moving from one wellhead to another within the 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

^d For surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure vented during the initial test. For land operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure vented at commissioning and annually.

^e Adjustable chokes are not required to be full sealing devices. Pressure testing against a closed choke is not required.

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.


Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.

XTO Energy feels break testing and our current procedures meet the intent of OOGO No. 2 and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than that of OOGO No. 2 (Every 21 days). In addition to function testing the annular, pipe rams and blind rams after each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the OOGO No.2.

Procedures

1. XTO Energy will use this document for our break testing plan for New Mexico Delaware basin. The summary below will be referenced in the APD or Sundry Notice and receive approval prior to implementing this variance.
2. XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
 - a. A full BOP test will be conducted on the first well on the pad.
 - b. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
 - i. Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
 - ii. Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.
 - c. A Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
 - d. A full BOP test will be required prior to drilling any production hole.
3. After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
 - a. Between the HCV valve and choke line connection
 - b. Between the BOP quick connect and the wellhead
4. The BOP is then lifted and removed from the wellhead by a hydraulic system.
5. After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
6. The connections mentioned in 3a and 3b will then be reconnected.
7. Install test plug into the wellhead using test joint or drill pipe.
8. A shell test is performed against the upper pipe rams testing the two breaks.
9. The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
10. Function test will be performed on the following components: lower pipe rams, blind rams, and annular.

- Note: Picture below highlights BOP components that will be tested during batch operations*



A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.


Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to **ONLY** retest broken pressure seals if the following conditions are met:

1. After a full BOP test is conducted on the first well on the pad.
2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
4. Full BOP test will be required prior to drilling the production hole.

Only **ONE** test will occur during each break test procedure.

All valves in red including the upper pipe rams will be shut to test the broken connections.

** Each valve on choke manifold will alternate being tested against during each rig skid.



The connection between the HCV and kill line connection will **NOT** be broken on each skid and does not need to be retested.

The connection between the BOP stack / BOP Quick Connect and wellhead will be broken, as well as, the connection between the HCV and Choke Line on each skid and will be re-tested each time.



XTO Energy

**Eddy County, NM (NAD-27)
POKER LAKE UNIT 23 DTD
#107H**

Wellbore #1

Plan: PERMIT

Standard Planning Report

29 June, 2021



Project: Eddy County, NM (NAD-27)
Site: POKER LAKE UNIT 23 DTD
Well: #107H
Wellbore: Wellbore #1
Design: PERMIT

PROJECT DETAILS: Eddy County, NM (NAD-27)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

WELL DETAILS: #107H

Rig Name:		RKB = 30' @ 3473.00usft		Ground Level: 3443.00	
+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
0.00	0.00	441103.70	651206.80	32.2117658	-103.8444367

DESIGN TARGET DETAILS


Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
PLAT SHL #107H: 455' FSL, 606' FEL	0.00	0.00	0.00	441103.70	651206.80	32.2117658	-103.8444367	Point
PLAT BHL #107H: 200' FNL, 1430' FEL	11320.00	15165.60	-887.00	456269.30	650319.80	32.2534655	-103.8470826	Point
PLAT FTP #107H	11320.00	-359.70	-823.60	440744.00	650383.20	32.2107873	-103.8471048	Point
PLAT LTP #107H	11320.00	15035.60	-886.50	456139.30	650320.30	32.2531081	-103.8470829	Point

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2	2000.00	0.00	0.00	2000.00	0.00	0.00	0.00	0.00	0.00
3	2403.41	8.07	219.43	2402.08	-21.90	-18.01	2.00	219.43	-21.83
4	10771.89	8.07	219.43	10687.72	-929.07	-764.06	0.00	0.00	-925.99
5	11733.91	90.00	359.77	11320.00	-359.70	-823.60	10.00	140.05	-356.39
6	27129.34	90.00	359.77	11320.00	15035.60	-886.47	0.00	0.00	15039.04
7	27259.34	90.00	359.77	11320.00	15165.60	-887.00	0.00	0.00	15169.04

FORMATION TOP DETAILS

TVDPATH	Formation
470.00	Rustler
840.00	Top Salt
3860.00	Base Salt
4080.00	Delaware
5000.00	Cherry Canyon
6310.00	Brushy Canyon
7660.00	Basal Brushy Canyon
7960.00	Bone Spring Fm
8020.00	Bone Spring Lime
8050.00	Avalon Sand
8510.00	Lower Avalon Shale
8700.00	1st Bone Spring Lime
8920.00	1st Bone Spring Ss
9400.00	2nd Bone Spring Lime
9740.00	2nd Bone Spring Ss
9780.00	2nd Bone Spring T/B Carb
10090.00	3rd Bone Spring Lm
10890.00	3rd Bone Spring Ss
11185.00	Red Hills SS
11260.00	Wolfcamp
11290.00	Wolfcamp X
11320.00	LP





Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Project	Eddy County, NM (NAD-27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		

Site	POKER LAKE UNIT 23 DTD		
Site Position:		Northing:	441,023.90 usft
From:	Map	Easting:	646,650.40 usft
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "
		Latitude:	32.2116026
		Longitude:	-103.8591696
		Grid Convergence:	0.25 °

Well	#107H		
Well Position	+N/-S	79.80 usft	Northing:
	+E/-W	4,556.40 usft	Easting:
Position Uncertainty	0.00 usft	Wellhead Elevation:	0.00 usft
		Latitude:	32.2117659
		Longitude:	-103.8444367
		Ground Level:	3,443.00 usft

Wellbore	Wellbore #1		
Magnetics	Model Name	Sample Date	Declination (°)
	IGRF2020	06/29/21	6.67
			Dip Angle (°)
			59.85
			Field Strength (nT)
			47,454

Design	PERMIT		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth:
			0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)
	0.00	0.00	0.00
			Direction (°)
			359.77

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,403.41	8.07	219.43	2,402.08	-21.90	-18.01	2.00	2.00	0.00	219.43	
10,771.89	8.07	219.43	10,687.72	-929.07	-764.06	0.00	0.00	0.00	0.00	
11,733.91	90.00	359.77	11,320.00	-359.70	-823.60	10.00	8.52	14.59	140.05	PLAT FTP #107H
27,129.34	90.00	359.77	11,320.00	15,035.60	-886.47	0.00	0.00	0.00	0.00	PLAT LTP #107H
27,259.34	90.00	359.77	11,320.00	15,165.60	-887.00	0.00	0.00	0.00	0.00	PLAT BHL #107H: 1



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
470.00	0.00	0.00	470.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler									
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
840.00	0.00	0.00	840.00	0.00	0.00	0.00	0.00	0.00	0.00
Top Salt									
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	2.00	219.43	2,099.98	-1.35	-1.11	-1.34	2.00	2.00	0.00
2,200.00	4.00	219.43	2,199.84	-5.39	-4.43	-5.37	2.00	2.00	0.00
2,300.00	6.00	219.43	2,299.45	-12.12	-9.97	-12.08	2.00	2.00	0.00
2,403.41	8.07	219.43	2,402.08	-21.90	-18.01	-21.83	2.00	2.00	0.00
2,500.00	8.07	219.43	2,497.71	-32.37	-26.62	-32.26	0.00	0.00	0.00
2,600.00	8.07	219.43	2,596.72	-43.21	-35.54	-43.07	0.00	0.00	0.00
2,700.00	8.07	219.43	2,695.73	-54.05	-44.45	-53.87	0.00	0.00	0.00
2,800.00	8.07	219.43	2,794.74	-64.89	-53.37	-64.68	0.00	0.00	0.00
2,900.00	8.07	219.43	2,893.75	-75.73	-62.28	-75.48	0.00	0.00	0.00
3,000.00	8.07	219.43	2,992.76	-86.57	-71.20	-86.29	0.00	0.00	0.00
3,100.00	8.07	219.43	3,091.77	-97.41	-80.11	-97.09	0.00	0.00	0.00
3,200.00	8.07	219.43	3,190.78	-108.25	-89.03	-107.90	0.00	0.00	0.00
3,300.00	8.07	219.43	3,289.79	-119.09	-97.94	-118.70	0.00	0.00	0.00
3,400.00	8.07	219.43	3,388.80	-129.93	-106.86	-129.50	0.00	0.00	0.00
3,500.00	8.07	219.43	3,487.81	-140.77	-115.77	-140.31	0.00	0.00	0.00
3,600.00	8.07	219.43	3,586.82	-151.61	-124.69	-151.11	0.00	0.00	0.00
3,700.00	8.07	219.43	3,685.83	-162.46	-133.60	-161.92	0.00	0.00	0.00
3,800.00	8.07	219.43	3,784.84	-173.30	-142.52	-172.72	0.00	0.00	0.00
3,875.91	8.07	219.43	3,860.00	-181.52	-149.28	-180.92	0.00	0.00	0.00
Base Salt									
3,900.00	8.07	219.43	3,883.85	-184.14	-151.43	-183.53	0.00	0.00	0.00
4,000.00	8.07	219.43	3,982.86	-194.98	-160.35	-194.33	0.00	0.00	0.00
4,098.11	8.07	219.43	4,080.00	-205.61	-169.09	-204.93	0.00	0.00	0.00
Delaware									
4,100.00	8.07	219.43	4,081.87	-205.82	-169.26	-205.13	0.00	0.00	0.00
4,200.00	8.07	219.43	4,180.88	-216.66	-178.18	-215.94	0.00	0.00	0.00
4,300.00	8.07	219.43	4,279.89	-227.50	-187.09	-226.74	0.00	0.00	0.00
4,400.00	8.07	219.43	4,378.91	-238.34	-196.01	-237.55	0.00	0.00	0.00
4,500.00	8.07	219.43	4,477.92	-249.18	-204.92	-248.35	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,600.00	8.07	219.43	4,576.93	-260.02	-213.84	-259.16	0.00	0.00	0.00
4,700.00	8.07	219.43	4,675.94	-270.86	-222.75	-269.96	0.00	0.00	0.00
4,800.00	8.07	219.43	4,774.95	-281.70	-231.67	-280.77	0.00	0.00	0.00
4,900.00	8.07	219.43	4,873.96	-292.54	-240.58	-291.57	0.00	0.00	0.00
5,000.00	8.07	219.43	4,972.97	-303.38	-249.50	-302.37	0.00	0.00	0.00
5,027.30	8.07	219.43	5,000.00	-306.34	-251.93	-305.32	0.00	0.00	0.00
Cherry Canyon									
5,100.00	8.07	219.43	5,071.98	-314.22	-258.41	-313.18	0.00	0.00	0.00
5,200.00	8.07	219.43	5,170.99	-325.06	-267.33	-323.98	0.00	0.00	0.00
5,300.00	8.07	219.43	5,270.00	-335.90	-276.24	-334.79	0.00	0.00	0.00
5,400.00	8.07	219.43	5,369.01	-346.74	-285.16	-345.59	0.00	0.00	0.00
5,500.00	8.07	219.43	5,468.02	-357.58	-294.07	-356.40	0.00	0.00	0.00
5,600.00	8.07	219.43	5,567.03	-368.42	-302.99	-367.20	0.00	0.00	0.00
5,700.00	8.07	219.43	5,666.04	-379.26	-311.90	-378.00	0.00	0.00	0.00
5,800.00	8.07	219.43	5,765.05	-390.10	-320.82	-388.81	0.00	0.00	0.00
5,900.00	8.07	219.43	5,864.06	-400.94	-329.73	-399.61	0.00	0.00	0.00
6,000.00	8.07	219.43	5,963.07	-411.78	-338.65	-410.42	0.00	0.00	0.00
6,100.00	8.07	219.43	6,062.08	-422.62	-347.56	-421.22	0.00	0.00	0.00
6,200.00	8.07	219.43	6,161.09	-433.46	-356.48	-432.03	0.00	0.00	0.00
6,300.00	8.07	219.43	6,260.10	-444.30	-365.39	-442.83	0.00	0.00	0.00
6,350.40	8.07	219.43	6,310.00	-449.77	-369.89	-448.28	0.00	0.00	0.00
Brushy Canyon									
6,400.00	8.07	219.43	6,359.11	-455.14	-374.31	-453.64	0.00	0.00	0.00
6,500.00	8.07	219.43	6,458.12	-465.98	-383.22	-464.44	0.00	0.00	0.00
6,600.00	8.07	219.43	6,557.13	-476.82	-392.14	-475.24	0.00	0.00	0.00
6,700.00	8.07	219.43	6,656.14	-487.66	-401.05	-486.05	0.00	0.00	0.00
6,800.00	8.07	219.43	6,755.15	-498.50	-409.97	-496.85	0.00	0.00	0.00
6,900.00	8.07	219.43	6,854.16	-509.34	-418.88	-507.66	0.00	0.00	0.00
7,000.00	8.07	219.43	6,953.17	-520.18	-427.80	-518.46	0.00	0.00	0.00
7,100.00	8.07	219.43	7,052.18	-531.02	-436.71	-529.27	0.00	0.00	0.00
7,200.00	8.07	219.43	7,151.19	-541.86	-445.63	-540.07	0.00	0.00	0.00
7,300.00	8.07	219.43	7,250.20	-552.70	-454.54	-550.87	0.00	0.00	0.00
7,400.00	8.07	219.43	7,349.21	-563.54	-463.46	-561.68	0.00	0.00	0.00
7,500.00	8.07	219.43	7,448.22	-574.38	-472.37	-572.48	0.00	0.00	0.00
7,600.00	8.07	219.43	7,547.23	-585.22	-481.29	-583.29	0.00	0.00	0.00
7,700.00	8.07	219.43	7,646.24	-596.07	-490.20	-594.09	0.00	0.00	0.00
7,713.90	8.07	219.43	7,660.00	-597.57	-491.44	-595.59	0.00	0.00	0.00
Basal Brushy Canyon									
7,800.00	8.07	219.43	7,745.25	-606.91	-499.12	-604.90	0.00	0.00	0.00
7,900.00	8.07	219.43	7,844.26	-617.75	-508.03	-615.70	0.00	0.00	0.00
8,000.00	8.07	219.43	7,943.27	-628.59	-516.95	-626.51	0.00	0.00	0.00
8,016.90	8.07	219.43	7,960.00	-630.42	-518.45	-628.33	0.00	0.00	0.00
Bone Spring Fm									
8,077.50	8.07	219.43	8,020.00	-636.99	-523.86	-634.88	0.00	0.00	0.00
Bone Spring Lime									
8,100.00	8.07	219.43	8,042.28	-639.43	-525.86	-637.31	0.00	0.00	0.00
8,107.80	8.07	219.43	8,050.00	-640.27	-526.56	-638.15	0.00	0.00	0.00
Avalon Sand									
8,200.00	8.07	219.43	8,141.29	-650.27	-534.78	-648.11	0.00	0.00	0.00
8,300.00	8.07	219.43	8,240.30	-661.11	-543.69	-658.92	0.00	0.00	0.00
8,400.00	8.07	219.43	8,339.31	-671.95	-552.61	-669.72	0.00	0.00	0.00
8,500.00	8.07	219.43	8,438.32	-682.79	-561.52	-680.53	0.00	0.00	0.00
8,572.40	8.07	219.43	8,510.00	-690.63	-567.98	-688.35	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
Lower Avalon Shale									
8,600.00	8.07	219.43	8,537.33	-693.63	-570.44	-691.33	0.00	0.00	0.00
8,700.00	8.07	219.43	8,636.34	-704.47	-579.35	-702.14	0.00	0.00	0.00
8,764.29	8.07	219.43	8,700.00	-711.44	-585.08	-709.08	0.00	0.00	0.00
1st Bone Spring Lime									
8,800.00	8.07	219.43	8,735.35	-715.31	-588.27	-712.94	0.00	0.00	0.00
8,900.00	8.07	219.43	8,834.36	-726.15	-597.18	-723.75	0.00	0.00	0.00
8,986.49	8.07	219.43	8,920.00	-735.52	-604.89	-733.09	0.00	0.00	0.00
1st Bone Spring Ss									
9,000.00	8.07	219.43	8,933.37	-736.99	-606.10	-734.55	0.00	0.00	0.00
9,100.00	8.07	219.43	9,032.38	-747.83	-615.01	-745.35	0.00	0.00	0.00
9,200.00	8.07	219.43	9,131.39	-758.67	-623.93	-756.16	0.00	0.00	0.00
9,300.00	8.07	219.43	9,230.40	-769.51	-632.84	-766.96	0.00	0.00	0.00
9,400.00	8.07	219.43	9,329.41	-780.35	-641.76	-777.77	0.00	0.00	0.00
9,471.29	8.07	219.43	9,400.00	-788.08	-648.11	-785.47	0.00	0.00	0.00
2nd Bone Spring Lime									
9,500.00	8.07	219.43	9,428.42	-791.19	-650.67	-788.57	0.00	0.00	0.00
9,600.00	8.07	219.43	9,527.43	-802.03	-659.59	-799.38	0.00	0.00	0.00
9,700.00	8.07	219.43	9,626.44	-812.87	-668.50	-810.18	0.00	0.00	0.00
9,800.00	8.07	219.43	9,725.45	-823.71	-677.42	-820.98	0.00	0.00	0.00
9,814.69	8.07	219.43	9,740.00	-825.30	-678.73	-822.57	0.00	0.00	0.00
2nd Bone Spring Ss									
9,855.09	8.07	219.43	9,780.00	-829.68	-682.33	-826.94	0.00	0.00	0.00
2nd Bone Spring T/B Carb									
9,900.00	8.07	219.43	9,824.46	-834.55	-686.33	-831.79	0.00	0.00	0.00
10,000.00	8.07	219.43	9,923.47	-845.39	-695.25	-842.59	0.00	0.00	0.00
10,100.00	8.07	219.43	10,022.48	-856.23	-704.16	-853.40	0.00	0.00	0.00
10,168.19	8.07	219.43	10,090.00	-863.62	-710.24	-860.77	0.00	0.00	0.00
3rd Bone Spring Lm									
10,200.00	8.07	219.43	10,121.49	-867.07	-713.08	-864.20	0.00	0.00	0.00
10,300.00	8.07	219.43	10,220.50	-877.91	-721.99	-875.01	0.00	0.00	0.00
10,400.00	8.07	219.43	10,319.51	-888.75	-730.91	-885.81	0.00	0.00	0.00
10,500.00	8.07	219.43	10,418.53	-899.59	-739.82	-896.62	0.00	0.00	0.00
10,600.00	8.07	219.43	10,517.54	-910.43	-748.74	-907.42	0.00	0.00	0.00
10,700.00	8.07	219.43	10,616.55	-921.27	-757.65	-918.22	0.00	0.00	0.00
10,771.89	8.07	219.43	10,687.72	-929.07	-764.06	-925.99	0.00	0.00	0.00
10,800.00	6.18	236.44	10,715.62	-931.43	-766.58	-928.34	10.00	-6.71	60.50
10,850.00	5.41	287.07	10,765.39	-932.22	-771.08	-929.12	10.00	-1.53	101.27
10,900.00	8.38	321.89	10,815.05	-928.66	-775.58	-925.54	10.00	5.94	69.63
10,950.00	12.69	336.08	10,864.20	-920.76	-780.06	-917.63	10.00	8.62	28.38
10,976.58	15.16	340.25	10,890.00	-914.82	-782.42	-911.67	10.00	9.27	15.69
3rd Bone Spring Ss									
11,000.00	17.37	342.95	10,912.48	-908.60	-784.48	-905.44	10.00	9.47	11.54
11,050.00	22.19	346.95	10,959.52	-892.25	-788.81	-889.08	10.00	9.63	7.99
11,100.00	27.07	349.57	11,004.95	-871.85	-793.00	-868.66	10.00	9.76	5.24
11,150.00	31.99	351.44	11,048.45	-847.55	-797.04	-844.35	10.00	9.83	3.73
11,200.00	36.92	352.85	11,089.67	-819.54	-800.88	-816.32	10.00	9.87	2.83
11,250.00	41.87	353.97	11,128.29	-788.02	-804.50	-784.79	10.00	9.90	2.24
11,300.00	46.83	354.90	11,164.04	-753.25	-807.88	-750.00	10.00	9.92	1.85
11,331.58	49.96	355.41	11,185.00	-729.72	-809.87	-726.47	10.00	9.93	1.61
Red Hills SS									
11,350.00	51.79	355.68	11,196.62	-715.47	-810.98	-712.21	10.00	9.93	1.50
11,400.00	56.76	356.37	11,225.81	-674.99	-813.79	-671.72	10.00	9.94	1.37



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,450.00	61.73	356.98	11,251.37	-632.11	-816.28	-628.83	10.00	9.94	1.22
11,468.81	63.61	357.19	11,260.00	-615.42	-817.13	-612.14	10.00	9.95	1.14
Wolfcamp									
11,500.00	66.71	357.53	11,273.10	-587.15	-818.43	-583.86	10.00	9.95	1.09
11,547.30	71.42	358.02	11,290.00	-543.02	-820.14	-539.72	10.00	9.95	1.03
Wolfcamp X									
11,550.00	71.69	358.05	11,290.85	-540.46	-820.22	-537.16	10.00	9.95	1.00
11,600.00	76.66	358.54	11,304.49	-492.39	-821.65	-489.09	10.00	9.96	0.97
11,650.00	81.64	359.00	11,313.89	-443.31	-822.71	-440.00	10.00	9.96	0.93
11,700.00	86.62	359.46	11,319.00	-393.59	-823.37	-390.28	10.00	9.96	0.91
11,733.91	90.00	359.77	11,320.00	-359.70	-823.60	-356.39	10.00	9.96	0.90
LP									
11,800.00	90.00	359.77	11,320.00	-293.61	-823.87	-290.30	0.00	0.00	0.00
11,900.00	90.00	359.77	11,320.00	-193.61	-824.28	-190.30	0.00	0.00	0.00
12,000.00	90.00	359.77	11,320.00	-93.62	-824.69	-90.30	0.00	0.00	0.00
12,100.00	90.00	359.77	11,320.00	6.38	-825.09	9.70	0.00	0.00	0.00
12,200.00	90.00	359.77	11,320.00	106.38	-825.50	109.70	0.00	0.00	0.00
12,300.00	90.00	359.77	11,320.00	206.38	-825.91	209.70	0.00	0.00	0.00
12,400.00	90.00	359.77	11,320.00	306.38	-826.32	309.70	0.00	0.00	0.00
12,500.00	90.00	359.77	11,320.00	406.38	-826.73	409.70	0.00	0.00	0.00
12,600.00	90.00	359.77	11,320.00	506.38	-827.14	509.70	0.00	0.00	0.00
12,700.00	90.00	359.77	11,320.00	606.38	-827.55	609.70	0.00	0.00	0.00
12,800.00	90.00	359.77	11,320.00	706.38	-827.95	709.70	0.00	0.00	0.00
12,900.00	90.00	359.77	11,320.00	806.38	-828.36	809.70	0.00	0.00	0.00
13,000.00	90.00	359.77	11,320.00	906.38	-828.77	909.70	0.00	0.00	0.00
13,100.00	90.00	359.77	11,320.00	1,006.38	-829.18	1,009.70	0.00	0.00	0.00
13,200.00	90.00	359.77	11,320.00	1,106.37	-829.59	1,109.70	0.00	0.00	0.00
13,300.00	90.00	359.77	11,320.00	1,206.37	-830.00	1,209.70	0.00	0.00	0.00
13,400.00	90.00	359.77	11,320.00	1,306.37	-830.40	1,309.70	0.00	0.00	0.00
13,500.00	90.00	359.77	11,320.00	1,406.37	-830.81	1,409.70	0.00	0.00	0.00
13,600.00	90.00	359.77	11,320.00	1,506.37	-831.22	1,509.70	0.00	0.00	0.00
13,700.00	90.00	359.77	11,320.00	1,606.37	-831.63	1,609.70	0.00	0.00	0.00
13,800.00	90.00	359.77	11,320.00	1,706.37	-832.04	1,709.70	0.00	0.00	0.00
13,900.00	90.00	359.77	11,320.00	1,806.37	-832.45	1,809.70	0.00	0.00	0.00
14,000.00	90.00	359.77	11,320.00	1,906.37	-832.85	1,909.70	0.00	0.00	0.00
14,100.00	90.00	359.77	11,320.00	2,006.37	-833.26	2,009.70	0.00	0.00	0.00
14,200.00	90.00	359.77	11,320.00	2,106.37	-833.67	2,109.70	0.00	0.00	0.00
14,300.00	90.00	359.77	11,320.00	2,206.37	-834.08	2,209.70	0.00	0.00	0.00
14,400.00	90.00	359.77	11,320.00	2,306.36	-834.49	2,309.70	0.00	0.00	0.00
14,500.00	90.00	359.77	11,320.00	2,406.36	-834.90	2,409.70	0.00	0.00	0.00
14,600.00	90.00	359.77	11,320.00	2,506.36	-835.30	2,509.70	0.00	0.00	0.00
14,700.00	90.00	359.77	11,320.00	2,606.36	-835.71	2,609.70	0.00	0.00	0.00
14,800.00	90.00	359.77	11,320.00	2,706.36	-836.12	2,709.70	0.00	0.00	0.00
14,900.00	90.00	359.77	11,320.00	2,806.36	-836.53	2,809.70	0.00	0.00	0.00
15,000.00	90.00	359.77	11,320.00	2,906.36	-836.94	2,909.70	0.00	0.00	0.00
15,100.00	90.00	359.77	11,320.00	3,006.36	-837.35	3,009.70	0.00	0.00	0.00
15,200.00	90.00	359.77	11,320.00	3,106.36	-837.75	3,109.70	0.00	0.00	0.00
15,300.00	90.00	359.77	11,320.00	3,206.36	-838.16	3,209.70	0.00	0.00	0.00
15,400.00	90.00	359.77	11,320.00	3,306.36	-838.57	3,309.70	0.00	0.00	0.00
15,500.00	90.00	359.77	11,320.00	3,406.36	-838.98	3,409.70	0.00	0.00	0.00
15,600.00	90.00	359.77	11,320.00	3,506.35	-839.39	3,509.70	0.00	0.00	0.00
15,700.00	90.00	359.77	11,320.00	3,606.35	-839.80	3,609.70	0.00	0.00	0.00
15,800.00	90.00	359.77	11,320.00	3,706.35	-840.20	3,709.70	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,900.00	90.00	359.77	11,320.00	3,806.35	-840.61	3,809.70	0.00	0.00	0.00
16,000.00	90.00	359.77	11,320.00	3,906.35	-841.02	3,909.70	0.00	0.00	0.00
16,100.00	90.00	359.77	11,320.00	4,006.35	-841.43	4,009.70	0.00	0.00	0.00
16,200.00	90.00	359.77	11,320.00	4,106.35	-841.84	4,109.70	0.00	0.00	0.00
16,300.00	90.00	359.77	11,320.00	4,206.35	-842.25	4,209.70	0.00	0.00	0.00
16,400.00	90.00	359.77	11,320.00	4,306.35	-842.65	4,309.70	0.00	0.00	0.00
16,500.00	90.00	359.77	11,320.00	4,406.35	-843.06	4,409.70	0.00	0.00	0.00
16,600.00	90.00	359.77	11,320.00	4,506.35	-843.47	4,509.70	0.00	0.00	0.00
16,700.00	90.00	359.77	11,320.00	4,606.35	-843.88	4,609.70	0.00	0.00	0.00
16,800.00	90.00	359.77	11,320.00	4,706.34	-844.29	4,709.70	0.00	0.00	0.00
16,900.00	90.00	359.77	11,320.00	4,806.34	-844.70	4,809.70	0.00	0.00	0.00
17,000.00	90.00	359.77	11,320.00	4,906.34	-845.10	4,909.70	0.00	0.00	0.00
17,100.00	90.00	359.77	11,320.00	5,006.34	-845.51	5,009.70	0.00	0.00	0.00
17,200.00	90.00	359.77	11,320.00	5,106.34	-845.92	5,109.70	0.00	0.00	0.00
17,300.00	90.00	359.77	11,320.00	5,206.34	-846.33	5,209.70	0.00	0.00	0.00
17,400.00	90.00	359.77	11,320.00	5,306.34	-846.74	5,309.70	0.00	0.00	0.00
17,500.00	90.00	359.77	11,320.00	5,406.34	-847.15	5,409.70	0.00	0.00	0.00
17,600.00	90.00	359.77	11,320.00	5,506.34	-847.55	5,509.70	0.00	0.00	0.00
17,700.00	90.00	359.77	11,320.00	5,606.34	-847.96	5,609.70	0.00	0.00	0.00
17,800.00	90.00	359.77	11,320.00	5,706.34	-848.37	5,709.70	0.00	0.00	0.00
17,900.00	90.00	359.77	11,320.00	5,806.34	-848.78	5,809.70	0.00	0.00	0.00
18,000.00	90.00	359.77	11,320.00	5,906.33	-849.19	5,909.70	0.00	0.00	0.00
18,100.00	90.00	359.77	11,320.00	6,006.33	-849.60	6,009.70	0.00	0.00	0.00
18,200.00	90.00	359.77	11,320.00	6,106.33	-850.01	6,109.70	0.00	0.00	0.00
18,300.00	90.00	359.77	11,320.00	6,206.33	-850.41	6,209.70	0.00	0.00	0.00
18,400.00	90.00	359.77	11,320.00	6,306.33	-850.82	6,309.70	0.00	0.00	0.00
18,500.00	90.00	359.77	11,320.00	6,406.33	-851.23	6,409.70	0.00	0.00	0.00
18,600.00	90.00	359.77	11,320.00	6,506.33	-851.64	6,509.70	0.00	0.00	0.00
18,700.00	90.00	359.77	11,320.00	6,606.33	-852.05	6,609.70	0.00	0.00	0.00
18,800.00	90.00	359.77	11,320.00	6,706.33	-852.46	6,709.70	0.00	0.00	0.00
18,900.00	90.00	359.77	11,320.00	6,806.33	-852.86	6,809.70	0.00	0.00	0.00
19,000.00	90.00	359.77	11,320.00	6,906.33	-853.27	6,909.70	0.00	0.00	0.00
19,100.00	90.00	359.77	11,320.00	7,006.33	-853.68	7,009.70	0.00	0.00	0.00
19,200.00	90.00	359.77	11,320.00	7,106.32	-854.09	7,109.70	0.00	0.00	0.00
19,300.00	90.00	359.77	11,320.00	7,206.32	-854.50	7,209.70	0.00	0.00	0.00
19,400.00	90.00	359.77	11,320.00	7,306.32	-854.91	7,309.70	0.00	0.00	0.00
19,500.00	90.00	359.77	11,320.00	7,406.32	-855.31	7,409.70	0.00	0.00	0.00
19,600.00	90.00	359.77	11,320.00	7,506.32	-855.72	7,509.70	0.00	0.00	0.00
19,700.00	90.00	359.77	11,320.00	7,606.32	-856.13	7,609.70	0.00	0.00	0.00
19,800.00	90.00	359.77	11,320.00	7,706.32	-856.54	7,709.70	0.00	0.00	0.00
19,900.00	90.00	359.77	11,320.00	7,806.32	-856.95	7,809.70	0.00	0.00	0.00
20,000.00	90.00	359.77	11,320.00	7,906.32	-857.36	7,909.70	0.00	0.00	0.00
20,100.00	90.00	359.77	11,320.00	8,006.32	-857.76	8,009.70	0.00	0.00	0.00
20,200.00	90.00	359.77	11,320.00	8,106.32	-858.17	8,109.70	0.00	0.00	0.00
20,300.00	90.00	359.77	11,320.00	8,206.32	-858.58	8,209.70	0.00	0.00	0.00
20,400.00	90.00	359.77	11,320.00	8,306.31	-858.99	8,309.70	0.00	0.00	0.00
20,500.00	90.00	359.77	11,320.00	8,406.31	-859.40	8,409.70	0.00	0.00	0.00
20,600.00	90.00	359.77	11,320.00	8,506.31	-859.81	8,509.70	0.00	0.00	0.00
20,700.00	90.00	359.77	11,320.00	8,606.31	-860.21	8,609.70	0.00	0.00	0.00
20,800.00	90.00	359.77	11,320.00	8,706.31	-860.62	8,709.70	0.00	0.00	0.00
20,900.00	90.00	359.77	11,320.00	8,806.31	-861.03	8,809.70	0.00	0.00	0.00
21,000.00	90.00	359.77	11,320.00	8,906.31	-861.44	8,909.70	0.00	0.00	0.00
21,100.00	90.00	359.77	11,320.00	9,006.31	-861.85	9,009.70	0.00	0.00	0.00
21,200.00	90.00	359.77	11,320.00	9,106.31	-862.26	9,109.70	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
21,300.00	90.00	359.77	11,320.00	9,206.31	-862.66	9,209.70	0.00	0.00	0.00
21,400.00	90.00	359.77	11,320.00	9,306.31	-863.07	9,309.70	0.00	0.00	0.00
21,500.00	90.00	359.77	11,320.00	9,406.31	-863.48	9,409.70	0.00	0.00	0.00
21,600.00	90.00	359.77	11,320.00	9,506.30	-863.89	9,509.70	0.00	0.00	0.00
21,700.00	90.00	359.77	11,320.00	9,606.30	-864.30	9,609.70	0.00	0.00	0.00
21,800.00	90.00	359.77	11,320.00	9,706.30	-864.71	9,709.70	0.00	0.00	0.00
21,900.00	90.00	359.77	11,320.00	9,806.30	-865.11	9,809.70	0.00	0.00	0.00
22,000.00	90.00	359.77	11,320.00	9,906.30	-865.52	9,909.70	0.00	0.00	0.00
22,100.00	90.00	359.77	11,320.00	10,006.30	-865.93	10,009.70	0.00	0.00	0.00
22,200.00	90.00	359.77	11,320.00	10,106.30	-866.34	10,109.70	0.00	0.00	0.00
22,300.00	90.00	359.77	11,320.00	10,206.30	-866.75	10,209.70	0.00	0.00	0.00
22,400.00	90.00	359.77	11,320.00	10,306.30	-867.16	10,309.70	0.00	0.00	0.00
22,500.00	90.00	359.77	11,320.00	10,406.30	-867.56	10,409.70	0.00	0.00	0.00
22,600.00	90.00	359.77	11,320.00	10,506.30	-867.97	10,509.70	0.00	0.00	0.00
22,700.00	90.00	359.77	11,320.00	10,606.30	-868.38	10,609.70	0.00	0.00	0.00
22,800.00	90.00	359.77	11,320.00	10,706.29	-868.79	10,709.70	0.00	0.00	0.00
22,900.00	90.00	359.77	11,320.00	10,806.29	-869.20	10,809.70	0.00	0.00	0.00
23,000.00	90.00	359.77	11,320.00	10,906.29	-869.61	10,909.70	0.00	0.00	0.00
23,100.00	90.00	359.77	11,320.00	11,006.29	-870.01	11,009.70	0.00	0.00	0.00
23,200.00	90.00	359.77	11,320.00	11,106.29	-870.42	11,109.70	0.00	0.00	0.00
23,300.00	90.00	359.77	11,320.00	11,206.29	-870.83	11,209.70	0.00	0.00	0.00
23,400.00	90.00	359.77	11,320.00	11,306.29	-871.24	11,309.70	0.00	0.00	0.00
23,500.00	90.00	359.77	11,320.00	11,406.29	-871.65	11,409.70	0.00	0.00	0.00
23,600.00	90.00	359.77	11,320.00	11,506.29	-872.06	11,509.70	0.00	0.00	0.00
23,700.00	90.00	359.77	11,320.00	11,606.29	-872.47	11,609.70	0.00	0.00	0.00
23,800.00	90.00	359.77	11,320.00	11,706.29	-872.87	11,709.70	0.00	0.00	0.00
23,900.00	90.00	359.77	11,320.00	11,806.29	-873.28	11,809.70	0.00	0.00	0.00
24,000.00	90.00	359.77	11,320.00	11,906.28	-873.69	11,909.70	0.00	0.00	0.00
24,100.00	90.00	359.77	11,320.00	12,006.28	-874.10	12,009.70	0.00	0.00	0.00
24,200.00	90.00	359.77	11,320.00	12,106.28	-874.51	12,109.70	0.00	0.00	0.00
24,300.00	90.00	359.77	11,320.00	12,206.28	-874.92	12,209.70	0.00	0.00	0.00
24,400.00	90.00	359.77	11,320.00	12,306.28	-875.32	12,309.70	0.00	0.00	0.00
24,500.00	90.00	359.77	11,320.00	12,406.28	-875.73	12,409.70	0.00	0.00	0.00
24,600.00	90.00	359.77	11,320.00	12,506.28	-876.14	12,509.70	0.00	0.00	0.00
24,700.00	90.00	359.77	11,320.00	12,606.28	-876.55	12,609.70	0.00	0.00	0.00
24,800.00	90.00	359.77	11,320.00	12,706.28	-876.96	12,709.70	0.00	0.00	0.00
24,900.00	90.00	359.77	11,320.00	12,806.28	-877.37	12,809.70	0.00	0.00	0.00
25,000.00	90.00	359.77	11,320.00	12,906.28	-877.77	12,909.70	0.00	0.00	0.00
25,100.00	90.00	359.77	11,320.00	13,006.28	-878.18	13,009.70	0.00	0.00	0.00
25,200.00	90.00	359.77	11,320.00	13,106.28	-878.59	13,109.70	0.00	0.00	0.00
25,300.00	90.00	359.77	11,320.00	13,206.27	-879.00	13,209.70	0.00	0.00	0.00
25,400.00	90.00	359.77	11,320.00	13,306.27	-879.41	13,309.70	0.00	0.00	0.00
25,500.00	90.00	359.77	11,320.00	13,406.27	-879.82	13,409.70	0.00	0.00	0.00
25,600.00	90.00	359.77	11,320.00	13,506.27	-880.22	13,509.70	0.00	0.00	0.00
25,700.00	90.00	359.77	11,320.00	13,606.27	-880.63	13,609.70	0.00	0.00	0.00
25,800.00	90.00	359.77	11,320.00	13,706.27	-881.04	13,709.70	0.00	0.00	0.00
25,900.00	90.00	359.77	11,320.00	13,806.27	-881.45	13,809.70	0.00	0.00	0.00
26,000.00	90.00	359.77	11,320.00	13,906.27	-881.86	13,909.70	0.00	0.00	0.00
26,100.00	90.00	359.77	11,320.00	14,006.27	-882.27	14,009.70	0.00	0.00	0.00
26,200.00	90.00	359.77	11,320.00	14,106.27	-882.67	14,109.70	0.00	0.00	0.00
26,300.00	90.00	359.77	11,320.00	14,206.27	-883.08	14,209.70	0.00	0.00	0.00
26,400.00	90.00	359.77	11,320.00	14,306.27	-883.49	14,309.70	0.00	0.00	0.00
26,500.00	90.00	359.77	11,320.00	14,406.26	-883.90	14,409.70	0.00	0.00	0.00
26,600.00	90.00	359.77	11,320.00	14,506.26	-884.31	14,509.70	0.00	0.00	0.00



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
26,700.00	90.00	359.77	11,320.00	14,606.26	-884.72	14,609.70	0.00	0.00	0.00
26,800.00	90.00	359.77	11,320.00	14,706.26	-885.12	14,709.70	0.00	0.00	0.00
26,900.00	90.00	359.77	11,320.00	14,806.26	-885.53	14,809.70	0.00	0.00	0.00
27,000.00	90.00	359.77	11,320.00	14,906.26	-885.94	14,909.70	0.00	0.00	0.00
27,100.00	90.00	359.77	11,320.00	15,006.26	-886.35	15,009.70	0.00	0.00	0.00
27,129.34	90.00	359.77	11,320.00	15,035.60	-886.47	15,039.04	0.00	0.00	0.00
27,200.00	90.00	359.77	11,320.00	15,106.26	-886.76	15,109.70	0.00	0.00	0.00
27,259.34	90.00	359.77	11,320.00	15,165.60	-887.00	15,169.04	0.00	0.00	0.00

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PLAT SHL #107H: 45'	0.00	0.00	0.00	0.00	0.00	441,103.70	651,206.80	32.2117659	-103.8444367
- plan hits target center									
- Point									
PLAT BHL #107H: 20'	0.00	0.00	11,320.00	15,165.60	-887.00	456,269.30	650,319.80	32.2534655	-103.8470826
- plan hits target center									
- Point									
PLAT FTP #107H	0.00	0.00	11,320.00	-359.70	-823.60	440,744.00	650,383.20	32.2107873	-103.8471048
- plan hits target center									
- Point									
PLAT LTP #107H	0.00	0.00	11,320.00	15,035.60	-886.50	456,139.30	650,320.30	32.2531082	-103.8470829
- plan misses target center by 0.03usft at 27129.34usft MD (11320.00 TVD, 15035.60 N, -886.47 E)									
- Point									



Planning Report

Database:	EDM 5000.1.13 Single User Db	Local Co-ordinate Reference:	Well #107H
Company:	XTO Energy	TVD Reference:	RKB = 30' @ 3473.00usft
Project:	Eddy County, NM (NAD-27)	MD Reference:	RKB = 30' @ 3473.00usft
Site:	POKER LAKE UNIT 23 DTD	North Reference:	Grid
Well:	#107H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	PERMIT		

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
470.00	470.00	Rustler			
840.00	840.00	Top Salt			
3,875.91	3,860.00	Base Salt			
4,098.11	4,080.00	Delaware			
5,027.30	5,000.00	Cherry Canyon			
6,350.40	6,310.00	Brushy Canyon			
7,713.90	7,660.00	Basal Brushy Canyon			
8,016.90	7,960.00	Bone Spring Fm			
8,077.50	8,020.00	Bone Spring Lime			
8,107.80	8,050.00	Avalon Sand			
8,572.40	8,510.00	Lower Avalon Shale			
8,764.29	8,700.00	1st Bone Spring Lime			
8,986.49	8,920.00	1st Bone Spring Ss			
9,471.29	9,400.00	2nd Bone Spring Lime			
9,814.69	9,740.00	2nd Bone Spring Ss			
9,855.09	9,780.00	2nd Bone Spring T/B Carb			
10,168.19	10,090.00	3rd Bone Spring Lm			
10,976.58	10,890.00	3rd Bone Spring Ss			
11,331.58	11,185.00	Red Hills SS			
11,468.81	11,260.00	Wolfcamp			
11,547.30	11,290.00	Wolfcamp X			
11,733.91	11,320.00	LP			

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	XTO Permian Operating, LLC
LEASE NO.:	NMNM-068905
WELL NAME & NO.:	Poker Lake 23 DTD Federal Com 107H
SURFACE HOLE FOOTAGE:	0455' FSL & 0606' FEL
BOTTOM HOLE FOOTAGE:	0200' FNL & 1430' FEL Sec. 02, T.24 S., R.30 E.
LOCATION:	Section 14, T.24 S., R.30 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	☐ Yes	☒ No	
Potash	☒ None	☐ Secretary	☐ R-111-P
Cave/Karst Potential	☒ Low	☐ Medium	☐ High
Cave/Karst Potential	☐ Critical		
Variance	☐ None	☒ Flex Hose	☐ Other
Wellhead	☐ Conventional	☒ Multibowl	☐ Both
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP
Other	☒ Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	☒ COM	☐ Unit

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Red Beds, Rustler, and Delaware.

Abnormal pressure may be encountered in the 3rd Bone Spring and all subsequent formations.

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **9-5/8** inch surface casing shall be set at approximately **740** feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **7-5/8** inch intermediate casing is:
 - Cement to surface. If cement does not circulate see B.1.a, c-d above.
3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance approved to use a 5M annular. The annular must be tested to 70% working pressure (3500 psi.)**
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

BOP Break Testing Variance

- Shell testing is not approved for any portion of the hole with a MASP of 5000 psi or greater.
- While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Any well control event while drilling require notification to the BLM Petroleum Engineer prior to the commencement of any BOP Break Testing operations.
- A full BOP test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOP test will be required.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
4. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
5. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
6. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.


D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 03162022

H2S Briefing Areas and Alarm Locations





HYDROGEN SULFIDE (H₂S) CONTINGENCY PLAN

Assumed 100 ppm ROE □ 3000'

m² o e r a o all r e r a a o o l a

Emergency Procedures

ee eo a rele e o a o a , e r r e o d e r m

- **Isolate the area and release the other person into the safe room RO**
- **Isolate a person in place if someone is in the safe room RO**
- **The equipped person O_2 monitor and air tank in order to control the release**
- **Use the “buddy system” to ensure no injuries occur during the release**
- **Take precautions to avoid personal injury during the operation**
- **Communicate for a clear local signal to aid in the operation once the person is released**
- **Take released person in the**
 - o **Debrief O_2 and**
 - o **Measure for role to a safe place**
 - o **Remove the person for role to a safe and emergency release**

Ignition of Gas source

• Old control valve will be considered lost and must be considered take care to replace
 a valve before it is shut down. O₂ must be local must be coordinated with the
 MOCD and local control. Call the M. Make Police make some colored M. Make
 Police call the the mode. Command of the of a major release. Take care to replace
 do not and never use a valve on the air

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H ₂ S	1.189 Air ☐ I	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO ₂	2.21 Air ☐ I	2 ppm	N/A	1000 ppm

Contacting Authorities

[illegible]

CARLSBAD OFFICE – EDDY & LEA COUNTIES

3104 E. Greene St., Carlsbad, NM 88220
Carlsbad, NM

575-887-7329

XTO PERSONNEL:

Kendall Decker, Drilling Manager
Milton Turman, Drilling Superintendent
Jeff Raines, Construction Foreman
Toady Sanders, EH & S Manager
Wes McSpadden, Production Foreman

903-521-6477
817-524-5107
432-557-3159
903-520-1601
575-441-1147

SHERIFF DEPARTMENTS:

Eddy County
Lea County

575-887-7551
575-396-3611

NEW MEXICO STATE POLICE:

575-392-5588

FIRE DEPARTMENTS:

Carlsbad
Eunice
Hobbs
Jal
Lovington

911
575-885-2111
575-394-2111
575-397-9308
575-395-2221
575-396-2359

HOSPITALS:

Carlsbad Medical Emergency
Eunice Medical Emergency
Hobbs Medical Emergency
Jal Medical Emergency
Lovington Medical Emergency

911
575-885-2111
575-394-2112
575-397-9308
575-395-2221
575-396-2359

AGENT NOTIFICATIONS:**For Lea County:**

Bureau of Land Management – Hobbs
New Mexico Oil Conservation Division – Hobbs

575-393-3612
575-393-6161

For Eddy County:

Bureau of Land Management - Carlsbad
New Mexico Oil Conservation Division - Artesia

575-234-5972
575-748-1283

Operator Name: XTO PERMIAN OPERATING LLC**Well Name:** POKER LAKE 23 DTD FEDERAL COM**Well Number:** 107H**Safe containment description:** Steel mud pits**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** COMMERCIAL**Disposal type description:****Disposal location description:** R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240**Waste type:** DRILLING**Waste content description:** Cuttings**Amount of waste:** 2100 pounds**Waste disposal frequency :** One Time Only**Safe containment description:** The well will be drilled utilizing a closed-loop mud system. Drill cuttings will be held in roll-off style mud boxes.**Safe containmant attachment:****Waste disposal type:** HAUL TO COMMERCIAL FACILITY**Disposal location ownership:** COMMERCIAL**Disposal type description:****Disposal location description:** R360 Environmental Solutions 4507 W Carlsbad Hwy, Hobbs, NM 88240

Reserve Pit

Reserve Pit being used? NO**Temporary disposal of produced water into reserve pit?** NO**Reserve pit length (ft.)****Reserve pit width (ft.)****Reserve pit depth (ft.)****Reserve pit volume (cu. yd.)****Is at least 50% of the reserve pit in cut?****Reserve pit liner****Reserve pit liner specifications and installation description**

Cuttings Area

Cuttings Area being used? NO**Are you storing cuttings on location?** Y

Description of cuttings location Cuttings. The well will be drilled utilizing a closed-loop mud system. Drill cutting will be held in roll-off style mud boxes and taken to a New Mexico Oil Conservation Division (NMOCD) approved disposal site. Drilling fluids. These will be contained in steel mud pits and then taken to a NMOCD approved commercial disposal facility. Produced fluids. water produced from the well during completion will be held temporarily in steel tanks and then taken to a NMOCD approved commercial disposal facility. oil produced during operations will be stored in tanks until sold.

Cuttings area length (ft.)**Cuttings area width (ft.)**

State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description

Effective May 25, 2021

I. Operator: XTO Permian Operating, LLC **OGRID:** 373075 **Date:** 11 / 13 / 2023

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
SEE ATTACHED WELL LIST						

IV. Central Delivery Point Name: Poker Lake Unit 23 CTB [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
SEE ATTACHED WELL LIST						

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan
EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☐ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☐ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system.

If Operator checks this box, Operator will select one of the following:

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- (a) power generation on lease;
- (b) power generation for grid;
- (c) compression on lease;
- (d) liquids removal on lease;
- (e) reinjection for underground storage;
- (f) reinjection for temporary storage;
- (g) reinjection for enhanced oil recovery;
- (h) fuel cell production; and
- (i) other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	
Printed Name:	RUSTY KLEIN
Title:	REGULATORY ANALYST
E-mail Address:	ranell.klein@exxonmobil.com
Date:	November 13, 2023
Phone:	575-703-6412
OIL CONSERVATION DIVISION (Only applicable when submitted as a standalone form)	
Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

III. WELLS

WELL NAME	API	ULSTR	FOOTAGES	ANTICIPATED OIL BBL/DAY	ANTICIPATED GAS	ANTICIPATED PRODUCED
Poker Lake Unit 23 DTD 101H	TBD	M-23-T24S-R30E	406' FSL & 191' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 102H	TBD	M-23-T24S-R30E	406' FSL & 251' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 107H	TBD	P-14-T24S-R30E	455' FSL & 606' FEL	2000	3200	3500
Poker Lake Unit 23 DTD 121H	TBD	M-23-T24S-R30E	406' FSL & 221' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 122H	TBD	M-23-T24S-R30E	406' FSL & 281' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 151H	TBD	M-23-T24S-R30E	406' FSL & 681' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 152H	TBD	M-23-T24S-R30E	406' FSL & 741' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 158H	TBD	G-23-T24S-R30E	1342' FNL & 1680' FEL	2000	3200	3500
Poker Lake Unit 23 DTD 171H	TBD	M-23-T24S-R30E	406' FSL & 711' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 172H	TBD	M-23-T24S-R30E	406' FSL & 771' FWL	2000	3200	3500
Poker Lake Unit 23 DTD 177H	TBD	P-14-T24S-R30E	455' FSL & 546' FEL	2000	3200	3500
Poker Lake Unit 23 DTD 178H	TBD	P-14-T24S-R30E	455' FSL & 516' FEL	2000	3200	3500
Poker Lake Unit 23 DTD 179H	TBD	P-14-T24S-R30E	455' FSL & 476' FEL	2000	3200	3500

V. ANTICIPATED SCHEDULE

WELL NAME	API	SPUD DATE	TD REACHED DATED	COMPLETION COMMENCEMENT DATE	INITIAL FLOW BACK DATE	FIRST PRODUCTION DATE
Poker Lake Unit 23 DTD 101H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 102H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 107H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 121H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 122H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 151H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 152H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 158H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 171H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 172H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 177H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 178H	TBD	TBD	TBD	TBD	TBD	TBD
Poker Lake Unit 23 DTD 179H	TBD	TBD	TBD	TBD	TBD	TBD

VI. Separation Equipment:

XTO Permian Operating, LLC. production tank batteries include separation equipment designed to efficiently separate gas from liquid phases to optimize gas capture based on projected and estimated volumes from the targeted pool in conjunction with the total number of wells planned to or existing within the facility. Separation equipment is upgraded prior to well being drilled or completed, if determined to be undersized or needed. The separation equipment is designed and built according to the relevant industry specifications (API Specification 12J and ASME Sec VIII Div I). Other recognized industry publications such as the Gas Processors Suppliers Association (GPSA) are referenced when designing separation equipment to optimize gas capture.

VII. Operational Practices:**1. Subsection B.**

- During drilling, flare stacks will be located a minimum of 150 feet from the nearest surface hole location. All gas is captured or combusted. If an emergency or malfunction occurs, gas will be flared or vented for public health, safety and the environment and be properly reported to the NMOCD pursuant to 19.15.27.8.G.
- Measure or estimate the volume of natural gas that is vented, flared or beneficially used during drilling, completion and production operations, regardless of the reason or authorization for such venting or flaring.
- At any point in the well life (drilling, completion, production, inactive) an audio, visual and olfactory (AVO) inspection will be performed weekly (at minimum) to confirm that all production equipment is operating properly and there are no leaks or releases except as allowed in Subsection D of 19.15.27.8 NMAC.

2. Subsection C.

- During completion operations, operator does not produce oil or gas but maintains adequate well control through completion operations.

For emergencies, equipment malfunction, or if the operator decides to produce oil and gas during well completion:

- Flowlines will be routed for flowback fluids into a completion or storage tank and, if feasible under well conditions, flare rather than vent and commence operation of a separator as soon as it is technically feasible for a separator to function.
- Measure or estimate the volume of natural gas that is vented, flared or beneficially used during drilling, completion and production operations, regardless of the reason or authorization for such venting or flaring.
- At any point in the well life (drilling, completion, production, inactive) an audio, visual and olfactory (AVO) inspection will be performed weekly (at minimum) to confirm that all production equipment is operating properly and there are no leaks or releases except as allowed in Subsection D of 19.15.27.8 NMAC.

3. Subsection D.

- At any point in the well life (drilling, completion, production, inactive) an audio, visual and olfactory (AVO) inspection will be performed weekly (at minimum) to confirm that all production equipment is operating properly and there are no leaks or releases except as allowed in Subsection D of 19.15.27.8 NMAC.
- Monitor manual liquid unloading for wells on-site or in close proximity (<30 minutes' drive time), take reasonable actions to achieve a stabilized rate and pressure at the earliest practical time, and take reasonable actions to minimize venting to the maximum extent practicable.

- Measure or estimate the volume of natural gas that is vented, flared or beneficially used during drilling, completion and production operations, regardless of the reason or authorization for such venting or flaring.
- 4. Subsection E.
 - All tanks and separation equipment are designed for maximum throughput and pressure to minimize waste.
 - Flare stack was installed prior to May 25, 2021 but has been designed for proper size and combustion efficiency. Flare currently has a continuous pilot and is located more than 100 feet from any known well and storage tanks.
 - At any point in the well life (drilling, completion, production, inactive) an audio, visual and olfactory (AVO) inspection will be performed weekly (at minimum) to confirm that all production equipment is operating properly and there are no leaks or releases except as allowed in Subsection D of 19.15.27.8 NMAC.
- 5. Subsection F.
 - Measurement equipment is installed to measure the volume of natural gas flared from process piping or a flowline piped from the equipment associated with a well and facility associated with the approved application for permit to drill that has an average daily production greater than 60 mcf of natural gas.
 - Measurement equipment installed is not designed or equipped with a manifold to allow diversion of natural gas around the metering equipment, except for the sole purpose of inspecting and servicing the measurement equipment, as noted in NMAC 19.15.27.8 Subsection G.

VIII. Best Management Practices:

1. During completion operations, operator does not produce oil or gas but maintains adequate well control through completion operations.
2. Operator does not flow well (well shut in) during initial production until all flowlines, tank batteries, and oil/gas takeaway are installed, tested, and determined operational.
3. Operator equips storage tanks with an automatic gauging system to reduce venting of natural gas.
4. Operator reduces the number of blowdowns by looking for opportunities to coordinate repair and maintenance activities.
5. Operator combusts natural gas that would otherwise be vented or flared, when feasible.
6. Operator has a flare stack designed in accordance with need and to handle sufficient volume to ensure proper combustion efficiency. Flare stacks are equipped with continuous pilots and securely anchored at least 100 feet (at minimum) from storage tanks and wells.
7. Operator minimizes venting (when feasible) through pump downs of vessels and reducing time required to purge equipment before returning equipment to service.
8. Operator will shut in wells (when feasible) in the event of a takeaway disruption, emergency situation, or other operations where venting or flaring may occur due to equipment failures.

District I

1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720

District II

811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720

District III

1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170

District IV

1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 285874

CONDITIONS

Operator: XTO PERMIAN OPERATING LLC. 6401 HOLIDAY HILL ROAD MIDLAND, TX 79707	OGRID:
	373075
	Action Number:
	285874
Action Type:	
[C-101] BLM - Federal/Indian Land Lease (Form 3160-3)	

CONDITIONS

Created By	Condition	Condition Date
ward.rikala	Notify OCD 24 hours prior to casing & cement	11/28/2023
ward.rikala	Will require a File As Drilled C-102 and a Directional Survey with the C-104	11/28/2023
ward.rikala	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string	11/28/2023
ward.rikala	Cement is required to circulate on both surface and intermediate1 strings of casing	11/28/2023
ward.rikala	If cement does not circulate on any string, a CBL is required for that string of casing	11/28/2023
ward.rikala	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system	11/28/2023