

1625 N. French Dr., Hobbs, NM 88240

District II

811 S. First St., Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural ResourcesForm C-104
Revised August 1, 2011Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT**I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT**

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710		² OGRID Number 16696
		³ Reason for Filing Code/ Effective Date NW - 11/20/2023
⁴ API Number 30 - 025-48974	⁵ Pool Name Antelope Ridge; Wolfcamp	
	⁶ Pool Code 2220	
⁷ Property Code 330861	⁸ Property Name Maltese 5 8 Fed COM	⁹ Well Number 31H

II. ¹⁰ Surface Location

U1 or lot no. 3	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 475	North/South Line North	Feet from the 1475	East/West line West	County Lea
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

¹¹ Bottom Hole Location

UL or lot no. M	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 23	North/South line South	Feet from the 352	East/West line West	County Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date 11/26/23	¹⁵ C-129 Permit Number	¹⁶ C-129 Effective Date	¹⁷ C-129 Expiration Date				

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline, L.P.	O
248749	DCP Midstream, L.P.	G

IV. Well Completion Data

²¹ Spud Date 06/21/2023	²² Ready Date 11/20/2023	²³ TD 22234' MD, 11980' TVD	²⁴ PBTB 22190' MD, 11978' TVD	²⁵ Perforations 11938'-22041'	²⁶ DHC, MC R22665
²⁷ Hole Size	²⁸ Casing & Tubing Size	²⁹ Depth Set		³⁰ Sacks Cement	
17 1/2"	13 3/8" 54.5# J-55	1111'		1128sx Class C - TOC 0'	
9 7/8"	7 5/8" 26.4# HCL80	11319'		3154sx Class H - TOC 0'	
6 3/4"	5 1/2" 20# P110	22214'		774sx Class H- TOC 0'	

V. Well Test Data

³¹ Date New Oil 11/26/2023	³² Gas Delivery Date 11/26/2023	³³ Test Date 11/29/2023	³⁴ Test Length 24 hours	³⁵ Tbg. Pressure 0	³⁶ Csg. Pressure 2274
³⁷ Choke Size 0	³⁸ Oil 2901	³⁹ Water 5438	⁴⁰ Gas 2131	⁴¹ Test Method Flowing	
⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: <i>Sarah McKinney</i>			OIL CONSERVATION DIVISION		
Printed name: Sarah McKinney			Approved by:		
Title: Regulatory Analyst Sr.			Title:		
E-mail Address: sarah_mckinney@oxy.com			Approval Date:		
Date: 01/05/2024		Phone: 713-215-7295			

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48974	² Pool Code 2220	³ Pool Name ANTELOPE RIDGE; Wolfcamp
⁴ Property Code 330861	⁵ Property Name MALTESE 5 8 FED COM	⁶ Well Number 31H
⁷ OGRID No. 16696	⁸ Operator Name OXY USA INC.	⁹ Elevation 3454.3' (NAVD 88)


¹⁰ Surface Location

UL or lot no. 3	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 475	North/South line NORTH	Feet from the 1475	East/West line WEST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. M	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 23	North/South line SOUTH	Feet from the 352	East/West line WEST	County LEA
¹² Dedicated Acres 1280	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No. R-22665						

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



¹⁷ OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.
Sarah McKinney 1/5/21
Signature Date
Sarah McKinney
Printed Name
sarah.mckinney@oxy.com
E-mail Address

¹⁸ SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.
December 12, 2019
Date of Survey
Signature and Seal of Professional Surveyor:

Certificate Number:

APPROXIMATE WELL BORE DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
NMNM 014164	4,988.58'
FEE	2,641.96'
NMNM 0001228A	2,429.07'
TOTAL	10,059.61'

NOTE:
• Distances referenced on plat to section lines are perpendicular.
• Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
• As-Drilled well head has not been field verified.
• Wellbore data provided by Oxy USA Inc.

2000' 1000' 0' 2000'
SCALE
DRAWN BY: N.R. 11-03-23



Oxy Maltese 5-8 Fed Com 31H IFR1 to 22234ft Survey Geodetic Report



DefinitiveSurvey

Report Date:	August 07, 2023 - 03:29 PM (UTC 0)	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	185.732 °(Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	Oxy Maltese 5-8 Fed Com Pad Lot 3 / Maltese 5-8 Fed Com 31H	TVD Reference Datum:	RKB
Well:	Maltese 5-8 Fed Com 31H	TVD Reference Elevation:	3479.300 ft above MSL
Borehole:	Maltese 5-8 Fed Com 31H	Seabed / Ground Elevation:	3454.300 ft above MSL
UBH/ API / JobNumber:	Unknown / Unknown / Unknown	Magnetic Declination:	6.301°
Survey Name / Version:	Oxy Maltese 5-8 Fed Com 31H IFR1 to 22234ft / 5	Total Gravity Field Strength:	998.4651mgn (9.80665 Based)
Survey Date:	August 04, 2023	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	362.249 ° / 11739.553 ft / 6.897 / 0.980	Total Magnetic Field Strength:	47519.1 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	59.826°
Location Lat / Long:	N 32°15'06.299", W 103°23'36.14306"	Declination Date:	July 27, 2023
Location Grid N/E Y/X:	N 456871.220 RUS , E 831918.220 RUS	Magnetic Declination Model:	IFR1
CRS Grid Convergence Angle:	0.502°	North Reference:	Grid
Grid Scale Factor:	1.0000058	Total Corr Mag	5.802°
Engine Version:	2023.1.0.1	Local Coord Referenced To:	Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (1100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")	Closure (ft)	Closure Azimuth (°)
WRP	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3.479.30		456,871.22	831,918.22	N 32°15'06"	W 103°23'36.14"		
SHL	25.00	0.00	0.00	25.00	0.00	0.00	0.00	-3.454.30	0.00	456,871.22	831,918.22	N 32°15'06"	W 103°23'36.14"	0.00	0.00
First SLB Survey	174.00	0.10	243.67	174.00	0.07	-0.06	-0.12	-3.305.30	0.07	456,871.16	831,918.10	N 32°15'06"	W 103°23'36.14"	0.13	243.67
	268.00	0.32	1.30	268.00	-0.15	0.17	0.18	-3.211.30	0.40	456,871.39	831,918.04	N 32°15'06"	W 103°23'36.15"	0.25	312.44
	363.00	0.59	81.72	363.00	-0.53	0.50	0.31	-3.116.30	0.66	456,871.72	831,918.53	N 32°15'07"	W 103°23'36.14"	0.59	31.26
	447.00	0.54	56.19	446.99	-0.89	0.79	1.06	-3.032.31	0.30	456,872.01	831,919.28	N 32°15'07"	W 103°23'36.13"	1.32	53.50
	541.00	0.26	349.62	540.99	-1.38	1.24	1.39	-2.938.31	0.53	456,872.46	831,919.61	N 32°15'08"	W 103°23'36.13"	1.87	48.25
	636.00	0.24	313.12	635.99	-1.70	1.59	1.21	-2.843.31	0.17	456,872.81	831,919.43	N 32°15'08"	W 103°23'36.13"	2.00	37.22
	731.00	0.45	245.61	730.99	-1.64	1.57	0.72	-2.748.31	0.44	456,872.79	831,918.94	N 32°15'08"	W 103°23'36.13"	1.73	24.70
	826.00	0.39	208.05	825.99	-1.15	1.13	0.23	-2.653.31	0.29	456,872.35	831,918.45	N 32°15'07"	W 103°23'36.14"	1.16	11.55
	920.00	0.56	221.18	919.98	-0.48	0.51	-0.22	-2.559.32	0.21	456,871.73	831,918.00	N 32°15'07"	W 103°23'36.15"	0.55	336.35
	1,015.00	0.43	220.38	1,014.98	0.19	-0.12	-0.76	-2.464.32	0.14	456,871.10	831,917.46	N 32°15'06"	W 103°23'36.15"	0.77	261.33
	1,132.00	0.33	253.43	1,131.98	0.68	-0.55	-1.37	-2.347.32	0.20	456,870.67	831,916.85	N 32°15'06"	W 103°23'36.16"	1.47	248.20
	1,226.00	0.24	171.58	1,225.98	0.97	-0.82	-1.60	-2.253.32	0.40	456,870.40	831,916.62	N 32°15'06"	W 103°23'36.16"	1.79	242.86
	1,416.00	0.12	163.09	1,415.98	1.54	-1.40	-1.48	-2.063.32	0.06	456,869.82	831,916.74	N 32°15'05"	W 103°23'36.16"	2.04	226.54
	1,511.00	0.23	82.50	1,510.98	1.59	-1.47	-1.26	-1.968.32	0.25	456,869.75	831,916.96	N 32°15'05"	W 103°23'36.16"	1.94	220.60
	1,606.00	0.08	343.27	1,605.97	1.49	-1.38	-1.09	-1.873.33	0.27	456,869.84	831,917.13	N 32°15'05"	W 103°23'36.16"	1.76	218.27
	1,701.00	0.20	287.11	1,700.97	1.39	-1.27	-1.27	-1.778.33	0.18	456,869.95	831,916.95	N 32°15'05"	W 103°23'36.16"	1.80	224.95
	1,796.00	0.26	266.37	1,795.97	1.39	-1.24	-1.64	-1.683.33	0.11	456,869.98	831,916.58	N 32°15'05"	W 103°23'36.16"	2.06	233.03
	1,890.00	0.12	330.55	1,889.97	1.35	-1.16	-1.90	-1.589.33	0.25	456,870.06	831,916.32	N 32°15'05"	W 103°23'36.17"	2.23	238.56
	1,985.00	0.35	43.52	1,984.97	1.04	-0.87	-1.75	-1.494.33	0.35	456,870.35	831,916.47	N 32°15'05"	W 103°23'36.16"	1.96	243.68
	2,080.00	0.06	336.70	2,079.97	0.77	-0.61	-1.57	-1.399.33	0.35	456,870.61	831,916.65	N 32°15'06"	W 103°23'36.16"	1.69	248.77
	2,174.00	0.16	23.50	2,173.97	0.60	-0.45	-1.54	-1.305.33	0.13	456,870.77	831,916.68	N 32°15'06"	W 103°23'36.16"	1.60	253.86
	2,269.00	0.27	291.35	2,268.97	0.41	-0.24	-1.70	-1.210.33	0.34	456,870.98	831,916.58	N 32°15'06"	W 103°23'36.16"	1.71	261.86
	2,364.00	0.36	330.26	2,363.97	0.11	0.10	-2.05	-1,115.33	0.24	456,871.32	831,916.17	N 32°15'06"	W 103°23'36.17"	2.05	272.74
	2,459.00	0.26	8.16	2,458.97	-0.35	0.57	-2.17	-1,020.33	0.23	456,871.79	831,916.05	N 32°15'07"	W 103°23'36.17"	2.24	284.73
	2,554.00	0.29	23.86	2,553.97	-0.79	1.00	-2.04	-925.33	0.09	456,872.22	831,916.18	N 32°15'07"	W 103°23'36.17"	2.28	296.18
	2,649.00	0.27	44.73	2,648.97	-1.20	1.38	-1.79	-830.33	0.11	456,872.60	831,916.43	N 32°15'08"	W 103°23'36.16"	2.26	307.73
	2,743.00	0.36	20.92	2,742.97	-1.65	1.82	-1.53	-736.33	0.17	456,873.04	831,916.69	N 32°15'08"	W 103°23'36.16"	2.37	319.96
	2,838.00	0.35	16.12	2,837.96	-2.23	2.37	-1.34	-641.34	0.03	456,873.59	831,916.88	N 32°15'09"	W 103°23'36.16"	2.73	330.57
	2,933.00	0.41	356.15	2,932.96	-2.85	2.99	-1.28	-546.34	0.15	456,874.21	831,916.94	N 32°15'09"	W 103°23'36.16"	3.25	336.82
	3,028.00	0.21	12.19	3,027.96	-3.36	3.50	-1.27	-451.34	0.23	456,874.72	831,916.95	N 32°15'10"	W 103°23'36.16"	3.72	340.10
	3,123.00	0.26	36.51	3,122.96	-3.71	3.84	-1.10	-356.34	0.12	456,875.06	831,917.12	N 32°15'10"	W 103°23'36.16"	4.00	344.00
	3,313.00	0.35	0.73	3,312.96	-4.66	4.77	-0.94	-166.34	0.11	456,875.99	831,917.38	N 32°15'10"	W 103°23'36.15"	4.84	350.03
	3,408.00	0.17	121.40	3,407.96	-4.89	4.99	-0.71	-71.34	0.48	456,876.21	831,917.51	N 32°15'11"	W 103°23'36.15"	5.04	351.85
	3,502.00	0.86	211.16	3,501.95	-4.19	4.31	-0.96	22.65	0.93	456,875.53	831,917.26	N 32°15'11"	W 103°23'36.15"	4.42	347.44
	3,597.00	1.24	217.12	3,596.94	-2.67	2.88	-1.95	117.64	0.42	456,874.10	831,916.27	N 32°15'09"	W 103°23'36.17"	3.48	325.92
	3,692.00	0.73	202.79	3,691.92	-1.22	1.50	-2.80	212.62	0.59	456,872.72	831,915.42	N 32°15'08"	W 103°23'36.18"	3.18	298.20
	3,787.00	0.51	126.05	3,786.92	-0.42	0.70	-2.70	307.62	0.83	456,871.92	831,915.52	N 32°15'07"	W 103°23'36.17"	2.79	284.49
	3,882.00	0.16	8.70	3,881.92	-0.34	0.58	-2.33	402.62	0.63	456,871.80	831,915.89	N 32°15'07"	W 103°23'36.17"	2.41	283.94
	3,976.00	0.56	64.82	3,975.91	-0.71	0.90	-1.90	496.61	0.52	456,872.12	831,916.32	N 32°15'07"	W 103°23'36.17"	2.10	295.47
	4,072.00	0.76	69.10	4,071.91	-1.24	1.33	-0.88	592.61	0.21	456,872.55	831,917.34	N 32°15'08"	W 103°23'36.15"	1.60	326.53
	4,167.00	0.88	54.55	4,166.90	-1.89	1.88	1.17	687.60	0.21	456,873.10	831,918.39	N 32°15'08"	W 103°23'36.14"	1.89	5.09
	4,262.00	0.69	56.33	4,261.89	-2.73	1.82	1.24	782.59	0.22	456,873.54	831,919.46	N 32°15'08"	W 103°23'36.13"	2.90	25.35
	4,357.00	1.74	55.58	4,356.87	-4.13	3.94	3.84	877.57	0.89	456,875.06	831,921.26	N 32°15'10"	W 103°23'36.11"	4.30	38.39
	4,451.00	1.73	61.42	4,450.82	-5.85	5.33	5.47	971.52	0.19	456,876.55	831,923.69	N 32°15'12"	W 103°23'36.08"	7.64	45.74
	4,547.00	2.07	56.39	4,546.77	-7.76	6.98	8.18	1,067.47	0.39	456,878.20	831,926.40	N 32°15'13"	W 103°23'36.05"	10.76	49.53
	4,642.00	2.40	53.17	4,641.70	-10.20	9.12	11.21	1,162.40	0.37	456,880.34	831,929.43	N 32°15'15"	W 103°23'36.01"	14.45	50.85
	4,687.00	2.38	50.99	4,686.66	-11.49	10.28	12.69	1,207.36	0.21	456,881.50	831,930.91	N 32°15'16"	W 103°23'35.99"	16.33	50.99
	4,737.00	2.35	46.84	4,736.62	-13.00	11.63	14.24	1,257.32	0.35	456,882.85	831,932.46	N 32°15'18"	W 103°23'35.98"	18.39	50.76
	4,780.00	2.21	34.90	4,779.58	-14.38	12.91	15.36	1,300.28	1.15	456,884.13	831,933.58	N 32°15'19"	W 103°23'35.96"	20.07	49.94
	4,832.00	1.86	27.15	4,831.55	-16.04	14.49	16.32	1,352.25	0.85	456,885.71	831,934.54	N 32°15'20"	W 103°23'35.95"	21.82	48.40
	4,926.00	1.29	356.53	4,925.52	-18.51	16.90	16.95	1,446.22	1.06	456,888.12	831,935.17	N 32°15'23"	W 103°23'35.94"	23.94	45.08
	5,021.00	2.03	314.56	5,020.48	-20.62	19.15	15.68	1,541.18	1.45	456,890.37	831,933.90	N 32°15'25"	W 103°23'35.96"	24.75	39.32
	5,116.00	3.62	298.43	5,115.36	-22.23	21.18	11.61	1,636.06	2.17	456,892.40	831,939.83	N 32°15'27"	W 103°23'36.01"	24.15	28.73
	5,211.00	3.35	286.88	5,210.19	-23.33	22.83	6.08	1,730.89	0.29	456,894.05	831,924.30	N 32°15'29"	W 103°23'36.07"	23.63	14.90
	5,306.00	4.94	275.37	5,304.94	-23.84	24.02	-0.65	1,825.64	1.88	456,895.24	831,917.57	N 32°15'30"	W 103°23'36.15"	24.03	358.44
	5,401.00	8.27	274.76	5,399.29	-23.69	24.97	-11.54	1,919.99	3.51	456,896.19	831,906.68	N 32°15'31"	W 103°23'36.27"	27.51	335.20
	5,496.00	11.18	276.05	5,492.92	-23.63	26.51	-27.51	2,013.62	3.07	456,897.73	831,890.71	N 32°15'33"	W 103°23'36.46"	38.20	313.94
	5,590.00	13.60	276.49	5,584.72	-23.83	28.72	-47.55	2,105.42	2.58	456,899.94	831,870.67	N 32°15'35"	W 103°23'36.69"	55.55	301.13
	5,685.00	13.75	275.89	5,677.03	-24.01	31.14	-69.88	2,197.73	0.22	456					

	9,098.00	8.44	293.67	8,980.16	-245.33	333.31	-864.29	5,500.86	0.51	457,204.54	831,053.93	N 32°15'12.44"	W 103°23'46.17"	926.34	291.09
	9,193.00	7.16	298.80	9,074.28	-249.80	338.97	-875.86	5,594.98	1.53	457,210.19	831,042.35	N 32°15'12.49"	W 103°23'46.31"	939.17	291.16
	9,288.00	6.69	295.01	9,168.58	-253.95	344.16	-886.07	5,689.28	0.69	457,215.38	831,032.15	N 32°15'12.54"	W 103°23'46.43"	950.56	291.23
	9,383.00	5.70	289.42	9,263.03	-258.89	348.07	-895.53	5,783.73	1.22	457,219.29	831,022.68	N 32°15'12.58"	W 103°23'46.54"	960.80	291.24
	9,478.00	5.62	288.66	9,357.54	-259.17	351.20	-904.52	5,878.24	0.25	457,225.42	831,013.59	N 32°15'12.62"	W 103°23'46.64"	970.40	291.22
	9,573.00	5.71	293.66	9,452.05	-261.65	354.67	-913.59	5,972.75	0.58	457,225.89	831,004.62	N 32°15'12.65"	W 103°23'46.71"	980.02	291.22
	9,667.00	6.25	291.37	9,545.54	-264.47	358.41	-922.64	6,066.24	0.63	457,229.63	830,995.58	N 32°15'12.69"	W 103°23'46.85"	989.81	291.23
	9,762.00	6.33	290.65	9,639.97	-267.21	362.14	-932.36	6,160.67	0.12	457,233.36	830,985.86	N 32°15'12.73"	W 103°23'46.96"	1,000.22	291.23
	9,857.00	6.55	293.66	9,734.37	-270.23	366.16	-942.22	6,255.07	0.42	457,237.38	830,976.00	N 32°15'12.77"	W 103°23'47.08"	1,010.87	291.24
	9,952.00	6.52	287.84	9,828.75	-273.03	369.99	-952.32	6,349.45	0.70	457,241.21	830,965.90	N 32°15'12.81"	W 103°23'47.19"	1,021.67	291.23
	10,047.00	5.91	290.03	9,923.20	-275.37	373.31	-962.05	6,443.90	0.69	457,244.54	830,956.17	N 32°15'12.84"	W 103°23'47.31"	1,031.94	291.21
	10,142.00	6.02	292.22	10,017.68	-277.99	376.87	-971.25	6,538.38	0.27	457,248.10	830,946.96	N 32°15'12.88"	W 103°23'47.41"	1,041.81	291.21
	10,237.00	5.64	294.68	10,112.19	-280.92	380.71	-980.11	6,632.89	0.48	457,251.93	830,938.11	N 32°15'12.91"	W 103°23'47.52"	1,051.45	291.23
	10,332.00	5.58	299.92	10,206.74	-284.33	384.96	-988.35	6,727.44	0.54	457,256.18	830,929.98	N 32°15'12.96"	W 103°23'47.61"	1,060.68	291.28
	10,427.00	5.66	292.64	10,301.28	-287.58	389.07	-996.68	6,821.98	0.75	457,260.29	830,921.54	N 32°15'13.00"	W 103°23'47.71"	1,069.93	291.32
	10,522.00	5.82	275.30	10,395.81	-288.91	391.32	-1,005.80	6,916.51	1.83	457,262.54	830,912.42	N 32°15'13.02"	W 103°23'47.81"	1,079.24	291.26
	10,617.00	5.63	275.06	10,490.34	-288.82	392.17	-1,015.24	7,011.04	0.20	457,265.39	830,902.98	N 32°15'13.03"	W 103°23'47.82"	1,088.35	291.12
	10,711.00	5.58	282.77	10,583.89	-289.32	393.59	-1,024.29	7,104.59	0.80	457,264.81	830,893.93	N 32°15'13.05"	W 103°23'48.03"	1,097.31	291.02
	10,806.00	7.33	285.69	10,678.28	-290.94	396.25	-1,034.63	7,198.98	1.87	457,267.47	830,883.59	N 32°15'13.07"	W 103°23'48.15"	1,107.91	291.06
	10,901.00	7.88	291.78	10,772.45	-293.79	400.30	-1,046.51	7,293.15	1.03	457,271.52	830,871.71	N 32°15'13.11"	W 103°23'48.29"	1,120.46	290.93
	10,996.00	6.52	286.82	10,866.70	-296.63	404.28	-1,057.72	7,387.40	1.57	457,275.50	830,860.49	N 32°15'13.15"	W 103°23'48.42"	1,132.35	290.92
	11,091.00	6.09	277.60	10,961.13	-297.83	406.51	-1,067.88	7,481.83	1.16	457,277.73	830,850.34	N 32°15'13.18"	W 103°23'48.54"	1,142.63	290.84
	11,186.00	6.09	272.78	11,055.59	-297.73	407.42	-1,077.91	7,576.29	0.54	457,278.64	830,840.31	N 32°15'13.19"	W 103°23'48.65"	1,152.33	290.71
	11,280.00	5.46	274.23	11,149.03	-297.34	408.05	-1,088.16	7,669.73	0.43	457,279.27	830,830.05	N 32°15'13.19"	W 103°23'48.77"	1,162.15	290.56
	11,305.00	6.20	274.01	11,173.87	-297.26	408.25	-1,089.51	7,695.97	1.04	457,279.47	830,820.30	N 32°15'13.20"	W 103°23'48.80"	1,164.90	290.52
	11,360.00	5.67	257.62	11,226.58	-296.32	407.87	-1,096.53	7,749.28	3.22	457,279.10	830,821.69	N 32°15'13.19"	W 103°23'48.81"	1,169.99	290.40
	11,387.00	5.60	248.80	11,255.45	-295.31	407.11	-1,099.06	7,776.15	3.22	457,278.33	830,819.16	N 32°15'13.19"	W 103°23'48.80"	1,172.04	290.33
	11,481.00	10.16	200.15	11,348.63	-285.19	397.66	-1,106.20	7,869.33	8.19	457,268.88	830,812.01	N 32°15'13.09"	W 103°23'48.98"	1,175.51	289.77
	11,576.00	19.73	183.55	11,440.35	-260.99	373.72	-1,110.09	7,961.05	10.94	457,244.94	830,808.12	N 32°15'12.86"	W 103°23'49.03"	1,171.31	288.61
	11,601.00	21.96	180.62	11,463.71	-252.11	364.83	-1,110.40	7,984.41	9.83	457,236.05	830,807.81	N 32°15'12.77"	W 103°23'49.04"	1,168.80	288.19
	11,671.00	28.39	174.81	11,527.04	-222.70	335.14	-1,109.04	8,047.74	9.83	457,206.36	830,809.18	N 32°15'12.47"	W 103°23'49.02"	1,158.57	286.81
	11,766.00	38.09	173.47	11,606.40	-171.77	283.41	-1,103.65	8,127.10	10.24	457,154.63	830,814.56	N 32°15'11.96"	W 103°23'48.97"	1,139.46	284.40
	11,861.00	19.75	176.43	11,676.47	-108.87	219.64	-1,098.15	8,197.17	9.35	457,090.86	830,820.06	N 32°15'11.33"	W 103°23'48.91"	1,119.90	281.31
	11,955.00	54.50	178.49	11,736.07	-37.01	147.10	-1,095.01	8,256.77	8.42	457,018.32	830,823.21	N 32°15'10.81"	W 103°23'48.88"	1,104.85	277.65
	12,050.00	57.53	179.52	11,780.00	-27.71	81.95	-1,092.68	8,307.24	4.00	456,953.17	830,826.33	N 32°15'10.93"	W 103°23'48.87"	1,096.95	274.28
	12,050.00	58.16	179.73	11,789.73	41.51	68.07	-1,093.80	8,309.43	4.00	456,939.29	830,824.42	N 32°15'10.93"	W 103°23'48.87"	1,095.91	273.56
	12,145.00	64.20	181.70	11,834.51	124.39	-15.12	-1,094.88	8,355.21	6.61	456,856.10	830,823.34	N 32°15'10.91"	W 103°23'48.87"	1,094.98	269.21
	12,240.00	73.35	184.54	11,888.87	212.75	-103.43	-1,090.76	8,389.57	10.03	456,767.79	830,818.45	N 32°15'10.13"	W 103°23'48.96"	1,104.61	264.63
	12,334.00	81.96	185.22	11,888.95	304.48	-194.84	-1,107.57	8,409.65	9.19	456,676.38	830,810.64	N 32°15'17.23"	W 103°23'49.06"	1,124.58	260.02
	12,429.00	90.46	179.63	11,895.22	398.98	-289.42	-1,111.56	8,415.92	10.70	456,581.80	830,806.66	N 32°15'16.30"	W 103°23'49.12"	1,148.62	255.41
	12,524.00	89.99	176.97	11,894.85	493.18	-384.37	-1,108.74	8,415.55	2.84	456,486.85	830,809.48	N 32°15'15.36"	W 103°23'49.09"	1,173.47	250.88
	12,619.00	89.74	174.55	11,895.08	586.73	-479.10	-1,101.72	8,415.78	2.56	456,392.12	830,816.50	N 32°15'14.42"	W 103°23'49.02"	1,201.38	246.50
	12,714.00	89.98	169.69	11,895.31	679.04	-573.18	-1,088.70	8,416.01	5.12	456,298.04	830,829.52	N 32°15'13.49"	W 103°23'48.88"	1,230.36	242.23
	12,740.00	90.20	170.22	11,895.27	704.06	-598.78	-1,084.16	8,415.97	2.20	456,272.44	830,834.06	N 32°15'13.23"	W 103°23'48.87"	1,238.52	241.09
	12,830.00	92.78	171.81	11,894.66	770.26	-689.25	-1,073.26	8,415.96	1.20	456,204.31	830,844.95	N 32°15'12.96"	W 103°23'48.71"	1,253.59	238.14
	12,903.00	90.78	178.88	11,891.72	863.08	-760.47	-1,065.48	8,412.82	8.01	456,110.75	830,852.74	N 32°15'11.63"	W 103°23'48.63"	1,309.03	234.48
	12,998.00	89.29	181.94	11,890.01	957.63	-855.43	-1,066.16	8,410.71	4.89	456,015.79	830,852.06	N 32°15'10.69"	W 103°23'48.64"	1,366.91	231.26
	13,154.00	88.71	187.92	11,892.72	1,113.52	-1,010.75	-1,079.55	8,413.42	3.85	455,860.46	830,838.67	N 32°15'15.91"	W 103°23'48.82"	1,478.87	226.89
	13,188.00	88.59	189.22	11,893.52	1,147.46	-1,044.37	-1,084.61	8,414.22	3.85	455,826.85	830,833.60	N 32°15'15.82"	W 103°23'48.88"	1,505.69	226.08
	13,283.00	87.41	189.41	11,896.84	1,242.22	-1,138.05	-1,099.98	8,417.54	1.26	455,733.16	830,818.23	N 32°15'17.90"	W 103°23'49.07"	1,582.76	224.03
	13,373.00	89.14	182.61	11,899.55	1,332.12	-1,227.46	-1,109.39	8,420.25	7.79	455,643.75	830,808.82	N 32°15'17.01"	W 103°23'49.19"	1,654.51	222.11
	13,468.00	89.42	177.24	11,900.75	1,426.59	-1,322.42	-1,109.27	8,421.45	5.66	455,548.79	830,808.95	N 32°15'16.07"	W 103°23'49.19"	1,726.06	219.99
	13,563.00	91.80	174.80	11,899.74	1,520.21	-1,417.17	-1,102.68	8,420.44	3.59	455,454.04	830,815.54	N 32°15'15.14"	W 103°23'49.13"	1,795.63	217.89
	13,658.00	92.73	173.85	11,896.98	1,613.26	-1,511.63	-1,093.29	8,416.68	1.40	455,359.58	830,824.93	N 32°15'14.20"	W 103°23'49.03"	1,865.56	215.88
	13,753.00	92.55	173.32	11,891.77	1,708.04	-1,605.94	-1,082.69	8,412.47	0.69	455,265.27	830,835.53	N 32°15'13.27"	W 103°23'49.01"	1,936.82	213.99
	13,848.00	93.78	174.81	11,886.69	1,798.94	-1,700.29	-1,072.90	8,407.39	2.20	455,170.92	830,845.31	N 32°15'12.33"	W 103°23'48.81"	2,010.50	212.25
	13,861.00	93.91	175.07	11,885.82	1,811.69	-1,713.22	-1,071.76	8,406.52	2.02	455,158.00	830,846.46	N 32°15'12.20"	W 103°23'48.80"	2,020.84	212.03
	13,943.00	94.71	176.52	11,879.66	1,892.23	-1,794.76	-1,065.76	8,400.36	2.02	455,076.45	830,852.45	N 32°15'11.40"	W 103°23'48.73"	2,087.35	210.70
	14,134.00	90.62	182.15	11,870.77	2,081.72	-1,985.42	-1,063.57	8,391.47	3.64	454,885.79	830,854.65	N 32°15'14.91"	W 103°23'48.73"	2,252.35	208.18
	14,264.00	90.77	181.12	11,869.20	2,211.37	-2,115.36	-1,067.27	8,389.90	0.80	454,755.85	830,850.94	N 32°15'14.82"	W 103°23'48.79"	2,369.35	206.77
	14,324.00	90.84	180.64	11,868.35	2,271.15</										

21,060.00	90.37	179.00	11,926.05	8,967.41	-8,906.45	-1,056.29	8,446.75	5.07	447,964.74	830,861.92	N 32°13'41.03"	W 103°23'49.35"	8,968.87	186.76
21,155.00	89.40	176.91	11,926.24	9,061.53	-9,001.38	-1,052.90	8,446.94	2.43	447,869.81	830,865.31	N 32°13'40.09"	W 103°23'49.32"	9,062.75	186.67
21,250.00	88.55	177.96	11,927.94	9,155.52	-9,096.27	-1,048.65	8,448.64	1.42	447,774.92	830,869.56	N 32°13'39.15"	W 103°23'49.28"	9,156.52	186.58
21,345.00	87.98	178.83	11,930.81	9,249.70	-9,191.19	-1,045.99	8,451.51	1.09	447,680.00	830,872.22	N 32°13'38.21"	W 103°23'49.26"	9,250.51	186.49
21,439.00	87.44	179.60	11,934.57	9,343.01	-9,285.10	-1,044.71	8,455.27	1.00	447,586.08	830,873.51	N 32°13'37.28"	W 103°23'49.25"	9,343.69	186.42
21,534.00	87.29	180.56	11,938.94	9,437.45	-9,380.00	-1,044.84	8,459.64	1.02	447,491.19	830,873.38	N 32°13'36.34"	W 103°23'49.26"	9,438.01	186.36
21,629.00	87.33	180.04	11,943.40	9,531.92	-9,474.89	-1,045.34	8,464.10	0.55	447,396.29	830,872.88	N 32°13'35.40"	W 103°23'49.28"	9,532.38	186.30
21,724.00	87.54	180.30	11,947.65	9,626.38	-9,569.80	-1,045.62	8,468.35	0.35	447,301.39	830,872.60	N 32°13'34.46"	W 103°23'49.29"	9,626.75	186.24
21,819.00	86.95	180.16	11,952.21	9,720.83	-9,664.69	-1,046.00	8,472.91	0.64	447,206.50	830,872.22	N 32°13'33.52"	W 103°23'49.30"	9,721.13	186.18
21,914.00	86.07	176.95	11,958.00	9,814.90	-9,759.47	-1,043.61	8,478.70	3.50	447,111.72	830,874.61	N 32°13'32.59"	W 103°23'49.29"	9,815.11	186.10
22,009.00	84.90	173.88	11,965.48	9,908.06	-9,853.86	-1,036.04	8,486.18	3.45	447,017.33	830,882.17	N 32°13'31.65"	W 103°23'49.21"	9,908.17	186.00
22,104.00	86.20	173.60	11,972.85	10,000.71	-9,948.00	-1,025.71	8,493.55	1.40	446,923.18	830,892.50	N 32°13'30.72"	W 103°23'49.10"	10,000.74	185.89
LTP / 100 ft FSL Cross	22,156.00	86.40	173.67	11,976.20	10,051.45	-9,999.57	8,496.90	0.42	446,871.61	830,898.25	N 32°13'30.21"	W 103°23'49.03"	10,051.46	185.82
Last SLB Survey	22,196.00	86.56	173.73	11,978.66	10,090.49	-10,039.26	8,499.36	0.42	446,831.92	830,902.63	N 32°13'29.81"	W 103°23'48.99"	10,090.50	185.78
Projection to Total Depth	22,234.00	86.58	173.73	11,980.94	10,127.60	-10,078.98	8,501.64	0.00	446,794.22	830,906.78	N 32°13'29.44"	W 103°23'48.94"	10,127.60	185.73

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	13,283.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 31H / Oxy Maltese 5-8 Fed Com 31H IFR1 to 22234ft
	1	13,283.000	13,943.000	Act Stns		A009Mb_MWD+IFR1+SAG	Maltese 5-8 Fed Com 31H / Oxy Maltese 5-8 Fed Com 31H IFR1 to 22234ft
	1	13,943.000	22,234.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 31H / Oxy Maltese 5-8 Fed Com 31H IFR1 to 22234ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
22,234.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48974		
Operator Name: OXY USA INC.	Property Name: Maltese 5 8 Fed Com	Well Number 31H

Kick Off Point (KOP)

UL 4	Section 5	Township 24S	Range 35E	Lot	Feet 57	From N/S North	Feet 383	From E/W West	County Lea
Latitude 32.253665					Longitude -103.396908			NAD Nad83	

First Take Point (FTP)

UL 4	Section 5	Township 24S	Range 35E	Lot	Feet 304	From N/S North	Feet 381	From E/W West	County Lea
Latitude 32.252986					Longitude -103.396912			NAD Nad83	

Last Take Point (LTP)

UL M	Section 8	Township 24S	Range 35E	Lot	Feet 214	From N/S South	Feet 333	From E/W West	County Lea
Latitude 32.225371					Longitude -103.396992			NAD Nad83	

Is this well the defining well for the Horizontal Spacing Unit? ☐Is this well an infill well? ☐

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW /	County or Parish/State:
Well Number: 31H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM14164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548974	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Subsequent Report

Sundry ID: 2762867

Type of Submission: Subsequent Report

Type of Action: Hydraulic Fracturing

Date Sundry Submitted: 11/27/2023

Time Sundry Submitted: 08:14

Date Operation Actually Began: 10/03/2023

Actual Procedure: RUPU 10/03/2023, RIH & Clean out to PBTD 22190'. Test production casing to 6000 psi for 30 min. RIH and Perf from 11938'-22041', total 2466 holes, 0.42". Frac in 41 stages with 27,731,900 #'s sand and 515,084 bbls produced water, RD Frac and well ready to produce on 11/20/2023. OXY USA Inc. requests a tubing exception while continuing to flow back this well. The estimated date of tubing install is 1/20/2024.

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW /	County or Parish/State:
Well Number: 31H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM14164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548974	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SARAH MCKINNEY	Signed on: NOV 27, 2023 08:12 AM
Name: OXY USA INCORPORATED	
Title: Regulatory Analyst Sr	
Street Address: 5 GREENWAY PLAZA SUITE 110	
City: HOUSTON	State: TX
Phone: (713) 215-7295	
Email address: SARAH_MCKINNEY@OXY.COM	

Field


Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752345972	BLM POC Email Address: jshepard@blm.gov
Disposition: Accepted	Disposition Date: 12/15/2023
Signature: Jonathon Shepard	

Submit To Appropriate District Office Two Copies District I 1625 N. French Dr., Hobbs, NM 88240 District II 811 S. First St., Artesia, NM 88210 District III 1000 Rio Brazos Rd., Aztec, NM 87410 District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised April 3, 2017				
1. WELL API NO. 30-025-48974										
2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN										
3. State Oil & Gas Lease No.										
WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name Maltese 5 8 Fed COM				
						6. Well Number: 31H				
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER										
8. Name of Operator OXY USA INC.						9. OGRID 16696				
10. Address of Operator PO Box 50250, MIDLAND, TX 79710						11. Pool name or Wildcat Antelope Ridge; Wolfcamp				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	3	5	24S	35E		475	North	1475	West	Lea
BH:	M	8	24S	35E		23	South	352	West	Lea
13. Date Spudded 06/21/2023	14. Date T.D. Reached 8/3/2023	15. Date Rig Released 08/06/2023			16. Date Completed (Ready to Produce) 11/20/2023			17. Elevations (DF and RKB, RT, GR, etc.) 3454' GR		
18. Total Measured Depth of Well 22234' MD, 11980' TVD			19. Plug Back Measured Depth 22190' MD, 11978' TVD			20. Was Directional Survey Made? Yes		21. Type Electric and Other Logs Run CBL/GAMMA		
22. Producing Interval(s), of this completion - Top, Bottom, Name 11938'-22041' ; Wolfcamp										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1111'		17 1/2"		1128sx Class C - TOC 0'		
7 5/8"		26.4# HCL80		11319'		9 7/8"		3154sx Class H - TOC 0'		
5 1/2"		20# P110		22214'		6 3/4"		774sx Class H- TOC 0'		
24. LINER RECORD										
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	25. TUBING RECORD					
					SIZE	DEPTH SET	PACKER SET			
26. Perforation record (interval, size, and number) 11938'-22041', 0.42", 2466 holes					27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.					
					DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED			
					11938'-22041'		27,731,900 # sand, 515,084 bbls produced water.			
28. PRODUCTION										
Date First Production 11/26/2023		Production Method (Flowing, gas lift, pumping - Size and type pump) Flowing				Well Status (Prod. or Shut-in) Producing				
Date of Test 11/29/2023	Hours Tested 24 hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 2901	Gas - MCF 2131	Water - Bbl. 5438	Gas - Oil Ratio 735			
Flow Tubing Press.	Casing Pressure 2274	Calculated 24-Hour Rate	Oil - Bbl. 2901	Gas - MCF 2131	Water - Bbl. 5438	Oil Gravity - API - (Corr.)				
29. Disposition of Gas (Sold, used for fuel, vented, etc.) Sold							30. Test Witnessed By			
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							33. Rig Release Date:			
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney		Title Regulatory Analyst Sr.			Date 01/05/2024			
E-mail Address sarah_mckinney@oxy.com										

OXY USA Inc.
Maltese 5 8 Fed Com 31H
API No. 30-025-48974



District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 319334

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 319334
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 319334

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 319334
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
smcgrath	File 3160-4 within 10 days of BLM Approval.	3/1/2024