

1625 N. French Dr., Hobbs, NM 88240

District II

811 S. First St., Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals & Natural ResourcesForm C-104
Revised August 1, 2011Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit one copy to appropriate District Office

☐ AMENDED REPORT

I. REQUEST FOR ALLOWABLE AND AUTHORIZATION TO TRANSPORT

¹ Operator name and Address OXY USA INC. PO BOX 50250 MIDLAND, TX 79710		² OGRID Number 16696
		³ Reason for Filing Code/ Effective Date NW - 11/20/2023
⁴ API Number 30 - 025-48979	⁵ Pool Name ANTELOPE RIDGE; Wolfcamp	
		⁶ Pool Code 2220
⁷ Property Code 330861	⁸ Property Name MALTESE 5 8 FEDERAL COM	⁹ Well Number 36H

II. ¹⁰ Surface Location

UL or lot no. 3	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 475	North/South Line North	Feet from the 1545	East/West line West	County Lea
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

¹¹ Bottom Hole Location

UL or lot no. N	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 25	North/South line South	Feet from the 2071	East/West line West	County Lea
¹² Lse Code F	¹³ Producing Method Code F	¹⁴ Gas Connection Date 11/27/23	¹⁵ C-129 Permit Number	¹⁶ C-129 Effective Date	¹⁷ C-129 Expiration Date				

III. Oil and Gas Transporters

¹⁸ Transporter OGRID	¹⁹ Transporter Name and Address	²⁰ O/G/W
237722	Centerion Pipeline, L.P.	O
248749	DCP Midstream, L.P.	G

IV. Well Completion Data

²¹ Spud Date 06/22/2023	²² Ready Date 11/20/2023	²³ TD 22104' MD, 12162' TVD	²⁴ PBTB 22064' MD, 12159' TVD	²⁵ Perforations 11914-21943	²⁶ DHC, MC
²⁷ Hole Size	²⁸ Casing & Tubing Size	²⁹ Depth Set		³⁰ Sacks Cement	
17 1/2"	13 3/8" 54.5# J-55	1144'		1128sx Class C - TOC 0'	
9 7/8"	7 5/8" 26.4# HCL80	11234'		3163sx Class H - TOC 0'	
6 3/4"	5 1/2" 20# P110	22087'		741sx Class H - TOC 11040'	

V. Well Test Data

³¹ Date New Oil 11/27/2023	³² Gas Delivery Date 11/27/2023	³³ Test Date 12/07/2023	³⁴ Test Length 24 hours	³⁵ Tbg. Pressure	³⁶ Csg. Pressure 1145
³⁷ Choke Size 0	³⁸ Oil 2574	³⁹ Water 2988	⁴⁰ Gas 1948		⁴¹ Test Method Flowing
⁴² I hereby certify that the rules of the Oil Conservation Division have been complied with and that the information given above is true and complete to the best of my knowledge and belief. Signature: <i>Sarah McKinney</i>			OIL CONSERVATION DIVISION		
Printed name: Sarah McKinney			Approved by: <i>PATRICIA MARTINEZ</i>		
Title: Regulatory Analyst Sr.			Title: <i>PETROLEUM SPECIALIST</i>		
E-mail Address: sarah_mckinney@oxy.com			Approval Date: <i>4/19/2024</i>		
Date: 01/09/2024		Phone: 713-215-7295			

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

☒ AMENDED REPORT

As-Drilled Plat

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30-025-48979	² Pool Code 2220	³ Pool Name ANTELOPE RIDGE; Wolfcamp
⁴ Property Code 330861	⁵ Property Name MALTESE 5 8 FED COM	⁶ Well Number 36H
⁷ OGRID No. 16696	⁸ Operator Name OXY USA INC.	⁹ Elevation 3454.2' (NAVD 88)

¹⁰ Surface Location

UL or lot no. 3	Section 5	Township 24S	Range 35E	Lot Idn	Feet from the 475	North/South line NORTH	Feet from the 1545	East/West line WEST	County LEA
--------------------	--------------	-----------------	--------------	---------	----------------------	---------------------------	-----------------------	------------------------	---------------

¹¹ Bottom Hole Location If Different From Surface

UL or lot no. N	Section 8	Township 24S	Range 35E	Lot Idn	Feet from the 25	North/South line SOUTH	Feet from the 2071	East/West line WEST	County LEA
¹² Dedicated Acres 1280	¹³ Joint or Infill Infill	¹⁴ Consolidation Code	¹⁵ Order No.						

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

NAD 83 (SURFACE HOLE LOCATION) LATITUDE = 32°15'09.06" (32.252517°) LONGITUDE = -103°23'35.33" (-103.393147°)	NAD 83 (AS-DRILLED KOP) LATITUDE = 32°15'12.66" (32.253516°) LONGITUDE = -103°23'29.22" (-103.391451°)	NAD 83 (AS-DRILLED FTP) LATITUDE = 32°15'09.90" (32.252750°) LONGITUDE = -103°23'29.03" (-103.391397°)
NAD 27 (SURFACE HOLE LOCATION) LATITUDE = 32°15'08.61" (32.252392°) LONGITUDE = -103°23'33.63" (-103.392674°)	NAD 27 (AS-DRILLED KOP) LATITUDE = 32°15'12.21" (32.253391°) LONGITUDE = -103°23'27.52" (-103.390978°)	NAD 27 (AS-DRILLED FTP) LATITUDE = 32°15'09.45" (32.252625°) LONGITUDE = -103°23'27.33" (-103.390924°)
STATE PLANE NAD 83 (N.M. EAST) N: 456871.72' E: 831988.21'	STATE PLANE NAD 83 (N.M. EAST) N: 457239.71' E: 832509.15'	STATE PLANE NAD 83 (N.M. EAST) N: 456961.30' E: 832528.53'
STATE PLANE NAD 27 (N.M. EAST) N: 456812.32' E: 790803.55'	STATE PLANE NAD 27 (N.M. EAST) N: 457180.29' E: 791324.48'	STATE PLANE NAD 27 (N.M. EAST) N: 456901.89' E: 791343.86'
NAD 83 (AS-DRILLED LPP #1) LATITUDE = 32°14'21.49" (32.239302°) LONGITUDE = -103°23'28.26" (-103.391183°)	NAD 83 (AS-DRILLED LPP #2) LATITUDE = 32°14'08.42" (32.235672°) LONGITUDE = -103°23'28.41" (-103.391224°)	NAD 83 (AS-DRILLED LPP #3) LATITUDE = 32°13'55.35" (32.232043°) LONGITUDE = -103°23'28.53" (-103.391258°)
NAD 27 (AS-DRILLED LPP #1) LATITUDE = 32°14'21.04" (32.239176°) LONGITUDE = -103°23'26.56" (-103.390711°)	NAD 27 (AS-DRILLED LPP #2) LATITUDE = 32°14'07.97" (32.235547°) LONGITUDE = -103°23'26.71" (-103.390752°)	NAD 27 (AS-DRILLED LPP #3) LATITUDE = 32°13'54.90" (32.231917°) LONGITUDE = -103°23'26.83" (-103.390786°)
STATE PLANE NAD 83 (N.M. EAST) N: 452069.24' E: 832637.34'	STATE PLANE NAD 83 (N.M. EAST) N: 450748.70' E: 832636.38'	STATE PLANE NAD 83 (N.M. EAST) N: 449428.18' E: 832637.60'
STATE PLANE NAD 27 (N.M. EAST) N: 452009.95' E: 791452.47'	STATE PLANE NAD 27 (N.M. EAST) N: 450689.45' E: 791451.45'	STATE PLANE NAD 27 (N.M. EAST) N: 449368.97' E: 791452.62'
NAD 83 (AS-DRILLED LTP) LATITUDE = 32°13'31.07" (32.225297°) LONGITUDE = -103°23'28.95" (-103.391375°)	NAD 83 (AS-DRILLED BHL) LATITUDE = 32°13'29.48" (32.224856°) LONGITUDE = -103°23'28.93" (-103.391368°)	
NAD 27 (AS-DRILLED LTP) LATITUDE = 32°13'30.62" (32.225172°) LONGITUDE = -103°23'27.25" (-103.390903°)	NAD 27 (AS-DRILLED BHL) LATITUDE = 32°13'29.03" (32.224731°) LONGITUDE = -103°23'27.23" (-103.390897°)	
STATE PLANE NAD 83 (N.M. EAST) N: 446973.91' E: 832622.94'	STATE PLANE NAD 83 (N.M. EAST) N: 446813.39' E: 832626.28'	
STATE PLANE NAD 27 (N.M. EAST) N: 446914.76' E: 791437.85'	STATE PLANE NAD 27 (N.M. EAST) N: 446754.24' E: 791441.19'	

¹⁷ OPERATOR
CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Sarah McKinney 1/09/24
Signature Date

Sarah McKinney
Printed Name

sarah_mckinney@oxy.com
E-mail Address

¹⁸ SURVEYOR
CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

December 12, 2019

Date of Survey
Signature and Seal of Professional Surveyor:



Certificate Number:


APPROXIMATE WELL BORE DISTANCE FROM FTP TO LTP	
TRACT	DISTANCE
NMNM 014164	4,896.56'
NMNM 034253	1,320.80'
NMNM 014164	1,321.37'
NMNM 0001228A	2,455.62'
TOTAL	9,994.35'

NOTE:

- Distances referenced on plat to section lines are perpendicular.
- Basis of Bearing is a Transverse Mercator Projection with a Central Meridian of W103°53'00" (NAD 83)
- As-Drilled well head has not been field verified.
- Wellbore data provided by Oxy USA Inc.



SCALE
DRAWN BY: N.R. 11-03-23





Oxy Maltese 5-8 Fed Com 36H IFR1 to 22104ft Survey Geodetic Report



DefinitiveSurvey

Report Date:	August 29, 2023 - 02:25 PM (UTC 0)	Survey / DLS Computation:	Minimum Curvature / Lubinski
Client:	OXY	Vertical Section Azimuth:	176.370 °(Grid North)
Field:	NM Lea County (NAD 83)	Vertical Section Origin:	0.000 ft, 0.000 ft
Structure / Slot:	Oxy Maltese 5-8 Fed Com Pad Lot 3 / Maltese 5-8 Fed Com 36H	TVD Reference Datum:	RKB
Well:	Maltese 5-8 Fed Com 36H	TVD Reference Elevation:	3479.200 ft above MSL
Borehole:	Maltese 5-8 Fed Com 36H	Seabed / Ground Elevation:	3454.200 ft above MSL
UBHI / API / JobNumber:	Unknown / Unknown / Unknown	Magnetic Declination:	6.313°
Survey Name / Version:	Oxy Maltese 5-8 Fed Com 36H IFR1 to 22104ft / 3	Total Gravity Field Strength:	998.4651mgn (9.80665 Based)
Survey Date:	August 28, 2023	Gravity Model:	GARM
Tort / AHD / DDI / ERD Ratio:	285.898 ° / 11131.737 ft / 6.762 / 0.915	Total Magnetic Field Strength:	47517.1 nT
Coordinate Reference System:	NAD83 New Mexico State Plane, Eastern Zone, US Feet	Magnetic Dip Angle:	59.822°
Location Lat / Long:	N 32°15'9.06187" , W 103°23'35.32806"	Declination Date:	August 01, 2023
Location Grid N/E Y/X:	N 456871.720 ftUS , E 831988.210 ftUS	Magnetic Declination Model:	IFR1
CRS Grid Convergence Angle:	0.502°	North Reference:	Grid
Grid Scale Factor:	1.00000584	Local Coord. way North S Grid:	5.811°
Engine Version:	2023.1.0.1	Local Coord Referenced To:	Well Head

Comments	MD (ft)	Incl (°)	Azim (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	TVDSS (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ' '')	Longitude (E/W ° ' ' '')	Closure (ft)	Closure Azimuth (°)
WRP First SLB Survey	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-3,479.20		456,871.72	831,988.21	N 32°15'9.06"	W 103°23'35.33"		
	25.00	0.00	0.00	25.00	0.00	0.00	0.00	-3,454.20	0.00	456,871.72	831,988.21	N 32°15'9.06"	W 103°23'35.33"	0.00	0.00
	206.00	0.56	355.51	206.00	-0.88	0.88	-0.07	-3,273.20	0.31	456,872.60	831,988.14	N 32°15'9.07"	W 103°23'35.33"	0.88	355.51
	269.00	0.80	320.66	268.99	-1.55	1.53	-0.37	-3,210.21	0.74	456,873.25	831,987.84	N 32°15'9.08"	W 103°23'35.33"	1.57	346.32
	352.00	0.83	304.23	351.98	-2.39	2.32	-1.24	-3,127.22	0.28	456,874.04	831,986.97	N 32°15'9.08"	W 103°23'35.34"	2.62	331.89
	447.00	0.62	330.59	446.98	-3.27	3.15	-2.06	-3,032.22	0.41	456,874.87	831,986.15	N 32°15'9.09"	W 103°23'35.35"	3.76	326.84
	541.00	0.76	284.30	540.97	-3.92	3.75	-2.91	-2,938.23	0.59	456,875.47	831,985.30	N 32°15'9.10"	W 103°23'35.36"	4.75	322.15
	636.00	0.79	277.75	635.96	-4.25	3.99	-4.17	-2,843.24	0.10	456,875.71	831,984.04	N 32°15'9.10"	W 103°23'35.38"	5.77	313.74
	731.00	1.02	274.39	730.95	-4.49	4.14	-5.66	-2,748.25	0.25	456,875.86	831,982.55	N 32°15'9.10"	W 103°23'35.39"	7.02	306.19
	826.00	0.33	217.00	825.94	-4.40	3.99	-6.67	-2,653.26	0.93	456,875.71	831,981.54	N 32°15'9.10"	W 103°23'35.41"	7.77	300.89
	920.00	1.07	143.72	919.94	-3.46	3.07	-6.31	-2,559.26	1.09	456,874.79	831,981.90	N 32°15'9.09"	W 103°23'35.40"	7.02	295.90
	1,015.00	0.52	106.18	1,014.93	-2.57	2.23	-5.38	-2,464.27	0.77	456,873.95	831,982.83	N 32°15'9.08"	W 103°23'35.39"	5.82	292.54
	1,068.00	0.67	115.10	1,067.93	-2.34	2.03	-4.86	-2,411.27	0.33	456,873.75	831,983.35	N 32°15'9.08"	W 103°23'35.38"	5.27	292.68
	1,224.00	0.36	176.65	1,223.92	-1.41	1.16	-4.01	-2,255.28	0.38	456,872.88	831,984.20	N 32°15'9.07"	W 103°23'35.37"	4.17	286.09
	1,319.00	0.07	26.77	1,318.92	-1.16	0.91	-3.97	-2,160.28	0.44	456,872.63	831,984.24	N 32°15'9.07"	W 103°23'35.37"	4.07	282.93
	1,414.00	0.04	204.79	1,413.92	-1.18	0.93	-3.95	-2,065.28	0.12	456,872.65	831,984.26	N 32°15'9.07"	W 103°23'35.37"	4.06	283.27
	1,509.00	0.06	121.91	1,508.92	-1.12	0.88	-3.93	-1,970.28	0.07	456,872.60	831,984.28	N 32°15'9.07"	W 103°23'35.37"	4.02	282.58
	1,603.00	0.01	257.16	1,602.92	-1.09	0.85	-3.89	-1,876.28	0.07	456,872.57	831,984.32	N 32°15'9.07"	W 103°23'35.37"	3.98	282.29
	1,698.00	0.03	34.55	1,697.92	-1.11	0.87	-3.89	-1,781.28	0.04	456,872.59	831,984.32	N 32°15'9.07"	W 103°23'35.37"	3.98	282.57
	1,793.00	0.06	329.02	1,792.92	-1.17	0.93	-3.90	-1,686.28	0.06	456,872.65	831,984.31	N 32°15'9.07"	W 103°23'35.37"	4.01	283.42
	1,888.00	0.03	8.37	1,887.92	-1.24	1.00	-3.92	-1,591.28	0.04	456,872.72	831,984.29	N 32°15'9.07"	W 103°23'35.37"	4.04	284.27
	1,983.00	0.04	110.43	1,982.92	-1.25	1.01	-3.88	-1,496.28	0.06	456,872.73	831,984.33	N 32°15'9.07"	W 103°23'35.37"	4.01	284.58
	2,077.00	0.06	270.19	2,076.92	-1.24	1.00	-3.90	-1,402.28	0.10	456,872.72	831,984.31	N 32°15'9.07"	W 103°23'35.37"	4.03	284.36
	2,172.00	0.06	84.26	2,171.92	-1.25	1.00	-3.90	-1,307.28	0.13	456,872.72	831,984.31	N 32°15'9.07"	W 103°23'35.37"	4.03	284.43
	2,267.00	0.04	35.89	2,266.92	-1.28	1.04	-3.83	-1,212.28	0.05	456,872.76	831,984.38	N 32°15'9.07"	W 103°23'35.37"	3.97	285.12
	2,362.00	0.03	311.47	2,361.92	-1.32	1.08	-3.83	-1,117.28	0.05	456,872.80	831,984.38	N 32°15'9.07"	W 103°23'35.37"	3.98	285.72
	2,457.00	0.02	76.66	2,456.92	-1.34	1.10	-3.84	-1,022.28	0.05	456,872.82	831,984.37	N 32°15'9.07"	W 103°23'35.37"	3.99	285.99
	2,552.00	0.03	328.12	2,551.92	-1.36	1.12	-3.83	-927.28	0.04	456,872.84	831,984.38	N 32°15'9.07"	W 103°23'35.37"	3.99	286.35
	2,646.00	0.04	3.28	2,645.92	-1.42	1.18	-3.84	-833.28	0.02	456,872.90	831,984.37	N 32°15'9.07"	W 103°23'35.37"	4.02	287.04
	2,741.00	0.06	113.44	2,740.92	-1.43	1.19	-3.80	-738.28	0.09	456,872.91	831,984.41	N 32°15'9.07"	W 103°23'35.37"	3.98	287.42
	2,836.00	0.03	238.52	2,835.92	-1.39	1.16	-3.77	-643.28	0.09	456,872.88	831,984.44	N 32°15'9.07"	W 103°23'35.37"	3.95	287.07
	2,931.00	0.04	288.45	2,930.92	-1.40	1.16	-3.82	-548.28	0.03	456,872.88	831,984.39	N 32°15'9.07"	W 103°23'35.37"	4.00	286.82
	3,026.00	0.12	196.15	3,025.92	-1.31	1.07	-3.88	-453.28	0.13	456,872.79	831,984.33	N 32°15'9.07"	W 103°23'35.37"	4.03	285.42
	3,121.00	0.07	43.61	3,120.92	-1.26	1.02	-3.87	-358.28	0.19	456,872.74	831,984.34	N 32°15'9.07"	W 103°23'35.37"	4.00	284.73
	3,215.00	0.08	42.91	3,214.92	-1.34	1.11	-3.79	-264.28	0.01	456,872.83	831,984.42	N 32°15'9.07"	W 103°23'35.37"	3.95	286.30
	3,310.00	0.22	299.98	3,309.92	-1.49	1.25	-3.90	-169.28	0.26	456,872.97	831,984.31	N 32°15'9.07"	W 103°23'35.37"	4.09	287.73
	3,405.00	0.09	47.11	3,404.92	-1.64	1.39	-4.00	-74.28	0.27	456,873.11	831,984.21	N 32°15'9.08"	W 103°23'35.37"	4.24	289.13
	3,500.00	1.60	215.84	3,499.91	-0.66	0.36	-4.73	20.71	1.78	456,872.08	831,983.48	N 32°15'9.07"	W 103°23'35.38"	4.74	274.41
	3,595.00	1.75	207.83	3,594.87	1.60	-1.99	-6.18	115.67	0.29	456,869.73	831,982.03	N 32°15'9.04"	W 103°23'35.40"	6.49	252.12
	3,690.00	0.39	153.72	3,689.85	3.13	-3.57	-6.71	210.65	1.64	456,868.15	831,981.50	N 32°15'9.03"	W 103°23'35.41"	7.60	242.02
	3,784.00	0.76	76.59	3,783.85	3.32	-3.71	-5.96	304.65	0.82	456,868.01	831,982.25	N 32°15'9.03"	W 103°23'35.40"	7.02	238.13
	3,879.00	0.22	10.67	3,878.84	3.04	-3.38	-5.32	399.64	0.74	456,868.34	831,982.89	N 32°15'9.03"	W 103°23'35.39"	6.30	237.54
	3,974.00	0.82	46.08	3,973.84	2.42	-2.73	-4.79	494.64	0.69	456,868.99	831,983.42	N 32°15'9.04"	W 103°23'35.38"	5.52	240.32
	4,069.00	0.86	49.62	4,068.83	1.56	-1.80	-3.76	589.63	0.07	456,869.92	831,984.45	N 32°15'9.04"	W 103°23'35.37"	4.17	244.44
	4,164.00	0.81	37.63	4,163.82	0.63	-0.81	-2.81	684.62	0.19	456,870.91	831,985.40	N 32°15'9.05"	W 103°23'35.36"	2.92	254.00
	4,259.00	1.23	30.30	4,258.80	-0.72	0.61	-1.88	779.60	0.46	456,872.33	831,986.33	N 32°15'9.07"	W 103°23'35.35"	1.98	287.84
	4,354.00	1.86	54.42	4,353.77	-2.39	2.38	-0.12	874.57	0.94	456,874.10	831,988.09	N 32°15'9.09"	W 103°23'35.33"	2.39	357.21
	4,449.00	2.43	58.30	4,448.70	-4.15	4.34	2.85	969.50	0.62	456,876.06	831,991.06	N 32°15'9.10"	W 103°23'35.29"	5.19	33.31
	4,544.00	2.66	67.24	4,543.61	-5.82	6.25	6.60	1,064.41	0.48	456,877.97	831,994.81	N 32°15'9.12"	W 103°23'35.25"	9.09	46.55
	4,639.00	2.75	86.42	4,638.50	-6.54	7.25	10.90	1,159.30	0.95	456,878.97	831,999.11	N 32°15'9.13"	W 103°23'35.20"	13.09	56.40
	4,734.00	2.13	84.48	4,733.42	-6.60	7.56	14.94	1,254.22	0.66	456,879.28	832,003.15	N 32°15'9.14"	W 103°23'35.15"	16.74	63.16
	4,829.00	3.30	56.23	4,828.31	-8.03	9.25	18.97	1,349.11	1.84	456,880.97	832,007.18	N 32°15'9.15"	W 103°23'35.11"	21.10	64.01
	4,924.00	2.89	61.97	4,923.17	-10.39	11.89	23.35								

Actual KOP	8,531.00	8.88	60.26	8,481.74	-310.99	341.98	478.79	5,002.54	1.20	457,213.70	832,467.00	N 32°15'12.40"	W 103°23'29.72"	588.38	54.46
	8,626.00	7.49	57.01	8,575.77	-317.25	348.99	490.35	5,096.57	1.54	457,220.71	832,478.56	N 32°15'12.47"	W 103°23'29.58"	601.86	54.56
	8,721.00	7.45	58.15	8,669.96	-323.20	355.61	500.77	5,190.76	0.16	457,227.34	832,488.98	N 32°15'12.54"	W 103°23'29.46"	614.19	54.62
	8,816.00	6.08	56.58	8,764.30	-328.61	361.64	510.20	5,285.10	1.46	457,233.36	832,498.42	N 32°15'12.60"	W 103°23'29.35"	625.37	54.67
	8,911.00	4.50	55.85	8,858.89	-333.00	366.50	517.49	5,379.69	1.66	457,238.22	832,505.70	N 32°15'12.64"	W 103°23'29.27"	634.12	54.69
	9,005.00	2.69	52.23	8,952.70	-336.11	369.92	522.28	5,473.50	1.94	457,241.64	832,510.49	N 32°15'12.68"	W 103°23'29.21"	640.02	54.69
	9,100.00	1.02	50.30	9,047.65	-337.86	371.83	524.70	5,568.45	1.76	457,243.55	832,512.91	N 32°15'12.70"	W 103°23'29.18"	643.09	54.68
	9,195.00	0.33	276.70	9,142.65	-338.41	372.40	525.07	5,663.45	1.34	457,244.12	832,513.29	N 32°15'12.70"	W 103°23'29.18"	643.73	54.65
	9,290.00	0.56	276.53	9,237.64	-338.54	372.48	524.34	5,758.44	0.24	457,244.20	832,512.55	N 32°15'12.70"	W 103°23'29.18"	643.18	54.61
	9,385.00	0.18	289.92	9,332.64	-338.68	372.59	523.74	5,853.44	0.41	457,244.31	832,511.95	N 32°15'12.70"	W 103°23'29.19"	642.75	54.57
	9,480.00	0.23	41.46	9,427.64	-338.88	372.78	523.73	5,948.44	0.36	457,244.50	832,511.94	N 32°15'12.70"	W 103°23'29.19"	642.85	54.56
	9,575.00	0.24	223.28	9,522.64	-338.87	372.78	523.72	6,043.44	0.49	457,244.50	832,511.93	N 32°15'12.70"	W 103°23'29.19"	642.84	54.56
	9,669.00	0.54	225.67	9,616.64	-338.45	372.33	523.26	6,137.44	0.32	457,244.05	832,511.48	N 32°15'12.70"	W 103°23'29.20"	642.21	54.57
	9,764.00	0.75	268.58	9,711.63	-338.18	372.00	522.32	6,232.43	0.54	457,243.72	832,510.53	N 32°15'12.70"	W 103°23'29.21"	641.25	54.54
	9,859.00	0.50	283.82	9,806.63	-338.33	372.08	521.30	6,327.43	0.31	457,243.80	832,509.51	N 32°15'12.70"	W 103°23'29.22"	640.47	54.48
	9,954.00	0.19	321.41	9,901.62	-338.58	372.30	520.80	6,422.42	0.39	457,244.02	832,509.01	N 32°15'12.70"	W 103°23'29.23"	640.19	54.44
	10,047.00	0.34	312.79	9,994.62	-338.91	372.61	520.50	6,515.42	0.17	457,244.33	832,508.71	N 32°15'12.70"	W 103°23'29.23"	640.12	54.40
	10,141.00	0.47	224.61	10,088.62	-338.86	372.53	520.02	6,609.42	0.61	457,244.25	832,508.24	N 32°15'12.70"	W 103°23'29.23"	639.69	54.38
	10,236.00	0.74	199.52	10,183.62	-338.03	371.67	519.54	6,704.42	0.39	457,243.39	832,507.76	N 32°15'12.69"	W 103°23'29.24"	638.80	54.42
	10,331.00	0.63	208.04	10,278.61	-337.02	370.63	519.09	6,799.41	0.16	457,242.35	832,507.31	N 32°15'12.68"	W 103°23'29.25"	637.83	54.47
	10,426.00	0.64	218.22	10,373.60	-336.18	369.75	518.52	6,894.40	0.12	457,241.47	832,506.73	N 32°15'12.68"	W 103°23'29.25"	636.85	54.51
	10,521.00	0.36	225.42	10,468.60	-335.59	369.13	517.98	6,989.40	0.30	457,240.85	832,506.19	N 32°15'12.67"	W 103°23'29.26"	636.05	54.53
	10,616.00	0.84	0.20	10,563.60	-336.09	369.61	517.77	7,084.40	1.18	457,241.34	832,505.98	N 32°15'12.67"	W 103°23'29.26"	636.16	54.48
	10,711.00	1.20	354.25	10,658.58	-337.78	371.30	517.67	7,179.38	0.39	457,243.02	832,505.88	N 32°15'12.69"	W 103°23'29.26"	637.06	54.35
	10,806.00	1.45	76.98	10,753.56	-338.97	372.56	518.74	7,274.36	1.85	457,244.28	832,506.96	N 32°15'12.70"	W 103°23'29.25"	638.67	54.31
	10,900.00	1.03	133.63	10,847.55	-338.54	372.25	520.51	7,368.35	1.31	457,243.97	832,508.73	N 32°15'12.70"	W 103°23'29.23"	639.92	54.43
	10,995.00	1.14	169.48	10,942.53	-336.98	370.73	521.30	7,463.33	0.71	457,242.45	832,509.52	N 32°15'12.68"	W 103°23'29.22"	639.69	54.58
11,090.00	1.10	171.22	11,037.51	-335.13	368.90	521.62	7,558.31	0.06	457,240.62	832,509.83	N 32°15'12.67"	W 103°23'29.22"	638.88	54.73	
11,185.00	0.30	233.17	11,132.50	-334.09	367.85	521.56	7,653.30	1.05	457,239.57	832,509.77	N 32°15'12.66"	W 103°23'29.22"	638.23	54.81	
11,217.00	0.19	291.72	11,164.50	-334.07	367.82	521.44	7,685.30	0.81	457,239.54	832,509.65	N 32°15'12.66"	W 103°23'29.22"	638.11	54.80	
11,310.00	0.43	302.18	11,257.50	-334.34	368.06	521.00	7,778.30	0.26	457,239.78	832,509.21	N 32°15'12.66"	W 103°23'29.22"	637.89	54.76	
11,320.00	1.09	200.16	11,267.50	-334.27	367.99	520.94	7,788.30	12.56	457,239.71	832,509.15	N 32°15'12.66"	W 103°23'29.22"	637.80	54.76	
11,404.00	11.59	182.39	11,350.87	-325.12	358.78	520.31	7,871.67	12.56	457,230.50	832,508.52	N 32°15'12.57"	W 103°23'29.23"	632.01	55.41	
11,499.00	20.55	173.28	11,442.08	-298.92	332.63	521.86	7,962.88	9.77	457,204.35	832,510.08	N 32°15'12.31"	W 103°23'29.22"	618.86	57.49	
11,594.00	27.81	169.39	11,528.69	-260.22	294.23	527.90	8,049.49	7.82	457,165.95	832,516.12	N 32°15'11.93"	W 103°23'29.15"	604.36	60.87	
11,689.00	31.43	173.45	11,611.27	-213.47	247.82	534.81	8,132.07	4.35	457,119.54	832,523.02	N 32°15'11.47"	W 103°23'29.08"	589.44	65.14	
11,783.00	46.96	179.47	11,683.93	-154.31	188.74	537.95	8,204.73	16.99	457,060.46	832,526.16	N 32°15'10.88"	W 103°23'29.05"	570.10	70.67	
11,878.00	49.54	179.09	11,747.18	-83.53	117.88	538.84	8,267.98	2.73	456,989.60	832,527.05	N 32°15'10.18"	W 103°23'29.04"	551.58	77.66	
11,958.87	54.41	175.07	11,797.00	-19.87	54.30	542.16	8,317.80	7.18	456,926.02	832,530.37	N 32°15'9.55"	W 103°23'29.01"	544.87	84.28	
11,973.00	55.27	174.42	11,805.13	-8.32	42.80	543.22	8,325.93	7.18	456,914.52	832,531.43	N 32°15'9.44"	W 103°23'29.00"	544.90	85.49	
12,068.00	67.58	173.83	11,850.49	74.88	-40.03	551.76	8,371.29	12.97	456,831.69	832,539.98	N 32°15'8.62"	W 103°23'28.91"	553.21	94.15	
12,162.00	80.12	178.15	11,876.59	164.96	-129.90	557.96	8,397.39	14.05	456,741.82	832,546.17	N 32°15'7.73"	W 103°23'28.84"	572.88	103.11	
12,257.00	90.68	181.00	11,884.20	259.36	-224.45	558.64	8,405.00	11.51							

	19,539.00	86.76	177.87	11,988.56	7,526.83	-7,500.61	651.70	8,509.36	0.32	449,371.08	832,639.91	N 32°13'54.79"	W 103°23'28.51"	7,528.87	175.03
	19,634.00	86.58	179.02	11,994.08	7,621.60	-7,595.42	654.27	8,514.88	1.22	449,276.28	832,642.49	N 32°13'53.85"	W 103°23'28.49"	7,623.54	175.08
	19,728.00	89.19	178.76	11,997.55	7,715.44	-7,689.33	656.09	8,518.35	2.79	449,182.36	832,644.31	N 32°13'52.92"	W 103°23'28.47"	7,717.27	175.12
	19,823.00	84.97	178.83	12,002.39	7,810.21	-7,784.16	658.09	8,523.19	4.44	449,087.53	832,646.30	N 32°13'51.98"	W 103°23'28.46"	7,811.93	175.17
	19,918.00	85.52	180.30	12,010.27	7,904.73	-7,878.83	658.81	8,531.07	1.65	448,992.86	832,647.02	N 32°13'51.05"	W 103°23'28.46"	7,906.32	175.22
	20,013.00	85.26	180.57	12,017.90	7,999.19	-7,973.52	658.09	8,538.70	0.39	448,898.17	832,646.30	N 32°13'50.11"	W 103°23'28.48"	8,000.63	175.28
	20,203.00	85.40	179.81	12,033.37	8,188.13	-8,162.88	657.46	8,554.17	0.41	448,708.80	832,645.67	N 32°13'48.24"	W 103°23'28.51"	8,189.32	175.40
	20,298.00	85.40	181.05	12,040.99	8,282.59	-8,257.57	656.75	8,561.79	1.30	448,614.11	832,644.96	N 32°13'47.30"	W 103°23'28.52"	8,283.65	175.45
	20,392.00	84.88	180.53	12,048.95	8,375.97	-8,351.23	655.46	8,569.75	0.78	448,520.46	832,643.67	N 32°13'46.37"	W 103°23'28.55"	8,376.91	175.51
	20,487.00	86.23	179.96	12,056.32	8,470.46	-8,445.94	655.05	8,577.12	1.54	448,425.75	832,643.27	N 32°13'45.43"	W 103°23'28.56"	8,471.30	175.57
	20,677.00	85.94	180.18	12,069.29	8,659.63	-8,635.49	654.82	8,590.09	0.19	448,236.19	832,643.04	N 32°13'43.56"	W 103°23'28.59"	8,660.28	175.66
	20,772.00	86.06	180.64	12,075.91	8,754.16	-8,730.26	654.14	8,596.71	0.50	448,141.43	832,642.36	N 32°13'42.62"	W 103°23'28.60"	8,754.73	175.71
	20,962.00	85.30	179.88	12,090.23	8,943.18	-8,919.71	653.28	8,611.03	0.56	447,951.97	832,641.50	N 32°13'40.75"	W 103°23'28.63"	8,943.61	175.81
	21,057.00	85.07	180.54	12,098.20	9,037.63	-9,014.38	652.94	8,619.00	0.73	447,857.31	832,641.15	N 32°13'39.81"	W 103°23'28.65"	9,037.99	175.86
	21,152.00	86.55	181.73	12,105.14	9,132.05	-9,109.10	651.06	8,625.94	2.00	447,762.58	832,639.27	N 32°13'38.87"	W 103°23'28.68"	9,132.34	175.91
	21,247.00	87.90	182.94	12,109.74	9,226.42	-9,203.91	647.19	8,630.54	1.91	447,667.78	832,635.41	N 32°13'37.94"	W 103°23'28.73"	9,226.63	175.98
	21,436.00	88.62	185.08	12,115.48	9,413.64	-9,392.34	633.98	8,636.28	1.19	447,479.34	832,622.20	N 32°13'36.07"	W 103°23'28.91"	9,413.72	176.14
	21,531.00	86.68	181.85	12,119.38	9,507.82	-9,487.07	628.25	8,640.18	3.96	447,384.61	832,616.46	N 32°13'35.14"	W 103°23'28.98"	9,507.85	176.21
	21,626.00	85.40	179.45	12,125.94	9,602.32	-9,581.83	627.17	8,646.74	2.86	447,289.85	832,615.38	N 32°13'34.20"	W 103°23'29.00"	9,602.34	176.26
	21,815.00	85.64	178.48	12,140.70	9,790.54	-9,770.22	630.57	8,661.50	0.53	447,101.46	832,618.78	N 32°13'32.33"	W 103°23'28.98"	9,790.55	176.31
	21,910.00	85.51	177.67	12,148.03	9,885.22	-9,864.88	633.75	8,668.83	0.86	447,006.80	832,621.97	N 32°13'31.40"	W 103°23'28.96"	9,885.22	176.32
	22,005.00	85.76	178.93	12,155.26	9,979.89	-9,959.56	636.56	8,676.06	1.35	446,912.12	832,624.78	N 32°13'30.46"	W 103°23'28.93"	9,979.89	176.34
LTP / 100 ft FSL Cross	22,029.00	85.84	179.04	12,157.02	10,003.80	-9,983.50	636.99	8,677.82	0.55	446,888.19	832,625.20	N 32°13'30.22"	W 103°23'28.93"	10,003.80	176.35
Final Survey	22,070.00	85.97	179.22	12,159.95	10,044.64	-10,024.39	637.61	8,680.75	0.55	446,847.29	832,625.82	N 32°13'29.82"	W 103°23'28.93"	10,044.64	176.36
Projection to Total Depth	22,104.00	85.97	179.22	12,162.34	10,078.52	-10,058.30	638.07	8,683.14	0.00	446,813.38	832,626.28	N 32°13'29.48"	W 103°23'28.93"	10,078.52	176.37

Survey Type: DefinitiveSurvey

Survey Error Model: ISCWSA0 2.795 sigma

Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Expected Max Inclination (deg)	Survey Tool Code	Borehole / Survey
	1	0.000	1,068.000	Act Stns		A009Mb_MWD+IFR1+SAG	Maltese 5-8 Fed Com 36H / Oxy Maltese 5-8 Fed Com 36H IFR1 to 22104ft
	1	1,068.000	22,104.000	Act Stns		A010Mb_MWD+IFR1+SAG+MS	Maltese 5-8 Fed Com 36H / Oxy Maltese 5-8 Fed Com 36H IFR1 to 22104ft

EOU Geometry:

End MD (ft)	Hole Size (in)	Casing Size (in)	Name
22,104.000	26.400	26.400	

Intent ☐ As Drilled ☒

API # 30-025-48979		
Operator Name: OXY USA INC.	Property Name: Maltese 5 8 Federal Com	Well Number 36H

Kick Off Point (KOP)

UL 3	Section 5	Township 24S	Range 35E	Lot	Feet 112	From N/S North	Feet 2070	From E/W West	County Lea
Latitude 32.253516					Longitude -103.391451				NAD Nad83

First Take Point (FTP)

UL 3	Section 5	Township 24S	Range 35E	Lot	Feet 391	From N/S North	Feet 2086	From E/W West	County Lea
Latitude 32.252750					Longitude -103.391397				NAD Nad83

Last Take Point (LTP)

UL N	Section 8	Township 24S	Range 35E	Lot	Feet 186	From N/S South	Feet 2070	From E/W West	County Lea
Latitude 32.225297					Longitude -103.391375				NAD Nad83

Is this well the defining well for the Horizontal Spacing Unit? ☐ NoIs this well an infill well? ☐ Yes

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API # 30-025-48978		
Operator Name: OXY USA INC.	Property Name: Maltese 5 8 Fed Com	Well Number 35H

KZ 06/29/2018

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW / 32.252517 / -103.393146	County or Parish/State: LEA / NM
Well Number: 36H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM014164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548979	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Subsequent Report

Sundry ID: 2767967

Type of Submission: Subsequent Report	Type of Action: Hydraulic Fracturing
Date Sundry Submitted: 01/03/2024	Time Sundry Submitted: 12:45
Date Operation Actually Began: 10/03/2023	

Actual Procedure: RUPU 10/03/2023, RIH & Clean out to PBTD 22063'. Test production casing to 6000 psi for 30 min, good test. RIH and Perf from 11914'-21943', total 2400 holes, 0.42". Frac in 40 stages with 27,027,620 #'s sand and 492,900 bbls produced water, 11,365 bbls brackish water, RD Frac and well ready to produce on 11/20/2023.

Received by OCD: 1/18/2024 8:06:15 AM

Page 8 of 13

Well Name: MALTESE 5_8 FEDERAL COM	Well Location: T24S / R35E / SEC 5 / NENW / 32.252517 / -103.393146	County or Parish/State: LEA / NM
Well Number: 36H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM014164	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002548979	Well Status: Producing Oil Well	Operator: OXY USA INCORPORATED

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: SARAH MCKINNEY	Signed on: JAN 03, 2024 12:45 PM
Name: OXY USA INCORPORATED	
Title: Regulatory Analyst Sr	
Street Address: 5 GREENWAY PLAZA SUITE 110	
City: HOUSTON	State: TX
Phone: (713) 215-7295	
Email address: SARAH_MCKINNEY@OXY.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: JONATHON W SHEPARD	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752345972	BLM POC Email Address: jshepard@blm.gov
Disposition: Accepted	Disposition Date: 01/10/2024
Signature: Jonathon Shepard	

Submit To Appropriate District Office Two Copies District I 1625 N. French Dr., Hobbs, NM 88240 District II 811 S. First St., Artesia, NM 88210 District III 1000 Rio Brazos Rd., Aztec, NM 87410 District IV 1220 S. St. Francis Dr., Santa Fe, NM 87505		State of New Mexico Energy, Minerals and Natural Resources Oil Conservation Division 1220 South St. Francis Dr. Santa Fe, NM 87505				Form C-105 Revised April 3, 2017				
1. WELL API NO. 30-025-48979										
2. Type of Lease ☐ STATE ☐ FEE ☒ FED/INDIAN										
3. State Oil & Gas Lease No.										
WELL COMPLETION OR RECOMPLETION REPORT AND LOG										
4. Reason for filing: ☒ COMPLETION REPORT (Fill in boxes #1 through #31 for State and Fee wells only) ☐ C-144 CLOSURE ATTACHMENT (Fill in boxes #1 through #9, #15 Date Rig Released and #32 and/or #33; attach this and the plat to the C-144 closure report in accordance with 19.15.17.13.K NMAC)						5. Lease Name or Unit Agreement Name Maltese 5 8 Fed COM				
7. Type of Completion: ☒ NEW WELL ☐ WORKOVER ☐ DEEPENING ☐ PLUGBACK ☐ DIFFERENT RESERVOIR ☐ OTHER						6. Well Number: 36H				
8. Name of Operator OXY USA INC.						9. OGRID 16696				
10. Address of Operator PO Box 50250, MIDLAND, TX 79710						11. Pool name or Wildcat Antelope Ridge; Wolfcamp				
12. Location	Unit Ltr	Section	Township	Range	Lot	Feet from the	N/S Line	Feet from the	E/W Line	County
Surface:	3	5	24S	35E		475	North	1545	West	Lea
BH:	N	8	24S	35E		25	South	2071	West	Lea
13. Date Spudded 06/22/2023	14. Date T.D. Reached 08/27/2023		15. Date Rig Released 08/31/2023		16. Date Completed (Ready to Produce) 11/20/2023			17. Elevations (DF and RKB, RT, GR, etc.) 3454' GR		
18. Total Measured Depth of Well 22104' MD, 12162' TVD			19. Plug Back Measured Depth 22064' MD, 12159' TVD		20. Was Directional Survey Made? Yes			21. Type Electric and Other Logs Run CBL/GAMMA		
22. Producing Interval(s), of this completion - Top, Bottom, Name 11914-21943, Wolfcamp										
23. CASING RECORD (Report all strings set in well)										
CASING SIZE		WEIGHT LB./FT.		DEPTH SET		HOLE SIZE		CEMENTING RECORD		AMOUNT PULLED
13 3/8"		54.5# J-55		1144'		17 1/2"		1128sx Class C - TOC 0'		
7 5/8"		26.4# HCL80		11234'		9 7/8"		3163sx Class H - TOC 0'		
5 1/2"		20# P110		22087'		6 3/4"		741sx Class H - TOC 11040'		
24. LINER RECORD										
SIZE	TOP	BOTTOM	SACKS CEMENT	SCREEN	25. TUBING RECORD					
					SIZE	DEPTH SET	PACKER SET			
26. Perforation record (interval, size, and number) 11914-21943, 0.42", 2400 Holes					27. ACID, SHOT, FRACTURE, CEMENT, SQUEEZE, ETC.					
					DEPTH INTERVAL		AMOUNT AND KIND MATERIAL USED			
					11914-21943		492,900 bbls Produced Water, 11365 bbls brackish water, 27,027,620 #'s sand.			
28. PRODUCTION										
Date First Production 11/27/2023		Production Method (Flowing, gas lift, pumping - Size and type pump) Flowing				Well Status (Prod. or Shut-in) Producing				
Date of Test 12/07/2023	Hours Tested 24 hours	Choke Size 0	Prod'n For Test Period	Oil - Bbl 2574	Gas - MCF 1948	Water - Bbl. 2988	Gas - Oil Ratio 757			
Flow Tubing Press.	Casing Pressure 1145	Calculated 24-Hour Rate	Oil - Bbl. 2574	Gas - MCF 1948	Water - Bbl. 2988	Oil Gravity - API - (Corr.)				
29. Disposition of Gas (Sold, used for fuel, vented, etc.) Sold							30. Test Witnessed By			
31. List Attachments C104c, C102, WBD, Directional Survey, CBL										
32. If a temporary pit was used at the well, attach a plat with the location of the temporary pit.							33. Rig Release Date:			
34. If an on-site burial was used at the well, report the exact location of the on-site burial:										
Latitude _____ Longitude _____ NAD83										
I hereby certify that the information shown on both sides of this form is true and complete to the best of my knowledge and belief										
Signature 		Printed Name Sarah McKinney		Title Regulatory Analyst Sr.			Date 01/09/2024			
E-mail Address sarah_mckinney@oxy.com										

This form is to be filed with the appropriate District Office of the Division not later than 20 days after the completion of any newly-drilled or deepened well and not later than 60 days after completion of closure. When submitted as a completion report, this shall be accompanied by one copy of all electrical and radio-activity logs run on the well and a summary of all special tests conducted, including drill stem tests. All depths reported shall be measured depths. In the case of directionally drilled wells, true vertical depths shall also be reported. For multiple completions, items 11, 12 and 26-31 shall be reported for each zone.

Southeastern New Mexico		Northwestern New Mexico	
T. Rustler 824'	T. Bell Canyon	T. Ojo Alamo	T. Penn A"
T. Salado 1181'	T. Strawn	T. Kirtland	T. Penn. "B"
T. Castile 4030'	T. Atoka	T. Fruitland	T. Penn. "C"
T. Delaware 5224'	T. Miss	T. Pictured Cliffs	T. Penn. "D"
T. Cherry Canyon 6237'	T. Devonian	T. Cliff House	T. Leadville
T. Brushy Canyon 7596'	T. Silurian	T. Menefee	T. Madison
T. Grayburg	T. Montoya	T. Point Lookout	T. Elbert
T. San Andres	T. Simpson	T. Mancos	T. McCracken
T. Glorieta	T. McKee	T. Gallup	T. Ignacio Otzte
T. Paddock	T. Ellenburger	Base Greenhorn	T. Granite
T. Blinebry	T. Gr. Wash	T. Dakota	
T. Tubb	T. Delaware Sand	T. Morrison	
T. Drinkard	T. Bone Springs 8913'	T. Todilto	
T. Abo	T. 1 st Bone Springs 9999'	T. Entrada	
T. Wolfcamp	T. 2 nd Bone Springs 10546'	T. Wingate	
T. Penn	T. 3 rd Bone Springs 11560'	T. Chinle	
T. Cisco (Bough C)	T. Wolfcamp 11991	T. Permian	

No. 1, from.....to.....

No. 2, from.....to.....

No. 3, from.....to.....

No. 4, from.....to.....


Include data on rate of water inflow and elevation to which water rose in hole.

No. 1, from.....to.....feet.....
 No. 2, from.....to.....feet.....
 No. 3, from.....to.....feet.....

From	To	Thickness In Feet	Lithology

From	To	Thickness In Feet	Lithology

OXY USA Inc.
Maltese 5 8 Fed Com 36H
API No. 30-025-48979



District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

ACKNOWLEDGMENTS

Action 304804

ACKNOWLEDGMENTS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 304804
	Action Type: [C-104] Completion Packet (C-104C)

ACKNOWLEDGMENTS

☒	I hereby certify that the required Water Use Report has been, or will be, submitted for this wells completion.
☒	I hereby certify that the required FracFocus disclosure has been, or will be, submitted for this wells completion.

District I
1625 N. French Dr., Hobbs, NM 88240
Phone:(575) 393-6161 Fax:(575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone:(575) 748-1283 Fax:(575) 748-9720
District III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone:(505) 334-6178 Fax:(505) 334-6170
District IV
1220 S. St Francis Dr., Santa Fe, NM 87505
Phone:(505) 476-3470 Fax:(505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 304804

CONDITIONS

Operator: OXY USA INC P.O. Box 4294 Houston, TX 772104294	OGRID: 16696
	Action Number: 304804
	Action Type: [C-104] Completion Packet (C-104C)

CONDITIONS

Created By	Condition	Condition Date
plmartinez	File 3160-4 Completion Report within 10 days of BLM approval.	4/19/2024