

Well Name: POKER LAKE UNIT 28 BS	Well Location: T25S / R31E / SEC 28 / SENW / 32.10187 / -103.785143	County or Parish/State: EDDY / NM
Well Number: 210H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMLC062140A	Unit or CA Name: POKER LAKE UNIT	Unit or CA Number: NMNM71016X
US Well Number:	Operator: XTO PERMIAN OPERATING LLC	

Notice of Intent

Sundry ID: 2820229

Type of Submission: Notice of Intent	Type of Action: APD Change
Date Sundry Submitted: 10/31/2024	Time Sundry Submitted: 01:14
Date proposed operation will begin: 11/14/2024	

Procedure Description: XTO Permian Operating, LLC. respectfully requests approval to make the following changes to the approved APD. Changes to include KOP, FTP, LTP, BHL, & Proposed total Depth. There will be no additional surface disturbance. FROM: TO: KOP: 2435' FNL & 2040' FWL OF SECTION 28-T25S-R31E 2036' FNL & 2008' FWL OF SECTION 28-T25S-R31E FTP: 2435' FNL & 2530' FWL OF SECTION 28-T25S-R31E 2552' FSL & 2010' FWL OF SECTION 28-T25S-R31E LTP: 100' FSL & 2530' FWL OF SECTION 4-T26S-R31E 100' FSL & 2010' FWL OF SECTION 4-T26S-R31E BHL: 50' FSL & 2530' FWL OF SECTION 4-T26S-R31E 50' FSL & 2010' FWL OF SECTION 4-T26S-R31E The proposed total depth is changing from 24799' MD; 10989' TVD (Bone Spring) to 24348' MD; 10790' TVD (Bone Spring). A saturated salt brine will be utilized while drilling through the salt formations.

NOI Attachments

Procedure Description

PLU_28_BS____210H_Sundry_Attachments_20241209103637.pdf

Well Name: POKER LAKE UNIT 28 BS	Well Location: T25S / R31E / SEC 28 / SENW / 32.10187 / -103.785143	County or Parish/State: EDDY / NM
Well Number: 210H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMLC062140A	Unit or CA Name: POKER LAKE UNIT	Unit or CA Number: NMNM71016X
US Well Number:	Operator: XTO PERMIAN OPERATING LLC	

Conditions of Approval

Additional

Poker_Lake_Unit_28_BS_309H_310H_209H_210H_COA_20241216074701.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: TERRA SEBASTIAN	Signed on: DEC 09, 2024 10:36 AM
Name: XTO PERMIAN OPERATING LLC	
Title: Regulatory Advisor	
Street Address: 6401 HOLIDAY HILL ROAD SUITE 200	
City: MIDLAND	State: TX
Phone: (432) 999-3107	
Email address: TERRA.B.SEBASTIAN@EXXONMOBIL.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752342234	BLM POC Email Address: cwalls@blm.gov
Disposition: Approved	Disposition Date: 12/16/2024
Signature: Chris Walls	

Form 3160-5 (June 2019)	UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT	FORM APPROVED OMB No. 1004-0137 Expires: October 31, 2021
SUNDRY NOTICES AND REPORTS ON WELLS <i>Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.</i>		5. Lease Serial No.
		6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2		7. If Unit of CA/Agreement, Name and/or No.
1. Type of Well <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		8. Well Name and No.
2. Name of Operator		9. API Well No.
3a. Address	3b. Phone No. (include area code)	10. Field and Pool or Exploratory Area
4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)		11. Country or Parish, State

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA				
TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)		
	Title	
Signature	Date	

THE SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Location of Well

0. SHL: SENW / 2435 FNL / 2040 FWL / TWSP: 25S / RANGE: 31E / SECTION: 28 / LAT: 32.10187 / LONG: -103.785143 (TVD: 0 feet, MD: 0 feet)

PPP: SENW / 2435 FNL / 2530 FWL / TWSP: 25S / RANGE: 31E / SECTION: 28 / LAT: 32.101869 / LONG: -103.783561 (TVD: 10989 feet, MD: 11349 feet)

PPP: NENW / 0 FNL / 2550 FWL / TWSP: 25S / RANGE: 31E / SECTION: 33 / LAT: 32.093982 / LONG: -103.783575 (TVD: 10989 feet, MD: 14289 feet)

PPP: NESW / 2652 FNL / 2531 FWL / TWSP: 25S / RANGE: 31E / SECTION: 28 / LAT: 32.101273 / LONG: -103.783562 (TVD: 10989 feet, MD: 11649 feet)

BHL: SESW / 50 FSL / 2530 FWL / TWSP: 26S / RANGE: 31E / SECTION: 4 / LAT: 32.064895 / LONG: -103.783625 (TVD: 10989 feet, MD: 24799 feet)

CONFIDENTIAL

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	XTO
LEASE NO.:	NMLC062140A
LOCATION:	Sec. 28, T.25 S, R 31 E
COUNTY:	Eddy County, New Mexico ▼
WELL NAME & NO.:	Poker Lake Unit 28 BS 309H
SURFACE HOLE FOOTAGE:	2435'/N & 1951'/E
BOTTOM HOLE FOOTAGE:	50'/S & 2332'/E

WELL NAME & NO.:	Poker Lake Unit 28 BS 310H
SURFACE HOLE FOOTAGE:	2435'/N & 1921'/E
BOTTOM HOLE FOOTAGE:	50'/S & 1712'/E

WELL NAME & NO.:	Poker Lake Unit 28 BS 209H
SURFACE HOLE FOOTAGE:	2435'/N & 2010'/W
BOTTOM HOLE FOOTAGE:	50'/S & 1750'/W

WELL NAME & NO.:	Poker Lake Unit 28 BS 210H
SURFACE HOLE FOOTAGE:	2435'/N & 2040'/W
BOTTOM HOLE FOOTAGE:	50'/S & 2010'/W

COA

H ₂ S	<input checked="" type="radio"/> No <input type="radio"/> Yes			
Potash / WIPP	<input checked="" type="radio"/> None <input type="radio"/> Secretary <input type="radio"/> R-111-Q <input type="checkbox"/> Open Annulus <input type="checkbox"/> WIPP	Choose an option (including blank option.)		
Cave / Karst	<input type="radio"/> Low	<input type="radio"/> Medium	<input checked="" type="radio"/> High	<input type="radio"/> Critical
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both	<input type="radio"/> Diverter
Cementing	<input checked="" type="checkbox"/> Primary Squeeze	<input type="checkbox"/> Cont. Squeeze	<input checked="" type="checkbox"/> EchoMeter	<input type="checkbox"/> DV Tool
Special Req	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input checked="" type="checkbox"/> Unit
Waste Prev.	<input type="radio"/> Self-Certification	<input type="radio"/> Waste Min. Plan	<input checked="" type="radio"/> APD Submitted prior to 06/10/2024	
Additional Language	<input checked="" type="checkbox"/> Flex Hose <input type="checkbox"/> Casing Clearance <input type="checkbox"/> Pilot Hole <input checked="" type="checkbox"/> Break Testing	<input type="checkbox"/> Four-String <input checked="" type="checkbox"/> Offline Cementing <input type="checkbox"/> Fluid-Filled		

Changes approved through engineering via **Sundry 2820285,2820283,2820196,2820229** on 12-15-2024. Any previous COAs not addressed within the updated COAs still apply.

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet 43 CFR 3176 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The **9-5/8** inch surface casing shall be set at approximately **995** feet (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite, above the salt, and below usable fresh water) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 pounds compressive strength**, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **7-5/8** inch intermediate casing is:
Operator has proposed to cement in two stages by conventionally cementing the first stage and performing a bradenhead squeeze on the second stage, contingent upon no returns to surface.
 - a. **First stage:** Operator will cement with intent to reach the top of the **Brushy Canyon at 6873-6900’**.
 - b. **Second stage:** Operator will perform bradenhead squeeze and top-out. Cement to surface. If cement does not reach surface, the appropriate BLM office shall be notified.

Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

- ❖ In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

Operator has proposed to pump down **Surface X Intermediate 1** annulus after primary cementing stage. **Operator must run Echo-meter to verify Cement Slurry/Fluid top in the annulus OR operator shall run a CBL from TD of the Surface casing to tieback requirements listed above after the second stage BH to verify TOC.** Submit results to the BLM. No displacement fluid/wash out shall be utilized at the top of the cement slurry between

second stage BH and top out. Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

If cement does not reach surface, the next casing string must come to surface.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)

Unit Wells

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months. **(This is not necessary for secondary recovery unit wells)**

BOPE Break Testing Variance

- BOPE Break Testing is ONLY permitted for intervals utilizing a 5M BOPE or less. **(Annular preventer must be tested to a minimum of 70% of BOPE working pressure and shall be higher than the MASP.)**
- BOPE Break Testing is NOT permitted to drilling the production hole section.
- Variance only pertains to the intermediate hole-sections and no deeper than the Bone Springs formation.
- While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Any well control event while drilling require notification to the BLM Petroleum Engineer **(575-706-2779)** prior to the commencement of any BOPE Break Testing operations.
- A full BOPE test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOPE test will be required. (200' TVD tolerance between intermediate shoes is allowable).
- The BLM is to be contacted **(575-361-2822 Eddy County)** 4 hours prior to BOPE tests.
- As a minimum, a full BOPE test shall be performed at 21-day intervals.
- In the event any repairs or replacement of the BOPE is required, the BOPE shall test as per **43 CFR 3172**.
- If in the event break testing is not utilized, then a full BOPE test would be conducted.

Offline Cementing

Contact the BLM prior to the commencement of any offline cementing procedure.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Contact Eddy County Petroleum Engineering Inspection Staff:

Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220;
[BLM NM CFO DrillingNotifications@BLM.GOV](mailto:BLM_NM_CFO_DrillingNotifications@BLM.GOV); (575) 361-2822

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - i. Notify the BLM when moving in and removing the Spudder Rig.
 - ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.

- iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - iii. Manufacturer representative shall install the test plug for the initial BOP test.
 - iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.

- v. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)
 - iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - iv. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - v. The results of the test shall be reported to the appropriate BLM office.

- vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- vii. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Approved by Zota Stevens on 12/15/2024
575-234-5998 / zstevens@blm.gov

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- d. Spudding well (minimum of 24 hours)
- e. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- f. BOPE tests (minimum of 4 hours)

Contact Eddy County Petroleum Engineering Inspection Staff:

Email or call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220;

BLM_NM_CFO_DrillingNotifications@BLM.GOV; (575) 361-2822

- 4. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - i. Notify the BLM when moving in and removing the Spudder Rig.
 - ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.
- 5. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 6. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

E. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

F. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's

requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - iii. Manufacturer representative shall install the test plug for the initial BOP test.
 - iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
 - v. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve

- open. (only applies to single stage cement jobs, prior to the cement setting up.)
- iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - iv. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - v. The results of the test shall be reported to the appropriate BLM office.
 - vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - vii. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
 - viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

G. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

H. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be

disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Approved by Zota Stevens on 12/15/2024

575-234-5998 / zstevens@blm.gov

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION		Revised July 9, 2024	
			Submittal Type:	<input type="checkbox"/> Initial Submittal
				<input checked="" type="checkbox"/> Amended Report
		<input type="checkbox"/> As Drilled		

APD ID: 10400094969		WELL LOCATION INFORMATION	
API Number 30-015	Pool Code 97860	Pool Name Jennings, Bone Springs, west	
Property Code	Property Name POKER LAKE UNIT 28 BS	Well Number 210H	
ORGID No. 373075	Operator Name XTO PERMIAN OPERATING, LLC.	Ground Level Elevation 3,335'	
Surface Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal		Mineral Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal	

Surface Location									
UL F	Section 28	Township 25 S	Range 31 E	Lot	Ft. from N/S 2,435' FNL	Ft. from E/W 2,040' FWL	Latitude 32.101870	Longitude -103.785143	County EDDY
Bottom Hole Location									
UL N	Section 4	Township 26 S	Range 31 E	Lot	Ft. from N/S 50' FSL	Ft. from E/W 2,010' FWL	Latitude 32.064892	Longitude -103.785303	County EDDY
Dedicated Acres 400		Infill or Defining Well INFILL		Defining Well API		Overlapping Spacing Unit (Y/N) No		Consolidation Code U	
Order Numbers.						Well setbacks are under Common Ownership: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			

Kick Off Point (KOP)									
UL F	Section 28	Township 25 S	Range 31 E	Lot	Ft. from N/S 2,036' FNL	Ft. from E/W 2,008' FWL	Latitude 32.102967	Longitude -103.785242	County EDDY
First Take Point (FTP)									
UL K	Section 28	Township 25 S	Range 31 E	Lot	Ft. from N/S 2,552' FSL	Ft. from E/W 2,010' FWL	Latitude 32.100998	Longitude -103.785246	County EDDY
Last Take Point (LTP)									
UL N	Section 4	Township 26 S	Range 31 E	Lot	Ft. from N/S 100' FSL	Ft. from E/W 2,010' FWL	Latitude 32.065029	Longitude -103.785303	County EDDY
Unitized Area or Area of Uniform Interest NMNM-071016X		Spacing Unit Type <input checked="" type="checkbox"/> Horizontal <input type="checkbox"/> Vertical				Ground Floor Elevation: 3,335'			

OPERATOR CERTIFICATIONS		SURVEYOR CERTIFICATIONS	
<p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p>If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling form the division.</p> <p>Terra Sebastian 10/30/2024</p>		<p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>I, TIM C. PAPPAS, NEW MEXICO PROFESSIONAL SURVEYOR NO. 21209, DO HEREBY CERTIFY THAT THIS SURVEY PLAT AND THE ACTUAL SURVEY ON THE GROUND UPON WHICH IT IS BASED WERE PERFORMED BY ME OR UNDER MY DIRECT SUPERVISION; THAT I AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY MEETS THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO, AND THAT IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.</p> <p>30 Sept 2024</p> <p>TIM C. PAPPAS REGISTERED PROFESSIONAL LAND SURVEYOR STATE OF NEW MEXICO NO. 21209</p>	
Signature Date		Signature and Seal of Professional Surveyor	
Terra Sebastian			
Printed Name		Certificate Number	Date of Survey
terra.b.sebastian@exxonmobil.com		TIM C. PAPPAS 21209	9/28/2024
Email Address			

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

**DRILLING PLAN: BLM COMPLIANCE
(Supplement to BLM 3160-3)**

XTO Energy Inc.
POKER LAKE UNIT 28 BS 210H
Projected TD: 24348.04' MD / 10790' TVD
SHL: 2435' FNL & 2040' FWL , Section 28, T25S, R31E
BHL: 50' FSL & 2010' FWL , Section 4, T26S, R31E
EDDY County, NM

1. Geologic Name of Surface Formation

A. Quaternary

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

Formation	Well Depth (TVD)	Water/Oil/Gas
Rustler	922'	Water
Top of Salt	1222'	Water
Base of Salt	3991'	Water
Delaware	4222'	Water
Brushy Canyon	6873'	Water/Oil/Gas
Bone Spring	8164'	Water
Avalon	8273'	Water/Oil/Gas
1st Bone Spring	8900'	Water/Oil/Gas
2nd Bone Spring	9418'	Water/Oil/Gas
3rd Bone Spring	10242'	Water/Oil/Gas
Target/Land Curve	10790'	Water/Oil/Gas

*** Hydrocarbons @ Brushy Canyon

*** Groundwater depth 40' (per NM State Engineers Office).

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 9.625 inch casing @ 1022' (200' above the salt) and circulating cement back to surface. The intermediate will isolate from the top of salt down to the next casing seat by setting 7.625 inch casing at 9888.45' and cemented to surface. A 6.75 inch curve and 6.75 inch lateral hole will be drilled to 24348.04 MD/TD and 5.5 inch production casing will be set at TD and cemented back up in the intermediate shoe (estimated TOC 9588.45 feet).

3. Casing Design

Hole Size	Depth	OD Csg	Weight	Grade	Collar	New/Used	SF Burst	SF Collapse	SF Tension
12.25	0' – 1022'	9.625	40	J-55	BTC	New	1.61	6.16	15.41
8.75	0' – 4000'	7.625	29.7	RY P-110	Flush Joint	New	2.82	2.86	1.90
8.75	4000' – 9888.45'	7.625	29.7	HC L-80	Flush Joint	New	2.05	2.32	2.32
6.75	0' – 9788.45'	5.5	20	RY P-110	Freedom/Semi-Permium	New	1.05	2.14	2.03
6.75	9788.45' - 24348.04'	5.5	20	RY P-110	Talon/Semi-Flush	New	1.05	1.94	2.03

· XTO requests the option to utilize a spudder rig (Atlas Copco RD20 or Equivalent) to set and cement surface casing per this Sundry

Wellhead:

Operator will utilize Multibowl System - See Attached

4. Cement Program**Surface Casing: 9.625, 40 New BTC, J-55 casing to be set at +/- 1022'**Lead: 240 sxs EconoCem-HLTRRC (mixed at 10.5 ppg, 1.87 ft³/sx, 10.13 gal/sx water)Tail: 130 sxs Class C + 2% CaCl (mixed at 14.8 ppg, 1.35 ft³/sx, 6.39 gal/sx water)

Top of Cement: Surface

Compressives: 12-hr = 900 psi 24 hr = 1500 psi

Intermediate Casing: 7.625, 29.7 New casing to be set at +/- 9888.45'1st StageOptional Lead: 370 sxs Class C (mixed at 10.5 ppg, 2.77 ft³/sx, 15.59 gal/sx water)

TOC: Surface

Tail: 280 sxs Class C (mixed at 14.8 ppg, 1.35 ft³/sx, 6.39 gal/sx water)

TOC: Brushy Canyon @ 6873

Compressives: 12-hr = 900 psi 24 hr = 1150 psi

2nd StageLead: 0 sxs Class C (mixed at 12.9 ppg, 2.16 ft³/sx, 9.61 gal/sx water)Tail: 770 sxs Class C (mixed at 14.8 ppg, 1.33 ft³/sx, 6.39 gal/sx water)

Top of Cement: 0

Compressives: 12-hr = 900 psi 24 hr = 1150 psi

XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brush Canyon (6873') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If cement is not visually confirmed to circulate to surface, the final cement top after the second stage job will be verified by Echo-meter. If necessary, a top out consisting of 1,500 sack of Class C cement + 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. If cement is still unable to circulate to surface, another Echo-meter run will be performed for cement top verification.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

XTO requests to pump an Optional Lead if well conditions dictate in an attempt to bring cement inside the first intermediate casing. If cement reaches the desired height, the BLM will be notified and the second stage bradenhead squeeze and subsequent TOC verification will be negated.

XTO requests the option to conduct the bradenhead squeeze and TOC verification offline as per standard approval from BLM when unplanned remediation is needed and batch drilling is approved. In the event the bradenhead is conducted, we will ensure the first stage cement job is cemented properly and the well is static with floats holding and no pressure on the csg annulus as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops.

Production Casing: 5.5, 20 New Talon/Semi-Flush, RY P-110 casing to be set at +/- 24348.04'

Lead: 20 sxs NeoCem (mixed at 11.5 ppg, 2.69 ft3/sx, 15.00 gal/sx water) Top of Cement: 9588.45 feet
Tail: 1020 sxs VersaCem (mixed at 13.2 ppg, 1.51 ft3/sx, 8.38 gal/sx water) Top of Cement: 10088.45 feet
Compressives: 12-hr = 800 psi 24 hr = 1500 psi

XTO requests the option to offline cement and remediate (if needed) surface and intermediate casing strings where batch drilling is approved and if unplanned remediation is needed. XTO will ensure well is static with no pressure on the csg annulus, as with all other casing strings where batch drilling operations occur before moving off the rig. The TA cap will also be installed when applicable per Cactus procedure and pressure inside the casing will be monitored via the valve on the TA cap as per standard batch drilling ops. Offline cement operations will then be conducted after the rig is moved off the current well to the next well in the batch sequence.

5. Pressure Control Equipment

Once the permanent WH is installed on the surface casing, the blow out preventer equipment (BOP) will consist of a **5M Hydril Annular** and a **10M Triple Ram BOP**

All BOP testing will be done by an independent service company. Operator will test as per BLM CFR43-3172

A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors.

XTO requests a variance to be able to batch drill this well if necessary. In doing so, XTO will set casing and ensure that the well is cemented properly (unless approval is given for offline cementing) and the well is static. With floats holding, no pressure on the csg annulus, and the installation of a 10K TA cap as per Cactus recommendations, XTO will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and both intermediate strings are all completed, XTO will begin drilling the production hole on each of the wells.

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken. We will request permission to **ONLY** retest broken pressure seals if the following conditions are met: 1. After a full BOP test is conducted on the first well on the pad 2. When skidding to drill an intermediate section that does not penetrate into the Wolfcamp.

6. Proposed Mud Circulation System

INTERVAL	Hole Size	Mud Type	MW (ppg)	Viscosity (sec/qt)	Fluid Loss (cc)	Additional Comments
0' - 1022'	12.25	FW/Native	8.4-8.9	35-40	NC	Fresh water or native water
1022' - 9888.45'	8.75	Saturated brine for salt interval / Direct Emulsion	9-9.5	30-32	NC	Fully saturated salt across salado / salt
9888.45' - 24348.04'	6.75	OBM	10.2-10.7	50-60	NC - 20	N/A

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Spud with fresh water/native mud. Drill out from under surface casing with Saturated Salt. A saturated salt brine mud will be used while drilling through the salt formation. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.

7. Auxiliary Well Control and Monitoring Equipment

- A. A Kelly cock will be in the drill string at all times.
- B. A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.
- C. H2S monitors will be on location when drilling below the 9.625 casing.

8. Logging, Coring and Testing Program

Open hole logging will not be done on this well.

9. Abnormal Pressures and Temperatures / Potential Hazards

None Anticipated. BHT of 170 to 190 F is anticipated. No H2S is expected but monitors will be in place to detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation could occur but is not expected to be a serious problem in this area and hole seepage will be compensated for by additions of small amounts of LCM in the drilling fluid.

10. Anticipated Starting Date and Duration of Operations

Anticipated spud date will be after BLM approval. Move in operations and drilling is expected to take 40 days.

Well Plan Report - Poker Lake Unit 28 BS 210H

Measured Depth: 24348.04 ft

TVD RKB: 10790.00 ft

Location

Cartographic Reference System: New Mexico East - NAD 27

Northing: 401170.70 ft

Easting: 669897.20 ft

RKB: 3367.00 ft

Ground Level: 3335.00 ft

North Reference: Grid

Convergence Angle: 0.29 Deg

Plan Sections

Poker Lake Unit 28 BS 210H

Measured			TVD			Build	Turn	Dogleg		
Depth	Inclination	Azimuth	RKB	Y Offset	X Offset	Rate	Rate	Rate	Target	
(ft)	(Deg)	(Deg)	(ft)	(ft)	(ft)	(Deg/100ft)	(Deg/100ft)	(Deg/100ft)		
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
1100.00	0.00	0.00	1100.00	0.00	0.00	0.00	0.00	0.00		
1312.38	4.25	355.31	1312.18	7.84	-0.64	2.00	0.00	2.00		
6502.26	4.25	355.31	6487.82	390.95	-32.09	0.00	0.00	0.00		
6714.64	0.00	0.00	6700.00	398.79	-32.73	-2.00	0.00	2.00		
10088.45	0.00	0.00	10073.80	398.79	-32.73	0.00	0.00	0.00		
11213.45	90.00	179.79	10790.00	-317.40	-30.10	8.00	0.00	8.00	FTP	9
24298.04	90.00	179.79	10790.00	-13401.90	18.00	0.00	0.00	0.00	LTP	9
24348.04	90.00	179.79	10790.00	-13451.90	18.18	0.00	0.00	0.00	BHL	3

Position Uncertainty

Poker Lake Unit 28 BS 210H

Measured	TVD	Highside	Lateral	Vertical	Magnitude	Semi-major	Semi-minor	Semi-minor	Tool
----------	-----	----------	---------	----------	-----------	------------	------------	------------	------

Depth	Inclination	Azimuth	RKB	Error	Bias	Error	Bias	Error	Bias	of Bias	Error	Error	Azimuth	Used
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(ft)	(°)	
0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	XOMR2_OWSG MWD+IFR1+MS
100.000	0.000	0.000	100.000	0.358	0.000	0.179	0.000	2.300	0.000	0.000	0.358	0.179	90.000	XOMR2_OWSG MWD+IFR1+MS
200.000	0.000	0.000	200.000	0.717	0.000	0.538	0.000	2.310	0.000	0.000	0.717	0.538	90.000	XOMR2_OWSG MWD+IFR1+MS
300.000	0.000	0.000	300.000	1.075	0.000	0.896	0.000	2.325	0.000	0.000	1.075	0.896	90.000	XOMR2_OWSG MWD+IFR1+MS
400.000	0.000	0.000	400.000	1.434	0.000	1.255	0.000	2.347	0.000	0.000	1.434	1.255	90.000	XOMR2_OWSG MWD+IFR1+MS
500.000	0.000	0.000	500.000	1.792	0.000	1.613	0.000	2.374	0.000	0.000	1.792	1.613	90.000	XOMR2_OWSG MWD+IFR1+MS
600.000	0.000	0.000	600.000	2.151	0.000	1.972	0.000	2.406	0.000	0.000	2.151	1.972	90.000	XOMR2_OWSG MWD+IFR1+MS
700.000	0.000	0.000	700.000	2.509	0.000	2.330	0.000	2.443	0.000	0.000	2.509	2.330	90.000	XOMR2_OWSG MWD+IFR1+MS
800.000	0.000	0.000	800.000	2.868	0.000	2.689	0.000	2.485	0.000	0.000	2.868	2.689	90.000	XOMR2_OWSG MWD+IFR1+MS
900.000	0.000	0.000	900.000	3.226	0.000	3.047	0.000	2.531	0.000	0.000	3.226	3.047	90.000	XOMR2_OWSG MWD+IFR1+MS
1000.000	0.000	0.000	1000.000	3.585	0.000	3.405	0.000	2.580	0.000	0.000	3.585	3.405	90.000	XOMR2_OWSG MWD+IFR1+MS
1100.000	0.000	0.000	1100.000	3.943	0.000	3.764	0.000	2.634	0.000	0.000	3.943	3.764	90.000	XOMR2_OWSG MWD+IFR1+MS
1200.000	2.000	355.308	1199.980	4.298	0.000	4.123	0.000	2.690	0.000	0.000	4.302	4.122	89.997	XOMR2_OWSG MWD+IFR1+MS
1300.000	4.000	355.308	1299.838	4.650	0.000	4.480	0.000	2.747	0.000	0.000	4.662	4.478	89.976	XOMR2_OWSG MWD+IFR1+MS
1312.379	4.248	355.308	1312.185	4.694	0.000	4.524	0.000	2.753	0.000	0.000	4.707	4.522	89.942	XOMR2_OWSG MWD+IFR1+MS
1400.000	4.248	355.308	1399.565	5.007	0.000	4.836	0.000	2.807	0.000	0.000	5.020	4.835	89.987	XOMR2_OWSG MWD+IFR1+MS
1500.000	4.248	355.308	1499.290	5.366	0.000	5.193	0.000	2.873	0.000	0.000	5.378	5.191	90.039	XOMR2_OWSG MWD+IFR1+MS
1600.000	4.248	355.308	1599.016	5.726	0.000	5.550	0.000	2.941	0.000	0.000	5.736	5.548	90.086	XOMR2_OWSG MWD+IFR1+MS
1700.000	4.248	355.308	1698.741	6.085	0.000	5.907	0.000	3.012	0.000	0.000	6.095	5.906	90.129	XOMR2_OWSG MWD+IFR1+MS

1800.000	4.248	355.308	1798.466	6.445	0.000	6.264	0.000	3.084	0.000	0.000	6.454	6.263	90.168	XOMR2_OWSG MWD+IFR1+MS
1900.000	4.248	355.308	1898.192	6.805	0.000	6.622	0.000	3.159	0.000	0.000	6.813	6.621	90.204	XOMR2_OWSG MWD+IFR1+MS
2000.000	4.248	355.308	1997.917	7.166	0.000	6.980	0.000	3.236	0.000	0.000	7.173	6.979	90.238	XOMR2_OWSG MWD+IFR1+MS
2100.000	4.248	355.308	2097.642	7.526	0.000	7.338	0.000	3.315	0.000	0.000	7.532	7.337	90.269	XOMR2_OWSG MWD+IFR1+MS
2200.000	4.248	355.308	2197.368	7.887	0.000	7.696	0.000	3.395	0.000	0.000	7.892	7.695	90.298	XOMR2_OWSG MWD+IFR1+MS
2300.000	4.248	355.308	2297.093	8.248	0.000	8.055	0.000	3.477	0.000	0.000	8.252	8.053	90.325	XOMR2_OWSG MWD+IFR1+MS
2400.000	4.248	355.308	2396.818	8.609	0.000	8.413	0.000	3.561	0.000	0.000	8.612	8.412	90.351	XOMR2_OWSG MWD+IFR1+MS
2500.000	4.248	355.308	2496.543	8.970	0.000	8.772	0.000	3.646	0.000	0.000	8.972	8.770	90.375	XOMR2_OWSG MWD+IFR1+MS
2600.000	4.248	355.308	2596.269	9.331	0.000	9.130	0.000	3.733	0.000	0.000	9.332	9.129	90.398	XOMR2_OWSG MWD+IFR1+MS
2700.000	4.248	355.308	2695.994	9.692	0.000	9.489	0.000	3.821	0.000	0.000	9.693	9.487	90.419	XOMR2_OWSG MWD+IFR1+MS
2800.000	4.248	355.308	2795.719	10.054	0.000	9.848	0.000	3.911	0.000	0.000	10.053	9.846	90.440	XOMR2_OWSG MWD+IFR1+MS
2900.000	4.248	355.308	2895.445	10.415	0.000	10.206	0.000	4.001	0.000	0.000	10.414	10.205	90.459	XOMR2_OWSG MWD+IFR1+MS
3000.000	4.248	355.308	2995.170	10.777	0.000	10.565	0.000	4.094	0.000	0.000	10.774	10.563	90.478	XOMR2_OWSG MWD+IFR1+MS
3100.000	4.248	355.308	3094.895	11.138	0.000	10.924	0.000	4.188	0.000	0.000	11.135	10.922	90.496	XOMR2_OWSG MWD+IFR1+MS
3200.000	4.248	355.308	3194.621	11.500	0.000	11.283	0.000	4.283	0.000	0.000	11.495	11.281	90.513	XOMR2_OWSG MWD+IFR1+MS
3300.000	4.248	355.308	3294.346	11.861	0.000	11.642	0.000	4.379	0.000	0.000	11.856	11.640	90.529	XOMR2_OWSG MWD+IFR1+MS
3400.000	4.248	355.308	3394.071	12.223	0.000	12.001	0.000	4.477	0.000	0.000	12.217	11.999	90.545	XOMR2_OWSG MWD+IFR1+MS
3500.000	4.248	355.308	3493.797	12.585	0.000	12.360	0.000	4.576	0.000	0.000	12.578	12.358	90.560	XOMR2_OWSG MWD+IFR1+MS
3600.000	4.248	355.308	3593.522	12.946	0.000	12.719	0.000	4.677	0.000	0.000	12.939	12.717	90.574	XOMR2_OWSG MWD+IFR1+MS
3700.000	4.248	355.308	3693.247	13.308	0.000	13.078	0.000	4.779	0.000	0.000	13.299	13.076	90.588	XOMR2_OWSG MWD+IFR1+MS

3800.000	4.248	355.308	3792.973	13.670	0.000	13.437	0.000	4.882	0.000	0.000	13.660	13.435	90.601	XOMR2_OWSG MWD+IFR1+MS
3900.000	4.248	355.308	3892.698	14.032	0.000	13.796	0.000	4.987	0.000	0.000	14.021	13.794	90.614	XOMR2_OWSG MWD+IFR1+MS
4000.000	4.248	355.308	3992.423	14.394	0.000	14.155	0.000	5.094	0.000	0.000	14.382	14.153	90.627	XOMR2_OWSG MWD+IFR1+MS
4100.000	4.248	355.308	4092.149	14.755	0.000	14.514	0.000	5.202	0.000	0.000	14.743	14.512	90.639	XOMR2_OWSG MWD+IFR1+MS
4200.000	4.248	355.308	4191.874	15.117	0.000	14.873	0.000	5.311	0.000	0.000	15.104	14.871	90.650	XOMR2_OWSG MWD+IFR1+MS
4300.000	4.248	355.308	4291.599	15.479	0.000	15.232	0.000	5.422	0.000	0.000	15.465	15.230	90.661	XOMR2_OWSG MWD+IFR1+MS
4400.000	4.248	355.308	4391.325	15.841	0.000	15.592	0.000	5.535	0.000	0.000	15.826	15.590	90.672	XOMR2_OWSG MWD+IFR1+MS
4500.000	4.248	355.308	4491.050	16.203	0.000	15.951	0.000	5.649	0.000	0.000	16.187	15.949	90.682	XOMR2_OWSG MWD+IFR1+MS
4600.000	4.248	355.308	4590.775	16.565	0.000	16.310	0.000	5.766	0.000	0.000	16.548	16.308	90.692	XOMR2_OWSG MWD+IFR1+MS
4700.000	4.248	355.308	4690.501	16.927	0.000	16.669	0.000	5.883	0.000	0.000	16.910	16.667	90.702	XOMR2_OWSG MWD+IFR1+MS
4800.000	4.248	355.308	4790.226	17.289	0.000	17.028	0.000	6.003	0.000	0.000	17.271	17.026	90.711	XOMR2_OWSG MWD+IFR1+MS
4900.000	4.248	355.308	4889.951	17.651	0.000	17.388	0.000	6.124	0.000	0.000	17.632	17.385	90.720	XOMR2_OWSG MWD+IFR1+MS
5000.000	4.248	355.308	4989.677	18.013	0.000	17.747	0.000	6.247	0.000	0.000	17.993	17.745	90.729	XOMR2_OWSG MWD+IFR1+MS
5100.000	4.248	355.308	5089.402	18.375	0.000	18.106	0.000	6.372	0.000	0.000	18.354	18.104	90.737	XOMR2_OWSG MWD+IFR1+MS
5200.000	4.248	355.308	5189.127	18.737	0.000	18.465	0.000	6.499	0.000	0.000	18.715	18.463	90.745	XOMR2_OWSG MWD+IFR1+MS
5300.000	4.248	355.308	5288.853	19.099	0.000	18.825	0.000	6.628	0.000	0.000	19.077	18.822	90.753	XOMR2_OWSG MWD+IFR1+MS
5400.000	4.248	355.308	5388.578	19.461	0.000	19.184	0.000	6.759	0.000	0.000	19.438	19.181	90.761	XOMR2_OWSG MWD+IFR1+MS
5500.000	4.248	355.308	5488.303	19.823	0.000	19.543	0.000	6.892	0.000	0.000	19.799	19.541	90.768	XOMR2_OWSG MWD+IFR1+MS
5600.000	4.248	355.308	5588.029	20.185	0.000	19.902	0.000	7.027	0.000	0.000	20.160	19.900	90.775	XOMR2_OWSG MWD+IFR1+MS
5700.000	4.248	355.308	5687.754	20.548	0.000	20.262	0.000	7.164	0.000	0.000	20.522	20.259	90.782	XOMR2_OWSG MWD+IFR1+MS

5800.000	4.248	355.308	5787.479	20.910	0.000	20.621	0.000	7.303	0.000	0.000	20.883	20.618	90.788	XOMR2_OWSG MWD+IFR1+MS
5900.000	4.248	355.308	5887.205	21.272	0.000	20.980	0.000	7.444	0.000	0.000	21.244	20.978	90.795	XOMR2_OWSG MWD+IFR1+MS
6000.000	4.248	355.308	5986.930	21.634	0.000	21.339	0.000	7.587	0.000	0.000	21.605	21.337	90.801	XOMR2_OWSG MWD+IFR1+MS
6100.000	4.248	355.308	6086.655	21.996	0.000	21.699	0.000	7.733	0.000	0.000	21.967	21.696	90.807	XOMR2_OWSG MWD+IFR1+MS
6200.000	4.248	355.308	6186.381	22.358	0.000	22.058	0.000	7.880	0.000	0.000	22.328	22.056	90.812	XOMR2_OWSG MWD+IFR1+MS
6300.000	4.248	355.308	6286.106	22.720	0.000	22.417	0.000	8.030	0.000	0.000	22.689	22.415	90.818	XOMR2_OWSG MWD+IFR1+MS
6400.000	4.248	355.308	6385.831	23.082	0.000	22.777	0.000	8.183	0.000	0.000	23.051	22.774	90.823	XOMR2_OWSG MWD+IFR1+MS
6502.265	4.248	355.308	6487.815	23.453	0.000	23.144	0.000	8.341	0.000	0.000	23.420	23.142	90.828	XOMR2_OWSG MWD+IFR1+MS
6600.000	2.293	355.308	6585.387	23.803	0.000	23.495	0.000	8.494	0.000	0.000	23.772	23.492	90.835	XOMR2_OWSG MWD+IFR1+MS
6700.000	0.293	355.308	6685.356	24.133	0.000	23.851	0.000	8.651	0.000	0.000	24.129	23.849	90.840	XOMR2_OWSG MWD+IFR1+MS
6714.644	0.000	0.000	6700.000	24.181	0.000	23.901	0.000	8.675	0.000	0.000	24.181	23.901	90.842	XOMR2_OWSG MWD+IFR1+MS
6800.000	0.000	0.000	6785.356	24.485	0.000	24.205	0.000	8.810	0.000	0.000	24.485	24.204	90.860	XOMR2_OWSG MWD+IFR1+MS
6900.000	0.000	0.000	6885.356	24.840	0.000	24.560	0.000	8.970	0.000	0.000	24.840	24.560	90.880	XOMR2_OWSG MWD+IFR1+MS
7000.000	0.000	0.000	6985.356	25.195	0.000	24.916	0.000	9.133	0.000	0.000	25.195	24.916	90.901	XOMR2_OWSG MWD+IFR1+MS
7100.000	0.000	0.000	7085.356	25.551	0.000	25.272	0.000	9.298	0.000	0.000	25.551	25.272	90.920	XOMR2_OWSG MWD+IFR1+MS
7200.000	0.000	0.000	7185.356	25.907	0.000	25.628	0.000	9.466	0.000	0.000	25.907	25.628	90.939	XOMR2_OWSG MWD+IFR1+MS
7300.000	0.000	0.000	7285.356	26.262	0.000	25.984	0.000	9.637	0.000	0.000	26.262	25.984	90.958	XOMR2_OWSG MWD+IFR1+MS
7400.000	0.000	0.000	7385.356	26.618	0.000	26.340	0.000	9.810	0.000	0.000	26.618	26.340	90.976	XOMR2_OWSG MWD+IFR1+MS
7500.000	0.000	0.000	7485.356	26.974	0.000	26.696	0.000	9.986	0.000	0.000	26.974	26.696	90.994	XOMR2_OWSG MWD+IFR1+MS
7600.000	0.000	0.000	7585.356	27.330	0.000	27.052	0.000	10.165	0.000	0.000	27.330	27.052	91.011	XOMR2_OWSG MWD+IFR1+MS

7700.000	0.000	0.000	7685.356	27.686	0.000	27.409	0.000	10.346	0.000	0.000	27.686	27.409	91.028	XOMR2_OWSG MWD+IFR1+MS
7800.000	0.000	0.000	7785.356	28.042	0.000	27.765	0.000	10.530	0.000	0.000	28.042	27.765	91.045	XOMR2_OWSG MWD+IFR1+MS
7900.000	0.000	0.000	7885.356	28.398	0.000	28.121	0.000	10.717	0.000	0.000	28.398	28.121	91.061	XOMR2_OWSG MWD+IFR1+MS
8000.000	0.000	0.000	7985.356	28.754	0.000	28.478	0.000	10.907	0.000	0.000	28.754	28.478	91.076	XOMR2_OWSG MWD+IFR1+MS
8100.000	0.000	0.000	8085.356	29.110	0.000	28.834	0.000	11.099	0.000	0.000	29.110	28.834	91.092	XOMR2_OWSG MWD+IFR1+MS
8200.000	0.000	0.000	8185.356	29.467	0.000	29.191	0.000	11.294	0.000	0.000	29.467	29.191	91.107	XOMR2_OWSG MWD+IFR1+MS
8300.000	0.000	0.000	8285.356	29.823	0.000	29.547	0.000	11.492	0.000	0.000	29.823	29.547	91.122	XOMR2_OWSG MWD+IFR1+MS
8400.000	0.000	0.000	8385.356	30.179	0.000	29.904	0.000	11.693	0.000	0.000	30.179	29.904	91.136	XOMR2_OWSG MWD+IFR1+MS
8500.000	0.000	0.000	8485.356	30.536	0.000	30.261	0.000	11.896	0.000	0.000	30.536	30.261	91.150	XOMR2_OWSG MWD+IFR1+MS
8600.000	0.000	0.000	8585.356	30.892	0.000	30.617	0.000	12.103	0.000	0.000	30.892	30.617	91.164	XOMR2_OWSG MWD+IFR1+MS
8700.000	0.000	0.000	8685.356	31.249	0.000	30.974	0.000	12.312	0.000	0.000	31.249	30.974	91.177	XOMR2_OWSG MWD+IFR1+MS
8800.000	0.000	0.000	8785.356	31.605	0.000	31.331	0.000	12.524	0.000	0.000	31.605	31.331	91.191	XOMR2_OWSG MWD+IFR1+MS
8900.000	0.000	0.000	8885.356	31.962	0.000	31.688	0.000	12.739	0.000	0.000	31.962	31.688	91.203	XOMR2_OWSG MWD+IFR1+MS
9000.000	0.000	0.000	8985.356	32.319	0.000	32.045	0.000	12.957	0.000	0.000	32.319	32.044	91.216	XOMR2_OWSG MWD+IFR1+MS
9100.000	0.000	0.000	9085.356	32.675	0.000	32.402	0.000	13.178	0.000	0.000	32.675	32.401	91.229	XOMR2_OWSG MWD+IFR1+MS
9200.000	0.000	0.000	9185.356	33.032	0.000	32.758	0.000	13.401	0.000	0.000	33.032	32.758	91.241	XOMR2_OWSG MWD+IFR1+MS
9300.000	0.000	0.000	9285.356	33.389	0.000	33.115	0.000	13.628	0.000	0.000	33.389	33.115	91.253	XOMR2_OWSG MWD+IFR1+MS
9400.000	0.000	0.000	9385.356	33.746	0.000	33.472	0.000	13.857	0.000	0.000	33.746	33.472	91.264	XOMR2_OWSG MWD+IFR1+MS
9500.000	0.000	0.000	9485.356	34.102	0.000	33.829	0.000	14.090	0.000	0.000	34.103	33.829	91.276	XOMR2_OWSG MWD+IFR1+MS
9600.000	0.000	0.000	9585.356	34.459	0.000	34.187	0.000	14.325	0.000	0.000	34.459	34.186	91.287	XOMR2_OWSG MWD+IFR1+MS

9700.000	0.000	0.000	9685.356	34.816	0.000	34.544	0.000	14.564	0.000	0.000	34.816	34.543	91.298	XOMR2_OWSG MWD+IFR1+MS
9800.000	0.000	0.000	9785.356	35.173	0.000	34.901	0.000	14.805	0.000	0.000	35.173	34.901	91.309	XOMR2_OWSG MWD+IFR1+MS
9900.000	0.000	0.000	9885.356	35.530	0.000	35.258	0.000	15.049	0.000	0.000	35.530	35.258	91.319	XOMR2_OWSG MWD+IFR1+MS
10000.000	0.000	0.000	9985.356	35.887	0.000	35.615	0.000	15.296	0.000	0.000	35.887	35.615	91.330	XOMR2_OWSG MWD+IFR1+MS
10088.447	0.000	0.000	10073.803	36.203	0.000	35.931	0.000	15.518	0.000	0.000	36.203	35.931	91.339	XOMR2_OWSG MWD+IFR1+MS
10100.000	0.924	179.789	10085.356	36.218	0.000	35.970	-0.000	15.547	0.000	0.000	36.242	35.970	91.339	XOMR2_OWSG MWD+IFR1+MS
10200.000	8.924	179.789	10184.906	36.005	0.000	36.285	-0.000	15.794	0.000	0.000	36.554	36.285	91.384	XOMR2_OWSG MWD+IFR1+MS
10300.000	16.924	179.789	10282.293	35.212	0.000	36.586	-0.000	16.028	0.000	0.000	36.847	36.586	91.515	XOMR2_OWSG MWD+IFR1+MS
10400.000	24.924	179.789	10375.622	33.869	0.000	36.867	-0.000	16.245	0.000	0.000	37.113	36.867	91.768	XOMR2_OWSG MWD+IFR1+MS
10500.000	32.924	179.789	10463.077	32.025	0.000	37.127	-0.000	16.442	0.000	0.000	37.345	37.126	92.206	XOMR2_OWSG MWD+IFR1+MS
10600.000	40.924	179.789	10542.956	29.758	0.000	37.362	-0.000	16.621	0.000	0.000	37.540	37.361	92.990	XOMR2_OWSG MWD+IFR1+MS
10700.000	48.924	179.789	10613.702	27.180	0.000	37.571	-0.000	16.784	0.000	0.000	37.695	37.570	94.647	XOMR2_OWSG MWD+IFR1+MS
10800.000	56.924	179.789	10673.940	24.449	0.000	37.754	-0.000	16.940	0.000	0.000	37.812	37.752	100.287	XOMR2_OWSG MWD+IFR1+MS
10900.000	64.924	179.789	10722.497	21.786	0.000	37.909	-0.000	17.095	0.000	0.000	37.914	37.885	-24.652	XOMR2_OWSG MWD+IFR1+MS
11000.000	72.924	179.789	10758.428	19.502	0.000	38.036	-0.000	17.258	0.000	0.000	38.037	37.938	-6.137	XOMR2_OWSG MWD+IFR1+MS
11100.000	80.924	179.789	10781.034	17.988	0.000	38.133	-0.000	17.435	0.000	0.000	38.134	37.964	-3.255	XOMR2_OWSG MWD+IFR1+MS
11200.000	88.924	179.789	10789.874	17.610	0.000	38.202	-0.000	17.629	0.000	0.000	38.202	37.975	-2.073	XOMR2_OWSG MWD+IFR1+MS
11213.447	90.000	179.789	10790.000	17.657	0.000	38.208	-0.000	17.657	0.000	0.000	38.208	37.977	-1.969	XOMR2_OWSG MWD+IFR1+MS
11300.000	90.000	179.789	10790.000	17.847	0.000	38.255	-0.000	17.847	0.000	0.000	38.255	37.981	-1.335	XOMR2_OWSG MWD+IFR1+MS
11400.000	90.000	179.789	10790.000	18.097	0.000	38.325	-0.000	18.097	0.000	0.000	38.325	37.986	-0.788	XOMR2_OWSG MWD+IFR1+MS

11500.000	90.000	179.789	10790.000	18.377	0.000	38.410	-0.000	18.377	0.000	0.000	38.410	37.992	-0.408	XOMR2_OWSG MWD+IFR1+MS
11600.000	90.000	179.789	10790.000	18.685	0.000	38.509	-0.000	18.685	0.000	0.000	38.509	37.999	-0.151	XOMR2_OWSG MWD+IFR1+MS
11700.000	90.000	179.789	10790.000	19.021	0.000	38.624	-0.000	19.021	0.000	0.000	38.624	38.006	0.020	XOMR2_OWSG MWD+IFR1+MS
11800.000	90.000	179.789	10790.000	19.383	0.000	38.753	-0.000	19.383	0.000	0.000	38.753	38.014	0.134	XOMR2_OWSG MWD+IFR1+MS
11900.000	90.000	179.789	10790.000	19.770	0.000	38.897	-0.000	19.770	0.000	0.000	38.897	38.022	0.208	XOMR2_OWSG MWD+IFR1+MS
12000.000	90.000	179.789	10790.000	20.179	0.000	39.056	-0.000	20.179	0.000	0.000	39.056	38.031	0.255	XOMR2_OWSG MWD+IFR1+MS
12100.000	90.000	179.789	10790.000	20.611	0.000	39.228	-0.000	20.611	0.000	0.000	39.228	38.041	0.284	XOMR2_OWSG MWD+IFR1+MS
12200.000	90.000	179.789	10790.000	21.062	0.000	39.415	-0.000	21.062	0.000	0.000	39.415	38.052	0.301	XOMR2_OWSG MWD+IFR1+MS
12300.000	90.000	179.789	10790.000	21.533	0.000	39.616	-0.000	21.533	0.000	0.000	39.616	38.063	0.309	XOMR2_OWSG MWD+IFR1+MS
12400.000	90.000	179.789	10790.000	22.022	0.000	39.830	-0.000	22.022	0.000	0.000	39.830	38.075	0.311	XOMR2_OWSG MWD+IFR1+MS
12500.000	90.000	179.789	10790.000	22.528	0.000	40.058	-0.000	22.528	0.000	0.000	40.058	38.087	0.308	XOMR2_OWSG MWD+IFR1+MS
12600.000	90.000	179.789	10790.000	23.049	0.000	40.299	-0.000	23.049	0.000	0.000	40.299	38.101	0.303	XOMR2_OWSG MWD+IFR1+MS
12700.000	90.000	179.789	10790.000	23.585	0.000	40.553	-0.000	23.585	0.000	0.000	40.553	38.114	0.296	XOMR2_OWSG MWD+IFR1+MS
12800.000	90.000	179.789	10790.000	24.134	0.000	40.820	-0.000	24.134	0.000	0.000	40.820	38.129	0.287	XOMR2_OWSG MWD+IFR1+MS
12900.000	90.000	179.789	10790.000	24.696	0.000	41.099	-0.000	24.696	0.000	0.000	41.099	38.144	0.278	XOMR2_OWSG MWD+IFR1+MS
13000.000	90.000	179.789	10790.000	25.270	0.000	41.390	-0.000	25.270	0.000	0.000	41.390	38.160	0.268	XOMR2_OWSG MWD+IFR1+MS
13100.000	90.000	179.789	10790.000	25.855	0.000	41.694	-0.000	25.855	0.000	0.000	41.694	38.176	0.258	XOMR2_OWSG MWD+IFR1+MS
13200.000	90.000	179.789	10790.000	26.451	0.000	42.009	-0.000	26.451	0.000	0.000	42.009	38.194	0.248	XOMR2_OWSG MWD+IFR1+MS
13300.000	90.000	179.789	10790.000	27.056	0.000	42.336	-0.000	27.056	0.000	0.000	42.336	38.211	0.237	XOMR2_OWSG MWD+IFR1+MS
13400.000	90.000	179.789	10790.000	27.670	0.000	42.673	-0.000	27.670	0.000	0.000	42.674	38.230	0.227	XOMR2_OWSG MWD+IFR1+MS

13500.000	90.000	179.789	10790.000	28.292	0.000	43.022	-0.000	28.292	0.000	0.000	43.023	38.249	0.218	XOMR2_OWSG MWD+IFR1+MS
13600.000	90.000	179.789	10790.000	28.923	0.000	43.382	-0.000	28.923	0.000	0.000	43.382	38.269	0.208	XOMR2_OWSG MWD+IFR1+MS
13700.000	90.000	179.789	10790.000	29.561	0.000	43.752	-0.000	29.561	0.000	0.000	43.752	38.289	0.198	XOMR2_OWSG MWD+IFR1+MS
13800.000	90.000	179.789	10790.000	30.205	0.000	44.132	-0.000	30.205	0.000	0.000	44.132	38.310	0.189	XOMR2_OWSG MWD+IFR1+MS
13900.000	90.000	179.789	10790.000	30.857	0.000	44.522	-0.000	30.857	0.000	0.000	44.522	38.332	0.180	XOMR2_OWSG MWD+IFR1+MS
14000.000	90.000	179.789	10790.000	31.514	0.000	44.921	-0.000	31.514	0.000	0.000	44.922	38.354	0.172	XOMR2_OWSG MWD+IFR1+MS
14100.000	90.000	179.789	10790.000	32.177	0.000	45.330	-0.000	32.177	0.000	0.000	45.331	38.377	0.164	XOMR2_OWSG MWD+IFR1+MS
14200.000	90.000	179.789	10790.000	32.845	0.000	45.748	-0.000	32.845	0.000	0.000	45.749	38.401	0.156	XOMR2_OWSG MWD+IFR1+MS
14300.000	90.000	179.789	10790.000	33.519	0.000	46.175	-0.000	33.519	0.000	0.000	46.176	38.425	0.148	XOMR2_OWSG MWD+IFR1+MS
14400.000	90.000	179.789	10790.000	34.197	0.000	46.611	-0.000	34.197	0.000	0.000	46.611	38.450	0.140	XOMR2_OWSG MWD+IFR1+MS
14500.000	90.000	179.789	10790.000	34.880	0.000	47.055	-0.000	34.880	0.000	0.000	47.055	38.476	0.133	XOMR2_OWSG MWD+IFR1+MS
14600.000	90.000	179.789	10790.000	35.567	0.000	47.507	-0.000	35.567	0.000	0.000	47.507	38.502	0.126	XOMR2_OWSG MWD+IFR1+MS
14700.000	90.000	179.789	10790.000	36.258	0.000	47.967	-0.000	36.258	0.000	0.000	47.968	38.529	0.120	XOMR2_OWSG MWD+IFR1+MS
14800.000	90.000	179.789	10790.000	36.952	0.000	48.435	-0.000	36.952	0.000	0.000	48.435	38.557	0.113	XOMR2_OWSG MWD+IFR1+MS
14900.000	90.000	179.789	10790.000	37.650	0.000	48.910	-0.000	37.650	0.000	0.000	48.911	38.585	0.107	XOMR2_OWSG MWD+IFR1+MS
15000.000	90.000	179.789	10790.000	38.352	0.000	49.393	-0.000	38.352	0.000	0.000	49.393	38.614	0.101	XOMR2_OWSG MWD+IFR1+MS
15100.000	90.000	179.789	10790.000	39.057	0.000	49.883	-0.000	39.057	0.000	0.000	49.883	38.643	0.095	XOMR2_OWSG MWD+IFR1+MS
15200.000	90.000	179.789	10790.000	39.764	0.000	50.379	-0.000	39.764	0.000	0.000	50.379	38.673	0.089	XOMR2_OWSG MWD+IFR1+MS
15300.000	90.000	179.789	10790.000	40.475	0.000	50.882	-0.000	40.475	0.000	0.000	50.882	38.704	0.084	XOMR2_OWSG MWD+IFR1+MS
15400.000	90.000	179.789	10790.000	41.188	0.000	51.392	-0.000	41.188	0.000	0.000	51.392	38.735	0.079	XOMR2_OWSG MWD+IFR1+MS

15500.000	90.000	179.789	10790.000	41.904	0.000	51.907	-0.000	41.904	0.000	0.000	51.908	38.767	0.073	XOMR2_OWSG MWD+IFR1+MS
15600.000	90.000	179.789	10790.000	42.622	0.000	52.429	-0.000	42.622	0.000	0.000	52.430	38.800	0.069	XOMR2_OWSG MWD+IFR1+MS
15700.000	90.000	179.789	10790.000	43.342	0.000	52.957	-0.000	43.342	0.000	0.000	52.957	38.833	0.064	XOMR2_OWSG MWD+IFR1+MS
15800.000	90.000	179.789	10790.000	44.065	0.000	53.491	-0.000	44.065	0.000	0.000	53.491	38.867	0.059	XOMR2_OWSG MWD+IFR1+MS
15900.000	90.000	179.789	10790.000	44.790	0.000	54.030	-0.000	44.790	0.000	0.000	54.030	38.901	0.055	XOMR2_OWSG MWD+IFR1+MS
16000.000	90.000	179.789	10790.000	45.517	0.000	54.574	-0.000	45.517	0.000	0.000	54.575	38.936	0.050	XOMR2_OWSG MWD+IFR1+MS
16100.000	90.000	179.789	10790.000	46.245	0.000	55.124	-0.000	46.245	0.000	0.000	55.124	38.972	0.046	XOMR2_OWSG MWD+IFR1+MS
16200.000	90.000	179.789	10790.000	46.976	0.000	55.679	-0.000	46.976	0.000	0.000	55.679	39.008	0.042	XOMR2_OWSG MWD+IFR1+MS
16300.000	90.000	179.789	10790.000	47.708	0.000	56.239	-0.000	47.708	0.000	0.000	56.239	39.045	0.038	XOMR2_OWSG MWD+IFR1+MS
16400.000	90.000	179.789	10790.000	48.442	0.000	56.803	-0.000	48.442	0.000	0.000	56.803	39.083	0.034	XOMR2_OWSG MWD+IFR1+MS
16500.000	90.000	179.789	10790.000	49.177	0.000	57.372	-0.000	49.177	0.000	0.000	57.372	39.121	0.031	XOMR2_OWSG MWD+IFR1+MS
16600.000	90.000	179.789	10790.000	49.914	0.000	57.946	-0.000	49.914	0.000	0.000	57.946	39.159	0.027	XOMR2_OWSG MWD+IFR1+MS
16700.000	90.000	179.789	10790.000	50.653	0.000	58.524	-0.000	50.653	0.000	0.000	58.524	39.199	0.023	XOMR2_OWSG MWD+IFR1+MS
16800.000	90.000	179.789	10790.000	51.393	0.000	59.106	-0.000	51.393	0.000	0.000	59.106	39.239	0.020	XOMR2_OWSG MWD+IFR1+MS
16900.000	90.000	179.789	10790.000	52.134	0.000	59.692	-0.000	52.134	0.000	0.000	59.693	39.279	0.017	XOMR2_OWSG MWD+IFR1+MS
17000.000	90.000	179.789	10790.000	52.876	0.000	60.283	-0.000	52.876	0.000	0.000	60.283	39.320	0.013	XOMR2_OWSG MWD+IFR1+MS
17100.000	90.000	179.789	10790.000	53.619	0.000	60.877	-0.000	53.619	0.000	0.000	60.877	39.362	0.010	XOMR2_OWSG MWD+IFR1+MS
17200.000	90.000	179.789	10790.000	54.364	0.000	61.475	-0.000	54.364	0.000	0.000	61.475	39.405	0.007	XOMR2_OWSG MWD+IFR1+MS
17300.000	90.000	179.789	10790.000	55.110	0.000	62.077	-0.000	55.110	0.000	0.000	62.077	39.448	0.004	XOMR2_OWSG MWD+IFR1+MS
17400.000	90.000	179.789	10790.000	55.857	0.000	62.682	-0.000	55.857	0.000	0.000	62.682	39.491	0.001	XOMR2_OWSG MWD+IFR1+MS

17500.000	90.000	179.789	10790.000	56.605	0.000	63.291	-0.000	56.605	0.000	0.000	63.291	39.535	-0.001	XOMR2_OWSG MWD+IFR1+MS
17600.000	90.000	179.789	10790.000	57.354	0.000	63.903	-0.000	57.354	0.000	0.000	63.903	39.580	-0.004	XOMR2_OWSG MWD+IFR1+MS
17700.000	90.000	179.789	10790.000	58.103	0.000	64.518	-0.000	58.103	0.000	0.000	64.518	39.625	-0.007	XOMR2_OWSG MWD+IFR1+MS
17800.000	90.000	179.789	10790.000	58.854	0.000	65.136	-0.000	58.854	0.000	0.000	65.137	39.671	-0.010	XOMR2_OWSG MWD+IFR1+MS
17900.000	90.000	179.789	10790.000	59.606	0.000	65.758	-0.000	59.606	0.000	0.000	65.758	39.718	-0.012	XOMR2_OWSG MWD+IFR1+MS
18000.000	90.000	179.789	10790.000	60.358	0.000	66.383	-0.000	60.358	0.000	0.000	66.383	39.765	-0.015	XOMR2_OWSG MWD+IFR1+MS
18100.000	90.000	179.789	10790.000	61.112	0.000	67.010	-0.000	61.112	0.000	0.000	67.010	39.813	-0.017	XOMR2_OWSG MWD+IFR1+MS
18200.000	90.000	179.789	10790.000	61.866	0.000	67.640	-0.000	61.866	0.000	0.000	67.640	39.861	-0.019	XOMR2_OWSG MWD+IFR1+MS
18300.000	90.000	179.789	10790.000	62.620	0.000	68.273	-0.000	62.620	0.000	0.000	68.274	39.910	-0.022	XOMR2_OWSG MWD+IFR1+MS
18400.000	90.000	179.789	10790.000	63.376	0.000	68.909	-0.000	63.376	0.000	0.000	68.909	39.959	-0.024	XOMR2_OWSG MWD+IFR1+MS
18500.000	90.000	179.789	10790.000	64.132	0.000	69.547	-0.000	64.132	0.000	0.000	69.547	40.009	-0.026	XOMR2_OWSG MWD+IFR1+MS
18600.000	90.000	179.789	10790.000	64.889	0.000	70.188	-0.000	64.889	0.000	0.000	70.188	40.060	-0.028	XOMR2_OWSG MWD+IFR1+MS
18700.000	90.000	179.789	10790.000	65.647	0.000	70.831	-0.000	65.647	0.000	0.000	70.832	40.111	-0.030	XOMR2_OWSG MWD+IFR1+MS
18800.000	90.000	179.789	10790.000	66.405	0.000	71.477	-0.000	66.405	0.000	0.000	71.477	40.162	-0.032	XOMR2_OWSG MWD+IFR1+MS
18900.000	90.000	179.789	10790.000	67.164	0.000	72.125	-0.000	67.164	0.000	0.000	72.125	40.215	-0.034	XOMR2_OWSG MWD+IFR1+MS
19000.000	90.000	179.789	10790.000	67.923	0.000	72.775	-0.000	67.923	0.000	0.000	72.775	40.268	-0.036	XOMR2_OWSG MWD+IFR1+MS
19100.000	90.000	179.789	10790.000	68.683	0.000	73.428	-0.000	68.683	0.000	0.000	73.428	40.321	-0.038	XOMR2_OWSG MWD+IFR1+MS
19200.000	90.000	179.789	10790.000	69.444	0.000	74.082	-0.000	69.444	0.000	0.000	74.083	40.375	-0.040	XOMR2_OWSG MWD+IFR1+MS
19300.000	90.000	179.789	10790.000	70.205	0.000	74.739	-0.000	70.205	0.000	0.000	74.739	40.429	-0.042	XOMR2_OWSG MWD+IFR1+MS
19400.000	90.000	179.789	10790.000	70.966	0.000	75.398	-0.000	70.966	0.000	0.000	75.398	40.484	-0.044	XOMR2_OWSG MWD+IFR1+MS

19500.000	90.000	179.789	10790.000	71.729	0.000	76.058	-0.000	71.729	0.000	0.000	76.059	40.540	-0.046	XOMR2_OWSG MWD+IFR1+MS
19600.000	90.000	179.789	10790.000	72.491	0.000	76.721	-0.000	72.491	0.000	0.000	76.721	40.596	-0.047	XOMR2_OWSG MWD+IFR1+MS
19700.000	90.000	179.789	10790.000	73.254	0.000	77.386	-0.000	73.254	0.000	0.000	77.386	40.653	-0.049	XOMR2_OWSG MWD+IFR1+MS
19800.000	90.000	179.789	10790.000	74.018	0.000	78.052	-0.000	74.018	0.000	0.000	78.052	40.710	-0.051	XOMR2_OWSG MWD+IFR1+MS
19900.000	90.000	179.789	10790.000	74.782	0.000	78.720	-0.000	74.782	0.000	0.000	78.720	40.768	-0.052	XOMR2_OWSG MWD+IFR1+MS
20000.000	90.000	179.789	10790.000	75.546	0.000	79.390	-0.000	75.546	0.000	0.000	79.390	40.826	-0.054	XOMR2_OWSG MWD+IFR1+MS
20100.000	90.000	179.789	10790.000	76.311	0.000	80.062	-0.000	76.311	0.000	0.000	80.062	40.885	-0.056	XOMR2_OWSG MWD+IFR1+MS
20200.000	90.000	179.789	10790.000	77.076	0.000	80.735	-0.000	77.076	0.000	0.000	80.735	40.944	-0.057	XOMR2_OWSG MWD+IFR1+MS
20300.000	90.000	179.789	10790.000	77.841	0.000	81.410	-0.000	77.841	0.000	0.000	81.410	41.004	-0.059	XOMR2_OWSG MWD+IFR1+MS
20400.000	90.000	179.789	10790.000	78.607	0.000	82.086	-0.000	78.607	0.000	0.000	82.086	41.065	-0.060	XOMR2_OWSG MWD+IFR1+MS
20500.000	90.000	179.789	10790.000	79.374	0.000	82.764	-0.000	79.374	0.000	0.000	82.764	41.126	-0.061	XOMR2_OWSG MWD+IFR1+MS
20600.000	90.000	179.789	10790.000	80.140	0.000	83.444	-0.000	80.140	0.000	0.000	83.444	41.187	-0.063	XOMR2_OWSG MWD+IFR1+MS
20700.000	90.000	179.789	10790.000	80.907	0.000	84.125	-0.000	80.907	0.000	0.000	84.125	41.249	-0.064	XOMR2_OWSG MWD+IFR1+MS
20800.000	90.000	179.789	10790.000	81.675	0.000	84.807	-0.000	81.675	0.000	0.000	84.807	41.312	-0.066	XOMR2_OWSG MWD+IFR1+MS
20900.000	90.000	179.789	10790.000	82.443	0.000	85.491	-0.000	82.443	0.000	0.000	85.491	41.375	-0.067	XOMR2_OWSG MWD+IFR1+MS
21000.000	90.000	179.789	10790.000	83.211	0.000	86.176	-0.000	83.211	0.000	0.000	86.176	41.438	-0.068	XOMR2_OWSG MWD+IFR1+MS
21100.000	90.000	179.789	10790.000	83.979	0.000	86.862	-0.000	83.979	0.000	0.000	86.863	41.502	-0.070	XOMR2_OWSG MWD+IFR1+MS
21200.000	90.000	179.789	10790.000	84.747	0.000	87.550	-0.000	84.747	0.000	0.000	87.550	41.567	-0.071	XOMR2_OWSG MWD+IFR1+MS
21300.000	90.000	179.789	10790.000	85.516	0.000	88.239	-0.000	85.516	0.000	0.000	88.239	41.632	-0.072	XOMR2_OWSG MWD+IFR1+MS
21400.000	90.000	179.789	10790.000	86.286	0.000	88.930	-0.000	86.286	0.000	0.000	88.930	41.698	-0.073	XOMR2_OWSG MWD+IFR1+MS

21500.000	90.000	179.789	10790.000	87.055	0.000	89.621	-0.000	87.055	0.000	0.000	89.621	41.764	-0.075	XOMR2_OWSG MWD+IFR1+MS
21600.000	90.000	179.789	10790.000	87.825	0.000	90.314	-0.000	87.825	0.000	0.000	90.314	41.830	-0.076	XOMR2_OWSG MWD+IFR1+MS
21700.000	90.000	179.789	10790.000	88.595	0.000	91.007	-0.000	88.595	0.000	0.000	91.008	41.897	-0.077	XOMR2_OWSG MWD+IFR1+MS
21800.000	90.000	179.789	10790.000	89.365	0.000	91.702	-0.000	89.365	0.000	0.000	91.703	41.965	-0.078	XOMR2_OWSG MWD+IFR1+MS
21900.000	90.000	179.789	10790.000	90.136	0.000	92.398	-0.000	90.136	0.000	0.000	92.399	42.033	-0.079	XOMR2_OWSG MWD+IFR1+MS
22000.000	90.000	179.789	10790.000	90.906	0.000	93.096	-0.000	90.906	0.000	0.000	93.096	42.102	-0.080	XOMR2_OWSG MWD+IFR1+MS
22100.000	90.000	179.789	10790.000	91.677	0.000	93.794	-0.000	91.677	0.000	0.000	93.794	42.171	-0.081	XOMR2_OWSG MWD+IFR1+MS
22200.000	90.000	179.789	10790.000	92.449	0.000	94.493	-0.000	92.449	0.000	0.000	94.493	42.240	-0.082	XOMR2_OWSG MWD+IFR1+MS
22300.000	90.000	179.789	10790.000	93.220	0.000	95.193	-0.000	93.220	0.000	0.000	95.193	42.310	-0.083	XOMR2_OWSG MWD+IFR1+MS
22400.000	90.000	179.789	10790.000	93.992	0.000	95.894	-0.000	93.992	0.000	0.000	95.895	42.381	-0.084	XOMR2_OWSG MWD+IFR1+MS
22500.000	90.000	179.789	10790.000	94.764	0.000	96.596	-0.000	94.764	0.000	0.000	96.597	42.452	-0.086	XOMR2_OWSG MWD+IFR1+MS
22600.000	90.000	179.789	10790.000	95.536	0.000	97.300	-0.000	95.536	0.000	0.000	97.300	42.523	-0.087	XOMR2_OWSG MWD+IFR1+MS
22700.000	90.000	179.789	10790.000	96.308	0.000	98.004	-0.000	96.308	0.000	0.000	98.004	42.595	-0.088	XOMR2_OWSG MWD+IFR1+MS
22800.000	90.000	179.789	10790.000	97.081	0.000	98.709	-0.000	97.081	0.000	0.000	98.709	42.668	-0.088	XOMR2_OWSG MWD+IFR1+MS
22900.000	90.000	179.789	10790.000	97.853	0.000	99.414	-0.000	97.853	0.000	0.000	99.415	42.741	-0.089	XOMR2_OWSG MWD+IFR1+MS
23000.000	90.000	179.789	10790.000	98.626	0.000	100.121	-0.000	98.626	0.000	0.000	100.121	42.814	-0.090	XOMR2_OWSG MWD+IFR1+MS
23100.000	90.000	179.789	10790.000	99.399	0.000	100.829	-0.000	99.399	0.000	0.000	100.829	42.888	-0.091	XOMR2_OWSG MWD+IFR1+MS
23200.000	90.000	179.789	10790.000	100.173	0.000	101.537	-0.000	100.173	0.000	0.000	101.537	42.962	-0.092	XOMR2_OWSG MWD+IFR1+MS
23300.000	90.000	179.789	10790.000	100.946	0.000	102.246	-0.000	100.946	0.000	0.000	102.246	43.037	-0.093	XOMR2_OWSG MWD+IFR1+MS
23400.000	90.000	179.789	10790.000	101.720	0.000	102.956	-0.000	101.720	0.000	0.000	102.956	43.112	-0.094	XOMR2_OWSG MWD+IFR1+MS

23500.000	90.000	179.789	10790.000	102.493	0.000	103.667	-0.000	102.493	0.000	0.000	103.667	43.188	-0.095	XOMR2_OWSG MWD+IFR1+MS
23600.000	90.000	179.789	10790.000	103.267	0.000	104.378	-0.000	103.267	0.000	0.000	104.378	43.264	-0.096	XOMR2_OWSG MWD+IFR1+MS
23700.000	90.000	179.789	10790.000	104.041	0.000	105.091	-0.000	104.041	0.000	0.000	105.091	43.341	-0.097	XOMR2_OWSG MWD+IFR1+MS
23800.000	90.000	179.789	10790.000	104.816	0.000	105.804	-0.000	104.816	0.000	0.000	105.804	43.418	-0.097	XOMR2_OWSG MWD+IFR1+MS
23900.000	90.000	179.789	10790.000	105.590	0.000	106.517	-0.000	105.590	0.000	0.000	106.517	43.495	-0.098	XOMR2_OWSG MWD+IFR1+MS
24000.000	90.000	179.789	10790.000	106.365	0.000	107.232	-0.000	106.365	0.000	0.000	107.232	43.573	-0.099	XOMR2_OWSG MWD+IFR1+MS
24100.000	90.000	179.789	10790.000	107.139	0.000	107.947	-0.000	107.139	0.000	0.000	107.947	43.651	-0.100	XOMR2_OWSG MWD+IFR1+MS
24200.000	90.000	179.789	10790.000	107.914	0.000	108.663	-0.000	107.914	0.000	0.000	108.663	43.730	-0.101	XOMR2_OWSG MWD+IFR1+MS
24298.035	90.000	179.789	10790.000	108.674	0.000	109.365	-0.000	108.674	0.000	0.000	109.365	43.808	-0.101	XOMR2_OWSG MWD+IFR1+MS
24300.000	90.000	179.789	10790.000	108.689	0.000	109.379	-0.000	108.689	0.000	0.000	109.379	43.809	-0.101	XOMR2_OWSG MWD+IFR1+MS
24348.036	90.000	179.789	10790.000	109.062	0.000	109.723	-0.000	109.062	0.000	0.000	109.723	43.848	-0.102	XOMR2_OWSG MWD+IFR1+MS

Plan Targets

Poker Lake Unit 28 BS 210H

Target Name	Measured Depth (ft)	Grid Northing (ft)	Grid Easting (ft)	TVD MSL (ft)	Target Shape
FTP 9	11213.45	400853.30	669867.10	7423.00	CIRCLE
LTP 9	24298.04	387768.80	669915.20	7423.00	CIRCLE
BHL 3	24348.15	387718.80	669915.50	7423.00	CIRCLE

ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.



ALL DIMENSIONS APPROXIMATE			
CACTUS WELLHEAD LLC			
20" x 9-5/8" x 7-5/8" x 5-1/2" MBU-T-CFL-R-DBLO Wellhead With 11" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head And 9-5/8", 7-5/8" & 5-1/2" Pin Bottom Mandrel Casing Hangers			
XTO ENERGY INC DELAWARE BASIN		DRAWN VJK 31MAR22	
DRAWING NO. HBE0000479		APPRV	

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

Background

Onshore Oil and Gas Order CFR Title 43 Part 3170, Drilling Operations, Sections III.A.2.i.iv.B states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. CFR Title 43 Part 3170 states, "Some situation may exist either on a well-by-well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO Energy feels the break testing the BOPE is such a situation. Therefore, as per CFR Title 43 Part 3170, XTO Energy submits this request for the variance.

Supporting Documentation

CFR Title 43 Part 3170 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time there have been significant changes in drilling technology. BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since CFR Title 43 Part 3170 was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. CFR Title 43 Part 3170 recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, *Well Control Equipment Systems for Drilling Wells* (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states “A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component.” See Table C.4 below for reference.

62

API STANDARD 53

Table C.4—Initial Pressure Testing, Surface BOP Stacks

Component to be Pressure Tested	Pressure Test—Low Pressure ^{a,c} psig (MPa)	Pressure Test—High Pressure ^{a,c}	
		Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket
Annular preventer ^b	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.
Fixed pipe, variable bore, blind, and BSR preventers ^{b,d}	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	ITP
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2.41)	RWP of side outlet valve or wellhead system, whichever is lower	ITP
Choke manifold—upstream of chokes ^e	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower	ITP
Choke manifold—downstream of chokes ^e	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or MASP for the well program, whichever is lower	
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	MASP for the well program	

^a Pressure test evaluation periods shall be a minimum of five minutes.

No visible leaks.

The pressure shall remain stable during the evaluation period. The pressure shall not decrease below the intended test pressure.

^b Annular(s) and VBR(s) shall be pressure tested on the largest and smallest OD drill pipe to be used in well program.

^c For pad drilling operations, moving from one wellhead to another within the 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

^d For surface offshore operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure vented during the initial test. For land operations, the ram BOPs shall be pressure tested with the ram locks engaged and the closing and locking pressure vented at commissioning and annually.

^e Adjustable chokes are not required to be full sealing devices. Pressure testing against a closed choke is not required.

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.

XTO Energy feels break testing and our current procedures meet the intent of CFR Title 43 Part 317 0and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than that of CFR Title 43 Part 3170 (Every 21 days). In addition to function testing the annular, pipe rams and blind rams after


each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the CFR Title 43 Part 3170.

Procedures

1. XTO Energy will use this document for our break testing plan for New Mexico Delaware basin. The summary below will be referenced in the APD or Sundry Notice and receive approval prior to implementing this variance.
2. XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
 - a. A full BOP test will be conducted on the first well on the pad.
 - b. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
 - i. Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
 - ii. Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.
 - c. A Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
 - d. A full BOP test will be required prior to drilling any production hole.
3. After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
 - a. Between the HCV valve and choke line connection
 - b. Between the BOP quick connect and the wellhead
4. The BOP is then lifted and removed from the wellhead by a hydraulic system.
5. After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
6. The connections mentioned in 3a and 3b will then be reconnected.
7. Install test plug into the wellhead using test joint or drill pipe.
8. A shell test is performed against the upper pipe rams testing the two breaks.
9. The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
10. Function test will be performed on the following components: lower pipe rams, blind rams, and annular.

11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
12. A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window.

Note: Picture below highlights BOP components that will be tested during batch operations



Summary

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.


The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation.

Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to **ONLY** retest broken pressure seals if the following conditions are met:

1. After a full BOP test is conducted on the first well on the pad.
2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
4. Full BOP test will be required prior to drilling the production hole.


Only **ONE** test will occur during each break test procedure.

All valves in red including the upper pipe rams will be shut to test the broken connections.
** Each valve on choke manifold will alternate being tested against during each rig skid.




The connection between the HCV and kill line connection will **NOT** be broken on each skid and does not need to be retested.

The connection between the BOP stack / BOP Quick Connect and wellhead will be broken, as well as, the connection between the HCV and Choke Line on each skid and will be re-tested each time.



Bleed line will discharge 100' from wellhead for non-H2S situations and 150' from wellhead for H2S situations.



Drilling Operations Choke Manifold 10M Service

10M Choke Manifold Diagram
XTO



U. S. Steel Tubular Products

5.500" 20.00lb/ft (0.361" Wall) P110 RY USS-FREEDOM HTQ[®]

11/8/2023 1:08:50 PM



MECHANICAL PROPERTIES	Pipe	USS-FREEDOM HTQ [®]		--
Minimum Yield Strength	110,000	--	psi	--
Maximum Yield Strength	125,000	--	psi	--
Minimum Tensile Strength	125,000	--	psi	--
DIMENSIONS	Pipe	USS-FREEDOM HTQ [®]		--
Outside Diameter	5.500	6.300	in.	--
Wall Thickness	0.361	--	in.	--
Inside Diameter	4.778	4.778	in.	--
Standard Drift	4.653	4.653	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	20.00	--	lb/ft	--
Plain End Weight	19.83	--	lb/ft	--
SECTION AREA	Pipe	USS-FREEDOM HTQ [®]		--
Critical Area	5.828	5.828	sq. in.	--
Joint Efficiency	--	100.0	%	--
PERFORMANCE	Pipe	USS-FREEDOM HTQ [®]		--
Minimum Collapse Pressure	11,100	11,100	psi	--
Minimum Internal Yield Pressure	12,640	12,640	psi	--
Minimum Pipe Body Yield Strength	641,000	--	lb	--
Joint Strength	--	641,000	lb	--
Compression Rating	--	641,000	lb	--
Reference Length [4]	--	21,370	ft	--
Maximum Uniaxial Bend Rating [2]	--	91.7	deg/100 ft	--
MAKE-UP DATA	Pipe	USS-FREEDOM HTQ [®]		--
Make-Up Loss	--	4.13	in.	--
Minimum Make-Up Torque [3]	--	15,000	ft-lb	--
Maximum Make-Up Torque [3]	--	21,000	ft-lb	--
Maximum Operating Torque[3]	--	29,500	ft-lb	--

UNCONTROLLED

Notes

1.

Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
2.

Uniaxial bending rating shown is structural only, and equal to compression efficiency.
3.

Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
4.

Reference length is calculated by joint strength divided by plain end weight with 1.5 safety factor.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com

XTO Permian Operating, LLC Offline Cementing Variance Request

XTO requests the option to cement the surface and intermediate casing strings offline as a prudent batch drilling efficiency of acreage development.


1. Cement Program

No changes to the cement program will take place for offline cementing.

2. Offline Cementing Procedure


The operational sequence will be as follows. If a well control event occurs, the BLM will be contacted for approval prior to conducting offline cementing operations.

1. Run casing as per normal operations. While running casing, conduct negative pressure test and confirm integrity of the float equipment (float collar and shoe)
2. Land casing with mandrel
3. Fill pipe with kill weight fluid, do not circulate through floats and confirm well is static
4. Set annular packoff shown below and pressure test to confirm integrity of the seal. Pressure ratings of wellhead components and valves is 5,000 psi.
5. After confirmation of both annular barriers and internal barriers, nipple down BOP and install cap flange.
 - a. If any barrier fails to test, the BOP stack will not be nippedled down until after the cement job is completed with cement 500ft above the highest formation capable of flow with kill weight mud above or after it has achieved 50-psi compressive strength if kill weight fluid cannot be verified.



Annular packoff with both external and internal seals

XTO Permian Operating, LLC Offline Cementing Variance Request



Wellhead diagram during skidding operations

6. Skid rig to next well on pad.
7. Confirm well is static before removing cap flange, flange will not be removed and offline cementing operations will not commence until well is under control. If well is not static, casing outlet valves will provide access to both the casing ID and annulus. Rig or third party pump truck will kill well prior to cementing or nipping up for further remediation.
 - a. Well Control Plan
 - i. The Drillers Method will be the primary well control method to regain control of the wellbore prior to cementing, if wellbore conditions do not permit the drillers method other methods of well control may be used
 - ii. Rig pumps or a 3rd party pump will be tied into the upper casing valve to pump down the casing ID
 - iii. A high pressure return line will be rigged up to lower casing valve and run to choke manifold to control annular pressure
 - iv. Once influx is circulated out of the hole, kill weight mud will be circulated
 - v. Well will be confirmed static
 - vi. Once confirmed static, cap flange will be removed to allow for offline cementing operations to commence
8. Install offline cement tool
9. Rig up cement equipment

XTO Permian Operating, LLC Offline Cementing Variance Request

Wellhead diagram during offline cementing operations

10. Circulate bottoms up with cement truck
 - a. If gas is present on bottoms up, well will be shut in and returns rerouted through gas buster to handle entrained gas
 - b. Max anticipated time before circulating with cement truck is 6 hrs
11. Perform cement job taking returns from the annulus wellhead valve
12. Confirm well is static and floats are holding after cement job
13. Remove cement equipment, offline cement tools and install night cap with pressure gauge for monitoring.

XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

Description of Operations:

1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
 - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
2. The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached.
3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. Spudder rig operations are expected to take 2-3 days per well on the pad.
5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
6. Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nipped up and tested on the wellhead before drilling operations resume on each well.
 - a. The larger rig will move back onto the location within 90 days from the point at which the wells are secured and the spudder rig is moved off location.
 - b. The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations
7. XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
8. Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area.



U. S. Steel Tubular Products

5.500" 20.00lb/ft (0.361" Wall) P110 RY USS-TALON HTQ™ RD

11/29/2021 4:16:04 PM

MECHANICAL PROPERTIES	Pipe	USS-TALON HTQ™ RD		[6]
Minimum Yield Strength	110,000	--	psi	--
Maximum Yield Strength	125,000	--	psi	--
Minimum Tensile Strength	125,000	--	psi	--
DIMENSIONS	Pipe	USS-TALON HTQ™ RD		--
Outside Diameter	5.500	5.900	in.	--
Wall Thickness	0.361	--	in.	--
Inside Diameter	4.778	4.778	in.	--
Standard Drift	4.653	4.653	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	20.00	--	lb/ft	--
Plain End Weight	19.83	--	lb/ft	--
SECTION AREA	Pipe	USS-TALON HTQ™ RD		--
Critical Area	5.828	5.828	sq. in.	--
Joint Efficiency	--	100.0	%	[2]
PERFORMANCE	Pipe	USS-TALON HTQ™ RD		--
Minimum Collapse Pressure	11,100	11,100	psi	--
Minimum Internal Yield Pressure	12,640	12,640	psi	--
Minimum Pipe Body Yield Strength	641,000	--	lb	--
Joint Strength	--	641,000	lb	--
Compression Rating	--	641,000	lb	--
Reference Length	--	21,370	ft	[5]
Maximum Uniaxial Bend Rating	--	91.7	deg/100 ft	[3]
MAKE-UP DATA	Pipe	USS-TALON HTQ™ RD		--
Make-Up Loss	--	5.58	in.	--
Minimum Make-Up Torque	--	17,000	ft-lb	[4]
Maximum Make-Up Torque	--	20,000	ft-lb	[4]
Maximum Operating Torque	--	39,500	ft-lb	[4]

UNCONTROLLED

Notes

1.

Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
2.

Joint efficiencies are calculated by dividing the connection critical area by the pipe body area.
3.

Uniaxial bend rating shown is structural only.
4.

Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
5.

Reference length is calculated by Joint Strength divided by Nominal Linear Weight, T&C with a 1.5 Safety factor.
6.

Coupling must meet minimum mechanical properties of the pipe.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

**BLACK GOLD®**

GATES ENGINEERING & SERVICES NORTH AMERICA
7603 Prairie Oak Dr.
Houston, TX. 77086

PHONE: +1 (281) 602-4100**FAX: +1 (281) 602-4147****EMAIL: gesna.quality@gates.com****WEB: www.gates.com/oilandgas**

*NEW CHOKE HOSE
INSTALLED 02-10-2024*

CERTIFICATE OF CONFORMANCE

This is to verify that the items detailed below meet the requirements of the Customer's Purchase Order referenced herein, and are in Conformance with applicable specifications, and that Records of Required Tests are on file and subject to examination. The following items were inspected and hydrostatically tested at **Gates Engineering & Services North America** facilities in Houston, TX, USA.

CUSTOMER: NABORS DRILLING TECHNOLOGIES USA DBA NABORS DRILLING USA
CUSTOMER P.O.#: 15582803 (TAG NABORS PO #15582803 SN 74621 ASSET 66-1531)
CUSTOMER P/N: IMR RETEST SN 74621 ASSET #66-1531

PART DESCRIPTION: RETEST OF CUSTOMER 3" X 45 FT 16C CHOKE & KILL HOSE ASSEMBLY C/W 4 1/16" 10K FLANGES

SALES ORDER #: 529480
QUANTITY: 1
SERIAL #: 74621 H3-012524-1

SIGNATURE:*F. Cismos***TITLE:****QUALITY ASSURANCE****DATE:****1/25/2024**



H3-15/16

1/25/2024 11:48:06 AM

TEST REPORT

CUSTOMER

Company: Nabors Industries Inc.

Production description: 74621/66-1531

Sales order #: 529480

Customer reference: FG1213

TEST OBJECT

Serial number: H3-012524-1

Lot number:

Description: 74621/66-1531

Hose ID: 3" 16C CK

Part number:

TEST INFORMATION

Test procedure: GTS-04-053

Test pressure: 15000.00 psi

Test pressure hold: 3600.00 sec

Work pressure: 10000.00 psi

Work pressure hold: 900.00 sec

Length difference: 0.00 %

Length difference: 0.00 inch

Fitting 1: 3.0 x 4-1/16 10K

Part number:

Description:

Fitting 2: 3.0 x 4-1/16 10K

Part number:

Description:


Visual check:

Pressure test result: PASS

Length measurement result:

Length: 45 feet

Test operator: Travis





H3-15/16


1/25/2024 11:48:06 AM



TEST REPORT

GAUGE TRACEABILITY

Description	Serial number	Calibration date	Calibration due date
S-25-A-W	110D3PHO	2023-06-06	2024-06-06
S-25-A-W	110IQWDG	2023-05-16	2024-05-16

Comment





Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 415508

CONDITIONS

Operator: XTO PERMIAN OPERATING LLC. 6401 HOLIDAY HILL ROAD MIDLAND, TX 79707	OGRID: 373075
	Action Number: 415508
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
ward.rikala	Any previous COA's not addressed within the updated COA's still apply.	1/15/2025