Form 3160-3
(June 2015)

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.: NMNM04591

6. If Indian, Allotee or Tribe Name:

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☑ Single Zone ☐ Multiple Zone

7. If Unit or CA Agreement, Name and No.:

8. Lease Name and Well No.: STONE COLD 23/14 B2PA FED COM 1H

2. Name of Operator: MEWBOURNE OIL COMPANY

9. API Well No.: 30-025-54576

3a. Address: P O BOX 5270, HOBBS, NM 88241

3b. Phone No. *(include area code)*: (575) 393-5905

10. Field and Pool, or Exploratory: CORBIN/Bone Spring South

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface: NENE / 400 FNL / 870 FEL / LAT 32.7248073 / LONG -103.6279546

At proposed prod. zone: NENE / 100 FNL / 660 FEL / LAT 32.7546532 / LONG -103.6272839

11. Sec., T. R. M. or Blk. and Survey or Area: SEC 26/T18S/R33E/NMP

14. Distance in miles and direction from nearest town or post office*: 10 miles

12. County or Parish: LEA

13. State: NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any): 100 feet

16. No of acres in lease:

17. Spacing Unit dedicated to this well: 320.0

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.: 30 feet

19. Proposed Depth: 9229 feet / 20362 feet

20. BLM/BIA Bond No. in file: FED: NM1693

21. Elevations (Show whether DF, KDB, RT, GL, etc.): 3846 feet

22. Approximate date work will start*: 10/01/2024

23. Estimated duration: 60 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature: (Electronic Submission)

Name *(Printed/Typed)*: BRADLEY BISHOP / Ph: (575) 393-5905

Date: 07/29/2024

Title: Regulatory

Approved by *(Signature)*: (Electronic Submission)

Name *(Printed/Typed)*: CODY LAYTON / Ph: (575) 234-5959

Date: 02/21/2025

Title: Assistant Field Manager Lands & Minerals

Office: Carlsbad Field Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS

Approval Date: 02/21/2025

(Continued on page 2)

*(Instructions on page 2)

Santa Fe Main Office
Phone: (505) 476-3441 Fax: (55) 476-3462
General Information
Phone: (505) 629-6116

Online Phone Directory Visit:
https://www.emnrd.nm.gov/ocd/contact-us/

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION

C-102
Revised July 9, 2024
Submit Electronically via OCD Permitting

Submittal Type: ☑ Initial Submittal ☐ Amended Report ☐ As Drilled

WELL LOCATION INFORMATION

API Number	Pool Code	Pool Name
30-025-54576	13160	CORBIN; BONE SPRING, SOUTH

Property Code	Property Name	Well Number
337136	STONE COLD 23/14 B2PA FED COM	1H

OGRID No.	Operator Name	Ground Level Elevation
14744	MEWBOURNE OIL COMPANY	3846'

Surface Owner: ☐ State ☐ Fee ☐ Tribal ☑ Federal
Mineral Owner: ☑ State ☐ Fee ☐ Tribal ☑ Federal

Surface Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	26	18S	33E		400' FNL	870' FEL	32.7248073	-103.627955	LEA

Bottom Hole Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	14	18S	33E		100' FNL	660' FEL	32.7546533	-103.627284	LEA

Dedicated Acres	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
160	DEFINING		N	C

Order Numbers.
Well setbacks are under Common Ownership: ☐Yes ☑No

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	26	18S	33E		473' FNL	660' FEL	32.7246084	-103.627272	LEA

First Take Point (FTP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
P	23	18S	33E		100' FSL	660' FEL	32.7261830	-103.627273	LEA

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	14	18S	33E		100' FNL	660' FEL	32.7546533	-103.627284	LEA

Unitized Area or Area of Uniform Interest	Spacing Unit Type ☑ Horizontal ☐ Vertical	Ground Floor Elevation:
		3873'

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

John Smith — Signature
04/03/2025 — Date
John Smith — Printed Name
john.smith@mewbourne.com — Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

ROBERT M. HOWETT NEW MEXICO 19680 PROFESSIONAL SURVEYOR

Signature and Seal of Professional Surveyor
Robert M. Howett
Certificate Number: 19680
Date of Survey: 07/25/2024

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

ACREAGE DEDICATION PLATS

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.



Santa Fe Main Office
Phone: (505) 476-3441 Fax: (55) 476-3462
General Information
Phone: (505) 629-6116

Online Phone Directory Visit:
https://www.emnrd.nm.gov/ocd/contact-us/

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION

C-102
Revised July 9, 2024
Submit Electronically via OCD Permitting

Submittal Type: ☐ Initial Submittal ☐ Amended Report ☐ As Drilled

WELL LOCATION INFORMATION

API Number	Pool Code	Pool Name
30-025-54576	45793	MESCALERO ESCARPE; BONE SPRING

Property Code	Property Name	Well Number
337136	STONE COLD 23/14 B2PA FED COM	1H

OGRID No.	Operator Name	Ground Level Elevation
14744	MEWBOURNE OIL COMPANY	3846'

Surface Owner: ☐ State ☐ Fee ☐ Tribal ☑ Federal
Mineral Owner: ☑ State ☐ Fee ☐ Tribal ☑ Federal

Surface Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	26	18S	33E		400' FNL	870' FEL	32.7248073	-103.627955	LEA

Bottom Hole Location

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	14	18S	33E		100' FNL	660' FEL	32.7546533	-103.627284	LEA

Dedicated Acres	Infill or Defining Well	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
160	DEFINING		N	C

Order Numbers.
Well setbacks are under Common Ownership: ☐Yes ☑No

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	26	18S	33E		473' FNL	660' FEL	32.7246084	-103.627272	LEA

First Take Point (FTP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
P	23	18S	33E		100' FSL	660' FEL	32.7261830	-103.627273	LEA

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Ft. from N/S	Ft. from E/W	Latitude	Longitude	County
A	14	18S	33E		100' FNL	660' FEL	32.7546533	-103.627284	LEA

Unitized Area or Area of Uniform Interest	Spacing Unit Type ☑ Horizontal ☐ Vertical	Ground Floor Elevation:
		3873'

OPERATOR CERTIFICATIONS

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.

John Smith — Signature
04/03/2025 — Date
John Smith — Printed Name
john.smith@mewbourne.com — Email Address

SURVEYOR CERTIFICATIONS

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

ROBERT M. HOWETT NEW MEXICO 19680 PROFESSIONAL SURVEYOR

Signature and Seal of Professional Surveyor
Robert M. Howett
Certificate Number: 19680
Date of Survey: 07/25/2024

Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

ACREAGE DEDICATION PLATS

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.



State of New Mexico
Energy, Minerals and Natural Resources Department

Submit Electronically
Via E-permitting

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

NATURAL GAS MANAGEMENT PLAN

This Natural Gas Management Plan must be submitted with each Application for Permit to Drill (APD) for a new or recompleted well.

Section 1 – Plan Description
Effective May 25, 2021

I. Operator: Mewbourne Oil Co. **OGRID:** 14744 **Date:** 5/2/22

II. Type: ☒ Original ☐ Amendment due to ☐ 19.15.27.9.D(6)(a) NMAC ☐ 19.15.27.9.D(6)(b) NMAC ☐ Other.

If Other, please describe: _____

III. Well(s): Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	ULSTR	Footages	Anticipated Oil BBL/D	Anticipated Gas MCF/D	Anticipated Produced Water BBL/D
Stone Cold 23-14 B2PA Fed Com 1H		A 26 18S 33E	400' FNL x 870' FEL	1500	1000	2500
				Y1-400 Y2-300 Y3-200	Y1-800 Y2-600 Y3-400	Y1-500 Y2-400 Y3-250

IV. Central Delivery Point Name: Stone Cold 23-14 B2PA Fed Com 1H [See 19.15.27.9(D)(1) NMAC]

V. Anticipated Schedule: Provide the following information for each new or recompleted well or set of wells proposed to be drilled or proposed to be recompleted from a single well pad or connected to a central delivery point.

Well Name	API	Spud Date	TD Reached Date	Completion Commencement Date	Initial Flow Back Date	First Production Date
Stone Cold 23-14 B2PA Fed Com 1H		7/2/22	8/2/22	9/2/22	9/17/22	9/17/22

VI. Separation Equipment: ☒ Attach a complete description of how Operator will size separation equipment to optimize gas capture.

VII. Operational Practices: ☒ Attach a complete description of the actions Operator will take to comply with the requirements of Subsection A through F of 19.15.27.8 NMAC.

VIII. Best Management Practices: ☒ Attach a complete description of Operator's best management practices to minimize venting during active and planned maintenance.

Section 2 – Enhanced Plan

EFFECTIVE APRIL 1, 2022

Beginning April 1, 2022, an operator that is not in compliance with its statewide natural gas capture requirement for the applicable reporting area must complete this section.

☒ Operator certifies that it is not required to complete this section because Operator is in compliance with its statewide natural gas capture requirement for the applicable reporting area.

IX. Anticipated Natural Gas Production:

Well	API	Anticipated Average Natural Gas Rate MCF/D	Anticipated Volume of Natural Gas for the First Year MCF

X. Natural Gas Gathering System (NGGS):

Operator	System	ULSTR of Tie-in	Anticipated Gathering Start Date	Available Maximum Daily Capacity of System Segment Tie-in

XI. Map. ☐ Attach an accurate and legible map depicting the location of the well(s), the anticipated pipeline route(s) connecting the production operations to the existing or planned interconnect of the natural gas gathering system(s), and the maximum daily capacity of the segment or portion of the natural gas gathering system(s) to which the well(s) will be connected.

XII. Line Capacity. The natural gas gathering system ☐ will ☐ will not have capacity to gather 100% of the anticipated natural gas production volume from the well prior to the date of first production.

XIII. Line Pressure. Operator ☐ does ☐ does not anticipate that its existing well(s) connected to the same segment, or portion, of the natural gas gathering system(s) described above will continue to meet anticipated increases in line pressure caused by the new well(s).

☐ Attach Operator's plan to manage production in response to the increased line pressure.

XIV. Confidentiality: ☐ Operator asserts confidentiality pursuant to Section 71-2-8 NMSA 1978 for the information provided in Section 2 as provided in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and attaches a full description of the specific information for which confidentiality is asserted and the basis for such assertion.

Section 3 - Certifications

Effective May 25, 2021

Operator certifies that, after reasonable inquiry and based on the available information at the time of submittal:

☒ Operator will be able to connect the well(s) to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system; or

☐ Operator will not be able to connect to a natural gas gathering system in the general area with sufficient capacity to transport one hundred percent of the anticipated volume of natural gas produced from the well(s) commencing on the date of first production, taking into account the current and anticipated volumes of produced natural gas from other wells connected to the pipeline gathering system. ***If Operator checks this box, Operator will select one of the following:***

Well Shut-In. ☐ Operator will shut-in and not produce the well until it submits the certification required by Paragraph (4) of Subsection D of 19.15.27.9 NMAC; or

Venting and Flaring Plan. ☐ Operator has attached a venting and flaring plan that evaluates and selects one or more of the potential alternative beneficial uses for the natural gas until a natural gas gathering system is available, including:

- **(a)** power generation on lease;
- **(b)** power generation for grid;
- **(c)** compression on lease;
- **(d)** liquids removal on lease;
- **(e)** reinjection for underground storage;
- **(f)** reinjection for temporary storage;
- **(g)** reinjection for enhanced oil recovery;
- **(h)** fuel cell production; and
- **(i)** other alternative beneficial uses approved by the division.

Section 4 - Notices

1. If, at any time after Operator submits this Natural Gas Management Plan and before the well is spud:

(a) Operator becomes aware that the natural gas gathering system it planned to connect the well(s) to has become unavailable or will not have capacity to transport one hundred percent of the production from the well(s), no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised venting and flaring plan containing the information specified in Paragraph (5) of Subsection D of 19.15.27.9 NMAC; or

(b) Operator becomes aware that it has, cumulatively for the year, become out of compliance with its baseline natural gas capture rate or natural gas capture requirement, no later than 20 days after becoming aware of such information, Operator shall submit for OCD's approval a new or revised Natural Gas Management Plan for each well it plans to spud during the next 90 days containing the information specified in Paragraph (2) of Subsection D of 19.15.27.9 NMAC, and shall file an update for each Natural Gas Management Plan until Operator is back in compliance with its baseline natural gas capture rate or natural gas capture requirement.

2. OCD may deny or conditionally approve an APD if Operator does not make a certification, fails to submit an adequate venting and flaring plan which includes alternative beneficial uses for the anticipated volume of natural gas produced, or if OCD determines that Operator will not have adequate natural gas takeaway capacity at the time a well will be spud.

I certify that, after reasonable inquiry, the statements in and attached to this Natural Gas Management Plan are true and correct to the best of my knowledge and acknowledge that a false statement may be subject to civil and criminal penalties under the Oil and Gas Act.

Signature:	Bradley Bishop
Printed Name:	BRADLEY BISHOP
Title:	REGULATORY MANAGER
E-mail Address:	BBISHOP@MEWBOURNE.COM
Date:	5/2/22
Phone:	575-393-5905

OIL CONSERVATION DIVISION
(Only applicable when submitted as a standalone form)

Approved By:	
Title:	
Approval Date:	
Conditions of Approval:	

Mewbourne Oil Company

Natural Gas Management Plan – Attachment

VI. Separation equipment will be sized by construction engineering staff based on stated manufacturer daily throughput capacities and anticipated daily production rates to ensure adequate capacity. Closed vent system piping, compression needs, and VRUs will be sized utilizing ProMax modelling software to ensure adequate capacity for anticipated production volumes and conditions.

VII. Mewbourne Oil Company (MOC) will take following actions to comply with the regulations listed in 19.15.27.8 :

A. MOC will maximize the recovery of natural gas by minimizing the waste, as defined by 19.15.2 NMAC, of natural gas through venting and flaring. MOC will ensure that well(s) will be connected to a natural gas gathering system with sufficient capacity to transport natural gas. If there is no adequate takeaway for the gas, well(s) will be shut in until the natural gas gathering system is available.

B. All drilling operations will be equipped with a rig flare located at least 100 ft from the nearest surface hole. Rig flare will be utilized to combust any natural gas that is brought to surface during normal drilling operations. In the case of emergency venting or flaring the volumes will be estimated and reported appropriately.

C. During completion operations any natural gas brought to surface will be flared. Immediately following the finish of completion operations, all well flow will be directed to permanent separation equipment. Produced natural gas from separation equipment will be sent to sales. It is not anticipated that gas will not meet pipeline standards. However, if natural gas does not meet gathering pipeline quality specifications, MOC will flare the natural gas for 60 days or until the natural gas meets the pipeline quality specifications, whichever is sooner. MOC will ensure that the flare is sized properly and is equipped with automatic igniter or continuous pilot. The gas sample will analyzed twice per week and the gas will be routed into a gathering system as soon as pipeline specifications are met.

D. Natural gas will not be flared with the exceptions and provisions listed in the 19.15.27.8 D.(1) through (4). If there is no adequate takeaway for the separator gas, well(s) will be shut in until the natural gas gathering system is available with exception of emergency or malfunction situations. Venting and/or flaring volumes will be estimated and reported appropriately.

E. MOC will comply with the performance standards requirements and provisions listed in 19.15.27.8 E.(1) through (8). All equipment will be designed and sized to handle maximum anticipated pressures and throughputs in order to minimize the waste. Production storage tanks constructed after May 25, 2021 will be equipped with automatic gauging system. Flares constructed after May 25, 2021 will be equipped with automatic igniter or continuous pilot. Flares will be located at least 100' from the well and storage tanks unless otherwise approved by the division. MOC will conduct AVO inspections as described in 19.15.27.8 E (5) (a) with frequencies specified in 19.15.27.8 E (5) (b) and (c). All emergencies will be resolved as quickly and safely as feasible to minimize waste.

F. The volume of natural gas that is vented or flared as the result of malfunction or emergency during drilling and completions operations will be estimated. The volume of natural gas that is vented, flared or beneficially used during production operations, will be measured or estimated. MOC will install equipment to measure

the volume of natural gas flared from existing process piping or a flowline piped from equipment such as high pressure separators, heater treaters, or vapor recovery units associated with a well or facility associated with a well authorized by an APD issued after May 25, 2021 that has an average daily production greater than 60 Mcf/day. If metering is not practicable due to circumstances such as low flow rate or low pressure venting and flaring, MOC will estimate the volume of vented or flared natural gas. Measuring equipment will conform to industry standards and will not be designed or equipped with a manifold that allows the diversion of natural gas around the metering element except for the sole purpose of inspecting and servicing the measurement equipment.

VIII. For maintenance activities involving production equipment and compression, venting will be limited to the depressurization of the subject equipment to ensure safe working conditions. For maintenance of production and compression equipment the associated producing wells will be shut in to eliminate venting. For maintenance of VRUs all gas normally routed to the VRU will be routed to flare to eliminate venting.



Oil, Bbl/day
Qual= LEABS2.0
Ref= 1/2025
Cum=
Rem= 33209
EUR= 33209
Yrs= 3.00
Qi= 1150.
b= 0.95000
De= 74.00000
Df= 23.84809
Qab= 116.

Gas, Mcf/day
Qual= LEABS2.0
Ref= 1/2025
Cum=
Rem= 621833
EUR= 621833
Yrs= 3.000
Qi= 1375.0
b= 1.050000
De= 56.000000
Df= 20.240305
Qab= 291.1

Water, Bbl/d
Qual= LEABS2.0
Ref= 1/2025
Cum= 0
Rem= 492387
EUR= 492387
Yrs= 3.000
Qi= 1700.0
b= 1.050000
De= 74.000000
Df= 22.172770
Qab= 183.7

AFMSS
U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report
02/27/2025

APD ID: 10400087674
Submission Date: 07/29/2024
Operator Name: MEWBOURNE OIL COMPANY
Well Name: STONE COLD 23/14 B2PA FED COM
Well Number: 1H
Well Type: OIL WELL
Well Work Type: Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical	Measured Depth	Lithologies	Mineral Resources	Producing Formatio
15075794	UNKNOWN	3874	28	28	OTHER : Topsoil	NONE	N
15075795	RUSTLER	2280	1594	1594	ANHYDRITE, DOLOMITE	USEABLE WATER	N
15075805	TOP SALT	2015	1859	1859	SALT	NONE	N
15075806	BASE OF SALT	890	2984	2984	SALT	NONE	N
15075815	YATES	775	3099	3099	SANDSTONE	NATURAL GAS, OIL	N
15075816	SEVEN RIVERS	230	3644	3644	DOLOMITE	NATURAL GAS, OIL	N
15075817	QUEEN	-450	4324	4324	DOLOMITE, SANDSTONE	NATURAL GAS, OIL	N
15075818	SAN ANDRES	-1175	5049	5049	DOLOMITE	NATURAL GAS, OIL	N
15075808	LAMAR	-1420	5294	5294	LIMESTONE	NATURAL GAS, OIL	N
15075802	BONE SPRING	-3575	7449	7449	LIMESTONE, SHALE	NATURAL GAS, OIL	N
15075803	BONE SPRING 1ST	-4800	8674	8674	SANDSTONE	NATURAL GAS, OIL	N
15075813	BONE SPRING 2ND	-5450	9324	9324	SANDSTONE	NATURAL GAS, OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M
Rating Depth: 20362

Equipment: Annular Pipe Rams Blind Rams Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.
Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for hydrostatic test chart. Anchors are not required by manufacturer. A variance is requested to use a multi-bowl wellhead.

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Testing Procedure: BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested. Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

Choke Diagram Attachment:

Stone_Cold_23_14_B2PA_Fed_Com_1H_5M_BOPE_Choke_Diagram_20220824134036.pdf

Flex_Line_Specs_API_16C_20241120151531.pdf

Cactus_5K_WH_20241120151531.pdf

BOP Diagram Attachment:

Stone_Cold_23_14_B2PA_Fed_Com_1H_5M_BOPE_Schematic_20220824134027.pdf

Stone_Cold_23_14_B2PA_Fed_Com_1H_5M_Mutli_Bowl_WH_20220824134028.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	1670	0	1670	3874	2204	1670	J-55	54.5	ST&C	1.48	3.57	DRY	5.65	DRY	9.37
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	3100	0	3100		774	3100	J-55	36	LT&C	1.25	2.18	DRY	4.06	DRY	5.05
3	PRODUCTION	8.75	7.0	NEW	API	N	0	9029	0	9026		-5152	9029	P-110	26	LT&C	1.37	2.19	DRY	2.72	DRY	3.54
4	LINER	6.125	4.5	NEW	API	N	8829	20362	8826	9229	-4952	-5355	11533	P-110	13.5	LT&C	1.77	2.06	DRY	2.17	DRY	2.71

Casing Attachments

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Casing Attachments

Casing ID: 1 **String** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Stone_Cold_23_14_B2PA_Fed_Com_1H_Csg_Assumptions_20220824134427.pdf

Casing ID: 2 **String** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Stone_Cold_23_14_B2PA_Fed_Com_1H_Csg_Assumptions_20220824134237.pdf

Casing ID: 3 **String** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Stone_Cold_23_14_B2PA_Fed_Com_1H_Csg_Assumptions_20220824134147.pdf

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Casing Attachments

Casing ID: 4 **String** LINER

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Stone_Cold_23_14_B2PA_Fed_Com_1H_Csg_Assumptions_20220824134353.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	1477	970	2.12	12.5	2056	100	Class C	Salt, Gel, Extender, LCM
SURFACE	Tail		1477	1670	200	1.34	14.8	268	100	Class C	Retarder
INTERMEDIATE	Lead		0	2408	440	2.12	12.5	933	25	Class C	Salt, Gel, Extender, LCM
INTERMEDIATE	Tail		2408	3100	200	1.34	14.8	268	25	Class C	Retarder
PRODUCTION	Lead	5295	2900	4677	160	2.12	12.5	328	25	Class C	Salt, Gel, Extender, LCM, Defoamer
PRODUCTION	Tail		4677	5295	100	1.18	15.6	118	25	Class H	Retarder
PRODUCTION	Lead	5295	5295	6530	110	2.12	12.5	233	25	Class C	Salt, Gel, Extender, LCM Defoamer
PRODUCTION	Tail		6530	9029	400	1.18	15.6	472	25	Class H	Retarder, Fluid Loss, Defoamer
LINER	Lead		8829	20362	740	1.85	13.5	1369	25	Class H	Salt, Gel, Fluid Loss, Retarder, Dispersant, Defoamer, Anti-settling Agent

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Lost circulation material, sweeps, mud scavengers

Describe the mud monitoring system utilized: Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	1670	SPUD MUD	8.4	8.8							
1670	3100	SALT SATURATED	10	10							
3100	9029	WATER-BASED MUD	8.6	9.7							
9029	20362	OIL-BASED MUD	8.6	12							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GR/CNL on deeper offset Stone Cold 23/14 B2OB Fed Com #1H from KOP to surface.

List of open and cased hole logs run in the well:

DIRECTIONAL SURVEY,MEASUREMENT WHILE DRILLING,MUD LOG/GEOLOGIC LITHOLOGY LOG,

Coring operation description for the well:

None

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 5759 **Anticipated Surface Pressure:** 3632

Anticipated Bottom Hole Temperature(F): 185

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geoharzards description:

Contingency Plans geohazards

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations

Stone_Cold_23_14_B2PA_Fed_Com_1H_H2S_Plan_20220824134905.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Stone_Cold_23_14_B2PA_Fed_Com_1H_MOC_DIR_PLAN_20220824135004.pdf
Stone_Cold_23_14_B2PA_Fed_Com_1H_MOC_DIR_PLOT_20220824135004.pdf

Other proposed operations facets description:

Other proposed operations facets attachment:

Stone_Cold_23_14_B2PA_Fed_Com_1H_Additional_Information___Permitting_20220824134958.pdf
Stone_Cold_23_14_B2PA_Fed_Com_1H_NGMP_1_20241121145427.pdf

Other Variance attachment:

5M BOPE & Closed Loop Equipment Schematic



Drawing not to scale

LETONE

LUOHE LETONE HYDRAULICS TECHNOLOGY CO.,LTD

HYDROSTATIC TESTING REPORT

LTYY/QR-5.7.1-28 №: 230826015

Product Name	Choke And Kill Hose	Standard	API Spec 16C 3rd edition
Product Specification	3″×10000psi×60ft（18.29m）	Serial Number	7660144
Inspection Equipment	MTU-BS-1600-3200-E	Test medium	Water
Inspection Department	Q.C. Department	Inspection Date	2023.08.26
Rate of length change			
Standard requirements	At working pressure ,the rate of length change should not more than ±2%		
Testing result	10000psi (69.0MPa) ,Rate of length change 0.7%		
Hydrostatic testing			
Standard requirements	At 1.5 times working pressure, the initial pressure-holding period of not less than three minutes, the second pressure-holding period of not less than one hour, no leaks.		
Testing result	15000psi (103.5MPa), 3 min for the first time, 60 min for the second time, no leakage		

Graph of pressure testing:



Conclusion	The inspected items meet standard requirements of API Spec 16C 3rd edition				
Approver	Jiaolong Chen	Auditor	Huiqing Dong	Inspector	Zhansheng Wang

LETONE

LUOHE LETONE HYDRAULICS TECHNOLOGY CO.,LTD

CERTIFICATE OF QUALITY

LTYY/QR-5.7.1-19B №: LT2023-126-002

Customer Name	Austin Hose		
Product Name	Choke And Kill Hose		
Product Specification	3″×10000psi×60ft（18.29m）	Quantity	2PCS
Serial Number	7660143~7660144	FSL	FSL3
Temperature Range	-29℃～+121℃	Standard	API Spec 16C 3rd edition
Inspection Department	Q.C. Department	Inspection date	2023.08.26

Inspection Items	Inspection results
Appearance Checking	In accordance with API Spec 16C 3rd edition
Size and Lengths	In accordance with API Spec 16C 3rd edition
Dimensions and Tolerances	In accordance with API Spec 16C 3rd edition
End Connections: 4-1/16″×10000psi Integral flange for sour gas service	In accordance with API Spec 6A 21st edition
End Connections: 4-1/16″×10000psi Integral flange for sour gas service	In accordance with API Spec 17D 3rd edition
Hydrostatic Testing	In accordance with API Spec 16C 3rd edition
product Marking	In accordance with API Spec 16C 3rd edition
Inspection conclusion	The inspected items meet standard requirements of API Spec 16C 3rd edition
Remarks	

Approver	Jiaolong Chen	Auditor	Hinging Dong	Inspector	Zhansheng Wang

LETONE

LUOHE LETONE HYDRAULICS TECHNOLOGY CO.,LTD

CERTIFICATE OF CONFORMANCE

№:LT230826016

Product Name：Choke And Kill Hose

Product Specification：3″×10000psi×60ft（18.29m）

Serial Number：7660143~7660144

End Connections: 4-1/16″×10000psi Integral flange for sour gas service

The Choke And Kill Hose assembly was produced by LUOHE LETONE HYDRAULICS TECHNOLOGY CO.,LTD . in Aug 2023, and inspected by LUOHE LETONE HYDRAULICS TECHNOLOGY CO.,LTD. according to API Spec 16C 3rd edition on Aug 26, 2023. The overall condition is good. This is to certify that the Choke And Kill Hose complies with all current standards and specifications for API Spec 16C 3rd edition .

QC Manager：Jiaolong Chen Date:Aug 26, 2023



ALL DIMENSIONS APPROXIMATE

CACTUS WELLHEAD LLC	MEWBOURNE OIL COMPANY NEW MEXICO		
20" x 13-3/8" x 9-5/8" x 7" MBU-3T-CFL-R-DBLO Wellhead System With 9-5/8" & 7" Fluted Mandrel Casing Hangers And 13-5/8" 5M x 7-1/16" 10M CTH-DBLHPS Tubing Head	DRAWN	DLE	18APR22
	APPRV		
	DRAWING NO.	HBE0000660	

5M BOPE Schematic



CAMERON
A Schlumberger Company

13-5/8" MN-DS Wellhead System



MEWBOURNE OIL COMPANY

C7585
Rev. 02

NOTE: All dimensions on this drawing are estimated measurements and should be evaluated by engineering.

Capping flange 57" conductor cut-off

Mewbourne Oil Company, Stone Cold 23/14 B2PA Fed Com #1H
Sec 26, T18S, R33E
SHL: 400' FNL & 870' FEL, Sec 26
BHL: 100' FNL & 660' FEL, Sec 14

Casing Program

Hole Size	Casing Interval From	Casing Interval To	Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
17.5"	0'	1670'	13.375"	54.5	J55	STC	1.48	3.57	5.65	9.37
12.25"	0'	3100'	9.625"	36	J55	LTC	1.25	2.18	4.06	5.05
8.75"	0'	9029'	7"	26	P110	LTC	1.37	2.19	2.72	3.54
6.125"	8829'	20362'	4.5"	13.5	P110	LTC	1.77	2.06	2.17	2.71
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Stone Cold 23/14 B2PA Fed Com #1H
Sec 26, T18S, R33E
SHL: 400' FNL & 870' FEL, Sec 26
BHL: 100' FNL & 660' FEL, Sec 14

Casing Program

Hole Size	Casing Interval From	To	Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
17.5"	0'	1670'	13.375"	54.5	J55	STC	1.48	3.57	5.65	9.37
12.25"	0'	3100'	9.625"	36	J55	LTC	1.25	2.18	4.06	5.05
8.75"	0'	9029'	7"	26	P110	LTC	1.37	2.19	2.72	3.54
6.125"	8829'	20362'	4.5"	13.5	P110	LTC	1.77	2.06	2.17	2.71
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Stone Cold 23/14 B2PA Fed Com #1H
Sec 26, T18S, R33E
SHL: 400' FNL & 870' FEL, Sec 26
BHL: 100' FNL & 660' FEL, Sec 14

Casing Program

Hole Size	Casing Interval From	To	Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
17.5"	0'	1670'	13.375"	54.5	J55	STC	1.48	3.57	5.65	9.37
12.25"	0'	3100'	9.625"	36	J55	LTC	1.25	2.18	4.06	5.05
8.75"	0'	9029'	7"	26	P110	LTC	1.37	2.19	2.72	3.54
6.125"	8829'	20362'	4.5"	13.5	P110	LTC	1.77	2.06	2.17	2.71
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company, Stone Cold 23/14 B2PA Fed Com #1H
Sec 26, T18S, R33E
SHL: 400' FNL & 870' FEL, Sec 26
BHL: 100' FNL & 660' FEL, Sec 14

Casing Program

Hole Size	Casing Interval From	Casing Interval To	Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Jt Tension	SF Body Tension
17.5"	0'	1670'	13.375"	54.5	J55	STC	1.48	3.57	5.65	9.37
12.25"	0'	3100'	9.625"	36	J55	LTC	1.25	2.18	4.06	5.05
8.75"	0'	9029'	7"	26	P110	LTC	1.37	2.19	2.72	3.54
6.125"	8829'	20362'	4.5"	13.5	P110	LTC	1.77	2.06	2.17	2.71
				BLM Minimum Safety Factor			1.125	1	1.6 Dry 1.8 Wet	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h
Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Mewbourne Oil Company

Lea County, New Mexico NAD 83
Stone Cold 23/14 B2PA Fed Com #1H
Sec 26, T18S, R33E
SHL: 400' FNL & 870' FEL (Sec 26)
BHL: 100' FNL & 660' FEL (Sec 14)

Plan: Design #1

Standard Planning Report

23 August, 2022

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Project	Lea County, New Mexico NAD 83		
Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Stone Cold 23/14 B2PA Fed Com #1H				
Site Position:		**Northing:**	628,138.30 usft	**Latitude:**	32.7248073
From:	Map	**Easting:**	758,261.20 usft	**Longitude:**	-103.6279546
Position Uncertainty:	0.0 usft	**Slot Radius:**	13-3/16 "		

Well	Sec 26, T18S, R33E					
Well Position	**+N/-S**	0.1 usft	**Northing:**	628,138.30 usft	**Latitude:**	32.7248073
	+E/-W	0.2 usft	**Easting:**	758,261.20 usft	**Longitude:**	-103.6279546
Position Uncertainty		0.0 usft	**Wellhead Elevation:**	3,874.0 usft	**Ground Level:**	3,846.0 usft
Grid Convergence:		0.38 °				

Wellbore	BHL: 100' FNL & 660' FEL (Sec 14)				
Magnetics	**Model Name**	**Sample Date**	**Declination (°)**	**Dip Angle (°)**	**Field Strength (nT)**
	IGRF2010	12/31/2014	7.21	60.55	48,553.22002017

Design	Design #1				
Audit Notes:					
Version:		**Phase:**	PROTOTYPE	**Tie On Depth:**	0.0
Vertical Section:	**Depth From (TVD) (usft)**	**+N/-S (usft)**	**+E/-W (usft)**	**Direction (°)**	
	0.0	0.1	0.2	0.71	

Plan Survey Tool Program **Date** 8/23/2022

	Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks
1	0.0	20,362.2	Design #1 (BHL: 100' FNL & 660'		

Plan Sections

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.1	0.2	0.00	0.00	0.00	0.00	
1,750.0	0.00	0.00	1,750.0	0.1	0.2	0.00	0.00	0.00	0.00	
1,837.6	1.75	108.67	1,837.6	-0.3	1.5	2.00	2.00	0.00	108.67	
9,006.7	1.75	108.67	9,003.4	-70.5	209.3	0.00	0.00	0.00	0.00	
9,094.4	0.00	0.00	9,091.0	-71.0	210.5	2.00	-2.00	0.00	180.00	KOP: 473' FNL & 660
10,019.4	92.41	359.60	9,664.0	526.6	206.4	9.99	9.99	0.00	-0.40	
20,362.2	92.41	359.60	9,229.0	10,860.1	134.1	0.00	0.00	0.00	0.00	BHL: 100' FNL & 660'

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.0	0.00	0.00	0.0	0.1	0.2	0.0	0.00	0.00	0.00
SHL: 400' FNL & 870' FEL (Sec 26)									
100.0	0.00	0.00	100.0	0.1	0.2	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.1	0.2	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.1	0.2	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.1	0.2	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.1	0.2	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.1	0.2	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.1	0.2	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.1	0.2	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.1	0.2	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.1	0.2	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.1	0.2	0.0	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.1	0.2	0.0	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.1	0.2	0.0	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.1	0.2	0.0	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.1	0.2	0.0	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.1	0.2	0.0	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.1	0.2	0.0	0.00	0.00	0.00
1,750.0	0.00	0.00	1,750.0	0.1	0.2	0.0	0.00	0.00	0.00
1,800.0	1.00	108.67	1,800.0	0.0	0.7	-0.1	2.00	2.00	0.00
1,837.6	1.75	108.67	1,837.6	-0.3	1.5	-0.4	2.00	2.00	0.00
1,900.0	1.75	108.67	1,900.0	-0.9	3.3	-1.0	0.00	0.00	0.00
2,000.0	1.75	108.67	1,999.9	-1.9	6.2	-1.9	0.00	0.00	0.00
2,100.0	1.75	108.67	2,099.9	-2.9	9.1	-2.9	0.00	0.00	0.00
2,200.0	1.75	108.67	2,199.8	-3.9	12.0	-3.8	0.00	0.00	0.00
2,300.0	1.75	108.67	2,299.8	-4.8	14.9	-4.8	0.00	0.00	0.00
2,400.0	1.75	108.67	2,399.7	-5.8	17.8	-5.7	0.00	0.00	0.00
2,500.0	1.75	108.67	2,499.7	-6.8	20.7	-6.7	0.00	0.00	0.00
2,600.0	1.75	108.67	2,599.6	-7.8	23.6	-7.6	0.00	0.00	0.00
2,700.0	1.75	108.67	2,699.6	-8.8	26.5	-8.6	0.00	0.00	0.00
2,800.0	1.75	108.67	2,799.5	-9.7	29.4	-9.5	0.00	0.00	0.00
2,900.0	1.75	108.67	2,899.5	-10.7	32.3	-10.4	0.00	0.00	0.00
3,000.0	1.75	108.67	2,999.4	-11.7	35.2	-11.4	0.00	0.00	0.00
3,100.0	1.75	108.67	3,099.4	-12.7	38.1	-12.3	0.00	0.00	0.00
3,200.0	1.75	108.67	3,199.3	-13.7	41.0	-13.3	0.00	0.00	0.00
3,300.0	1.75	108.67	3,299.3	-14.6	43.9	-14.2	0.00	0.00	0.00
3,400.0	1.75	108.67	3,399.3	-15.6	46.8	-15.2	0.00	0.00	0.00
3,500.0	1.75	108.67	3,499.2	-16.6	49.7	-16.1	0.00	0.00	0.00
3,600.0	1.75	108.67	3,599.2	-17.6	52.6	-17.0	0.00	0.00	0.00
3,700.0	1.75	108.67	3,699.1	-18.6	55.5	-18.0	0.00	0.00	0.00
3,800.0	1.75	108.67	3,799.1	-19.5	58.4	-18.9	0.00	0.00	0.00
3,900.0	1.75	108.67	3,899.0	-20.5	61.3	-19.9	0.00	0.00	0.00
4,000.0	1.75	108.67	3,999.0	-21.5	64.2	-20.8	0.00	0.00	0.00
4,100.0	1.75	108.67	4,098.9	-22.5	67.1	-21.8	0.00	0.00	0.00
4,200.0	1.75	108.67	4,198.9	-23.5	70.0	-22.7	0.00	0.00	0.00
4,300.0	1.75	108.67	4,298.8	-24.4	72.9	-23.6	0.00	0.00	0.00
4,400.0	1.75	108.67	4,398.8	-25.4	75.8	-24.6	0.00	0.00	0.00
4,500.0	1.75	108.67	4,498.7	-26.4	78.7	-25.5	0.00	0.00	0.00
4,600.0	1.75	108.67	4,598.7	-27.4	81.6	-26.5	0.00	0.00	0.00
4,700.0	1.75	108.67	4,698.6	-28.4	84.5	-27.4	0.00	0.00	0.00
4,800.0	1.75	108.67	4,798.6	-29.3	87.4	-28.4	0.00	0.00	0.00
4,900.0	1.75	108.67	4,898.6	-30.3	90.3	-29.3	0.00	0.00	0.00
5,000.0	1.75	108.67	4,998.5	-31.3	93.2	-30.3	0.00	0.00	0.00

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,100.0	1.75	108.67	5,098.5	-32.3	96.1	-31.2	0.00	0.00	0.00
5,200.0	1.75	108.67	5,198.4	-33.3	99.0	-32.1	0.00	0.00	0.00
5,300.0	1.75	108.67	5,298.4	-34.2	101.8	-33.1	0.00	0.00	0.00
5,400.0	1.75	108.67	5,398.3	-35.2	104.7	-34.0	0.00	0.00	0.00
5,500.0	1.75	108.67	5,498.3	-36.2	107.6	-35.0	0.00	0.00	0.00
5,600.0	1.75	108.67	5,598.2	-37.2	110.5	-35.9	0.00	0.00	0.00
5,700.0	1.75	108.67	5,698.2	-38.1	113.4	-36.9	0.00	0.00	0.00
5,800.0	1.75	108.67	5,798.1	-39.1	116.3	-37.8	0.00	0.00	0.00
5,900.0	1.75	108.67	5,898.1	-40.1	119.2	-38.7	0.00	0.00	0.00
6,000.0	1.75	108.67	5,998.0	-41.1	122.1	-39.7	0.00	0.00	0.00
6,100.0	1.75	108.67	6,098.0	-42.1	125.0	-40.6	0.00	0.00	0.00
6,200.0	1.75	108.67	6,197.9	-43.0	127.9	-41.6	0.00	0.00	0.00
6,300.0	1.75	108.67	6,297.9	-44.0	130.8	-42.5	0.00	0.00	0.00
6,400.0	1.75	108.67	6,397.9	-45.0	133.7	-43.5	0.00	0.00	0.00
6,500.0	1.75	108.67	6,497.8	-46.0	136.6	-44.4	0.00	0.00	0.00
6,600.0	1.75	108.67	6,597.8	-47.0	139.5	-45.4	0.00	0.00	0.00
6,700.0	1.75	108.67	6,697.7	-47.9	142.4	-46.3	0.00	0.00	0.00
6,800.0	1.75	108.67	6,797.7	-48.9	145.3	-47.2	0.00	0.00	0.00
6,900.0	1.75	108.67	6,897.6	-49.9	148.2	-48.2	0.00	0.00	0.00
7,000.0	1.75	108.67	6,997.6	-50.9	151.1	-49.1	0.00	0.00	0.00
7,100.0	1.75	108.67	7,097.5	-51.9	154.0	-50.1	0.00	0.00	0.00
7,200.0	1.75	108.67	7,197.5	-52.8	156.9	-51.0	0.00	0.00	0.00
7,300.0	1.75	108.67	7,297.4	-53.8	159.8	-52.0	0.00	0.00	0.00
7,400.0	1.75	108.67	7,397.4	-54.8	162.7	-52.9	0.00	0.00	0.00
7,500.0	1.75	108.67	7,497.3	-55.8	165.6	-53.8	0.00	0.00	0.00
7,600.0	1.75	108.67	7,597.3	-56.8	168.5	-54.8	0.00	0.00	0.00
7,700.0	1.75	108.67	7,697.2	-57.7	171.4	-55.7	0.00	0.00	0.00
7,800.0	1.75	108.67	7,797.2	-58.7	174.3	-56.7	0.00	0.00	0.00
7,900.0	1.75	108.67	7,897.1	-59.7	177.2	-57.6	0.00	0.00	0.00
8,000.0	1.75	108.67	7,997.1	-60.7	180.1	-58.6	0.00	0.00	0.00
8,100.0	1.75	108.67	8,097.1	-61.7	183.0	-59.5	0.00	0.00	0.00
8,200.0	1.75	108.67	8,197.0	-62.6	185.9	-60.4	0.00	0.00	0.00
8,300.0	1.75	108.67	8,297.0	-63.6	188.8	-61.4	0.00	0.00	0.00
8,400.0	1.75	108.67	8,396.9	-64.6	191.7	-62.3	0.00	0.00	0.00
8,500.0	1.75	108.67	8,496.9	-65.6	194.6	-63.3	0.00	0.00	0.00
8,600.0	1.75	108.67	8,596.8	-66.6	197.5	-64.2	0.00	0.00	0.00
8,700.0	1.75	108.67	8,696.8	-67.5	200.4	-65.2	0.00	0.00	0.00
8,800.0	1.75	108.67	8,796.7	-68.5	203.3	-66.1	0.00	0.00	0.00
8,900.0	1.75	108.67	8,896.7	-69.5	206.2	-67.1	0.00	0.00	0.00
9,000.0	1.75	108.67	8,996.6	-70.5	209.1	-68.0	0.00	0.00	0.00
9,006.7	1.75	108.67	9,003.4	-70.5	209.3	-68.1	0.00	0.00	0.00
9,094.4	0.00	0.00	9,091.0	-71.0	210.5	-68.5	2.00	-2.00	0.00
KOP: 473' FNL & 660' FEL (Sec 26)									
9,100.0	0.56	359.60	9,096.6	-70.9	210.5	-68.4	9.99	9.99	0.00
9,200.0	10.55	359.60	9,196.0	-61.3	210.5	-58.8	9.99	9.99	0.00
9,300.0	20.54	359.60	9,292.2	-34.5	210.3	-32.0	9.99	9.99	0.00
9,400.0	30.53	359.60	9,382.4	8.6	210.0	11.0	9.99	9.99	0.00
9,500.0	40.52	359.60	9,463.6	66.6	209.6	69.1	9.99	9.99	0.00
9,600.0	50.51	359.60	9,533.6	137.8	209.1	140.3	9.99	9.99	0.00
9,700.0	60.50	359.60	9,590.2	220.2	208.5	222.6	9.99	9.99	0.00
9,800.0	70.49	359.60	9,631.6	311.0	207.9	313.5	9.99	9.99	0.00
9,900.0	80.48	359.60	9,656.6	407.7	207.2	410.1	9.99	9.99	0.00
9,994.6	89.94	359.60	9,664.5	501.9	206.5	504.3	9.99	9.99	0.00
FTP/LP: 100' FSL & 660' FEL (Sec 23)									

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
10,000.0	90.47	359.60	9,664.5	507.3	206.5	509.7	9.99	9.99	0.00
10,019.4	92.41	359.60	9,664.0	526.6	206.4	529.0	9.99	9.99	0.00
10,100.0	92.41	359.60	9,660.6	607.2	205.8	609.6	0.00	0.00	0.00
10,200.0	92.41	359.60	9,656.4	707.1	205.1	709.5	0.00	0.00	0.00
10,300.0	92.41	359.60	9,652.2	807.0	204.4	809.4	0.00	0.00	0.00
10,400.0	92.41	359.60	9,648.0	906.9	203.7	909.3	0.00	0.00	0.00
10,500.0	92.41	359.60	9,643.8	1,006.8	203.0	1,009.2	0.00	0.00	0.00
10,600.0	92.41	359.60	9,639.6	1,106.7	202.3	1,109.0	0.00	0.00	0.00
10,700.0	92.41	359.60	9,635.4	1,206.7	201.6	1,208.9	0.00	0.00	0.00
10,800.0	92.41	359.60	9,631.2	1,306.6	200.9	1,308.8	0.00	0.00	0.00
10,900.0	92.41	359.60	9,627.0	1,406.5	200.2	1,408.7	0.00	0.00	0.00
11,000.0	92.41	359.60	9,622.8	1,506.4	199.5	1,508.6	0.00	0.00	0.00
11,100.0	92.41	359.60	9,618.6	1,606.3	198.8	1,608.5	0.00	0.00	0.00
11,200.0	92.41	359.60	9,614.3	1,706.2	198.1	1,708.4	0.00	0.00	0.00
11,215.3	92.41	359.60	9,613.7	1,721.4	198.0	1,723.6	0.00	0.00	0.00
PPP2: 1320' FSL & 660' FEL (Sec 23)									
11,300.0	92.41	359.60	9,610.1	1,806.1	197.4	1,808.3	0.00	0.00	0.00
11,400.0	92.41	359.60	9,605.9	1,906.0	196.7	1,908.2	0.00	0.00	0.00
11,500.0	92.41	359.60	9,601.7	2,005.9	196.0	2,008.1	0.00	0.00	0.00
11,600.0	92.41	359.60	9,597.5	2,105.8	195.3	2,108.0	0.00	0.00	0.00
11,700.0	92.41	359.60	9,593.3	2,205.7	194.6	2,207.9	0.00	0.00	0.00
11,800.0	92.41	359.60	9,589.1	2,305.7	193.9	2,307.8	0.00	0.00	0.00
11,900.0	92.41	359.60	9,584.9	2,405.6	193.2	2,407.7	0.00	0.00	0.00
12,000.0	92.41	359.60	9,580.7	2,505.5	192.5	2,507.5	0.00	0.00	0.00
12,100.0	92.41	359.60	9,576.5	2,605.4	191.8	2,607.4	0.00	0.00	0.00
12,200.0	92.41	359.60	9,572.3	2,705.3	191.1	2,707.3	0.00	0.00	0.00
12,300.0	92.41	359.60	9,568.1	2,805.2	190.4	2,807.2	0.00	0.00	0.00
12,400.0	92.41	359.60	9,563.9	2,905.1	189.7	2,907.1	0.00	0.00	0.00
12,500.0	92.41	359.60	9,559.7	3,005.0	189.0	3,007.0	0.00	0.00	0.00
12,600.0	92.41	359.60	9,555.5	3,104.9	188.3	3,106.9	0.00	0.00	0.00
12,700.0	92.41	359.60	9,551.3	3,204.8	187.6	3,206.8	0.00	0.00	0.00
12,800.0	92.41	359.60	9,547.1	3,304.7	186.9	3,306.7	0.00	0.00	0.00
12,900.0	92.41	359.60	9,542.8	3,404.7	186.2	3,406.6	0.00	0.00	0.00
13,000.0	92.41	359.60	9,538.6	3,504.6	185.6	3,506.5	0.00	0.00	0.00
13,100.0	92.41	359.60	9,534.4	3,604.5	184.9	3,606.4	0.00	0.00	0.00
13,200.0	92.41	359.60	9,530.2	3,704.4	184.2	3,706.3	0.00	0.00	0.00
13,300.0	92.41	359.60	9,526.0	3,804.3	183.5	3,806.2	0.00	0.00	0.00
13,400.0	92.41	359.60	9,521.8	3,904.2	182.8	3,906.0	0.00	0.00	0.00
13,500.0	92.41	359.60	9,517.6	4,004.1	182.1	4,005.9	0.00	0.00	0.00
13,600.0	92.41	359.60	9,513.4	4,104.0	181.4	4,105.8	0.00	0.00	0.00
13,700.0	92.41	359.60	9,509.2	4,203.9	180.7	4,205.7	0.00	0.00	0.00
13,800.0	92.41	359.60	9,505.0	4,303.8	180.0	4,305.6	0.00	0.00	0.00
13,900.0	92.41	359.60	9,500.8	4,403.7	179.3	4,405.5	0.00	0.00	0.00
14,000.0	92.41	359.60	9,496.6	4,503.7	178.6	4,505.4	0.00	0.00	0.00
14,100.0	92.41	359.60	9,492.4	4,603.6	177.9	4,605.3	0.00	0.00	0.00
14,200.0	92.41	359.60	9,488.2	4,703.5	177.2	4,705.2	0.00	0.00	0.00
14,300.0	92.41	359.60	9,484.0	4,803.4	176.5	4,805.1	0.00	0.00	0.00
14,400.0	92.41	359.60	9,479.8	4,903.3	175.8	4,905.0	0.00	0.00	0.00
14,500.0	92.41	359.60	9,475.6	5,003.2	175.1	5,004.9	0.00	0.00	0.00
14,600.0	92.41	359.60	9,471.3	5,103.1	174.4	5,104.8	0.00	0.00	0.00
14,700.0	92.41	359.60	9,467.1	5,203.0	173.7	5,204.7	0.00	0.00	0.00
14,800.0	92.41	359.60	9,462.9	5,302.9	173.0	5,304.5	0.00	0.00	0.00
14,900.0	92.41	359.60	9,458.7	5,402.8	172.3	5,404.4	0.00	0.00	0.00

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,000.0	92.41	359.60	9,454.5	5,502.7	171.6	5,504.3	0.00	0.00	0.00
15,100.0	92.41	359.60	9,450.3	5,602.7	170.9	5,604.2	0.00	0.00	0.00
15,200.0	92.41	359.60	9,446.1	5,702.6	170.2	5,704.1	0.00	0.00	0.00
15,300.0	92.41	359.60	9,441.9	5,802.5	169.5	5,804.0	0.00	0.00	0.00
15,400.0	92.41	359.60	9,437.7	5,902.4	168.8	5,903.9	0.00	0.00	0.00
15,500.0	92.41	359.60	9,433.5	6,002.3	168.1	6,003.8	0.00	0.00	0.00
15,600.0	92.41	359.60	9,429.3	6,102.2	167.4	6,103.7	0.00	0.00	0.00
15,700.0	92.41	359.60	9,425.1	6,202.1	166.7	6,203.6	0.00	0.00	0.00
15,800.0	92.41	359.60	9,420.9	6,302.0	166.0	6,303.5	0.00	0.00	0.00
15,900.0	92.41	359.60	9,416.7	6,401.9	165.3	6,403.4	0.00	0.00	0.00
16,000.0	92.41	359.60	9,412.5	6,501.8	164.6	6,503.3	0.00	0.00	0.00
16,100.0	92.41	359.60	9,408.3	6,601.7	163.9	6,603.2	0.00	0.00	0.00
16,200.0	92.41	359.60	9,404.1	6,701.7	163.2	6,703.0	0.00	0.00	0.00
16,300.0	92.41	359.60	9,399.8	6,801.6	162.5	6,802.9	0.00	0.00	0.00
16,400.0	92.41	359.60	9,395.6	6,901.5	161.8	6,902.8	0.00	0.00	0.00
16,499.7	92.41	359.60	9,391.5	7,001.1	161.1	7,002.4	0.00	0.00	0.00
PPP3: 1320' FSL & 660' FEL (Sec 14)									
16,500.0	92.41	359.60	9,391.4	7,001.4	161.1	7,002.7	0.00	0.00	0.00
16,600.0	92.41	359.60	9,387.2	7,101.3	160.4	7,102.6	0.00	0.00	0.00
16,700.0	92.41	359.60	9,383.0	7,201.2	159.7	7,202.5	0.00	0.00	0.00
16,800.0	92.41	359.60	9,378.8	7,301.1	159.0	7,302.4	0.00	0.00	0.00
16,900.0	92.41	359.60	9,374.6	7,401.0	158.3	7,402.3	0.00	0.00	0.00
17,000.0	92.41	359.60	9,370.4	7,500.9	157.6	7,502.2	0.00	0.00	0.00
17,100.0	92.41	359.60	9,366.2	7,600.8	156.9	7,602.1	0.00	0.00	0.00
17,200.0	92.41	359.60	9,362.0	7,700.7	156.2	7,702.0	0.00	0.00	0.00
17,300.0	92.41	359.60	9,357.8	7,800.7	155.5	7,801.9	0.00	0.00	0.00
17,400.0	92.41	359.60	9,353.6	7,900.6	154.8	7,901.8	0.00	0.00	0.00
17,500.0	92.41	359.60	9,349.4	8,000.5	154.1	8,001.7	0.00	0.00	0.00
17,600.0	92.41	359.60	9,345.2	8,100.4	153.4	8,101.5	0.00	0.00	0.00
17,700.0	92.41	359.60	9,341.0	8,200.3	152.7	8,201.4	0.00	0.00	0.00
17,800.0	92.41	359.60	9,336.8	8,300.2	152.0	8,301.3	0.00	0.00	0.00
17,900.0	92.41	359.60	9,332.6	8,400.1	151.3	8,401.2	0.00	0.00	0.00
18,000.0	92.41	359.60	9,328.4	8,500.0	150.6	8,501.1	0.00	0.00	0.00
18,100.0	92.41	359.60	9,324.1	8,599.9	149.9	8,601.0	0.00	0.00	0.00
18,200.0	92.41	359.60	9,319.9	8,699.8	149.2	8,700.9	0.00	0.00	0.00
18,300.0	92.41	359.60	9,315.7	8,799.7	148.5	8,800.8	0.00	0.00	0.00
18,400.0	92.41	359.60	9,311.5	8,899.7	147.8	8,900.7	0.00	0.00	0.00
18,500.0	92.41	359.60	9,307.3	8,999.6	147.1	9,000.6	0.00	0.00	0.00
18,600.0	92.41	359.60	9,303.1	9,099.5	146.4	9,100.5	0.00	0.00	0.00
18,700.0	92.41	359.60	9,298.9	9,199.4	145.7	9,200.4	0.00	0.00	0.00
18,800.0	92.41	359.60	9,294.7	9,299.3	145.0	9,300.3	0.00	0.00	0.00
18,900.0	92.41	359.60	9,290.5	9,399.2	144.4	9,400.2	0.00	0.00	0.00
19,000.0	92.41	359.60	9,286.3	9,499.1	143.7	9,500.0	0.00	0.00	0.00
19,100.0	92.41	359.60	9,282.1	9,599.0	143.0	9,599.9	0.00	0.00	0.00
19,200.0	92.41	359.60	9,277.9	9,698.9	142.3	9,699.8	0.00	0.00	0.00
19,300.0	92.41	359.60	9,273.7	9,798.8	141.6	9,799.7	0.00	0.00	0.00
19,400.0	92.41	359.60	9,269.5	9,898.7	140.9	9,899.6	0.00	0.00	0.00
19,500.0	92.41	359.60	9,265.3	9,998.7	140.2	9,999.5	0.00	0.00	0.00
19,600.0	92.41	359.60	9,261.1	10,098.6	139.5	10,099.4	0.00	0.00	0.00
19,700.0	92.41	359.60	9,256.9	10,198.5	138.8	10,199.3	0.00	0.00	0.00
19,800.0	92.41	359.60	9,252.6	10,298.4	138.1	10,299.2	0.00	0.00	0.00
19,900.0	92.41	359.60	9,248.4	10,398.3	137.4	10,399.1	0.00	0.00	0.00
20,000.0	92.41	359.60	9,244.2	10,498.2	136.7	10,499.0	0.00	0.00	0.00
20,100.0	92.41	359.60	9,240.0	10,598.1	136.0	10,598.9	0.00	0.00	0.00

Planning Report

Database:	Hobbs	**Local Co-ordinate Reference:**	Site Stone Cold 23/14 B2PA Fed Com #1H
Company:	Mewbourne Oil Company	**TVD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Project:	Lea County, New Mexico NAD 83	**MD Reference:**	WELL @ 3874.0usft (Original Well Elev)
Site:	Stone Cold 23/14 B2PA Fed Com #1H	**North Reference:**	Grid
Well:	Sec 26, T18S, R33E	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	BHL: 100' FNL & 660' FEL (Sec 14)		
Design:	Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
20,200.0	92.41	359.60	9,235.8	10,698.0	135.3	10,698.8	0.00	0.00	0.00
20,300.0	92.41	359.60	9,231.6	10,797.9	134.6	10,798.7	0.00	0.00	0.00
20,362.2	92.41	359.60	9,229.0	10,860.1	134.1	10,860.8	0.00	0.00	0.00
BHL: 100' FNL & 660' FEL (Sec 14)									

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SHL: 400' FNL & 870' FE - plan hits target center - Point	0.00	0.00	0.0	0.1	0.2	628,138.30	758,261.20	32.7248073	-103.6279546
KOP: 473' FNL & 660' FI - plan hits target center - Point	0.00	0.00	9,091.0	-71.0	210.5	628,067.23	758,471.50	32.7246081	-103.6272724
BHL: 100' FNL & 660' FE - plan hits target center - Point	0.00	0.00	9,229.0	10,860.1	134.1	638,998.30	758,395.10	32.7546532	-103.6272839
PPP3: 1320' FSL & 660' - plan hits target center - Point	0.00	0.00	9,391.5	7,001.1	161.1	635,139.26	758,422.07	32.7440463	-103.6272798
PPP2: 1320' FSL & 660' - plan hits target center - Point	0.00	0.00	9,613.7	1,721.4	198.0	629,859.64	758,458.97	32.7295347	-103.6272743
FTP/LP: 100' FSL & 660 - plan hits target center - Point	0.00	0.00	9,664.5	501.9	206.5	628,640.11	758,467.49	32.7261827	-103.6272730


Stone Cold 23/14 B2PA Fed Com #1H
BHL: 100' FNL & 660' FEL (Sec 14)
Sec 14
PPP3: 1320' FSL & 660' FEL (Sec 14)
Hard Lines
PPP2: 1320' FSL & 660' FEL (Sec 23)
Sec 23
FTP/LP: 100' FSL & 660' FEL (Sec 23)
SHL: 400' FNL & 870' FEL (Sec 26)
KOP: 473' FNL & 660' FEL (Sec 26)
Sec 26
South(-)/North(+) (3500 usft/in)
West(-)/East(+) (3500 usft/in)


SHL: 400' FNL & 870' FEL (Sec 26)
KOP: 473' FNL & 660' FEL (Sec 26)
PPP2: 1320' FSL & 660' FEL (Sec 23)
PPP3: 1320' FSL & 660' FEL (Sec 14)
BHL: 100' FNL & 660' FEL (Sec 14)
FTP/LP: 100' FSL & 660' FEL (Sec 23)
True Vertical Depth (2500 usft/in)
Vertical Section at 0.71° (2500 usft/in)

Operator Name:	Property Name:	Well Number
Mewbourne Oil Company	Stone Cold 23/14 B2PA Fed Com	1H

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
B	26	18S	33E		473	FNL	660	FEL	LEA
Latitude				Longitude				NAD	
32.7246081				-103.6272724				83	

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
O	23	18S	33E		100	FSL	660	FEL	LEA
Latitude				Longitude				NAD	
32.7261827				-103.6272730				83	

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
B	14	18S	33E		100	FNL	660	FEL	LEA
Latitude				Longitude				NAD	
32.7546532				-103.6272839				83	

Is this well the defining well for the Horizontal Spacing Unit? Y

Is this well an infill well? N

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #

Operator Name:	Property Name:	Well Number

KZ 06/27/2018

PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	MEWBOURNE OIL COMPANY
WELL NAME & NO.:	STONE COLD 23/14 B2PA FED COM 1H
APD ID:	10400087674
LOCATION:	Section 26, T.18 S., R.33 E. NMP.
COUNTY:	Lea County, New Mexico

COA

H_2S	○ No		◉ Yes	
Potash / WIPP	◉ None	○ Secretary	○ R-111-Q	☐ Open Annulus ☐ WIPP
Cave / Karst	◉ Low	○ Medium	○ High	○ Critical
Wellhead	○ Conventional	◉ Multibowl	○ Both	○ Diverter
Cementing	☐ Primary Squeeze	☐ Cont. Squeeze	☐ EchoMeter	☑ DV Tool
Special Req	☐ Capitan Reef	☐ Water Disposal	☑ COM	☐ Unit
Waste Prev.	○ Self-Certification	○ Waste Min. Plan	◉ APD Submitted prior to 06/10/2024	
Additional Language	☑ Flex Hose ☐ Four-String	☐ Casing Clearance ☐ Offline Cementing	☐ Pilot Hole ☐ Fluid-Filled	☐ Break Testing

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H_2S) Drilling Plan shall be activated **AT SPUD**. As a result, the Hydrogen Sulfide area must meet **43 CFR 3176** requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING DESIGN

1. The **13-3/8** inch surface casing shall be set at approximately **1,670 ft.** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 ft. above the salt.**
   a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic-type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
   b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or **500 psi compressive strength**, whichever is greater. (This is to

include the lead cement)

c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 psi compressive strength, whichever is greater.
d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The **9-5/8** inch intermediate casing shall be set in a competent bed at approximately **3,100 ft.** The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:

- **Cement to surface.** If cement does not circulate see B.1.a, c-d above.

Note: Excess cement is below CFO's recommendation of %25. More cement might be needed.

3. Operator has proposed to set **7 inch** production casing at approximately **9,029 ft.** (9,026 ft. TVD). The minimum required fill of cement behind the **7 inch** production casing is:

Option 1 (Single Stage): Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification.

Option 2 (Two-Stage): Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
b. Second stage above DV tool: Cement should tie-back **at least 200 feet** into previous casing string. Operator shall provide method of verification. If cement does not circulate, contact the appropriate BLM office.

4. The minimum required fill of cement behind the **4-1/2 in.** production liner is:
   - Cement should tie-back **at least 100 feet** into previous casing string. Operator shall provide method of verification.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

2. Operator has proposed a multi-bowl wellhead assembly. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below

the surface casing shoe shall be **5000 (5M)** psi. BOP and BOPE shall be tested in accordance with title **43 CFR 3172**.

i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
iii. Manufacturer representative shall install the test plug for the initial BOP test.
iv. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
v. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172 must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

Contact Lea County Petroleum Engineering Inspection Staff:
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 689-5981.

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.

a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
b. When the operator proposes to set surface casing with Spudder Rig
   i. Notify the BLM when moving in and removing the Spudder Rig.
   ii. Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
   iii. BOP/BOPE test to be conducted per **43 CFR 3172** as soon as 2nd Rig is rigged up on well.

2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the doghouse or stairway area.
3. For intervals in which cement to surface is required, cement to surface should be verified with a visual check and density or pH check to differentiate cement from spacer and drilling mud. The results should be documented in the driller's log and daily reports.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until

both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-Q potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR 3172**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
   i. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
   ii. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
   iii. Manufacturer representative shall install the test plug for the initial BOP test.
   iv. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
   v. If the cement does not circulate and one-inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
   i. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
   ii. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be initiated after bumping the cement plug with the casing valve open. (Only applies to single stage cement jobs, prior to the cement setting up.)
   iii. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

iv. The test shall be run on a 5000-psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one-hour chart. A circular chart shall have a maximum 2-hour clock. If a twelve hour or twenty-four-hour chart is used, tester shall make a notation that it is run with a two hour clock.

v. The results of the test shall be reported to the appropriate BLM office.

vi. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.

vii. The BOP/BOPE test shall include a low-pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

viii. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

SA 02/12/2025

Hydrogen Sulfide Drilling Operations Plan
Mewbourne Oil Company

1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H2S were found. MOC will have on location and working all H2S safety equipment before the Delaware formation for purposes of safety and insurance requirements.

2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

1. The hazards and characteristics of hydrogen sulfide gas.
2. The proper use of personal protective equipment and life support systems.
3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

1 The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a know hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the 9 5/8" intermediate casing.

1. Well Control Equipment
   - A. Choke manifold with minimum of one adjustable choke/remote choke.
   - B. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
   - C. Auxiliary equipment including annular type blowout preventer.
2. Protective Equipment for Essential Personnel
   Thirty minute self contained work unit located in the dog house and at briefing areas.

Additionally: If H2S is encountered in concentrations less than 10 ppm, fans will be placed in work areas to prevent the accumulation of hazardous amounts of poisonous gas. If higher concentrations of H2S are detected the well will be shut in and a rotating head, mud/gas separator, remote choke and flare line with igniter will be installed.

3. Hydrogen Sulfide Protection and Monitoring Equipment
Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 PPM.

4. Visual Warning Systems
A. Wind direction indicators as indicated on the wellsite diagram.
B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

4. Mud Program

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

5. Metallurgy

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

6. Communications

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

7. Well Testing

Drill stem testing is not an anticipated requirement for evaluation of this well. If a drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.

8. Emergency Phone Numbers

Eddy County Sheriff's Office	**911 or 575-887-7551**
Ambulance Service	**911 or 575-885-2111**
Carlsbad Fire Dept	**911 or 575-885-2111**
Loco Hills Volunteer Fire Dept.	**911 or 575-677-3266**
Closest Medical Facility - Columbia Medical Center of Carlsbad	**575-492-5000**

Mewbourne Oil Company	**Hobbs District Office**	**575-393-5905**
	Fax	**575-397-6252**
	2nd Fax	**575-393-7259**
District Manager	**Robin Terrell**	**575-390-4816**
Drilling Superintendent	**Frosty Lathan**	**575-390-4103**
	Bradley Bishop	**575-390-6838**
Drilling Foreman	**Wesley Noseff**	**575-441-0729**

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Disposal location description: City of Carlsbad Water Treatment facility

Waste type: GARBAGE

Waste content description: Garbage & Trash

Amount of waste: 1500 pounds

Waste disposal frequency : One Time Only

Safe containment description: Enclosed trash trailer

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: Waste Management facility in Carlsbad.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit? NO

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? N

Description of cuttings location

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Operator Name: MEWBOURNE OIL COMPANY

Well Name: STONE COLD 23/14 B2PA FED COM **Well Number:** 1H

Section 8 - Ancillary

Are you requesting any Ancillary Facilities?: N

Ancillary Facilities

Comments:

Section 9 - Well Site

Well Site Layout Diagram:

Stone_Cold_23_14_B2PA_Fed_Com_1H_WellSiteLayout_20220824114125.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: Stone Cold 23/14 PA, OB

Multiple Well Pad Number: 2

Recontouring

Drainage/Erosion control construction: NONE

Drainage/Erosion control reclamation: NONE

Well pad proposed disturbance (acres): 5.9	**Well pad interim reclamation (acres):** 1.3	**Well pad long term disturbance (acres):** 4.6
Road proposed disturbance (acres): 0.41	**Road interim reclamation (acres):** 0	**Road long term disturbance (acres):** 0
Powerline proposed disturbance (acres): 0	**Powerline interim reclamation (acres):** 0	**Powerline long term disturbance (acres):** 0
Pipeline proposed disturbance (acres):	**Pipeline interim reclamation (acres):** 0	**Pipeline long term disturbance (acres):** 0
Other proposed disturbance (acres): 0	**Other interim reclamation (acres):** 0	**Other long term disturbance (acres):** 0
Total proposed disturbance: 6.3100000000000005	**Total interim reclamation:** 1.3	**Total long term disturbance:** 4.6

Disturbance Comments: In areas to be heavily disturbed, the top 6 inches of soil material, will be stripped and stockpiled on the perimeter of the well location to keep topsoil viable, and to make redistribution of topsoil more efficient during interim reclamation. Stockpiled topsoil should include vegetative material. Topsoil will be clearly segregated and stored separately from subsoils. Contaminated soil will not be stockpiled, but properly treated and handled prior to topsoil salvaging.

Reconstruction method: The areas planned for interim reclamation will then be recontoured to the original contour if feasible, or if not feasible, to an interim contour that blends with the surrounding topography as much as possible. Where applicable, the fill material of the well pad will be backfilled into the cut to bring the area back to the original contour. The interim cut and fill slopes prior to re-seeding will not be steeper than a 3:1 ration, unless the adjacent native topography is steeper. Note: Constructed slopes may be much steeper during drilling, but will be recontoured to the above ratios during interim reclamation.
Topsoil redistribution: Topsoil will be evenly respread and aggressively revegetated over the entire disturbed area not needed for all-weather operations including cuts & fills. To see the area, the proper BLM seed mixture, free of noxious weeks, will be used.

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
https://www.emnrd.nm.gov/ocd/contact-us

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Operator: MEWBOURNE OIL CO P.O. Box 5270 Hobbs, NM 88241	OGRID: 14744
	Action Number: 436127
	Action Type: [C-101] BLM - Federal/Indian Land Lease (Form 3160-3)

CONDITIONS

Created By	Condition	Condition Date
mleal	Cement is required to circulate on both surface and intermediate1 strings of casing.	2/27/2025
mleal	If cement does not circulate on any string, a Cement Bond Log (CBL) is required for that string of casing.	2/27/2025
matthew.gomez	A [C-103] Sub. Drilling (C-103N) is required within (10) days of spud.	4/9/2025
matthew.gomez	Notify the OCD 24 hours prior to casing & cement.	4/9/2025
matthew.gomez	Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string.	4/9/2025
matthew.gomez	Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.	4/9/2025
matthew.gomez	File As Drilled C-102 and a directional Survey with C-104 completion packet.	4/9/2025