

Well Name: GATO GRANDE 9-4 FED COM	Well Location: T23S / R32E / SEC 9 / SESE / 32.3125739 / -103.6746773	County or Parish/State: LEA / NM
Well Number: 733H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM98192	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002551329	Operator: DEVON ENERGY PRODUCTION COMPANY LP	

Notice of Intent

Sundry ID: 2840514

Type of Submission: Notice of Intent	Type of Action: APD Change
Date Sundry Submitted: 03/07/2025	Time Sundry Submitted: 06:58
Date proposed operation will begin: 03/07/2025	

Procedure Description: Devon Energy Production Co., L.P. (Devon) respectfully requests to move the SHL/BHL, a name change and depth and formation change on the subject well. Please see attached revised C102, Drill plan, directional plan. Permitted SHL: SESE 250 FSL, 1205 FEL, 9-23S-32E Proposed SHL: SESE, 206 FSL, 1092 FEL, 9-23S-32E Permitted BHL: LOT 2, 20 FNL, 1650 FEL, 4-23S-32E Proposed BHL: LOT 1, 20 FNL, 330 FEL, 4-23S-32E Permitted Well name: GATO GRANDE 9-4 FED COM 733H Proposed Well name: GATO GRANDE 9-4 FED COM 834H Permitted TVD/MD: 12295 / 22741 - [98248 WC-025 G-08 S243217P/UPR WOLFCAMP Proposed TVD/MD: 12744 / 23235 - [98393] WC-025 S233206C;LWR WOLFCAMP (GAS)

NOI Attachments

Procedure Description

- 5.5_20lb_P110HP_TALON_RD_20250307134353.pdf
- 7.625_29.7lb_P110_HP_Talon_SFC_20250307134324.pdf
- 9.625_40lb_J55_SeAH_20250307134252.pdf
- New_Site_Map_834H_GATO_GRANDE_9_WP_3_R2_20250307124143.pdf
- WA018132100_GATO_GRANDE_9_4_FED_COM_834H_R3_20250306170915.pdf
- GATO_GRANDE_9_4_FED_COM_834H_combined_20250306170913.pdf
- GATO_GRANDE_9_4_FED_COM_834H_Directional_Plan_03_05_25_20250306170913.pdf

Received by OCD: 4/17/2025 9:46:33 AM

Page 2 of 38

Well Name: GATO GRANDE 9-4 FED COM	Well Location: T23S / R32E / SEC 9 / SESE / 32.3125739 / -103.6746773	County or Parish/State: LEA / NM
Well Number: 733H	Type of Well: OIL WELL	Allottee or Tribe Name:
Lease Number: NMNM98192	Unit or CA Name:	Unit or CA Number:
US Well Number: 3002551329	Operator: DEVON ENERGY PRODUCTION COMPANY LP	

Conditions of Approval

Additional

9_23_32_P_Sundry_ID_2840514_Gato_Grande_9_4_Fed_Com_834H_Alt_20250321125435.pdf
9_23_32_P_Sundry_ID_2840514_Gato_Grande_9_4_Fed_Com_834H_20250321125435.pdf
Gato_Grande_9_4_Fed_Com_834H_Dr_COA_20250321125435.pdf

Operator

I certify that the foregoing is true and correct. Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction. Electronic submission of Sundry Notices through this system satisfies regulations requiring a

Operator Electronic Signature: LAUREN WATSON	Signed on: MAR 07, 2025 06:58 PM
Name: DEVON ENERGY PRODUCTION COMPANY LP	
Title: Regulatory Compliance Professional	
Street Address: 333 W. SHERIDAN AVE.	
City: OKLAHOMA CITY	State: OK
Phone: (405) 552-3379	
Email address: LAUREN.WATSON@DVN.COM	

Field

Representative Name:		
Street Address:		
City:	State:	Zip:
Phone:		
Email address:		

BLM Point of Contact

BLM POC Name: CHRISTOPHER WALLS	BLM POC Title: Petroleum Engineer
BLM POC Phone: 5752342234	BLM POC Email Address: cwalls@blm.gov
Disposition: Approved	Disposition Date: 04/16/2025
Signature: Chris Walls	

Form 3160-5 (June 2019)	UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT	FORM APPROVED OMB No. 1004-0137 Expires: October 31, 2021
SUNDRY NOTICES AND REPORTS ON WELLS <i>Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.</i>		5. Lease Serial No.
		6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2		7. If Unit of CA/Agreement, Name and/or No.
1. Type of Well <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		8. Well Name and No.
2. Name of Operator		9. API Well No.
3a. Address	3b. Phone No. (include area code)	10. Field and Pool or Exploratory Area
4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)		11. Country or Parish, State

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA				
TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be perfonned or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)		
	Title	
Signature	Date	

THE SPACE FOR FEDERAL OR STATE OFFICE USE		
Approved by	Title	Date
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.	Office	

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

GENERAL INSTRUCTIONS

This form is designed for submitting proposals to perform certain well operations and reports of such operations when completed as indicated on Federal and Indian lands pursuant to applicable Federal law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local area or regional procedures and practices, are either shown below, will be issued by or may be obtained from the local Federal office.

SPECIFIC INSTRUCTIONS

Item 4 - Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult the local Federal office for specific instructions.

Item 13: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by the local Federal office. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to the top of any tubing left in the hole; method of closing top of well and date well site conditioned for final inspection looking for approval of the abandonment. If the proposal will involve **hydraulic fracturing operations**, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The privacy Act of 1974 and the regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 351 et seq., 25 U.S.C. 396; 43 CFR 3160.

PRINCIPAL PURPOSE: The information is used to: (1) Evaluate, when appropriate, approve applications, and report completion of subsequent well operations, on a Federal or Indian lease; and (2) document for administrative use, information for the management, disposal and use of National Resource lands and resources, such as: (a) evaluating the equipment and procedures to be used during a proposed subsequent well operation and reviewing the completed well operations for compliance with the approved plan; (b) requesting and granting approval to perform those actions covered by 43 CFR 3162.3-2, 3162.3-3, and 3162.3-4; (c) reporting the beginning or resumption of production, as required by 43 CFR 3162.4-1(c) and (d) analyzing future applications to drill or modify operations in light of data obtained and methods used.

ROUTINE USES: Information from the record and/or the record will be transferred to appropriate Federal, State, local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecutions in connection with congressional inquiries or to consumer reporting agencies to facilitate collection of debts owed the Government.

EFFECT OF NOT PROVIDING THE INFORMATION: Filing of this notice and report and disclosure of the information is mandatory for those subsequent well operations specified in 43 CFR 3162.3-2, 3162.3-3, 3162.3-4.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to evaluate proposed and/or completed subsequent well operations on Federal or Indian oil and gas leases.

Response to this request is mandatory.

The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C St., N.W., Mail Stop 401 LS, Washington, D.C. 20240

Additional Information

Additional Remarks

Permitted TVD/MD: 12295 / 22741 - [98248 WC-025 G-08 S243217P/UPR WOLFCAMP

Proposed TVD/MD: 12744 / 23235 - [98393] WC-025 S233206C;LWR WOLFCAMP (GAS)

Location of Well

0. SHL: SESE / 250 FSL / 1115 FEL / TWSP: 23S / RANGE: 32E / SECTION: 9 / LAT: 32.3125739 / LONG: -103.6746773 (TVD: 0 feet, MD: 0 feet)

PPP: SWSE / 100 FSL / 1650 FEL / TWSP: 23S / RANGE: 32E / SECTION: 9 / LAT: 32.312156 / LONG: -103.6764081 (TVD: 12097 feet, MD: 12149 feet)

PPP: SWSE / 194 FSL / 1654 FEL / TWSP: 23S / RANGE: 32E / SECTION: 4 / LAT: 32.3268571 / LONG: -103.6765092 (TVD: 12385 feet, MD: 17700 feet)

BHL: LOT 2 / 20 FNL / 1650 FEL / TWSP: 23S / RANGE: 32E / SECTION: 4 / LAT: 32.340806 / LONG: -103.6764262 (TVD: 12295 feet, MD: 22741 feet)

CONFIDENTIAL

9-23-32-P Sundry ID 2840514 Gato Grande 9-4 Fed Com 834H-Alt

Gato Grande 9-4 Fed Com 834H

10 3/4		surface csg in a		14 3/4		inch hole.		Design Factors				Surface		
Segment	#/ft	Grade		Coupling		Body	Collapse	Burst	Length	B@s	a-B	a-C	Weight	
"A"	45.50	j 55		btc		12.47	3.55	0.53	1,261	6	0.89	6.70	57,376	
"B"				btc					0				0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 1,500							Tail Cmt	does not	cirtc to sfc.		Totals:	1,261	57,376	
Comparison of Proposed to Minimum Required Cement Volumes														
Hole	Annular	1 Stage		1 Stage		Min	1 Stage	Drilling	Calc			Min Dist		
Size	Volume	Cmt Sx		CuFt Cmt		Cu Ft	% Excess	Mud Wt	MASP	Req'd BOPE		Hole-Cplg		
14 3/4	0.5563	711		1024		702	46	9.00	4014	5M		1.50		
Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.														
Site plot (page racks S or E) as per O.G. L.H.D.A. not found.														

8 5/8		casing inside the		10 3/4		Design Factors			Int 1			
Segment	#/ft	Grade		Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight
"A"	32.00		p 110	vam sprint fj	1.89	0.59	1.03	12,333	1	1.72	1.00	394,656
"B"								0				0
w/8.4#/g mud, 30min Sfc Csg Test psig:								Totals:	12,333			394,656
The cement volume(s) are intended to achieve a top of								0	ft from surface or a		1261	overlap.
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE				Min Dist Hole-Cplg
9 7/8	0.1261	619	891	1566	-43	10.50	4148	5M				0.61
D V Tool(s):												Σ%excess
by stage % :												29
Class 'C' tail cmt yld > 1.35												

Tail cmt												
5 1/2		casing inside the		8 5/8		Design Factors				Prod 1		
Segment	#/ft	Grade		Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight
"A"	20.00		p 110	dwc/c is+	2.86	1.74	2.07	23,235	2	3.46	2.91	464,700
								0			0	
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,804								Totals:	23,235			464,700
The cement volume(s) are intended to achieve a top of 1213 ft from surface or a 200 overlap.												
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE			Min Dist Hole-Cplg	
7 7/8	0.1733	1547	2442	1924	27	10.50					0.79	
Class 'C' tail cmt yld > 1.35												

#N/A											
0	5 1/2			Design Factors				<Choose Casing>			
Segment	#/ft	Grade	Coupling	#N/A	Collapse	Burst	Length	B@s	a-B	a-C	Weight
"A"			0.00				0				0
"B"			0.00				0				0
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	0			0
Cmt vol calc below includes this csg, TOC intended							#N/A	ft from surface or a	#N/A		overlap.
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE			Min Dist Hole-Cplg
0		#N/A	#N/A	0	#N/A						
#N/A											
Capitan Reef est top XXXX.											

9-23-32-P Sundry ID 2840514 Gato Grande 9-4 Fed Com 834H

Gato Grande 9-4 Fed Com 834H

9 5/8		surface csg in a		13 1/2	inch hole.		Design Factors				Surface		
Segment	#/ft	Grade			Coupling	Body	Collapse	Burst	Length	B@s	a-B	a-C	Weight
"A"	40.00			j 55	btc	12.49	4.36	0.59	1,261	7	0.98	8.23	50,440
"B"					btc				0				0
w/8.4#/g mud, 30min Sfc Csg Test psig: 1,500					Tail Cmt	does not	circ to sfc.		Totals:	1,261	50,440		
Comparison of Proposed to Minimum Required Cement Volumes													
Hole	Annular	1 Stage	1 Stage	Min	1 Stage	Drilling	Calc	Req'd	Min Dist				
Size	Volume	Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE	Hole-Cplg				
13 1/2	0.4887	622	896	616	45	9.00	4014	5M	1.44				
Burst Frac Gradient(s) for Segment(s) A, B = , b All > 0.70, OK.													
Site plot (pipe racks S or E) as per O.G. L.H.D. A.C. not found.													

7 5/8		casing inside the		9 5/8		Design Factors					Int 1						
Segment	#/ft	Grade			Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight				
"A"	29.70			p 110	talon sfc	2.50	1.08	1.55	12,333	2	2.59	1.81	366,290				
"B"													0				
w/8.4#/g mud, 30min Sfc Csg Test psig:									Totals:	12,333				366,290			
The cement volume(s) are intended to achieve a top of														0	ft from surface or a		overlap.
Hole	Annular	1 Stage		1 Stage	Min	1 Stage	Drilling	Calc	Req'd		Min Dist						
Size	Volume	Cmt Sx		CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	BOPE		Hole-Cplg						
8 3/4	0.1005	493		710	1249	-43	10.50	4148	5M		0.43						
D V Tool(s):									sum of sx		Σ CuFt		Σ% excess				
by stage % :											1595		28				
Class 'C' tail cmt yld > 1.35																	

Tail cmt		casing inside the		7 5/8	Design Factors					Prod 1			
5 1/2	Segment	#/ft	Grade		Coupling	Joint	Collapse	Burst	Length	B@s	a-B	a-C	Weight
	"A"	20.00		p 110	talon rd	2.86	1.89	2.07	23,235	2	3.46	3.17	464,700
	"B"								0				0
w/8.4#/g mud, 30min Sfc Csg Test psig: 2,804									Totals:	23,235			464,700
The cement volume(s) are intended to achieve a top of 12133 ft from surface or a 200 overlap.													
Hole	Annular		1 Stage	1 Stage	Min	1 Stage	Drilling	Calc					Min Dist
Size	Volume		Cmt Sx	CuFt Cmt	Cu Ft	% Excess	Mud Wt	MASP	Req'd				Hole-Cplg
6 3/4	0.0835		751	1195	928	29	10.50		BOPE				0.43
Class 'C' tail cmt yld > 1.35													

#N/A													
0	5 1/2												
Design Factors													
<Choose Casing>													
Segment	#/ft	Grade	Coupling	#N/A	Collapse	Burst	Length	B@s	a-B	a-C	Weight		
"A"			0.00				0				0		
"B"			0.00				0				0		
w/8.4#/g mud, 30min Sfc Csg Test psig:							Totals:	0	0				
Cmt vol calc below includes this csg, TOC intended							#N/A	ft from surface or a	#N/A	overlap.			
Hole Size	Annular Volume	1 Stage Cmt Sx	1 Stage CuFt Cmt	Min Cu Ft	1 Stage % Excess	Drilling Mud Wt	Calc MASP	Req'd BOPE				Min Dist Hole-Cplg	
0		#N/A	#N/A	0	#N/A								
#N/A													
Capitan Reef est top XXXX.													

**PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Devon Energy Production Company LP
LOCATION:	Section 9, T.23 S., R.32 E., NMPM
COUNTY:	Lea County, New Mexico

WELL NAME & NO.:	Gato Grande 9-4 Fed Com 834H
ATS/API ID:	3002551329
APD ID:	10400081231
Sundry ID:	2840514

COA

Primary Design:

H2S	Yes ▼		
Potash	None ▼	None ▼	
Cave/Karst Potential	Low ▼		
Cave/Karst Potential	<input type="checkbox"/> Critical		
Variance	<input checked="" type="checkbox"/> None	<input checked="" type="checkbox"/> Flex Hose	<input checked="" type="checkbox"/> Other
Wellhead	Conventional and Multibowl ▼		
Other	<input type="checkbox"/> 4 String <input type="checkbox"/> 5 String	Capitan Reef None ▼	<input type="checkbox"/> WIPP
Other	Pilot Hole None ▼	<input type="checkbox"/> Open Annulus	
Cementing	Contingency Squeeze None ▼	Echo-Meter Int 1 ▼	Primary Cement Squeeze None ▼
Special Requirements	<input type="checkbox"/> Water Disposal/Injection	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit
Special Requirements	<input type="checkbox"/> Batch Sundry	Waste Prevention None ▼	
Special Requirements Variance	<input type="checkbox"/> BOPE Break Testing <input type="checkbox"/> Offline BOPE Testing	<input type="checkbox"/> Offline Cementing	<input type="checkbox"/> Casing Clearance

Alternate Design:

Potash	None ▼	None ▼	
Cave/Karst Potential	Low ▼		
Cave/Karst Potential	<input type="checkbox"/> Critical		
Other	<input type="checkbox"/> 4 String <input type="checkbox"/> 5 String	Capitan Reef None ▼	<input type="checkbox"/> WIPP
Other	Pilot Hole None ▼	<input type="checkbox"/> Open Annulus	
Cementing	Contingency Squeeze None ▼	Echo-Meter Int 1 ▼	Primary Cement Squeeze None ▼

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the **Delaware** formation. As a result, the Hydrogen Sulfide area must meet **43 CFR part 3170 Subpart 3176** requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

Primary Design

B. CASING

1. The **9-5/8** inch surface casing shall be set at approximately **1261 feet** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt when present, and below usable fresh water) and cemented to the surface. The surface hole shall be **13 1/2** inch in diameter.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **7-5/8** inch intermediate casing is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

Option 2:

Operator has proposed to cement in two stages by conventionally cementing the first stage and performing a bradenhead squeeze on the second stage, contingent upon no returns to surface.

- a. First stage: Operator will cement with intent to reach the top of the **Brushy Canyon at 6915'**.
- b. Second stage:
 - Operator will perform bradenhead squeeze and top-out. Cement to surface. If cement does not reach surface, the appropriate BLM office shall be notified. (**Squeeze 385 sxs Class C**)

Operator has proposed to pump down **9-5/8" X 7-5/8"** annulus after primary cementing stage. Operator must run Echo-meter to verify Cement Slurry/Fluid top in the annulus Or operator shall run a CBL from TD of the 7-5/8" casing to surface after the second stage BH to verify TOC.

Submit results to the BLM. No displacement fluid/wash out shall be utilized at the top of the cement slurry between second stage BH and top out. Operator must run one CBL per Well Pad. Operator may conduct a negative and positive pressure test during completion to remediate sustained casing pressure.

If cement does not reach surface, the next casing string must come to surface.

Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
 - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

Alternate Design

C. CASING

4. The **10-3/4** inch surface casing shall be set at approximately **1261 feet** (a minimum of **25 feet (Lea County)** into the Rustler Anhydrite and above the salt when present, and below usable fresh water) and cemented to the surface. The surface hole shall be **14 3/4** inch in diameter.
 - e. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - f. Wait on cement (WOC) time for a primary cement job will be a minimum of **8 hours** or 500 pounds compressive strength, whichever is greater. (This is to

- include the lead cement)
- g. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - h. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

5. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above.

Option 2:

Operator has proposed to cement in two stages by conventionally cementing the first stage and performing a bradenhead squeeze on the second stage, contingent upon no returns to surface.

- c. First stage: Operator will cement with intent to reach the top of the **Brushy Canyon at 6915'**.
- d. Second stage:
 - Operator will perform bradenhead squeeze and top-out. Cement to surface. If cement does not reach surface, the appropriate BLM office shall be notified. **(Squeeze 488 sxs Class C)**

Operator has proposed to pump down **10-3/4" X 8-5/8"** annulus after primary cementing stage. Operator must run Echo-meter to verify Cement Slurry/Fluid top in the annulus Or operator shall run a CBL from TD of the 8-5/8" casing to surface after the second stage BH to verify TOC.

Submit results to the BLM. No displacement fluid/wash out shall be utilized at the top of the cement slurry between second stage BH and top out. Operator must run one CBL per Well Pad. Operator may conduct a negative and positive pressure test during completion to remediate sustained casing pressure.

If cement does not reach surface, the next casing string must come to surface.

Operator must use a limited flush fluid volume of 1 bbl following backside cementing procedures.

6. The minimum required fill of cement behind the **5-1/2** inch production casing is:

- Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

D. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2.

Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Annular which shall be tested to 5000 (5M) psi.**
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **10,000 (10M) psi. Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**

Option 2:

Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **10,000 (10M) psi. Variance is approved to use a 5000 (5M) Annular which shall be tested to 5000 (5M) psi.**

- a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
- b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- c. Manufacturer representative shall install the test plug for the initial BOP test.
- d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
- e. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.

E. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- The operator will submit an as-drilled survey well plat of the well completion, but are not limited to, those specified in **43 CFR part 3170 Subpart 3171**
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240,
(575) 689-5981

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per **43 CFR part 3170 Subpart 3172** as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends of both lead and tail cement, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in **43 CFR part 3170 Subpart 3172 and API STD 53 Sec. 5.3**.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke

manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in 43 CFR 3172.6(b)(9) must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead cement), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the cement plug. The BOPE test can be

initiated after bumping the cement plug with the casing valve open. (only applies to single stage cement jobs, prior to the cement setting up.)

- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer and can be initiated immediately with the casing valve open. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to **43 CFR part 3170 Subpart 3172** with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for 8 hours or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per **43 CFR part 3170 Subpart 3172**.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and

disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.


Long Vo (LVO) 3/21/2025



U. S. Steel Tubular Products

5.500" 20.00lb/ft (0.361" Wall) P110 HP USS-TALON HTQ™ RD

2/21/2024 7:48:59 AM

				
MECHANICAL PROPERTIES	Pipe	USS-TALON HTQ™ RD		[6]
Minimum Yield Strength	125,000	--	psi	--
Maximum Yield Strength	140,000	--	psi	--
Minimum Tensile Strength	130,000	--	psi	--
DIMENSIONS	Pipe	USS-TALON HTQ™ RD		--
Outside Diameter	5.500	5.900	in.	--
Wall Thickness	0.361	--	in.	--
Inside Diameter	4.778	4.778	in.	--
Standard Drift	4.653	4.653	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	20.00	--	lb/ft	--
Plain End Weight	19.83	--	lb/ft	--
SECTION AREA	Pipe	USS-TALON HTQ™ RD		--
Critical Area	5.828	5.828	sq. in.	--
Joint Efficiency	--	100.0	%	[2]
PERFORMANCE	Pipe	USS-TALON HTQ™ RD		--
Minimum Collapse Pressure	13,150	13,150	psi	--
Minimum Internal Yield Pressure	14,360	14,360	psi	--
Minimum Pipe Body Yield Strength	729,000	--	lb	--
Joint Strength	--	729,000	lb	--
Compression Rating	--	729,000	lb	--
Reference Length	--	24,300	ft	[5]
Maximum Uniaxial Bend Rating	--	104.2	deg/100 ft	[3]
MAKE-UP DATA	Pipe	USS-TALON HTQ™ RD		--
Make-Up Loss	--	5.58	in.	--
Minimum Make-Up Torque	--	18,400	ft-lb	[4]
Maximum Make-Up Torque	--	21,400	ft-lb	[4]
Maximum Operating Torque	--	44,400	ft-lb	[4]

UNCONTROLLED

Notes

1. Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
2. Joint efficiencies are calculated by dividing the connection critical area by the pipe body area.
3. Uniaxial bend rating shown is structural only.
4. Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
5. Reference length is calculated by Joint Strength divided by Nominal Linear Weight, T&C with a 1.5 Safety factor.
6. Coupling must meet minimum mechanical properties of the pipe.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.



U. S. Steel Tubular Products

7.625" 29.70lb/ft (0.375" Wall) P110 HP USS-TALON SFC™

5/15/2024 6:31:14 PM



MECHANICAL PROPERTIES	Pipe	USS-TALON SFC™		[6]
Minimum Yield Strength	125,000	--	psi	--
Maximum Yield Strength	140,000	--	psi	--
Minimum Tensile Strength	130,000	--	psi	--
DIMENSIONS	Pipe	USS-TALON SFC™		--
Outside Diameter	7.625	7.900	in.	--
Wall Thickness	0.375	--	in.	--
Inside Diameter	6.875	6.815	in.	--
Standard Drift	6.750	6.750	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	29.70	--	lb/ft	--
Plain End Weight	29.06	--	lb/ft	--
SECTION AREA	Pipe	USS-TALON SFC™		--
Critical Area	8.541	7.331	sq. in.	--
Joint Efficiency	--	85.8	%	[2]
PERFORMANCE	Pipe	USS-TALON SFC™		--
Minimum Collapse Pressure	7,260	7,260	psi	--
Minimum Internal Yield Pressure	10,750	10,750	psi	--
Minimum Pipe Body Yield Strength	1,068,000	--	lb	--
Joint Strength	--	916,000	lb	--
Compression Rating	--	916,000	lb	--
Reference Length	--	20,560	ft	[5]
Maximum Uniaxial Bend Rating	--	64.4	deg/100 ft	[3]
MAKE-UP DATA	Pipe	USS-TALON SFC™		--
Make-Up Loss	--	5.08	in.	--
Minimum Make-Up Torque	--	30,000	ft-lb	[4]
Maximum Make-Up Torque	--	33,000	ft-lb	[4]
Maximum Operating Torque	--	80,500	ft-lb	[4]

UNCONTROLLED

Notes

1. Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
2. Joint efficiencies are calculated by dividing the connection critical area by the pipe body area.
3. Uniaxial bend rating shown is structural only.
4. Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
5. Reference length is calculated by Joint Strength divided by Nominal Linear Weight, T&C with a 1.5 Safety factor.
6. Coupling must meet minimum mechanical properties of the pipe.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com



9.625" 40# .395" J-55

Dimensions (Nominal)

Outside Diameter	9.625	in.
Wall	0.395	in.
Inside Diameter	8.835	in.
Drift	8.750	in.
Weight, T&C	40.000	lbs./ft.
Weight, PE	38.970	lbs./ft.

Performance Properties

Collapse, PE	2570	psi
Internal Yield Pressure at Minimum Yield		
PE	3950	psi
LTC	3950	psi
BTC	3950	psi
Yield Strength, Pipe Body	630	1000 lbs.
Joint Strength		
STC	452	1000 lbs.
LTC	520	1000 lbs.
BTC	714	1000 lbs.

Note: SeAH Steel has produced this specification sheet for general information only. SeAH does not assume liability or responsibility for any loss or injury resulting from the use of information or data contained herein. All applications for the material described are at the customer's own risk and responsibility.



PROPOSED SURFACE SITE EXHIBIT

GATO GRANDE 9 WP3 R2


UCID# AA000487611

SECTION 9, TOWNSHIP 23 SOUTH, RANGE 32 EAST


NEW MEXICO PRINCIPAL MERIDIAN

LEA COUNTY, NEW MEXICO

SECTION 9
TOWNSHIP 23 SOUTH
RANGE 32 EAST
NEW MEXICO PRINCIPAL MERIDIAN
LEA COUNTY, NEW MEXICO



SECTION 9
SECTION 16



LEGEND

- SECTION LINES
- x-x-x- EXISTING FENCE
- OHE-OHE- EXISTING ELECTRIC
- - - - - FOREIGN PIPELINE
- - - - - PROPOSED SURFACE SITE
- - - - - 100' OFFSET BOUNDARY
- ⊕ PROPOSED SURFACE HOLE
- FOUND MONUMENT
- CALCULATED CORNER

TOTAL SURFACE SITE ACREAGE BREAKDOWN BY
SECTION 1/4 1/4

1/4 1/4	OWNERSHIP	SQ. FEET	ACRES
SW-SE	BLM	180,518	4.14
SE-SE	BLM	194,482	4.46
TOTAL		375,000	8.61

A	GATO GRANDE 9 4 FED COM 832H
B	GATO GRANDE 9 4 FED COM 835H
C	GATO GRANDE 9 4 FED COM 833H
D	GATO GRANDE 9 4 FED COM 614H
E	GATO GRANDE 9 4 FED COM 814H
F	GATO GRANDE 9 4 FED COM 714H
G	GATO GRANDE 9 4 FED COM 834H

I, Nicholas Cole Phipps, New Mexico Professional Surveyor No. 29796, do hereby certify that this Easement Survey Plat and the actual survey on the ground upon which it is based were performed by me or under my direct supervision, that I am responsible for this survey; that this survey meets the Minimum Standards for Surveying in New Mexico; and that it is true and correct to the best of my knowledge and belief. I further certify that this survey is not a land division or subdivision as defined in the New Mexico Subdivision Act and that this instrument is an Easement Survey Plat of an existing tract or tracts.

NOTES:

- 1.) BEARINGS AND COORDINATES ARE GRID AS DERIVED FROM GPS OBSERVATION AND ARE BASED ON THE STATE PLANE COORDINATES FOR THE NEW MEXICO EAST ZONE 3001-NAD83.
- 2.) CERTIFICATION IS MADE ONLY TO THE LOCATION OF THIS EASEMENT. IN RELATION TO THE EVIDENCE DURING A FIELD SURVEY, MADE ON THE GROUND, UNDER MY SUPERVISION, AND USING DOCUMENTATION PROVIDED BY THE CLIENT. ONLY UTILITIES/EASEMENTS THAT WERE VISIBLE ON THE DATE OF THIS SURVEY, WITHIN/ADJOINING THIS EASEMENT, HAVE BEEN LOCATED AS SHOWN HEREON OF WHICH I HAVE KNOWLEDGE. THIS CERTIFICATION IS LIMITED TO THOSE PERSONS OR ENTITIES KNOWN ON THE FACE OF THIS PLAT AND IS NON-TRANSFERABLE, AND MADE FOR THIS TRANSACTION ONLY.

Nicholas Cole Phipps PS NO. 29796 Date **2-24-25**
DWG: AA000487611_GATO_GRANDE_9_WP_3_R2

DRAWING PATH: D:\Coosa Consulting Dropbox\Coosa Consulting\Clients - Projects\Devon Energy\24-122788_Gato Grande 9 4 Unit\Drafting\EXHIBITS\Surface Sites

Drawn: JMJ

Date: 02/24/2025

Job: 24-122788

Scale: 1=200'

Checked: NCP

Date: 02/24/2025

REVISION NO. 2

SHEET 1 OF 2



PO BOX 1583, MIDLAND, TEXAS 79701

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	<input checked="" type="checkbox"/> Initial Submittal
			<input type="checkbox"/> Amended Report
			<input type="checkbox"/> As Drilled

WELL LOCATION INFORMATION

API Number 30-025-51329	Pool Code 98393	Pool Name WC-025 S233206C;LWR WOLFCAMP (GAS)
Property Code	Property Name GATO GRANDE 9 4 FED COM	Well Number 834H
OGRID No. 6137	Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	Ground Level Elevation 3,684.19'
Surface Owner: <input type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal		Mineral Owner: <input checked="" type="checkbox"/> State <input type="checkbox"/> Fee <input type="checkbox"/> Tribal <input checked="" type="checkbox"/> Federal

Surface Location

UL P	Section 9	Township 23S	Range 32E	Lot	Ft. from N/S 206' FSL	Ft. from E/W 1,092' FEL	Latitude 32.312455°	Longitude -103.674602°	County LEA
----------------	---------------------	------------------------	---------------------	-----	---------------------------------	-----------------------------------	-------------------------------	----------------------------------	----------------------

Bottom Hole Location

UL LOT 1	Section 4	Township 23S	Range 32E	Lot	Ft. from N/S 20' FNL	Ft. from E/W 330' FEL	Latitude 32.340820°	Longitude -103.672154°	County LEA
--------------------	---------------------	------------------------	---------------------	-----	--------------------------------	---------------------------------	-------------------------------	----------------------------------	----------------------

Dedicated Acres 638.93	Infill or Defining Well Defining	Defining Well API	Overlapping Spacing Unit (Y/N)	Consolidation Code
Order Numbers.			Well setbacks are under Common Ownership: <input type="checkbox"/> Yes <input type="checkbox"/> No	

Kick Off Point (KOP)

UL P	Section 9	Township 23S	Range 32E	Lot	Ft. from N/S 50' FSL	Ft. from E/W 330' FEL	Latitude 32.312033°	Longitude -103.672136°	County LEA
----------------	---------------------	------------------------	---------------------	-----	--------------------------------	---------------------------------	-------------------------------	----------------------------------	----------------------




First Take Point (FTP)

UL P	Section 9	Township 23S	Range 32E	Lot	Ft. from N/S 100' FSL	Ft. from E/W 330' FEL	Latitude 32.312170°	Longitude -103.672136°	County LEA
----------------	---------------------	------------------------	---------------------	-----	---------------------------------	---------------------------------	-------------------------------	----------------------------------	----------------------

Last Take Point (LTP)

UL LOT 1	Section 4	Township 23S	Range 32E	Lot	Ft. from N/S 100' FNL	Ft. from E/W 330' FEL	Latitude 32.340600°	Longitude -103.672154°	County LEA
--------------------	---------------------	------------------------	---------------------	-----	---------------------------------	---------------------------------	-------------------------------	----------------------------------	----------------------

Unitized Area or Area of Uniform Interest	Spacing Unit Type <input checked="" type="checkbox"/> Horizontal <input type="checkbox"/> Vertical	Ground Floor Elevation:
---	--	-------------------------

OPERATOR CERTIFICATIONS I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. If this well is a horizontal well, I further certify that this organization has received the consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.  Signature Lauren Watson Printed Name Lauren.Watson@dvN.com Email Address 3/6/2025 Date		SURVEYOR CERTIFICATIONS I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.  NICHOLAS COLE PHIPPS PS 29796 COOSA CONSULTING CORPORATION PO BOX 1583, MIDLAND, TEXAS 79701 Signature and Seal of Professional Surveyor  Certificate Number 29796 Date of Survey 2/7/2025	
--	--	--	--


Note: No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

ACREAGE DEDICATION PLATS

This grid represents a standard section. You may superimpose a non-standard section, or larger area, over this grid. Operators must outline the dedicated acreage in a red box, clearly show the well surface location and bottom hole location, if it is directionally drilled, with the dimensions from the section lines in the cardinal directions. If this is a horizontal wellbore show on this plat the location of the First Take Point and Last Take Point, and the point within the Completed interval (other than the First Take Point or Last Take Point) that is closest to any outer boundary of the tract.

Surveyors shall use the latest United States government survey or dependent resurvey. Well locations will be in reference to the New Mexico Principal Meridian. If the land is not surveyed, contact the OCD Engineering Bureau. Independent subdivision surveys will not be acceptable.

GATO GRANDE 9 4 FED COM 834H



SURFACE HOLE LOCATION
206' FSL & 1,092' FEL
ELEV. = 3,684.19'

NAD 83 X = 744,842.85'
NAD 83 Y = 478,028.69'
NAD 83 LAT = 32.312455°
NAD 83 LONG = -103.674602°

KICK-OFF POINT
50' FSL & 330' FEL

NAD 83 X = 745,605.61'
NAD 83 Y = 477,879.88'
NAD 83 LAT = 32.312033°
NAD 83 LONG = -103.672136°

FIRST TAKE POINT &
PENETRATION POINT 1
100' FSL & 330' FEL

NAD 83 X = 745,605.25'
NAD 83 Y = 477,929.88'
NAD 83 LAT = 32.312170°
NAD 83 LONG = -103.672136°

PENETRATION POINT 2
0' FSL & 330' FEL

NAD 83 X = 745,567.60'
NAD 83 Y = 483,111.36'
NAD 83 LAT = 32.326413°
NAD 83 LONG = -103.672154°

PENETRATION POINT 3
2,623' FNL & 330' FEL

NAD 83 X = 745,551.35'
NAD 83 Y = 485,749.52'
NAD 83 LAT = 32.333665°
NAD 83 LONG = -103.672154°

PENETRATION POINT 4
1,303' FNL & 330' FEL

NAD 83 X = 745,543.22'
NAD 83 Y = 487,069.94'
NAD 83 LAT = 32.337294°
NAD 83 LONG = -103.672154°

LAST TAKE POINT
100' FNL & 330' FEL

NAD 83 X = 745,535.81'
NAD 83 Y = 488,272.59'
NAD 83 LAT = 32.340600°
NAD 83 LONG = -103.672154°

BOTTOM HOLE LOCATION
20' FNL & 330' FEL

NAD 83 X = 745,535.28'
NAD 83 Y = 488,352.58'
NAD 83 LAT = 32.340820°
NAD 83 LONG = -103.672154°

CORNER COORDINATES NEW MEXICO EAST - NAD 83	
A	IRON PIPE W/BRASS CAP N:488,323.10' E:740,583.37'
B	CALCULATED CORNER N:488,349.49' E:743,224.26'
C	IRON PIPE W/BRASS CAP N:488,375.88' E:745,865.14'
D	IRON PIPE W/BRASS CAP N:485,753.66' E:745,881.34'
E	CALCULATED CORNER N:483,114.70' E:745,897.59'
F	IRON PIPE W/BRASS CAP N:480,473.91' E:745,917.15'
G	IRON PIPE W/BRASS CAP N:477,833.17' E:745,935.94'
H	IRON PIPE W/BRASS CAP N:477,806.86' E:743,296.26'
I	IRON PIPE W/BRASS CAP N:477,780.24' E:740,653.25'
J	IRON PIPE W/BRASS CAP N:480,419.18' E:740,635.92'
K	IRON PIPE W/BRASS CAP N:483,060.19' E:740,618.94'
L	IRON PIPE W/BRASS CAP N:485,687.56' E:740,606.09'
M	IRON PIPE W/BRASS CAP N:483,088.03' E:743,258.71'



2-7-25

GATO GRANDE 9-4 FED COM 834H

1. Geologic Formations

TVD of target	12746	Pilot hole depth	N/A
MD at TD:	23235	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	1160		
Salt	1454		
Base of Salt	4564		
Delaware	4819		
Cherry Canyon	5966		
Brushy Canyon	6915		
1st Bone Spring Lime	8640		
Bone Spring 1st	9780		
Bone Spring 2nd	10408		
3rd Bone Spring Lime	10946		
Bone Spring 3rd	11550		
Wolfcamp	11945		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

GATO GRANDE 9-4 FED COM 834H

2. Casing Program (Primary Design)

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
13 1/2	9 5/8	40	J-55	BTC	0	1185	0	1185
8 3/4	7 5/8	29.7	P110HP	TALON SFC	0	12333	0	12333
6 3/4	5 1/2	20	P110HP	TALON RD	0	23235	0	12746

•All casing strings will be tested in accordance with 43 CFR 3172.

3. Cementing Program (Primary Design)

Assuming no returns are established while drilling, Devon requests to pump a two stage cement job on the intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brushy Canyon and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. The final cement top will be verified by Echo-meter. Devon will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program. Devon will report to the BLM the volume of fluid (limited to 1 bbls) used to flush intermediate casing valves following backside cementing procedures

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	622	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	385	Surf	13.0	2.3	2nd State: Bradenhead Squeeze - Lead: Class C Cement + additives
	493	6980	13.2	1.44	Tail: Class H / C + additives
Production	62	10433	9	3.27	Lead: Class H / C + additives
	689	12433	13.2	1.44	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Prod	10%

GATO GRANDE 9-4 FED COM 834H

2. Casing Program (Secondary Design)

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
14 3/4	10 3/4	45 1/2	J-55	BTC	0	1185	0	1185
9 7/8	8 5/8	32	P110	Sprint FJ	0	12333	0	12333
7 7/8	5 1/2	20	P110	DWC / C-IS+	0	23235	0	12746

•All casing strings will be tested in accordance with 43 CFR 3172. Must have table for contingency casing.

3. Cementing Program (Secondary Design)

Assuming no returns are established while drilling, Devon requests to pump a two stage cement job on the intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brushy Canyon and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. The final cement top will be verified by Echo-meter. Devon will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program. Devon will report to the BLM the volume of fluid (limited to 1 bbls) used to flush intermediate casing valves following backside cementing procedures.

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	711	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	488	Surf	13.0	2.3	2nd State: Bradenhead Squeeze - Lead: Class C Cement + additives
	619	6980	13.2	1.44	Tail: Class H / C + additives
Production	117	10433	9	3.27	Lead: Class H / C + additives
	1430	12433	13.2	1.44	Tail: Class H / C + additives

Devon Energy requests to offline cement on intermediate strings that are set in formations shallower than the Wolfcamp. Prior to commencing offline cementing operations, the well will be monitored for any abnormal pressures and confirmed to be static. A dual manifold system (equipped with chokes) for the returns will also be utilized as a redundancy. All equipment used for offline cementing will have a minimum 5M rating to match intermediate sections' 5M BOPE requirements.

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Prod	10%

GATO GRANDE 9-4 FED COM 834H

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?		Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular		X	50% of rated working pressure
			Blind Ram		X	5M
			Pipe Ram			
			Double Ram		X	
			Other*			
Production	13-5/8"	10M	Annular (5M)		X	100% of rated working pressure
			Blind Ram		X	10M
			Pipe Ram			
			Double Ram		X	
			Other*			
			Annular (5M)			
			Blind Ram			
			Pipe Ram			
			Double Ram			
			Other*			
N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
Y	A variance is requested to run a 5 M annular on a 10M system					

GATO GRANDE 9-4 FED COM 834H

5. Mud Program

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	10-10.5

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH pressure at deepest TVD	6959
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H ₂ S) monitors will be installed prior to drilling out the surface shoe. If H ₂ S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of 43 CFR 3176. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.	
N	H ₂ S is present
Y	H ₂ S plan attached.

GATO GRANDE 9-4 FED COM 834H

8. Other facets of operation

Is this a walking operation? Potentially

- 1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
- 2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
- 3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.


NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially


- 1 Spudder rig will move in and batch drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
- 2 After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (43 CFR 3172, all COAs and NMOCD regulations).
- 3 The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
- 4 A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
- 5 Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
- 6 The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 7 Drilling operations will be performed with drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan
 Other, describe



MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
2000.00	0.00	101.05	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2500.00	10.00	101.05	2497.47	-8.34	42.72	-5.46	2.00	Hold Tangent
6475.00	10.00	101.05	6412.07	-140.64	720.17	-92.13	0.00	Drop to Vertical
6975.00	0.00	101.05	6909.54	-148.98	762.89	-97.59	2.00	Hold Vertical
12432.61	0.00	359.61	12367.15	-148.98	762.89	-97.59	0.00	KOP
13343.97	91.14	359.61	12940.00	435.32	758.95	1085.13	10.00	Landing Point
23234.71	91.14	359.61	12744.00	10323.89	692.43	10347.09	0.00	BHL



Key Depths	MD (ft)	TVD (ft)
Rustler	1160.00	1160.00
Salt	1454.00	1454.00
Base of Salt	4598.41	4564.00
Delaware	4857.35	4819.00
Cherry Canyon	6022.04	5966.00
Brushy Canyon	6980.46	6915.00
1st Bone Spring Lime	8705.46	8640.00
Bone Spring 1st	9845.46	9780.00
Bone Spring 2nd	10473.46	10408.00
3rd Bone Spring Lime	11011.46	10946.00
Bone Spring 3rd	11615.46	11550.00
Wolfcamp / Point of Penetration	12010.46	11945.00
exit	23154.71	12745.60

SHL
KOP
Point of Penetration
Exit
BHL

MD	TVD	Lat	Long	Section Footages
(ft)	(ft)	(°)	(°)	
0.00	0.00	32.3124	-103.6747	206' FSL, 1092' FEL of Sec 9 in T23S, R32E
12432.61	12367.15	32.3120	-103.6721	50' FSL, 330' FEL of Sec 9 in T23S, R32E
12010.46	11945.00	32.3122	-103.6721	100' FSL, 330' FEL of Sec 9 in T23S, R32E
23154.71	12745.60	32.3406	-103.6722	100' FNL, 330' FEL of Sec 4 in T23S, R32E
23234.71	12744.00	32.3407	-103.6722	20' FNL, 330' FEL of Sec 4 in T23S, R32E
	Y	X	MD	
KOP	477880	745606	12432.61	

GATO GRANDE 9-4 FED COM 834H



Well: GATO GRANDE 9-4 FED COM 834H
 County: Lea
 Wellbore: Permit Plan
 Design: Permit Plan #1

Geodetic System: US State Plane 1983
 Datum: North American Datum 1927
 Ellipsoid: Clarke 1866
 Zone: 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (")	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	SHL
100.00	0.00	101.05	100.00	0.00	0.00	0.00	0.00	
200.00	0.00	101.05	200.00	0.00	0.00	0.00	0.00	
300.00	0.00	101.05	300.00	0.00	0.00	0.00	0.00	
400.00	0.00	101.05	400.00	0.00	0.00	0.00	0.00	
500.00	0.00	101.05	500.00	0.00	0.00	0.00	0.00	
600.00	0.00	101.05	600.00	0.00	0.00	0.00	0.00	
700.00	0.00	101.05	700.00	0.00	0.00	0.00	0.00	
800.00	0.00	101.05	800.00	0.00	0.00	0.00	0.00	
900.00	0.00	101.05	900.00	0.00	0.00	0.00	0.00	
1000.00	0.00	101.05	1000.00	0.00	0.00	0.00	0.00	
1100.00	0.00	101.05	1100.00	0.00	0.00	0.00	0.00	
1160.00	0.00	101.05	1160.00	0.00	0.00	0.00	0.00	Rustler
1200.00	0.00	101.05	1200.00	0.00	0.00	0.00	0.00	
1300.00	0.00	101.05	1300.00	0.00	0.00	0.00	0.00	
1400.00	0.00	101.05	1400.00	0.00	0.00	0.00	0.00	
1454.00	0.00	101.05	1454.00	0.00	0.00	0.00	0.00	Salt
1500.00	0.00	101.05	1500.00	0.00	0.00	0.00	0.00	
1600.00	0.00	101.05	1600.00	0.00	0.00	0.00	0.00	
1700.00	0.00	101.05	1700.00	0.00	0.00	0.00	0.00	
1800.00	0.00	101.05	1800.00	0.00	0.00	0.00	0.00	
1900.00	0.00	101.05	1900.00	0.00	0.00	0.00	0.00	
2000.00	0.00	101.05	2000.00	0.00	0.00	0.00	0.00	Start Tangent
2100.00	2.00	101.05	2099.98	-0.33	1.71	-0.22	2.00	
2200.00	4.00	101.05	2199.84	-1.34	6.85	-0.88	2.00	
2300.00	6.00	101.05	2299.45	-3.01	15.40	-1.97	2.00	
2400.00	8.00	101.05	2398.70	-5.34	27.36	-3.50	2.00	
2500.00	10.00	101.05	2497.47	-8.34	42.72	-5.46	2.00	Hold Tangent
2600.00	10.00	101.05	2595.95	-11.67	59.76	-7.64	0.00	
2700.00	10.00	101.05	2694.43	-15.00	76.80	-9.82	0.00	
2800.00	10.00	101.05	2792.91	-18.33	93.84	-12.01	0.00	
2900.00	10.00	101.05	2891.39	-21.65	110.89	-14.19	0.00	
3000.00	10.00	101.05	2989.87	-24.98	127.93	-16.37	0.00	
3100.00	10.00	101.05	3088.35	-28.31	144.97	-18.55	0.00	
3200.00	10.00	101.05	3186.83	-31.64	162.02	-20.73	0.00	
3300.00	10.00	101.05	3285.31	-34.97	179.06	-22.91	0.00	
3400.00	10.00	101.05	3383.79	-38.30	196.10	-25.09	0.00	
3500.00	10.00	101.05	3482.27	-41.62	213.14	-27.27	0.00	
3600.00	10.00	101.05	3580.75	-44.95	230.19	-29.45	0.00	
3700.00	10.00	101.05	3679.23	-48.28	247.23	-31.63	0.00	
3800.00	10.00	101.05	3777.72	-51.61	264.27	-33.81	0.00	
3900.00	10.00	101.05	3876.20	-54.94	281.32	-35.99	0.00	
4000.00	10.00	101.05	3974.68	-58.26	298.36	-38.17	0.00	
4100.00	10.00	101.05	4073.16	-61.59	315.40	-40.35	0.00	
4200.00	10.00	101.05	4171.64	-64.92	332.44	-42.53	0.00	
4300.00	10.00	101.05	4270.12	-68.25	349.49	-44.71	0.00	
4400.00	10.00	101.05	4368.60	-71.58	366.53	-46.89	0.00	
4500.00	10.00	101.05	4467.08	-74.91	383.57	-49.07	0.00	
4598.41	10.00	101.05	4564.00	-78.18	400.35	-51.21	0.00	Base of Salt
4600.00	10.00	101.05	4565.56	-78.23	400.62	-51.25	0.00	
4700.00	10.00	101.05	4664.04	-81.56	417.66	-53.43	0.00	
4800.00	10.00	101.05	4762.52	-84.89	434.70	-55.61	0.00	
4857.35	10.00	101.05	4819.00	-86.80	444.48	-56.86	0.00	Delaware
4900.00	10.00	101.05	4861.00	-88.22	451.74	-57.79	0.00	
5000.00	10.00	101.05	4959.48	-91.55	468.79	-59.97	0.00	
5100.00	10.00	101.05	5057.97	-94.88	485.83	-62.15	0.00	
5200.00	10.00	101.05	5156.45	-98.20	502.87	-64.33	0.00	
5300.00	10.00	101.05	5254.93	-101.53	519.92	-66.51	0.00	
5400.00	10.00	101.05	5353.41	-104.86	536.96	-68.69	0.00	
5500.00	10.00	101.05	5451.89	-108.19	554.00	-70.87	0.00	
5600.00	10.00	101.05	5550.37	-111.52	571.04	-73.05	0.00	
5700.00	10.00	101.05	5648.85	-114.84	588.09	-75.23	0.00	
5800.00	10.00	101.05	5747.33	-118.17	605.13	-77.41	0.00	
5900.00	10.00	101.05	5845.81	-121.50	622.17	-79.59	0.00	
6000.00	10.00	101.05	5944.29	-124.83	639.22	-81.77	0.00	
6022.04	10.00	101.05	5966.00	-125.56	642.97	-82.25	0.00	Cherry Canyon
6100.00	10.00	101.05	6042.77	-128.16	656.26	-83.95	0.00	
6200.00	10.00	101.05	6141.25	-131.49	673.30	-86.13	0.00	
6300.00	10.00	101.05	6239.73	-134.81	690.34	-88.31	0.00	
6400.00	10.00	101.05	6338.22	-138.14	707.39	-90.49	0.00	

GATO GRANDE 9-4 FED COM 834H



Well: GATO GRANDE 9-4 FED COM 834H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (")	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS (°/100ft)	Comment
6475.00	10.00	101.05	6412.07	-140.64	720.17	-92.13	0.00	Drop to Vertical
6500.00	9.50	101.05	6436.72	-141.45	724.33	-92.66	2.00	
6600.00	7.50	101.05	6535.61	-144.28	738.83	-94.52	2.00	
6700.00	5.50	101.05	6634.96	-146.45	749.94	-95.94	2.00	
6800.00	3.50	101.05	6734.65	-147.96	757.64	-96.92	2.00	
6900.00	1.50	101.05	6834.55	-148.79	761.92	-97.47	2.00	
6975.00	0.00	101.05	6909.54	-148.98	762.89	-97.59	2.00	Hold Vertical
6980.46	0.00	359.61	6915.00	-148.98	762.89	-97.59	0.00	Brushy Canyon
7000.00	0.00	359.61	6934.54	-148.98	762.89	-97.59	0.00	
7100.00	0.00	359.61	7034.54	-148.98	762.89	-97.59	0.00	
7200.00	0.00	359.61	7134.54	-148.98	762.89	-97.59	0.00	
7300.00	0.00	359.61	7234.54	-148.98	762.89	-97.59	0.00	
7400.00	0.00	359.61	7334.54	-148.98	762.89	-97.59	0.00	
7500.00	0.00	359.61	7434.54	-148.98	762.89	-97.59	0.00	
7600.00	0.00	359.61	7534.54	-148.98	762.89	-97.59	0.00	
7700.00	0.00	359.61	7634.54	-148.98	762.89	-97.59	0.00	
7800.00	0.00	359.61	7734.54	-148.98	762.89	-97.59	0.00	
7900.00	0.00	359.61	7834.54	-148.98	762.89	-97.59	0.00	
8000.00	0.00	359.61	7934.54	-148.98	762.89	-97.59	0.00	
8100.00	0.00	359.61	8034.54	-148.98	762.89	-97.59	0.00	
8200.00	0.00	359.61	8134.54	-148.98	762.89	-97.59	0.00	
8300.00	0.00	359.61	8234.54	-148.98	762.89	-97.59	0.00	
8400.00	0.00	359.61	8334.54	-148.98	762.89	-97.59	0.00	
8500.00	0.00	359.61	8434.54	-148.98	762.89	-97.59	0.00	
8600.00	0.00	359.61	8534.54	-148.98	762.89	-97.59	0.00	
8700.00	0.00	359.61	8634.54	-148.98	762.89	-97.59	0.00	
8705.46	0.00	359.61	8640.00	-148.98	762.89	-97.59	0.00	1st Bone Spring Lime
8800.00	0.00	359.61	8734.54	-148.98	762.89	-97.59	0.00	
8900.00	0.00	359.61	8834.54	-148.98	762.89	-97.59	0.00	
9000.00	0.00	359.61	8934.54	-148.98	762.89	-97.59	0.00	
9100.00	0.00	359.61	9034.54	-148.98	762.89	-97.59	0.00	
9200.00	0.00	359.61	9134.54	-148.98	762.89	-97.59	0.00	
9300.00	0.00	359.61	9234.54	-148.98	762.89	-97.59	0.00	
9400.00	0.00	359.61	9334.54	-148.98	762.89	-97.59	0.00	
9500.00	0.00	359.61	9434.54	-148.98	762.89	-97.59	0.00	
9600.00	0.00	359.61	9534.54	-148.98	762.89	-97.59	0.00	
9700.00	0.00	359.61	9634.54	-148.98	762.89	-97.59	0.00	
9800.00	0.00	359.61	9734.54	-148.98	762.89	-97.59	0.00	
9845.46	0.00	359.61	9780.00	-148.98	762.89	-97.59	0.00	Bone Spring 1st
9900.00	0.00	359.61	9834.54	-148.98	762.89	-97.59	0.00	
10000.00	0.00	359.61	9934.54	-148.98	762.89	-97.59	0.00	
10100.00	0.00	359.61	10034.54	-148.98	762.89	-97.59	0.00	
10200.00	0.00	359.61	10134.54	-148.98	762.89	-97.59	0.00	
10300.00	0.00	359.61	10234.54	-148.98	762.89	-97.59	0.00	
10400.00	0.00	359.61	10334.54	-148.98	762.89	-97.59	0.00	
10473.46	0.00	359.61	10408.00	-148.98	762.89	-97.59	0.00	Bone Spring 2nd
10500.00	0.00	359.61	10434.54	-148.98	762.89	-97.59	0.00	
10600.00	0.00	359.61	10534.54	-148.98	762.89	-97.59	0.00	
10700.00	0.00	359.61	10634.54	-148.98	762.89	-97.59	0.00	
10800.00	0.00	359.61	10734.54	-148.98	762.89	-97.59	0.00	
10900.00	0.00	359.61	10834.54	-148.98	762.89	-97.59	0.00	
11000.00	0.00	359.61	10934.54	-148.98	762.89	-97.59	0.00	
11011.46	0.00	359.61	10946.00	-148.98	762.89	-97.59	0.00	3rd Bone Spring Lime
11100.00	0.00	359.61	11034.54	-148.98	762.89	-97.59	0.00	
11200.00	0.00	359.61	11134.54	-148.98	762.89	-97.59	0.00	
11300.00	0.00	359.61	11234.54	-148.98	762.89	-97.59	0.00	
11400.00	0.00	359.61	11334.54	-148.98	762.89	-97.59	0.00	
11500.00	0.00	359.61	11434.54	-148.98	762.89	-97.59	0.00	
11600.00	0.00	359.61	11534.54	-148.98	762.89	-97.59	0.00	
11615.46	0.00	359.61	11550.00	-148.98	762.89	-97.59	0.00	Bone Spring 3rd
11700.00	0.00	359.61	11634.54	-148.98	762.89	-97.59	0.00	
11800.00	0.00	359.61	11734.54	-148.98	762.89	-97.59	0.00	
11900.00	0.00	359.61	11834.54	-148.98	762.89	-97.59	0.00	
12000.00	0.00	359.61	11934.54	-148.98	762.89	-97.59	0.00	
12010.46	0.00	359.61	11945.00	-148.98	762.89	-97.59	0.00	Wolfcamp / Point of Penetration
12100.00	0.00	359.61	12034.54	-148.98	762.89	-97.59	0.00	
12200.00	0.00	359.61	12134.54	-148.98	762.89	-97.59	0.00	
12300.00	0.00	359.61	12234.54	-148.98	762.89	-97.59	0.00	
12400.00	0.00	359.61	12334.54	-148.98	762.89	-97.59	0.00	
12432.61	0.00	359.61	12367.15	-148.98	762.89	-97.59	0.00	KOP

GATO GRANDE 9-4 FED COM 834H



Well: GATO GRANDE 9-4 FED COM 834H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD (ft)	INC (")	AZI (")	TVD (ft)	NS (ft)	EW (ft)	VS (ft)	DLS ("/100ft)	Comment
12500.00	6.74	359.61	12434.39	-145.02	762.86	-93.65	10.00	
12600.00	16.74	359.61	12532.17	-124.70	762.72	-73.38	10.00	
12700.00	26.74	359.61	12624.94	-87.71	762.47	-36.49	10.00	
12800.00	36.74	359.61	12709.88	-35.18	762.12	15.90	10.00	
12900.00	46.74	359.61	12784.40	31.31	761.67	82.21	10.00	
13000.00	56.74	359.61	12846.25	109.73	761.14	160.42	10.00	
13100.00	66.74	359.61	12893.54	197.69	760.55	248.15	10.00	
13200.00	76.74	359.61	12924.83	292.53	759.91	342.73	10.00	
13300.00	86.74	359.61	12939.19	391.37	759.25	441.30	10.00	
13343.97	91.14	359.61	12940.00	435.32	758.95	485.13	10.00	Landing Point
13400.00	91.14	359.61	12938.89	491.34	758.58	541.00	0.00	
13500.00	91.14	359.61	12936.91	591.32	757.90	640.71	0.00	
13600.00	91.14	359.61	12934.93	691.29	757.23	740.42	0.00	
13700.00	91.14	359.61	12932.95	791.27	756.56	840.13	0.00	
13800.00	91.14	359.61	12930.96	891.25	755.88	939.84	0.00	
13900.00	91.14	359.61	12928.98	991.23	755.21	1039.55	0.00	
14000.00	91.14	359.61	12927.00	1091.21	754.54	1139.25	0.00	
14100.00	91.14	359.61	12925.02	1191.18	753.87	1238.96	0.00	
14200.00	91.14	359.61	12923.04	1291.16	753.19	1338.67	0.00	
14300.00	91.14	359.61	12921.06	1391.14	752.52	1438.38	0.00	
14400.00	91.14	359.61	12919.07	1491.12	751.85	1538.09	0.00	
14500.00	91.14	359.61	12917.09	1591.10	751.17	1637.80	0.00	
14600.00	91.14	359.61	12915.11	1691.07	750.50	1737.51	0.00	
14700.00	91.14	359.61	12913.13	1791.05	749.83	1837.22	0.00	
14800.00	91.14	359.61	12911.15	1891.03	749.15	1936.93	0.00	
14900.00	91.14	359.61	12909.17	1991.01	748.48	2036.64	0.00	
15000.00	91.14	359.61	12907.19	2090.99	747.81	2136.34	0.00	
15100.00	91.14	359.61	12905.20	2190.97	747.13	2236.05	0.00	
15200.00	91.14	359.61	12903.22	2290.94	746.46	2335.76	0.00	
15300.00	91.14	359.61	12901.24	2390.92	745.79	2435.47	0.00	
15400.00	91.14	359.61	12899.26	2490.90	745.11	2535.18	0.00	
15500.00	91.14	359.61	12897.28	2590.88	744.44	2634.89	0.00	
15600.00	91.14	359.61	12895.30	2690.86	743.77	2734.60	0.00	
15700.00	91.14	359.61	12893.32	2790.83	743.10	2834.31	0.00	
15800.00	91.14	359.61	12891.33	2890.81	742.42	2934.02	0.00	
15900.00	91.14	359.61	12889.35	2990.79	741.75	3033.72	0.00	
16000.00	91.14	359.61	12887.37	3090.77	741.08	3133.43	0.00	
16100.00	91.14	359.61	12885.39	3190.75	740.40	3233.14	0.00	
16200.00	91.14	359.61	12883.41	3290.72	739.73	3332.85	0.00	
16300.00	91.14	359.61	12881.43	3390.70	739.06	3432.56	0.00	
16400.00	91.14	359.61	12879.44	3490.68	738.38	3532.27	0.00	
16500.00	91.14	359.61	12877.46	3590.66	737.71	3631.98	0.00	
16600.00	91.14	359.61	12875.48	3690.64	737.04	3731.69	0.00	
16700.00	91.14	359.61	12873.50	3790.62	736.36	3831.40	0.00	
16800.00	91.14	359.61	12871.52	3890.59	735.69	3931.10	0.00	
16900.00	91.14	359.61	12869.54	3990.57	735.02	4030.81	0.00	
17000.00	91.14	359.61	12867.56	4090.55	734.34	4130.52	0.00	
17100.00	91.14	359.61	12865.57	4190.53	733.67	4230.23	0.00	
17200.00	91.14	359.61	12863.59	4290.51	733.00	4329.94	0.00	
17300.00	91.14	359.61	12861.61	4390.48	732.33	4429.65	0.00	
17400.00	91.14	359.61	12859.63	4490.46	731.65	4529.36	0.00	
17500.00	91.14	359.61	12857.65	4590.44	730.98	4629.07	0.00	
17600.00	91.14	359.61	12855.67	4690.42	730.31	4728.78	0.00	
17700.00	91.14	359.61	12853.68	4790.40	729.63	4828.49	0.00	
17800.00	91.14	359.61	12851.70	4890.37	728.96	4928.19	0.00	
17900.00	91.14	359.61	12849.72	4990.35	728.29	5027.90	0.00	
18000.00	91.14	359.61	12847.74	5090.33	727.61	5127.61	0.00	
18100.00	91.14	359.61	12845.76	5190.31	726.94	5227.32	0.00	
18200.00	91.14	359.61	12843.78	5290.29	726.27	5327.03	0.00	
18300.00	91.14	359.61	12841.80	5390.26	725.59	5426.74	0.00	
18400.00	91.14	359.61	12839.81	5490.24	724.92	5526.45	0.00	
18500.00	91.14	359.61	12837.83	5590.22	724.25	5626.16	0.00	
18600.00	91.14	359.61	12835.85	5690.20	723.57	5725.87	0.00	
18700.00	91.14	359.61	12833.87	5790.18	722.90	5825.57	0.00	
18800.00	91.14	359.61	12831.89	5890.16	722.23	5925.28	0.00	
18900.00	91.14	359.61	12829.91	5990.13	721.56	6024.99	0.00	
19000.00	91.14	359.61	12827.93	6090.11	720.88	6124.70	0.00	
19100.00	91.14	359.61	12825.94	6190.09	720.21	6224.41	0.00	
19200.00	91.14	359.61	12823.96	6290.07	719.54	6324.12	0.00	
19300.00	91.14	359.61	12821.98	6390.05	718.86	6423.83	0.00	

GATO GRANDE 9-4 FED COM 834H



Well: GATO GRANDE 9-4 FED COM 834H
County: Lea
Wellbore: Permit Plan
Design: Permit Plan #1

Geodetic System: US State Plane 1983
Datum: North American Datum 1927
Ellipsoid: Clarke 1866
Zone: 3001 - NM East (NAD83)

MD	INC	AZI	TVD	NS	EW	VS	DLS	Comment
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	
19400.00	91.14	359.61	12820.00	6490.02	718.19	6523.54	0.00	
19500.00	91.14	359.61	12818.02	6590.00	717.52	6623.25	0.00	
19600.00	91.14	359.61	12816.04	6689.98	716.84	6722.95	0.00	
19700.00	91.14	359.61	12814.05	6789.96	716.17	6822.66	0.00	
19800.00	91.14	359.61	12812.07	6889.94	715.50	6922.37	0.00	
19900.00	91.14	359.61	12810.09	6989.91	714.82	7022.08	0.00	
20000.00	91.14	359.61	12808.11	7089.89	714.15	7121.79	0.00	
20100.00	91.14	359.61	12806.13	7189.87	713.48	7221.50	0.00	
20200.00	91.14	359.61	12804.15	7289.85	712.80	7321.21	0.00	
20300.00	91.14	359.61	12802.17	7389.83	712.13	7420.92	0.00	
20400.00	91.14	359.61	12800.18	7489.80	711.46	7520.63	0.00	
20500.00	91.14	359.61	12798.20	7589.78	710.79	7620.34	0.00	
20600.00	91.14	359.61	12796.22	7689.76	710.11	7720.04	0.00	
20700.00	91.14	359.61	12794.24	7789.74	709.44	7819.75	0.00	
20800.00	91.14	359.61	12792.26	7889.72	708.77	7919.46	0.00	
20900.00	91.14	359.61	12790.28	7989.70	708.09	8019.17	0.00	
21000.00	91.14	359.61	12788.29	8089.67	707.42	8118.88	0.00	
21100.00	91.14	359.61	12786.31	8189.65	706.75	8218.59	0.00	
21200.00	91.14	359.61	12784.33	8289.63	706.07	8318.30	0.00	
21300.00	91.14	359.61	12782.35	8389.61	705.40	8418.01	0.00	
21400.00	91.14	359.61	12780.37	8489.59	704.73	8517.72	0.00	
21500.00	91.14	359.61	12778.39	8589.56	704.05	8617.42	0.00	
21600.00	91.14	359.61	12776.41	8689.54	703.38	8717.13	0.00	
21700.00	91.14	359.61	12774.42	8789.52	702.71	8816.84	0.00	
21800.00	91.14	359.61	12772.44	8889.50	702.03	8916.55	0.00	
21900.00	91.14	359.61	12770.46	8989.48	701.36	9016.26	0.00	
22000.00	91.14	359.61	12768.48	9089.45	700.69	9115.97	0.00	
22100.00	91.14	359.61	12766.50	9189.43	700.02	9215.68	0.00	
22200.00	91.14	359.61	12764.52	9289.41	699.34	9315.39	0.00	
22300.00	91.14	359.61	12762.54	9389.39	698.67	9415.10	0.00	
22400.00	91.14	359.61	12760.55	9489.37	698.00	9514.80	0.00	
22500.00	91.14	359.61	12758.57	9589.34	697.32	9614.51	0.00	
22600.00	91.14	359.61	12756.59	9689.32	696.65	9714.22	0.00	
22700.00	91.14	359.61	12754.61	9789.30	695.98	9813.93	0.00	
22800.00	91.14	359.61	12752.63	9889.28	695.30	9913.64	0.00	
22900.00	91.14	359.61	12750.65	9989.26	694.63	10013.35	0.00	
23000.00	91.14	359.61	12748.66	10089.24	693.96	10113.06	0.00	
23100.00	91.14	359.61	12746.68	10189.21	693.28	10212.77	0.00	
23154.71	91.14	359.61	12745.60	10243.91	692.92	10267.31	0.00	exit
23200.00	91.14	359.61	12744.70	10289.19	692.61	10312.48	0.00	
23234.71	91.14	359.61	12744.00	10323.89	692.43	10347.09	0.00	BHL

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 453046

CONDITIONS

Operator: DEVON ENERGY PRODUCTION COMPANY, LP 333 West Sheridan Ave. Oklahoma City, OK 73102	OGRID: 6137
	Action Number: 453046
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
matthew.gomez	Administrative order required for non-standard location prior to production.	5/14/2025
matthew.gomez	If cement is not circulated to surface during cementing operations, a Cement Bond Log (CBL) is required.	5/14/2025
matthew.gomez	A [C-103] Sub. Drilling (C-103N) is required within (10) days of spud.	5/14/2025
matthew.gomez	Notify the OCD 24 hours prior to casing & cement.	5/14/2025
matthew.gomez	Any previous COA's not addressed within the updated COA's still apply.	5/14/2025