

Form 3160-5
(June 2019)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: October 31, 2021**SUNDRY NOTICES AND REPORTS ON WELLS**
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

NMNM101609

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

CIVITAS PERMIAN OPERATING LLC

3a. Address 555 17TH STREET SUITE 3700, DENVER, CO 8

3b. Phone No. (include area code)
(303) 293-1000

7. If Unit of CA/Agreement, Name and/or No.

8. Well Name and No.

JUNIOR MINT FED/135H

9. API Well No.

10. Field and Pool or Exploratory Area

WC-02 H-08 S2535340/BONE SPRING

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEC 15/T25S/R35E/NMP

11. Country or Parish, State

LEA/NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION				
☒ Notice of Intent	☐ Acidize	☐ Deepen	☐ Production (Start/Resume)	☐ Water Shut-Off	
☐ Subsequent Report	☐ Alter Casing	☐ Hydraulic Fracturing	☐ Reclamation	☐ Well Integrity	
☐ Final Abandonment Notice	☐ Casing Repair	☐ New Construction	☐ Recomplete	☐ Other	
	☒ Change Plans	☐ Plug and Abandon	☐ Temporarily Abandon		
	☐ Convert to Injection	☐ Plug Back	☐ Water Disposal		

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has detennined that the site is ready for final inspection.)

Civitas Permian Operating, LLC requests the following changes to the previously approved surface hole location (SHL) and drill plan. Change SHL from 296 FNL & 1426 FWL, NENW, Sec. 15, T.25S, R.35E to 511 FNL & 1434 FWL, NENW, Sec. 15, T.25S, R.35E. Changes to the drill plan and other variance requests are detailed in the attached summary and supporting documents. Please see the attached revised C102 plat, directional plan, anticollision report, production casing spec sheets and wellhead diagram for additional information.

14. I hereby certify that the foregoing is true and correct. Name (Printed/Typed)

BRIAN WOOD / Ph: (505) 466-8120

Permitting Agent

Title

(Electronic Submission)

Signature

Date

04/18/2025

THE SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

CHRISTOPHER WALLS / Ph: (575) 234-2234 / Approved

Petroleum Engineer

Title

05/27/2025

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office CARLSBAD

Title 18 U.S.C Section 1001 and Title 43 U.S.C Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

Additional Information

Location of Well

0. SHL: NENW / 296 FNL / 1426 FWL / TWSP: 25S / RANGE: 35E / SECTION: 15 / LAT: 32.1368229 / LONG: -103.359327 (TVD: 0 feet, MD: 0 feet)

PPP: NWNW / 165 FNL / 1268 FWL / TWSP: 25S / RANGE: 35E / SECTION: 15 / LAT: 32.1371815 / LONG: -103.3598372 (TVD: 11895 feet, MD: 11936 feet)

BHL: SWSW / 5 FSL / 1269 FWL / TWSP: 25S / RANGE: 35E / SECTION: 22 / LAT: 32.1086298 / LONG: -103.3598502 (TVD: 12211 feet, MD: 22398 feet)

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	☐ Initial Submittal
			☒ Amended Report
		☐ As Drilled	

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-025-54740	Pool Code 98185	Pool Name WC-025 G-09 S253502B;LWR BONE SPRING
Property Code 337333	Property Name JUNIOR MINT FED	Well Number 135H
OGRID No. 332195	Operator Name CIVITAS PERMIAN OPERATING, LLC	Ground Level Elevation 3220'
Surface Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal		Mineral Owner: ☐ State ☐ Fee ☐ Tribal ☒ Federal

Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
C	15	25-S	35-E	-	511' N	1434' W	N 32.1362317	W 103.3593010	LEA

Bottom Hole Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
M	22	25-S	35-E	-	5' S	1269' W	N 32.1086298	W 103.3598501	LEA

Dedicated Acres 1280.00	Infill or Defining Well Defining	Defining Well API - 30-025-54740	Overlapping Spacing Unit (Y/N) No	Consolidated Code N/A
Order Numbers N/A			Well Setbacks are under Common Ownership: ☒ Yes ☐ No	

Kick Off Point (KOP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
D	15	25-S	35-E	-	100' N	1269' W	N 32.1373630	W 103.3598351	LEA

First Take Point (FTP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
D	15	25-S	35-E	-	100' N	1269' W	N 32.1373630	W 103.3598351	LEA


Last Take Point (LTP)

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the N/S	Feet from the E/W	Latitude	Longitude	County
M	22	25-S	35-E	-	100' S	1269' W	N 32.1088909	W 103.3598495	LEA

Unitized Area or Area of Uniform Intrest -	Spacing Unity Type ☒ Horizontal ☐ Vertical	Ground Floor Elevation -
--	--	------------------------------------

OPERATOR CERTIFICATION <i>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief; and, if the well is a vertical or directional well, that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of a working interest or unleased mineral interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</i> <i>If this well is a horizontal well, I further certify that this organization has received The consent of at least one lessee or owner of a working interest or unleased mineral interest in each tract (in the target pool or formation) in which any part of the well's completed interval will be located or obtained a compulsory pooling order from the division.</i>  4-16-25		SURVEYORS CERTIFICATION <i>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</i>  2/6/2025 3:29:42 PM	
Signature Cory Walk		Signature and Seal of Professional Surveyor	
Date 4-16-25		Date 2/6/2025 3:29:42 PM	
Print Name cory@permitswest.com		Certificate Number	Date of Survey 01/30/2025
E-mail Address			

C-102 Submit Electronically Via OCD Permitting	State of New Mexico Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION	Revised July 9, 2024	
		Submittal Type:	☐ Initial Submittal
			☒ Amended Report
Property Name and Well Number		JUNIOR MINT FED 135H	





Junior Mint Sundry Summary

4/3/2025

Civitas Resources is requesting sundries/variances for the upcoming Junior Mint drilling campaigns.

1. Cement Volumes and Design: Civitas Resources requests to sundry cement volumes to the following strings with comments noted below:

- Intermediate Cement: for all Junior Mint wells with deepset 7 5/8" intermediate strings, the following items are updated in the cement table:
 - i. Intermediate Lead/Tail Volumes: based of offset TapRock wells drilled in the previous two years, the lead and tail cement volumes are increased to improve assurance of cement to surface.
 - ii. Intermediate Yield: The lead cement yield for the 10.5 ppg slurry is updated to reflect recent labs from cement providers.
 - iii. Intermediate Contingency for no returns and/or lack of cement to surface: the goal is to ensure quality cement from shoe to surface
 - 1. No Returns at TD of 9 7/8" Hole: Civitas Resources requests to pump an intentional 2-stage cement job where stage 1 would be pumped to the mid/base of the Brushy Canyon and stage 2 would be pumped as a standard bradenhead squeeze to the mid/base of Brushy Canyon, thus cementing the entire string. To verify the TOC of stage 2, and Echo-meter will be used

Stage 1 Cement Details (conventional):
Single slurry: 15.6 ppg cement, Class H, Yield: 1.18 cuft/sk, 25% xs DBE Emulsion Spacer (weighted)

Stage 2 Cement Details (bradenhead):
Lead: 14.8 ppg, Class C Thixotropic + LCM, Yield: 1.44 cuft/sk, 100% xs DBE Spacer (weighted)

Tail: 14.8 ppg, Class C Thixotropic, Yield: 1.44 cuft/sk, 100% xs, shoot temp survey to determine TOC

Top Out (if necessary): 14.8 Class C Neat, Yield: 1.33 cuft/sk; if required, Civitas Resources will request BLM approval to top out after running a temp survey and report back to BLM the amount of volume to flush cement lines to wellhead.
- 2. No Cement to Surface 7 5/8" cement Job: Civitas Resources requests to pump an intentional 2-stage cement job where stage 1 would be pumped to the




mid/base of the Brushy Canyon and stage 2 would be pumped as a standard bradenhead squeeze to the mid/base of Brushy Canyon (as described above), thus cementing the entire string. To verify the TOC of stage 2, and Echo-meter will be used and with BLM approval, top out the job as needed.

- Production Cement: the production tail volume has been increased from 200' to 500' to improve the overlap between intermediate and production casing



2. **Offline Cementing Intermediate Casing Only:** In addition to the batch drilling variance submitted in the original APD, Civitas Resources requests a variance for the option to offline cement intermediate casing strings set higher than the top of the WCA during the Junior Mint drilling campaign. To execute offline cement jobs safely, the following precautions and equipment are detailed below:
- During the drilling of the 9 7/8" and 10 5/8" hole sections (all TD'd above the WCA top), hole conditions will be monitored and addressed to ensure for a successful casing run. In the event hole conditions change after running casing and/or the well is not in a static state, Civitas Resources can elect to pump the cement job online.
 - Equipment for the offline cement job will include a tested/charted 5M working pressure dual manifold cement head system will be used with a standard offline cement tool that is packed off and tested through a port between the upper valve and packoff assembly (diagram below). Returns from the manifold will be taken to an auxiliary mud-gas separator during cement job. The operational scope is described in the following steps: the casing will be landed on the mandrel, pull tested, packoff installed and tested to 80% of collapse of casing on the top and bottom seals, nipple down BOP and install offline cement tool/manifold. The offline cement tool screws into the top of the packoff assembly. During the cement job, all returns will be taken through the A-Section valve (flanged).





3. **BOPE Testing Procedure for Batch Drilling:** Civitas Resources requests a variance to adjust the BOPE testing procedure to accommodate batch drilling. Details of the request are below:
- In lieu of a full BOP test during batch intermediate drilling operations, Civitas Resources requests to "Break-Test" or only test BOP connection breaks that are separated during skids between intermediate casing strings set above 5M BOPE thresholds/Wolfcamp A top. Industry standards are adhered to in terms of timing of breaks as noted in API Standard 53 which will include test charts during each skid for the following: Top Pipe Rams or VBRs, HCR, Downstream Kill Line, QDC Adapter – wellhead quick connect, and the body/shell of the BOP stack to 5M for 10 minutes.
 - Depending on the length and position of the next batch drilled intermediate hole section, the flex hose that connects to the choke manifold might have to be broken out, at which point the break will also be tested. This is not expected with Civitas Resources' rig fleet but could occur.
 - All "Break Test" BOPE operations will follow a 14-day limit, such that, Civitas Resources can have a 7-day buffer to execute a full test as per Onshore Order 43 CFR 3172 (21-day limit).
 - After completion of batch drilling operations for all intermediate hole sections above the WCA, the BOP tests will follow Onshore Order 43 CFR 3172
 - In the event any part of the BOPE equipment is changed or fails a test, a full test BOPE test will be performed. If the "Break Test" is not performed during the proper timing interval, a full BOPE test will take place.
 - The BLM will be contacted in the event a well control event is encountered.
 - During all "Break Test" or full BOPE tests, the BLM will be notified 4 hours before the test.
 - Before drilling out intermediate shoes and commencing production hole drilling, a full BOP test will be performed for all targets requiring a 10M BOPE pressure test; this test will override a previous 14 day "Break Test" interval.
4. **Centralizer Variance:** Due to the design of the intermediate casing strings on the Third Bone Spring Sand, WCA, and WCB intervals on the Junior Mint development (11 3/4" x 7 5/8" x 5 1/2" casing design), a variance to waive the centralizers is requested due to the tight clearance between 6 3/4" hole and 5 1/2" casing and the risk of not getting casing to bottom.



- Junior Mint Fed 135, 3BSS Target

Estimated Tops:

Formation	TVD	MD	Lithologies	Bearing
Quaternary Deposits	0	0	Surface	None
Rustler	660	660	Salt	Salt
Top Salt	1,100	1,100	Salt	Salt
Base Salt	4,920	4,922	Salt	Salt
DMG	5,160	5,189	Sandstone	None
Lamar	5,165	5,194	Sandstone	Hydrocarbons
Bell Canyon	5,185	5,215	Sandstone	Hydrocarbons
Ramsey Sand	5,205	5,235	Sandstone	Hydrocarbons
Cherry Canyon	6,150	6,180	Limestone	Hydrocarbons
Brushy Canyon	7,620	7,650	Sandstone	Hydrocarbons
Bone Spring Lime	8,930	8,960	Carbonate	Hydrocarbons
Upper Avalon	8,955	8,985	Carbonate	Hydrocarbons
Middle Avalon	9,185	9,215	Carbonate	Hydrocarbons
1st BS Sand	10,165	10,195	Sandstone	Hydrocarbons
2nd BS Carb	10,330	10,360	Carbonate	Hydrocarbons
2nd BS Sand	10,715	10,745	Sandstone	Hydrocarbons
3rd BS Carb	11,265	11,295	Carbonate	Hydrocarbons
3rd BS Sand	11,895	11,925	Sandstone	Hydrocarbons
KOP	11151	11581	Carbonate	Hydrocarbons
TD	12210	22411	Carbonate	Hydrocarbons

Casing Design:

Section	Drilled Interval			Casing Size	Standard	Tapered	Casing Set Depths				Casing Details					
	Hole Size	Top	Btm				Top MD	Bottom MD	Top TVD	BTM TVD	Grade	Weight	Thread	Collapse	Burst	Tension
Surface	14 3/4	0	1,075	11 3/4	API	No	0	1,075	0	1,075	J-55	47	BTC	1.13	1.15	1.6
1st Intermediate	9 7/8	1,075	11,481	7 5/8	API	No	0	11,481	0	11,351	P-110	29.7	BTC	1.13	1.15	1.6
Production	6 3/4	11,481	11,581	5 1/2	NON API	No	0	11,581	0	11,551	P110RYS	23	Talon	1.13	1.15	1.6
	6 3/4	11,581	22,411	5 1/2	NON API	No	11,581	22,411	11,551	12,210	P110RY	23	Talon	1.13	1.15	1.6

Cement Volumes:

Name	Type	Top MD	Sacks	Yield	Cu. Ft	Weight	Excess	Cement	Additives
Surface	Lead	0	391	1.72	672	13.5	100%	C	Additives + LCM
	Tail	775	196	1.33	260	14.8	100%	C	Additives + LCM
Intermediate	Lead	0	1028	4.29	4409	10.5	200%	C	Contingency Bradenhead Squeeze, LCM Lead
	Tail	10481	129	1.67	215	13.2	100%	C	Additives + LCM
Production	Tail	10981	924	1.24	1146	13.2	20%	H	Fluid Loss + Dispersant + Retarder + LCM

Mud Program:

Name	Top	Bottom	Type	Mud Weight	Visc	Fluid Loss
Surface	0	1,075	FW Spud Mud	8.40	28	NC
1st Intermediate	1,075	11,481	DBE	9.20	27-30	NC
Production	11,481	22,411	OBM	12.50	55-65	<16



U. S. Steel Tubular Products

2/25/2025 2:43:45 PM

5.500" 23.00lb/ft (0.415" Wall) P110 RY USS-TALON HTQ™ RD



MECHANICAL PROPERTIES	Pipe	USS-TALON HTQ™ RD		[6]
Minimum Yield Strength	110,000	--	psi	--
Maximum Yield Strength	125,000	--	psi	--
Minimum Tensile Strength	125,000	--	psi	--
DIMENSIONS	Pipe	USS-TALON HTQ™ RD		--
Outside Diameter	5.500	5.900	in.	--
Wall Thickness	0.415	--	in.	--
Inside Diameter	4.670	4.670	in.	--
Standard Drift	4.545	4.545	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	23.00	--	lb/ft	--
Plain End Weight	22.56	--	lb/ft	--
SECTION AREA	Pipe	USS-TALON HTQ™ RD		--
Critical Area	6.630	6.425	sq. in.	--
Joint Efficiency	--	96.9	%	[2]
PERFORMANCE	Pipe	USS-TALON HTQ™ RD		--
Minimum Collapse Pressure	14,540	14,540	psi	--
Minimum Internal Yield Pressure	14,520	14,520	psi	--
Minimum Pipe Body Yield Strength	729,000	--	lb	--
Joint Strength	--	707,000	lb	--
Compression Rating	--	707,000	lb	--
Reference Length	--	20,490	ft	[5]
Maximum Uniaxial Bend Rating	--	88.9	deg/100 ft	[3]
MAKE-UP DATA	Pipe	USS-TALON HTQ™ RD		--
Make-Up Loss	--	5.58	in.	--
Minimum Make-Up Torque	--	20,800	ft-lb	[4]
Maximum Make-Up Torque	--	23,800	ft-lb	[4]
Maximum Operating Torque	--	39,800	ft-lb	[4]

UNCONTROLLED

Notes

- Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
- Joint efficiencies are calculated by dividing the connection critical area by the pipe body area.
- Uniaxial bend rating shown is structural only.
- Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
- Reference length is calculated by Joint Strength divided by Nominal Linear Weight, T&C with a 1.5 Safety factor.
- Coupling must meet minimum mechanical properties of the pipe.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com



U. S. Steel Tubular Products

2/25/2025 2:25:12 PM

5.500" 23.00lb/ft (0.415" Wall) USS RYS110 USS-TALON HTQ™ RD



MECHANICAL PROPERTIES	Pipe	USS-TALON HTQ™ RD		[6]
Minimum Yield Strength	110,000	--	psi	--
Maximum Yield Strength	125,000	--	psi	--
Minimum Tensile Strength	120,000	--	psi	--
DIMENSIONS	Pipe	USS-TALON HTQ™ RD		--
Outside Diameter	5.500	5.900	in.	--
Wall Thickness	0.415	--	in.	--
Inside Diameter	4.670	4.670	in.	--
Standard Drift	4.545	4.545	in.	--
Alternate Drift	--	--	in.	--
Nominal Linear Weight, T&C	23.00	--	lb/ft	--
Plain End Weight	22.56	--	lb/ft	--
SECTION AREA	Pipe	USS-TALON HTQ™ RD		--
Critical Area	6.630	6.425	sq. in.	--
Joint Efficiency	--	96.9	%	[2]
PERFORMANCE	Pipe	USS-TALON HTQ™ RD		--
Minimum Collapse Pressure	14,540	14,540	psi	--
Minimum Internal Yield Pressure	14,520	14,520	psi	--
Minimum Pipe Body Yield Strength	729,000	--	lb	--
Joint Strength	--	707,000	lb	--
Compression Rating	--	707,000	lb	--
Reference Length	--	20,490	ft	[5]
Maximum Uniaxial Bend Rating	--	88.9	deg/100 ft	[3]
MAKE-UP DATA	Pipe	USS-TALON HTQ™ RD		--
Make-Up Loss	--	5.58	in.	--
Minimum Make-Up Torque	--	20,800	ft-lb	[4]
Maximum Make-Up Torque	--	23,800	ft-lb	[4]
Maximum Operating Torque	--	39,800	ft-lb	[4]

UNCONTROLLED

Notes


- Other than proprietary collapse and connection values, performance properties have been calculated using standard equations defined by API 5C3 and do not incorporate any additional design or safety factors. Calculations assume nominal pipe OD, nominal wall thickness, and Specified Minimum Yield Strength (SMYS).
- Joint efficiencies are calculated by dividing the connection critical area by the pipe body area.
- Uniaxial bend rating shown is structural only.
- Torques have been calculated assuming a thread compound friction factor of 1.0 and are recommended only. Field make-up torques may require adjustment based on actual field conditions (e.g. make-up speed, temperature, thread compound, etc.).
- Reference length is calculated by Joint Strength divided by Nominal Linear Weight, T&C with a 1.5 Safety factor.
- Coupling must meet minimum mechanical properties of the pipe.

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com



ALL DIMENSIONS APPROXIMATE

CIVITAS RESOURCES DELAWARE BASIN		DRAWING NO. REF: HBE0001444	
DRAWN	VJK	13FEB25	
APPRV			

CACTUS WELLHEAD LLC

20" x 11-3/4" x 7-5/8" x 5-1/2" MBU-3T-SF Wellhead System
With 13-5/8" 10M x 7-1/16" 15M CTH-DBLHPS Tubing Head
And Quick Connect Drill Adapter & Quick Connect TA Cap

INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.

Project: Lea County, NM (NAD 83)
 Site: Junior Mint Fed Pad
 Well: Junior Mint Fed 135H
 Wellbore: OH
 Design: Plan 1
 Rig: 26' KB



Azimuths to Grid North
 True North: -0.52°
 Magnetic North: 5.55°
 Magnetic Field
 Strength: 47068.1nT
 Dip Angle: 59.57°
 Date: 7/15/2025
 Model: HDGM2025

Total Magnetic Correction: 5.55°

PROJECT DETAILS: Lea County, NM (NAD 83)

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: New Mexico Eastern Zone

Reference Datum: GE 3220 + 26 @ 3246.00usft (26' KB)

SHL

RKB Elevation: GE 3220 + 26 @ 3246.00usft (26' KB)




+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
0.00	0.00	414660.00	842835.00	32.1362314	-103.3593009	

SECTION DETAILS



MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSEct	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	
1000.00	3.00	339.77	999.91	4.91	-1.81	1.50	339.77	-4.90	
1250.43	3.00	339.77	1250.00	17.21	-6.34	0.00	0.00	-17.16	
1550.47	7.50	339.77	1548.70	42.96	-15.83	1.50	-0.01	-42.84	
4702.13	7.50	339.77	4673.39	428.97	-158.13	0.00	0.00	-427.72	
5202.16	0.00	0.00	5172.00	459.64	-169.43	1.50	180.00	-458.30	
11581.16	0.00	0.00	11551.00	459.64	-169.43	0.00	0.00	-458.30	
12476.17	89.50	179.51	12123.94	-108.30	-164.54	10.00	179.51	109.59	
22411.61	89.50	179.51	12210.50	-10043.00	-79.00	0.00	0.00	10043.31	

WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
Junior Mint Fed 135H KOP/FTP	11551.00	410.00	-169.00	415070.00	842666.00	32.1373625	-103.3598348
Junior Mint Fed 135H LTP	12210.00	-9948.00	-80.00	404712.00	842755.00	32.1088908	-103.3598496
Junior Mint Fed 135H BHL	12210.50	-10043.00	-79.00	404617.00	842756.00	32.1086297	-103.3598492



Do Not Cross SL



Civitas Resources

Lea County, NM (NAD 83)
Junior Mint Fed Pad
Junior Mint Fed 135H

OH

Plan: Plan 1



Standard Plan Report

25 March, 2025

Total Report Version 1.70

COMPASS 5000.16 Build 97

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Project	Lea County, NM (NAD 83)	System Datum:	Mean Sea Level
Map System:	US State Plane 1983		
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Junior Mint Fed Pad				
Site Position:		Northing:	414,635.00 usft	Latitude:	32.1361627
From:	Map	Easting:	842,835.00 usft	Longitude:	-103.3593016
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "		

Well	Junior Mint Fed 135H					
Well Position	+N/-S	0.00 usft	Northing:	414,660.00 usft	Latitude:	32.1362315
	+E/-W	0.00 usft	Easting:	842,835.00 usft	Longitude:	-103.3593009
Position Uncertainty		0.50 usft	Wellhead Elevation:	usft	Ground Level:	3,220.00 usft
Grid Convergence:		0.52 °				

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM2025	7/15/2025	6.07	59.57	47,068.10000000

Design	Plan 1				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.00	0.00	0.00	180.45	

Survey Tool Program	Date	3/25/2025			
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
0.00	22,411.61	Plan 1 (OH)	MWD+HRGM+SAG+FDIF	OWSG MWD + HRGM + SAG + FDIR Correction	

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Plan Summary

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00	
1,000.00	3.00	339.77	999.91	4.91	-1.81	1.50	1.50	0.00	339.77	
1,250.43	3.00	339.77	1,250.00	17.21	-6.34	0.00	0.00	0.00	0.00	
1,550.47	7.50	339.77	1,548.70	42.96	-15.83	1.50	1.50	0.00	-0.01	
4,702.13	7.50	339.77	4,673.39	428.97	-158.13	0.00	0.00	0.00	0.00	
5,202.16	0.00	0.00	5,172.00	459.64	-169.43	1.50	-1.50	0.00	180.00	
11,581.16	0.00	0.00	11,551.00	459.64	-169.43	0.00	0.00	0.00	0.00	
12,476.17	89.50	179.51	12,123.94	-108.30	-164.54	10.00	10.00	20.06	179.51	
22,411.61	89.50	179.51	12,210.50	-10,043.00	-79.00	0.00	0.00	0.00	0.00	

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	Local Coordinates +E/-W (usft)	Map Coordinates Northing (usft)	Map Coordinates Easting (usft)	Geo Coordinates Latitude (°)	Geo Coordinates Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	414,660.00	842,835.00	32.1362315	-103.3593009	0.00	0.00	0.00	0.00
900.00	1.50	339.77	899.99	1.23	-0.45	414,661.23	842,834.55	32.1362348	-103.3593023	-1.22	1.50	1.50	0.00
1,000.00	3.00	339.77	999.91	4.91	-1.81	414,664.91	842,833.19	32.1362450	-103.3593066	-4.90	1.50	1.50	0.00
1,100.00	3.00	339.77	1,099.77	9.82	-3.62	414,669.82	842,831.38	32.1362585	-103.3593123	-9.79	0.00	0.00	0.00
1,200.00	3.00	339.77	1,199.63	14.73	-5.43	414,674.73	842,829.57	32.1362721	-103.3593180	-14.69	0.00	0.00	0.00
1,250.43	3.00	339.77	1,250.00	17.21	-6.34	414,677.21	842,828.66	32.1362789	-103.3593208	-17.16	0.00	0.00	0.00
1,300.00	3.74	339.77	1,299.48	19.95	-7.35	414,679.95	842,827.65	32.1362865	-103.3593240	-19.89	1.50	1.50	0.00
1,400.00	5.24	339.77	1,399.17	27.30	-10.06	414,687.30	842,824.94	32.1363067	-103.3593326	-27.22	1.50	1.50	0.00
1,500.00	6.74	339.77	1,498.62	37.09	-13.67	414,697.09	842,821.33	32.1363338	-103.3593439	-36.98	1.50	1.50	0.00
1,550.47	7.50	339.77	1,548.70	42.96	-15.83	414,702.96	842,819.17	32.1363499	-103.3593508	-42.84	1.50	1.50	0.00
1,600.00	7.50	339.77	1,597.81	49.03	-18.07	414,709.03	842,816.93	32.1363667	-103.3593578	-48.89	0.00	0.00	0.00
1,700.00	7.50	339.77	1,696.95	61.28	-22.59	414,721.28	842,812.41	32.1364004	-103.3593720	-61.10	0.00	0.00	0.00
1,800.00	7.50	339.77	1,796.09	73.53	-27.10	414,733.53	842,807.90	32.1364342	-103.3593863	-73.31	0.00	0.00	0.00
1,900.00	7.50	339.77	1,895.24	85.77	-31.62	414,745.77	842,803.38	32.1364680	-103.3594005	-85.52	0.00	0.00	0.00
2,000.00	7.50	339.77	1,994.38	98.02	-36.13	414,758.02	842,798.87	32.1365018	-103.3594147	-97.74	0.00	0.00	0.00
2,100.00	7.50	339.77	2,093.53	110.27	-40.65	414,770.27	842,794.35	32.1365356	-103.3594289	-109.95	0.00	0.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
2,200.00	7.50	339.77	2,192.67	122.52	-45.16	414,782.52	842,789.84	32.1365693	-103.3594432	-122.16	0.00	0.00	0.00
2,300.00	7.50	339.77	2,291.82	134.77	-49.67	414,794.77	842,785.33	32.1366031	-103.3594574	-134.37	0.00	0.00	0.00
2,400.00	7.50	339.77	2,390.96	147.01	-54.19	414,807.01	842,780.81	32.1366369	-103.3594716	-146.58	0.00	0.00	0.00
2,500.00	7.50	339.77	2,490.11	159.26	-58.70	414,819.26	842,776.30	32.1366707	-103.3594858	-158.80	0.00	0.00	0.00
2,600.00	7.50	339.77	2,589.25	171.51	-63.22	414,831.51	842,771.78	32.1367044	-103.3595001	-171.01	0.00	0.00	0.00
2,700.00	7.50	339.77	2,688.39	183.76	-67.73	414,843.76	842,767.27	32.1367382	-103.3595143	-183.22	0.00	0.00	0.00
2,800.00	7.50	339.77	2,787.54	196.00	-72.25	414,856.00	842,762.75	32.1367720	-103.3595285	-195.43	0.00	0.00	0.00
2,900.00	7.50	339.77	2,886.68	208.25	-76.76	414,868.25	842,758.24	32.1368058	-103.3595427	-207.64	0.00	0.00	0.00
3,000.00	7.50	339.77	2,985.83	220.50	-81.28	414,880.50	842,753.72	32.1368395	-103.3595570	-219.86	0.00	0.00	0.00
3,100.00	7.50	339.77	3,084.97	232.75	-85.79	414,892.75	842,749.21	32.1368733	-103.3595712	-232.07	0.00	0.00	0.00
3,200.00	7.50	339.77	3,184.12	245.00	-90.31	414,905.00	842,744.69	32.1369071	-103.3595854	-244.28	0.00	0.00	0.00
3,300.00	7.50	339.77	3,283.26	257.24	-94.82	414,917.24	842,740.18	32.1369409	-103.3595997	-256.49	0.00	0.00	0.00
3,400.00	7.50	339.77	3,382.40	269.49	-99.34	414,929.49	842,735.66	32.1369746	-103.3596139	-268.70	0.00	0.00	0.00
3,500.00	7.50	339.77	3,481.55	281.74	-103.85	414,941.74	842,731.15	32.1370084	-103.3596281	-280.92	0.00	0.00	0.00
3,600.00	7.50	339.77	3,580.69	293.99	-108.37	414,953.99	842,726.63	32.1370422	-103.3596423	-293.13	0.00	0.00	0.00
3,700.00	7.50	339.77	3,679.84	306.24	-112.88	414,966.24	842,722.12	32.1370760	-103.3596566	-305.34	0.00	0.00	0.00
3,800.00	7.50	339.77	3,778.98	318.48	-117.40	414,978.48	842,717.60	32.1371097	-103.3596708	-317.55	0.00	0.00	0.00
3,900.00	7.50	339.77	3,878.13	330.73	-121.91	414,990.73	842,713.09	32.1371435	-103.3596850	-329.76	0.00	0.00	0.00
4,000.00	7.50	339.77	3,977.27	342.98	-126.43	415,002.98	842,708.57	32.1371773	-103.3596992	-341.98	0.00	0.00	0.00
4,100.00	7.50	339.77	4,076.42	355.23	-130.94	415,015.23	842,704.06	32.1372111	-103.3597135	-354.19	0.00	0.00	0.00
4,200.00	7.50	339.77	4,175.56	367.47	-135.46	415,027.47	842,699.54	32.1372448	-103.3597277	-366.40	0.00	0.00	0.00
4,300.00	7.50	339.77	4,274.70	379.72	-139.97	415,039.72	842,695.03	32.1372786	-103.3597419	-378.61	0.00	0.00	0.00
4,400.00	7.50	339.77	4,373.85	391.97	-144.49	415,051.97	842,690.51	32.1373124	-103.3597561	-390.82	0.00	0.00	0.00
4,500.00	7.50	339.77	4,472.99	404.22	-149.00	415,064.22	842,686.00	32.1373462	-103.3597704	-403.04	0.00	0.00	0.00
4,600.00	7.50	339.77	4,572.14	416.47	-153.52	415,076.47	842,681.48	32.1373800	-103.3597846	-415.25	0.00	0.00	0.00
4,702.13	7.50	339.77	4,673.39	428.97	-158.13	415,088.97	842,676.87	32.1374144	-103.3597991	-427.72	0.00	0.00	0.00
4,800.00	6.03	339.77	4,770.58	439.79	-162.11	415,099.79	842,672.89	32.1374443	-103.3598117	-438.51	1.50	-1.50	0.00
4,900.00	4.53	339.77	4,870.15	448.43	-165.30	415,108.43	842,669.70	32.1374681	-103.3598217	-447.12	1.50	-1.50	0.00
5,000.00	3.03	339.77	4,969.93	454.62	-167.58	415,114.62	842,667.42	32.1374852	-103.3598289	-453.29	1.50	-1.50	0.00
5,100.00	1.53	339.77	5,069.85	458.36	-168.96	415,118.36	842,666.04	32.1374955	-103.3598333	-457.02	1.50	-1.50	0.00
5,202.16	0.00	0.00	5,172.00	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	1.50	-1.50	0.00
5,300.00	0.00	0.00	5,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
5,400.00	0.00	0.00	5,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
5,500.00	0.00	0.00	5,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
5,600.00	0.00	0.00	5,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
5,700.00	0.00	0.00	5,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
5,800.00	0.00	0.00	5,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,900.00	0.00	0.00	5,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,000.00	0.00	0.00	5,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,100.00	0.00	0.00	6,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,200.00	0.00	0.00	6,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,300.00	0.00	0.00	6,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,400.00	0.00	0.00	6,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,500.00	0.00	0.00	6,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,600.00	0.00	0.00	6,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,700.00	0.00	0.00	6,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,800.00	0.00	0.00	6,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
6,900.00	0.00	0.00	6,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,000.00	0.00	0.00	6,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,100.00	0.00	0.00	7,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,200.00	0.00	0.00	7,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,300.00	0.00	0.00	7,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,400.00	0.00	0.00	7,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,500.00	0.00	0.00	7,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,600.00	0.00	0.00	7,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,700.00	0.00	0.00	7,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,800.00	0.00	0.00	7,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
7,900.00	0.00	0.00	7,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,000.00	0.00	0.00	7,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,100.00	0.00	0.00	8,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,200.00	0.00	0.00	8,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,300.00	0.00	0.00	8,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,400.00	0.00	0.00	8,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,500.00	0.00	0.00	8,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,600.00	0.00	0.00	8,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,700.00	0.00	0.00	8,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,800.00	0.00	0.00	8,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
8,900.00	0.00	0.00	8,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,000.00	0.00	0.00	8,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,100.00	0.00	0.00	9,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,200.00	0.00	0.00	9,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,300.00	0.00	0.00	9,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,400.00	0.00	0.00	9,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,500.00	0.00	0.00	9,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,600.00	0.00	0.00	9,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,700.00	0.00	0.00	9,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,800.00	0.00	0.00	9,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
9,900.00	0.00	0.00	9,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,000.00	0.00	0.00	9,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,100.00	0.00	0.00	10,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,200.00	0.00	0.00	10,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,300.00	0.00	0.00	10,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,400.00	0.00	0.00	10,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,500.00	0.00	0.00	10,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,600.00	0.00	0.00	10,569.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,700.00	0.00	0.00	10,669.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,800.00	0.00	0.00	10,769.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
10,900.00	0.00	0.00	10,869.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,000.00	0.00	0.00	10,969.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,100.00	0.00	0.00	11,069.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,200.00	0.00	0.00	11,169.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,300.00	0.00	0.00	11,269.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,400.00	0.00	0.00	11,369.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,500.00	0.00	0.00	11,469.84	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,581.16	0.00	0.00	11,551.00	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.30	0.00	0.00	0.00
11,581.98	0.08	179.51	11,551.82	459.64	-169.43	415,119.64	842,665.57	32.1374990	-103.3598347	-458.29	10.00	10.00	0.00
Junior Mint Fed 135H KOP/FTP													
11,600.00	1.88	179.51	11,569.83	459.33	-169.43	415,119.33	842,665.57	32.1374982	-103.3598347	-457.99	10.00	10.00	0.00
11,650.00	6.88	179.51	11,619.67	455.51	-169.39	415,115.51	842,665.61	32.1374877	-103.3598348	-454.17	10.00	10.00	0.00
11,700.00	11.88	179.51	11,668.99	447.36	-169.32	415,107.36	842,665.68	32.1374653	-103.3598348	-446.02	10.00	10.00	0.00
11,750.00	16.88	179.51	11,717.40	434.94	-169.22	415,094.94	842,665.78	32.1374311	-103.3598348	-433.60	10.00	10.00	0.00
11,800.00	21.88	179.51	11,764.55	418.36	-169.07	415,078.36	842,665.93	32.1373855	-103.3598348	-417.01	10.00	10.00	0.00
11,850.00	26.88	179.51	11,810.08	397.72	-168.90	415,057.72	842,666.10	32.1373288	-103.3598348	-396.38	10.00	10.00	0.00
11,900.00	31.88	179.51	11,853.63	373.20	-168.69	415,033.20	842,666.31	32.1372614	-103.3598349	-371.86	10.00	10.00	0.00
11,950.00	36.88	179.51	11,894.88	344.97	-168.44	415,004.97	842,666.56	32.1371838	-103.3598349	-343.64	10.00	10.00	0.00
12,000.00	41.88	179.51	11,933.52	313.26	-168.17	414,973.26	842,666.83	32.1370966	-103.3598349	-311.93	10.00	10.00	0.00
12,050.00	46.88	179.51	11,969.24	278.30	-167.87	414,938.30	842,667.13	32.1370005	-103.3598350	-276.97	10.00	10.00	0.00
12,100.00	51.88	179.51	12,001.78	240.35	-167.54	414,900.35	842,667.46	32.1368962	-103.3598350	-239.03	10.00	10.00	0.00
12,150.00	56.88	179.51	12,030.89	199.72	-167.19	414,859.72	842,667.81	32.1367846	-103.3598351	-198.40	10.00	10.00	0.00
12,200.00	61.88	179.51	12,056.34	156.71	-166.82	414,816.71	842,668.18	32.1366663	-103.3598352	-155.39	10.00	10.00	0.00
12,250.00	66.88	179.51	12,077.95	111.64	-166.43	414,771.64	842,668.57	32.1365424	-103.3598352	-110.33	10.00	10.00	0.00
12,300.00	71.88	179.51	12,095.55	64.86	-166.03	414,724.86	842,668.97	32.1364138	-103.3598353	-63.55	10.00	10.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
12,350.00	76.88	179.51	12,109.01	16.72	-165.62	414,676.72	842,669.38	32.1362815	-103.3598354	-15.42	10.00	10.00	0.00
12,400.00	81.88	179.51	12,118.22	-32.41	-165.19	414,627.59	842,669.81	32.1361465	-103.3598354	33.70	10.00	10.00	0.00
12,450.00	86.88	179.51	12,123.11	-82.15	-164.77	414,577.85	842,670.23	32.1360098	-103.3598355	83.44	10.00	10.00	0.00
12,476.17	89.50	179.51	12,123.94	-108.30	-164.54	414,551.70	842,670.46	32.1359379	-103.3598355	109.59	10.00	10.00	0.00
12,500.00	89.50	179.51	12,124.14	-132.13	-164.33	414,527.87	842,670.67	32.1358724	-103.3598356	133.42	0.00	0.00	0.00
12,600.00	89.50	179.51	12,125.02	-232.12	-163.47	414,427.88	842,671.53	32.1355975	-103.3598357	233.40	0.00	0.00	0.00
12,700.00	89.50	179.51	12,125.89	-332.12	-162.61	414,327.88	842,672.39	32.1353227	-103.3598358	333.38	0.00	0.00	0.00
12,800.00	89.50	179.51	12,126.76	-432.11	-161.75	414,227.89	842,673.25	32.1350478	-103.3598360	433.37	0.00	0.00	0.00
12,900.00	89.50	179.51	12,127.63	-532.10	-160.89	414,127.90	842,674.11	32.1347730	-103.3598361	533.35	0.00	0.00	0.00
13,000.00	89.50	179.51	12,128.50	-632.09	-160.03	414,027.91	842,674.97	32.1344981	-103.3598363	633.33	0.00	0.00	0.00
13,100.00	89.50	179.51	12,129.37	-732.09	-159.17	413,927.91	842,675.83	32.1342232	-103.3598364	733.31	0.00	0.00	0.00
13,200.00	89.50	179.51	12,130.24	-832.08	-158.31	413,827.92	842,676.69	32.1339484	-103.3598365	833.30	0.00	0.00	0.00
13,300.00	89.50	179.51	12,131.11	-932.07	-157.45	413,727.93	842,677.55	32.1336735	-103.3598367	933.28	0.00	0.00	0.00
13,400.00	89.50	179.51	12,131.99	-1,032.06	-156.59	413,627.94	842,678.41	32.1333987	-103.3598368	1,033.26	0.00	0.00	0.00
13,500.00	89.50	179.51	12,132.86	-1,132.06	-155.73	413,527.94	842,679.27	32.1331238	-103.3598369	1,133.24	0.00	0.00	0.00
13,600.00	89.50	179.51	12,133.73	-1,232.05	-154.86	413,427.95	842,680.14	32.1328490	-103.3598371	1,233.23	0.00	0.00	0.00
13,700.00	89.50	179.51	12,134.60	-1,332.04	-154.00	413,327.96	842,681.00	32.1325741	-103.3598372	1,333.21	0.00	0.00	0.00
13,800.00	89.50	179.51	12,135.47	-1,432.03	-153.14	413,227.97	842,681.86	32.1322993	-103.3598374	1,433.19	0.00	0.00	0.00
13,900.00	89.50	179.51	12,136.34	-1,532.03	-152.28	413,127.97	842,682.72	32.1320244	-103.3598375	1,533.18	0.00	0.00	0.00
14,000.00	89.50	179.51	12,137.21	-1,632.02	-151.42	413,027.98	842,683.58	32.1317495	-103.3598376	1,633.16	0.00	0.00	0.00
14,100.00	89.50	179.51	12,138.08	-1,732.01	-150.56	412,927.99	842,684.44	32.1314747	-103.3598378	1,733.14	0.00	0.00	0.00
14,200.00	89.50	179.51	12,138.96	-1,832.00	-149.70	412,828.00	842,685.30	32.1311998	-103.3598379	1,833.12	0.00	0.00	0.00
14,300.00	89.50	179.51	12,139.83	-1,932.00	-148.84	412,728.00	842,686.16	32.1309250	-103.3598381	1,933.11	0.00	0.00	0.00
14,400.00	89.50	179.51	12,140.70	-2,031.99	-147.98	412,628.01	842,687.02	32.1306501	-103.3598382	2,033.09	0.00	0.00	0.00
14,500.00	89.50	179.51	12,141.57	-2,131.98	-147.12	412,528.02	842,687.88	32.1303753	-103.3598383	2,133.07	0.00	0.00	0.00
14,600.00	89.50	179.51	12,142.44	-2,231.97	-146.25	412,428.03	842,688.75	32.1301004	-103.3598385	2,233.05	0.00	0.00	0.00
14,700.00	89.50	179.51	12,143.31	-2,331.97	-145.39	412,328.03	842,689.61	32.1298256	-103.3598386	2,333.04	0.00	0.00	0.00
14,800.00	89.50	179.51	12,144.18	-2,431.96	-144.53	412,228.04	842,690.47	32.1295507	-103.3598387	2,433.02	0.00	0.00	0.00
14,900.00	89.50	179.51	12,145.05	-2,531.95	-143.67	412,128.05	842,691.33	32.1292758	-103.3598389	2,533.00	0.00	0.00	0.00
15,000.00	89.50	179.51	12,145.93	-2,631.94	-142.81	412,028.06	842,692.19	32.1290010	-103.3598390	2,632.98	0.00	0.00	0.00
15,100.00	89.50	179.51	12,146.80	-2,731.94	-141.95	411,928.06	842,693.05	32.1287261	-103.3598392	2,732.97	0.00	0.00	0.00
15,200.00	89.50	179.51	12,147.67	-2,831.93	-141.09	411,828.07	842,693.91	32.1284513	-103.3598393	2,832.95	0.00	0.00	0.00
15,300.00	89.50	179.51	12,148.54	-2,931.92	-140.23	411,728.08	842,694.77	32.1281764	-103.3598394	2,932.93	0.00	0.00	0.00
15,400.00	89.50	179.51	12,149.41	-3,031.91	-139.37	411,628.09	842,695.63	32.1279016	-103.3598396	3,032.91	0.00	0.00	0.00
15,500.00	89.50	179.51	12,150.28	-3,131.91	-138.51	411,528.09	842,696.49	32.1276267	-103.3598397	3,132.90	0.00	0.00	0.00
15,600.00	89.50	179.51	12,151.15	-3,231.90	-137.65	411,428.10	842,697.35	32.1273518	-103.3598398	3,232.88	0.00	0.00	0.00
15,700.00	89.50	179.51	12,152.02	-3,331.89	-136.78	411,328.11	842,698.22	32.1270770	-103.3598400	3,332.86	0.00	0.00	0.00
15,800.00	89.50	179.51	12,152.90	-3,431.88	-135.92	411,228.12	842,699.08	32.1268021	-103.3598401	3,432.85	0.00	0.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
15,900.00	89.50	179.51	12,153.77	-3,531.88	-135.06	411,128.12	842,699.94	32.1265273	-103.3598403	3,532.83	0.00	0.00	0.00
16,000.00	89.50	179.51	12,154.64	-3,631.87	-134.20	411,028.13	842,700.80	32.1262524	-103.3598404	3,632.81	0.00	0.00	0.00
16,100.00	89.50	179.51	12,155.51	-3,731.86	-133.34	410,928.14	842,701.66	32.1259776	-103.3598405	3,732.79	0.00	0.00	0.00
16,200.00	89.50	179.51	12,156.38	-3,831.85	-132.48	410,828.15	842,702.52	32.1257027	-103.3598407	3,832.78	0.00	0.00	0.00
16,300.00	89.50	179.51	12,157.25	-3,931.85	-131.62	410,728.15	842,703.38	32.1254279	-103.3598408	3,932.76	0.00	0.00	0.00
16,400.00	89.50	179.51	12,158.12	-4,031.84	-130.76	410,628.16	842,704.24	32.1251530	-103.3598409	4,032.74	0.00	0.00	0.00
16,500.00	89.50	179.51	12,158.99	-4,131.83	-129.90	410,528.17	842,705.10	32.1248781	-103.3598411	4,132.72	0.00	0.00	0.00
16,600.00	89.50	179.51	12,159.87	-4,231.82	-129.04	410,428.18	842,705.96	32.1246033	-103.3598412	4,232.71	0.00	0.00	0.00
16,700.00	89.50	179.51	12,160.74	-4,331.82	-128.17	410,328.18	842,706.83	32.1243284	-103.3598414	4,332.69	0.00	0.00	0.00
16,800.00	89.50	179.51	12,161.61	-4,431.81	-127.31	410,228.19	842,707.69	32.1240536	-103.3598415	4,432.67	0.00	0.00	0.00
16,900.00	89.50	179.51	12,162.48	-4,531.80	-126.45	410,128.20	842,708.55	32.1237787	-103.3598416	4,532.65	0.00	0.00	0.00
17,000.00	89.50	179.51	12,163.35	-4,631.79	-125.59	410,028.21	842,709.41	32.1235039	-103.3598418	4,632.64	0.00	0.00	0.00
17,100.00	89.50	179.51	12,164.22	-4,731.79	-124.73	409,928.21	842,710.27	32.1232290	-103.3598419	4,732.62	0.00	0.00	0.00
17,200.00	89.50	179.51	12,165.09	-4,831.78	-123.87	409,828.22	842,711.13	32.1229542	-103.3598420	4,832.60	0.00	0.00	0.00
17,300.00	89.50	179.51	12,165.96	-4,931.77	-123.01	409,728.23	842,711.99	32.1226793	-103.3598422	4,932.59	0.00	0.00	0.00
17,400.00	89.50	179.51	12,166.84	-5,031.76	-122.15	409,628.24	842,712.85	32.1224044	-103.3598423	5,032.57	0.00	0.00	0.00
17,500.00	89.50	179.51	12,167.71	-5,131.76	-121.29	409,528.24	842,713.71	32.1221296	-103.3598425	5,132.55	0.00	0.00	0.00
17,600.00	89.50	179.51	12,168.58	-5,231.75	-120.43	409,428.25	842,714.57	32.1218547	-103.3598426	5,232.53	0.00	0.00	0.00
17,700.00	89.50	179.51	12,169.45	-5,331.74	-119.56	409,328.26	842,715.44	32.1215799	-103.3598427	5,332.52	0.00	0.00	0.00
17,800.00	89.50	179.51	12,170.32	-5,431.73	-118.70	409,228.27	842,716.30	32.1213050	-103.3598429	5,432.50	0.00	0.00	0.00
17,900.00	89.50	179.51	12,171.19	-5,531.73	-117.84	409,128.27	842,717.16	32.1210302	-103.3598430	5,532.48	0.00	0.00	0.00
18,000.00	89.50	179.51	12,172.06	-5,631.72	-116.98	409,028.28	842,718.02	32.1207553	-103.3598431	5,632.46	0.00	0.00	0.00
18,100.00	89.50	179.51	12,172.93	-5,731.71	-116.12	408,928.29	842,718.88	32.1204804	-103.3598433	5,732.45	0.00	0.00	0.00
18,200.00	89.50	179.51	12,173.81	-5,831.70	-115.26	408,828.30	842,719.74	32.1202056	-103.3598434	5,832.43	0.00	0.00	0.00
18,300.00	89.50	179.51	12,174.68	-5,931.70	-114.40	408,728.30	842,720.60	32.1199307	-103.3598436	5,932.41	0.00	0.00	0.00
18,400.00	89.50	179.51	12,175.55	-6,031.69	-113.54	408,628.31	842,721.46	32.1196559	-103.3598437	6,032.39	0.00	0.00	0.00
18,500.00	89.50	179.51	12,176.42	-6,131.68	-112.68	408,528.32	842,722.32	32.1193810	-103.3598438	6,132.38	0.00	0.00	0.00
18,600.00	89.50	179.51	12,177.29	-6,231.67	-111.82	408,428.33	842,723.18	32.1191062	-103.3598440	6,232.36	0.00	0.00	0.00
18,700.00	89.50	179.51	12,178.16	-6,331.67	-110.96	408,328.33	842,724.04	32.1188313	-103.3598441	6,332.34	0.00	0.00	0.00
18,800.00	89.50	179.51	12,179.03	-6,431.66	-110.09	408,228.34	842,724.91	32.1185565	-103.3598442	6,432.33	0.00	0.00	0.00
18,900.00	89.50	179.51	12,179.90	-6,531.65	-109.23	408,128.35	842,725.77	32.1182816	-103.3598444	6,532.31	0.00	0.00	0.00
19,000.00	89.50	179.51	12,180.78	-6,631.64	-108.37	408,028.36	842,726.63	32.1180067	-103.3598445	6,632.29	0.00	0.00	0.00
19,100.00	89.50	179.51	12,181.65	-6,731.64	-107.51	407,928.36	842,727.49	32.1177319	-103.3598446	6,732.27	0.00	0.00	0.00
19,200.00	89.50	179.51	12,182.52	-6,831.63	-106.65	407,828.37	842,728.35	32.1174570	-103.3598448	6,832.26	0.00	0.00	0.00
19,300.00	89.50	179.51	12,183.39	-6,931.62	-105.79	407,728.38	842,729.21	32.1171822	-103.3598449	6,932.24	0.00	0.00	0.00
19,400.00	89.50	179.51	12,184.26	-7,031.61	-104.93	407,628.39	842,730.07	32.1169073	-103.3598451	7,032.22	0.00	0.00	0.00
19,500.00	89.50	179.51	12,185.13	-7,131.61	-104.07	407,528.39	842,730.93	32.1166325	-103.3598452	7,132.20	0.00	0.00	0.00

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Planned Survey

Measured Depth (usft)	INC (°)	AZI (°)	Vertical Depth (usft)	Local Coordinates +N/-S (usft)	+E/-W (usft)	Map Coordinates Northing (usft)	Easting (usft)	Geo Coordinates Latitude (°)	Longitude (°)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
19,600.00	89.50	179.51	12,186.00	-7,231.60	-103.21	407,428.40	842,731.79	32.1163576	-103.3598453	7,232.19	0.00	0.00	0.00
19,700.00	89.50	179.51	12,186.87	-7,331.59	-102.35	407,328.41	842,732.65	32.1160827	-103.3598455	7,332.17	0.00	0.00	0.00
19,800.00	89.50	179.51	12,187.75	-7,431.58	-101.48	407,228.42	842,733.52	32.1158079	-103.3598456	7,432.15	0.00	0.00	0.00
19,900.00	89.50	179.51	12,188.62	-7,531.58	-100.62	407,128.42	842,734.38	32.1155330	-103.3598457	7,532.13	0.00	0.00	0.00
20,000.00	89.50	179.51	12,189.49	-7,631.57	-99.76	407,028.43	842,735.24	32.1152582	-103.3598459	7,632.12	0.00	0.00	0.00
20,100.00	89.50	179.51	12,190.36	-7,731.56	-98.90	406,928.44	842,736.10	32.1149833	-103.3598460	7,732.10	0.00	0.00	0.00
20,200.00	89.50	179.51	12,191.23	-7,831.55	-98.04	406,828.45	842,736.96	32.1147085	-103.3598462	7,832.08	0.00	0.00	0.00
20,300.00	89.50	179.51	12,192.10	-7,931.55	-97.18	406,728.45	842,737.82	32.1144336	-103.3598463	7,932.07	0.00	0.00	0.00
20,400.00	89.50	179.51	12,192.97	-8,031.54	-96.32	406,628.46	842,738.68	32.1141588	-103.3598464	8,032.05	0.00	0.00	0.00
20,500.00	89.50	179.51	12,193.85	-8,131.53	-95.46	406,528.47	842,739.54	32.1138839	-103.3598466	8,132.03	0.00	0.00	0.00
20,600.00	89.50	179.51	12,194.72	-8,231.52	-94.60	406,428.48	842,740.40	32.1136090	-103.3598467	8,232.01	0.00	0.00	0.00
20,700.00	89.50	179.51	12,195.59	-8,331.52	-93.74	406,328.48	842,741.26	32.1133342	-103.3598468	8,332.00	0.00	0.00	0.00
20,800.00	89.50	179.51	12,196.46	-8,431.51	-92.88	406,228.49	842,742.12	32.1130593	-103.3598470	8,431.98	0.00	0.00	0.00
20,900.00	89.50	179.51	12,197.33	-8,531.50	-92.01	406,128.50	842,742.99	32.1127845	-103.3598471	8,531.96	0.00	0.00	0.00
21,000.00	89.50	179.51	12,198.20	-8,631.49	-91.15	406,028.51	842,743.85	32.1125096	-103.3598472	8,631.94	0.00	0.00	0.00
21,100.00	89.50	179.51	12,199.07	-8,731.49	-90.29	405,928.51	842,744.71	32.1122348	-103.3598474	8,731.93	0.00	0.00	0.00
21,200.00	89.50	179.51	12,199.94	-8,831.48	-89.43	405,828.52	842,745.57	32.1119599	-103.3598475	8,831.91	0.00	0.00	0.00
21,300.00	89.50	179.51	12,200.82	-8,931.47	-88.57	405,728.53	842,746.43	32.1116850	-103.3598477	8,931.89	0.00	0.00	0.00
21,400.00	89.50	179.51	12,201.69	-9,031.46	-87.71	405,628.54	842,747.29	32.1114102	-103.3598478	9,031.87	0.00	0.00	0.00
21,500.00	89.50	179.51	12,202.56	-9,131.46	-86.85	405,528.54	842,748.15	32.1111353	-103.3598479	9,131.86	0.00	0.00	0.00
21,600.00	89.50	179.51	12,203.43	-9,231.45	-85.99	405,428.55	842,749.01	32.1108605	-103.3598481	9,231.84	0.00	0.00	0.00
21,700.00	89.50	179.51	12,204.30	-9,331.44	-85.13	405,328.56	842,749.87	32.1105856	-103.3598482	9,331.82	0.00	0.00	0.00
21,800.00	89.50	179.51	12,205.17	-9,431.43	-84.27	405,228.57	842,750.73	32.1103108	-103.3598483	9,431.80	0.00	0.00	0.00
21,900.00	89.50	179.51	12,206.04	-9,531.43	-83.40	405,128.57	842,751.60	32.1100359	-103.3598485	9,531.79	0.00	0.00	0.00
22,000.00	89.50	179.51	12,206.91	-9,631.42	-82.54	405,028.58	842,752.46	32.1097610	-103.3598486	9,631.77	0.00	0.00	0.00
22,100.00	89.50	179.51	12,207.79	-9,731.41	-81.68	404,928.59	842,753.32	32.1094862	-103.3598487	9,731.75	0.00	0.00	0.00
22,200.00	89.50	179.51	12,208.66	-9,831.40	-80.82	404,828.60	842,754.18	32.1092113	-103.3598489	9,831.74	0.00	0.00	0.00
22,300.00	89.50	179.51	12,209.53	-9,931.40	-79.96	404,728.60	842,755.04	32.1089365	-103.3598490	9,931.72	0.00	0.00	0.00
22,316.61	89.50	179.51	12,209.67	-9,948.00	-79.82	404,712.00	842,755.18	32.1088908	-103.3598490	9,948.32	0.00	0.00	0.00
Junior Mint Fed 135H LTP													
22,400.00	89.50	179.51	12,210.40	-10,031.39	-79.10	404,628.61	842,755.90	32.1086616	-103.3598492	10,031.70	0.00	0.00	0.00
22,411.61	89.50	179.51	12,210.50	-10,043.00	-79.00	404,617.00	842,756.00	32.1086297	-103.3598492	10,043.31	0.00	0.00	0.00
Junior Mint Fed 135H BHL													

Total Directional Planned Survey Report



Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Well:	Junior Mint Fed 135H	North Reference:	Grid
Wellbore:	OH	Survey Calculation Method:	Minimum Curvature
Design:	Plan 1	Database:	.Total Directional Production DB

Design Targets

Target Name

- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- Shape									
Junior Mint Fed 135H	0.00	0.00	11,551.00	410.00	-169.00	415,070.00	842,666.00	32.1373626	-103.3598348
- plan misses target center by 49.64usft at 11581.20usft MD (11551.04 TVD, 459.64 N, -169.43 E)									
- Point									
Junior Mint Fed 135H	0.00	0.00	12,210.00	-9,948.00	-80.00	404,712.00	842,755.00	32.1088908	-103.3598496
- plan misses target center by 0.37usft at 22316.61usft MD (12209.67 TVD, -9948.00 N, -79.82 E)									
- Point									
Junior Mint Fed 135H	0.00	0.00	12,210.50	-10,043.00	-79.00	404,617.00	842,756.00	32.1086297	-103.3598492
- plan hits target center									
- Point									

Checked By: _____ Approved By: _____ Date: _____

Civitas Resources

Lea County, NM (NAD 83)
Junior Mint Fed Pad
Junior Mint Fed 135H

OH
Plan 1



Anticollision Report

Minimum Magnetic Interference Warning level is 50' center to center

25 March, 2025

Total Report Version 1.60

COMPASS 5000.16 Build 97

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Reference	Plan 1
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria
Interpolation Method:	MD + Stations Interval 100.00usft
Depth Range:	Unlimited
Results Limited by:	Maximum centre distance of 2,431.00usft
Warning Levels Evaluated at:	2.00 Sigma
Error Model:	ISCWSA
Scan Method:	Closest Approach 3D
Error Surface:	Pedal Curve
Casing Method:	Not applied

Well	Junior Mint Fed 135H					
Well Position	+N/-S	0.00 usft	Northing:	414,660.00 usft	Latitude:	32.1362315
	+E/-W	0.00 usft	Easting:	842,835.00 usft	Longitude:	-103.3593009
Position Uncertainty		0.50 usft	Wellhead Elevation:	usft	Ground Level:	3,220.00 usft
Grid Convergence:		0.52 °				

Survey Tool Program		Date	3/25/2025	
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description
0.00	22,411.61	Plan 1 (OH)	MWD+HRGM+SAG+FDIF OWSG	MWD + HRGM + SAG + FDIR Correction

Offset Listing								
Site Name	Ground LevelKB Height		Map Coordinates		Geographical Coordinates		Surface Uncertainty	
Offset Well			Northing	Easting	Latitude	Longitude	Site	Well
Civitas Resources - Junior Mint Fed Pad								
(O) Montera Federal 023H -	3,221.00	3,250.00	415,363.56	843,044.05	32.1381600	-103.3586050	0.00	0.00
(O) Montera Federal Com 601H -	3,226.90	3,253.00	415,439.30	841,823.90	32.1383985	-103.3625443	0.00	0.00
Junior Mint Fed 131H -	3,221.00	3,247.00	414,635.00	842,835.00	32.1361627	-103.3593016	0.00	0.50
Junior Mint Fed 132H -	3,220.00	3,246.00	414,820.00	842,835.00	32.1366712	-103.3592962	0.00	0.50
Junior Mint Fed 133H -	3,223.00	3,249.00	415,726.00	845,129.00	32.1391042	-103.3518593	0.00	0.50
Junior Mint Fed 137H -	3,220.00	3,246.00	414,845.00	842,835.00	32.1367399	-103.3592955	0.00	0.50
Junior Mint Fed 151H -	3,221.00	3,247.00	414,685.00	842,835.00	32.1363002	-103.3593001	0.00	0.50
Junior Mint Fed 152H -	3,220.00	3,246.00	414,870.00	842,835.00	32.1368087	-103.3592947	0.00	0.50
Junior Mint Fed 156H -	3,223.00	3,249.00	415,701.00	845,129.00	32.1390354	-103.3518600	0.00	0.50
Junior Mint Fed 211H -	3,221.00	3,247.00	414,660.00	842,810.00	32.1362321	-103.3593816	0.00	0.50
Junior Mint Fed 212H -	3,220.00	3,246.00	414,845.00	842,810.00	32.1367406	-103.3593762	0.00	0.50
Junior Mint Fed 213H -	3,222.00	3,248.00	415,701.00	845,154.00	32.1390348	-103.3517793	0.00	0.50
Junior Mint Fed 215H -	3,220.00	3,246.00	414,685.00	842,810.00	32.1363008	-103.3593809	0.00	0.50
Junior Mint Fed 216H -	3,223.00	3,249.00	415,751.00	845,129.00	32.1391729	-103.3518586	0.00	0.50
Junior Mint Fed 217H -	3,221.00	3,247.00	414,870.00	842,810.00	32.1368093	-103.3593755	0.00	0.50
Junior Mint Fed 221H -	3,221.00	3,247.00	414,635.00	842,810.00	32.1361634	-103.3593824	0.00	0.50
Junior Mint Fed 222H -	3,220.00	3,246.00	414,820.00	842,810.00	32.1366718	-103.3593769	0.00	0.50
Junior Mint Fed 223H -	3,223.00	3,249.00	415,751.00	845,154.00	32.1391723	-103.3517778	0.00	0.50

Summary						
Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Separation Between Ellipses (usft)	Warning Factor	Warning
Offset Well - Wellbore - Design						

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 2 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Summary

Site Name Offset Well - Wellbore - Design	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Separation Factor	Warning
Junior Mint Fed Pad						
(O) Montera Federal 023H - OH - OH	11,594.74	11,580.54	464.83	407.65	8.13	CC, ES
(O) Montera Federal 023H - OH - OH	11,600.00	11,585.77	464.84	407.65	8.13	SF
(O) Montera Federal Com 601H - OH - OH	5,177.11	5,155.29	890.19	860.73	30.22	CC
(O) Montera Federal Com 601H - OH - OH	5,400.00	5,378.02	890.68	860.20	29.23	ES
(O) Montera Federal Com 601H - OH - OH	11,100.00	11,059.65	936.72	881.44	16.95	SF
Junior Mint Fed 131H - OH - Plan 1	800.00	801.00	25.00	18.20	3.67	CC, ES
Junior Mint Fed 131H - OH - Plan 1	22,411.61	22,485.09	660.03	382.31	2.38	SF
Junior Mint Fed 132H - OH - Plan 1	1,754.36	1,741.57	152.44	141.95	14.53	CC
Junior Mint Fed 132H - OH - Plan 1	1,800.00	1,786.75	152.58	141.92	14.31	ES
Junior Mint Fed 132H - OH - Plan 1	22,411.61	22,428.60	660.03	380.32	2.36	SF
Junior Mint Fed 133H - OH - Plan 1	12,593.15	12,561.66	2,037.31	1,999.17	53.42	CC
Junior Mint Fed 133H - OH - Plan 1	22,411.61	22,379.08	2,042.34	1,751.38	7.02	ES, SF
Junior Mint Fed 137H - OH - Plan 1	300.00	300.00	185.00	181.04	46.69	CC
Junior Mint Fed 137H - OH - Plan 1	400.00	398.83	185.31	180.66	39.80	ES
Junior Mint Fed 137H - OH - Plan 1	22,411.61	22,512.90	1,320.07	1,039.58	4.71	SF
Junior Mint Fed 151H - OH - Plan 1	416.33	417.33	25.00	20.24	5.25	CC
Junior Mint Fed 151H - OH - Plan 1	500.00	501.00	25.00	19.73	4.74	ES
Junior Mint Fed 151H - OH - Plan 1	22,411.61	22,008.51	907.90	662.07	3.69	SF
Junior Mint Fed 152H - OH - Plan 1	300.00	300.00	210.00	206.04	53.00	CC, ES
Junior Mint Fed 152H - OH - Plan 1	22,411.61	21,935.47	723.39	499.36	3.23	SF
Junior Mint Fed 156H - OH - Plan 1	4,040.55	4,158.11	2,170.68	2,149.80	103.99	CC
Junior Mint Fed 156H - OH - Plan 1	22,411.61	21,915.80	2,275.39	1,992.52	8.04	ES, SF
Junior Mint Fed 211H - OH - Plan 1	216.33	217.33	25.00	21.74	7.66	CC
Junior Mint Fed 211H - OH - Plan 1	300.00	300.99	25.00	21.03	6.30	ES
Junior Mint Fed 211H - OH - Plan 1	22,411.61	22,892.95	1,011.65	752.30	3.90	SF
Junior Mint Fed 212H - OH - Plan 1	2,440.22	2,427.86	52.21	39.46	4.10	CC, ES
Junior Mint Fed 212H - OH - Plan 1	22,411.61	22,793.08	546.80	336.53	2.60	SF
Junior Mint Fed 213H - OH - Plan 1	11,639.41	11,724.62	1,707.03	1,672.94	50.08	CC
Junior Mint Fed 213H - OH - Plan 1	22,411.61	22,821.51	1,736.43	1,448.98	6.04	ES, SF
Junior Mint Fed 215H - OH - Plan 1	300.00	300.00	35.36	31.39	8.92	CC, ES
Junior Mint Fed 215H - OH - Plan 1	22,411.61	22,803.34	448.47	279.07	2.65	SF
Junior Mint Fed 216H - OH - Plan 1	11,600.00	11,603.91	2,417.04	2,384.87	75.14	ES
Junior Mint Fed 216H - OH - Plan 1	11,648.57	11,652.33	2,417.04	2,384.88	75.17	CC
Junior Mint Fed 216H - OH - Plan 1	12,250.00	12,330.09	2,430.36	2,397.82	74.69	SF
Junior Mint Fed 217H - OH - Plan 1	2,077.70	2,067.72	137.83	126.37	12.03	CC
Junior Mint Fed 217H - OH - Plan 1	2,100.00	2,089.65	137.89	126.35	11.95	ES
Junior Mint Fed 217H - OH - Plan 1	22,411.61	22,873.53	1,158.00	891.53	4.35	SF
Junior Mint Fed 221H - OH - Plan 1	812.15	813.21	35.26	28.40	5.14	CC, ES
Junior Mint Fed 221H - OH - Plan 1	1,000.00	1,000.92	37.19	29.52	4.85	SF
Junior Mint Fed 222H - OH - Plan 1	2,073.34	2,063.55	75.34	63.94	6.61	CC, ES
Junior Mint Fed 222H - OH - Plan 1	22,411.61	23,178.29	1,021.69	812.06	4.87	SF
Junior Mint Fed 223H - OH - Plan 1	11,642.47	11,688.95	1,936.02	1,902.26	57.34	CC
Junior Mint Fed 223H - OH - Plan 1	22,411.61	23,127.55	2,138.06	1,857.30	7.62	ES, SF

Offset Design: Junior Mint Fed Pad - (O) Montera Federal 023H - OH - OH

Offset Site Error: 0.00 usft

Survey Program: 100-3_Gyro-NS-CT_OWGS, 11638-3_MWD

Offset Well Error: 0.00 usft

Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
0.00	0.00	4.13	4.13	0.50	0.01		16.55	703.56	209.06	733.96			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 3 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Montera Federal 023H - OH - OH														Offset Site Error:	0.00 usft
Survey Program: 100-3_Gyro-NS-CT_OWSG, 11638-3_MWD														Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
100.00	100.00	107.25	107.24	0.98	0.15	16.55	703.33	208.96	733.72	732.59		1.13	648.717		
200.00	200.00	207.00	207.00	1.56	0.50	16.55	702.98	208.86	733.35	731.29		2.06	355.871		
300.00	300.00	308.44	308.44	1.98	0.86	16.54	702.50	208.64	732.85	730.01		2.84	258.371		
400.00	400.00	408.84	408.84	2.33	1.21	16.53	701.90	208.31	732.18	728.64		3.54	207.026		
500.00	500.00	509.20	509.19	2.63	1.56	16.48	701.46	207.53	731.53	727.34		4.19	174.464		
600.00	600.00	609.69	609.67	2.91	1.91	16.40	701.04	206.27	730.78	725.96		4.82	151.602		
700.00	700.00	708.89	708.86	3.16	2.26	16.31	700.62	205.06	730.03	724.61		5.42	134.654		
800.00	800.00	803.53	803.50	3.40	2.59	16.24	700.64	204.07	729.76	723.77		5.99	121.852		
838.54	838.53	839.41	839.37	3.51	2.71	36.45	700.85	203.70	729.71	723.49		6.22	117.397		
900.00	899.99	899.54	899.50	3.68	2.92	36.45	701.35	203.20	729.16	722.58		6.58	110.786		
1,000.00	999.91	999.22	999.17	3.94	3.27	36.59	702.17	202.52	726.60	719.42		7.17	101.284		
1,100.00	1,099.77	1,100.87	1,100.82	4.15	3.63	36.77	702.93	201.76	722.90	715.17		7.73	93.495		
1,200.00	1,199.63	1,201.04	1,200.99	4.35	3.98	36.93	703.63	200.87	719.13	710.85		8.28	86.853		
1,250.43	1,250.00	1,252.41	1,252.35	4.40	4.16	37.02	703.94	200.38	717.17	708.67		8.51	84.290		
1,300.00	1,299.48	1,301.89	1,301.83	4.45	4.33	37.14	704.20	199.89	714.96	706.22		8.73	81.881		
1,400.00	1,399.17	1,400.53	1,400.46	4.69	4.68	37.50	704.84	199.13	709.11	699.81		9.30	76.250		
1,500.00	1,498.62	1,500.00	1,499.93	4.93	5.02	38.02	705.43	198.46	701.21	691.34		9.87	71.067		
1,550.47	1,548.70	1,549.78	1,549.71	4.99	5.20	38.35	705.74	198.20	696.49	686.39		10.10	68.983		
1,600.00	1,597.81	1,598.56	1,598.48	5.05	5.37	38.65	706.03	197.96	691.62	681.30		10.32	67.018		
1,700.00	1,696.95	1,696.49	1,696.41	5.25	5.71	39.29	706.78	197.68	682.06	671.21		10.85	62.837		
1,800.00	1,796.09	1,795.14	1,795.06	5.44	6.06	39.96	707.57	197.68	672.73	661.34		11.39	59.059		
1,900.00	1,895.24	1,893.90	1,893.81	5.64	6.40	40.67	708.32	197.81	663.50	651.57		11.93	55.631		
2,000.00	1,994.38	1,993.05	1,992.96	5.83	6.75	41.42	709.06	198.19	654.45	641.99		12.46	52.508		
2,100.00	2,093.53	2,091.82	2,091.73	6.03	7.09	42.20	709.75	198.67	645.51	632.51		13.00	49.659		
2,200.00	2,192.67	2,191.55	2,191.46	6.22	7.44	43.01	710.44	199.17	636.70	623.16		13.54	47.035		
2,300.00	2,291.82	2,288.85	2,288.75	6.42	7.78	43.85	711.05	200.07	628.12	614.05		14.07	44.655		
2,400.00	2,390.96	2,386.67	2,386.56	6.61	8.12	44.75	711.78	201.31	619.93	605.33		14.60	42.471		
2,500.00	2,490.11	2,483.68	2,483.55	6.81	8.46	45.69	712.65	202.88	612.19	597.07		15.12	40.479		
2,600.00	2,589.25	2,578.88	2,578.72	7.00	8.79	46.66	713.83	204.89	605.15	589.51		15.64	38.683		
2,700.00	2,688.39	2,675.02	2,674.82	7.20	9.13	47.67	715.44	207.25	598.84	582.67		16.17	37.042		
2,800.00	2,787.54	2,787.81	2,787.56	7.39	9.53	48.89	717.27	210.14	592.85	576.11		16.75	35.404		
2,900.00	2,886.68	2,867.86	2,867.55	7.59	9.81	49.80	718.24	212.35	586.70	569.48		17.21	34.089		
3,000.00	2,985.83	2,966.02	2,965.62	7.78	10.16	50.90	721.05	215.58	582.46	564.72		17.74	32.837		
3,100.00	3,084.97	3,074.18	3,073.68	7.98	10.54	52.23	723.06	219.55	577.81	559.51		18.30	31.571		
3,200.00	3,184.12	3,172.18	3,171.61	8.17	10.89	53.51	723.90	223.19	572.63	553.80		18.83	30.413		
3,300.00	3,283.26	3,271.01	3,270.37	8.36	11.24	54.80	724.98	226.87	567.93	548.57		19.36	29.339		
3,400.00	3,382.40	3,381.05	3,380.36	8.56	11.63	56.22	725.59	229.89	562.54	542.61		19.92	28.236		
3,500.00	3,481.55	3,482.78	3,482.08	8.75	11.98	57.48	725.65	231.45	556.32	535.86		20.46	27.193		
3,600.00	3,580.69	3,582.96	3,582.25	8.95	12.33	58.71	725.66	232.32	549.92	528.93		20.99	26.201		
3,700.00	3,679.84	3,682.74	3,682.03	9.14	12.68	59.92	725.81	232.85	543.67	522.15		21.52	25.267		
3,800.00	3,778.98	3,781.70	3,780.99	9.33	13.03	61.14	725.83	233.22	537.47	515.43		22.04	24.384		
3,900.00	3,878.13	3,875.00	3,874.29	9.53	13.35	62.35	726.01	234.10	532.03	509.48		22.55	23.593		
4,000.00	3,977.27	3,965.09	3,964.32	9.72	13.67	63.72	726.07	237.20	528.46	505.41		23.04	22.933		
4,100.00	4,076.42	4,057.64	4,056.70	9.91	14.00	65.36	725.75	242.75	526.78	503.24		23.54	22.376		
4,200.00	4,175.56	4,158.66	4,157.46	10.11	14.37	67.28	724.89	249.94	526.08	502.00		24.07	21.852		
4,300.00	4,274.70	4,273.24	4,271.64	10.30	14.78	69.75	720.55	258.38	524.30	499.65		24.66	21.262		
4,400.00	4,373.85	4,405.54	4,403.63	10.49	15.24	72.40	712.70	261.16	517.77	492.52		25.25	20.506		
4,500.00	4,472.99	4,500.00	4,497.96	10.69	15.58	73.71	709.88	257.23	508.81	483.05		25.77	19.748		
4,600.00	4,572.14	4,581.76	4,579.60	10.88	15.87	74.44	711.75	253.32	502.71	476.45		26.26	19.142		
4,689.25	4,660.62	4,650.00	4,647.73	11.06	16.11	75.02	715.05	251.81	500.60	473.94		26.67	18.771		
4,700.00	4,671.28	4,658.25	4,655.97	11.08	16.14	75.11	715.43	251.91	500.63	473.91		26.72	18.739		
4,702.13	4,673.39	4,659.80	4,657.53	11.08	16.14	75.12	715.50	251.93	500.64	473.92		26.72	18.733		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 4 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Montera Federal 023H - OH - OH

Offset Site Error: 0.00 usft

Offset Well Error: 0.00 usft

Survey Program: 100-3_Gyro-NS-CT_OWSG, 11638-3_MWD

Rule Assigned:

Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
4,800.00	4,770.58	4,735.90	4,733.45	11.28	16.42	76.14	718.35	255.79	503.92	476.80	27.12	18.584	
4,900.00	4,870.15	4,829.40	4,826.49	11.48	16.77	77.58	720.12	264.87	511.01	483.44	27.58	18.531	
5,000.00	4,969.93	4,963.80	4,960.34	11.67	17.27	79.62	716.41	275.99	515.24	486.99	28.25	18.241	
5,100.00	5,069.85	5,079.64	5,075.99	11.85	17.67	80.84	711.47	280.11	515.49	486.72	28.77	17.918	
5,200.00	5,169.84	5,190.55	5,186.82	11.99	18.06	81.39	707.49	280.60	513.93	484.68	29.25	17.571	
5,202.16	5,172.00	5,192.85	5,189.12	12.00	18.06	81.16	707.42	280.57	513.87	484.62	29.26	17.563	
5,300.00	5,269.84	5,293.65	5,289.87	12.08	18.42	81.22	705.51	278.26	511.01	481.32	29.69	17.213	
5,400.00	5,369.84	5,392.60	5,388.77	12.17	18.77	81.16	704.60	275.43	508.07	477.94	30.12	16.866	
5,500.00	5,469.84	5,491.80	5,487.93	12.26	19.12	81.09	703.79	272.59	505.16	474.60	30.56	16.530	
5,600.00	5,569.84	5,590.12	5,586.21	12.34	19.47	81.02	703.01	269.98	502.46	471.46	31.00	16.211	
5,700.00	5,669.84	5,687.34	5,683.41	12.43	19.81	80.98	702.29	267.93	500.26	468.83	31.43	15.918	
5,800.00	5,769.84	5,786.71	5,782.77	12.52	20.16	80.95	701.57	266.21	498.38	466.52	31.86	15.641	
5,900.00	5,869.84	5,885.61	5,881.65	12.61	20.50	80.94	700.87	264.66	496.67	464.38	32.30	15.378	
6,000.00	5,969.84	5,985.15	5,981.18	12.69	20.85	80.92	700.22	263.17	495.06	462.32	32.73	15.123	
6,100.00	6,069.84	6,085.71	6,081.72	12.78	21.20	80.89	699.67	261.72	493.52	460.35	33.17	14.877	
6,200.00	6,169.84	6,185.27	6,181.27	12.87	21.55	80.93	698.69	260.53	492.00	458.39	33.61	14.639	
6,300.00	6,269.84	6,284.38	6,280.37	12.96	21.90	80.98	697.61	259.46	490.53	456.49	34.04	14.409	
6,400.00	6,369.84	6,383.15	6,379.13	13.04	22.24	81.04	696.55	258.68	489.32	454.84	34.48	14.193	
6,500.00	6,469.84	6,482.22	6,478.19	13.13	22.59	81.09	695.66	257.95	488.24	453.33	34.91	13.985	
6,600.00	6,569.84	6,581.96	6,577.93	13.22	22.93	81.14	694.88	257.35	487.33	451.99	35.35	13.787	
6,700.00	6,669.84	6,681.23	6,677.19	13.30	23.28	81.18	694.15	256.83	486.53	450.75	35.78	13.597	
6,800.00	6,769.84	6,781.63	6,777.59	13.39	23.63	81.23	693.38	256.29	485.68	449.46	36.22	13.410	
6,900.00	6,869.84	6,881.14	6,877.10	13.48	23.97	81.27	692.72	255.79	484.92	448.27	36.65	13.230	
7,000.00	6,969.84	6,979.68	6,975.63	13.56	24.31	81.32	692.09	255.53	484.38	447.30	37.09	13.061	
7,100.00	7,069.84	7,079.79	7,075.74	13.65	24.66	81.37	691.58	255.35	483.98	446.46	37.52	12.898	
7,200.00	7,169.84	7,180.03	7,175.98	13.74	25.01	81.42	690.91	255.19	483.52	445.56	37.96	12.738	
7,300.00	7,269.84	7,278.82	7,274.77	13.82	25.35	81.49	690.26	255.21	483.22	444.83	38.39	12.586	
7,400.00	7,369.84	7,377.98	7,373.93	13.91	25.69	81.55	689.80	255.28	483.07	444.24	38.83	12.441	
7,432.08	7,401.92	7,409.97	7,405.92	13.94	25.80	81.56	689.69	255.33	483.05	444.09	38.97	12.396	
7,500.00	7,469.84	7,477.58	7,473.53	14.00	26.04	81.59	689.51	255.46	483.08	443.82	39.26	12.304	
7,600.00	7,569.84	7,576.62	7,572.56	14.08	26.38	81.63	689.30	255.81	483.30	443.60	39.70	12.175	
7,700.00	7,669.84	7,675.30	7,671.24	14.17	26.73	81.65	689.24	256.01	483.45	443.32	40.13	12.048	
7,800.00	7,769.84	7,776.15	7,772.09	14.26	27.08	81.65	689.34	256.35	483.79	443.22	40.57	11.926	
7,900.00	7,869.84	7,874.68	7,870.62	14.34	27.42	81.63	689.78	256.81	484.42	443.42	41.00	11.816	
8,000.00	7,969.84	7,974.40	7,970.34	14.43	27.77	81.61	690.25	257.20	484.98	443.55	41.43	11.705	
8,100.00	8,069.84	8,073.61	8,069.54	14.51	28.11	81.57	690.94	257.90	485.93	444.06	41.87	11.607	
8,200.00	8,169.84	8,172.50	8,168.43	14.60	28.46	81.54	691.65	258.61	486.90	444.60	42.30	11.511	
8,300.00	8,269.84	8,273.18	8,269.11	14.69	28.81	81.50	692.44	259.40	487.97	445.23	42.74	11.418	
8,400.00	8,369.84	8,371.93	8,367.85	14.77	29.15	81.46	693.31	260.22	489.11	445.95	43.17	11.330	
8,500.00	8,469.84	8,471.12	8,467.03	14.86	29.50	81.41	694.24	261.08	490.33	446.73	43.60	11.245	
8,600.00	8,569.84	8,571.05	8,566.95	14.94	29.85	81.36	695.28	262.06	491.69	447.65	44.04	11.165	
8,700.00	8,669.84	8,671.30	8,667.18	15.03	30.20	81.32	696.21	263.08	493.03	448.55	44.48	11.085	
8,800.00	8,769.84	8,772.93	8,768.81	15.12	30.55	81.29	697.02	264.06	494.26	449.34	44.92	11.004	
8,900.00	8,869.84	8,870.96	8,866.83	15.20	30.90	81.26	697.90	265.00	495.53	450.18	45.35	10.927	
9,000.00	8,969.84	8,968.76	8,964.62	15.29	31.24	81.24	698.78	266.34	497.17	451.39	45.77	10.861	
9,100.00	9,069.84	9,066.43	9,062.27	15.37	31.58	81.32	699.21	268.48	499.29	453.09	46.20	10.807	
9,200.00	9,169.84	9,165.32	9,161.11	15.46	31.93	81.50	698.99	271.44	501.81	455.18	46.63	10.761	
9,300.00	9,269.84	9,265.83	9,261.57	15.54	32.29	81.69	698.77	274.43	504.33	457.26	47.07	10.714	
9,400.00	9,369.84	9,366.04	9,361.75	15.63	32.64	81.89	698.24	277.34	506.64	459.13	47.51	10.665	
9,500.00	9,469.84	9,472.02	9,467.68	15.71	33.02	82.15	697.17	280.15	508.50	460.54	47.96	10.602	
9,600.00	9,569.84	9,586.10	9,581.73	15.80	33.41	82.42	695.07	281.37	508.63	460.19	48.44	10.500	
9,700.00	9,669.84	9,688.31	9,683.90	15.89	33.77	82.58	692.96	280.35	506.79	457.91	48.88	10.368	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 5 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Monter Federal 023H - OH - OH

Offset Site Error: 0.00 usft

Offset Well Error: 0.00 usft

Survey Program: 100-3_Gyro-NS-CT_OWSG, 11638-3_MWD												Rule Assigned:			
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
9,800.00	9,769.84	9,788.74	9,784.31	15.97	34.12	62.72	690.92	279.14	504.80	455.48	49.32	10.236			
9,900.00	9,869.84	9,890.84	9,886.38	16.06	34.48	62.87	688.71	277.69	502.54	452.79	49.75	10.100			
10,000.00	9,969.84	9,991.50	9,986.99	16.14	34.83	63.04	686.21	276.02	499.93	449.74	50.19	9.961			
10,100.00	10,069.84	10,093.60	10,089.04	16.23	35.19	63.19	683.75	274.07	497.14	446.51	50.63	9.819			
10,200.00	10,169.84	10,192.47	10,187.87	16.31	35.54	63.23	682.15	271.57	494.15	443.09	51.06	9.678			
10,300.00	10,269.84	10,291.42	10,286.78	16.40	35.89	63.17	681.38	268.89	491.39	439.89	51.49	9.543			
10,400.00	10,369.84	10,389.70	10,385.03	16.48	36.24	63.11	680.75	266.52	488.95	437.02	51.92	9.417			
10,500.00	10,469.84	10,486.36	10,481.67	16.57	36.58	63.04	680.39	264.61	487.01	434.66	52.35	9.303			
10,600.00	10,569.84	10,583.26	10,578.55	16.65	36.92	62.94	680.67	263.22	485.86	433.08	52.78	9.206			
10,700.00	10,669.84	10,686.07	10,681.35	16.74	37.28	62.80	681.21	261.63	484.73	431.51	53.22	9.108			
10,800.00	10,769.84	10,787.46	10,782.72	16.82	37.63	62.66	681.37	259.47	482.91	429.24	53.66	8.999			
10,900.00	10,869.84	10,888.16	10,883.40	16.91	37.99	62.53	681.46	257.29	481.03	426.93	54.10	8.891			
11,000.00	10,969.84	10,989.85	10,985.05	16.99	38.35	62.38	681.62	254.80	478.93	424.39	54.54	8.781			
11,100.00	11,069.84	11,096.14	11,091.27	17.08	38.72	62.09	682.32	250.91	476.00	421.00	55.00	8.655			
11,200.00	11,169.84	11,195.13	11,190.04	17.16	39.08	61.43	685.48	245.24	472.46	417.02	55.44	8.522			
11,300.00	11,269.84	11,291.11	11,285.66	17.25	39.42	60.49	690.78	238.88	469.34	413.46	55.89	8.398			
11,400.00	11,369.84	11,386.93	11,381.21	17.33	39.75	59.63	695.92	233.80	467.41	411.09	56.33	8.298			
11,500.00	11,469.84	11,486.11	11,480.13	17.42	40.10	58.77	701.16	228.97	465.93	409.15	56.78	8.206			
11,581.16	11,551.00	11,566.71	11,560.53	17.48	40.39	58.09	705.34	225.21	464.91	407.78	57.14	8.137			
11,594.74	11,564.58	11,580.54	11,574.34	17.48	40.43	-121.54	705.99	224.61	464.83	407.65	57.18	8.129	CC, ES		
11,600.00	11,569.83	11,585.77	11,579.55	17.48	40.44	-121.60	706.23	224.38	464.84	407.65	57.19	8.128	SF		
11,650.00	11,619.67	11,635.25	11,628.95	17.49	40.54	-122.22	708.30	222.37	466.28	409.00	57.28	8.141			
11,700.00	11,668.99	11,681.62	11,675.26	17.51	40.54	-122.94	710.05	220.77	470.30	413.03	57.27	8.212			
11,750.00	11,717.40	11,726.91	11,720.50	17.51	40.55	-123.75	711.67	219.56	477.21	419.97	57.24	8.336			
11,800.00	11,764.55	11,772.00	11,765.56	17.52	40.55	-124.62	713.24	218.68	487.15	429.93	57.22	8.514			
11,850.00	11,810.08	11,803.00	11,796.53	17.52	40.55	-124.86	714.43	218.29	500.53	443.34	57.19	8.751			
11,900.00	11,853.63	11,835.00	11,828.47	17.52	40.55	-125.01	716.42	218.33	518.11	460.93	57.18	9.062			
11,950.00	11,894.88	11,866.00	11,859.34	17.53	40.55	-124.97	719.19	218.56	539.80	482.63	57.17	9.442			
12,000.00	11,933.52	11,886.77	11,879.97	17.53	40.56	-123.98	721.59	218.68	565.42	508.25	57.18	9.889			
12,050.00	11,969.24	11,898.00	11,891.09	17.53	40.56	-121.77	723.20	218.76	595.12	537.92	57.20	10.404			
12,100.00	12,001.78	11,915.38	11,908.20	17.53	40.56	-119.51	726.21	218.87	628.40	571.16	57.24	10.979			
12,150.00	12,030.89	11,929.00	11,921.52	17.53	40.56	-116.22	729.06	218.91	664.92	607.64	57.29	11.607			
12,200.00	12,056.34	11,929.00	11,921.52	17.53	40.56	-110.46	729.06	218.91	704.02	646.67	57.35	12.275			
12,250.00	12,077.95	11,929.00	11,921.52	17.54	40.56	-103.46	729.06	218.91	745.28	687.85	57.42	12.978			
12,300.00	12,095.55	11,938.34	11,930.60	17.55	40.56	-96.66	731.25	218.93	787.92	730.43	57.50	13.704			
12,350.00	12,109.01	11,938.82	11,931.07	17.56	40.56	-87.69	731.37	218.93	831.69	774.12	57.57	14.446			
12,400.00	12,118.22	11,929.00	11,921.52	17.58	40.56	-76.80	729.06	218.91	876.15	818.50	57.65	15.197			
12,450.00	12,123.11	11,929.00	11,921.52	17.60	40.56	-67.56	729.06	218.91	920.62	862.89	57.72	15.949			
12,476.17	12,123.94	11,929.00	11,921.52	17.61	40.56	-62.99	729.06	218.91	943.83	886.08	57.75	16.342			
12,500.00	12,124.14	11,929.00	11,921.52	17.62	40.56	-62.99	729.06	218.91	965.00	907.21	57.78	16.701			
12,600.00	12,125.02	11,929.00	11,921.52	17.69	40.56	-62.99	729.06	218.91	1,055.06	997.15	57.90	18.221			
12,700.00	12,125.89	11,929.00	11,921.52	17.79	40.56	-62.99	729.06	218.91	1,146.76	1,088.75	58.02	19.766			
12,800.00	12,126.76	11,913.40	11,906.26	17.95	40.56	-61.23	725.83	218.86	1,239.39	1,181.24	58.15	21.313			
12,900.00	12,127.63	11,898.00	11,891.09	18.21	40.56	-59.54	723.20	218.76	1,333.33	1,275.05	58.28	22.877			
13,000.00	12,128.50	11,898.00	11,891.09	18.61	40.56	-59.54	723.20	218.76	1,427.79	1,369.41	58.38	24.457			
13,100.00	12,129.37	11,898.00	11,891.09	19.18	40.56	-59.54	723.20	218.76	1,522.95	1,464.48	58.47	26.046			
13,200.00	12,130.24	11,898.00	11,891.09	19.87	40.56	-59.54	723.20	218.76	1,618.70	1,560.14	58.56	27.642			
13,300.00	12,131.11	11,898.00	11,891.09	20.66	40.56	-59.54	723.20	218.76	1,714.93	1,656.29	58.64	29.244			
13,400.00	12,131.99	11,898.00	11,891.09	21.53	40.56	-59.54	723.20	218.76	1,811.58	1,752.85	58.72	30.849			
13,500.00	12,132.86	11,898.00	11,891.09	22.45	40.56	-59.54	723.20	218.76	1,908.56	1,849.76	58.80	32.457			
13,600.00	12,133.73	11,885.05	11,878.27	23.43	40.56	-58.15	721.36	218.67	2,005.66	1,946.74	58.92	34.042			
13,700.00	12,134.60	11,882.43	11,875.66	24.44	40.56	-57.88	721.03	218.66	2,103.12	2,044.11	59.00	35.644			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 6 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Montera Federal 023H - OH - OH													
Survey Program: 100-3_Gyro-NS-CT_OWSSG, 11638-3_MWD												Offset Site Error:	0.00 usft
Reference												Offset Well Error:	0.00 usft
Measured	Vertical	Measured	Vertical	Semi Major Axis		Highside	Offset Wellbore Centre		Distance		Minimum	Separation	Warning
Depth	Depth	Depth	Depth	Reference	Offset		+N/-S	+E/-W	Between	Between	Separation	Factor	
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	(usft)	(usft)	Centres	Ellipses	(usft)		
									(usft)	(usft)			
13,800.00	12,135.47	11,879.99	11,873.25	25.50	40.56	-57.62	720.73	218.64	2,200.79	2,141.70	59.09	37.246	
13,900.00	12,136.34	11,866.00	11,859.34	26.58	40.55	-56.18	719.19	218.56	2,298.80	2,239.59	59.21	38.826	
14,000.00	12,137.21	11,866.00	11,859.34	27.69	40.55	-56.18	719.19	218.56	2,396.78	2,337.49	59.29	40.428	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 7 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Monter Federal Com 601H - OH - OH														Offset Site Error:	0.00 usft
Survey Program: 100-3_Gyro-NS-CT_OWGS, 11116-3_MWD														Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
0.00	0.00	6.67	6.67	0.50	0.01	-52.38	779.30	-1,011.10	1,276.57						
100.00	100.00	103.00	103.00	0.98	0.14	-52.39	779.25	-1,011.39	1,276.78	1,275.66	1.12	1,138.676			
200.00	200.00	209.31	209.31	1.56	0.51	-52.40	779.07	-1,011.54	1,276.78	1,274.71	2.07	616.138			
207.03	207.03	214.04	214.04	1.59	0.53	-52.40	779.06	-1,011.54	1,276.77	1,274.66	2.12	602.836			
300.00	300.00	303.29	303.29	1.98	0.84	-52.41	778.93	-1,011.98	1,277.05	1,274.23	2.82	452.736			
400.00	400.00	411.28	411.28	2.33	1.22	-52.44	778.47	-1,012.33	1,277.04	1,273.50	3.55	360.134			
500.00	500.00	510.54	510.53	2.63	1.57	-52.46	777.84	-1,012.38	1,276.70	1,272.50	4.20	304.163			
600.00	600.00	611.98	611.97	2.91	1.92	-52.49	777.20	-1,012.54	1,276.44	1,271.61	4.83	264.423			
700.00	700.00	712.08	712.07	3.16	2.27	-52.52	776.54	-1,012.59	1,276.08	1,270.65	5.43	234.976			
800.00	800.00	819.23	819.21	3.40	2.65	-52.54	775.61	-1,012.33	1,275.36	1,269.32	6.04	211.087			
900.00	899.99	919.26	919.24	3.68	3.00	-32.37	774.83	-1,011.84	1,273.38	1,266.73	6.65	191.370			
1,000.00	999.91	1,021.14	1,021.12	3.94	3.35	-32.48	774.65	-1,010.79	1,269.15	1,261.89	7.26	174.843			
1,100.00	1,099.77	1,119.62	1,119.58	4.15	3.70	-32.56	774.90	-1,009.33	1,263.71	1,255.91	7.81	161.878			
1,200.00	1,199.63	1,218.06	1,218.02	4.35	4.04	-32.64	775.16	-1,007.84	1,258.26	1,249.91	8.35	150.709			
1,250.43	1,250.00	1,269.83	1,269.77	4.40	4.22	-32.67	775.33	-1,007.04	1,255.51	1,246.93	8.58	146.346			
1,300.00	1,299.48	1,318.45	1,318.38	4.45	4.39	-32.74	775.51	-1,006.30	1,252.57	1,243.77	8.80	142.341			
1,400.00	1,399.17	1,419.30	1,419.23	4.69	4.74	-32.96	775.60	-1,004.91	1,244.93	1,235.55	9.38	132.731			
1,500.00	1,498.62	1,521.91	1,521.83	4.93	5.10	-33.28	775.42	-1,003.47	1,234.95	1,224.98	9.96	123.983			
1,550.47	1,548.70	1,572.31	1,572.23	4.99	5.28	-33.48	775.20	-1,002.82	1,229.06	1,218.86	10.19	120.573			
1,600.00	1,597.81	1,620.83	1,620.74	5.05	5.45	-33.63	775.03	-1,002.16	1,223.02	1,212.60	10.42	117.415			
1,700.00	1,696.95	1,720.50	1,720.40	5.25	5.80	-33.96	774.42	-1,000.89	1,210.75	1,199.80	10.96	110.504			
1,800.00	1,796.09	1,820.06	1,819.95	5.44	6.15	-34.30	773.68	-999.62	1,198.45	1,186.96	11.50	104.248			
1,900.00	1,895.24	1,922.00	1,921.87	5.64	6.51	-34.66	772.87	-998.19	1,186.06	1,174.02	12.04	98.484			
2,000.00	1,994.38	2,004.68	2,004.54	5.83	6.79	-35.01	771.56	-998.15	1,174.37	1,161.85	12.52	93.763			
2,100.00	2,093.53	2,100.37	2,100.20	6.03	7.13	-35.50	769.34	-999.58	1,163.58	1,150.53	13.05	89.162			
2,200.00	2,192.67	2,202.34	2,202.13	6.22	7.49	-36.03	766.91	-1,001.17	1,152.91	1,139.31	13.60	84.793			
2,300.00	2,291.82	2,302.97	2,302.71	6.42	7.84	-36.55	764.50	-1,002.47	1,142.10	1,127.96	14.14	80.779			
2,400.00	2,390.96	2,400.18	2,399.89	6.61	8.18	-37.06	762.24	-1,003.43	1,131.17	1,116.51	14.67	77.115			
2,500.00	2,490.11	2,505.40	2,505.09	6.81	8.55	-37.60	760.08	-1,003.97	1,120.08	1,104.86	15.22	73.571			
2,600.00	2,589.25	2,608.58	2,608.26	7.00	8.91	-38.10	758.37	-1,004.22	1,109.07	1,093.30	15.77	70.317			
2,700.00	2,688.39	2,703.77	2,703.43	7.20	9.25	-38.58	756.79	-1,004.20	1,097.91	1,081.61	16.29	67.381			
2,800.00	2,787.54	2,800.00	2,799.64	7.39	9.59	-39.10	754.66	-1,004.60	1,086.92	1,070.10	16.82	64.622			
2,900.00	2,886.68	2,895.71	2,895.22	7.59	9.93	-39.77	750.58	-1,006.94	1,076.73	1,059.38	17.35	62.070			
3,000.00	2,985.83	2,992.46	2,991.86	7.78	10.27	-40.46	746.39	-1,009.27	1,066.64	1,048.77	17.88	59.661			
3,100.00	3,084.97	3,094.08	3,093.38	7.98	10.63	-41.18	742.44	-1,011.43	1,056.69	1,038.26	18.42	57.352			
3,200.00	3,184.12	3,191.96	3,191.20	8.17	10.98	-41.83	739.33	-1,012.91	1,046.69	1,027.73	18.96	55.214			
3,300.00	3,283.26	3,296.25	3,295.36	8.36	11.35	-42.60	734.74	-1,014.81	1,036.53	1,017.02	19.51	53.121			
3,400.00	3,382.40	3,394.44	3,393.26	8.56	11.71	-43.50	727.93	-1,017.80	1,026.52	1,006.47	20.06	51.184			
3,500.00	3,481.55	3,498.57	3,497.17	8.75	12.09	-44.42	721.39	-1,020.12	1,016.32	995.71	20.62	49.297			
3,600.00	3,580.69	3,596.61	3,595.01	8.95	12.45	-45.29	715.41	-1,022.04	1,006.20	985.04	21.16	47.559			
3,700.00	3,679.84	3,698.12	3,696.31	9.14	12.82	-46.20	709.36	-1,024.01	996.37	974.66	21.71	45.898			
3,800.00	3,778.98	3,794.46	3,792.51	9.33	13.17	-47.02	704.35	-1,025.42	986.63	964.39	22.24	44.360			
3,900.00	3,878.13	3,894.64	3,892.56	9.53	13.54	-47.88	699.44	-1,026.63	977.00	954.21	22.78	42.879			
4,000.00	3,977.27	3,972.88	3,970.63	9.72	13.82	-48.64	694.75	-1,028.99	968.79	945.52	23.26	41.648			
4,100.00	4,076.42	4,057.48	4,054.96	9.91	14.14	-49.51	689.46	-1,032.93	962.34	938.59	23.76	40.510			
4,200.00	4,175.56	4,150.00	4,147.28	10.11	14.48	-50.38	685.44	-1,037.63	957.22	932.95	24.27	39.439			
4,300.00	4,274.70	4,244.81	4,241.96	10.30	14.81	-51.12	684.10	-1,042.15	952.97	928.19	24.78	38.454			
4,400.00	4,373.85	4,350.40	4,347.47	10.49	15.18	-51.78	685.27	-1,046.30	948.90	923.57	25.33	37.464			
4,500.00	4,472.99	4,495.59	4,492.56	10.69	15.69	-52.45	689.78	-1,047.25	942.63	916.62	26.01	36.240			
4,600.00	4,572.14	4,621.61	4,618.48	10.88	16.12	-53.21	689.05	-1,042.54	930.71	904.11	26.60	34.992			
4,700.00	4,671.28	4,716.39	4,713.15	11.08	16.45	-53.92	686.56	-1,039.01	918.60	891.49	27.11	33.879			
4,702.13	4,673.39	4,718.19	4,714.95	11.08	16.46	-53.93	686.45	-1,038.97	918.36	891.23	27.12	33.857			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 8 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Monter Federal Com 601H - OH - OH

Offset Site Error: 0.00 usft

Survey Program: 100-3_Gyro-NS-CT_OWSG, 11116-3_MWD

Offset Well Error: 0.00 usft

Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Distance Between Centres (usft)	Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
4,800.00	4,770.58	4,814.01	4,810.50	11.28	16.80	-54.79	679.39	-1,037.39	908.08	880.43	27.65	32.847	
4,900.00	4,870.15	4,914.53	4,910.69	11.48	17.17	-55.61	671.54	-1,035.59	899.06	870.89	28.17	31.911	
5,000.00	4,969.93	4,990.57	4,986.49	11.67	17.45	-56.15	665.65	-1,034.64	892.43	863.80	28.63	31.173	
5,100.00	5,069.85	5,076.79	5,072.47	11.85	17.77	-56.72	659.41	-1,036.39	890.44	861.35	29.09	30.611	
5,177.11	5,146.95	5,155.29	5,150.78	11.96	18.06	-57.14	654.15	-1,038.05	890.19	860.73	29.46	30.217	CC
5,200.00	5,169.84	5,176.41	5,171.85	11.99	18.14	-57.23	652.82	-1,038.45	890.25	860.69	29.56	30.114	
5,202.16	5,172.00	5,178.90	5,174.33	12.00	18.15	-77.48	652.66	-1,038.50	890.26	860.69	29.57	30.103	
5,300.00	5,269.84	5,278.90	5,274.13	12.08	18.52	-77.89	646.48	-1,039.98	890.38	860.36	30.02	29.656	
5,400.00	5,369.84	5,378.02	5,373.06	12.17	18.89	-78.28	640.57	-1,041.53	890.68	860.20	30.47	29.228	ES
5,500.00	5,469.84	5,460.90	5,455.76	12.26	19.19	-78.63	635.40	-1,043.23	891.55	860.68	30.87	28.883	
5,600.00	5,569.84	5,538.93	5,533.49	12.34	19.49	-79.01	630.24	-1,047.62	895.65	864.42	31.23	28.677	
5,700.00	5,669.84	5,638.88	5,633.04	12.43	19.87	-79.49	623.79	-1,053.86	900.60	868.91	31.69	28.421	
5,800.00	5,769.84	5,738.59	5,732.35	12.52	20.25	-79.96	617.33	-1,060.04	905.56	873.42	32.14	28.173	
5,900.00	5,869.84	5,838.19	5,831.57	12.61	20.63	-80.42	611.03	-1,066.06	910.45	877.85	32.60	27.931	
6,000.00	5,969.84	5,936.78	5,929.77	12.69	21.00	-80.87	604.76	-1,072.16	915.53	882.48	33.05	27.705	
6,100.00	6,069.84	6,037.37	6,029.99	12.78	21.39	-81.30	598.76	-1,078.31	920.66	887.16	33.50	27.481	
6,200.00	6,169.84	6,144.60	6,136.88	12.87	21.79	-81.73	592.61	-1,084.27	925.32	891.33	33.99	27.226	
6,300.00	6,269.84	6,251.63	6,243.61	12.96	22.20	-82.14	586.65	-1,089.48	929.36	894.90	34.47	26.962	
6,400.00	6,369.84	6,353.55	6,345.28	13.04	22.58	-82.53	580.91	-1,093.85	932.88	897.95	34.93	26.707	
6,500.00	6,469.84	6,455.01	6,446.50	13.13	22.96	-82.91	575.20	-1,097.87	936.09	900.70	35.39	26.451	
6,600.00	6,569.84	6,556.07	6,547.35	13.22	23.34	-83.25	569.90	-1,101.68	939.21	903.36	35.84	26.202	
6,700.00	6,669.84	6,656.26	6,647.33	13.30	23.72	-83.59	564.73	-1,105.38	942.29	905.99	36.30	25.961	
6,800.00	6,769.84	6,755.82	6,746.70	13.39	24.09	-83.92	559.65	-1,109.00	945.36	908.62	36.75	25.728	
6,900.00	6,869.84	6,886.10	6,876.81	13.48	24.57	-84.30	553.63	-1,110.89	946.14	908.84	37.30	25.366	
6,914.60	6,884.44	6,900.74	6,891.44	13.49	24.62	-84.34	552.98	-1,110.95	946.14	908.77	37.36	25.322	
7,000.00	6,969.84	6,975.00	6,965.64	13.56	24.89	-84.53	549.88	-1,111.44	946.39	908.68	37.71	25.098	
7,100.00	7,069.84	7,064.33	7,054.94	13.65	25.20	-84.58	549.16	-1,113.50	948.56	910.46	38.10	24.896	
7,200.00	7,169.84	7,165.42	7,156.00	13.74	25.54	-84.60	549.09	-1,115.78	950.79	912.26	38.53	24.675	
7,300.00	7,269.84	7,266.26	7,256.82	13.82	25.88	-84.62	549.00	-1,117.99	952.97	914.01	38.96	24.459	
7,400.00	7,369.84	7,366.66	7,357.20	13.91	26.23	-84.62	549.08	-1,120.01	954.98	915.59	39.39	24.243	
7,500.00	7,469.84	7,470.19	7,460.70	14.00	26.58	-84.64	549.04	-1,121.95	956.85	917.02	39.83	24.022	
7,600.00	7,569.84	7,570.59	7,561.09	14.08	26.92	-84.65	548.95	-1,123.61	958.48	918.22	40.26	23.807	
7,700.00	7,669.84	7,673.41	7,663.90	14.17	27.27	-84.65	549.15	-1,125.10	959.94	919.24	40.70	23.586	
7,800.00	7,769.84	7,770.60	7,761.08	14.26	27.60	-84.63	549.58	-1,126.41	961.32	920.20	41.12	23.380	
7,900.00	7,869.84	7,875.09	7,865.57	14.34	27.96	-84.61	550.04	-1,127.73	962.62	921.06	41.56	23.161	
8,000.00	7,969.84	7,976.94	7,967.41	14.43	28.30	-84.58	550.60	-1,128.82	963.74	921.74	42.00	22.948	
8,100.00	8,069.84	8,075.00	8,065.46	14.51	28.64	-84.57	550.92	-1,129.75	964.71	922.29	42.42	22.742	
8,200.00	8,169.84	8,162.77	8,153.21	14.60	28.94	-84.58	550.95	-1,131.34	966.53	923.72	42.81	22.579	
8,300.00	8,269.84	8,279.48	8,269.90	14.69	29.34	-84.57	551.27	-1,133.71	968.65	925.36	43.29	22.375	
8,400.00	8,369.84	8,401.33	8,391.74	14.77	29.76	-84.52	552.07	-1,133.38	968.49	924.70	43.79	22.118	
8,500.00	8,469.84	8,505.37	8,495.76	14.86	30.12	-84.46	553.00	-1,131.29	966.57	922.33	44.23	21.853	
8,600.00	8,569.84	8,605.35	8,595.71	14.94	30.47	-84.39	553.91	-1,129.12	964.49	919.83	44.66	21.595	
8,700.00	8,669.84	8,703.81	8,694.15	15.03	30.81	-84.33	554.67	-1,127.25	962.67	917.58	45.09	21.350	
8,800.00	8,769.84	8,804.02	8,794.34	15.12	31.16	-84.30	555.13	-1,125.47	960.96	915.44	45.52	21.110	
8,900.00	8,869.84	8,898.95	8,889.26	15.20	31.49	-84.27	555.43	-1,124.01	959.46	913.52	45.94	20.886	
9,000.00	8,969.84	8,996.23	8,986.53	15.29	31.82	-84.26	555.52	-1,122.85	958.28	911.92	46.36	20.671	
9,100.00	9,069.84	9,097.91	9,088.21	15.37	32.17	-84.26	555.40	-1,121.82	957.26	910.47	46.79	20.458	
9,200.00	9,169.84	9,196.48	9,186.77	15.46	32.51	-84.27	555.10	-1,120.80	956.20	908.98	47.22	20.251	
9,300.00	9,269.84	9,296.65	9,286.94	15.54	32.85	-84.30	554.53	-1,119.84	955.19	907.54	47.65	20.048	
9,400.00	9,369.84	9,391.95	9,382.22	15.63	33.18	-84.35	553.62	-1,119.33	954.55	906.49	48.06	19.861	
9,500.00	9,469.84	9,488.75	9,479.02	15.71	33.51	-84.41	552.57	-1,119.05	954.16	905.67	48.48	19.680	
9,600.00	9,569.84	9,590.94	9,581.21	15.80	33.86	-84.48	551.31	-1,118.76	953.76	904.83	48.92	19.495	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 9 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Monter Federal Com 601H - OH - OH

Offset Site Error: 0.00 usft

Offset Well Error: 0.00 usft

Survey Program: 100-3_Gyro-NS-CT_OWSG, 11116-3_MWD							Rule Assigned:				Offset Well Error:		0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)
9,700.00	9,669.84	9,690.12	9,680.38	15.89	34.21	-84.55	550.20	-1,118.52	953.41	904.05	49.35	19.319	SF
9,800.00	9,769.84	9,789.03	9,779.29	15.97	34.55	-84.60	549.25	-1,118.29	953.08	903.30	49.78	19.146	
9,900.00	9,869.84	9,892.69	9,882.94	16.06	34.90	-84.66	548.37	-1,118.02	952.75	902.53	50.22	18.971	
10,000.00	9,969.84	9,995.49	9,985.74	16.14	35.26	-84.69	547.78	-1,117.31	952.01	901.35	50.66	18.792	
10,100.00	10,069.84	10,093.88	10,084.12	16.23	35.60	-84.67	547.98	-1,116.58	951.29	900.20	51.09	18.621	
10,200.00	10,169.84	10,194.13	10,184.36	16.31	35.94	-84.64	548.52	-1,115.95	950.72	899.20	51.52	18.454	
10,300.00	10,269.84	10,298.61	10,288.83	16.40	36.31	-84.55	549.76	-1,114.70	949.63	897.66	51.97	18.274	
10,400.00	10,369.84	10,399.97	10,390.17	16.48	36.67	-84.45	551.34	-1,113.26	948.37	895.96	52.41	18.096	
10,500.00	10,469.84	10,507.86	10,498.02	16.57	37.05	-84.32	553.32	-1,111.02	946.48	893.61	52.87	17.902	
10,600.00	10,569.84	10,607.61	10,597.72	16.65	37.40	-84.19	555.16	-1,108.61	944.26	890.95	53.31	17.713	
10,700.00	10,669.84	10,711.00	10,701.06	16.74	37.77	-84.05	557.24	-1,106.02	941.97	888.22	53.76	17.523	
10,800.00	10,769.84	10,813.00	10,802.98	16.82	38.14	-83.87	559.86	-1,102.88	939.18	884.97	54.20	17.327	
10,900.00	10,869.84	10,912.72	10,902.60	16.91	38.49	-83.67	562.86	-1,099.87	936.51	881.86	54.65	17.137	
10,988.02	10,957.85	10,975.00	10,964.85	16.98	38.72	-83.57	564.42	-1,098.47	934.93	879.97	54.95	17.013	
11,000.00	10,969.84	10,983.35	10,973.20	16.99	38.75	-83.56	564.54	-1,098.47	934.95	879.96	54.99	17.001	
11,100.00	11,069.84	11,059.65	11,049.47	17.08	38.94	-83.48	565.95	-1,099.69	936.72	881.44	55.28	16.946	
11,200.00	11,169.84	11,138.99	11,128.72	17.16	39.05	-83.36	568.22	-1,102.58	940.68	885.23	55.45	16.964	
11,300.00	11,269.84	11,218.55	11,208.10	17.25	39.05	-83.25	570.65	-1,107.45	947.06	891.53	55.53	17.055	
11,400.00	11,369.84	11,382.58	11,371.95	17.33	39.06	-83.27	571.13	-1,114.09	951.23	895.58	55.65	17.093	
11,500.00	11,469.84	11,480.42	11,469.77	17.42	39.07	-83.36	569.64	-1,114.50	951.48	895.73	55.75	17.068	
11,581.16	11,551.00	11,563.65	11,553.00	17.48	39.08	-83.43	568.56	-1,115.24	952.07	896.26	55.82	17.057	
11,600.00	11,569.83	11,583.52	11,572.87	17.48	39.09	97.05	568.22	-1,115.37	952.20	896.38	55.82	17.058	
11,650.00	11,619.67	11,633.85	11,623.19	17.49	39.10	97.15	567.22	-1,115.68	952.86	897.06	55.80	17.076	
11,700.00	11,668.99	11,683.42	11,672.73	17.51	39.11	97.44	566.14	-1,115.99	954.09	898.33	55.77	17.109	
11,750.00	11,717.40	11,732.05	11,721.35	17.51	39.12	97.91	565.02	-1,116.30	955.97	900.26	55.72	17.158	
11,800.00	11,764.55	11,776.62	11,765.91	17.52	39.13	98.45	564.02	-1,116.62	958.69	903.03	55.66	17.225	
11,850.00	11,810.08	11,817.93	11,807.22	17.52	39.14	99.03	563.25	-1,117.08	962.58	906.99	55.59	17.316	
11,900.00	11,853.63	11,859.37	11,848.65	17.52	39.15	99.68	562.78	-1,117.68	967.82	912.30	55.52	17.432	
11,950.00	11,894.88	11,900.41	11,889.65	17.53	39.16	100.44	564.23	-1,117.87	974.49	919.04	55.45	17.573	
12,000.00	11,933.52	11,935.16	11,924.26	17.53	39.16	101.02	567.33	-1,117.60	982.97	927.57	55.40	17.743	
12,050.00	11,969.24	11,940.00	11,929.07	17.53	39.17	100.12	567.89	-1,117.53	993.96	938.60	55.36	17.956	
12,100.00	12,001.78	11,961.17	11,949.96	17.53	39.17	99.77	571.25	-1,117.29	1,007.46	952.12	55.34	18.204	
12,150.00	12,030.89	11,968.76	11,957.38	17.53	39.17	98.46	572.83	-1,117.25	1,023.86	968.51	55.35	18.496	
12,200.00	12,056.34	11,987.00	11,975.02	17.53	39.18	97.48	577.48	-1,117.21	1,043.12	987.72	55.40	18.829	
12,250.00	12,077.95	11,987.00	11,975.02	17.54	39.18	95.13	577.48	-1,117.21	1,064.46	1,008.99	55.47	19.188	
12,300.00	12,095.55	11,987.00	11,975.02	17.55	39.18	92.46	577.48	-1,117.21	1,088.03	1,032.45	55.58	19.576	
12,350.00	12,109.01	11,987.00	11,975.02	17.56	39.18	89.50	577.48	-1,117.21	1,113.50	1,057.79	55.71	19.988	
12,400.00	12,118.22	11,987.00	11,975.02	17.58	39.18	86.29	577.48	-1,117.21	1,140.56	1,084.70	55.86	20.420	
12,450.00	12,123.11	11,987.00	11,975.02	17.60	39.18	82.86	577.48	-1,117.21	1,168.90	1,112.88	56.02	20.867	
12,476.17	12,123.94	11,987.00	11,975.02	17.61	39.18	81.00	577.48	-1,117.21	1,184.15	1,128.04	56.10	21.106	
12,500.00	12,124.14	11,987.00	11,975.02	17.62	39.18	81.00	577.48	-1,117.21	1,198.29	1,142.11	56.19	21.327	
12,600.00	12,125.02	11,967.72	11,956.37	17.69	39.17	79.91	572.61	-1,117.25	1,260.21	1,203.65	56.57	22.279	
12,700.00	12,125.89	11,963.21	11,951.96	17.79	39.17	79.65	571.65	-1,117.28	1,327.00	1,270.05	56.94	23.303	
12,800.00	12,126.76	11,959.33	11,948.16	17.95	39.17	79.42	570.89	-1,117.31	1,397.69	1,340.38	57.32	24.386	
12,900.00	12,127.63	11,940.00	11,929.07	18.21	39.17	78.31	567.89	-1,117.53	1,472.21	1,414.52	57.69	25.519	
13,000.00	12,128.50	11,940.00	11,929.07	18.61	39.17	78.31	567.89	-1,117.53	1,549.00	1,490.97	58.03	26.695	
13,100.00	12,129.37	11,940.00	11,929.07	19.18	39.17	78.31	567.89	-1,117.53	1,628.31	1,569.97	58.34	27.912	
13,200.00	12,130.24	11,940.00	11,929.07	19.87	39.17	78.31	567.89	-1,117.53	1,709.79	1,651.16	58.63	29.164	
13,300.00	12,131.11	11,940.00	11,929.07	20.66	39.17	78.31	567.89	-1,117.53	1,793.14	1,734.25	58.90	30.446	
13,400.00	12,131.99	11,940.00	11,929.07	21.53	39.17	78.31	567.89	-1,117.53	1,878.12	1,818.98	59.15	31.754	
13,500.00	12,132.86	11,940.00	11,929.07	22.45	39.17	78.31	567.89	-1,117.53	1,964.52	1,905.14	59.38	33.085	
13,600.00	12,133.73	11,940.00	11,929.07	23.43	39.17	78.31	567.89	-1,117.53	2,052.15	1,992.56	59.59	34.436	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 10 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - (O) Montera Federal Com 601H - OH - OH													
Survey Program: 100-3_Gyro-NS-CT_OWSSG, 11116-3_MWD												Offset Site Error:	0.00 usft
Reference												Offset Well Error:	0.00 usft
Measured	Vertical	Measured	Vertical	Semi Major Axis		Highside	Offset Wellbore Centre		Distance		Minimum	Separation	Warning
Depth	Depth	Depth	Depth	Reference	Offset		+N/-S	+E/-W	Between	Between	Separation		
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	(usft)	(usft)	Centres	Ellipses	(usft)	Factor	
									(usft)	(usft)			
13,700.00	12,134.60	11,940.00	11,929.07	24.44	39.17	78.31	567.89	-1,117.53	2,140.87	2,081.07	59.80	35.803	
13,800.00	12,135.47	11,940.00	11,929.07	25.50	39.17	78.31	567.89	-1,117.53	2,230.54	2,170.55	59.99	37.185	
13,900.00	12,136.34	11,940.00	11,929.07	26.58	39.17	78.31	567.89	-1,117.53	2,321.05	2,260.89	60.16	38.579	
14,000.00	12,137.21	11,940.00	11,929.07	27.69	39.17	78.31	567.89	-1,117.53	2,412.32	2,351.99	60.33	39.984	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 11 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 131H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Rule Assigned:	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
0.00	0.00	1.00	1.00	0.50	0.50	180.00	-25.00	0.00	25.00	25.00					
100.00	100.00	101.00	101.00	0.98	0.99	180.00	-25.00	0.00	25.00	23.03	1.97	12.706			
200.00	200.00	201.00	201.00	1.56	1.57	180.00	-25.00	0.00	25.00	21.87	3.13	7.996			
300.00	300.00	301.00	301.00	1.98	1.98	180.00	-25.00	0.00	25.00	21.03	3.97	6.304			
400.00	400.00	401.00	401.00	2.33	2.33	180.00	-25.00	0.00	25.00	20.34	4.66	5.363			
500.00	500.00	501.00	501.00	2.63	2.64	180.00	-25.00	0.00	25.00	19.73	5.27	4.742			
600.00	600.00	601.00	601.00	2.91	2.91	180.00	-25.00	0.00	25.00	19.18	5.82	4.294			
700.00	700.00	701.00	701.00	3.16	3.17	180.00	-25.00	0.00	25.00	18.67	6.33	3.949			
800.00	800.00	801.00	801.00	3.40	3.40	180.00	-25.00	0.00	25.00	18.20	6.80	3.675	CC, ES		
900.00	899.99	900.99	900.99	3.68	3.63	-160.75	-25.00	0.00	26.23	18.93	7.30	3.594			
1,000.00	999.91	1,000.91	1,000.91	3.94	3.84	-163.21	-25.00	0.00	29.97	22.19	7.77	3.856			
1,100.00	1,099.77	1,100.77	1,100.77	4.15	4.04	-165.69	-25.00	0.00	35.01	26.83	8.18	4.280			
1,200.00	1,199.63	1,200.63	1,200.63	4.35	4.23	-167.53	-25.00	0.00	40.10	31.53	8.58	4.676			
1,250.43	1,250.00	1,251.00	1,251.00	4.40	4.33	-168.30	-25.00	0.00	42.68	33.96	8.72	4.894			
1,300.00	1,299.48	1,300.48	1,300.48	4.45	4.42	-169.03	-25.00	0.00	45.54	36.67	8.87	5.135			
1,400.00	1,399.17	1,400.17	1,400.17	4.69	4.60	-170.62	-25.00	0.00	53.26	43.96	9.29	5.731			
1,500.00	1,498.62	1,500.36	1,500.36	4.93	4.77	-171.55	-24.56	-0.76	62.99	53.29	9.70	6.493			
1,550.47	1,548.70	1,550.92	1,550.90	4.99	4.86	-171.62	-24.00	-1.72	68.45	58.61	9.84	6.953			
1,600.00	1,597.81	1,600.57	1,600.53	5.05	4.94	-171.47	-23.24	-3.04	73.84	63.86	9.98	7.398			
1,700.00	1,696.95	1,700.97	1,700.84	5.25	5.10	-170.56	-21.04	-6.84	83.86	73.52	10.34	8.112			
1,800.00	1,796.09	1,801.55	1,801.22	5.44	5.27	-169.01	-17.95	-12.17	92.78	82.09	10.69	8.677			
1,900.00	1,895.24	1,902.23	1,901.59	5.64	5.43	-166.93	-13.98	-19.04	100.69	89.64	11.05	9.116			
2,000.00	1,994.38	2,002.96	2,001.85	5.83	5.60	-164.40	-9.12	-27.43	107.69	96.29	11.40	9.449			
2,100.00	2,093.53	2,103.68	2,101.91	6.03	5.77	-161.43	-3.38	-37.35	113.94	102.19	11.75	9.699			
2,200.00	2,192.67	2,204.31	2,201.67	6.22	5.94	-158.05	3.24	-48.78	119.60	107.51	12.10	9.887			
2,300.00	2,291.82	2,304.81	2,301.06	6.42	6.11	-154.25	10.72	-61.70	124.90	112.45	12.45	10.034			
2,400.00	2,390.96	2,405.11	2,399.96	6.61	6.28	-150.07	19.06	-76.10	130.07	117.27	12.80	10.162			
2,500.00	2,490.11	2,505.15	2,498.31	6.81	6.46	-145.52	28.23	-91.96	135.37	122.22	13.15	10.292			
2,600.00	2,589.25	2,604.86	2,596.00	7.00	6.64	-140.67	38.24	-109.23	141.11	127.60	13.51	10.444			
2,700.00	2,688.39	2,704.20	2,692.96	7.20	6.83	-135.58	49.05	-127.91	147.58	133.71	13.87	10.640			
2,800.00	2,787.54	2,803.06	2,789.20	7.39	6.99	-130.52	60.38	-147.49	155.10	140.90	14.19	10.926			
2,900.00	2,886.68	2,901.87	2,885.38	7.59	7.20	-125.95	71.73	-167.10	163.72	149.15	14.57	11.238			
3,000.00	2,985.83	3,000.67	2,981.55	7.78	7.43	-121.85	83.08	-186.70	173.28	158.33	14.95	11.594			
3,100.00	3,084.97	3,099.48	3,077.73	7.98	7.66	-118.20	94.43	-206.31	183.64	168.31	15.33	11.980			
3,200.00	3,184.12	3,198.29	3,173.90	8.17	7.90	-114.93	105.78	-225.92	194.67	178.95	15.72	12.386			
3,300.00	3,283.26	3,297.09	3,270.07	8.36	8.14	-112.03	117.13	-245.52	206.26	190.15	16.11	12.805			
3,400.00	3,382.40	3,395.90	3,366.25	8.56	8.39	-109.43	128.48	-265.13	218.32	201.82	16.50	13.229			
3,500.00	3,481.55	3,494.70	3,462.42	8.75	8.64	-107.11	139.83	-284.73	230.78	213.88	16.90	13.655			
3,600.00	3,580.69	3,593.51	3,558.60	8.95	8.89	-105.03	151.18	-304.34	243.58	226.28	17.30	14.079			
3,700.00	3,679.84	3,692.32	3,654.77	9.14	9.15	-103.16	162.53	-323.95	256.67	238.96	17.70	14.497			
3,800.00	3,778.98	3,791.12	3,750.94	9.33	9.41	-101.46	173.88	-343.55	270.00	251.89	18.11	14.909			
3,900.00	3,878.13	3,889.93	3,847.12	9.53	9.67	-99.93	185.23	-363.16	283.54	265.02	18.52	15.313			
4,000.00	3,977.27	3,988.73	3,943.29	9.72	9.94	-98.54	196.58	-382.76	297.26	278.34	18.93	15.707			
4,100.00	4,076.42	4,087.54	4,039.47	9.91	10.21	-97.27	207.93	-402.37	311.14	291.81	19.34	16.092			
4,200.00	4,175.56	4,186.35	4,135.64	10.11	10.48	-96.11	219.28	-421.98	325.16	305.41	19.75	16.467			
4,300.00	4,274.70	4,285.15	4,231.81	10.30	10.76	-95.05	230.63	-441.58	339.30	319.14	20.16	16.832			
4,400.00	4,373.85	4,383.96	4,327.99	10.49	11.03	-94.07	241.98	-461.19	353.54	332.97	20.57	17.186			
4,500.00	4,472.99	4,482.76	4,424.16	10.69	11.31	-93.16	253.33	-480.79	367.88	346.90	20.99	17.530			
4,600.00	4,572.14	4,581.57	4,520.33	10.88	11.59	-92.33	264.68	-500.40	382.30	360.90	21.40	17.864			
4,700.00	4,671.28	4,680.38	4,616.51	11.08	11.87	-91.55	276.03	-520.01	396.80	374.98	21.82	18.186			
4,702.13	4,673.39	4,682.48	4,618.56	11.08	11.87	-91.54	276.27	-520.42	397.11	375.28	21.83	18.192			
4,800.00	4,770.58	4,779.11	4,712.61	11.28	12.15	-90.87	287.37	-539.60	411.34	389.12	22.22	18.512			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 12 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 131H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)
4,900.00	4,870.15	4,877.66	4,808.53	11.48	12.43	-89.91	298.69	-559.15	425.98	403.39	22.60	18.852	
5,000.00	4,969.93	4,975.94	4,904.20	11.67	12.71	-88.69	309.98	-578.65	440.86	417.91	22.94	19.214	
5,100.00	5,069.85	5,073.90	4,999.55	11.85	13.00	-87.24	321.23	-598.09	456.12	432.85	23.27	19.605	
5,200.00	5,169.84	5,171.47	5,094.51	11.99	13.28	-85.61	332.44	-617.45	471.94	448.38	23.56	20.030	
5,202.16	5,172.00	5,173.57	5,096.56	12.00	13.29	-105.81	332.68	-617.87	472.29	448.72	23.57	20.039	
5,300.00	5,269.84	5,268.80	5,189.26	12.08	13.56	-103.94	343.62	-636.77	488.38	464.54	23.84	20.486	
5,400.00	5,369.84	5,366.14	5,284.00	12.17	13.85	-102.16	354.80	-656.08	505.33	481.21	24.12	20.950	
5,500.00	5,469.84	5,463.47	5,378.74	12.26	14.13	-100.49	365.98	-675.39	522.73	498.33	24.40	21.421	
5,600.00	5,569.84	5,560.81	5,473.49	12.34	14.41	-98.92	377.17	-694.71	540.55	515.88	24.68	21.906	
5,700.00	5,669.84	5,665.27	5,575.32	12.43	14.69	-97.40	388.81	-714.82	558.20	533.23	24.98	22.349	
5,800.00	5,769.84	5,771.64	5,679.44	12.52	14.98	-96.06	399.72	-733.66	574.72	549.43	25.29	22.723	
5,900.00	5,869.84	5,878.80	5,784.73	12.61	15.25	-94.91	409.72	-750.95	589.98	564.38	25.60	23.045	
6,000.00	5,969.84	5,986.69	5,891.08	12.69	15.51	-93.91	418.80	-766.63	603.88	577.98	25.90	23.315	
6,100.00	6,069.84	6,095.24	5,998.41	12.78	15.74	-93.06	426.92	-780.65	616.37	590.17	26.19	23.531	
6,200.00	6,169.84	6,204.37	6,106.61	12.87	15.96	-92.35	434.05	-792.97	627.37	600.89	26.48	23.695	
6,300.00	6,269.84	6,314.01	6,215.56	12.96	16.15	-91.76	440.18	-803.56	636.83	610.08	26.75	23.808	
6,400.00	6,369.84	6,424.08	6,325.16	13.04	16.32	-91.28	445.28	-812.36	644.71	617.70	27.01	23.870	
6,500.00	6,469.84	6,534.51	6,435.29	13.13	16.48	-90.91	449.33	-819.36	650.99	623.73	27.26	23.882	
6,600.00	6,569.84	6,645.20	6,545.82	13.22	16.61	-90.64	452.32	-824.54	655.63	628.13	27.49	23.846	
6,700.00	6,669.84	6,756.09	6,656.64	13.30	16.72	-90.47	454.25	-827.87	658.61	630.90	27.71	23.764	
6,800.00	6,769.84	6,867.09	6,767.62	13.39	16.81	-90.39	455.10	-829.34	659.93	632.03	27.90	23.652	
6,900.00	6,869.84	6,970.30	6,870.84	13.48	16.88	-90.39	455.15	-829.42	660.01	631.95	28.06	23.521	
7,000.00	6,969.84	7,070.30	6,970.84	13.56	16.94	-90.39	455.15	-829.42	660.01	631.79	28.21	23.395	
7,100.00	7,069.84	7,170.30	7,070.84	13.65	17.00	-90.39	455.15	-829.42	660.01	631.64	28.36	23.269	
7,200.00	7,169.84	7,270.30	7,170.84	13.74	17.07	-90.39	455.15	-829.42	660.01	631.49	28.52	23.145	
7,300.00	7,269.84	7,370.30	7,270.84	13.82	17.13	-90.39	455.15	-829.42	660.01	631.34	28.67	23.022	
7,400.00	7,369.84	7,470.30	7,370.84	13.91	17.20	-90.39	455.15	-829.42	660.01	631.18	28.82	22.900	
7,500.00	7,469.84	7,570.30	7,470.84	14.00	17.26	-90.39	455.15	-829.42	660.01	631.03	28.97	22.779	
7,600.00	7,569.84	7,670.30	7,570.84	14.08	17.33	-90.39	455.15	-829.42	660.01	630.88	29.13	22.660	
7,700.00	7,669.84	7,770.30	7,670.84	14.17	17.39	-90.39	455.15	-829.42	660.01	630.73	29.28	22.542	
7,800.00	7,769.84	7,870.30	7,770.84	14.26	17.46	-90.39	455.15	-829.42	660.01	630.57	29.43	22.425	
7,900.00	7,869.84	7,970.30	7,870.84	14.34	17.52	-90.39	455.15	-829.42	660.01	630.42	29.58	22.309	
8,000.00	7,969.84	8,070.30	7,970.84	14.43	17.59	-90.39	455.15	-829.42	660.01	630.27	29.74	22.194	
8,100.00	8,069.84	8,170.30	8,070.84	14.51	17.65	-90.39	455.15	-829.42	660.01	630.11	29.89	22.080	
8,200.00	8,169.84	8,270.30	8,170.84	14.60	17.72	-90.39	455.15	-829.42	660.01	629.96	30.04	21.968	
8,300.00	8,269.84	8,370.30	8,270.84	14.69	17.79	-90.39	455.15	-829.42	660.01	629.81	30.20	21.856	
8,400.00	8,369.84	8,470.30	8,370.84	14.77	17.85	-90.39	455.15	-829.42	660.01	629.65	30.35	21.746	
8,500.00	8,469.84	8,570.30	8,470.84	14.86	17.92	-90.39	455.15	-829.42	660.01	629.50	30.50	21.637	
8,600.00	8,569.84	8,670.30	8,570.84	14.94	17.98	-90.39	455.15	-829.42	660.01	629.35	30.66	21.529	
8,700.00	8,669.84	8,770.30	8,670.84	15.03	18.05	-90.39	455.15	-829.42	660.01	629.19	30.81	21.421	
8,800.00	8,769.84	8,870.30	8,770.84	15.12	18.12	-90.39	455.15	-829.42	660.01	629.04	30.96	21.315	
8,900.00	8,869.84	8,970.30	8,870.84	15.20	18.18	-90.39	455.15	-829.42	660.01	628.89	31.12	21.210	
9,000.00	8,969.84	9,070.30	8,970.84	15.29	18.25	-90.39	455.15	-829.42	660.01	628.73	31.27	21.106	
9,100.00	9,069.84	9,170.30	9,070.84	15.37	18.32	-90.39	455.15	-829.42	660.01	628.58	31.43	21.002	
9,200.00	9,169.84	9,270.30	9,170.84	15.46	18.38	-90.39	455.15	-829.42	660.01	628.43	31.58	20.900	
9,300.00	9,269.84	9,370.30	9,270.84	15.54	18.45	-90.39	455.15	-829.42	660.01	628.27	31.73	20.798	
9,400.00	9,369.84	9,470.30	9,370.84	15.63	18.52	-90.39	455.15	-829.42	660.01	628.12	31.89	20.698	
9,500.00	9,469.84	9,570.30	9,470.84	15.71	18.58	-90.39	455.15	-829.42	660.01	627.96	32.04	20.599	
9,600.00	9,569.84	9,670.30	9,570.84	15.80	18.65	-90.39	455.15	-829.42	660.01	627.81	32.20	20.500	
9,700.00	9,669.84	9,770.30	9,670.84	15.89	18.72	-90.39	455.15	-829.42	660.01	627.66	32.35	20.402	
9,800.00	9,769.84	9,870.30	9,770.84	15.97	18.79	-90.39	455.15	-829.42	660.01	627.50	32.50	20.305	
9,900.00	9,869.84	9,970.30	9,870.84	16.06	18.86	-90.39	455.15	-829.42	660.01	627.35	32.66	20.209	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 13 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 131H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
14,000.00	12,137.21	14,073.48	12,140.22	27.69	30.34	90.17	-1,637.68	-811.40	660.01	604.09	55.92	11.802			
14,100.00	12,138.08	14,173.48	12,141.09	28.82	31.36	90.17	-1,737.68	-810.54	660.01	601.85	58.17	11.347			
14,200.00	12,138.96	14,273.48	12,141.96	29.98	32.41	90.17	-1,837.67	-809.68	660.01	599.56	60.45	10.918			
14,300.00	12,139.83	14,373.48	12,142.83	31.15	33.48	90.17	-1,937.66	-808.82	660.01	597.24	62.77	10.514			
14,400.00	12,140.70	14,473.48	12,143.71	32.33	34.57	90.17	-2,037.65	-807.96	660.01	594.89	65.13	10.135			
14,500.00	12,141.57	14,573.48	12,144.58	33.54	35.68	90.17	-2,137.65	-807.10	660.01	592.51	67.51	9.777			
14,600.00	12,142.44	14,673.48	12,145.45	34.75	36.81	90.17	-2,237.64	-806.24	660.01	590.10	69.92	9.440			
14,700.00	12,143.31	14,773.48	12,146.32	35.98	37.96	90.17	-2,337.63	-805.38	660.01	587.66	72.35	9.123			
14,800.00	12,144.18	14,873.48	12,147.19	37.21	39.12	90.17	-2,437.62	-804.52	660.01	585.21	74.80	8.823			
14,900.00	12,145.05	14,973.48	12,148.06	38.46	40.29	90.17	-2,537.62	-803.66	660.01	582.74	77.27	8.541			
15,000.00	12,145.93	15,073.48	12,148.93	39.71	41.48	90.17	-2,637.61	-802.80	660.01	580.25	79.77	8.274			
15,100.00	12,146.80	15,173.48	12,149.80	40.97	42.68	90.17	-2,737.60	-801.94	660.01	577.74	82.27	8.022			
15,200.00	12,147.67	15,273.48	12,150.67	42.24	43.89	90.17	-2,837.59	-801.08	660.01	575.22	84.79	7.784			
15,300.00	12,148.54	15,373.48	12,151.55	43.51	45.10	90.17	-2,937.59	-800.22	660.01	572.69	87.33	7.558			
15,400.00	12,149.41	15,473.48	12,152.42	44.79	46.33	90.17	-3,037.58	-799.35	660.01	570.14	89.87	7.344			
15,500.00	12,150.28	15,573.48	12,153.29	46.08	47.57	90.17	-3,137.57	-798.49	660.02	567.59	92.43	7.141			
15,600.00	12,151.15	15,673.48	12,154.16	47.37	48.81	90.17	-3,237.56	-797.63	660.02	565.02	94.99	6.948			
15,700.00	12,152.02	15,773.48	12,155.03	48.66	50.06	90.17	-3,337.56	-796.77	660.02	562.44	97.57	6.764			
15,800.00	12,152.90	15,873.48	12,155.90	49.96	51.31	90.17	-3,437.55	-795.91	660.02	559.86	100.16	6.590			
15,900.00	12,153.77	15,973.48	12,156.77	51.26	52.57	90.17	-3,537.54	-795.05	660.02	557.27	102.75	6.424			
16,000.00	12,154.64	16,073.48	12,157.64	52.57	53.84	90.17	-3,637.53	-794.19	660.02	554.67	105.35	6.265			
16,100.00	12,155.51	16,173.48	12,158.51	53.88	55.11	90.17	-3,737.53	-793.33	660.02	552.06	107.96	6.114			
16,200.00	12,156.38	16,273.48	12,159.39	55.19	56.39	90.17	-3,837.52	-792.47	660.02	549.45	110.57	5.969			
16,300.00	12,157.25	16,373.48	12,160.26	56.50	57.67	90.17	-3,937.51	-791.61	660.02	546.83	113.19	5.831			
16,400.00	12,158.12	16,473.48	12,161.13	57.82	58.95	90.17	-4,037.50	-790.75	660.02	544.20	115.82	5.699			
16,500.00	12,158.99	16,573.48	12,162.00	59.14	60.24	90.17	-4,137.50	-789.89	660.02	541.57	118.45	5.572			
16,600.00	12,159.87	16,673.48	12,162.87	60.46	61.53	90.17	-4,237.49	-789.03	660.02	538.94	121.08	5.451			
16,700.00	12,160.74	16,773.48	12,163.74	61.79	62.83	90.17	-4,337.48	-788.16	660.02	536.30	123.72	5.335			
16,800.00	12,161.61	16,873.48	12,164.61	63.11	64.13	90.17	-4,437.47	-787.30	660.02	533.65	126.37	5.223			
16,900.00	12,162.48	16,973.48	12,165.48	64.44	65.43	90.17	-4,537.47	-786.44	660.02	531.00	129.01	5.116			
17,000.00	12,163.35	17,073.48	12,166.36	65.77	66.73	90.17	-4,637.46	-785.58	660.02	528.35	131.67	5.013			
17,100.00	12,164.22	17,173.48	12,167.23	67.10	68.04	90.17	-4,737.45	-784.72	660.02	525.70	134.32	4.914			
17,200.00	12,165.09	17,273.48	12,168.10	68.43	69.35	90.17	-4,837.44	-783.86	660.02	523.04	136.98	4.818			
17,300.00	12,165.96	17,373.48	12,168.97	69.77	70.66	90.17	-4,937.44	-783.00	660.02	520.38	139.64	4.727			
17,400.00	12,166.84	17,473.48	12,169.84	71.10	71.97	90.17	-5,037.43	-782.14	660.02	517.71	142.31	4.638			
17,500.00	12,167.71	17,573.48	12,170.71	72.44	73.29	90.17	-5,137.42	-781.28	660.02	515.05	144.97	4.553			
17,600.00	12,168.58	17,673.48	12,171.58	73.78	74.61	90.17	-5,237.41	-780.42	660.02	512.38	147.64	4.470			
17,700.00	12,169.45	17,773.48	12,172.45	75.12	75.93	90.17	-5,337.41	-779.56	660.02	509.70	150.32	4.391			
17,800.00	12,170.32	17,873.48	12,173.32	76.46	77.25	90.17	-5,437.40	-778.70	660.02	507.03	152.99	4.314			
17,900.00	12,171.19	17,973.48	12,174.20	77.80	78.57	90.17	-5,537.39	-777.84	660.02	504.35	155.67	4.240			
18,000.00	12,172.06	18,073.48	12,175.07	79.14	79.90	90.17	-5,637.38	-776.98	660.02	501.67	158.35	4.168			
18,100.00	12,172.93	18,173.48	12,175.94	80.48	81.22	90.17	-5,737.38	-776.11	660.02	498.99	161.03	4.099			
18,200.00	12,173.81	18,273.48	12,176.81	81.83	82.55	90.17	-5,837.37	-775.25	660.02	496.31	163.71	4.032			
18,300.00	12,174.68	18,373.48	12,177.68	83.17	83.88	90.17	-5,937.36	-774.39	660.02	493.62	166.40	3.967			
18,400.00	12,175.55	18,473.48	12,178.55	84.52	85.21	90.17	-6,037.35	-773.53	660.02	490.94	169.08	3.903			
18,500.00	12,176.42	18,573.48	12,179.42	85.86	86.54	90.17	-6,137.35	-772.67	660.02	488.25	171.77	3.842			
18,600.00	12,177.29	18,673.48	12,180.29	87.21	87.88	90.17	-6,237.34	-771.81	660.02	485.56	174.46	3.783			
18,700.00	12,178.16	18,773.48	12,181.16	88.56	89.21	90.17	-6,337.33	-770.95	660.02	482.87	177.16	3.726			
18,800.00	12,179.03	18,873.48	12,182.04	89.91	90.55	90.17	-6,437.32	-770.09	660.02	480.17	179.85	3.670			
18,900.00	12,179.90	18,973.48	12,182.91	91.26	91.88	90.17	-6,537.32	-769.23	660.02	477.48	182.54	3.616			
19,000.00	12,180.78	19,073.48	12,183.78	92.61	93.22	90.17	-6,637.31	-768.37	660.02	474.78	185.24	3.563			
19,100.00	12,181.65	19,173.48	12,184.65	93.96	94.56	90.17	-6,737.30	-767.51	660.02	472.09	187.94	3.512			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 15 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 131H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
							+N/-S (usft)	+E/-W (usft)						
19,200.00	12,182.52	19,273.48	12,185.52	95.31	95.90	90.17	-6,837.29	-766.65	660.02	469.39	660.02	190.63	3.462	
19,300.00	12,183.39	19,373.48	12,186.39	96.66	97.24	90.17	-6,937.29	-765.79	660.02	466.69	660.02	193.33	3.414	
19,400.00	12,184.26	19,473.48	12,187.26	98.01	98.58	90.17	-7,037.28	-764.93	660.02	463.99	660.02	196.03	3.367	
19,500.00	12,185.13	19,573.48	12,188.13	99.36	99.92	90.17	-7,137.27	-764.06	660.02	461.29	660.02	198.74	3.321	
19,600.00	12,186.00	19,673.48	12,189.00	100.72	101.26	90.17	-7,237.26	-763.20	660.02	458.59	660.02	201.44	3.277	
19,700.00	12,186.87	19,773.48	12,189.88	102.07	102.60	90.17	-7,337.26	-762.34	660.02	455.88	660.02	204.14	3.233	
19,800.00	12,187.75	19,873.48	12,190.75	103.42	103.95	90.17	-7,437.25	-761.48	660.02	453.18	660.02	206.85	3.191	
19,900.00	12,188.62	19,973.48	12,191.62	104.78	105.29	90.17	-7,537.24	-760.62	660.02	450.47	660.02	209.55	3.150	
20,000.00	12,189.49	20,073.48	12,192.49	106.13	106.64	90.17	-7,637.23	-759.76	660.02	447.77	660.02	212.26	3.110	
20,100.00	12,190.36	20,173.48	12,193.36	107.49	107.98	90.17	-7,737.23	-758.90	660.03	445.06	660.03	214.97	3.070	
20,200.00	12,191.23	20,273.48	12,194.23	108.84	109.33	90.17	-7,837.22	-758.04	660.03	442.35	660.03	217.67	3.032	
20,300.00	12,192.10	20,373.48	12,195.10	110.20	110.68	90.17	-7,937.21	-757.18	660.03	439.64	660.03	220.38	2.995	
20,400.00	12,192.97	20,473.48	12,195.97	111.55	112.02	90.17	-8,037.20	-756.32	660.03	436.93	660.03	223.09	2.959	
20,500.00	12,193.85	20,573.48	12,196.84	112.91	113.37	90.17	-8,137.20	-755.46	660.03	434.22	660.03	225.80	2.923	
20,600.00	12,194.72	20,673.48	12,197.72	114.27	114.72	90.17	-8,237.19	-754.60	660.03	431.51	660.03	228.51	2.888	
20,700.00	12,195.59	20,773.48	12,198.59	115.62	116.07	90.17	-8,337.18	-753.74	660.03	428.80	660.03	231.23	2.854	
20,800.00	12,196.46	20,873.48	12,199.46	116.98	117.42	90.17	-8,437.17	-752.87	660.03	426.09	660.03	233.94	2.821	
20,900.00	12,197.33	20,973.48	12,200.33	118.34	118.77	90.17	-8,537.17	-752.01	660.03	423.38	660.03	236.65	2.789	
21,000.00	12,198.20	21,073.48	12,201.20	119.70	120.12	90.17	-8,637.16	-751.15	660.03	420.66	660.03	239.36	2.757	
21,100.00	12,199.07	21,173.48	12,202.07	121.05	121.47	90.17	-8,737.15	-750.29	660.03	417.95	660.03	242.08	2.726	
21,200.00	12,199.94	21,273.48	12,202.94	122.41	122.82	90.17	-8,837.14	-749.43	660.03	415.23	660.03	244.79	2.696	
21,300.00	12,200.82	21,373.48	12,203.81	123.77	124.17	90.17	-8,937.14	-748.57	660.03	412.52	660.03	247.51	2.667	
21,400.00	12,201.69	21,473.48	12,204.68	125.13	125.53	90.17	-9,037.13	-747.71	660.03	409.80	660.03	250.22	2.638	
21,500.00	12,202.56	21,573.48	12,205.56	126.49	126.88	90.17	-9,137.12	-746.85	660.03	407.09	660.03	252.94	2.609	
21,600.00	12,203.43	21,673.48	12,206.43	127.85	128.23	90.17	-9,237.11	-745.99	660.03	404.37	660.03	255.66	2.582	
21,700.00	12,204.30	21,773.48	12,207.30	129.21	129.58	90.17	-9,337.11	-745.13	660.03	401.65	660.03	258.38	2.555	
21,800.00	12,205.17	21,873.48	12,208.17	130.57	130.94	90.17	-9,437.10	-744.27	660.03	398.94	660.03	261.09	2.528	
21,900.00	12,206.04	21,973.48	12,209.04	131.93	132.29	90.17	-9,537.09	-743.41	660.03	396.22	660.03	263.81	2.502	
22,000.00	12,206.91	22,073.48	12,209.91	133.29	133.65	90.17	-9,637.08	-742.55	660.03	393.50	660.03	266.53	2.476	
22,100.00	12,207.79	22,173.48	12,210.78	134.65	135.00	90.17	-9,737.08	-741.69	660.03	390.78	660.03	269.25	2.451	
22,200.00	12,208.66	22,273.48	12,211.65	136.01	136.36	90.17	-9,837.07	-740.82	660.03	388.06	660.03	271.97	2.427	
22,300.00	12,209.53	22,373.48	12,212.53	137.37	137.71	90.17	-9,937.06	-739.96	660.03	385.34	660.03	274.69	2.403	
22,400.00	12,210.40	22,473.48	12,213.40	138.73	139.07	90.17	-10,037.05	-739.10	660.03	382.62	660.03	277.41	2.379	
22,411.61	12,210.50	22,485.09	12,213.50	138.89	139.22	90.17	-10,048.66	-739.00	660.03	382.31	660.03	277.72	2.377	SF

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 16 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 132H - OH - Plan 1														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
0.00	0.00	0.00	0.00	0.50	0.50	0.00	160.00	0.00	160.00	160.00					
100.00	100.00	100.00	100.00	0.98	0.98	0.00	160.00	0.00	160.00	158.04	1.96	81.542			
200.00	200.00	200.00	200.00	1.56	1.56	0.00	160.00	0.00	160.00	156.88	3.12	51.245			
300.00	300.00	300.00	300.00	1.98	1.98	0.00	160.00	0.00	160.00	156.04	3.96	40.380			
400.00	400.00	400.00	400.00	2.33	2.33	0.00	160.00	0.00	160.00	155.34	4.66	34.343			
500.00	500.00	500.00	500.00	2.63	2.63	0.00	160.00	0.00	160.00	154.73	5.27	30.366			
600.00	600.00	600.00	600.00	2.91	2.91	0.00	160.00	0.00	160.00	154.18	5.82	27.491			
700.00	700.00	700.00	700.00	3.16	3.16	0.00	160.00	0.00	160.00	153.67	6.33	25.286			
800.00	800.00	800.00	800.00	3.40	3.40	0.00	160.00	0.00	160.00	153.20	6.80	23.525			
900.00	899.99	897.81	897.80	3.68	3.67	20.77	160.66	1.06	159.45	152.15	7.30	21.834			
1,000.00	999.91	995.47	995.39	3.94	3.92	22.43	162.64	4.25	157.90	150.13	7.78	20.307			
1,100.00	1,099.77	1,092.88	1,092.59	4.15	4.17	25.02	165.91	9.54	156.81	148.62	8.19	19.147			
1,108.35	1,108.11	1,101.00	1,100.69	4.16	4.18	25.27	166.25	10.07	156.80	148.58	8.22	19.070			
1,200.00	1,199.63	1,191.46	1,190.82	4.35	4.28	28.26	170.33	16.66	157.40	148.90	8.50	18.517			
1,250.43	1,250.00	1,241.68	1,240.85	4.40	4.37	29.93	172.64	20.38	157.97	149.33	8.64	18.275			
1,300.00	1,299.48	1,291.02	1,290.00	4.45	4.47	31.62	174.90	24.03	158.39	149.59	8.79	18.012			
1,400.00	1,399.17	1,390.47	1,389.07	4.69	4.66	35.39	179.47	31.40	158.04	148.83	9.21	17.151			
1,500.00	1,498.62	1,489.73	1,487.95	4.93	4.86	39.77	184.03	38.75	156.37	146.75	9.62	16.248			
1,550.47	1,548.70	1,539.72	1,537.75	4.99	4.95	42.25	186.32	42.46	155.14	145.37	9.77	15.877			
1,600.00	1,597.81	1,588.76	1,586.60	5.05	5.05	44.79	188.58	46.09	154.00	144.08	9.91	15.532			
1,700.00	1,696.95	1,687.75	1,685.22	5.25	5.23	50.00	193.12	53.42	152.64	142.35	10.29	14.835			
1,754.36	1,750.85	1,741.57	1,738.83	5.35	5.34	52.85	195.59	57.41	152.44	141.95	10.49	14.531	CC		
1,800.00	1,796.09	1,786.75	1,783.84	5.44	5.42	55.25	197.67	60.75	152.58	141.92	10.66	14.314	ES		
1,900.00	1,895.24	1,885.74	1,882.46	5.64	5.61	60.47	202.22	68.09	153.83	142.80	11.03	13.950			
2,000.00	1,994.38	1,984.74	1,981.08	5.83	5.79	65.57	206.76	75.42	156.35	144.96	11.39	13.725			
2,100.00	2,093.53	2,083.73	2,079.69	6.03	5.98	70.46	211.31	82.75	160.08	148.33	11.75	13.620			
2,200.00	2,192.67	2,182.73	2,178.31	6.22	6.17	75.11	215.86	90.09	164.95	152.83	12.12	13.609			
2,300.00	2,291.82	2,279.48	2,274.66	6.42	6.35	79.37	220.56	97.67	171.36	158.90	12.46	13.747			
2,400.00	2,390.96	2,375.39	2,370.00	6.61	6.53	83.23	226.04	106.51	180.30	167.50	12.81	14.080			
2,500.00	2,490.11	2,471.01	2,464.86	6.81	6.71	86.64	232.34	116.68	191.67	178.52	13.15	14.579			
2,600.00	2,589.25	2,566.28	2,559.17	7.00	6.89	89.57	239.45	128.15	205.28	191.80	13.49	15.221			
2,700.00	2,688.39	2,661.17	2,652.86	7.20	7.08	92.04	247.35	140.89	220.98	207.15	13.83	15.981			
2,800.00	2,787.54	2,755.60	2,745.85	7.39	7.26	94.06	256.03	154.88	238.60	224.43	14.17	16.841			
2,900.00	2,886.68	2,849.55	2,838.08	7.59	7.45	95.70	265.46	170.09	258.01	243.50	14.51	17.780			
3,000.00	2,985.83	2,944.75	2,931.25	7.78	7.64	97.03	275.75	186.69	279.00	264.13	14.87	18.764			
3,100.00	3,084.97	3,042.27	3,026.64	7.98	7.84	98.19	286.42	203.92	300.36	285.12	15.24	19.704			
3,200.00	3,184.12	3,139.79	3,122.04	8.17	8.03	99.20	297.10	221.15	321.83	306.20	15.62	20.598			
3,300.00	3,283.26	3,237.32	3,217.43	8.36	8.23	100.07	307.78	238.37	343.38	327.37	16.01	21.453			
3,400.00	3,382.40	3,334.84	3,312.83	8.56	8.43	100.85	318.46	255.60	364.99	348.60	16.39	22.269			
3,500.00	3,481.55	3,432.36	3,408.22	8.75	8.63	101.54	329.14	272.83	386.67	369.89	16.78	23.050			
3,600.00	3,580.69	3,529.89	3,503.61	8.95	8.84	102.15	339.82	290.05	408.39	391.23	17.16	23.796			
3,700.00	3,679.84	3,627.41	3,599.01	9.14	9.05	102.71	350.50	307.28	430.15	412.60	17.55	24.510			
3,800.00	3,778.98	3,724.93	3,694.40	9.33	9.27	103.21	361.18	324.51	451.95	434.01	17.94	25.193			
3,900.00	3,878.13	3,822.46	3,789.79	9.53	9.49	103.66	371.86	341.73	473.77	455.44	18.33	25.847			
4,000.00	3,977.27	3,919.98	3,885.19	9.72	9.72	104.08	382.54	358.96	495.62	476.90	18.72	26.474			
4,100.00	4,076.42	4,017.50	3,980.58	9.91	9.95	104.46	393.22	376.19	517.50	498.39	19.11	27.082			
4,200.00	4,175.56	4,119.76	4,080.66	10.11	10.17	104.83	404.27	394.02	539.17	519.67	19.49	27.659			
4,300.00	4,274.70	4,226.70	4,185.68	10.30	10.42	105.28	414.92	411.20	559.42	539.49	19.93	28.070			
4,400.00	4,373.85	4,334.27	4,291.67	10.49	10.66	105.80	424.59	426.79	578.08	557.72	20.36	28.394			
4,500.00	4,472.99	4,442.39	4,398.53	10.69	10.89	106.37	433.25	440.76	595.15	574.37	20.78	28.640			
4,600.00	4,572.14	4,551.00	4,506.16	10.88	11.11	107.01	440.87	453.06	610.64	589.45	21.19	28.814			
4,700.00	4,671.28	4,660.01	4,614.45	11.08	11.31	107.71	447.45	463.67	624.57	602.97	21.60	28.919			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 17 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 132H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)												Rule Assigned:			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
4,702.13	4,673.39	4,662.33	4,616.77	11.08	11.31	107.73	447.57	463.87	624.85	603.24	21.61	28.921			
4,800.00	4,770.58	4,769.49	4,723.43	11.28	11.49	108.52	452.95	472.55	636.55	614.57	21.98	28.962			
4,900.00	4,870.15	4,879.50	4,833.12	11.48	11.66	109.14	457.38	479.69	646.12	623.78	22.33	28.930			
5,000.00	4,969.93	4,989.91	4,943.35	11.67	11.82	109.56	460.71	485.06	653.21	630.56	22.66	28.830			
5,100.00	5,069.85	5,100.61	5,053.97	11.85	11.97	109.80	462.92	488.63	657.80	634.85	22.95	28.666			
5,200.00	5,169.84	5,211.47	5,164.80	11.99	12.10	109.86	464.01	490.39	659.85	636.66	23.19	28.457			
5,202.16	5,172.00	5,213.86	5,167.20	12.00	12.10	89.62	464.02	490.40	659.87	636.67	23.19	28.453			
5,300.00	5,269.84	5,316.50	5,269.84	12.08	12.16	89.61	464.13	490.58	660.03	636.69	23.33	28.286			
5,400.00	5,369.84	5,416.50	5,369.84	12.17	12.24	89.61	464.13	490.58	660.03	636.53	23.50	28.086			
5,500.00	5,469.84	5,516.50	5,469.84	12.26	12.32	89.61	464.13	490.58	660.03	636.36	23.67	27.889			
5,600.00	5,569.84	5,616.50	5,569.84	12.34	12.40	89.61	464.13	490.58	660.03	636.19	23.83	27.695			
5,700.00	5,669.84	5,716.50	5,669.84	12.43	12.48	89.61	464.13	490.58	660.03	636.03	24.00	27.504			
5,800.00	5,769.84	5,816.50	5,769.84	12.52	12.56	89.61	464.13	490.58	660.03	635.86	24.16	27.315			
5,900.00	5,869.84	5,916.50	5,869.84	12.61	12.64	89.61	464.13	490.58	660.03	635.70	24.33	27.129			
6,000.00	5,969.84	6,016.50	5,969.84	12.69	12.72	89.61	464.13	490.58	660.03	635.53	24.50	26.945			
6,100.00	6,069.84	6,116.50	6,069.84	12.78	12.81	89.61	464.13	490.58	660.03	635.36	24.66	26.764			
6,200.00	6,169.84	6,216.50	6,169.84	12.87	12.89	89.61	464.13	490.58	660.03	635.20	24.83	26.585			
6,300.00	6,269.84	6,316.50	6,269.84	12.96	12.97	89.61	464.13	490.58	660.03	635.03	24.99	26.409			
6,400.00	6,369.84	6,416.50	6,369.84	13.04	13.05	89.61	464.13	490.58	660.03	634.87	25.16	26.235			
6,500.00	6,469.84	6,516.50	6,469.84	13.13	13.13	89.61	464.13	490.58	660.03	634.70	25.32	26.064			
6,600.00	6,569.84	6,616.50	6,569.84	13.22	13.21	89.61	464.13	490.58	660.03	634.54	25.49	25.895			
6,700.00	6,669.84	6,716.50	6,669.84	13.30	13.29	89.61	464.13	490.58	660.03	634.37	25.65	25.728			
6,800.00	6,769.84	6,816.50	6,769.84	13.39	13.37	89.61	464.13	490.58	660.03	634.21	25.82	25.563			
6,900.00	6,869.84	6,916.50	6,869.84	13.48	13.45	89.61	464.13	490.58	660.03	634.04	25.99	25.400			
7,000.00	6,969.84	7,016.50	6,969.84	13.56	13.53	89.61	464.13	490.58	660.03	633.87	26.15	25.239			
7,100.00	7,069.84	7,116.50	7,069.84	13.65	13.61	89.61	464.13	490.58	660.03	633.71	26.32	25.081			
7,200.00	7,169.84	7,216.50	7,169.84	13.74	13.70	89.61	464.13	490.58	660.03	633.54	26.48	24.924			
7,300.00	7,269.84	7,316.50	7,269.84	13.82	13.78	89.61	464.13	490.58	660.03	633.38	26.65	24.770			
7,400.00	7,369.84	7,416.50	7,369.84	13.91	13.86	89.61	464.13	490.58	660.03	633.21	26.81	24.617			
7,500.00	7,469.84	7,516.50	7,469.84	14.00	13.94	89.61	464.13	490.58	660.03	633.05	26.98	24.466			
7,600.00	7,569.84	7,616.50	7,569.84	14.08	14.02	89.61	464.13	490.58	660.03	632.88	27.14	24.317			
7,700.00	7,669.84	7,716.50	7,669.84	14.17	14.10	89.61	464.13	490.58	660.03	632.72	27.31	24.170			
7,800.00	7,769.84	7,816.50	7,769.84	14.26	14.18	89.61	464.13	490.58	660.03	632.55	27.47	24.025			
7,900.00	7,869.84	7,916.50	7,869.84	14.34	14.26	89.61	464.13	490.58	660.03	632.39	27.64	23.881			
8,000.00	7,969.84	8,016.50	7,969.84	14.43	14.34	89.61	464.13	490.58	660.03	632.22	27.80	23.740			
8,100.00	8,069.84	8,116.50	8,069.84	14.51	14.42	89.61	464.13	490.58	660.03	632.06	27.97	23.599			
8,200.00	8,169.84	8,216.50	8,169.84	14.60	14.51	89.61	464.13	490.58	660.03	631.89	28.13	23.461			
8,300.00	8,269.84	8,316.50	8,269.84	14.69	14.59	89.61	464.13	490.58	660.03	631.73	28.30	23.324			
8,400.00	8,369.84	8,416.50	8,369.84	14.77	14.67	89.61	464.13	490.58	660.03	631.56	28.46	23.189			
8,500.00	8,469.84	8,516.50	8,469.84	14.86	14.75	89.61	464.13	490.58	660.03	631.40	28.63	23.055			
8,600.00	8,569.84	8,616.50	8,569.84	14.94	14.83	89.61	464.13	490.58	660.03	631.23	28.79	22.923			
8,700.00	8,669.84	8,716.50	8,669.84	15.03	14.91	89.61	464.13	490.58	660.03	631.07	28.96	22.793			
8,800.00	8,769.84	8,816.50	8,769.84	15.12	14.99	89.61	464.13	490.58	660.03	630.90	29.12	22.664			
8,900.00	8,869.84	8,916.50	8,869.84	15.20	15.07	89.61	464.13	490.58	660.03	630.74	29.29	22.536			
9,000.00	8,969.84	9,016.50	8,969.84	15.29	15.15	89.61	464.13	490.58	660.03	630.57	29.45	22.410			
9,100.00	9,069.84	9,116.50	9,069.84	15.37	15.24	89.61	464.13	490.58	660.03	630.41	29.62	22.285			
9,200.00	9,169.84	9,216.50	9,169.84	15.46	15.32	89.61	464.13	490.58	660.03	630.24	29.78	22.162			
9,300.00	9,269.84	9,316.50	9,269.84	15.54	15.40	89.61	464.13	490.58	660.03	630.08	29.95	22.040			
9,400.00	9,369.84	9,416.50	9,369.84	15.63	15.48	89.61	464.13	490.58	660.03	629.91	30.11	21.919			
9,500.00	9,469.84	9,516.50	9,469.84	15.71	15.56	89.61	464.13	490.58	660.03	629.75	30.28	21.800			
9,600.00	9,569.84	9,616.50	9,569.84	15.80	15.64	89.61	464.13	490.58	660.03	629.58	30.44	21.682			
9,700.00	9,669.84	9,716.50	9,669.84	15.89	15.72	89.61	464.13	490.58	660.03	629.42	30.61	21.566			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 18 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 132H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:					Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)
9,800.00	9,769.84	9,816.50	9,769.84	15.97	15.80	89.61	464.13	490.58	660.03	629.25	30.77	21.450	
9,900.00	9,869.84	9,916.50	9,869.84	16.06	15.88	89.61	464.13	490.58	660.03	629.09	30.93	21.336	
10,000.00	9,969.84	10,016.50	9,969.84	16.14	15.97	89.61	464.13	490.58	660.03	628.93	31.10	21.223	
10,100.00	10,069.84	10,116.50	10,069.84	16.23	16.05	89.61	464.13	490.58	660.03	628.76	31.26	21.111	
10,200.00	10,169.84	10,216.50	10,169.84	16.31	16.13	89.61	464.13	490.58	660.03	628.60	31.43	21.001	
10,300.00	10,269.84	10,316.50	10,269.84	16.40	16.21	89.61	464.13	490.58	660.03	628.43	31.59	20.891	
10,400.00	10,369.84	10,416.50	10,369.84	16.48	16.29	89.61	464.13	490.58	660.03	628.27	31.76	20.783	
10,500.00	10,469.84	10,516.50	10,469.84	16.57	16.37	89.61	464.13	490.58	660.03	628.10	31.92	20.676	
10,600.00	10,569.84	10,616.50	10,569.84	16.65	16.45	89.61	464.13	490.58	660.03	627.94	32.09	20.570	
10,700.00	10,669.84	10,716.50	10,669.84	16.74	16.53	89.61	464.13	490.58	660.03	627.77	32.25	20.465	
10,800.00	10,769.84	10,816.50	10,769.84	16.82	16.61	89.61	464.13	490.58	660.03	627.61	32.42	20.361	
10,900.00	10,869.84	10,916.50	10,869.84	16.91	16.70	89.61	464.13	490.58	660.03	627.44	32.58	20.258	
11,000.00	10,969.84	11,016.50	10,969.84	16.99	16.78	89.61	464.13	490.58	660.03	627.28	32.75	20.156	
11,100.00	11,069.84	11,116.50	11,069.84	17.08	16.86	89.61	464.13	490.58	660.03	627.12	32.91	20.056	
11,200.00	11,169.84	11,216.50	11,169.84	17.16	16.94	89.61	464.13	490.58	660.03	626.95	33.07	19.956	
11,300.00	11,269.84	11,316.50	11,269.84	17.25	17.02	89.61	464.13	490.58	660.03	626.79	33.24	19.857	
11,400.00	11,369.84	11,416.50	11,369.84	17.33	17.10	89.61	464.13	490.58	660.03	626.62	33.40	19.759	
11,500.00	11,469.84	11,516.50	11,469.84	17.42	17.18	89.61	464.13	490.58	660.03	626.46	33.57	19.663	
11,581.16	11,551.00	11,597.66	11,551.00	17.48	17.25	89.61	464.13	490.58	660.03	626.33	33.69	19.590	
11,600.00	11,569.83	11,616.46	11,569.80	17.48	17.27	-89.90	463.88	490.58	660.03	626.33	33.69	19.589	
11,650.00	11,619.67	11,666.37	11,619.56	17.49	17.32	-89.92	460.25	490.61	660.02	626.37	33.65	19.613	
11,700.00	11,668.99	11,716.30	11,668.83	17.51	17.35	-89.93	452.30	490.68	660.02	626.46	33.57	19.664	
11,750.00	11,717.40	11,766.24	11,717.24	17.51	17.38	-89.95	440.09	490.79	660.02	626.58	33.45	19.734	
11,800.00	11,764.55	11,816.20	11,764.42	17.52	17.41	-89.97	423.70	490.93	660.02	626.73	33.30	19.822	
11,850.00	11,810.08	11,866.18	11,810.01	17.52	17.44	-89.99	403.26	491.10	660.02	626.90	33.13	19.925	
11,884.72	11,840.56	11,900.89	11,840.54	17.52	17.46	-90.00	386.75	491.25	660.02	627.03	33.00	20.004	
11,900.00	11,853.63	11,916.17	11,853.65	17.52	17.47	-90.00	378.91	491.31	660.02	627.09	32.94	20.039	
11,950.00	11,894.88	11,966.18	11,895.03	17.53	17.51	-90.02	350.85	491.56	660.02	627.29	32.74	20.160	
12,000.00	11,933.52	12,016.21	11,933.81	17.53	17.54	-90.04	319.27	491.83	660.02	627.48	32.54	20.284	
12,050.00	11,969.24	12,066.26	11,969.71	17.53	17.58	-90.06	284.42	492.13	660.02	627.67	32.35	20.403	
12,100.00	12,001.78	12,116.32	12,002.43	17.53	17.63	-90.07	246.55	492.45	660.02	627.85	32.18	20.512	
12,150.00	12,030.89	12,166.40	12,031.74	17.53	17.68	-90.09	205.97	492.80	660.03	627.99	32.03	20.604	
12,200.00	12,056.34	12,216.50	12,057.40	17.53	17.75	-90.10	162.96	493.17	660.03	628.10	31.93	20.673	
12,250.00	12,077.95	12,266.61	12,079.21	17.54	17.82	-90.12	117.86	493.56	660.03	628.16	31.86	20.714	
12,300.00	12,095.55	12,316.74	12,097.00	17.55	17.90	-90.13	71.02	493.96	660.03	628.17	31.85	20.721	
12,350.00	12,109.01	12,366.88	12,110.64	17.56	18.00	-90.15	22.79	494.38	660.03	628.13	31.90	20.691	
12,400.00	12,118.22	12,417.03	12,120.01	17.58	18.12	-90.16	-26.46	494.80	660.03	628.02	32.00	20.623	
12,450.00	12,123.11	12,467.19	12,125.04	17.60	18.25	-90.17	-76.36	495.23	660.03	627.86	32.17	20.517	
12,476.17	12,123.94	12,493.45	12,125.92	17.61	18.33	-90.17	-102.60	495.46	660.03	627.75	32.28	20.450	
12,500.00	12,124.14	12,517.29	12,126.13	17.62	18.40	-90.17	-126.43	495.67	660.03	627.63	32.40	20.372	
12,600.00	12,125.02	12,617.29	12,127.00	17.69	18.75	-90.17	-226.42	496.53	660.03	626.99	33.04	19.976	
12,700.00	12,125.89	12,717.29	12,127.88	17.79	19.18	-90.17	-326.42	497.39	660.03	626.13	33.89	19.473	
12,800.00	12,126.76	12,817.29	12,128.75	17.95	19.68	-90.17	-426.41	498.25	660.03	625.09	34.94	18.889	
12,900.00	12,127.63	12,917.29	12,129.62	18.21	20.26	-90.17	-526.40	499.11	660.03	623.86	36.17	18.249	
13,000.00	12,128.50	13,017.29	12,130.49	18.61	20.91	-90.17	-626.39	499.97	660.03	622.47	37.55	17.575	
13,100.00	12,129.37	13,117.29	12,131.36	19.18	21.63	-90.17	-726.39	500.83	660.03	620.94	39.08	16.888	
13,200.00	12,130.24	13,217.29	12,132.23	19.87	22.42	-90.17	-826.38	501.69	660.03	619.29	40.74	16.201	
13,300.00	12,131.11	13,317.29	12,133.10	20.66	23.26	-90.17	-926.37	502.55	660.03	617.52	42.51	15.526	
13,400.00	12,131.99	13,417.29	12,133.98	21.53	24.15	-90.17	-1,026.36	503.41	660.03	615.65	44.38	14.873	
13,500.00	12,132.86	13,517.29	12,134.85	22.45	25.08	-90.17	-1,126.36	504.27	660.03	613.69	46.33	14.245	
13,600.00	12,133.73	13,617.29	12,135.72	23.43	26.06	-90.17	-1,226.35	505.14	660.03	611.66	48.37	13.647	
13,700.00	12,134.60	13,717.29	12,136.59	24.44	27.07	-90.17	-1,326.34	506.00	660.03	609.56	50.46	13.079	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 19 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 132H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)	Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)						
13,800.00	12,135.47	13,817.29	12,137.46	25.50	28.12	-90.17	-1,426.33	506.86	660.03	607.41	52.62	12.543		
13,900.00	12,136.34	13,917.29	12,138.33	26.58	29.19	-90.17	-1,526.33	507.72	660.03	605.20	54.83	12.037		
14,000.00	12,137.21	14,017.29	12,139.20	27.69	30.28	-90.17	-1,626.32	508.58	660.03	602.94	57.09	11.561		
14,100.00	12,138.08	14,117.29	12,140.08	28.82	31.40	-90.17	-1,726.31	509.44	660.03	600.64	59.39	11.114		
14,200.00	12,138.96	14,217.29	12,140.95	29.98	32.54	-90.17	-1,826.30	510.30	660.03	598.31	61.72	10.694		
14,300.00	12,139.83	14,317.29	12,141.82	31.15	33.70	-90.17	-1,926.30	511.16	660.03	595.94	64.08	10.299		
14,400.00	12,140.70	14,417.29	12,142.69	32.33	34.87	-90.17	-2,026.29	512.02	660.03	593.55	66.48	9.928		
14,500.00	12,141.57	14,517.29	12,143.56	33.54	36.06	-90.17	-2,126.28	512.88	660.03	591.13	68.90	9.580		
14,600.00	12,142.44	14,617.29	12,144.43	34.75	37.26	-90.17	-2,226.27	513.75	660.03	588.69	71.34	9.252		
14,700.00	12,143.31	14,717.29	12,145.30	35.98	38.47	-90.17	-2,326.27	514.61	660.03	586.22	73.81	8.943		
14,800.00	12,144.18	14,817.29	12,146.18	37.21	39.69	-90.17	-2,426.26	515.47	660.03	583.74	76.29	8.652		
14,900.00	12,145.05	14,917.29	12,147.05	38.46	40.93	-90.17	-2,526.25	516.33	660.03	581.24	78.79	8.377		
15,000.00	12,145.93	15,017.29	12,147.92	39.71	42.17	-90.17	-2,626.24	517.19	660.03	578.72	81.30	8.118		
15,100.00	12,146.80	15,117.29	12,148.79	40.97	43.41	-90.17	-2,726.24	518.05	660.03	576.20	83.83	7.873		
15,200.00	12,147.67	15,217.29	12,149.66	42.24	44.67	-90.17	-2,826.23	518.91	660.03	573.65	86.37	7.641		
15,300.00	12,148.54	15,317.29	12,150.53	43.51	45.93	-90.17	-2,926.22	519.77	660.03	571.10	88.93	7.422		
15,400.00	12,149.41	15,417.29	12,151.40	44.79	47.20	-90.17	-3,026.21	520.63	660.03	568.53	91.49	7.214		
15,500.00	12,150.28	15,517.29	12,152.28	46.08	48.47	-90.17	-3,126.21	521.49	660.03	565.96	94.07	7.016		
15,600.00	12,151.15	15,617.29	12,153.15	47.37	49.75	-90.17	-3,226.20	522.36	660.03	563.38	96.65	6.829		
15,700.00	12,152.02	15,717.29	12,154.02	48.66	51.04	-90.17	-3,326.19	523.22	660.03	560.78	99.24	6.651		
15,800.00	12,152.90	15,817.29	12,154.89	49.96	52.33	-90.17	-3,426.18	524.08	660.03	558.18	101.84	6.481		
15,900.00	12,153.77	15,917.29	12,155.76	51.26	53.62	-90.17	-3,526.18	524.94	660.03	555.58	104.45	6.319		
16,000.00	12,154.64	16,017.29	12,156.63	52.57	54.92	-90.17	-3,626.17	525.80	660.03	552.96	107.06	6.165		
16,100.00	12,155.51	16,117.29	12,157.50	53.88	56.22	-90.17	-3,726.16	526.66	660.03	550.34	109.68	6.018		
16,200.00	12,156.38	16,217.29	12,158.38	55.19	57.52	-90.17	-3,826.15	527.52	660.03	547.72	112.31	5.877		
16,300.00	12,157.25	16,317.29	12,159.25	56.50	58.82	-90.17	-3,926.15	528.38	660.03	545.09	114.94	5.742		
16,400.00	12,158.12	16,417.29	12,160.12	57.82	60.13	-90.17	-4,026.14	529.24	660.03	542.45	117.58	5.614		
16,500.00	12,158.99	16,517.29	12,160.99	59.14	61.45	-90.17	-4,126.13	530.10	660.03	539.81	120.22	5.490		
16,600.00	12,159.87	16,617.29	12,161.86	60.46	62.76	-90.17	-4,226.12	530.97	660.03	537.17	122.86	5.372		
16,700.00	12,160.74	16,717.29	12,162.73	61.79	64.08	-90.17	-4,326.12	531.83	660.03	534.52	125.51	5.259		
16,800.00	12,161.61	16,817.29	12,163.60	63.11	65.40	-90.17	-4,426.11	532.69	660.03	531.87	128.16	5.150		
16,900.00	12,162.48	16,917.29	12,164.47	64.44	66.72	-90.17	-4,526.10	533.55	660.03	529.21	130.82	5.045		
17,000.00	12,163.35	17,017.29	12,165.35	65.77	68.04	-90.17	-4,626.09	534.41	660.03	526.55	133.48	4.945		
17,100.00	12,164.22	17,117.29	12,166.22	67.10	69.36	-90.17	-4,726.09	535.27	660.03	523.89	136.14	4.848		
17,200.00	12,165.09	17,217.29	12,167.09	68.43	70.69	-90.17	-4,826.08	536.13	660.03	521.22	138.81	4.755		
17,300.00	12,165.96	17,317.29	12,167.96	69.77	72.02	-90.17	-4,926.07	536.99	660.03	518.55	141.47	4.665		
17,400.00	12,166.84	17,417.29	12,168.83	71.10	73.35	-90.17	-5,026.06	537.85	660.03	515.88	144.15	4.579		
17,500.00	12,167.71	17,517.29	12,169.70	72.44	74.68	-90.17	-5,126.06	538.71	660.03	513.21	146.82	4.495		
17,600.00	12,168.58	17,617.29	12,170.57	73.78	76.01	-90.17	-5,226.05	539.58	660.03	510.53	149.50	4.415		
17,700.00	12,169.45	17,717.29	12,171.45	75.12	77.35	-90.17	-5,326.04	540.44	660.03	507.85	152.17	4.337		
17,800.00	12,170.32	17,817.29	12,172.32	76.46	78.68	-90.17	-5,426.03	541.30	660.03	505.17	154.85	4.262		
17,900.00	12,171.19	17,917.29	12,173.19	77.80	80.02	-90.17	-5,526.03	542.16	660.03	502.49	157.54	4.190		
18,000.00	12,172.06	18,017.29	12,174.06	79.14	81.36	-90.17	-5,626.02	543.02	660.03	499.81	160.22	4.119		
18,100.00	12,172.93	18,117.29	12,174.93	80.48	82.69	-90.17	-5,726.01	543.88	660.03	497.12	162.91	4.052		
18,200.00	12,173.81	18,217.29	12,175.80	81.83	84.03	-90.17	-5,826.00	544.74	660.03	494.43	165.60	3.986		
18,300.00	12,174.68	18,317.29	12,176.67	83.17	85.37	-90.17	-5,926.00	545.60	660.03	491.74	168.29	3.922		
18,400.00	12,175.55	18,417.29	12,177.55	84.52	86.72	-90.17	-6,025.99	546.46	660.03	489.05	170.98	3.860		
18,500.00	12,176.42	18,517.29	12,178.42	85.86	88.06	-90.17	-6,125.98	547.32	660.03	486.36	173.67	3.800		
18,600.00	12,177.29	18,617.29	12,179.29	87.21	89.40	-90.17	-6,225.97	548.19	660.03	483.66	176.36	3.742		
18,700.00	12,178.16	18,717.29	12,180.16	88.56	90.74	-90.17	-6,325.97	549.05	660.03	480.97	179.06	3.686		
18,800.00	12,179.03	18,817.29	12,181.03	89.91	92.09	-90.17	-6,425.96	549.91	660.03	478.27	181.76	3.631		
18,900.00	12,179.90	18,917.29	12,181.90	91.26	93.44	-90.17	-6,525.95	550.77	660.03	475.57	184.46	3.578		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 20 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 132H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
19,000.00	12,180.78	19,017.29	12,182.77	92.61	94.78	-90.17	-6,625.94	551.63	660.03	472.87	187.15	3.527			
19,100.00	12,181.65	19,117.29	12,183.65	93.96	96.13	-90.17	-6,725.94	552.49	660.03	470.17	189.86	3.476			
19,200.00	12,182.52	19,217.29	12,184.52	95.31	97.48	-90.17	-6,825.93	553.35	660.03	467.47	192.56	3.428			
19,300.00	12,183.39	19,317.29	12,185.39	96.66	98.82	-90.17	-6,925.92	554.21	660.03	464.77	195.26	3.380			
19,400.00	12,184.26	19,417.29	12,186.26	98.01	100.17	-90.17	-7,025.91	555.07	660.03	462.07	197.96	3.334			
19,500.00	12,185.13	19,517.29	12,187.13	99.36	101.52	-90.17	-7,125.91	555.93	660.03	459.36	200.67	3.289			
19,600.00	12,186.00	19,617.29	12,188.00	100.72	102.87	-90.17	-7,225.90	556.80	660.03	456.66	203.37	3.245			
19,700.00	12,186.87	19,717.29	12,188.87	102.07	104.22	-90.17	-7,325.89	557.66	660.03	453.95	206.08	3.203			
19,800.00	12,187.75	19,817.29	12,189.75	103.42	105.57	-90.17	-7,425.88	558.52	660.03	451.24	208.79	3.161			
19,900.00	12,188.62	19,917.29	12,190.62	104.78	106.92	-90.17	-7,525.88	559.38	660.03	448.53	211.50	3.121			
20,000.00	12,189.49	20,017.29	12,191.49	106.13	108.28	-90.17	-7,625.87	560.24	660.03	445.82	214.21	3.081			
20,100.00	12,190.36	20,117.29	12,192.36	107.49	109.63	-90.17	-7,725.86	561.10	660.03	443.11	216.92	3.043			
20,200.00	12,191.23	20,217.29	12,193.23	108.84	110.98	-90.17	-7,825.85	561.96	660.03	440.40	219.63	3.005			
20,300.00	12,192.10	20,317.29	12,194.10	110.20	112.33	-90.17	-7,925.85	562.82	660.03	437.69	222.34	2.969			
20,400.00	12,192.97	20,417.29	12,194.97	111.55	113.69	-90.17	-8,025.84	563.68	660.03	434.98	225.05	2.933			
20,500.00	12,193.85	20,517.29	12,195.85	112.91	115.04	-90.17	-8,125.83	564.54	660.03	432.27	227.76	2.898			
20,600.00	12,194.72	20,617.29	12,196.72	114.27	116.40	-90.17	-8,225.82	565.40	660.03	429.55	230.47	2.864			
20,700.00	12,195.59	20,717.29	12,197.59	115.62	117.75	-90.17	-8,325.82	566.27	660.03	426.84	233.19	2.830			
20,800.00	12,196.46	20,817.29	12,198.46	116.98	119.10	-90.17	-8,425.81	567.13	660.03	424.13	235.90	2.798			
20,900.00	12,197.33	20,917.29	12,199.33	118.34	120.46	-90.17	-8,525.80	567.99	660.03	421.41	238.62	2.766			
21,000.00	12,198.20	21,017.29	12,200.20	119.70	121.82	-90.17	-8,625.79	568.85	660.03	418.70	241.33	2.735			
21,100.00	12,199.07	21,117.29	12,201.07	121.05	123.17	-90.17	-8,725.79	569.71	660.03	415.98	244.05	2.704			
21,200.00	12,199.94	21,217.29	12,201.94	122.41	124.53	-90.17	-8,825.78	570.57	660.03	413.26	246.77	2.675			
21,300.00	12,200.82	21,317.29	12,202.82	123.77	125.88	-90.17	-8,925.77	571.43	660.03	410.55	249.48	2.646			
21,400.00	12,201.69	21,417.29	12,203.69	125.13	127.24	-90.17	-9,025.76	572.29	660.03	407.83	252.20	2.617			
21,500.00	12,202.56	21,517.29	12,204.56	126.49	128.60	-90.17	-9,125.76	573.15	660.03	405.11	254.92	2.589			
21,600.00	12,203.43	21,617.29	12,205.43	127.85	129.96	-90.17	-9,225.75	574.01	660.03	402.39	257.64	2.562			
21,700.00	12,204.30	21,717.29	12,206.30	129.21	131.31	-90.17	-9,325.74	574.88	660.03	399.67	260.36	2.535			
21,800.00	12,205.17	21,817.29	12,207.17	130.57	132.67	-90.17	-9,425.73	575.74	660.03	396.95	263.08	2.509			
21,900.00	12,206.04	21,917.29	12,208.04	131.93	134.03	-90.17	-9,525.73	576.60	660.03	394.23	265.80	2.483			
22,000.00	12,206.91	22,017.29	12,208.92	133.29	135.39	-90.17	-9,625.72	577.46	660.03	391.51	268.52	2.458			
22,100.00	12,207.79	22,117.29	12,209.79	134.65	136.75	-90.17	-9,725.71	578.32	660.03	388.79	271.24	2.433			
22,200.00	12,208.66	22,217.29	12,210.66	136.01	138.11	-90.17	-9,825.70	579.18	660.03	386.07	273.96	2.409			
22,300.00	12,209.53	22,317.29	12,211.53	137.37	139.46	-90.17	-9,925.70	580.04	660.03	383.35	276.68	2.386			
22,400.00	12,210.40	22,417.29	12,212.40	138.73	140.82	-90.17	-10,025.69	580.90	660.03	380.63	279.40	2.362			
22,401.19	12,210.41	22,418.48	12,212.41	138.75	140.84	-90.17	-10,026.88	580.91	660.03	380.60	279.43	2.362			
22,411.61	12,210.50	22,428.60	12,212.50	138.89	140.98	-90.17	-10,037.00	581.00	660.03	380.32	279.71	2.360	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 21 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 133H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Rule Assigned:	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
1,700.00	1,696.95	2,024.21	2,014.69	5.25	5.78	89.63	945.93	2,212.38	2,424.20	2,413.53	10.67	227.218			
1,800.00	1,796.09	2,120.95	2,110.24	5.44	5.96	90.14	933.41	2,203.87	2,411.11	2,400.06	11.05	218.106			
1,900.00	1,895.24	2,217.69	2,205.79	5.64	6.15	90.65	920.90	2,195.37	2,398.23	2,386.79	11.44	209.618			
2,000.00	1,994.38	2,314.43	2,301.34	5.83	6.34	91.16	908.39	2,186.87	2,385.54	2,373.71	11.83	201.693			
2,100.00	2,093.53	2,411.17	2,396.88	6.03	6.53	91.69	895.88	2,178.36	2,373.06	2,360.84	12.21	194.279			
2,200.00	2,192.67	2,507.90	2,492.43	6.22	6.72	92.21	883.37	2,169.86	2,360.78	2,348.18	12.60	187.328			
2,300.00	2,291.82	2,604.64	2,587.98	6.42	6.91	92.75	870.86	2,161.36	2,348.71	2,335.72	12.99	180.802			
2,400.00	2,390.96	2,701.38	2,683.53	6.61	7.10	93.28	858.35	2,152.85	2,336.85	2,323.47	13.38	174.663			
2,500.00	2,490.11	2,798.12	2,779.07	6.81	7.30	93.83	845.84	2,144.35	2,325.21	2,311.44	13.77	168.879			
2,600.00	2,589.25	2,894.85	2,874.62	7.00	7.49	94.37	833.33	2,135.84	2,313.79	2,299.63	14.16	163.423			
2,700.00	2,688.39	2,991.59	2,970.17	7.20	7.70	94.93	820.82	2,127.34	2,302.59	2,288.04	14.55	158.260			
2,800.00	2,787.54	3,088.33	3,065.72	7.39	7.92	95.48	808.31	2,118.84	2,291.61	2,276.67	14.94	153.388			
2,900.00	2,886.68	3,185.07	3,161.26	7.59	8.13	96.05	795.80	2,110.33	2,280.87	2,265.54	15.33	148.768			
3,000.00	2,985.83	3,281.80	3,256.81	7.78	8.35	96.61	783.29	2,101.83	2,270.35	2,254.63	15.72	144.388			
3,100.00	3,084.97	3,378.54	3,352.36	7.98	8.56	97.19	770.78	2,093.33	2,260.07	2,243.96	16.12	140.230			
3,200.00	3,184.12	3,475.28	3,447.91	8.17	8.78	97.76	758.27	2,084.82	2,250.03	2,233.52	16.51	136.278			
3,300.00	3,283.26	3,572.02	3,543.45	8.36	9.00	98.35	745.76	2,076.32	2,240.23	2,223.33	16.90	132.520			
3,400.00	3,382.40	3,668.75	3,639.00	8.56	9.21	98.93	733.25	2,067.81	2,230.68	2,213.38	17.30	128.942			
3,500.00	3,481.55	3,765.49	3,734.55	8.75	9.43	99.52	720.74	2,059.31	2,221.37	2,203.68	17.70	125.533			
3,600.00	3,580.69	3,862.23	3,830.10	8.95	9.65	100.12	708.23	2,050.81	2,212.32	2,194.22	18.09	122.282			
3,700.00	3,679.84	3,958.97	3,925.65	9.14	9.87	100.72	695.72	2,042.30	2,203.51	2,185.02	18.49	119.179			
3,800.00	3,778.98	4,055.71	4,021.19	9.33	10.09	101.33	683.20	2,033.80	2,194.97	2,176.08	18.89	116.216			
3,900.00	3,878.13	4,152.44	4,116.74	9.53	10.31	101.94	670.69	2,025.30	2,186.68	2,167.40	19.29	113.385			
4,000.00	3,977.27	4,249.18	4,212.29	9.72	10.52	102.55	658.18	2,016.79	2,178.66	2,158.98	19.68	110.677			
4,100.00	4,076.42	4,345.92	4,307.84	9.91	10.74	103.17	645.67	2,008.29	2,170.91	2,150.82	20.08	108.087			
4,200.00	4,175.56	4,442.66	4,403.38	10.11	10.96	103.79	633.16	1,999.78	2,163.42	2,142.93	20.49	105.606			
4,300.00	4,274.70	4,539.39	4,498.93	10.30	11.18	104.42	620.65	1,991.28	2,156.21	2,135.32	20.89	103.231			
4,400.00	4,373.85	4,636.13	4,594.48	10.49	11.40	105.05	608.14	1,982.78	2,149.26	2,127.98	21.29	100.954			
4,500.00	4,472.99	4,732.87	4,690.03	10.69	11.62	105.68	595.63	1,974.27	2,142.60	2,120.91	21.69	98.771			
4,600.00	4,572.14	4,829.61	4,785.57	10.88	11.84	106.32	583.12	1,965.77	2,136.22	2,114.12	22.10	96.677			
4,700.00	4,671.28	4,926.34	4,881.12	11.08	12.06	106.96	570.61	1,957.27	2,130.12	2,107.61	22.50	94.659			
4,702.13	4,673.39	4,928.41	4,883.16	11.08	12.07	106.98	570.34	1,957.08	2,129.99	2,107.48	22.51	94.617			
4,800.00	4,770.58	5,023.35	4,976.93	11.28	12.28	107.49	558.07	1,948.74	2,123.92	2,101.02	22.90	92.747			
4,900.00	4,870.15	5,120.86	5,073.24	11.48	12.50	107.95	545.45	1,940.17	2,117.18	2,093.89	23.28	90.931			
5,000.00	4,969.93	5,218.81	5,169.99	11.67	12.73	108.35	532.79	1,931.56	2,109.81	2,086.16	23.65	89.211			
5,100.00	5,069.85	5,317.14	5,267.11	11.85	12.95	108.67	520.07	1,922.91	2,101.78	2,077.78	24.00	87.591			
5,200.00	5,169.84	5,400.00	5,348.96	11.99	13.11	108.87	509.43	1,915.68	2,093.13	2,068.86	24.27	86.253			
5,202.16	5,172.00	5,400.00	5,348.96	12.00	13.11	88.63	509.43	1,915.68	2,092.95	2,068.68	24.27	86.236			
5,300.00	5,269.84	5,480.56	5,428.74	12.08	13.28	88.88	500.17	1,909.38	2,085.04	2,060.51	24.53	84.992			
5,400.00	5,369.84	5,556.02	5,503.67	12.17	13.43	89.09	492.75	1,904.34	2,078.16	2,053.39	24.77	83.883			
5,500.00	5,469.84	5,631.81	5,579.08	12.26	13.56	89.26	486.54	1,900.12	2,072.45	2,047.45	25.00	82.883			
5,600.00	5,569.84	5,700.00	5,647.05	12.34	13.67	89.38	482.01	1,897.04	2,067.92	2,042.71	25.21	82.033			
5,700.00	5,669.84	5,784.15	5,731.04	12.43	13.78	89.50	477.80	1,894.18	2,064.51	2,039.09	25.42	81.207			
5,800.00	5,769.84	5,860.57	5,807.40	12.52	13.87	89.56	475.30	1,892.48	2,062.26	2,036.65	25.61	80.532			
5,900.00	5,869.84	5,937.08	5,883.90	12.61	13.93	89.60	474.07	1,891.65	2,061.16	2,035.40	25.76	80.016			
5,963.09	5,932.92	5,989.11	5,935.92	12.66	13.95	89.60	473.93	1,891.55	2,061.03	2,035.20	25.83	79.797			
6,000.00	5,969.84	6,026.02	5,972.84	12.69	13.95	89.60	473.93	1,891.55	2,061.03	2,035.16	25.87	79.674			
6,100.00	6,069.84	6,126.02	6,072.84	12.78	13.99	89.60	473.93	1,891.55	2,061.03	2,035.04	25.99	79.305			
6,200.00	6,169.84	6,226.02	6,172.84	12.87	14.02	89.60	473.93	1,891.55	2,061.03	2,034.92	26.11	78.939			
6,300.00	6,269.84	6,326.02	6,272.84	12.96	14.05	89.60	473.93	1,891.55	2,061.03	2,034.80	26.23	78.575			
6,400.00	6,369.84	6,426.02	6,372.84	13.04	14.09	89.60	473.93	1,891.55	2,061.03	2,034.68	26.35	78.214			
6,500.00	6,469.84	6,526.02	6,472.84	13.13	14.12	89.60	473.93	1,891.55	2,061.03	2,034.56	26.47	77.855			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 22 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 133H - OH - Plan 1													Offset Site Error: 0.00 usft	
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error: 0.50 usft	
Reference		Offset		Semi Major Axis		Offset Wellbore Centre			Rule Assigned: Distance				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
21,000.00	12,198.20	20,967.47	12,131.43	119.70	133.17	-88.04	-8,613.48	1,949.18	2,041.61	1,789.05	252.55	8.084		
21,100.00	12,199.07	21,067.47	12,132.13	121.05	134.54	-88.04	-8,713.47	1,950.09	2,041.66	1,786.39	255.27	7.998		
21,200.00	12,199.94	21,167.47	12,132.83	122.41	135.90	-88.03	-8,813.46	1,950.99	2,041.71	1,783.72	257.99	7.914		
21,300.00	12,200.82	21,267.47	12,133.52	123.77	137.26	-88.03	-8,913.46	1,951.90	2,041.76	1,781.05	260.71	7.832		
21,400.00	12,201.69	21,367.47	12,134.22	125.13	138.62	-88.02	-9,013.45	1,952.81	2,041.81	1,778.39	263.43	7.751		
21,500.00	12,202.56	21,467.47	12,134.92	126.49	139.98	-88.02	-9,113.44	1,953.72	2,041.87	1,775.72	266.15	7.672		
21,600.00	12,203.43	21,567.47	12,135.62	127.85	141.34	-88.01	-9,213.44	1,954.62	2,041.92	1,773.05	268.87	7.594		
21,700.00	12,204.30	21,667.47	12,136.32	129.21	142.71	-88.01	-9,313.43	1,955.53	2,041.97	1,770.38	271.59	7.519		
21,800.00	12,205.17	21,767.47	12,137.02	130.57	144.07	-88.00	-9,413.42	1,956.44	2,042.02	1,767.71	274.31	7.444		
21,900.00	12,206.04	21,867.47	12,137.71	131.93	145.43	-88.00	-9,513.42	1,957.34	2,042.07	1,765.04	277.03	7.371		
22,000.00	12,206.91	21,967.47	12,138.41	133.29	146.79	-87.99	-9,613.41	1,958.25	2,042.12	1,762.37	279.75	7.300		
22,100.00	12,207.79	22,067.47	12,139.11	134.65	148.15	-87.99	-9,713.40	1,959.16	2,042.18	1,759.70	282.47	7.230		
22,200.00	12,208.66	22,167.47	12,139.81	136.01	149.52	-87.98	-9,813.40	1,960.06	2,042.23	1,757.03	285.20	7.161		
22,300.00	12,209.53	22,267.47	12,140.51	137.37	150.88	-87.98	-9,913.39	1,960.97	2,042.28	1,754.36	287.92	7.093		
22,400.00	12,210.40	22,367.47	12,141.21	138.73	152.24	-87.97	-10,013.38	1,961.88	2,042.33	1,751.69	290.64	7.027		
22,411.61	12,210.50	22,379.08	12,141.29	138.89	152.40	-87.97	-10,025.00	1,961.98	2,042.34	1,751.38	290.96	7.019	ES, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 26 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 137H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft		
Reference		Offset		Semi Major Axis		Offset Wellbore Centre			Distance		Separation		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	0.00	0.00	0.50	0.50	0.00	185.00	0.00	185.00					
100.00	100.00	100.00	100.00	0.98	0.98	0.00	185.00	0.00	185.00	183.04	1.96	94.283	CC ES	
200.00	200.00	200.00	200.00	1.56	1.56	0.00	185.00	0.00	185.00	181.88	3.12	59.252		
300.00	300.00	300.00	300.00	1.98	1.98	0.00	185.00	0.00	185.00	181.04	3.96	46.690		
400.00	400.00	398.83	398.82	2.33	2.41	0.38	185.31	1.24	185.31	180.66	4.66	39.796		
500.00	500.00	497.53	497.44	2.63	2.77	1.53	186.22	4.96	186.31	181.04	5.26	35.390		
600.00	600.00	595.97	595.67	2.91	3.10	3.39	187.74	11.13	188.12	182.30	5.82	32.333		
700.00	700.00	695.04	694.38	3.16	3.25	5.82	189.77	19.33	190.83	184.62	6.21	30.713		
800.00	800.00	794.66	793.62	3.40	3.49	8.23	191.85	27.76	193.95	187.25	6.70	28.935		
900.00	899.99	894.26	892.84	3.68	3.73	30.98	193.92	36.19	196.28	189.07	7.21	27.210		
1,000.00	999.91	993.76	991.96	3.94	3.96	33.85	196.00	44.61	196.81	189.11	7.70	25.567		
1,053.81	1,053.65	1,047.26	1,045.27	4.05	4.08	35.51	197.12	49.14	196.72	188.79	7.93	24.807		
1,100.00	1,099.77	1,093.19	1,091.02	4.15	4.18	36.93	198.07	53.03	196.78	188.65	8.13	24.206		
1,200.00	1,199.63	1,192.62	1,190.07	4.35	4.41	40.01	200.15	61.44	197.34	188.79	8.55	23.078		
1,250.43	1,250.00	1,242.77	1,240.03	4.40	4.52	41.55	201.19	65.68	197.83	189.12	8.71	22.714		
1,300.00	1,299.48	1,292.03	1,289.10	4.45	4.62	43.11	202.22	69.85	198.22	189.36	8.87	22.354		
1,400.00	1,399.17	1,391.27	1,387.96	4.69	4.84	46.65	204.29	78.25	198.12	188.82	9.30	21.307		
1,500.00	1,498.62	1,490.24	1,486.56	4.93	5.05	50.76	206.36	86.63	197.12	187.40	9.72	20.283		
1,550.47	1,548.70	1,540.06	1,536.19	4.99	5.15	53.06	207.40	90.84	196.40	186.53	9.88	19.888		
1,600.00	1,597.81	1,588.92	1,584.87	5.05	5.25	55.40	208.42	94.98	195.83	185.81	10.03	19.526		
1,658.78	1,656.08	1,646.90	1,642.62	5.17	5.37	58.19	209.63	99.88	195.60	185.33	10.26	19.059		
1,700.00	1,696.95	1,687.57	1,683.13	5.25	5.46	60.15	210.47	103.32	195.71	185.29	10.43	18.770		
1,800.00	1,796.09	1,786.21	1,781.40	5.44	5.66	64.87	212.53	111.67	196.97	186.14	10.82	18.199		
1,900.00	1,895.24	1,884.85	1,879.66	5.64	5.86	69.50	214.59	120.02	199.57	188.36	11.22	17.793		
2,000.00	1,994.38	1,983.49	1,977.93	5.83	6.06	73.98	216.65	128.36	203.47	191.87	11.61	17.529		
2,100.00	2,093.53	2,082.13	2,076.19	6.03	6.26	78.28	218.71	136.71	208.60	196.61	12.00	17.389		
2,200.00	2,192.67	2,180.77	2,174.46	6.22	6.46	82.35	220.76	145.06	214.87	202.48	12.39	17.341		
2,300.00	2,291.82	2,275.44	2,268.71	6.42	6.66	86.05	222.89	153.67	222.82	210.05	12.77	17.447		
2,400.00	2,390.96	2,368.24	2,360.87	6.61	6.87	89.50	225.49	164.23	234.04	220.89	13.15	17.796		
2,500.00	2,490.11	2,460.38	2,452.09	6.81	7.09	92.64	228.61	176.87	248.49	234.97	13.53	18.373		
2,600.00	2,589.25	2,551.78	2,542.23	7.00	7.30	95.44	232.21	191.51	266.05	252.16	13.89	19.153		
2,700.00	2,688.39	2,642.33	2,631.16	7.20	7.51	97.86	236.30	208.07	286.54	272.29	14.25	20.112		
2,800.00	2,787.54	2,731.95	2,718.75	7.39	7.72	99.92	240.83	226.48	309.80	295.21	14.60	21.226		
2,900.00	2,886.68	2,820.56	2,804.88	7.59	7.92	101.66	245.80	246.63	335.68	320.76	14.93	22.487		
3,000.00	2,985.83	2,911.35	2,892.67	7.78	8.09	103.15	251.34	269.11	363.87	348.63	15.24	23.875		
3,100.00	3,084.97	3,006.73	2,984.81	7.98	8.29	104.49	257.25	293.08	392.66	377.03	15.63	25.126		
3,200.00	3,184.12	3,102.12	3,076.94	8.17	8.49	105.64	263.16	317.06	421.62	405.60	16.02	26.326		
3,300.00	3,283.26	3,197.51	3,169.08	8.36	8.70	106.65	269.07	341.03	450.72	434.31	16.41	27.473		
3,400.00	3,382.40	3,292.90	3,261.22	8.56	8.91	107.54	274.98	365.01	479.93	463.14	16.80	28.571		
3,500.00	3,481.55	3,388.29	3,353.36	8.75	9.14	108.32	280.89	388.99	509.24	492.05	17.19	29.622		
3,600.00	3,580.69	3,483.68	3,445.49	8.95	9.38	109.02	286.80	412.96	538.62	521.04	17.59	30.627		
3,700.00	3,679.84	3,579.07	3,537.63	9.14	9.64	109.65	292.71	436.94	568.08	550.09	17.98	31.589		
3,800.00	3,778.98	3,674.45	3,629.77	9.33	9.92	110.22	298.62	460.92	597.58	579.20	18.38	32.510		
3,900.00	3,878.13	3,769.84	3,721.90	9.53	10.21	110.73	304.53	484.89	627.14	608.36	18.78	33.392		
4,000.00	3,977.27	3,865.23	3,814.04	9.72	10.50	111.20	310.44	508.87	656.74	637.55	19.18	34.237		
4,100.00	4,076.42	3,960.62	3,906.18	9.91	10.80	111.62	316.35	532.84	686.37	666.79	19.58	35.048		
4,200.00	4,175.56	4,056.01	3,998.31	10.11	11.11	112.01	322.26	556.82	716.04	696.05	19.99	35.825		
4,300.00	4,274.70	4,151.40	4,090.45	10.30	11.41	112.38	328.17	580.80	745.73	725.34	20.39	36.570		
4,400.00	4,373.85	4,246.79	4,182.59	10.49	11.72	112.71	334.08	604.77	775.45	754.65	20.80	37.286		
4,500.00	4,472.99	4,342.18	4,274.72	10.69	12.03	113.02	339.99	628.75	805.19	783.98	21.20	37.974		
4,600.00	4,572.14	4,437.56	4,366.86	10.88	12.34	113.30	345.90	652.72	834.95	813.34	21.61	38.635		
4,700.00	4,671.28	4,532.95	4,459.00	11.08	12.65	113.57	351.81	676.70	864.73	842.71	22.02	39.267		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 27 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 137H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
9,800.00	9,769.84	9,902.30	9,769.84	15.97	20.84	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,286.41	33.62	39.263	
9,900.00	9,869.84	10,002.30	9,869.84	16.06	20.90	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,286.27	33.76	39.097	
10,000.00	9,969.84	10,102.30	9,969.84	16.14	20.96	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,286.12	33.91	38.932	
10,100.00	10,069.84	10,202.30	10,069.84	16.23	21.01	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.98	34.05	38.769	
10,200.00	10,169.84	10,302.30	10,169.84	16.31	21.07	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.84	34.19	38.607	
10,300.00	10,269.84	10,402.30	10,269.84	16.40	21.13	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.70	34.34	38.445	
10,400.00	10,369.84	10,502.30	10,369.84	16.48	21.18	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.55	34.48	38.286	
10,500.00	10,469.84	10,602.30	10,469.84	16.57	21.24	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.41	34.62	38.127	
10,600.00	10,569.84	10,702.30	10,569.84	16.65	21.30	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.26	34.77	37.969	
10,700.00	10,669.84	10,802.30	10,669.84	16.74	21.35	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,285.12	34.91	37.813	
10,800.00	10,769.84	10,902.30	10,769.84	16.82	21.41	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.98	35.05	37.658	
10,900.00	10,869.84	11,002.30	10,869.84	16.91	21.47	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.83	35.20	37.504	
11,000.00	10,969.84	11,102.30	10,969.84	16.99	21.53	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.69	35.34	37.351	
11,100.00	11,069.84	11,202.30	11,069.84	17.08	21.59	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.54	35.49	37.199	
11,200.00	11,169.84	11,302.30	11,169.84	17.16	21.64	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.40	35.63	37.048	
11,300.00	11,269.84	11,402.30	11,269.84	17.25	21.70	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.26	35.78	36.898	
11,400.00	11,369.84	11,502.30	11,369.84	17.33	21.76	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,284.11	35.92	36.749	
11,500.00	11,469.84	11,602.30	11,469.84	17.42	21.82	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,283.97	36.06	36.602	
11,581.16	11,551.00	11,683.47	11,551.00	17.48	21.86	89.61	89.61	89.61	468.62	1,150.57	1,320.03	1,283.86	36.17	36.498	
11,600.00	11,569.83	11,702.24	11,569.77	17.48	21.86	-89.90	-89.90	-89.90	468.40	1,150.57	1,320.03	1,283.86	36.17	36.497	
11,650.00	11,619.67	11,752.05	11,619.44	17.49	21.90	-89.91	-89.91	-89.91	464.87	1,150.60	1,320.03	1,283.91	36.12	36.541	
11,700.00	11,668.99	11,801.89	11,668.64	17.51	21.93	-89.93	-89.93	-89.93	457.03	1,150.67	1,320.03	1,283.98	36.05	36.618	
11,750.00	11,717.40	11,851.75	11,717.00	17.51	21.95	-89.94	-89.94	-89.94	444.95	1,150.77	1,320.03	1,284.08	35.94	36.724	
11,800.00	11,764.55	11,901.64	11,764.15	17.52	21.97	-89.95	-89.95	-89.95	428.69	1,150.91	1,320.03	1,284.22	35.81	36.858	
11,850.00	11,810.08	11,951.55	11,809.73	17.52	21.99	-89.97	-89.97	-89.97	408.39	1,151.09	1,320.03	1,284.37	35.66	37.015	
11,900.00	11,853.63	12,001.50	11,853.40	17.52	22.01	-89.98	-89.98	-89.98	384.18	1,151.30	1,320.03	1,284.53	35.50	37.189	
11,914.74	11,866.04	12,016.22	11,865.85	17.52	22.01	-89.98	-89.98	-89.98	376.32	1,151.37	1,320.03	1,284.58	35.44	37.242	
11,950.00	11,894.88	12,051.47	11,894.81	17.53	22.03	-89.99	-89.99	-89.99	356.24	1,151.54	1,320.03	1,284.71	35.32	37.372	
12,000.00	11,933.52	12,101.47	11,933.66	17.53	22.05	-90.01	-90.01	-90.01	324.78	1,151.81	1,320.03	1,284.88	35.15	37.558	
12,050.00	11,969.24	12,151.51	11,969.64	17.53	22.09	-90.02	-90.02	-90.02	290.04	1,152.11	1,320.03	1,285.05	34.98	37.736	
12,100.00	12,001.78	12,201.57	12,002.46	17.53	22.13	-90.04	-90.04	-90.04	252.27	1,152.43	1,320.03	1,285.20	34.83	37.897	
12,150.00	12,030.89	12,251.66	12,031.89	17.53	22.19	-90.05	-90.05	-90.05	211.75	1,152.78	1,320.03	1,285.32	34.71	38.031	
12,200.00	12,056.34	12,301.77	12,057.67	17.53	22.26	-90.07	-90.07	-90.07	168.80	1,153.15	1,320.03	1,285.41	34.62	38.127	
12,250.00	12,077.95	12,351.92	12,079.62	17.54	22.36	-90.08	-90.08	-90.08	123.73	1,153.54	1,320.03	1,285.46	34.58	38.178	
12,300.00	12,095.55	12,402.09	12,097.55	17.55	22.47	-90.09	-90.09	-90.09	76.89	1,153.94	1,320.03	1,285.45	34.58	38.176	
12,350.00	12,109.01	12,452.28	12,111.32	17.56	22.61	-90.10	-90.10	-90.10	28.64	1,154.36	1,320.03	1,285.40	34.63	38.116	
12,400.00	12,118.22	12,502.50	12,120.82	17.58	22.76	-90.11	-90.11	-90.11	-20.65	1,154.78	1,320.03	1,285.29	34.74	37.995	
12,450.00	12,123.11	12,552.74	12,125.97	17.60	22.94	-90.12	-90.12	-90.12	-70.61	1,155.21	1,320.03	1,285.13	34.91	37.816	
12,476.17	12,123.94	12,579.05	12,126.91	17.61	23.04	-90.13	-90.13	-90.13	-96.90	1,155.44	1,320.03	1,285.02	35.01	37.700	
12,500.00	12,124.14	12,602.89	12,127.12	17.62	23.14	-90.13	-90.13	-90.13	-120.74	1,155.65	1,320.03	1,284.91	35.12	37.581	
12,600.00	12,125.02	12,702.89	12,127.99	17.69	23.58	-90.13	-90.13	-90.13	-220.73	1,156.51	1,320.03	1,284.29	35.75	36.927	
12,700.00	12,125.89	12,802.89	12,128.87	17.79	24.07	-90.13	-90.13	-90.13	-320.72	1,157.37	1,320.03	1,283.47	36.57	36.099	
12,800.00	12,126.76	12,902.89	12,129.74	17.95	24.63	-90.13	-90.13	-90.13	-420.71	1,158.23	1,320.03	1,282.46	37.57	35.134	
12,900.00	12,127.63	13,002.89	12,130.61	18.21	25.23	-90.13	-90.13	-90.13	-520.71	1,159.09	1,320.04	1,281.29	38.75	34.069	
13,000.00	12,128.50	13,102.89	12,131.48	18.61	25.88	-90.13	-90.13	-90.13	-620.70	1,159.95	1,320.04	1,279.96	40.08	32.938	
13,100.00	12,129.37	13,202.89	12,132.35	19.18	26.58	-90.13	-90.13	-90.13	-720.69	1,160.81	1,320.04	1,278.49	41.55	31.773	
13,200.00	12,130.24	13,302.89	12,133.22	19.87	27.32	-90.13	-90.13	-90.13	-820.68	1,161.68	1,320.04	1,276.90	43.14	30.598	
13,300.00	12,131.11	13,402.89	12,134.10	20.66	28.10	-90.13	-90.13	-90.13	-920.68	1,162.54	1,320.04	1,275.19	44.85	29.434	
13,400.00	12,131.99	13,502.89	12,134.97	21.53	28.92	-90.13	-90.13	-90.13	-1,020.67	1,163.40	1,320.04	1,273.38	46.65	28.295	
13,500.00	12,132.86	13,602.89	12,135.84	22.45	29.77	-90.13	-90.13	-90.13	-1,120.66	1,164.26	1,320.04	1,271.49	48.55	27.191	
13,600.00	12,133.73	13,702.89	12,136.71	23.43	30.66	-90.13	-90.13	-90.13	-1,220.65	1,165.12	1,320.04	1,269.52	50.52	26.130	
13,700.00	12,134.60	13,802.89	12,137.58	24.44	31.58	-90.13	-90.13	-90.13	-1,320.65	1,165.98	1,320.04	1,267.48	52.56	25.115	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 29 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 151H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:					Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)	
0.00	0.00	1.00	1.00	0.50	0.50	0.00	25.00	0.00	25.00					
100.00	100.00	101.00	101.00	0.98	0.99	0.00	25.00	0.00	25.00	23.03	1.97	12.706		
200.00	200.00	201.00	201.00	1.56	1.57	0.00	25.00	0.00	25.00	21.87	3.13	7.996		
300.00	300.00	301.00	301.00	1.98	1.98	0.00	25.00	0.00	25.00	21.03	3.97	6.304		
400.00	400.00	401.00	401.00	2.33	2.33	0.00	25.00	0.00	25.00	20.34	4.66	5.363		
416.33	416.33	417.33	417.33	2.38	2.38	0.00	25.00	0.00	25.00	20.24	4.76	5.251	CC	
500.00	500.00	501.00	501.00	2.63	2.64	0.00	25.00	0.00	25.00	19.73	5.27	4.742	ES	
600.00	600.00	600.70	600.69	2.91	2.98	-2.71	25.55	-1.21	25.58	19.75	5.83	4.385		
700.00	700.00	700.27	700.18	3.16	3.29	-9.97	27.17	-4.78	27.60	21.24	6.36	4.340		
800.00	800.00	799.57	799.26	3.40	3.57	-19.69	29.86	-10.69	31.77	24.89	6.88	4.620		
900.00	899.99	899.06	898.39	3.68	3.70	-8.98	33.39	-18.44	36.95	29.65	7.30	5.063		
1,000.00	999.91	998.84	997.79	3.94	3.92	-17.15	37.00	-26.36	40.52	32.72	7.80	5.197		
1,100.00	1,099.77	1,098.65	1,097.22	4.15	4.13	-24.59	40.60	-34.28	43.58	35.36	8.23	5.299		
1,200.00	1,199.63	1,198.45	1,196.64	4.35	4.35	-30.96	44.20	-42.19	47.29	38.64	8.64	5.470		
1,250.43	1,250.00	1,248.20	1,246.17	4.40	4.48	-33.83	46.11	-46.39	49.63	40.82	8.81	5.634		
1,300.00	1,299.48	1,296.98	1,294.67	4.45	4.60	-36.67	48.25	-51.08	52.41	43.44	8.97	5.843		
1,400.00	1,399.17	1,395.15	1,392.08	4.69	4.84	-42.88	53.32	-62.23	58.85	49.45	9.41	6.256		
1,500.00	1,498.62	1,492.98	1,488.80	4.93	5.09	-49.31	59.40	-75.59	66.70	56.89	9.81	6.797		
1,550.47	1,548.70	1,542.20	1,537.31	4.99	5.21	-52.50	62.85	-83.17	71.29	61.34	9.96	7.161		
1,600.00	1,597.81	1,590.40	1,584.70	5.05	5.33	-55.40	66.48	-91.14	76.43	66.34	10.09	7.572		
1,700.00	1,696.95	1,688.51	1,680.90	5.25	5.47	-59.99	74.47	-108.70	88.77	78.38	10.39	8.544		
1,800.00	1,796.09	1,787.49	1,777.90	5.44	5.67	-63.44	82.64	-126.66	101.80	91.04	10.76	9.459		
1,900.00	1,895.24	1,886.48	1,874.90	5.64	5.88	-66.09	90.81	-144.61	115.10	103.96	11.15	10.325		
2,000.00	1,994.38	1,985.47	1,971.90	5.83	6.08	-68.20	98.99	-162.57	128.60	117.06	11.54	11.147		
2,100.00	2,093.53	2,084.45	2,068.90	6.03	6.29	-69.90	107.16	-180.52	142.24	130.31	11.93	11.923		
2,200.00	2,192.67	2,183.44	2,165.90	6.22	6.50	-71.31	115.33	-198.48	155.98	143.65	12.33	12.654		
2,300.00	2,291.82	2,282.42	2,262.90	6.42	6.71	-72.49	123.50	-216.43	169.79	157.07	12.72	13.344		
2,400.00	2,390.96	2,381.41	2,359.90	6.61	6.93	-73.48	131.67	-234.38	183.67	170.54	13.12	13.994		
2,500.00	2,490.11	2,480.39	2,456.90	6.81	7.15	-74.34	139.84	-252.34	197.59	184.06	13.53	14.608		
2,600.00	2,589.25	2,579.38	2,553.90	7.00	7.39	-75.09	148.01	-270.29	211.55	197.62	13.93	15.187		
2,700.00	2,688.39	2,678.37	2,650.90	7.20	7.63	-75.74	156.19	-288.25	225.54	211.21	14.33	15.734		
2,800.00	2,787.54	2,777.35	2,747.90	7.39	7.89	-76.32	164.36	-306.20	239.56	224.82	14.74	16.253		
2,900.00	2,886.68	2,876.34	2,844.90	7.59	8.14	-76.83	172.53	-324.16	253.59	238.45	15.15	16.743		
3,000.00	2,985.83	2,975.32	2,941.90	7.78	8.40	-77.29	180.70	-342.11	267.65	252.10	15.55	17.208		
3,100.00	3,084.97	3,074.31	3,038.90	7.98	8.65	-77.71	188.87	-360.07	281.72	265.76	15.96	17.649		
3,200.00	3,184.12	3,173.29	3,135.90	8.17	8.91	-78.08	197.04	-378.02	295.81	279.43	16.37	18.069		
3,300.00	3,283.26	3,272.28	3,232.90	8.36	9.17	-78.42	205.21	-395.98	309.90	293.12	16.78	18.468		
3,400.00	3,382.40	3,371.26	3,329.90	8.56	9.43	-78.73	213.39	-413.93	324.01	306.81	17.19	18.848		
3,500.00	3,481.55	3,470.25	3,426.90	8.75	9.70	-79.02	221.56	-431.89	338.12	320.52	17.60	19.210		
3,600.00	3,580.69	3,569.24	3,523.90	8.95	9.96	-79.28	229.73	-449.84	352.24	334.23	18.01	19.556		
3,700.00	3,679.84	3,668.22	3,620.90	9.14	10.22	-79.52	237.90	-467.79	366.37	347.94	18.42	19.886		
3,800.00	3,778.98	3,767.21	3,717.90	9.33	10.48	-79.75	246.07	-485.75	380.50	361.67	18.84	20.202		
3,900.00	3,878.13	3,866.19	3,814.90	9.53	10.75	-79.95	254.24	-503.70	394.64	375.39	19.25	20.504		
4,000.00	3,977.27	3,965.18	3,911.90	9.72	11.01	-80.15	262.41	-521.66	408.78	389.12	19.66	20.793		
4,100.00	4,076.42	4,064.16	4,008.90	9.91	11.28	-80.33	270.59	-539.61	422.93	402.86	20.07	21.070		
4,200.00	4,175.56	4,163.15	4,105.90	10.11	11.54	-80.50	278.76	-557.57	437.08	416.60	20.49	21.336		
4,300.00	4,274.70	4,262.14	4,202.90	10.30	11.81	-80.65	286.93	-575.52	451.24	430.34	20.90	21.591		
4,400.00	4,373.85	4,361.12	4,299.90	10.49	12.07	-80.80	295.10	-593.48	465.40	444.08	21.31	21.837		
4,500.00	4,472.99	4,460.11	4,396.90	10.69	12.34	-80.94	303.27	-611.43	479.56	457.83	21.73	22.073		
4,600.00	4,572.14	4,559.09	4,493.90	10.88	12.61	-81.07	311.44	-629.39	493.72	471.58	22.14	22.300		
4,700.00	4,671.28	4,658.08	4,590.90	11.08	12.87	-81.20	319.61	-647.34	507.89	485.33	22.56	22.516		
4,702.13	4,673.39	4,660.19	4,592.97	11.08	12.88	-81.20	319.79	-647.72	508.19	485.62	22.57	22.520		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 32 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 151H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)						
4,800.00	4,770.58	4,757.04	4,687.88	11.28	13.14	-81.39	327.78	-665.29	522.24	499.28	22.96	22.747		
4,900.00	4,870.15	4,855.90	4,784.76	11.48	13.41	-81.31	335.95	-683.22	536.99	513.65	23.34	23.007		
5,000.00	4,969.93	4,954.61	4,881.48	11.67	13.67	-80.99	344.09	-701.13	552.17	528.47	23.70	23.299		
5,100.00	5,069.85	5,053.08	4,977.98	11.85	13.94	-80.44	352.22	-718.99	567.82	543.79	24.03	23.626		
5,200.00	5,169.84	5,151.25	5,074.18	11.99	14.20	-79.69	360.33	-736.80	584.04	559.70	24.35	23.988		
5,202.16	5,172.00	5,153.37	5,076.26	12.00	14.21	-99.90	360.50	-737.18	584.40	560.05	24.35	23.996		
5,300.00	5,269.84	5,249.25	5,170.21	12.08	14.47	-98.86	368.42	-754.57	600.70	576.05	24.64	24.376		
5,400.00	5,369.84	5,347.24	5,266.24	12.17	14.74	-97.85	376.51	-772.34	617.54	592.60	24.94	24.760		
5,500.00	5,469.84	5,445.24	5,362.27	12.26	15.00	-96.89	384.60	-790.12	634.57	609.33	25.24	25.143		
5,600.00	5,569.84	5,543.23	5,458.30	12.34	15.27	-95.99	392.69	-807.89	651.75	626.22	25.54	25.523		
5,700.00	5,669.84	5,641.22	5,554.33	12.43	15.53	-95.13	400.77	-825.67	669.10	643.26	25.83	25.899		
5,800.00	5,769.84	5,739.22	5,650.35	12.52	15.80	-94.31	408.86	-843.44	686.58	660.44	26.13	26.273		
5,900.00	5,869.84	5,837.21	5,746.38	12.61	16.07	-93.53	416.95	-861.22	704.19	677.76	26.43	26.641		
6,000.00	5,969.84	5,941.14	5,848.25	12.69	16.35	-92.75	425.47	-879.92	721.80	695.05	26.76	26.977		
6,100.00	6,069.84	6,059.90	5,965.18	12.78	16.64	-92.01	434.08	-898.84	737.46	710.35	27.12	27.195		
6,200.00	6,169.84	6,179.87	6,083.90	12.87	16.89	-91.41	441.24	-914.58	750.43	722.97	27.46	27.328		
6,300.00	6,269.84	6,300.83	6,204.08	12.96	17.12	-90.96	446.89	-927.00	760.61	732.83	27.78	27.382		
6,400.00	6,369.84	6,422.54	6,325.38	13.04	17.29	-90.65	450.99	-936.00	767.96	739.90	28.06	27.365		
6,500.00	6,469.84	6,544.76	6,447.44	13.13	17.43	-90.46	453.49	-941.49	772.44	744.12	28.32	27.277		
6,600.00	6,569.84	6,667.24	6,569.90	13.22	17.53	-90.39	454.37	-943.43	774.02	745.52	28.50	27.159		
6,700.00	6,669.84	6,768.18	6,670.84	13.30	17.58	-90.39	454.37	-943.43	774.02	745.38	28.63	27.031		
6,800.00	6,769.84	6,868.18	6,770.84	13.39	17.64	-90.39	454.37	-943.43	774.02	745.24	28.78	26.895		
6,900.00	6,869.84	6,968.18	6,870.84	13.48	17.70	-90.39	454.37	-943.43	774.02	745.09	28.92	26.760		
7,000.00	6,969.84	7,068.18	6,970.84	13.56	17.75	-90.39	454.37	-943.43	774.02	744.95	29.07	26.626		
7,100.00	7,069.84	7,168.18	7,070.84	13.65	17.81	-90.39	454.37	-943.43	774.02	744.80	29.22	26.493		
7,200.00	7,169.84	7,268.18	7,170.84	13.74	17.87	-90.39	454.37	-943.43	774.02	744.66	29.36	26.361		
7,300.00	7,269.84	7,368.18	7,270.84	13.82	17.93	-90.39	454.37	-943.43	774.02	744.51	29.51	26.231		
7,400.00	7,369.84	7,468.18	7,370.84	13.91	17.99	-90.39	454.37	-943.43	774.02	744.36	29.65	26.102		
7,500.00	7,469.84	7,568.18	7,470.84	14.00	18.05	-90.39	454.37	-943.43	774.02	744.22	29.80	25.974		
7,600.00	7,569.84	7,668.18	7,570.84	14.08	18.11	-90.39	454.37	-943.43	774.02	744.07	29.95	25.847		
7,700.00	7,669.84	7,768.18	7,670.84	14.17	18.17	-90.39	454.37	-943.43	774.02	743.93	30.09	25.721		
7,800.00	7,769.84	7,868.18	7,770.84	14.26	18.23	-90.39	454.37	-943.43	774.02	743.78	30.24	25.597		
7,900.00	7,869.84	7,968.18	7,870.84	14.34	18.29	-90.39	454.37	-943.43	774.02	743.63	30.39	25.473		
8,000.00	7,969.84	8,068.18	7,970.84	14.43	18.35	-90.39	454.37	-943.43	774.02	743.49	30.53	25.351		
8,100.00	8,069.84	8,168.18	8,070.84	14.51	18.42	-90.39	454.37	-943.43	774.02	743.34	30.68	25.229		
8,200.00	8,169.84	8,268.18	8,170.84	14.60	18.48	-90.39	454.37	-943.43	774.02	743.19	30.83	25.109		
8,300.00	8,269.84	8,368.18	8,270.84	14.69	18.54	-90.39	454.37	-943.43	774.02	743.04	30.97	24.990		
8,400.00	8,369.84	8,468.18	8,370.84	14.77	18.60	-90.39	454.37	-943.43	774.02	742.90	31.12	24.871		
8,500.00	8,469.84	8,568.18	8,470.84	14.86	18.66	-90.39	454.37	-943.43	774.02	742.75	31.27	24.754		
8,600.00	8,569.84	8,668.18	8,570.84	14.94	18.72	-90.39	454.37	-943.43	774.02	742.60	31.42	24.638		
8,700.00	8,669.84	8,768.18	8,670.84	15.03	18.78	-90.39	454.37	-943.43	774.02	742.45	31.56	24.523		
8,800.00	8,769.84	8,868.18	8,770.84	15.12	18.85	-90.39	454.37	-943.43	774.02	742.31	31.71	24.409		
8,900.00	8,869.84	8,968.18	8,870.84	15.20	18.91	-90.39	454.37	-943.43	774.02	742.16	31.86	24.295		
9,000.00	8,969.84	9,068.18	8,970.84	15.29	18.97	-90.39	454.37	-943.43	774.02	742.01	32.01	24.183		
9,100.00	9,069.84	9,168.18	9,070.84	15.37	19.03	-90.39	454.37	-943.43	774.02	741.86	32.15	24.072		
9,200.00	9,169.84	9,268.18	9,170.84	15.46	19.10	-90.39	454.37	-943.43	774.02	741.72	32.30	23.961		
9,300.00	9,269.84	9,368.18	9,270.84	15.54	19.16	-90.39	454.37	-943.43	774.02	741.57	32.45	23.852		
9,400.00	9,369.84	9,468.18	9,370.84	15.63	19.22	-90.39	454.37	-943.43	774.02	741.42	32.60	23.743		
9,500.00	9,469.84	9,568.18	9,470.84	15.71	19.28	-90.39	454.37	-943.43	774.02	741.27	32.75	23.636		
9,600.00	9,569.84	9,668.18	9,570.84	15.80	19.35	-90.39	454.37	-943.43	774.02	741.12	32.90	23.529		
9,700.00	9,669.84	9,768.18	9,670.84	15.89	19.41	-90.39	454.37	-943.43	774.02	740.97	33.05	23.423		
9,800.00	9,769.84	9,868.18	9,770.84	15.97	19.47	-90.39	454.37	-943.43	774.02	740.82	33.19	23.318		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 33 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 151H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
							+N/-S (usft)	+E/-W (usft)						
9,900.00	9,869.84	9,968.18	9,870.84	16.06	19.54	-90.39	454.37	-943.43	774.02	740.68	33.34	23.214		
10,000.00	9,969.84	10,068.18	9,970.84	16.14	19.60	-90.39	454.37	-943.43	774.02	740.53	33.49	23.111		
10,100.00	10,069.84	10,168.18	10,070.84	16.23	19.67	-90.39	454.37	-943.43	774.02	740.38	33.64	23.008		
10,200.00	10,169.84	10,268.18	10,170.84	16.31	19.73	-90.39	454.37	-943.43	774.02	740.23	33.79	22.907		
10,300.00	10,269.84	10,368.18	10,270.84	16.40	19.79	-90.39	454.37	-943.43	774.02	740.08	33.94	22.806		
10,400.00	10,369.84	10,468.18	10,370.84	16.48	19.86	-90.39	454.37	-943.43	774.02	739.93	34.09	22.706		
10,500.00	10,469.84	10,568.18	10,470.84	16.57	19.92	-90.39	454.37	-943.43	774.02	739.78	34.24	22.607		
10,600.00	10,569.84	10,668.18	10,570.84	16.65	19.99	-90.39	454.37	-943.43	774.02	739.63	34.39	22.508		
10,700.00	10,669.84	10,768.18	10,670.84	16.74	20.05	-90.39	454.37	-943.43	774.02	739.48	34.54	22.411		
10,800.00	10,769.84	10,868.18	10,770.84	16.82	20.12	-90.39	454.37	-943.43	774.02	739.33	34.69	22.314		
10,900.00	10,869.84	10,968.18	10,870.84	16.91	20.18	-90.39	454.37	-943.43	774.02	739.18	34.84	22.218		
11,000.00	10,969.84	11,068.18	10,970.84	16.99	20.25	-90.39	454.37	-943.43	774.02	739.03	34.99	22.123		
11,100.00	11,069.84	11,168.18	11,070.84	17.08	20.30	-90.39	454.37	-943.43	774.02	738.89	35.13	22.034		
11,147.08	11,116.92	11,215.29	11,117.92	17.12	20.32	-90.49	452.98	-943.42	774.02	738.85	35.17	22.010		
11,200.00	11,169.84	11,267.60	11,169.86	17.16	20.34	-90.94	446.96	-943.37	774.04	738.85	35.19	21.998		
11,300.00	11,269.84	11,367.77	11,261.16	17.25	20.35	-92.61	424.31	-943.17	774.61	739.41	35.20	22.008		
11,400.00	11,369.84	11,466.62	11,339.26	17.33	20.35	-95.05	391.34	-942.89	777.11	741.90	35.20	22.074		
11,500.00	11,469.84	11,520.35	11,402.53	17.42	20.34	-97.81	353.60	-942.56	783.35	748.08	35.28	22.206		
11,581.16	11,551.00	11,572.03	11,443.75	17.48	20.33	-100.07	322.45	-942.29	792.38	756.94	35.44	22.360		
11,600.00	11,569.83	11,583.19	11,452.27	17.48	20.33	79.66	315.24	-942.23	795.01	759.53	35.48	22.408		
11,650.00	11,619.67	11,612.56	11,474.01	17.49	20.33	77.62	295.50	-942.06	802.58	766.99	35.58	22.554		
11,700.00	11,668.99	11,641.61	11,494.48	17.51	20.33	75.62	274.89	-941.89	810.80	775.07	35.73	22.692		
11,750.00	11,717.40	11,670.38	11,513.71	17.51	20.34	73.67	253.49	-941.70	819.48	783.59	35.89	22.831		
11,800.00	11,764.55	11,700.00	11,532.35	17.52	20.35	71.76	230.48	-941.50	828.45	792.38	36.06	22.971		
11,850.00	11,810.08	11,727.27	11,548.44	17.52	20.36	70.01	208.48	-941.31	837.51	801.22	36.29	23.080		
11,900.00	11,853.63	11,750.00	11,561.05	17.52	20.38	68.47	189.56	-941.15	846.53	809.96	36.57	23.149		
11,950.00	11,894.88	11,783.45	11,578.20	17.53	20.40	66.75	160.85	-940.90	855.29	818.51	36.78	23.256		
12,000.00	11,933.52	11,811.34	11,591.21	17.53	20.43	65.30	136.18	-940.69	863.72	826.67	37.05	23.311		
12,050.00	11,969.24	11,839.12	11,602.95	17.53	20.47	63.98	111.01	-940.47	871.67	834.33	37.34	23.343		
12,100.00	12,001.78	11,866.81	11,613.43	17.53	20.50	62.80	85.38	-940.25	879.03	841.38	37.65	23.350		
12,150.00	12,030.89	11,900.00	11,624.34	17.53	20.56	61.67	54.04	-939.98	885.74	847.82	37.91	23.362		
12,200.00	12,056.34	11,921.96	11,630.55	17.53	20.60	60.86	32.99	-939.80	891.61	853.33	38.28	23.293		
12,250.00	12,077.95	11,950.00	11,637.30	17.54	20.66	60.10	5.77	-939.57	896.66	858.07	38.59	23.235		
12,300.00	12,095.55	11,976.88	11,642.52	17.55	20.72	59.49	-20.60	-939.34	900.81	861.90	38.91	23.148		
12,350.00	12,109.01	12,000.00	11,646.01	17.56	20.77	59.06	-43.45	-939.14	904.02	864.78	39.25	23.034		
12,400.00	12,118.22	12,031.68	11,649.30	17.58	20.86	58.72	-74.95	-938.87	906.21	866.68	39.53	22.926		
12,450.00	12,123.11	12,059.05	11,650.73	17.60	20.94	58.55	-102.28	-938.64	907.40	867.59	39.81	22.792		
12,476.17	12,123.94	12,075.84	11,650.98	17.61	20.99	58.52	-119.07	-938.49	907.61	867.67	39.94	22.726		
12,500.00	12,124.14	12,099.67	11,651.19	17.62	21.07	58.52	-142.90	-938.29	907.61	867.59	40.02	22.679		
12,600.00	12,125.02	12,199.67	11,652.06	17.69	21.42	58.52	-242.89	-937.43	907.61	867.13	40.48	22.420		
12,700.00	12,125.89	12,299.67	11,652.92	17.79	21.84	58.52	-342.88	-936.57	907.61	866.54	41.08	22.096		
12,800.00	12,126.76	12,399.67	11,653.79	17.95	22.31	58.52	-442.88	-935.71	907.62	865.82	41.80	21.714		
12,900.00	12,127.63	12,499.67	11,654.65	18.21	22.84	58.52	-542.87	-934.85	907.62	864.98	42.64	21.285		
13,000.00	12,128.50	12,599.67	11,655.52	18.61	23.41	58.52	-642.86	-933.99	907.62	864.02	43.60	20.817		
13,100.00	12,129.37	12,699.67	11,656.39	19.18	24.05	58.52	-742.85	-933.12	907.63	862.96	44.66	20.321		
13,200.00	12,130.24	12,799.67	11,657.25	19.87	24.73	58.52	-842.85	-932.26	907.63	861.80	45.83	19.805		
13,300.00	12,131.11	12,899.67	11,658.12	20.66	25.45	58.52	-942.84	-931.40	907.63	860.55	47.09	19.276		
13,400.00	12,131.99	12,999.67	11,658.98	21.53	26.23	58.52	-1,042.83	-930.54	907.63	859.21	48.43	18.743		
13,500.00	12,132.86	13,099.67	11,659.85	22.45	27.04	58.52	-1,142.82	-929.68	907.64	857.79	49.85	18.209		
13,600.00	12,133.73	13,199.67	11,660.72	23.43	27.90	58.52	-1,242.82	-928.82	907.64	856.30	51.34	17.680		
13,700.00	12,134.60	13,299.67	11,661.58	24.44	28.79	58.52	-1,342.81	-927.96	907.64	854.75	52.89	17.160		
13,800.00	12,135.47	13,399.67	11,662.45	25.50	29.72	58.52	-1,442.80	-927.10	907.65	853.14	54.51	16.651		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 34 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 151H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
19,100.00	12,181.65	18,699.67	11,708.35	93.96	95.53	58.50	-6,742.41	-881.48	907.80	739.21	168.59	5.385			
19,200.00	12,182.52	18,799.67	11,709.21	95.31	96.86	58.50	-6,842.40	-880.62	907.81	736.90	170.91	5.312			
19,300.00	12,183.39	18,899.67	11,710.08	96.66	98.20	58.50	-6,942.39	-879.76	907.81	734.58	173.23	5.241			
19,400.00	12,184.26	18,999.67	11,710.94	98.01	99.53	58.50	-7,042.38	-878.90	907.81	732.27	175.55	5.171			
19,500.00	12,185.13	19,099.67	11,711.81	99.36	100.87	58.50	-7,142.38	-878.04	907.81	729.95	177.87	5.104			
19,600.00	12,186.00	19,199.67	11,712.68	100.72	102.21	58.50	-7,242.37	-877.18	907.82	727.62	180.19	5.038			
19,700.00	12,186.87	19,299.67	11,713.54	102.07	103.55	58.50	-7,342.36	-876.32	907.82	725.30	182.52	4.974			
19,800.00	12,187.75	19,399.67	11,714.41	103.42	104.89	58.50	-7,442.35	-875.46	907.82	722.98	184.84	4.911			
19,900.00	12,188.62	19,499.67	11,715.27	104.78	106.23	58.50	-7,542.35	-874.59	907.83	720.65	187.17	4.850			
20,000.00	12,189.49	19,599.67	11,716.14	106.13	107.58	58.50	-7,642.34	-873.73	907.83	718.33	189.50	4.791			
20,100.00	12,190.36	19,699.67	11,717.01	107.49	108.92	58.50	-7,742.33	-872.87	907.83	716.00	191.83	4.732			
20,200.00	12,191.23	19,799.67	11,717.87	108.84	110.26	58.50	-7,842.32	-872.01	907.83	713.67	194.17	4.676			
20,300.00	12,192.10	19,899.67	11,718.74	110.20	111.61	58.50	-7,942.32	-871.15	907.84	711.34	196.50	4.620			
20,400.00	12,192.97	19,999.67	11,719.60	111.55	112.95	58.50	-8,042.31	-870.29	907.84	709.01	198.83	4.566			
20,500.00	12,193.85	20,099.67	11,720.47	112.91	114.30	58.50	-8,142.30	-869.43	907.84	706.68	201.17	4.513			
20,600.00	12,194.72	20,199.67	11,721.34	114.27	115.64	58.50	-8,242.29	-868.57	907.85	704.34	203.50	4.461			
20,700.00	12,195.59	20,299.67	11,722.20	115.62	116.99	58.50	-8,342.29	-867.71	907.85	702.01	205.84	4.410			
20,800.00	12,196.46	20,399.67	11,723.07	116.98	118.34	58.50	-8,442.28	-866.85	907.85	699.67	208.18	4.361			
20,900.00	12,197.33	20,499.67	11,723.93	118.34	119.69	58.50	-8,542.27	-865.99	907.86	697.34	210.52	4.312			
21,000.00	12,198.20	20,599.67	11,724.80	119.70	121.03	58.50	-8,642.26	-865.13	907.86	695.00	212.86	4.265			
21,100.00	12,199.07	20,699.67	11,725.67	121.05	122.38	58.49	-8,742.26	-864.27	907.86	692.66	215.20	4.219			
21,200.00	12,199.94	20,799.67	11,726.53	122.41	123.73	58.49	-8,842.25	-863.40	907.86	690.32	217.54	4.173			
21,300.00	12,200.82	20,899.67	11,727.40	123.77	125.08	58.49	-8,942.24	-862.54	907.87	687.98	219.89	4.129			
21,400.00	12,201.69	20,999.67	11,728.26	125.13	126.43	58.49	-9,042.24	-861.68	907.87	685.64	222.23	4.085			
21,500.00	12,202.56	21,099.67	11,729.13	126.49	127.78	58.49	-9,142.23	-860.82	907.87	683.30	224.58	4.043			
21,600.00	12,203.43	21,199.67	11,730.00	127.85	129.13	58.49	-9,242.22	-859.96	907.88	680.95	226.92	4.001			
21,700.00	12,204.30	21,299.67	11,730.86	129.21	130.48	58.49	-9,342.21	-859.10	907.88	678.61	229.27	3.960			
21,800.00	12,205.17	21,399.67	11,731.73	130.57	131.84	58.49	-9,442.21	-858.24	907.88	676.27	231.62	3.920			
21,900.00	12,206.04	21,499.67	11,732.59	131.93	133.19	58.49	-9,542.20	-857.38	907.89	673.92	233.96	3.880			
22,000.00	12,206.91	21,599.67	11,733.46	133.29	134.54	58.49	-9,642.19	-856.52	907.89	671.58	236.31	3.842			
22,100.00	12,207.79	21,699.67	11,734.33	134.65	135.89	58.49	-9,742.18	-855.66	907.89	669.23	238.66	3.804			
22,200.00	12,208.66	21,799.67	11,735.19	136.01	137.25	58.49	-9,842.18	-854.80	907.89	666.88	241.01	3.767			
22,300.00	12,209.53	21,899.67	11,736.06	137.37	138.60	58.49	-9,942.17	-853.94	907.90	664.54	243.36	3.731			
22,400.00	12,210.40	21,999.67	11,736.92	138.73	139.83	58.49	-10,042.16	-853.08	907.90	662.34	245.56	3.697			
22,400.01	12,210.40	21,999.68	11,736.92	138.73	139.83	58.49	-10,042.17	-853.08	907.90	662.34	245.56	3.697			
22,411.61	12,210.50	22,008.51	11,737.00	138.89	139.94	58.49	-10,051.00	-853.00	907.90	662.07	245.84	3.693	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 36 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 152H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Offset Wellbore Centre			Distance		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor
0.00	0.00	0.00	0.00	0.50	0.50	0.00	210.00	0.00	210.00			
100.00	100.00	100.00	100.00	0.98	0.98	0.00	210.00	0.00	210.00	208.04	1.96	107.024
200.00	200.00	200.00	200.00	1.56	1.56	0.00	210.00	0.00	210.00	206.88	3.12	67.259
300.00	300.00	300.00	300.00	1.98	1.98	0.00	210.00	0.00	210.00	206.04	3.96	52.999
400.00	400.00	397.00	396.99	2.33	2.40	0.28	210.69	1.02	210.71	206.04	4.67	45.091
500.00	500.00	493.88	493.80	2.63	2.76	1.10	212.75	4.08	212.88	207.58	5.30	40.197
600.00	600.00	590.51	590.23	2.91	3.09	2.43	216.16	9.16	216.58	210.72	5.86	36.942
700.00	700.00	688.68	688.05	3.16	3.24	4.16	220.81	16.06	221.71	215.45	6.27	35.379
800.00	800.00	788.30	787.29	3.40	3.48	5.89	225.65	23.27	227.20	220.45	6.75	33.656
900.00	899.99	887.94	886.55	3.68	3.72	27.88	230.50	30.47	231.74	224.47	7.26	31.898
1,000.00	999.91	987.56	985.79	3.94	3.96	29.90	235.35	37.68	234.22	226.46	7.75	30.204
1,100.00	1,099.77	1,087.15	1,085.00	4.15	4.18	32.05	240.19	44.88	235.88	227.69	8.19	28.803
1,200.00	1,199.63	1,186.74	1,184.21	4.35	4.41	34.18	245.04	52.08	237.87	229.26	8.61	27.614
1,250.43	1,250.00	1,236.97	1,234.25	4.40	4.52	35.23	247.48	55.71	239.00	230.23	8.78	27.236
1,300.00	1,299.48	1,286.32	1,283.41	4.45	4.63	36.30	249.88	59.28	239.93	231.00	8.93	26.854
1,400.00	1,399.17	1,385.79	1,382.51	4.69	4.84	38.72	254.72	66.47	240.53	231.16	9.37	25.657
1,500.00	1,498.62	1,485.08	1,481.42	4.93	5.05	41.54	259.55	73.65	239.60	229.80	9.80	24.438
1,550.47	1,548.70	1,535.10	1,531.24	4.99	5.16	43.13	261.98	77.27	238.63	228.66	9.96	23.948
1,600.00	1,597.81	1,584.15	1,580.11	5.05	5.26	44.75	264.37	80.82	237.62	227.50	10.12	23.481
1,700.00	1,696.95	1,683.19	1,678.77	5.25	5.47	48.05	269.19	87.98	236.18	225.66	10.52	22.454
1,800.00	1,796.09	1,782.23	1,777.43	5.44	5.67	51.38	274.01	95.14	235.55	224.64	10.91	21.582
1,827.69	1,823.55	1,809.65	1,804.75	5.50	5.73	52.31	275.34	97.13	235.52	224.50	11.02	21.366
1,900.00	1,895.24	1,881.26	1,876.09	5.64	5.87	54.72	278.82	102.30	235.73	224.42	11.31	20.850
2,000.00	1,994.38	1,980.30	1,974.75	5.83	6.07	58.04	283.64	109.47	236.72	225.03	11.69	20.242
2,100.00	2,093.53	2,079.33	2,073.41	6.03	6.27	61.32	288.46	116.63	238.52	226.44	12.08	19.746
2,200.00	2,192.67	2,178.37	2,172.07	6.22	6.48	64.54	293.28	123.79	241.10	228.63	12.47	19.335
2,300.00	2,291.82	2,273.17	2,266.45	6.42	6.68	67.57	298.21	131.13	245.05	232.20	12.85	19.076
2,400.00	2,390.96	2,366.00	2,358.65	6.61	6.89	70.49	304.26	140.11	252.04	238.81	13.22	19.063
2,500.00	2,490.11	2,458.39	2,450.12	6.81	7.10	73.26	311.51	150.89	262.13	248.53	13.59	19.286
2,600.00	2,589.25	2,551.00	2,541.46	7.00	7.27	75.84	320.01	163.53	275.23	261.31	13.91	19.781
2,700.00	2,688.39	2,649.17	2,638.15	7.20	7.45	78.32	329.53	177.67	289.82	275.55	14.27	20.313
2,800.00	2,787.54	2,747.35	2,734.83	7.39	7.66	80.57	339.04	191.81	304.91	290.26	14.65	20.818
2,900.00	2,886.68	2,845.52	2,831.51	7.59	7.86	82.60	348.56	205.96	320.41	305.38	15.02	21.327
3,000.00	2,985.83	2,943.70	2,928.20	7.78	8.06	84.44	358.07	220.10	336.27	320.87	15.40	21.834
3,100.00	3,084.97	3,041.87	3,024.88	7.98	8.26	86.12	367.59	234.25	352.45	336.67	15.78	22.336
3,200.00	3,184.12	3,140.05	3,121.57	8.17	8.47	87.65	377.11	248.39	368.89	352.74	16.16	22.831
3,300.00	3,283.26	3,238.22	3,218.25	8.36	8.67	89.05	386.62	262.53	385.58	369.04	16.54	23.317
3,400.00	3,382.40	3,336.40	3,314.93	8.56	8.87	90.34	396.14	276.68	402.47	385.55	16.92	23.793
3,500.00	3,481.55	3,434.57	3,411.62	8.75	9.07	91.52	405.65	290.82	419.54	402.24	17.30	24.257
3,600.00	3,580.69	3,532.75	3,508.30	8.95	9.28	92.61	415.17	304.97	436.77	419.10	17.68	24.710
3,700.00	3,679.84	3,630.93	3,604.98	9.14	9.48	93.61	424.68	319.11	454.15	436.09	18.06	25.152
3,800.00	3,778.98	3,733.51	3,706.04	9.33	9.69	94.59	434.52	333.74	471.49	453.04	18.46	25.544
3,900.00	3,878.13	3,845.19	3,816.47	9.53	9.94	95.68	443.84	347.58	486.85	467.93	18.91	25.742
4,000.00	3,977.27	3,957.56	3,928.01	9.72	10.18	96.84	451.39	358.80	499.63	480.28	19.35	25.824
4,100.00	4,076.42	4,070.43	4,040.41	9.91	10.41	98.08	457.13	367.33	509.86	490.10	19.76	25.802
4,200.00	4,175.56	4,183.60	4,153.36	10.11	10.63	99.41	461.02	373.11	517.58	497.43	20.15	25.688
4,300.00	4,274.70	4,296.87	4,266.57	10.30	10.83	100.86	463.04	376.12	522.83	502.32	20.51	25.495
4,400.00	4,373.85	4,404.15	4,373.85	10.49	10.91	102.33	463.35	376.58	525.93	505.19	20.74	25.354
4,500.00	4,472.99	4,503.30	4,472.99	10.69	10.99	103.70	463.35	376.58	528.90	507.90	21.00	25.187
4,600.00	4,572.14	4,602.44	4,572.14	10.88	11.08	105.06	463.35	376.58	532.16	510.91	21.25	25.038
4,700.00	4,671.28	4,701.59	4,671.28	11.08	11.16	106.39	463.35	376.58	535.73	514.22	21.51	24.903
4,702.13	4,673.39	4,703.70	4,673.39	11.08	11.16	106.42	463.35	376.58	535.81	514.29	21.52	24.901

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 37 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 152H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:						Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)	
4,800.00	4,770.58	4,800.88	4,770.58	11.28	11.24	107.64	463.35	376.58	539.21	517.45	21.76	24.778		
4,900.00	4,870.15	4,900.46	4,870.15	11.48	11.32	108.60	463.35	376.58	542.08	520.08	22.00	24.641		
5,000.00	4,969.93	5,000.23	4,969.93	11.67	11.41	109.29	463.35	376.58	544.23	522.01	22.22	24.491		
5,100.00	5,069.85	5,100.15	5,069.85	11.85	11.49	109.70	463.35	376.58	545.56	523.13	22.43	24.325		
5,200.00	5,169.84	5,200.14	5,169.84	11.99	11.57	109.85	463.35	376.58	546.02	523.41	22.61	24.145		
5,202.16	5,172.00	5,202.30	5,172.00	12.00	11.58	89.61	463.35	376.58	546.02	523.40	22.62	24.140		
5,300.00	5,269.84	5,300.14	5,269.84	12.08	11.66	89.61	463.35	376.58	546.02	523.24	22.78	23.964		
5,400.00	5,369.84	5,400.14	5,369.84	12.17	11.74	89.61	463.35	376.58	546.02	523.07	22.96	23.785		
5,500.00	5,469.84	5,500.14	5,469.84	12.26	11.82	89.61	463.35	376.58	546.02	522.89	23.13	23.609		
5,600.00	5,569.84	5,600.14	5,569.84	12.34	11.91	89.61	463.35	376.58	546.02	522.72	23.30	23.435		
5,700.00	5,669.84	5,700.14	5,669.84	12.43	11.99	89.61	463.35	376.58	546.02	522.55	23.47	23.264		
5,800.00	5,769.84	5,800.14	5,769.84	12.52	12.07	89.61	463.35	376.58	546.02	522.38	23.64	23.095		
5,900.00	5,869.84	5,900.14	5,869.84	12.61	12.16	89.61	463.35	376.58	546.02	522.21	23.81	22.929		
6,000.00	5,969.84	6,000.14	5,969.84	12.69	12.24	89.61	463.35	376.58	546.02	522.04	23.98	22.766		
6,100.00	6,069.84	6,100.14	6,069.84	12.78	12.32	89.61	463.35	376.58	546.02	521.87	24.16	22.605		
6,200.00	6,169.84	6,200.14	6,169.84	12.87	12.40	89.61	463.35	376.58	546.02	521.70	24.33	22.446		
6,300.00	6,269.84	6,300.14	6,269.84	12.96	12.49	89.61	463.35	376.58	546.02	521.53	24.50	22.290		
6,400.00	6,369.84	6,400.14	6,369.84	13.04	12.57	89.61	463.35	376.58	546.02	521.36	24.67	22.135		
6,500.00	6,469.84	6,500.14	6,469.84	13.13	12.65	89.61	463.35	376.58	546.02	521.18	24.84	21.984		
6,600.00	6,569.84	6,600.14	6,569.84	13.22	12.74	89.61	463.35	376.58	546.02	521.01	25.01	21.834		
6,700.00	6,669.84	6,700.14	6,669.84	13.30	12.82	89.61	463.35	376.58	546.02	520.84	25.18	21.686		
6,800.00	6,769.84	6,800.14	6,769.84	13.39	12.90	89.61	463.35	376.58	546.02	520.67	25.35	21.540		
6,900.00	6,869.84	6,900.14	6,869.84	13.48	12.99	89.61	463.35	376.58	546.02	520.50	25.52	21.397		
7,000.00	6,969.84	7,000.14	6,969.84	13.56	13.07	89.61	463.35	376.58	546.02	520.33	25.69	21.255		
7,100.00	7,069.84	7,100.14	7,069.84	13.65	13.15	89.61	463.35	376.58	546.02	520.16	25.86	21.116		
7,200.00	7,169.84	7,200.14	7,169.84	13.74	13.24	89.61	463.35	376.58	546.02	519.99	26.03	20.978		
7,300.00	7,269.84	7,300.14	7,269.84	13.82	13.32	89.61	463.35	376.58	546.02	519.82	26.20	20.842		
7,400.00	7,369.84	7,400.14	7,369.84	13.91	13.40	89.61	463.35	376.58	546.02	519.65	26.37	20.708		
7,500.00	7,469.84	7,500.14	7,469.84	14.00	13.48	89.61	463.35	376.58	546.02	519.48	26.54	20.575		
7,600.00	7,569.84	7,600.14	7,569.84	14.08	13.57	89.61	463.35	376.58	546.02	519.32	26.71	20.445		
7,700.00	7,669.84	7,700.14	7,669.84	14.17	13.65	89.61	463.35	376.58	546.02	519.15	26.88	20.316		
7,800.00	7,769.84	7,800.14	7,769.84	14.26	13.73	89.61	463.35	376.58	546.02	518.98	27.05	20.189		
7,900.00	7,869.84	7,900.14	7,869.84	14.34	13.82	89.61	463.35	376.58	546.02	518.81	27.22	20.063		
8,000.00	7,969.84	8,000.14	7,969.84	14.43	13.90	89.61	463.35	376.58	546.02	518.64	27.38	19.939		
8,100.00	8,069.84	8,100.14	8,069.84	14.51	13.98	89.61	463.35	376.58	546.02	518.47	27.55	19.817		
8,200.00	8,169.84	8,200.14	8,169.84	14.60	14.07	89.61	463.35	376.58	546.02	518.30	27.72	19.696		
8,300.00	8,269.84	8,300.14	8,269.84	14.69	14.15	89.61	463.35	376.58	546.02	518.13	27.89	19.577		
8,400.00	8,369.84	8,400.14	8,369.84	14.77	14.23	89.61	463.35	376.58	546.02	517.96	28.06	19.459		
8,500.00	8,469.84	8,500.14	8,469.84	14.86	14.31	89.61	463.35	376.58	546.02	517.79	28.23	19.342		
8,600.00	8,569.84	8,600.14	8,569.84	14.94	14.40	89.61	463.35	376.58	546.02	517.62	28.40	19.227		
8,700.00	8,669.84	8,700.14	8,669.84	15.03	14.48	89.61	463.35	376.58	546.02	517.46	28.57	19.114		
8,800.00	8,769.84	8,800.14	8,769.84	15.12	14.56	89.61	463.35	376.58	546.02	517.29	28.74	19.002		
8,900.00	8,869.84	8,900.14	8,869.84	15.20	14.65	89.61	463.35	376.58	546.02	517.12	28.90	18.891		
9,000.00	8,969.84	9,000.14	8,969.84	15.29	14.73	89.61	463.35	376.58	546.02	516.95	29.07	18.781		
9,100.00	9,069.84	9,100.14	9,069.84	15.37	14.81	89.61	463.35	376.58	546.02	516.78	29.24	18.673		
9,200.00	9,169.84	9,200.14	9,169.84	15.46	14.90	89.61	463.35	376.58	546.02	516.61	29.41	18.566		
9,300.00	9,269.84	9,300.14	9,269.84	15.54	14.98	89.61	463.35	376.58	546.02	516.44	29.58	18.461		
9,400.00	9,369.84	9,400.14	9,369.84	15.63	15.06	89.61	463.35	376.58	546.02	516.28	29.75	18.356		
9,500.00	9,469.84	9,500.14	9,469.84	15.71	15.14	89.61	463.35	376.58	546.02	516.11	29.91	18.253		
9,600.00	9,569.84	9,600.14	9,569.84	15.80	15.23	89.61	463.35	376.58	546.02	515.94	30.08	18.151		
9,700.00	9,669.84	9,700.14	9,669.84	15.89	15.31	89.61	463.35	376.58	546.02	515.77	30.25	18.050		
9,800.00	9,769.84	9,800.14	9,769.84	15.97	15.39	89.61	463.35	376.58	546.02	515.60	30.42	17.950		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 38 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 152H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:						Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)	
9,900.00	9,869.84	9,900.14	9,869.84	16.06	15.48	89.61	463.35	376.58	546.02	515.44	30.59	17.852		
10,000.00	9,969.84	10,000.14	9,969.84	16.14	15.56	89.61	463.35	376.58	546.02	515.27	30.75	17.754		
10,100.00	10,069.84	10,100.14	10,069.84	16.23	15.64	89.61	463.35	376.58	546.02	515.10	30.92	17.658		
10,200.00	10,169.84	10,200.14	10,169.84	16.31	15.72	89.61	463.35	376.58	546.02	514.93	31.09	17.562		
10,300.00	10,269.84	10,300.14	10,269.84	16.40	15.81	89.61	463.35	376.58	546.02	514.76	31.26	17.468		
10,400.00	10,369.84	10,400.14	10,369.84	16.48	15.89	89.61	463.35	376.58	546.02	514.60	31.43	17.375		
10,500.00	10,469.84	10,500.14	10,469.84	16.57	15.97	89.61	463.35	376.58	546.02	514.43	31.59	17.283		
10,600.00	10,569.84	10,600.14	10,569.84	16.65	16.06	89.61	463.35	376.58	546.02	514.26	31.76	17.191		
10,700.00	10,669.84	10,700.14	10,669.84	16.74	16.14	89.61	463.35	376.58	546.02	514.09	31.93	17.101		
10,800.00	10,769.84	10,800.14	10,769.84	16.82	16.22	89.61	463.35	376.58	546.02	513.93	32.10	17.012		
10,900.00	10,869.84	10,900.14	10,869.84	16.91	16.30	89.61	463.35	376.58	546.02	513.76	32.26	16.924		
11,000.00	10,969.84	11,000.14	10,969.84	16.99	16.39	89.61	463.35	376.58	546.02	513.59	32.43	16.836		
11,100.00	11,069.84	11,100.14	11,069.84	17.08	16.47	89.61	463.35	376.58	546.02	513.42	32.60	16.747		
11,104.58	11,074.41	11,104.72	11,074.41	17.08	16.48	89.61	463.35	376.58	546.02	513.41	32.61	16.743		
11,200.00	11,169.84	11,199.16	11,168.45	17.16	16.52	90.40	455.84	376.64	546.09	513.42	32.67	16.717		
11,300.00	11,269.84	11,292.91	11,259.33	17.25	16.56	92.77	433.23	376.84	547.01	514.34	32.67	16.744		
11,400.00	11,369.84	11,377.41	11,337.10	17.33	16.62	96.19	400.40	377.12	550.73	518.02	32.70	16.840		
11,500.00	11,469.84	11,450.00	11,399.45	17.42	16.67	99.99	363.32	377.44	559.73	526.81	32.92	17.003		
11,581.16	11,551.00	11,500.00	11,439.44	17.48	16.71	103.00	333.33	377.70	572.49	539.15	33.34	17.172		
11,600.00	11,569.83	11,513.55	11,449.81	17.48	16.72	-75.30	324.62	377.77	576.18	542.75	33.43	17.235		
11,650.00	11,619.67	11,542.85	11,471.52	17.49	16.74	-72.52	304.94	377.94	586.69	552.91	33.77	17.371		
11,700.00	11,668.99	11,571.84	11,491.98	17.51	16.77	-69.84	284.41	378.12	597.98	563.80	34.18	17.494		
11,750.00	11,717.40	11,600.00	11,510.83	17.51	16.80	-67.29	263.50	378.30	609.79	575.14	34.65	17.597		
11,800.00	11,764.55	11,629.05	11,529.18	17.52	16.83	-64.82	240.98	378.49	621.85	586.69	35.16	17.688		
11,850.00	11,810.08	11,650.00	11,541.70	17.52	16.85	-62.82	224.18	378.64	633.99	598.18	35.81	17.704		
11,900.00	11,853.63	11,685.47	11,561.45	17.52	16.90	-60.43	194.73	378.89	645.80	609.53	36.27	17.806		
11,950.00	11,894.88	11,713.44	11,575.73	17.53	16.93	-58.49	170.68	379.10	657.30	620.45	36.85	17.837		
12,000.00	11,933.52	11,750.00	11,592.58	17.53	16.99	-56.50	138.25	379.38	668.34	631.03	37.31	17.912		
12,050.00	11,969.24	11,769.04	11,600.53	17.53	17.02	-55.17	120.95	379.53	678.49	640.48	38.01	17.851		
12,100.00	12,001.78	11,800.00	11,612.22	17.53	17.07	-53.72	92.28	379.78	687.93	649.40	38.53	17.855		
12,150.00	12,030.89	11,824.27	11,620.28	17.53	17.12	-52.59	69.40	379.97	696.40	657.29	39.11	17.808		
12,200.00	12,056.34	11,850.00	11,627.77	17.53	17.17	-51.59	44.78	380.18	703.86	664.23	39.63	17.761		
12,250.00	12,077.95	11,879.23	11,634.92	17.54	17.23	-50.71	16.44	380.43	710.21	670.12	40.09	17.717		
12,300.00	12,095.55	11,900.00	11,639.12	17.55	17.28	-50.09	-3.90	380.60	715.45	674.89	40.56	17.639		
12,350.00	12,109.01	11,934.02	11,644.40	17.56	17.36	-49.53	-37.50	380.89	719.35	678.45	40.90	17.586		
12,400.00	12,118.22	11,950.00	11,646.19	17.58	17.41	-49.22	-53.38	381.03	722.22	680.94	41.29	17.492		
12,450.00	12,123.11	11,988.72	11,648.69	17.60	17.52	-49.01	-92.01	381.36	723.48	681.95	41.53	17.419		
12,476.17	12,123.94	12,004.48	11,648.96	17.61	17.57	-48.98	-107.77	381.50	723.71	682.06	41.65	17.376		
12,500.00	12,124.14	12,028.31	11,649.17	17.62	17.65	-48.98	-131.59	381.70	723.71	681.98	41.73	17.342		
12,600.00	12,125.02	12,128.31	11,650.05	17.69	18.03	-48.98	-231.59	382.56	723.71	681.57	42.14	17.175		
12,700.00	12,125.89	12,228.31	11,650.93	17.79	18.50	-48.98	-331.58	383.42	723.70	681.06	42.65	16.970		
12,800.00	12,126.76	12,328.31	11,651.80	17.95	19.05	-48.98	-431.57	384.29	723.70	680.44	43.26	16.731		
12,900.00	12,127.63	12,428.31	11,652.68	18.21	19.68	-48.98	-531.56	385.15	723.70	679.73	43.96	16.462		
13,000.00	12,128.50	12,528.31	11,653.55	18.61	20.39	-48.98	-631.56	386.01	723.69	678.93	44.76	16.168		
13,100.00	12,129.37	12,628.31	11,654.43	19.18	21.17	-48.98	-731.55	386.87	723.69	678.04	45.64	15.855		
13,200.00	12,130.24	12,728.31	11,655.31	19.87	22.02	-48.98	-831.54	387.73	723.69	677.07	46.61	15.525		
13,300.00	12,131.11	12,828.31	11,656.18	20.66	22.91	-48.98	-931.53	388.59	723.68	676.02	47.66	15.185		
13,400.00	12,131.99	12,928.31	11,657.06	21.53	23.86	-48.98	-1,031.52	389.45	723.68	674.90	48.78	14.837		
13,500.00	12,132.86	13,028.31	11,657.94	22.45	24.84	-48.98	-1,131.52	390.31	723.68	673.71	49.96	14.485		
13,600.00	12,133.73	13,128.31	11,658.81	23.43	25.87	-48.98	-1,231.51	391.17	723.67	672.46	51.21	14.132		
13,700.00	12,134.60	13,228.31	11,659.69	24.44	26.92	-48.98	-1,331.50	392.03	723.67	671.15	52.52	13.780		
13,800.00	12,135.47	13,328.31	11,660.57	25.50	28.01	-48.98	-1,431.49	392.90	723.67	669.79	53.88	13.432		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 39 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 152H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)		
13,900.00	12,136.34	13,428.31	11,661.44	26.58	29.12	-48.98	-1,531.49	393.76	723.66	668.37	55.29	13.089
14,000.00	12,137.21	13,528.31	11,662.32	27.69	30.25	-48.98	-1,631.48	394.62	723.66	666.91	56.75	12.752
14,100.00	12,138.08	13,628.31	11,663.20	28.82	31.40	-48.98	-1,731.47	395.48	723.65	665.41	58.25	12.423
14,200.00	12,138.96	13,728.31	11,664.07	29.98	32.57	-48.98	-1,831.46	396.34	723.65	663.86	59.79	12.103
14,300.00	12,139.83	13,828.31	11,664.95	31.15	33.75	-48.99	-1,931.46	397.20	723.65	662.28	61.37	11.792
14,400.00	12,140.70	13,928.31	11,665.82	32.33	34.95	-48.99	-2,031.45	398.06	723.64	660.66	62.98	11.490
14,500.00	12,141.57	14,028.31	11,666.70	33.54	36.16	-48.99	-2,131.44	398.92	723.64	659.02	64.62	11.198
14,600.00	12,142.44	14,128.31	11,667.58	34.75	37.38	-48.99	-2,231.43	399.78	723.64	657.34	66.30	10.915
14,700.00	12,143.31	14,228.31	11,668.45	35.98	38.61	-48.99	-2,331.43	400.64	723.63	655.64	68.00	10.642
14,800.00	12,144.18	14,328.31	11,669.33	37.21	39.85	-48.99	-2,431.42	401.50	723.63	653.91	69.72	10.379
14,900.00	12,145.05	14,428.31	11,670.21	38.46	41.10	-48.99	-2,531.41	402.37	723.63	652.16	71.47	10.125
15,000.00	12,145.93	14,528.31	11,671.08	39.71	42.36	-48.99	-2,631.40	403.23	723.62	650.38	73.24	9.880
15,100.00	12,146.80	14,628.31	11,671.96	40.97	43.63	-48.99	-2,731.40	404.09	723.62	648.59	75.03	9.644
15,200.00	12,147.67	14,728.31	11,672.84	42.24	44.90	-48.99	-2,831.39	404.95	723.62	646.78	76.84	9.417
15,300.00	12,148.54	14,828.31	11,673.71	43.51	46.17	-48.99	-2,931.38	405.81	723.61	644.95	78.67	9.198
15,400.00	12,149.41	14,928.31	11,674.59	44.79	47.45	-48.99	-3,031.37	406.67	723.61	643.10	80.51	8.988
15,500.00	12,150.28	15,028.31	11,675.47	46.08	48.74	-48.99	-3,131.37	407.53	723.61	641.24	82.37	8.785
15,600.00	12,151.15	15,128.31	11,676.34	47.37	50.03	-48.99	-3,231.36	408.39	723.60	639.37	84.24	8.590
15,700.00	12,152.02	15,228.31	11,677.22	48.66	51.33	-48.99	-3,331.35	409.25	723.60	637.48	86.12	8.402
15,800.00	12,152.90	15,328.31	11,678.09	49.96	52.62	-48.99	-3,431.34	410.11	723.60	635.58	88.02	8.221
15,900.00	12,153.77	15,428.31	11,678.97	51.26	53.93	-48.99	-3,531.34	410.98	723.59	633.66	89.93	8.046
16,000.00	12,154.64	15,528.31	11,679.85	52.57	55.23	-48.99	-3,631.33	411.84	723.59	631.74	91.85	7.878
16,100.00	12,155.51	15,628.31	11,680.72	53.88	56.54	-48.99	-3,731.32	412.70	723.59	629.81	93.78	7.716
16,200.00	12,156.38	15,728.31	11,681.60	55.19	57.85	-48.99	-3,831.31	413.56	723.58	627.87	95.72	7.559
16,300.00	12,157.25	15,828.31	11,682.48	56.50	59.17	-48.99	-3,931.31	414.42	723.58	625.91	97.67	7.409
16,400.00	12,158.12	15,928.31	11,683.35	57.82	60.48	-48.99	-4,031.30	415.28	723.58	623.95	99.62	7.263
16,500.00	12,158.99	16,028.31	11,684.23	59.14	61.80	-48.99	-4,131.29	416.14	723.57	621.99	101.59	7.123
16,600.00	12,159.87	16,128.31	11,685.11	60.46	63.12	-48.99	-4,231.28	417.00	723.57	620.01	103.56	6.987
16,700.00	12,160.74	16,228.31	11,685.98	61.79	64.45	-48.99	-4,331.28	417.86	723.57	618.03	105.54	6.856
16,800.00	12,161.61	16,328.31	11,686.86	63.11	65.77	-48.99	-4,431.27	418.72	723.56	616.04	107.53	6.729
16,900.00	12,162.48	16,428.31	11,687.73	64.44	67.10	-48.99	-4,531.26	419.59	723.56	614.04	109.52	6.607
17,000.00	12,163.35	16,528.31	11,688.61	65.77	68.43	-48.99	-4,631.25	420.45	723.56	612.04	111.52	6.488
17,100.00	12,164.22	16,628.31	11,689.49	67.10	69.76	-48.99	-4,731.25	421.31	723.55	610.03	113.52	6.374
17,200.00	12,165.09	16,728.31	11,690.36	68.43	71.09	-48.99	-4,831.24	422.17	723.55	608.02	115.53	6.263
17,300.00	12,165.96	16,828.31	11,691.24	69.77	72.43	-48.99	-4,931.23	423.03	723.55	606.00	117.55	6.155
17,400.00	12,166.84	16,928.31	11,692.12	71.10	73.76	-48.99	-5,031.22	423.89	723.54	603.98	119.57	6.051
17,500.00	12,167.71	17,028.31	11,692.99	72.44	75.10	-49.00	-5,131.22	424.75	723.54	601.95	121.59	5.951
17,600.00	12,168.58	17,128.31	11,693.87	73.78	76.43	-49.00	-5,231.21	425.61	723.54	599.92	123.62	5.853
17,700.00	12,169.45	17,228.31	11,694.75	75.12	77.77	-49.00	-5,331.20	426.47	723.53	597.88	125.65	5.758
17,800.00	12,170.32	17,328.31	11,695.62	76.46	79.11	-49.00	-5,431.19	427.33	723.53	595.84	127.69	5.666
17,900.00	12,171.19	17,428.31	11,696.50	77.80	80.45	-49.00	-5,531.19	428.19	723.53	593.80	129.73	5.577
18,000.00	12,172.06	17,528.31	11,697.38	79.14	81.79	-49.00	-5,631.18	429.06	723.52	591.75	131.77	5.491
18,100.00	12,172.93	17,628.31	11,698.25	80.48	83.14	-49.00	-5,731.17	429.92	723.52	589.70	133.82	5.407
18,200.00	12,173.81	17,728.31	11,699.13	81.83	84.48	-49.00	-5,831.16	430.78	723.52	587.65	135.87	5.325
18,300.00	12,174.68	17,828.31	11,700.00	83.17	85.82	-49.00	-5,931.16	431.64	723.51	585.59	137.92	5.246
18,400.00	12,175.55	17,928.31	11,700.88	84.52	87.17	-49.00	-6,031.15	432.50	723.51	583.53	139.98	5.169
18,500.00	12,176.42	18,028.31	11,701.76	85.86	88.51	-49.00	-6,131.14	433.36	723.51	581.47	142.04	5.094
18,600.00	12,177.29	18,128.31	11,702.63	87.21	89.86	-49.00	-6,231.13	434.22	723.50	579.40	144.10	5.021
18,700.00	12,178.16	18,228.31	11,703.51	88.56	91.21	-49.00	-6,331.13	435.08	723.50	577.33	146.17	4.950
18,800.00	12,179.03	18,328.31	11,704.39	89.91	92.55	-49.00	-6,431.12	435.94	723.50	575.26	148.24	4.881
18,900.00	12,179.90	18,428.31	11,705.26	91.26	93.90	-49.00	-6,531.11	436.80	723.49	573.19	150.31	4.813
19,000.00	12,180.78	18,528.31	11,706.14	92.61	95.25	-49.00	-6,631.10	437.67	723.49	571.11	152.38	4.748

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 40 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 152H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference	Vertical	Offset	Vertical	Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Depth (usft)	Measured Depth (usft)	Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)				
19,100.00	12,181.65	18,628.31	11,707.02	93.96	96.60	-49.00	-6,731.09	438.53	723.49	569.03	154.45	4.684		
19,200.00	12,182.52	18,728.31	11,707.89	95.31	97.95	-49.00	-6,831.09	439.39	723.48	566.95	156.53	4.622		
19,300.00	12,183.39	18,828.31	11,708.77	96.66	99.30	-49.00	-6,931.08	440.25	723.48	564.87	158.61	4.561		
19,400.00	12,184.26	18,928.31	11,709.65	98.01	100.65	-49.00	-7,031.07	441.11	723.48	562.79	160.69	4.502		
19,500.00	12,185.13	19,028.31	11,710.52	99.36	102.01	-49.00	-7,131.06	441.97	723.47	560.70	162.77	4.445		
19,600.00	12,186.00	19,128.31	11,711.40	100.72	103.36	-49.00	-7,231.06	442.83	723.47	558.61	164.86	4.388		
19,700.00	12,186.87	19,228.31	11,712.27	102.07	104.71	-49.00	-7,331.05	443.69	723.47	556.52	166.95	4.334		
19,800.00	12,187.75	19,328.31	11,713.15	103.42	106.06	-49.00	-7,431.04	444.55	723.46	554.43	169.03	4.280		
19,900.00	12,188.62	19,428.31	11,714.03	104.78	107.42	-49.00	-7,531.03	445.41	723.46	552.34	171.12	4.228		
20,000.00	12,189.49	19,528.31	11,714.90	106.13	108.77	-49.00	-7,631.03	446.28	723.46	550.24	173.21	4.177		
20,100.00	12,190.36	19,628.31	11,715.78	107.49	110.13	-49.00	-7,731.02	447.14	723.45	548.15	175.31	4.127		
20,200.00	12,191.23	19,728.31	11,716.66	108.84	111.48	-49.00	-7,831.01	448.00	723.45	546.05	177.40	4.078		
20,300.00	12,192.10	19,828.31	11,717.53	110.20	112.84	-49.00	-7,931.00	448.86	723.45	543.95	179.50	4.030		
20,400.00	12,192.97	19,928.31	11,718.41	111.55	114.19	-49.00	-8,031.00	449.72	723.44	541.85	181.60	3.984		
20,500.00	12,193.85	20,028.31	11,719.29	112.91	115.55	-49.00	-8,130.99	450.58	723.44	539.75	183.69	3.938		
20,600.00	12,194.72	20,128.31	11,720.16	114.27	116.90	-49.00	-8,230.98	451.44	723.44	537.64	185.79	3.894		
20,700.00	12,195.59	20,228.31	11,721.04	115.62	118.26	-49.00	-8,330.97	452.30	723.43	535.54	187.89	3.850		
20,800.00	12,196.46	20,328.31	11,721.91	116.98	119.62	-49.01	-8,430.97	453.16	723.43	533.43	190.00	3.808		
20,900.00	12,197.33	20,428.31	11,722.79	118.34	120.97	-49.01	-8,530.96	454.02	723.43	531.33	192.10	3.766		
21,000.00	12,198.20	20,528.31	11,723.67	119.70	122.33	-49.01	-8,630.95	454.88	723.42	529.22	194.20	3.725		
21,100.00	12,199.07	20,628.31	11,724.54	121.05	123.69	-49.01	-8,730.94	455.75	723.42	527.11	196.31	3.685		
21,200.00	12,199.94	20,728.31	11,725.42	122.41	125.05	-49.01	-8,830.94	456.61	723.42	525.00	198.42	3.646		
21,300.00	12,200.82	20,828.31	11,726.30	123.77	126.40	-49.01	-8,930.93	457.47	723.41	522.89	200.52	3.608		
21,400.00	12,201.69	20,928.31	11,727.17	125.13	127.76	-49.01	-9,030.92	458.33	723.41	520.78	202.63	3.570		
21,500.00	12,202.56	21,028.31	11,728.05	126.49	129.12	-49.01	-9,130.91	459.19	723.41	518.66	204.74	3.533		
21,600.00	12,203.43	21,128.31	11,728.93	127.85	130.48	-49.01	-9,230.91	460.05	723.40	516.55	206.85	3.497		
21,700.00	12,204.30	21,228.31	11,729.80	129.21	131.84	-49.01	-9,330.90	460.91	723.40	514.43	208.97	3.462		
21,800.00	12,205.17	21,328.31	11,730.68	130.57	133.20	-49.01	-9,430.89	461.77	723.40	512.32	211.08	3.427		
21,900.00	12,206.04	21,428.31	11,731.56	131.93	134.56	-49.01	-9,530.88	462.63	723.39	510.20	213.19	3.393		
22,000.00	12,206.91	21,528.31	11,732.43	133.29	135.92	-49.01	-9,630.88	463.49	723.39	508.08	215.30	3.360		
22,100.00	12,207.79	21,628.31	11,733.31	134.65	137.28	-49.01	-9,730.87	464.36	723.39	505.97	217.42	3.327		
22,200.00	12,208.66	21,728.31	11,734.18	136.01	138.64	-49.01	-9,830.86	465.22	723.38	503.85	219.54	3.295		
22,300.00	12,209.53	21,828.31	11,735.06	137.37	140.00	-49.01	-9,930.85	466.08	723.38	501.73	221.65	3.264		
22,400.00	12,210.40	21,928.31	11,735.94	138.73	141.36	-49.01	-10,030.85	466.94	723.38	499.61	223.77	3.233		
22,407.15	12,210.46	21,935.46	11,736.00	138.83	141.45	-49.01	-10,037.99	467.00	723.38	499.46	223.92	3.231		
22,411.61	12,210.50	21,935.47	11,736.00	138.89	141.45	-49.01	-10,038.00	467.00	723.39	499.36	224.03	3.229	SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 41 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 156H - OH - Plan 1														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Minimum Separation (usft)	Separation Factor	Warning		
							+N/-S (usft)	+E/-W (usft)							
15,400.00	12,149.41	14,904.23	11,619.28	44.79	56.91	-76.39	-3,014.69	2,063.27	2,266.30	2,166.84	99.47	22.785			
15,500.00	12,150.28	15,004.23	11,619.81	46.08	58.25	-76.39	-3,114.69	2,064.18	2,266.43	2,164.43	102.00	22.220			
15,600.00	12,151.15	15,104.23	11,620.33	47.37	59.58	-76.38	-3,214.68	2,065.09	2,266.56	2,162.02	104.54	21.681			
15,700.00	12,152.02	15,204.23	11,620.86	48.66	60.91	-76.37	-3,314.67	2,066.00	2,266.69	2,159.60	107.09	21.167			
15,800.00	12,152.90	15,304.23	11,621.38	49.96	62.25	-76.36	-3,414.67	2,066.91	2,266.82	2,157.17	109.64	20.675			
15,900.00	12,153.77	15,404.23	11,621.91	51.26	63.59	-76.35	-3,514.66	2,067.81	2,266.94	2,154.74	112.20	20.205			
16,000.00	12,154.64	15,504.23	11,622.43	52.57	64.93	-76.34	-3,614.66	2,068.72	2,267.07	2,152.31	114.76	19.754			
16,100.00	12,155.51	15,604.23	11,622.96	53.88	66.27	-76.34	-3,714.65	2,069.63	2,267.20	2,149.87	117.33	19.323			
16,200.00	12,156.38	15,704.23	11,623.48	55.19	67.61	-76.33	-3,814.64	2,070.54	2,267.33	2,147.43	119.90	18.910			
16,300.00	12,157.25	15,804.23	11,624.01	56.50	68.95	-76.32	-3,914.64	2,071.45	2,267.46	2,144.98	122.48	18.513			
16,400.00	12,158.12	15,904.23	11,624.53	57.82	70.30	-76.31	-4,014.63	2,072.36	2,267.59	2,142.53	125.06	18.132			
16,500.00	12,158.99	16,004.23	11,625.06	59.14	71.64	-76.30	-4,114.62	2,073.27	2,267.71	2,140.07	127.64	17.766			
16,600.00	12,159.87	16,104.23	11,625.58	60.46	72.99	-76.30	-4,214.62	2,074.18	2,267.84	2,137.61	130.23	17.414			
16,700.00	12,160.74	16,204.23	11,626.11	61.79	74.33	-76.29	-4,314.61	2,075.09	2,267.97	2,135.15	132.82	17.075			
16,800.00	12,161.61	16,304.23	11,626.63	63.11	75.68	-76.28	-4,414.61	2,075.99	2,268.10	2,132.69	135.42	16.749			
16,900.00	12,162.48	16,404.23	11,627.16	64.44	77.03	-76.27	-4,514.60	2,076.90	2,268.23	2,130.22	138.01	16.435			
17,000.00	12,163.35	16,504.22	11,627.68	65.77	78.38	-76.26	-4,614.59	2,077.81	2,268.36	2,127.75	140.61	16.132			
17,100.00	12,164.22	16,604.22	11,628.21	67.10	79.73	-76.25	-4,714.59	2,078.72	2,268.49	2,125.28	143.21	15.840			
17,200.00	12,165.09	16,704.22	11,628.73	68.43	81.08	-76.25	-4,814.58	2,079.63	2,268.62	2,122.80	145.81	15.558			
17,300.00	12,165.96	16,804.22	11,629.26	69.77	82.43	-76.24	-4,914.58	2,080.54	2,268.74	2,120.33	148.42	15.286			
17,400.00	12,166.84	16,904.22	11,629.78	71.10	83.78	-76.23	-5,014.57	2,081.45	2,268.87	2,117.85	151.03	15.023			
17,500.00	12,167.71	17,004.22	11,630.31	72.44	85.13	-76.22	-5,114.56	2,082.36	2,269.00	2,115.37	153.63	14.769			
17,600.00	12,168.58	17,104.22	11,630.83	73.78	86.48	-76.21	-5,214.56	2,083.27	2,269.13	2,112.89	156.25	14.523			
17,700.00	12,169.45	17,204.22	11,631.36	75.12	87.84	-76.21	-5,314.55	2,084.17	2,269.26	2,110.40	158.86	14.285			
17,800.00	12,170.32	17,304.22	11,631.88	76.46	89.19	-76.20	-5,414.55	2,085.08	2,269.39	2,107.92	161.47	14.054			
17,900.00	12,171.19	17,404.22	11,632.41	77.80	90.55	-76.19	-5,514.54	2,085.99	2,269.52	2,105.43	164.09	13.831			
18,000.00	12,172.06	17,504.22	11,632.93	79.14	91.90	-76.18	-5,614.53	2,086.90	2,269.65	2,102.94	166.70	13.615			
18,100.00	12,172.93	17,604.22	11,633.46	80.48	93.26	-76.17	-5,714.53	2,087.81	2,269.78	2,100.45	169.32	13.405			
18,200.00	12,173.81	17,704.22	11,633.98	81.83	94.61	-76.16	-5,814.52	2,088.72	2,269.91	2,097.96	171.94	13.202			
18,300.00	12,174.68	17,804.22	11,634.51	83.17	95.97	-76.16	-5,914.51	2,089.63	2,270.04	2,095.47	174.56	13.004			
18,400.00	12,175.55	17,904.22	11,635.03	84.52	97.32	-76.15	-6,014.51	2,090.50	2,270.17	2,092.98	177.19	12.812			
18,500.00	12,176.42	18,004.22	11,635.56	85.86	98.68	-76.14	-6,114.50	2,091.45	2,270.29	2,090.49	179.81	12.626			
18,600.00	12,177.29	18,104.22	11,636.09	87.21	100.04	-76.13	-6,214.50	2,092.35	2,270.42	2,087.99	182.43	12.445			
18,700.00	12,178.16	18,204.21	11,636.61	88.56	101.39	-76.12	-6,314.49	2,093.26	2,270.55	2,085.50	185.06	12.269			
18,800.00	12,179.03	18,304.21	11,637.14	89.91	102.75	-76.12	-6,414.48	2,094.17	2,270.68	2,083.00	187.68	12.098			
18,900.00	12,179.90	18,404.21	11,637.66	91.26	104.11	-76.11	-6,514.48	2,095.08	2,270.81	2,080.50	190.31	11.932			
19,000.00	12,180.78	18,504.21	11,638.19	92.61	105.47	-76.10	-6,614.47	2,095.99	2,270.94	2,078.00	192.94	11.770			
19,100.00	12,181.65	18,604.21	11,638.71	93.96	106.83	-76.09	-6,714.47	2,096.90	2,271.07	2,075.51	195.57	11.613			
19,200.00	12,182.52	18,704.21	11,639.24	95.31	108.18	-76.08	-6,814.46	2,097.81	2,271.20	2,073.01	198.20	11.459			
19,300.00	12,183.39	18,804.21	11,639.76	96.66	109.54	-76.07	-6,914.45	2,098.72	2,271.33	2,070.51	200.83	11.310			
19,400.00	12,184.26	18,904.21	11,640.29	98.01	110.90	-76.07	-7,014.45	2,099.63	2,271.46	2,068.01	203.46	11.164			
19,500.00	12,185.13	19,004.21	11,640.81	99.36	112.26	-76.06	-7,114.44	2,100.53	2,271.59	2,065.50	206.09	11.022			
19,600.00	12,186.00	19,104.21	11,641.34	100.72	113.62	-76.05	-7,214.44	2,101.44	2,271.72	2,063.00	208.72	10.884			
19,700.00	12,186.87	19,204.21	11,641.86	102.07	114.98	-76.04	-7,314.43	2,102.35	2,271.85	2,060.50	211.35	10.749			
19,800.00	12,187.75	19,304.21	11,642.39	103.42	116.34	-76.03	-7,414.42	2,103.26	2,271.98	2,058.00	213.99	10.617			
19,900.00	12,188.62	19,404.21	11,642.91	104.78	117.70	-76.03	-7,514.42	2,104.17	2,272.11	2,055.49	216.62	10.489			
20,000.00	12,189.49	19,504.21	11,643.44	106.13	119.06	-76.02	-7,614.41	2,105.08	2,272.24	2,052.99	219.25	10.364			
20,100.00	12,190.36	19,604.21	11,643.96	107.49	120.42	-76.01	-7,714.40	2,105.99	2,272.37	2,050.48	221.89	10.241			
20,200.00	12,191.23	19,704.21	11,644.49	108.84	121.78	-76.00	-7,814.40	2,106.90	2,272.50	2,047.98	224.52	10.121			
20,300.00	12,192.10	19,804.20	11,645.01	110.20	123.15	-75.99	-7,914.39	2,107.81	2,272.63	2,045.47	227.16	10.005			
20,400.00	12,192.97	19,904.20	11,645.54	111.55	124.51	-75.98	-8,014.39	2,108.72	2,272.76	2,042.97	229.79	9.890			
20,500.00	12,193.85	20,004.20	11,646.06	112.91	125.87	-75.98	-8,114.38	2,109.62	2,272.89	2,040.46	232.43	9.779			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 45 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 156H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)	Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)						
20,600.00	12,194.72	20,104.20	11,646.59	114.27	127.23	-75.97	-8,214.37	2,110.53	2,273.02	2,037.96	235.07	9.670		
20,700.00	12,195.59	20,204.20	11,647.11	115.62	128.59	-75.96	-8,314.37	2,111.44	2,273.15	2,035.45	237.70	9.563		
20,800.00	12,196.46	20,304.20	11,647.64	116.98	129.95	-75.95	-8,414.36	2,112.35	2,273.28	2,032.94	240.34	9.459		
20,900.00	12,197.33	20,404.20	11,648.16	118.34	131.32	-75.94	-8,514.36	2,113.26	2,273.42	2,030.44	242.98	9.356		
21,000.00	12,198.20	20,504.20	11,648.69	119.70	132.68	-75.94	-8,614.35	2,114.17	2,273.55	2,027.93	245.62	9.256		
21,100.00	12,199.07	20,604.20	11,649.21	121.05	134.04	-75.93	-8,714.34	2,115.08	2,273.68	2,025.42	248.26	9.159		
21,200.00	12,199.94	20,704.20	11,649.74	122.41	135.40	-75.92	-8,814.34	2,115.99	2,273.81	2,022.91	250.89	9.063		
21,300.00	12,200.82	20,804.20	11,650.26	123.77	136.77	-75.91	-8,914.33	2,116.90	2,273.94	2,020.41	253.53	8.969		
21,400.00	12,201.69	20,904.20	11,650.79	125.13	138.13	-75.90	-9,014.33	2,117.80	2,274.07	2,017.90	256.17	8.877		
21,500.00	12,202.56	21,004.20	11,651.31	126.49	139.49	-75.89	-9,114.32	2,118.71	2,274.20	2,015.39	258.81	8.787		
21,600.00	12,203.43	21,104.20	11,651.84	127.85	140.86	-75.89	-9,214.31	2,119.62	2,274.33	2,012.88	261.45	8.699		
21,700.00	12,204.30	21,204.20	11,652.36	129.21	142.22	-75.88	-9,314.31	2,120.53	2,274.46	2,010.37	264.09	8.612		
21,800.00	12,205.17	21,304.20	11,652.89	130.57	143.58	-75.87	-9,414.30	2,121.44	2,274.59	2,007.86	266.73	8.528		
21,900.00	12,206.04	21,404.19	11,653.41	131.93	144.95	-75.86	-9,514.29	2,122.35	2,274.72	2,005.35	269.37	8.445		
22,000.00	12,206.91	21,504.19	11,653.94	133.29	146.31	-75.85	-9,614.29	2,123.26	2,274.85	2,002.84	272.01	8.363		
22,100.00	12,207.79	21,604.19	11,654.46	134.65	147.67	-75.85	-9,714.28	2,124.17	2,274.99	2,000.34	274.65	8.283		
22,200.00	12,208.66	21,704.19	11,654.99	136.01	149.04	-75.84	-9,814.28	2,125.08	2,275.12	1,997.83	277.29	8.205		
22,300.00	12,209.53	21,804.19	11,655.51	137.37	150.40	-75.83	-9,914.27	2,125.98	2,275.25	1,995.32	279.93	8.128		
22,400.00	12,210.40	21,904.19	11,656.04	138.73	151.77	-75.82	-10,014.26	2,126.89	2,275.38	1,992.81	282.57	8.052		
22,411.61	12,210.50	21,915.80	11,656.10	138.89	151.92	-75.82	-10,025.88	2,127.00	2,275.39	1,992.52	282.88	8.044	ES, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 46 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 211H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:					Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)
0.00	0.00	1.00	1.00	0.50	0.50	-90.00	0.00	-25.00	25.00				
100.00	100.00	101.00	101.00	0.98	0.99	-90.00	0.00	-25.00	25.00	23.03	1.97	12.706	
200.00	200.00	201.00	201.00	1.56	1.57	-90.00	0.00	-25.00	25.00	21.87	3.13	7.996	
216.33	216.33	217.33	217.33	1.63	1.63	-90.00	0.00	-25.00	25.00	21.74	3.26	7.663	
300.00	300.00	300.99	300.99	1.98	1.99	-90.00	0.00	-25.00	25.00	21.03	3.97	6.303	
400.00	400.00	400.37	400.36	2.33	2.41	-88.88	0.51	-26.22	26.23	21.50	4.73	5.544	
500.00	500.00	499.61	499.52	2.63	2.78	-86.12	2.02	-29.81	29.91	24.52	5.40	5.542	
600.00	600.00	598.58	598.28	2.91	3.11	-82.80	4.52	-35.75	36.14	30.14	6.00	6.024	
700.00	700.00	697.89	697.22	3.16	3.25	-79.85	7.81	-43.59	44.44	38.05	6.39	6.953	
800.00	800.00	797.51	796.46	3.40	3.50	-77.79	11.17	-51.59	52.98	46.11	6.88	7.703	
900.00	899.99	897.19	895.77	3.68	3.74	-56.99	14.53	-59.60	60.85	53.50	7.36	8.271	
1,000.00	999.91	996.97	995.16	3.94	3.97	-58.42	17.90	-67.62	67.33	59.52	7.81	8.619	
1,100.00	1,099.77	1,096.76	1,094.57	4.15	4.20	-60.55	21.27	-75.64	73.19	64.95	8.23	8.889	
1,200.00	1,199.63	1,196.55	1,193.99	4.35	4.42	-62.36	24.63	-83.66	79.13	70.49	8.65	9.154	
1,250.43	1,250.00	1,246.89	1,244.13	4.40	4.49	-63.18	26.33	-87.70	82.16	73.40	8.76	9.383	
1,300.00	1,299.48	1,295.44	1,292.48	4.45	4.55	-64.01	28.06	-91.83	85.24	76.39	8.86	9.626	
1,400.00	1,399.17	1,392.96	1,389.39	4.69	4.81	-66.20	32.25	-101.80	92.51	83.23	9.28	9.972	
1,500.00	1,498.62	1,490.15	1,485.68	4.93	5.06	-68.86	37.38	-114.01	101.31	91.62	9.69	10.460	
1,550.47	1,548.70	1,539.07	1,533.99	4.99	5.19	-70.30	40.32	-121.01	106.38	96.54	9.84	10.812	
1,600.00	1,597.81	1,586.98	1,581.23	5.05	5.31	-71.68	43.43	-128.42	111.88	101.89	9.99	11.199	
1,700.00	1,696.95	1,683.37	1,675.93	5.25	5.55	-73.69	50.38	-144.97	124.83	114.44	10.39	12.019	
1,800.00	1,796.09	1,779.23	1,769.63	5.44	5.79	-74.84	58.21	-163.62	140.09	129.31	10.78	12.990	
1,900.00	1,895.24	1,876.41	1,864.18	5.64	5.98	-75.40	66.92	-184.35	157.20	146.05	11.15	14.104	
2,000.00	1,994.38	1,974.90	1,959.94	5.83	6.18	-75.83	75.82	-205.55	174.51	162.96	11.55	15.108	
2,100.00	2,093.53	2,073.38	2,055.70	6.03	6.40	-76.18	84.72	-226.75	191.82	179.86	11.97	16.032	
2,200.00	2,192.67	2,171.86	2,151.46	6.22	6.61	-76.47	93.63	-247.95	209.15	196.76	12.38	16.892	
2,300.00	2,291.82	2,270.35	2,247.22	6.42	6.83	-76.72	102.53	-269.16	226.47	213.67	12.80	17.695	
2,400.00	2,390.96	2,368.83	2,342.98	6.61	7.07	-76.94	111.43	-290.36	243.80	230.59	13.22	18.445	
2,500.00	2,490.11	2,467.31	2,438.74	6.81	7.32	-77.12	120.34	-311.56	261.14	247.50	13.64	19.149	
2,600.00	2,589.25	2,565.79	2,534.50	7.00	7.60	-77.28	129.24	-332.76	278.47	264.42	14.06	19.809	
2,700.00	2,688.39	2,664.28	2,630.26	7.20	7.88	-77.42	138.14	-353.96	295.81	281.33	14.48	20.432	
2,800.00	2,787.54	2,762.76	2,726.02	7.39	8.17	-77.55	147.05	-375.16	313.15	298.25	14.90	21.016	
2,900.00	2,886.68	2,861.24	2,821.78	7.59	8.46	-77.66	155.95	-396.37	330.49	315.17	15.32	21.568	
3,000.00	2,985.83	2,959.73	2,917.55	7.78	8.76	-77.77	164.85	-417.57	347.83	332.09	15.75	22.090	
3,100.00	3,084.97	3,058.21	3,013.31	7.98	9.05	-77.86	173.76	-438.77	365.18	349.01	16.17	22.583	
3,200.00	3,184.12	3,156.69	3,109.07	8.17	9.35	-77.94	182.66	-459.97	382.52	365.92	16.59	23.051	
3,300.00	3,283.26	3,255.18	3,204.83	8.36	9.65	-78.02	191.56	-481.17	399.86	382.84	17.02	23.495	
3,400.00	3,382.40	3,353.66	3,300.59	8.56	9.95	-78.09	200.46	-502.38	417.21	399.76	17.44	23.917	
3,500.00	3,481.55	3,452.14	3,396.35	8.75	10.25	-78.15	209.37	-523.58	434.55	416.68	17.87	24.318	
3,600.00	3,580.69	3,550.62	3,492.11	8.95	10.55	-78.21	218.27	-544.78	451.90	433.60	18.30	24.700	
3,700.00	3,679.84	3,649.11	3,587.87	9.14	10.86	-78.27	227.17	-565.98	469.25	450.52	18.72	25.064	
3,800.00	3,778.98	3,747.59	3,683.63	9.33	11.16	-78.32	236.08	-587.18	486.59	467.44	19.15	25.412	
3,900.00	3,878.13	3,846.07	3,779.39	9.53	11.46	-78.37	244.98	-608.38	503.94	484.36	19.58	25.744	
4,000.00	3,977.27	3,944.56	3,875.15	9.72	11.77	-78.41	253.88	-629.59	521.29	501.29	20.00	26.061	
4,100.00	4,076.42	4,043.04	3,970.91	9.91	12.07	-78.45	262.79	-650.79	538.64	518.21	20.43	26.365	
4,200.00	4,175.56	4,141.52	4,066.67	10.11	12.38	-78.49	271.69	-671.99	555.98	535.13	20.86	26.656	
4,300.00	4,274.70	4,240.01	4,162.44	10.30	12.68	-78.53	280.59	-693.19	573.33	552.05	21.29	26.936	
4,400.00	4,373.85	4,338.49	4,258.20	10.49	12.99	-78.57	289.50	-714.39	590.68	568.97	21.71	27.203	
4,500.00	4,472.99	4,436.97	4,353.96	10.69	13.30	-78.60	298.40	-735.59	608.03	585.89	22.14	27.461	
4,600.00	4,572.14	4,535.46	4,449.72	10.88	13.61	-78.63	307.30	-756.80	625.38	602.81	22.57	27.708	
4,700.00	4,671.28	4,633.94	4,545.48	11.08	13.91	-78.66	316.21	-778.00	642.73	619.73	23.00	27.943	
4,702.13	4,673.39	4,636.04	4,547.52	11.08	13.92	-78.66	316.40	-778.45	643.10	620.09	23.01	27.948	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 47 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 211H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Semi Major Axis		Offset Wellbore Centre			Rule Assigned: Distance		Offset Well Error: 0.50 usft		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
9,900.00	9,869.84	9,997.02	9,870.84	16.06	20.87	-90.39	453.28	-1,104.42	935.01	901.22	33.79	27.670	
10,000.00	9,969.84	10,097.02	9,970.84	16.14	20.93	-90.39	453.28	-1,104.42	935.01	901.07	33.94	27.550	
10,100.00	10,069.84	10,197.02	10,070.84	16.23	20.99	-90.39	453.28	-1,104.42	935.01	900.93	34.09	27.432	
10,200.00	10,169.84	10,297.02	10,170.84	16.31	21.05	-90.39	453.28	-1,104.42	935.01	900.78	34.23	27.314	
10,300.00	10,269.84	10,397.02	10,270.84	16.40	21.11	-90.39	453.28	-1,104.42	935.01	900.63	34.38	27.197	
10,400.00	10,369.84	10,497.02	10,370.84	16.48	21.17	-90.39	453.28	-1,104.42	935.01	900.49	34.53	27.081	
10,500.00	10,469.84	10,597.02	10,470.84	16.57	21.23	-90.39	453.28	-1,104.42	935.01	900.34	34.67	26.966	
10,600.00	10,569.84	10,697.02	10,570.84	16.65	21.29	-90.39	453.28	-1,104.42	935.01	900.19	34.82	26.852	
10,700.00	10,669.84	10,797.02	10,670.84	16.74	21.35	-90.39	453.28	-1,104.42	935.01	900.04	34.97	26.739	
10,800.00	10,769.84	10,897.02	10,770.84	16.82	21.41	-90.39	453.28	-1,104.42	935.01	899.90	35.12	26.626	
10,900.00	10,869.84	10,997.02	10,870.84	16.91	21.48	-90.39	453.28	-1,104.42	935.01	899.75	35.26	26.515	
11,000.00	10,969.84	11,097.02	10,970.84	16.99	21.54	-90.39	453.28	-1,104.42	935.01	899.60	35.41	26.404	
11,100.00	11,069.84	11,197.02	11,070.84	17.08	21.60	-90.39	453.28	-1,104.42	935.01	899.45	35.56	26.294	
11,200.00	11,169.84	11,297.02	11,170.84	17.16	21.66	-90.39	453.28	-1,104.42	935.01	899.30	35.71	26.185	
11,300.00	11,269.84	11,397.02	11,270.84	17.25	21.72	-90.39	453.28	-1,104.42	935.01	899.16	35.86	26.077	
11,400.00	11,369.84	11,497.02	11,370.84	17.33	21.78	-90.39	453.28	-1,104.42	935.01	899.01	36.00	25.970	
11,500.00	11,469.84	11,597.02	11,470.84	17.42	21.84	-90.39	453.28	-1,104.42	935.01	898.86	36.15	25.863	
11,581.16	11,551.00	11,678.18	11,552.00	17.48	21.89	-90.39	453.28	-1,104.42	935.01	898.75	36.26	25.784	
11,600.00	11,569.83	11,697.01	11,570.83	17.48	21.91	90.12	453.28	-1,104.42	935.01	898.74	36.27	25.776	
11,650.00	11,619.67	11,746.85	11,620.67	17.49	21.94	90.35	453.28	-1,104.42	935.03	898.76	36.27	25.779	
11,700.00	11,668.99	11,796.17	11,669.99	17.51	21.97	90.84	453.28	-1,104.42	935.11	898.88	36.24	25.804	
11,750.00	11,717.40	11,844.59	11,718.40	17.51	22.00	91.55	453.28	-1,104.42	935.38	899.20	36.18	25.852	
11,800.00	11,764.55	11,891.74	11,765.55	17.52	22.03	92.44	453.28	-1,104.42	936.00	899.89	36.10	25.925	
11,850.00	11,810.08	11,937.26	11,811.08	17.52	22.05	93.47	453.28	-1,104.42	937.17	901.16	36.01	26.026	
11,900.00	11,853.63	11,980.82	11,854.63	17.52	22.08	94.58	453.28	-1,104.42	939.15	903.25	35.91	26.156	
11,950.00	11,894.88	12,022.07	11,895.88	17.53	22.10	95.68	453.28	-1,104.42	942.22	906.43	35.80	26.323	
12,000.00	11,933.52	12,060.70	11,934.52	17.53	22.12	96.72	453.28	-1,104.42	946.66	910.97	35.69	26.525	
12,050.00	11,969.24	12,111.45	11,985.21	17.53	22.14	98.20	451.33	-1,104.40	952.50	916.93	35.57	26.775	
12,100.00	12,001.78	12,168.47	12,041.71	17.53	22.16	99.78	443.82	-1,104.34	959.43	923.96	35.47	27.048	
12,150.00	12,030.89	12,231.99	12,103.42	17.53	22.16	101.46	428.88	-1,104.21	967.28	931.86	35.42	27.311	
12,200.00	12,056.34	12,303.96	12,170.84	17.53	22.15	103.26	403.84	-1,103.99	975.83	940.38	35.45	27.527	
12,250.00	12,077.95	12,386.85	12,243.88	17.54	22.12	105.21	364.80	-1,103.66	984.72	949.11	35.61	27.651	
12,300.00	12,095.55	12,483.57	12,320.93	17.55	22.08	107.28	306.53	-1,103.16	993.46	957.50	35.95	27.632	
12,350.00	12,109.01	12,596.92	12,397.23	17.56	22.06	109.35	222.95	-1,102.44	1,001.33	964.86	36.47	27.453	
12,400.00	12,118.22	12,728.10	12,463.00	17.58	22.10	111.14	109.80	-1,101.46	1,007.48	970.39	37.08	27.167	
12,450.00	12,123.11	12,874.23	12,503.91	17.60	22.30	112.25	-30.08	-1,100.26	1,010.99	973.44	37.55	26.921	
12,476.17	12,123.94	12,954.05	12,510.87	17.61	22.48	112.43	-109.53	-1,099.58	1,011.55	973.92	37.64	26.877	
12,500.00	12,124.14	12,981.34	12,511.13	17.62	22.55	112.43	-136.81	-1,099.34	1,011.56	973.88	37.68	26.848	
12,600.00	12,125.02	13,081.34	12,512.00	17.69	22.85	112.43	-236.80	-1,098.48	1,011.56	973.57	37.99	26.629	
12,700.00	12,125.89	13,181.34	12,512.88	17.79	23.22	112.43	-336.79	-1,097.62	1,011.56	973.09	38.46	26.299	
12,800.00	12,126.76	13,281.34	12,513.75	17.95	23.64	112.43	-436.79	-1,096.76	1,011.56	972.46	39.10	25.869	
12,900.00	12,127.63	13,381.34	12,514.62	18.21	24.13	112.43	-536.78	-1,095.90	1,011.56	971.66	39.90	25.355	
13,000.00	12,128.50	13,481.34	12,515.49	18.61	24.66	112.43	-636.77	-1,095.04	1,011.56	970.73	40.83	24.773	
13,100.00	12,129.37	13,581.34	12,516.37	19.18	25.25	112.43	-736.76	-1,094.18	1,011.56	969.66	41.91	24.139	
13,200.00	12,130.24	13,681.34	12,517.24	19.87	25.88	112.43	-836.76	-1,093.32	1,011.56	968.46	43.10	23.469	
13,300.00	12,131.11	13,781.34	12,518.11	20.66	26.56	112.43	-936.75	-1,092.46	1,011.56	967.15	44.42	22.775	
13,400.00	12,131.99	13,881.34	12,518.99	21.53	27.29	112.43	-1,036.74	-1,091.60	1,011.56	965.73	45.83	22.071	
13,500.00	12,132.86	13,981.34	12,519.86	22.45	28.06	112.43	-1,136.73	-1,090.73	1,011.56	964.22	47.34	21.366	
13,600.00	12,133.73	14,081.34	12,520.73	23.43	28.87	112.43	-1,236.73	-1,089.87	1,011.57	962.62	48.94	20.668	
13,700.00	12,134.60	14,181.34	12,521.61	24.44	29.72	112.43	-1,336.72	-1,089.01	1,011.57	960.94	50.62	19.983	
13,800.00	12,135.47	14,281.34	12,522.48	25.50	30.61	112.43	-1,436.71	-1,088.15	1,011.57	959.20	52.37	19.316	
13,900.00	12,136.34	14,381.34	12,523.35	26.58	31.52	112.43	-1,536.70	-1,087.29	1,011.57	957.39	54.18	18.670	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 49 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 211H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
14,000.00	12,137.21	14,481.34	12,524.23	27.69	32.47	112.43		112.43	-1,636.70	-1,086.43	1,011.57	955.52	56.05	18.047	
14,100.00	12,138.08	14,581.34	12,525.10	28.82	33.45	112.43		112.43	-1,736.69	-1,085.57	1,011.57	953.59	57.98	17.448	
14,200.00	12,138.96	14,681.34	12,525.97	29.98	34.45	112.43		112.43	-1,836.68	-1,084.71	1,011.57	951.63	59.95	16.875	
14,300.00	12,139.83	14,781.34	12,526.84	31.15	35.47	112.43		112.43	-1,936.67	-1,083.85	1,011.57	949.61	61.96	16.327	
14,400.00	12,140.70	14,881.34	12,527.72	32.33	36.52	112.43		112.43	-2,036.67	-1,082.99	1,011.57	947.56	64.01	15.803	
14,500.00	12,141.57	14,981.34	12,528.59	33.54	37.59	112.43		112.43	-2,136.66	-1,082.13	1,011.57	945.48	66.10	15.304	
14,600.00	12,142.44	15,081.34	12,529.46	34.75	38.67	112.43		112.43	-2,236.65	-1,081.27	1,011.58	943.36	68.22	14.829	
14,700.00	12,143.31	15,181.34	12,530.34	35.98	39.78	112.43		112.43	-2,336.64	-1,080.41	1,011.58	941.21	70.36	14.377	
14,800.00	12,144.18	15,281.34	12,531.21	37.21	40.90	112.43		112.43	-2,436.64	-1,079.55	1,011.58	939.04	72.54	13.946	
14,900.00	12,145.05	15,381.34	12,532.08	38.46	42.03	112.43		112.43	-2,536.63	-1,078.69	1,011.58	936.84	74.73	13.536	
15,000.00	12,145.93	15,481.34	12,532.96	39.71	43.18	112.43		112.43	-2,636.62	-1,077.82	1,011.58	934.62	76.96	13.145	
15,100.00	12,146.80	15,581.34	12,533.83	40.97	44.34	112.43		112.43	-2,736.61	-1,076.96	1,011.58	932.38	79.20	12.773	
15,200.00	12,147.67	15,681.34	12,534.70	42.24	45.52	112.43		112.43	-2,836.61	-1,076.10	1,011.58	930.13	81.45	12.419	
15,300.00	12,148.54	15,781.34	12,535.57	43.51	46.70	112.43		112.43	-2,936.60	-1,075.24	1,011.58	927.85	83.73	12.081	
15,400.00	12,149.41	15,881.34	12,536.45	44.79	47.89	112.43		112.43	-3,036.59	-1,074.38	1,011.58	925.56	86.02	11.759	
15,500.00	12,150.28	15,981.34	12,537.32	46.08	49.10	112.43		112.43	-3,136.58	-1,073.52	1,011.58	923.25	88.33	11.452	
15,600.00	12,151.15	16,081.34	12,538.19	47.37	50.31	112.43		112.43	-3,236.58	-1,072.66	1,011.59	920.94	90.65	11.159	
15,700.00	12,152.02	16,181.34	12,539.07	48.66	51.53	112.44		112.44	-3,336.57	-1,071.80	1,011.59	918.60	92.98	10.879	
15,800.00	12,152.90	16,281.34	12,539.94	49.96	52.76	112.44		112.44	-3,436.56	-1,070.94	1,011.59	916.26	95.32	10.612	
15,900.00	12,153.77	16,381.34	12,540.81	51.26	53.99	112.44		112.44	-3,536.55	-1,070.08	1,011.59	913.91	97.68	10.356	
16,000.00	12,154.64	16,481.34	12,541.69	52.57	55.23	112.44		112.44	-3,636.55	-1,069.22	1,011.59	911.55	100.04	10.111	
16,100.00	12,155.51	16,581.34	12,542.56	53.88	56.48	112.44		112.44	-3,736.54	-1,068.36	1,011.59	909.17	102.42	9.877	
16,200.00	12,156.38	16,681.34	12,543.43	55.19	57.73	112.44		112.44	-3,836.53	-1,067.50	1,011.59	906.79	104.80	9.653	
16,300.00	12,157.25	16,781.34	12,544.31	56.50	58.99	112.44		112.44	-3,936.52	-1,066.64	1,011.59	904.40	107.19	9.437	
16,400.00	12,158.12	16,881.34	12,545.18	57.82	60.25	112.44		112.44	-4,036.52	-1,065.78	1,011.59	902.01	109.59	9.231	
16,500.00	12,158.99	16,981.34	12,546.05	59.14	61.52	112.44		112.44	-4,136.51	-1,064.92	1,011.59	899.60	111.99	9.033	
16,600.00	12,159.87	17,081.34	12,546.92	60.46	62.79	112.44		112.44	-4,236.50	-1,064.05	1,011.59	897.19	114.40	8.842	
16,700.00	12,160.74	17,181.34	12,547.80	61.79	64.06	112.44		112.44	-4,336.49	-1,063.19	1,011.60	894.78	116.82	8.659	
16,800.00	12,161.61	17,281.34	12,548.67	63.11	65.34	112.44		112.44	-4,436.49	-1,062.33	1,011.60	892.35	119.24	8.483	
16,900.00	12,162.48	17,381.34	12,549.54	64.44	66.62	112.44		112.44	-4,536.48	-1,061.47	1,011.60	889.93	121.67	8.314	
17,000.00	12,163.35	17,481.34	12,550.42	65.77	67.91	112.44		112.44	-4,636.47	-1,060.61	1,011.60	887.49	124.11	8.151	
17,100.00	12,164.22	17,581.34	12,551.29	67.10	69.20	112.44		112.44	-4,736.46	-1,059.75	1,011.60	885.05	126.54	7.994	
17,200.00	12,165.09	17,681.34	12,552.16	68.43	70.49	112.44		112.44	-4,836.46	-1,058.89	1,011.60	882.61	128.99	7.843	
17,300.00	12,165.96	17,781.34	12,553.04	69.77	71.79	112.44		112.44	-4,936.45	-1,058.03	1,011.60	880.17	131.44	7.697	
17,400.00	12,166.84	17,881.34	12,553.91	71.10	73.09	112.44		112.44	-5,036.44	-1,057.17	1,011.60	877.72	133.89	7.556	
17,500.00	12,167.71	17,981.34	12,554.78	72.44	74.39	112.44		112.44	-5,136.43	-1,056.31	1,011.60	875.26	136.34	7.420	
17,600.00	12,168.58	18,081.34	12,555.65	73.78	75.69	112.44		112.44	-5,236.43	-1,055.45	1,011.60	872.80	138.80	7.288	
17,700.00	12,169.45	18,181.34	12,556.53	75.12	77.00	112.44		112.44	-5,336.42	-1,054.59	1,011.61	870.34	141.26	7.161	
17,800.00	12,170.32	18,281.34	12,557.40	76.46	78.31	112.44		112.44	-5,436.41	-1,053.73	1,011.61	867.88	143.73	7.038	
17,900.00	12,171.19	18,381.34	12,558.27	77.80	79.62	112.44		112.44	-5,536.40	-1,052.87	1,011.61	865.41	146.20	6.919	
18,000.00	12,172.06	18,481.34	12,559.15	79.14	80.93	112.44		112.44	-5,636.40	-1,052.01	1,011.61	862.94	148.67	6.804	
18,100.00	12,172.93	18,581.34	12,560.02	80.48	82.24	112.44		112.44	-5,736.39	-1,051.14	1,011.61	860.46	151.15	6.693	
18,200.00	12,173.81	18,681.34	12,560.89	81.83	83.56	112.44		112.44	-5,836.38	-1,050.28	1,011.61	857.99	153.62	6.585	
18,300.00	12,174.68	18,781.34	12,561.77	83.17	84.87	112.44		112.44	-5,936.37	-1,049.42	1,011.61	855.51	156.10	6.480	
18,400.00	12,175.55	18,881.34	12,562.64	84.52	86.19	112.44		112.44	-6,036.37	-1,048.56	1,011.61	853.03	158.58	6.379	
18,500.00	12,176.42	18,981.34	12,563.51	85.86	87.51	112.44		112.44	-6,136.36	-1,047.70	1,011.61	850.54	161.07	6.281	
18,600.00	12,177.29	19,081.34	12,564.39	87.21	88.84	112.44		112.44	-6,236.35	-1,046.84	1,011.61	848.06	163.56	6.185	
18,700.00	12,178.16	19,181.34	12,565.26	88.56	90.16	112.44		112.44	-6,336.34	-1,045.98	1,011.62	845.57	166.05	6.092	
18,800.00	12,179.03	19,281.34	12,566.13	89.91	91.49	112.44		112.44	-6,436.34	-1,045.12	1,011.62	843.08	168.54	6.002	
18,900.00	12,179.90	19,381.34	12,567.00	91.26	92.81	112.44		112.44	-6,536.33	-1,044.26	1,011.62	840.59	171.03	5.915	
19,000.00	12,180.78	19,481.34	12,567.88	92.61	94.14	112.44		112.44	-6,636.32	-1,043.40	1,011.62	838.09	173.52	5.830	
19,100.00	12,181.65	19,581.34	12,568.75	93.96	95.47	112.44		112.44	-6,736.31	-1,042.54	1,011.62	835.60	176.02	5.747	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 50 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 211H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference	Vertical	Offset	Vertical	Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Depth (usft)	Measured Depth (usft)	Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)				
19,200.00	12,182.52	19,681.34	12,569.62	95.31	96.80	112.44	-6,836.31	-1,041.68	1,011.62	833.10	178.52	5.667		
19,300.00	12,183.39	19,781.34	12,570.50	96.66	98.13	112.44	-6,936.30	-1,040.82	1,011.62	830.60	181.02	5.588		
19,400.00	12,184.26	19,881.34	12,571.37	98.01	99.46	112.44	-7,036.29	-1,039.96	1,011.62	828.10	183.52	5.512		
19,500.00	12,185.13	19,981.34	12,572.24	99.36	100.80	112.44	-7,136.28	-1,039.10	1,011.62	825.60	186.02	5.438		
19,600.00	12,186.00	20,081.34	12,573.12	100.72	102.13	112.44	-7,236.28	-1,038.24	1,011.62	823.10	188.53	5.366		
19,700.00	12,186.87	20,181.34	12,573.99	102.07	103.46	112.44	-7,336.27	-1,037.37	1,011.62	820.59	191.03	5.296		
19,800.00	12,187.75	20,281.34	12,574.86	103.42	104.80	112.44	-7,436.26	-1,036.51	1,011.63	818.09	193.54	5.227		
19,900.00	12,188.62	20,381.34	12,575.74	104.78	106.14	112.44	-7,536.25	-1,035.65	1,011.63	815.58	196.05	5.160		
20,000.00	12,189.49	20,481.34	12,576.61	106.13	107.48	112.44	-7,636.25	-1,034.79	1,011.63	813.07	198.56	5.095		
20,100.00	12,190.36	20,581.34	12,577.48	107.49	108.81	112.44	-7,736.24	-1,033.93	1,011.63	810.56	201.07	5.031		
20,200.00	12,191.23	20,681.34	12,578.35	108.84	110.15	112.44	-7,836.23	-1,033.07	1,011.63	808.05	203.58	4.969		
20,300.00	12,192.10	20,781.34	12,579.23	110.20	111.49	112.44	-7,936.22	-1,032.21	1,011.63	805.54	206.09	4.909		
20,400.00	12,192.97	20,881.34	12,580.10	111.55	112.83	112.44	-8,036.22	-1,031.35	1,011.63	803.02	208.61	4.849		
20,500.00	12,193.85	20,981.34	12,580.97	112.91	114.18	112.44	-8,136.21	-1,030.49	1,011.63	800.51	211.12	4.792		
20,600.00	12,194.72	21,081.34	12,581.85	114.27	115.52	112.44	-8,236.20	-1,029.63	1,011.63	798.00	213.64	4.735		
20,700.00	12,195.59	21,181.34	12,582.72	115.62	116.86	112.44	-8,336.19	-1,028.77	1,011.63	795.48	216.16	4.680		
20,800.00	12,196.46	21,281.34	12,583.59	116.98	118.20	112.44	-8,436.19	-1,027.91	1,011.64	792.96	218.67	4.626		
20,900.00	12,197.33	21,381.34	12,584.47	118.34	119.55	112.44	-8,536.18	-1,027.05	1,011.64	790.44	221.19	4.574		
21,000.00	12,198.20	21,481.34	12,585.34	119.70	120.89	112.44	-8,636.17	-1,026.19	1,011.64	787.93	223.71	4.522		
21,100.00	12,199.07	21,581.34	12,586.21	121.05	122.24	112.44	-8,736.16	-1,025.33	1,011.64	785.41	226.23	4.472		
21,200.00	12,199.94	21,681.34	12,587.08	122.41	123.58	112.44	-8,836.16	-1,024.46	1,011.64	782.89	228.75	4.422		
21,300.00	12,200.82	21,781.34	12,587.96	123.77	124.93	112.44	-8,936.15	-1,023.60	1,011.64	780.37	231.27	4.374		
21,400.00	12,201.69	21,881.34	12,588.83	125.13	126.28	112.44	-9,036.14	-1,022.74	1,011.64	777.84	233.80	4.327		
21,500.00	12,202.56	21,981.34	12,589.70	126.49	127.62	112.44	-9,136.13	-1,021.88	1,011.64	775.32	236.32	4.281		
21,600.00	12,203.43	22,081.34	12,590.58	127.85	128.97	112.44	-9,236.13	-1,021.02	1,011.64	772.80	238.85	4.236		
21,700.00	12,204.30	22,181.34	12,591.45	129.21	130.32	112.44	-9,336.12	-1,020.16	1,011.64	770.27	241.37	4.191		
21,800.00	12,205.17	22,281.34	12,592.32	130.57	131.67	112.44	-9,436.11	-1,019.30	1,011.65	767.75	243.90	4.148		
21,900.00	12,206.04	22,381.34	12,593.20	131.93	133.02	112.44	-9,536.10	-1,018.44	1,011.65	765.22	246.42	4.105		
22,000.00	12,206.91	22,481.34	12,594.07	133.29	134.37	112.44	-9,636.10	-1,017.58	1,011.65	762.70	248.95	4.064		
22,100.00	12,207.79	22,581.34	12,594.94	134.65	135.72	112.44	-9,736.09	-1,016.72	1,011.65	760.17	251.48	4.023		
22,200.00	12,208.66	22,681.34	12,595.82	136.01	137.07	112.44	-9,836.08	-1,015.86	1,011.65	757.65	254.00	3.983		
22,300.00	12,209.53	22,781.34	12,596.69	137.37	138.42	112.44	-9,936.07	-1,015.00	1,011.65	755.12	256.53	3.944		
22,400.00	12,210.40	22,881.34	12,597.56	138.73	139.77	112.44	-10,036.07	-1,014.14	1,011.65	752.59	259.06	3.905		
22,411.61	12,210.50	22,892.95	12,597.66	138.89	139.93	112.44	-10,047.68	-1,014.04	1,011.65	752.30	259.35	3.901	SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 51 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 212H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)		
0.00	0.00	0.00	0.00	0.50	0.50	-7.70	185.00	-25.00	186.68			
100.00	100.00	100.00	100.00	0.98	0.98	-7.70	185.00	-25.00	186.68	184.72	1.96	95.140
200.00	200.00	200.00	200.00	1.56	1.56	-7.70	185.00	-25.00	186.68	183.56	3.12	59.791
300.00	300.00	300.00	300.00	1.98	1.98	-7.70	185.00	-25.00	186.68	182.72	3.96	47.114
400.00	400.00	400.00	400.00	2.33	2.33	-7.70	185.00	-25.00	186.68	182.02	4.66	40.070
500.00	500.00	500.00	500.00	2.63	2.63	-7.70	185.00	-25.00	186.68	181.41	5.27	35.430
600.00	600.00	600.00	600.00	2.91	2.91	-7.70	185.00	-25.00	186.68	180.86	5.82	32.075
700.00	700.00	700.00	700.00	3.16	3.16	-7.70	185.00	-25.00	186.68	180.35	6.33	29.503
800.00	800.00	800.00	800.00	3.40	3.40	-7.70	185.00	-25.00	186.68	179.88	6.80	27.448
900.00	899.99	899.99	899.99	3.68	3.62	12.63	185.00	-25.00	185.40	178.10	7.30	25.397
1,000.00	999.91	999.91	999.91	3.94	3.84	12.91	185.00	-25.00	181.58	173.80	7.77	23.359
1,100.00	1,099.77	1,099.77	1,099.77	4.15	4.04	13.29	185.00	-25.00	176.48	168.30	8.18	21.575
1,200.00	1,199.63	1,199.63	1,199.63	4.35	4.23	13.69	185.00	-25.00	171.39	162.81	8.57	19.991
1,250.43	1,250.00	1,250.00	1,250.00	4.40	4.33	13.90	185.00	-25.00	168.82	160.11	8.72	19.365
1,300.00	1,299.48	1,299.48	1,299.48	4.45	4.42	14.16	185.00	-25.00	166.00	157.13	8.86	18.728
1,400.00	1,399.17	1,399.17	1,399.17	4.69	4.60	14.88	185.00	-25.00	158.41	149.13	9.28	17.064
1,500.00	1,498.62	1,498.62	1,498.62	4.93	4.77	15.96	185.00	-25.00	148.34	138.65	9.69	15.305
1,550.47	1,548.70	1,548.70	1,548.70	4.99	4.86	16.68	185.00	-25.00	142.33	132.49	9.84	14.469
1,600.00	1,597.81	1,597.81	1,597.81	5.05	4.94	17.46	185.00	-25.00	136.15	126.17	9.98	13.649
1,700.00	1,696.95	1,696.95	1,696.95	5.25	5.11	19.27	185.00	-25.00	123.75	113.41	10.33	11.976
1,800.00	1,796.09	1,796.09	1,796.09	5.44	5.27	21.48	185.00	-25.00	111.49	100.81	10.68	10.436
1,900.00	1,895.24	1,895.24	1,895.24	5.64	5.43	24.23	185.00	-25.00	99.45	88.42	11.03	9.017
2,000.00	1,994.38	1,994.38	1,994.38	5.83	5.58	27.73	185.00	-25.00	87.69	76.32	11.37	7.714
2,100.00	2,093.53	2,093.53	2,093.53	6.03	5.73	32.28	185.00	-25.00	76.35	64.66	11.70	6.528
2,200.00	2,192.67	2,192.67	2,192.67	6.22	5.88	38.36	185.00	-25.00	65.65	53.64	12.01	5.466
2,300.00	2,291.82	2,290.51	2,290.51	6.42	6.05	46.78	185.82	-24.30	57.02	44.69	12.33	4.624
2,400.00	2,390.96	2,388.45	2,388.37	6.61	6.22	57.94	188.54	-21.98	52.61	39.98	12.63	4.165
2,440.22	2,430.84	2,427.86	2,427.73	6.69	6.29	62.85	190.17	-20.59	52.21	39.46	12.75	4.095
2,500.00	2,490.11	2,486.45	2,486.18	6.81	6.39	70.05	193.17	-18.03	53.10	40.18	12.92	4.110
2,600.00	2,589.25	2,584.41	2,583.76	7.00	6.56	80.57	199.70	-12.45	58.33	45.12	13.21	4.416
2,700.00	2,688.39	2,682.18	2,680.90	7.20	6.73	88.10	208.12	-5.27	67.46	53.96	13.51	4.995
2,800.00	2,787.54	2,780.45	2,778.26	7.39	6.83	92.92	218.26	3.39	79.39	65.62	13.76	5.768
2,900.00	2,886.68	2,879.52	2,876.37	7.59	6.97	96.38	228.75	12.33	92.00	77.93	14.08	6.536
3,000.00	2,985.83	2,978.59	2,974.47	7.78	7.12	99.00	239.23	21.28	104.87	90.47	14.40	7.282
3,100.00	3,084.97	3,077.66	3,072.58	7.98	7.27	101.04	249.72	30.23	117.91	103.18	14.73	8.003
3,200.00	3,184.12	3,176.73	3,170.68	8.17	7.42	102.67	260.20	39.18	131.06	116.00	15.07	8.700
3,300.00	3,283.26	3,275.79	3,268.79	8.36	7.57	104.01	270.69	48.12	144.31	128.90	15.40	9.370
3,400.00	3,382.40	3,374.86	3,366.89	8.56	7.73	105.12	281.17	57.07	157.61	141.87	15.74	10.015
3,500.00	3,481.55	3,473.93	3,465.00	8.75	7.89	106.06	291.66	66.02	170.96	154.89	16.08	10.634
3,600.00	3,580.69	3,573.00	3,563.10	8.95	8.05	106.86	302.14	74.97	184.36	167.94	16.42	11.229
3,700.00	3,679.84	3,672.07	3,661.21	9.14	8.21	107.55	312.63	83.91	197.78	181.02	16.76	11.801
3,800.00	3,778.98	3,771.14	3,759.31	9.33	8.37	108.16	323.11	92.86	211.23	194.13	17.10	12.350
3,900.00	3,878.13	3,870.20	3,857.42	9.53	8.53	108.69	333.60	101.81	224.70	207.25	17.45	12.878
4,000.00	3,977.27	3,969.27	3,955.52	9.72	8.70	109.16	344.08	110.76	238.18	220.39	17.79	13.386
4,100.00	4,076.42	4,068.34	4,053.63	9.91	8.86	109.58	354.57	119.71	251.68	233.54	18.14	13.874
4,200.00	4,175.56	4,167.41	4,151.73	10.11	9.03	109.96	365.05	128.65	265.19	246.70	18.49	14.343
4,300.00	4,274.70	4,266.48	4,249.84	10.30	9.20	110.30	375.54	137.60	278.71	259.88	18.84	14.795
4,400.00	4,373.85	4,365.55	4,347.94	10.49	9.37	110.61	386.02	146.55	292.25	273.06	19.19	15.230
4,500.00	4,472.99	4,464.62	4,446.05	10.69	9.54	110.90	396.51	155.50	305.78	286.24	19.54	15.650
4,600.00	4,572.14	4,563.68	4,544.15	10.88	9.71	111.16	406.99	164.44	319.33	299.44	19.89	16.054
4,700.00	4,671.28	4,662.75	4,642.26	11.08	9.88	111.39	417.48	173.39	332.88	312.63	20.25	16.441
4,702.13	4,673.39	4,664.86	4,644.35	11.08	9.89	111.40	417.70	173.58	333.17	312.91	20.25	16.450

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 52 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 212H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)

Rule Assigned:

Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
4,800.00	4,770.58	4,761.89	4,740.43	11.28	10.06	111.60	427.97	182.34	345.98	325.39	20.59	16.802	
4,900.00	4,870.15	4,863.80	4,841.38	11.48	10.22	111.42	438.55	191.38	357.97	337.05	20.92	17.115	
5,000.00	4,969.93	4,969.67	4,946.56	11.67	10.41	111.11	447.71	199.19	367.57	346.33	21.25	17.300	
5,100.00	5,069.85	5,076.00	5,052.49	11.85	10.61	110.73	454.66	205.12	374.50	352.94	21.56	17.374	
5,200.00	5,169.84	5,182.65	5,158.96	11.99	10.79	110.27	459.38	209.15	378.74	356.91	21.82	17.353	
5,202.16	5,172.00	5,184.96	5,161.27	12.00	10.80	90.03	459.46	209.22	378.80	356.97	21.83	17.352	
5,300.00	5,269.84	5,289.52	5,265.78	12.08	10.97	89.67	461.84	211.25	380.71	358.65	22.06	17.258	
5,400.00	5,369.84	5,393.58	5,369.84	12.17	11.05	89.61	462.23	211.58	381.02	358.80	22.22	17.147	
5,500.00	5,469.84	5,493.58	5,469.84	12.26	11.14	89.61	462.23	211.58	381.02	358.62	22.40	17.010	
5,600.00	5,569.84	5,593.58	5,569.84	12.34	11.23	89.61	462.23	211.58	381.02	358.44	22.58	16.872	
5,700.00	5,669.84	5,693.58	5,669.84	12.43	11.33	89.61	462.23	211.58	381.02	358.25	22.76	16.737	
5,800.00	5,769.84	5,793.58	5,769.84	12.52	11.42	89.61	462.23	211.58	381.02	358.07	22.95	16.604	
5,900.00	5,869.84	5,893.58	5,869.84	12.61	11.52	89.61	462.23	211.58	381.02	357.89	23.13	16.474	
6,000.00	5,969.84	5,993.58	5,969.84	12.69	11.61	89.61	462.23	211.58	381.02	357.71	23.31	16.346	
6,100.00	6,069.84	6,093.58	6,069.84	12.78	11.70	89.61	462.23	211.58	381.02	357.53	23.49	16.220	
6,200.00	6,169.84	6,193.58	6,169.84	12.87	11.79	89.61	462.23	211.58	381.02	357.35	23.67	16.096	
6,300.00	6,269.84	6,293.58	6,269.84	12.96	11.89	89.61	462.23	211.58	381.02	357.17	23.85	15.974	
6,400.00	6,369.84	6,393.58	6,369.84	13.04	11.98	89.61	462.23	211.58	381.02	356.99	24.03	15.854	
6,500.00	6,469.84	6,493.58	6,469.84	13.13	12.07	89.61	462.23	211.58	381.02	356.81	24.21	15.736	
6,600.00	6,569.84	6,593.58	6,569.84	13.22	12.16	89.61	462.23	211.58	381.02	356.63	24.39	15.620	
6,700.00	6,669.84	6,693.58	6,669.84	13.30	12.26	89.61	462.23	211.58	381.02	356.45	24.57	15.506	
6,800.00	6,769.84	6,793.58	6,769.84	13.39	12.35	89.61	462.23	211.58	381.02	356.27	24.75	15.394	
6,900.00	6,869.84	6,893.58	6,869.84	13.48	12.44	89.61	462.23	211.58	381.02	356.09	24.93	15.283	
7,000.00	6,969.84	6,993.58	6,969.84	13.56	12.53	89.61	462.23	211.58	381.02	355.91	25.11	15.174	
7,100.00	7,069.84	7,093.58	7,069.84	13.65	12.62	89.61	462.23	211.58	381.02	355.73	25.29	15.067	
7,200.00	7,169.84	7,193.58	7,169.84	13.74	12.72	89.61	462.23	211.58	381.02	355.55	25.47	14.961	
7,300.00	7,269.84	7,293.58	7,269.84	13.82	12.81	89.61	462.23	211.58	381.02	355.37	25.65	14.857	
7,400.00	7,369.84	7,393.58	7,369.84	13.91	12.90	89.61	462.23	211.58	381.02	355.20	25.82	14.755	
7,500.00	7,469.84	7,493.58	7,469.84	14.00	12.99	89.61	462.23	211.58	381.02	355.02	26.00	14.654	
7,600.00	7,569.84	7,593.58	7,569.84	14.08	13.08	89.61	462.23	211.58	381.02	354.84	26.18	14.554	
7,700.00	7,669.84	7,693.58	7,669.84	14.17	13.17	89.61	462.23	211.58	381.02	354.66	26.36	14.456	
7,800.00	7,769.84	7,793.58	7,769.84	14.26	13.26	89.61	462.23	211.58	381.02	354.49	26.53	14.360	
7,900.00	7,869.84	7,893.58	7,869.84	14.34	13.35	89.61	462.23	211.58	381.02	354.31	26.71	14.265	
8,000.00	7,969.84	7,993.58	7,969.84	14.43	13.44	89.61	462.23	211.58	381.02	354.13	26.89	14.171	
8,100.00	8,069.84	8,093.58	8,069.84	14.51	13.53	89.61	462.23	211.58	381.02	353.95	27.06	14.078	
8,200.00	8,169.84	8,193.58	8,169.84	14.60	13.62	89.61	462.23	211.58	381.02	353.78	27.24	13.987	
8,300.00	8,269.84	8,293.58	8,269.84	14.69	13.71	89.61	462.23	211.58	381.02	353.60	27.42	13.897	
8,400.00	8,369.84	8,393.58	8,369.84	14.77	13.80	89.61	462.23	211.58	381.02	353.42	27.59	13.808	
8,500.00	8,469.84	8,493.58	8,469.84	14.86	13.89	89.61	462.23	211.58	381.02	353.25	27.77	13.721	
8,600.00	8,569.84	8,593.58	8,569.84	14.94	13.98	89.61	462.23	211.58	381.02	353.07	27.95	13.634	
8,700.00	8,669.84	8,693.58	8,669.84	15.03	14.07	89.61	462.23	211.58	381.02	352.90	28.12	13.549	
8,800.00	8,769.84	8,793.58	8,769.84	15.12	14.16	89.61	462.23	211.58	381.02	352.72	28.30	13.465	
8,900.00	8,869.84	8,893.58	8,869.84	15.20	14.25	89.61	462.23	211.58	381.02	352.55	28.47	13.382	
9,000.00	8,969.84	8,993.58	8,969.84	15.29	14.34	89.61	462.23	211.58	381.02	352.37	28.65	13.300	
9,100.00	9,069.84	9,093.58	9,069.84	15.37	14.43	89.61	462.23	211.58	381.02	352.20	28.82	13.219	
9,200.00	9,169.84	9,193.58	9,169.84	15.46	14.52	89.61	462.23	211.58	381.02	352.02	29.00	13.139	
9,300.00	9,269.84	9,293.58	9,269.84	15.54	14.61	89.61	462.23	211.58	381.02	351.85	29.17	13.060	
9,400.00	9,369.84	9,393.58	9,369.84	15.63	14.70	89.61	462.23	211.58	381.02	351.67	29.35	12.983	
9,500.00	9,469.84	9,493.58	9,469.84	15.71	14.79	89.61	462.23	211.58	381.02	351.50	29.52	12.906	
9,600.00	9,569.84	9,593.58	9,569.84	15.80	14.88	89.61	462.23	211.58	381.02	351.32	29.70	12.830	
9,700.00	9,669.84	9,693.58	9,669.84	15.89	14.97	89.61	462.23	211.58	381.02	351.15	29.87	12.755	
9,800.00	9,769.84	9,793.58	9,769.84	15.97	15.06	89.61	462.23	211.58	381.02	350.97	30.05	12.681	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 53 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 212H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)		
9,900.00	9,869.84	9,893.58	9,869.84	16.06	15.15	89.61	462.23	211.58	381.02	350.80	30.22	12.608
10,000.00	9,969.84	9,993.58	9,969.84	16.14	15.23	89.61	462.23	211.58	381.02	350.62	30.39	12.536
10,100.00	10,069.84	10,093.58	10,069.84	16.23	15.32	89.61	462.23	211.58	381.02	350.45	30.57	12.465
10,200.00	10,169.84	10,193.58	10,169.84	16.31	15.41	89.61	462.23	211.58	381.02	350.28	30.74	12.394
10,300.00	10,269.84	10,293.58	10,269.84	16.40	15.50	89.61	462.23	211.58	381.02	350.10	30.92	12.325
10,400.00	10,369.84	10,393.58	10,369.84	16.48	15.59	89.61	462.23	211.58	381.02	349.93	31.09	12.256
10,500.00	10,469.84	10,493.58	10,469.84	16.57	15.68	89.61	462.23	211.58	381.02	349.76	31.26	12.188
10,600.00	10,569.84	10,593.58	10,569.84	16.65	15.77	89.61	462.23	211.58	381.02	349.58	31.44	12.121
10,700.00	10,669.84	10,693.58	10,669.84	16.74	15.85	89.61	462.23	211.58	381.02	349.41	31.61	12.054
10,800.00	10,769.84	10,793.58	10,769.84	16.82	15.94	89.61	462.23	211.58	381.02	349.24	31.78	11.988
10,900.00	10,869.84	10,893.58	10,869.84	16.91	16.03	89.61	462.23	211.58	381.02	349.06	31.96	11.924
11,000.00	10,969.84	10,993.58	10,969.84	16.99	16.12	89.61	462.23	211.58	381.02	348.89	32.13	11.859
11,100.00	11,069.84	11,093.58	11,069.84	17.08	16.21	89.61	462.23	211.58	381.02	348.72	32.30	11.796
11,200.00	11,169.84	11,193.58	11,169.84	17.16	16.29	89.61	462.23	211.58	381.02	348.55	32.47	11.733
11,300.00	11,269.84	11,293.58	11,269.84	17.25	16.38	89.61	462.23	211.58	381.02	348.37	32.65	11.671
11,400.00	11,369.84	11,393.58	11,369.84	17.33	16.47	89.61	462.23	211.58	381.02	348.20	32.82	11.610
11,500.00	11,469.84	11,493.58	11,469.84	17.42	16.56	89.61	462.23	211.58	381.02	348.03	32.99	11.549
11,581.16	11,551.00	11,574.74	11,551.00	17.48	16.63	89.61	462.23	211.58	381.02	347.90	33.12	11.504
11,600.00	11,569.83	11,593.58	11,569.83	17.48	16.65	-89.94	462.23	211.58	381.02	347.88	33.14	11.498
11,609.42	11,579.24	11,602.99	11,579.24	17.48	16.65	-90.00	462.23	211.58	381.02	347.88	33.14	11.497
11,650.00	11,619.67	11,643.41	11,619.67	17.49	16.69	-90.51	462.23	211.58	381.03	347.88	33.15	11.494
11,700.00	11,668.99	11,692.73	11,668.99	17.51	16.73	-91.70	462.23	211.58	381.19	348.05	33.14	11.501
11,750.00	11,717.40	11,741.15	11,717.40	17.51	16.77	-93.45	462.23	211.58	381.77	348.65	33.12	11.527
11,800.00	11,764.55	11,788.30	11,764.55	17.52	16.82	-95.65	462.23	211.58	383.17	350.09	33.08	11.583
11,850.00	11,810.08	11,833.82	11,810.08	17.52	16.86	-98.16	462.23	211.58	385.91	352.87	33.04	11.681
11,900.00	11,853.63	11,877.38	11,853.63	17.52	16.89	-100.82	462.23	211.58	390.55	357.56	32.99	11.838
11,950.00	11,894.88	11,918.63	11,894.88	17.53	16.93	-103.46	462.23	211.58	397.70	364.75	32.95	12.069
12,000.00	11,933.52	11,957.26	11,933.52	17.53	16.95	-105.89	462.23	211.58	407.93	375.00	32.93	12.388
12,050.00	11,969.24	12,005.01	11,981.24	17.53	16.97	-109.02	460.95	211.59	421.30	388.38	32.92	12.797
12,100.00	12,001.78	12,060.93	12,036.76	17.53	17.00	-112.48	454.51	211.65	436.89	403.88	33.01	13.235
12,150.00	12,030.89	12,123.24	12,097.56	17.53	17.03	-116.00	440.99	211.76	454.16	420.85	33.31	13.633
12,200.00	12,056.34	12,193.93	12,164.28	17.53	17.06	-119.63	417.78	211.96	472.53	438.55	33.98	13.908
12,250.00	12,077.95	12,275.59	12,237.10	17.54	17.10	-123.36	380.99	212.28	491.23	456.08	35.15	13.976
12,300.00	12,095.55	12,371.38	12,314.83	17.55	17.15	-127.12	325.20	212.76	509.25	472.30	36.95	13.782
12,350.00	12,109.01	12,484.58	12,393.16	17.56	17.21	-130.68	243.73	213.46	525.33	485.97	39.37	13.345
12,400.00	12,118.22	12,589.18	12,449.71	17.58	17.28	-132.92	155.94	214.22	537.88	496.50	41.38	12.999
12,450.00	12,123.11	12,738.24	12,501.23	17.60	17.41	-135.13	16.63	215.42	545.22	501.32	43.90	12.419
12,476.17	12,123.94	12,848.75	12,516.68	17.61	17.57	-135.80	-92.72	216.36	546.61	501.57	45.04	12.136
12,500.00	12,124.14	12,881.47	12,516.11	17.62	17.63	-135.81	-125.43	216.64	546.65	501.50	45.15	12.107
12,600.00	12,125.02	12,981.47	12,516.98	17.69	17.87	-135.81	-225.42	217.50	546.65	501.20	45.45	12.028
12,700.00	12,125.89	13,081.47	12,517.86	17.79	18.22	-135.81	-325.41	218.36	546.65	500.82	45.83	11.928
12,800.00	12,126.76	13,181.47	12,518.73	17.95	18.68	-135.81	-425.40	219.22	546.65	500.36	46.30	11.808
12,900.00	12,127.63	13,281.47	12,519.60	18.21	19.25	-135.81	-525.40	220.08	546.65	499.81	46.84	11.670
13,000.00	12,128.50	13,381.47	12,520.48	18.61	19.93	-135.81	-625.39	220.94	546.65	499.18	47.47	11.515
13,100.00	12,129.37	13,481.47	12,521.35	19.18	20.68	-135.81	-725.38	221.81	546.66	498.48	48.18	11.347
13,200.00	12,130.24	13,581.47	12,522.22	19.87	21.51	-135.81	-825.37	222.67	546.66	497.70	48.95	11.167
13,300.00	12,131.11	13,681.47	12,523.10	20.66	22.40	-135.81	-925.37	223.53	546.66	496.86	49.80	10.977
13,400.00	12,131.99	13,781.47	12,523.97	21.53	23.33	-135.81	-1,025.36	224.39	546.66	495.95	50.72	10.779
13,500.00	12,132.86	13,881.47	12,524.84	22.45	24.31	-135.81	-1,125.35	225.25	546.66	494.97	51.69	10.576
13,600.00	12,133.73	13,981.47	12,525.72	23.43	25.34	-135.81	-1,225.34	226.11	546.66	493.94	52.73	10.368
13,700.00	12,134.60	14,081.47	12,526.59	24.44	26.39	-135.81	-1,325.34	226.97	546.67	492.85	53.82	10.158
13,800.00	12,135.47	14,181.47	12,527.46	25.50	27.47	-135.81	-1,425.33	227.83	546.67	491.71	54.96	9.947

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 54 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 212H - OH - Plan 1												Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)												Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Minimum Separation (usft)	Warning	
							+N/-S (usft)	+E/-W (usft)	Between Ellipses (usft)	Separation Factor			
19,100.00	12,181.65	19,481.47	12,573.75	93.96	96.08	-135.82	-6,724.93	273.46	546.75	401.00	145.75	3.751	
19,200.00	12,182.52	19,581.47	12,574.63	95.31	97.43	-135.82	-6,824.92	274.33	546.75	399.08	147.67	3.703	
19,300.00	12,183.39	19,681.47	12,575.50	96.66	98.78	-135.82	-6,924.92	275.19	546.75	397.16	149.59	3.655	
19,400.00	12,184.26	19,781.47	12,576.37	98.01	100.13	-135.82	-7,024.91	276.05	546.75	395.24	151.52	3.609	
19,500.00	12,185.13	19,881.47	12,577.25	99.36	101.48	-135.82	-7,124.90	276.91	546.76	393.31	153.44	3.563	
19,600.00	12,186.00	19,981.47	12,578.12	100.72	102.83	-135.82	-7,224.89	277.77	546.76	391.38	155.37	3.519	
19,700.00	12,186.87	20,081.47	12,578.99	102.07	104.18	-135.82	-7,324.89	278.63	546.76	389.46	157.30	3.476	
19,800.00	12,187.75	20,181.47	12,579.87	103.42	105.54	-135.82	-7,424.88	279.49	546.76	387.52	159.24	3.434	
19,900.00	12,188.62	20,281.47	12,580.74	104.78	106.89	-135.82	-7,524.87	280.35	546.76	385.59	161.17	3.392	
20,000.00	12,189.49	20,381.47	12,581.61	106.13	108.25	-135.82	-7,624.86	281.21	546.76	383.65	163.11	3.352	
20,100.00	12,190.36	20,481.47	12,582.49	107.49	109.60	-135.82	-7,724.86	282.07	546.76	381.72	165.05	3.313	
20,200.00	12,191.23	20,581.47	12,583.36	108.84	110.96	-135.82	-7,824.85	282.94	546.77	379.78	166.99	3.274	
20,300.00	12,192.10	20,681.47	12,584.23	110.20	112.31	-135.82	-7,924.84	283.80	546.77	377.84	168.93	3.237	
20,400.00	12,192.97	20,781.47	12,585.11	111.55	113.67	-135.82	-8,024.83	284.66	546.77	375.89	170.88	3.200	
20,500.00	12,193.85	20,881.47	12,585.98	112.91	115.02	-135.82	-8,124.83	285.52	546.77	373.95	172.82	3.164	
20,600.00	12,194.72	20,981.47	12,586.85	114.27	116.38	-135.82	-8,224.82	286.38	546.77	372.00	174.77	3.129	
20,700.00	12,195.59	21,081.47	12,587.73	115.62	117.74	-135.83	-8,324.81	287.24	546.77	370.05	176.72	3.094	
20,800.00	12,196.46	21,181.47	12,588.60	116.98	119.09	-135.83	-8,424.80	288.10	546.78	368.11	178.67	3.060	
20,900.00	12,197.33	21,281.47	12,589.47	118.34	120.45	-135.83	-8,524.80	288.96	546.78	366.15	180.62	3.027	
21,000.00	12,198.20	21,381.47	12,590.35	119.70	121.81	-135.83	-8,624.79	289.82	546.78	364.20	182.58	2.995	
21,100.00	12,199.07	21,481.47	12,591.22	121.05	123.16	-135.83	-8,724.78	290.68	546.78	362.25	184.53	2.963	
21,200.00	12,199.94	21,581.47	12,592.09	122.41	124.52	-135.83	-8,824.77	291.55	546.78	360.29	186.49	2.932	
21,300.00	12,200.82	21,681.47	12,592.97	123.77	125.88	-135.83	-8,924.77	292.41	546.78	358.34	188.44	2.902	
21,400.00	12,201.69	21,781.47	12,593.84	125.13	127.24	-135.83	-9,024.76	293.27	546.78	356.38	190.40	2.872	
21,500.00	12,202.56	21,881.47	12,594.71	126.49	128.60	-135.83	-9,124.75	294.13	546.79	354.42	192.36	2.842	
21,600.00	12,203.43	21,981.47	12,595.59	127.85	129.96	-135.83	-9,224.74	294.99	546.79	352.46	194.32	2.814	
21,700.00	12,204.30	22,081.47	12,596.46	129.21	131.32	-135.83	-9,324.74	295.85	546.79	350.50	196.28	2.786	
21,800.00	12,205.17	22,181.47	12,597.33	130.57	132.68	-135.83	-9,424.73	296.71	546.79	348.54	198.25	2.758	
21,900.00	12,206.04	22,281.47	12,598.21	131.93	134.04	-135.83	-9,524.72	297.57	546.79	346.58	200.21	2.731	
22,000.00	12,206.91	22,381.47	12,599.08	133.29	135.39	-135.83	-9,624.71	298.43	546.79	344.62	202.18	2.705	
22,100.00	12,207.79	22,481.47	12,599.96	134.65	136.75	-135.83	-9,724.71	299.29	546.80	342.65	204.14	2.678	
22,200.00	12,208.66	22,581.47	12,600.83	136.01	138.12	-135.83	-9,824.70	300.15	546.80	340.69	206.11	2.653	
22,300.00	12,209.53	22,681.47	12,601.70	137.37	139.48	-135.83	-9,924.69	301.02	546.80	338.72	208.08	2.628	
22,400.00	12,210.40	22,781.47	12,602.58	138.73	140.84	-135.83	-10,024.68	301.88	546.80	336.75	210.05	2.603	
22,411.61	12,210.50	22,793.08	12,602.68	138.89	140.99	-135.83	-10,036.29	301.98	546.80	336.53	210.27	2.600	SF

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 56 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 213H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
1,550.47	1,548.70	2,184.26	2,164.44	4.99	6.33	91.17	883.60	2,170.13	2,421.12	2,410.29	10.83	223.577	
1,600.00	1,597.81	2,231.32	2,209.90	5.05	6.45	91.38	876.95	2,159.93	2,408.60	2,397.61	10.99	219.174	
1,700.00	1,696.95	2,326.33	2,301.67	5.25	6.71	91.83	863.52	2,139.32	2,383.43	2,372.04	11.38	209.400	
1,800.00	1,796.09	2,421.35	2,393.45	5.44	6.99	92.29	850.10	2,118.72	2,358.40	2,346.62	11.78	200.186	
1,900.00	1,895.24	2,516.36	2,485.23	5.64	7.27	92.75	836.67	2,098.11	2,333.52	2,321.34	12.18	191.553	
2,000.00	1,994.38	2,611.38	2,577.00	5.83	7.57	93.23	823.24	2,077.51	2,308.80	2,296.21	12.59	183.452	
2,100.00	2,093.53	2,706.39	2,668.78	6.03	7.86	93.71	809.82	2,056.91	2,284.23	2,271.24	12.99	175.838	
2,200.00	2,192.67	2,801.40	2,760.55	6.22	8.17	94.21	796.39	2,036.30	2,259.83	2,246.43	13.40	168.671	
2,300.00	2,291.82	2,896.42	2,852.33	6.42	8.47	94.71	782.96	2,015.70	2,235.59	2,221.78	13.81	161.913	
2,400.00	2,390.96	2,991.43	2,944.11	6.61	8.78	95.23	769.54	1,995.09	2,211.53	2,197.31	14.22	155.533	
2,500.00	2,490.11	3,086.45	3,035.88	6.81	9.09	95.75	756.11	1,974.49	2,187.65	2,173.02	14.63	149.502	
2,600.00	2,589.25	3,181.46	3,127.66	7.00	9.40	96.29	742.68	1,953.89	2,163.95	2,148.90	15.05	143.792	
2,700.00	2,688.39	3,276.47	3,219.43	7.20	9.72	96.84	729.26	1,933.28	2,140.45	2,124.98	15.47	138.380	
2,800.00	2,787.54	3,371.49	3,311.21	7.39	10.04	97.40	715.83	1,912.68	2,117.14	2,101.25	15.89	133.245	
2,900.00	2,886.68	3,466.50	3,402.99	7.59	10.36	97.97	702.40	1,892.07	2,094.04	2,077.73	16.31	128.368	
3,000.00	2,985.83	3,561.52	3,494.76	7.78	10.68	98.55	688.98	1,871.47	2,071.15	2,054.42	16.74	123.729	
3,100.00	3,084.97	3,656.53	3,586.54	7.98	11.00	99.15	675.55	1,850.87	2,048.49	2,031.32	17.17	119.314	
3,200.00	3,184.12	3,751.54	3,678.32	8.17	11.33	99.76	662.12	1,830.26	2,026.04	2,008.44	17.60	115.108	
3,300.00	3,283.26	3,846.56	3,770.09	8.36	11.65	100.38	648.70	1,809.66	2,003.83	1,985.80	18.04	111.097	
3,400.00	3,382.40	3,941.57	3,861.87	8.56	11.98	101.02	635.27	1,789.05	1,981.87	1,963.39	18.48	107.269	
3,500.00	3,481.55	4,036.59	3,953.64	8.75	12.30	101.67	621.84	1,768.45	1,960.15	1,941.23	18.92	103.613	
3,600.00	3,580.69	4,131.60	4,045.42	8.95	12.63	102.33	608.42	1,747.85	1,938.69	1,919.32	19.36	100.119	
3,700.00	3,679.84	4,226.61	4,137.20	9.14	12.96	103.00	594.99	1,727.24	1,917.50	1,897.68	19.81	96.778	
3,800.00	3,778.98	4,321.63	4,228.97	9.33	13.29	103.70	581.56	1,706.64	1,896.58	1,876.31	20.27	93.580	
3,900.00	3,878.13	4,416.64	4,320.75	9.53	13.62	104.40	568.13	1,686.03	1,875.95	1,855.22	20.72	90.518	
4,000.00	3,977.27	4,511.66	4,412.52	9.72	13.95	105.12	554.71	1,665.43	1,855.61	1,834.42	21.19	87.586	
4,100.00	4,076.42	4,600.00	4,497.86	9.91	14.26	105.80	542.22	1,646.27	1,835.59	1,813.95	21.64	84.830	
4,200.00	4,175.56	4,670.96	4,566.58	10.11	14.50	106.35	532.56	1,631.44	1,816.73	1,794.66	22.07	82.320	
4,300.00	4,274.70	4,738.40	4,632.17	10.30	14.72	106.86	524.02	1,618.34	1,799.68	1,777.19	22.49	80.030	
4,400.00	4,373.85	4,800.00	4,692.33	10.49	14.91	107.32	516.78	1,607.23	1,784.44	1,761.55	22.89	77.966	
4,500.00	4,472.99	4,875.11	4,765.95	10.69	15.12	107.86	508.66	1,594.77	1,770.96	1,747.66	23.30	75.995	
4,600.00	4,572.14	4,944.31	4,834.03	10.88	15.30	108.34	501.89	1,584.38	1,759.29	1,735.59	23.70	74.236	
4,700.00	4,671.28	5,000.00	4,888.97	11.08	15.44	108.72	496.92	1,576.76	1,749.48	1,725.42	24.06	72.719	
4,702.13	4,673.39	5,015.52	4,904.30	11.08	15.47	108.82	495.62	1,574.76	1,749.21	1,725.11	24.10	72.594	
4,800.00	4,770.58	5,084.35	4,972.43	11.28	15.63	109.13	490.24	1,566.50	1,740.86	1,716.41	24.45	71.192	
4,900.00	4,870.15	5,155.34	5,042.86	11.48	15.77	109.37	485.40	1,559.07	1,733.19	1,708.41	24.79	69.922	
5,000.00	4,969.93	5,226.89	5,114.00	11.67	15.90	109.56	481.24	1,552.69	1,726.33	1,701.24	25.09	68.808	
5,100.00	5,069.85	5,300.00	5,186.83	11.85	16.02	109.68	477.74	1,547.33	1,720.24	1,694.88	25.36	67.835	
5,200.00	5,169.84	5,371.17	5,257.83	11.99	16.12	109.72	475.07	1,543.22	1,714.88	1,689.30	25.58	67.041	
5,202.16	5,172.00	5,372.73	5,259.39	12.00	16.12	89.49	475.02	1,543.15	1,714.77	1,689.19	25.58	67.024	
5,300.00	5,269.84	5,443.65	5,330.22	12.08	16.21	89.55	473.09	1,540.19	1,710.67	1,684.90	25.77	66.383	
5,400.00	5,369.84	5,516.25	5,402.78	12.17	16.28	89.59	471.86	1,538.30	1,708.06	1,682.12	25.94	65.849	
5,500.00	5,469.84	5,598.47	5,485.00	12.26	16.34	89.61	471.38	1,537.56	1,707.08	1,681.00	26.08	65.453	
5,538.39	5,508.22	5,623.70	5,510.22	12.29	16.35	89.61	471.38	1,537.56	1,707.03	1,680.92	26.11	65.376	
5,600.00	5,569.84	5,685.31	5,571.84	12.34	16.37	89.61	471.38	1,537.56	1,707.03	1,680.84	26.19	65.184	
5,700.00	5,669.84	5,785.31	5,671.84	12.43	16.40	89.61	471.38	1,537.56	1,707.03	1,680.72	26.31	64.874	
5,800.00	5,769.84	5,885.31	5,771.84	12.52	16.44	89.61	471.38	1,537.56	1,707.03	1,680.59	26.44	64.567	
5,900.00	5,869.84	5,985.31	5,871.84	12.61	16.48	89.61	471.38	1,537.56	1,707.03	1,680.47	26.56	64.262	
6,000.00	5,969.84	6,085.31	5,971.84	12.69	16.52	89.61	471.38	1,537.56	1,707.03	1,680.34	26.69	63.959	
6,100.00	6,069.84	6,185.31	6,071.84	12.78	16.55	89.61	471.38	1,537.56	1,707.03	1,680.22	26.82	63.659	
6,200.00	6,169.84	6,285.31	6,171.84	12.87	16.59	89.61	471.38	1,537.56	1,707.03	1,680.09	26.94	63.360	
6,300.00	6,269.84	6,385.31	6,271.84	12.96	16.63	89.61	471.38	1,537.56	1,707.03	1,679.96	27.07	63.064	

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 213H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)				Offset		Rule Assigned:			Offset Well Error:		0.50 usft			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
6,400.00	6,369.84	6,485.31	6,371.84	13.04	16.67	89.61	471.38	1,537.56	1,707.03	1,679.84	27.19	62.770		
6,500.00	6,469.84	6,585.31	6,471.84	13.13	16.71	89.61	471.38	1,537.56	1,707.03	1,679.71	27.32	62.478		
6,600.00	6,569.84	6,685.31	6,571.84	13.22	16.75	89.61	471.38	1,537.56	1,707.03	1,679.58	27.45	62.188		
6,700.00	6,669.84	6,785.31	6,671.84	13.30	16.79	89.61	471.38	1,537.56	1,707.03	1,679.45	27.58	61.901		
6,800.00	6,769.84	6,885.31	6,771.84	13.39	16.83	89.61	471.38	1,537.56	1,707.03	1,679.33	27.70	61.615		
6,900.00	6,869.84	6,985.31	6,871.84	13.48	16.87	89.61	471.38	1,537.56	1,707.03	1,679.20	27.83	61.331		
7,000.00	6,969.84	7,085.31	6,971.84	13.56	16.91	89.61	471.38	1,537.56	1,707.03	1,679.07	27.96	61.050		
7,100.00	7,069.84	7,185.31	7,071.84	13.65	16.95	89.61	471.38	1,537.56	1,707.03	1,678.94	28.09	60.770		
7,200.00	7,169.84	7,285.31	7,171.84	13.74	16.99	89.61	471.38	1,537.56	1,707.03	1,678.81	28.22	60.493		
7,300.00	7,269.84	7,385.31	7,271.84	13.82	17.03	89.61	471.38	1,537.56	1,707.03	1,678.68	28.35	60.217		
7,400.00	7,369.84	7,485.31	7,371.84	13.91	17.07	89.61	471.38	1,537.56	1,707.03	1,678.55	28.48	59.944		
7,500.00	7,469.84	7,585.31	7,471.84	14.00	17.11	89.61	471.38	1,537.56	1,707.03	1,678.42	28.61	59.672		
7,600.00	7,569.84	7,685.31	7,571.84	14.08	17.16	89.61	471.38	1,537.56	1,707.03	1,678.29	28.74	59.403		
7,700.00	7,669.84	7,785.31	7,671.84	14.17	17.20	89.61	471.38	1,537.56	1,707.03	1,678.16	28.87	59.135		
7,800.00	7,769.84	7,885.31	7,771.84	14.26	17.24	89.61	471.38	1,537.56	1,707.03	1,678.03	29.00	58.869		
7,900.00	7,869.84	7,985.31	7,871.84	14.34	17.28	89.61	471.38	1,537.56	1,707.03	1,677.90	29.13	58.605		
8,000.00	7,969.84	8,085.31	7,971.84	14.43	17.33	89.61	471.38	1,537.56	1,707.03	1,677.77	29.26	58.343		
8,100.00	8,069.84	8,185.31	8,071.84	14.51	17.37	89.61	471.38	1,537.56	1,707.03	1,677.64	29.39	58.083		
8,200.00	8,169.84	8,285.31	8,171.84	14.60	17.42	89.61	471.38	1,537.56	1,707.03	1,677.51	29.52	57.824		
8,300.00	8,269.84	8,385.31	8,271.84	14.69	17.46	89.61	471.38	1,537.56	1,707.03	1,677.38	29.65	57.568		
8,400.00	8,369.84	8,485.31	8,371.84	14.77	17.50	89.61	471.38	1,537.56	1,707.03	1,677.25	29.78	57.313		
8,500.00	8,469.84	8,585.31	8,471.84	14.86	17.55	89.61	471.38	1,537.56	1,707.03	1,677.11	29.92	57.060		
8,600.00	8,569.84	8,685.31	8,571.84	14.94	17.59	89.61	471.38	1,537.56	1,707.03	1,676.98	30.05	56.809		
8,700.00	8,669.84	8,785.31	8,671.84	15.03	17.64	89.61	471.38	1,537.56	1,707.03	1,676.85	30.18	56.560		
8,800.00	8,769.84	8,885.31	8,771.84	15.12	17.69	89.61	471.38	1,537.56	1,707.03	1,676.72	30.31	56.312		
8,900.00	8,869.84	8,985.31	8,871.84	15.20	17.73	89.61	471.38	1,537.56	1,707.03	1,676.58	30.45	56.066		
9,000.00	8,969.84	9,085.31	8,971.84	15.29	17.78	89.61	471.38	1,537.56	1,707.03	1,676.45	30.58	55.822		
9,100.00	9,069.84	9,185.31	9,071.84	15.37	17.82	89.61	471.38	1,537.56	1,707.03	1,676.32	30.71	55.580		
9,200.00	9,169.84	9,285.31	9,171.84	15.46	17.87	89.61	471.38	1,537.56	1,707.03	1,676.18	30.85	55.339		
9,300.00	9,269.84	9,385.31	9,271.84	15.54	17.92	89.61	471.38	1,537.56	1,707.03	1,676.05	30.98	55.100		
9,400.00	9,369.84	9,485.31	9,371.84	15.63	17.96	89.61	471.38	1,537.56	1,707.03	1,675.92	31.11	54.862		
9,500.00	9,469.84	9,585.31	9,471.84	15.71	18.01	89.61	471.38	1,537.56	1,707.03	1,675.78	31.25	54.627		
9,600.00	9,569.84	9,685.31	9,571.84	15.80	18.06	89.61	471.38	1,537.56	1,707.03	1,675.65	31.38	54.392		
9,700.00	9,669.84	9,785.31	9,671.84	15.89	18.11	89.61	471.38	1,537.56	1,707.03	1,675.51	31.52	54.160		
9,800.00	9,769.84	9,885.31	9,771.84	15.97	18.16	89.61	471.38	1,537.56	1,707.03	1,675.38	31.65	53.929		
9,900.00	9,869.84	9,985.31	9,871.84	16.06	18.20	89.61	471.38	1,537.56	1,707.03	1,675.24	31.79	53.700		
10,000.00	9,969.84	10,085.31	9,971.84	16.14	18.25	89.61	471.38	1,537.56	1,707.03	1,675.11	31.92	53.472		
10,100.00	10,069.84	10,185.31	10,071.84	16.23	18.30	89.61	471.38	1,537.56	1,707.03	1,674.97	32.06	53.246		
10,200.00	10,169.84	10,285.31	10,171.84	16.31	18.35	89.61	471.38	1,537.56	1,707.03	1,674.84	32.20	53.021		
10,300.00	10,269.84	10,385.31	10,271.84	16.40	18.40	89.61	471.38	1,537.56	1,707.03	1,674.70	32.33	52.798		
10,400.00	10,369.84	10,485.31	10,371.84	16.48	18.45	89.61	471.38	1,537.56	1,707.03	1,674.56	32.47	52.577		
10,500.00	10,469.84	10,585.31	10,471.84	16.57	18.50	89.61	471.38	1,537.56	1,707.03	1,674.43	32.60	52.357		
10,600.00	10,569.84	10,685.31	10,571.84	16.65	18.55	89.61	471.38	1,537.56	1,707.03	1,674.29	32.74	52.138		
10,700.00	10,669.84	10,785.31	10,671.84	16.74	18.60	89.61	471.38	1,537.56	1,707.03	1,674.15	32.88	51.921		
10,800.00	10,769.84	10,885.31	10,771.84	16.82	18.65	89.61	471.38	1,537.56	1,707.03	1,674.02	33.01	51.706		
10,900.00	10,869.84	10,985.31	10,871.84	16.91	18.70	89.61	471.38	1,537.56	1,707.03	1,673.88	33.15	51.492		
11,000.00	10,969.84	11,085.31	10,971.84	16.99	18.75	89.61	471.38	1,537.56	1,707.03	1,673.74	33.29	51.280		
11,100.00	11,069.84	11,185.31	11,071.84	17.08	18.80	89.61	471.38	1,537.56	1,707.03	1,673.60	33.43	51.068		
11,200.00	11,169.84	11,285.31	11,171.84	17.16	18.86	89.61	471.38	1,537.56	1,707.03	1,673.47	33.56	50.859		
11,300.00	11,269.84	11,385.31	11,271.84	17.25	18.91	89.61	471.38	1,537.56	1,707.03	1,673.33	33.70	50.651		
11,400.00	11,369.84	11,485.31	11,371.84	17.33	18.96	89.61	471.38	1,537.56	1,707.03	1,673.19	33.84	50.444		
11,500.00	11,469.84	11,585.31	11,471.84	17.42	19.01	89.61	471.38	1,537.56	1,707.03	1,673.05	33.98	50.238		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 58 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 213H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned: Distance Between Centres (usft)		Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)		Ellipses (usft)				
20,800.00	12,196.46	21,209.91	12,499.71	116.98	130.27	-99.99	-8,414.54	1,617.49	1,736.77	1,492.65	244.13	7.114		
20,900.00	12,197.33	21,309.91	12,500.24	118.34	131.62	-99.98	-8,514.53	1,618.39	1,736.75	1,489.94	246.81	7.037		
21,000.00	12,198.20	21,409.91	12,500.76	119.70	132.98	-99.97	-8,614.53	1,619.29	1,736.73	1,487.23	249.50	6.961		
21,100.00	12,199.07	21,509.91	12,501.29	121.05	134.34	-99.95	-8,714.52	1,620.19	1,736.71	1,484.52	252.19	6.887		
21,200.00	12,199.94	21,609.91	12,501.81	122.41	135.69	-99.94	-8,814.52	1,621.08	1,736.69	1,481.81	254.87	6.814		
21,300.00	12,200.82	21,709.91	12,502.34	123.77	137.05	-99.93	-8,914.51	1,621.98	1,736.66	1,479.10	257.56	6.743		
21,400.00	12,201.69	21,809.91	12,502.87	125.13	138.41	-99.92	-9,014.50	1,622.88	1,736.64	1,476.39	260.25	6.673		
21,500.00	12,202.56	21,909.91	12,503.39	126.49	139.76	-99.91	-9,114.50	1,623.78	1,736.62	1,473.68	262.94	6.605		
21,600.00	12,203.43	22,009.91	12,503.92	127.85	141.12	-99.90	-9,214.49	1,624.68	1,736.60	1,470.97	265.63	6.538		
21,700.00	12,204.30	22,109.90	12,504.45	129.21	142.48	-99.89	-9,314.49	1,625.58	1,736.58	1,468.26	268.32	6.472		
21,800.00	12,205.17	22,209.90	12,504.97	130.57	143.84	-99.87	-9,414.48	1,626.48	1,736.56	1,465.55	271.01	6.408		
21,900.00	12,206.04	22,309.90	12,505.50	131.93	145.20	-99.86	-9,514.47	1,627.38	1,736.54	1,462.83	273.70	6.345		
22,000.00	12,206.91	22,409.90	12,506.02	133.29	146.55	-99.85	-9,614.47	1,628.28	1,736.51	1,460.12	276.39	6.283		
22,100.00	12,207.79	22,509.90	12,506.55	134.65	147.91	-99.84	-9,714.46	1,629.18	1,736.49	1,457.41	279.09	6.222		
22,200.00	12,208.66	22,609.90	12,507.08	136.01	149.27	-99.83	-9,814.45	1,630.08	1,736.47	1,454.69	281.78	6.162		
22,300.00	12,209.53	22,709.90	12,507.60	137.37	150.63	-99.82	-9,914.45	1,630.98	1,736.45	1,451.98	284.47	6.104		
22,400.00	12,210.40	22,809.90	12,508.13	138.73	151.98	-99.81	-10,014.44	1,631.88	1,736.43	1,449.27	287.16	6.047		
22,411.61	12,210.50	22,821.51	12,508.19	138.89	152.13	-99.80	-10,026.05	1,631.98	1,736.43	1,448.98	287.45	6.041	ES, SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 61 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 215H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:					Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre			Distance		Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)			
0.00	0.00	0.00	0.00	0.50	0.50	-45.00	25.00	-25.00	35.36					
100.00	100.00	100.00	100.00	0.98	0.98	-45.00	25.00	-25.00	35.36	33.39	1.96	18.018	CC, ES	
200.00	200.00	200.00	200.00	1.56	1.56	-45.00	25.00	-25.00	35.36	32.23	3.12	11.324		
300.00	300.00	300.00	300.00	1.98	1.98	-45.00	25.00	-25.00	35.36	31.39	3.96	8.923		
400.00	400.00	399.06	399.05	2.33	2.41	-44.85	25.97	-25.84	36.65	31.91	4.74	7.735		
500.00	500.00	497.99	497.90	2.63	2.78	-44.45	28.89	-28.34	40.53	35.12	5.41	7.491		
600.00	600.00	596.66	596.36	2.91	3.11	-43.94	33.73	-32.51	46.99	40.97	6.01	7.813		
700.00	700.00	695.83	695.17	3.16	3.26	-43.44	40.15	-38.03	55.51	49.11	6.41	8.664		
800.00	800.00	795.45	794.41	3.40	3.50	-43.07	46.73	-43.69	64.22	57.33	6.89	9.320		
900.00	899.99	895.16	893.74	3.68	3.74	-22.91	53.32	-49.35	71.72	64.32	7.40	9.691		
1,000.00	999.91	995.02	993.22	3.94	3.98	-23.74	59.92	-55.03	76.83	68.94	7.89	9.739		
1,100.00	1,099.77	1,094.93	1,092.75	4.15	4.21	-24.88	66.53	-60.71	80.77	72.45	8.32	9.707		
1,200.00	1,199.63	1,194.84	1,192.28	4.35	4.44	-25.91	73.13	-66.38	84.73	75.98	8.75	9.686		
1,250.43	1,250.00	1,244.29	1,241.52	4.40	4.56	-26.37	76.57	-69.34	86.97	78.06	8.92	9.754		
1,300.00	1,299.48	1,292.67	1,289.64	4.45	4.69	-26.83	80.40	-72.63	89.51	80.43	9.08	9.854		
1,400.00	1,399.17	1,390.18	1,386.40	4.69	4.94	-28.07	89.51	-80.47	94.82	85.28	9.55	9.932		
1,500.00	1,498.62	1,488.85	1,484.03	4.93	5.09	-29.71	100.37	-89.80	100.06	90.16	9.91	10.101		
1,550.47	1,548.70	1,539.24	1,533.87	4.99	5.19	-30.76	106.01	-94.66	102.02	91.97	10.06	10.143		
1,600.00	1,597.81	1,588.71	1,582.79	5.05	5.30	-31.86	111.56	-99.43	103.70	93.49	10.21	10.154		
1,700.00	1,696.95	1,688.57	1,681.55	5.25	5.52	-33.97	122.75	-109.06	107.21	96.60	10.61	10.101		
1,800.00	1,796.09	1,788.44	1,780.32	5.44	5.73	-35.95	133.95	-118.68	110.85	99.84	11.01	10.068		
1,900.00	1,895.24	1,888.30	1,879.08	5.64	5.94	-37.80	145.14	-128.31	114.61	103.21	11.40	10.050		
2,000.00	1,994.38	1,988.16	1,977.85	5.83	6.16	-39.53	156.34	-137.94	118.49	106.69	11.80	10.044		
2,100.00	2,093.53	2,088.02	2,076.62	6.03	6.37	-41.15	167.53	-147.56	122.46	110.27	12.19	10.049		
2,200.00	2,192.67	2,187.89	2,175.38	6.22	6.58	-42.66	178.73	-157.19	126.53	113.95	12.58	10.061		
2,300.00	2,291.82	2,287.75	2,274.15	6.42	6.79	-44.08	189.92	-166.82	130.68	117.72	12.96	10.080		
2,400.00	2,390.96	2,387.61	2,372.91	6.61	7.00	-45.42	201.12	-176.45	134.91	121.55	13.35	10.104		
2,500.00	2,490.11	2,487.48	2,471.68	6.81	7.20	-46.67	212.31	-186.07	139.20	125.46	13.74	10.133		
2,600.00	2,589.25	2,587.34	2,570.44	7.00	7.41	-47.84	223.51	-195.70	143.56	129.43	14.12	10.164		
2,700.00	2,688.39	2,687.20	2,669.21	7.20	7.62	-48.95	234.70	-205.33	147.97	133.46	14.51	10.199		
2,800.00	2,787.54	2,787.07	2,767.97	7.39	7.83	-49.99	245.90	-214.95	152.43	137.54	14.89	10.235		
2,900.00	2,886.68	2,886.93	2,866.74	7.59	8.03	-50.97	257.09	-224.58	156.95	141.67	15.28	10.273		
3,000.00	2,985.83	2,986.79	2,965.50	7.78	8.24	-51.90	268.29	-234.21	161.50	145.84	15.66	10.311		
3,100.00	3,084.97	3,086.65	3,064.27	7.98	8.45	-52.78	279.48	-243.83	166.10	150.05	16.05	10.351		
3,200.00	3,184.12	3,186.52	3,163.04	8.17	8.65	-53.61	290.67	-253.46	170.73	154.30	16.43	10.391		
3,300.00	3,283.26	3,286.38	3,261.80	8.36	8.86	-54.39	301.87	-263.09	175.40	158.58	16.81	10.432		
3,400.00	3,382.40	3,386.24	3,360.57	8.56	9.06	-55.14	313.06	-272.71	180.10	162.90	17.20	10.472		
3,500.00	3,481.55	3,486.11	3,459.33	8.75	9.27	-55.84	324.26	-282.34	184.82	167.24	17.58	10.512		
3,600.00	3,580.69	3,585.97	3,558.10	8.95	9.47	-56.51	335.45	-291.97	189.58	171.61	17.96	10.553		
3,700.00	3,679.84	3,685.83	3,656.86	9.14	9.68	-57.15	346.65	-301.59	194.35	176.01	18.35	10.593		
3,800.00	3,778.98	3,785.70	3,755.63	9.33	9.89	-57.76	357.84	-311.22	199.16	180.42	18.73	10.632		
3,900.00	3,878.13	3,885.56	3,854.39	9.53	10.09	-58.34	369.04	-320.85	203.98	184.86	19.11	10.671		
4,000.00	3,977.27	3,985.42	3,953.16	9.72	10.30	-58.89	380.23	-330.48	208.82	189.32	19.50	10.710		
4,100.00	4,076.42	4,085.28	4,051.92	9.91	10.50	-59.41	391.43	-340.10	213.68	193.80	19.88	10.748		
4,200.00	4,175.56	4,185.15	4,150.69	10.11	10.71	-59.92	402.62	-349.73	218.56	198.29	20.26	10.785		
4,300.00	4,274.70	4,285.01	4,249.46	10.30	10.91	-60.40	413.82	-359.36	223.45	202.80	20.65	10.822		
4,400.00	4,373.85	4,384.87	4,348.22	10.49	11.11	-60.86	425.01	-368.98	228.36	207.33	21.03	10.860		
4,500.00	4,472.99	4,489.00	4,451.36	10.69	11.33	-61.50	435.83	-378.29	232.47	211.04	21.43	10.850		
4,600.00	4,572.14	4,593.66	4,555.39	10.88	11.55	-62.59	444.57	-385.81	234.58	212.78	21.81	10.758		
4,700.00	4,671.28	4,698.18	4,659.54	11.08	11.76	-64.13	451.14	-391.45	234.79	212.63	22.16	10.597		
4,702.13	4,673.39	4,700.40	4,661.76	11.08	11.76	-64.17	451.26	-391.55	234.78	212.61	22.16	10.592		
4,800.00	4,770.58	4,802.50	4,763.69	11.28	11.95	-65.86	455.54	-395.24	233.75	211.28	22.47	10.401		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 62 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 215H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:						Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)	
4,900.00	4,870.15	4,906.67	4,867.82	11.48	12.12	-67.48	457.78	-397.16	232.06	209.32	22.74	10.203		
5,000.00	4,969.93	5,008.78	4,969.93	11.67	12.20	-68.93	458.09	-397.43	229.88	206.95	22.92	10.028		
5,100.00	5,069.85	5,108.70	5,069.85	11.85	12.28	-69.84	458.09	-397.43	228.47	205.36	23.12	9.883		
5,200.00	5,169.84	5,208.69	5,169.84	11.99	12.36	-70.15	458.09	-397.43	228.01	204.71	23.30	9.787		
5,202.16	5,172.00	5,210.85	5,172.00	12.00	12.36	-90.39	458.09	-397.43	228.01	204.70	23.30	9.785		
5,300.00	5,269.84	5,308.69	5,269.84	12.08	12.44	-90.39	458.09	-397.43	228.01	204.54	23.46	9.717		
5,400.00	5,369.84	5,408.69	5,369.84	12.17	12.52	-90.39	458.09	-397.43	228.01	204.37	23.63	9.647		
5,500.00	5,469.84	5,508.69	5,469.84	12.26	12.61	-90.39	458.09	-397.43	228.01	204.20	23.80	9.579		
5,600.00	5,569.84	5,608.69	5,569.84	12.34	12.69	-90.39	458.09	-397.43	228.01	204.03	23.97	9.511		
5,700.00	5,669.84	5,708.69	5,669.84	12.43	12.77	-90.39	458.09	-397.43	228.01	203.86	24.14	9.444		
5,800.00	5,769.84	5,808.69	5,769.84	12.52	12.85	-90.39	458.09	-397.43	228.01	203.69	24.31	9.379		
5,900.00	5,869.84	5,908.69	5,869.84	12.61	12.93	-90.39	458.09	-397.43	228.01	203.53	24.48	9.314		
6,000.00	5,969.84	6,008.69	5,969.84	12.69	13.01	-90.39	458.09	-397.43	228.01	203.36	24.65	9.250		
6,100.00	6,069.84	6,108.69	6,069.84	12.78	13.10	-90.39	458.09	-397.43	228.01	203.19	24.82	9.187		
6,200.00	6,169.84	6,208.69	6,169.84	12.87	13.18	-90.39	458.09	-397.43	228.01	203.02	24.99	9.125		
6,300.00	6,269.84	6,308.69	6,269.84	12.96	13.26	-90.39	458.09	-397.43	228.01	202.85	25.15	9.064		
6,400.00	6,369.84	6,408.69	6,369.84	13.04	13.34	-90.39	458.09	-397.43	228.01	202.68	25.32	9.004		
6,500.00	6,469.84	6,508.69	6,469.84	13.13	13.42	-90.39	458.09	-397.43	228.01	202.51	25.49	8.944		
6,600.00	6,569.84	6,608.69	6,569.84	13.22	13.51	-90.39	458.09	-397.43	228.01	202.35	25.66	8.886		
6,700.00	6,669.84	6,708.69	6,669.84	13.30	13.59	-90.39	458.09	-397.43	228.01	202.18	25.83	8.828		
6,800.00	6,769.84	6,808.69	6,769.84	13.39	13.67	-90.39	458.09	-397.43	228.01	202.01	26.00	8.771		
6,900.00	6,869.84	6,908.69	6,869.84	13.48	13.75	-90.39	458.09	-397.43	228.01	201.84	26.16	8.714		
7,000.00	6,969.84	7,008.69	6,969.84	13.56	13.83	-90.39	458.09	-397.43	228.01	201.67	26.33	8.659		
7,100.00	7,069.84	7,108.69	7,069.84	13.65	13.92	-90.39	458.09	-397.43	228.01	201.50	26.50	8.604		
7,200.00	7,169.84	7,208.69	7,169.84	13.74	14.00	-90.39	458.09	-397.43	228.01	201.34	26.67	8.550		
7,300.00	7,269.84	7,308.69	7,269.84	13.82	14.08	-90.39	458.09	-397.43	228.01	201.17	26.84	8.496		
7,400.00	7,369.84	7,408.69	7,369.84	13.91	14.16	-90.39	458.09	-397.43	228.01	201.00	27.00	8.443		
7,500.00	7,469.84	7,508.69	7,469.84	14.00	14.24	-90.39	458.09	-397.43	228.01	200.83	27.17	8.391		
7,600.00	7,569.84	7,608.69	7,569.84	14.08	14.33	-90.39	458.09	-397.43	228.01	200.67	27.34	8.340		
7,700.00	7,669.84	7,708.69	7,669.84	14.17	14.41	-90.39	458.09	-397.43	228.01	200.50	27.51	8.289		
7,800.00	7,769.84	7,808.69	7,769.84	14.26	14.49	-90.39	458.09	-397.43	228.01	200.33	27.68	8.239		
7,900.00	7,869.84	7,908.69	7,869.84	14.34	14.57	-90.39	458.09	-397.43	228.01	200.16	27.84	8.189		
8,000.00	7,969.84	8,008.69	7,969.84	14.43	14.65	-90.39	458.09	-397.43	228.01	200.00	28.01	8.140		
8,100.00	8,069.84	8,108.69	8,069.84	14.51	14.74	-90.39	458.09	-397.43	228.01	199.83	28.18	8.092		
8,200.00	8,169.84	8,208.69	8,169.84	14.60	14.82	-90.39	458.09	-397.43	228.01	199.66	28.34	8.044		
8,300.00	8,269.84	8,308.69	8,269.84	14.69	14.90	-90.39	458.09	-397.43	228.01	199.49	28.51	7.997		
8,400.00	8,369.84	8,408.69	8,369.84	14.77	14.98	-90.39	458.09	-397.43	228.01	199.33	28.68	7.950		
8,500.00	8,469.84	8,508.69	8,469.84	14.86	15.06	-90.39	458.09	-397.43	228.01	199.16	28.85	7.904		
8,600.00	8,569.84	8,608.69	8,569.84	14.94	15.15	-90.39	458.09	-397.43	228.01	198.99	29.01	7.858		
8,700.00	8,669.84	8,708.69	8,669.84	15.03	15.23	-90.39	458.09	-397.43	228.01	198.82	29.18	7.813		
8,800.00	8,769.84	8,808.69	8,769.84	15.12	15.31	-90.39	458.09	-397.43	228.01	198.66	29.35	7.769		
8,900.00	8,869.84	8,908.69	8,869.84	15.20	15.39	-90.39	458.09	-397.43	228.01	198.49	29.52	7.725		
9,000.00	8,969.84	9,008.69	8,969.84	15.29	15.47	-90.39	458.09	-397.43	228.01	198.32	29.68	7.682		
9,100.00	9,069.84	9,108.69	9,069.84	15.37	15.56	-90.39	458.09	-397.43	228.01	198.16	29.85	7.639		
9,200.00	9,169.84	9,208.69	9,169.84	15.46	15.64	-90.39	458.09	-397.43	228.01	197.99	30.02	7.596		
9,300.00	9,269.84	9,308.69	9,269.84	15.54	15.72	-90.39	458.09	-397.43	228.01	197.82	30.18	7.554		
9,400.00	9,369.84	9,408.69	9,369.84	15.63	15.80	-90.39	458.09	-397.43	228.01	197.66	30.35	7.513		
9,500.00	9,469.84	9,508.69	9,469.84	15.71	15.89	-90.39	458.09	-397.43	228.01	197.49	30.52	7.472		
9,600.00	9,569.84	9,608.69	9,569.84	15.80	15.97	-90.39	458.09	-397.43	228.01	197.32	30.68	7.431		
9,700.00	9,669.84	9,708.69	9,669.84	15.89	16.05	-90.39	458.09	-397.43	228.01	197.16	30.85	7.391		
9,800.00	9,769.84	9,808.69	9,769.84	15.97	16.13	-90.39	458.09	-397.43	228.01	196.99	31.02	7.351		
9,900.00	9,869.84	9,908.69	9,869.84	16.06	16.21	-90.39	458.09	-397.43	228.01	196.82	31.18	7.312		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 63 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 215H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)			
10,000.00	9,969.84	10,008.69	9,969.84	16.14	16.30	-90.39	-90.39	458.09	-397.43	228.01	196.66	196.66	31.35	7.273	
10,100.00	10,069.84	10,108.69	10,069.84	16.23	16.38	-90.39	-90.39	458.09	-397.43	228.01	196.49	196.49	31.52	7.234	
10,200.00	10,169.84	10,208.69	10,169.84	16.31	16.46	-90.39	-90.39	458.09	-397.43	228.01	196.32	196.32	31.68	7.196	
10,300.00	10,269.84	10,308.69	10,269.84	16.40	16.54	-90.39	-90.39	458.09	-397.43	228.01	196.16	196.16	31.85	7.159	
10,400.00	10,369.84	10,408.69	10,369.84	16.48	16.62	-90.39	-90.39	458.09	-397.43	228.01	195.99	195.99	32.02	7.122	
10,500.00	10,469.84	10,508.69	10,469.84	16.57	16.71	-90.39	-90.39	458.09	-397.43	228.01	195.82	195.82	32.18	7.085	
10,600.00	10,569.84	10,608.69	10,569.84	16.65	16.79	-90.39	-90.39	458.09	-397.43	228.01	195.66	195.66	32.35	7.048	
10,700.00	10,669.84	10,708.69	10,669.84	16.74	16.87	-90.39	-90.39	458.09	-397.43	228.01	195.49	195.49	32.52	7.012	
10,800.00	10,769.84	10,808.69	10,769.84	16.82	16.95	-90.39	-90.39	458.09	-397.43	228.01	195.32	195.32	32.68	6.977	
10,900.00	10,869.84	10,908.69	10,869.84	16.91	17.04	-90.39	-90.39	458.09	-397.43	228.01	195.16	195.16	32.85	6.941	
11,000.00	10,969.84	11,008.69	10,969.84	16.99	17.12	-90.39	-90.39	458.09	-397.43	228.01	194.99	194.99	33.01	6.906	
11,100.00	11,069.84	11,108.69	11,069.84	17.08	17.20	-90.39	-90.39	458.09	-397.43	228.01	194.83	194.83	33.18	6.872	
11,200.00	11,169.84	11,208.69	11,169.84	17.16	17.28	-90.39	-90.39	458.09	-397.43	228.01	194.66	194.66	33.35	6.837	
11,300.00	11,269.84	11,308.69	11,269.84	17.25	17.36	-90.39	-90.39	458.09	-397.43	228.01	194.49	194.49	33.51	6.804	
11,400.00	11,369.84	11,408.69	11,369.84	17.33	17.45	-90.39	-90.39	458.09	-397.43	228.01	194.33	194.33	33.68	6.770	
11,500.00	11,469.84	11,508.69	11,469.84	17.42	17.53	-90.39	-90.39	458.09	-397.43	228.01	194.16	194.16	33.84	6.737	
11,581.16	11,551.00	11,589.85	11,551.00	17.48	17.59	-90.39	-90.39	458.09	-397.43	228.01	194.03	194.03	33.97	6.712	
11,600.00	11,569.83	11,608.69	11,569.83	17.48	17.61	90.18	90.18	458.09	-397.43	228.01	194.02	194.02	33.99	6.709	
11,650.00	11,619.67	11,658.52	11,619.67	17.49	17.65	91.13	91.13	458.09	-397.43	228.05	194.05	194.05	34.00	6.707	
11,700.00	11,668.99	11,707.84	11,668.99	17.51	17.69	93.12	93.12	458.09	-397.43	228.36	194.35	194.35	34.01	6.714	
11,750.00	11,717.40	11,756.26	11,717.40	17.51	17.73	96.02	96.02	458.09	-397.43	229.38	195.37	195.37	34.01	6.744	
11,800.00	11,764.55	11,803.41	11,764.55	17.52	17.77	99.63	99.63	458.09	-397.43	231.79	197.76	197.76	34.02	6.812	
11,850.00	11,810.08	11,848.93	11,810.08	17.52	17.81	103.70	103.70	458.09	-397.43	236.37	202.32	202.32	34.06	6.941	
11,900.00	11,853.63	11,892.49	11,853.63	17.52	17.84	107.93	107.93	458.09	-397.43	243.99	209.87	209.87	34.12	7.151	
11,950.00	11,894.88	11,933.74	11,894.88	17.53	17.87	111.99	111.99	458.09	-397.43	255.40	221.19	221.19	34.22	7.464	
12,000.00	11,933.52	11,972.37	11,933.52	17.53	17.90	115.61	115.61	458.09	-397.43	271.18	236.82	236.82	34.35	7.894	
12,050.00	11,969.24	12,022.97	11,984.06	17.53	17.91	120.39	120.39	456.15	-397.41	290.76	256.26	256.26	34.50	8.427	
12,100.00	12,001.78	12,079.77	12,040.35	17.53	17.93	125.09	125.09	448.69	-397.35	312.58	277.76	277.76	34.82	8.978	
12,150.00	12,030.89	12,143.02	12,101.80	17.53	17.94	129.57	129.57	433.88	-397.22	335.81	300.38	300.38	35.43	9.477	
12,200.00	12,056.34	12,214.63	12,168.92	17.53	17.96	133.86	133.86	409.05	-397.01	359.64	323.13	323.13	36.51	9.851	
12,250.00	12,077.95	12,297.05	12,241.64	17.54	17.98	137.96	137.96	370.40	-396.67	383.09	344.92	344.92	38.17	10.035	
12,300.00	12,095.55	12,393.19	12,318.40	17.55	18.00	141.77	141.77	312.71	-396.18	405.04	364.52	364.52	40.52	9.997	
12,350.00	12,109.01	12,505.88	12,394.60	17.56	18.04	145.11	145.11	229.94	-395.47	424.09	380.66	380.66	43.43	9.765	
12,400.00	12,118.22	12,636.39	12,460.64	17.58	18.11	147.69	147.69	117.69	-394.50	438.60	392.10	392.10	46.49	9.434	
12,450.00	12,123.11	12,782.08	12,502.30	17.60	18.25	149.17	149.17	-21.49	-393.30	446.87	397.98	397.98	48.89	9.140	
12,476.17	12,123.94	12,861.82	12,509.79	17.61	18.36	149.42	149.42	-100.82	-392.62	448.28	398.73	398.73	49.55	9.046	
12,500.00	12,124.14	12,891.73	12,510.12	17.62	18.41	149.43	149.43	-130.72	-392.36	448.30	398.69	398.69	49.61	9.036	
12,600.00	12,125.02	12,991.73	12,510.99	17.69	18.60	149.43	149.43	-230.72	-391.50	448.30	398.55	398.55	49.75	9.011	
12,700.00	12,125.89	13,091.73	12,511.87	17.79	18.85	149.43	149.43	-330.71	-390.64	448.30	398.36	398.36	49.94	8.977	
12,800.00	12,126.76	13,191.73	12,512.74	17.95	19.18	149.43	149.43	-430.70	-389.78	448.31	398.12	398.12	50.18	8.934	
12,900.00	12,127.63	13,291.73	12,513.61	18.21	19.58	149.43	149.43	-530.69	-388.92	448.31	397.84	397.84	50.47	8.882	
13,000.00	12,128.50	13,391.73	12,514.48	18.61	20.07	149.43	149.43	-630.69	-388.06	448.31	397.50	397.50	50.81	8.823	
13,100.00	12,129.37	13,491.73	12,515.36	19.18	20.65	149.43	149.43	-730.68	-387.19	448.31	397.11	397.11	51.20	8.756	
13,200.00	12,130.24	13,591.73	12,516.23	19.87	21.31	149.43	149.43	-830.67	-386.33	448.31	396.68	396.68	51.63	8.683	
13,300.00	12,131.11	13,691.73	12,517.10	20.66	22.05	149.43	149.43	-930.66	-385.47	448.32	396.21	396.21	52.11	8.603	
13,400.00	12,131.99	13,791.73	12,517.98	21.53	22.86	149.43	149.43	-1,030.66	-384.61	448.32	395.68	395.68	52.63	8.518	
13,500.00	12,132.86	13,891.73	12,518.85	22.45	23.73	149.43	149.43	-1,130.65	-383.75	448.32	395.12	395.12	53.20	8.427	
13,600.00	12,133.73	13,991.73	12,519.72	23.43	24.65	149.43	149.43	-1,230.64	-382.89	448.32	394.51	394.51	53.81	8.332	
13,700.00	12,134.60	14,091.73	12,520.60	24.44	25.62	149.43	149.43	-1,330.63	-382.03	448.32	393.87	393.87	54.45	8.233	
13,800.00	12,135.47	14,191.73	12,521.47	25.50	26.62	149.43	149.43	-1,430.63	-381.17	448.32	393.18	393.18	55.14	8.130	
13,900.00	12,136.34	14,291.73	12,522.34	26.58	27.66	149.43	149.43	-1,530.62	-380.31	448.33	392.46	392.46	55.87	8.025	
14,000.00	12,137.21	14,391.73	12,523.22	27.69	28.73	149.43	149.43	-1,630.61	-379.45	448.33	391.70	391.70	56.63	7.917	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 64 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 215H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft
Reference	Offset	Semi Major Axis		Offset Wellbore Centre			Distance		Separation		Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor
14,100.00	12,138.08	14,491.73	12,524.09	28.82	29.82	149.43	-1,730.60	-378.59	448.33	390.91	57.42	7.808
14,200.00	12,138.96	14,591.73	12,524.96	29.98	30.94	149.43	-1,830.60	-377.72	448.33	390.08	58.25	7.697
14,300.00	12,139.83	14,691.73	12,525.84	31.15	32.08	149.43	-1,930.59	-376.86	448.33	389.23	59.11	7.585
14,400.00	12,140.70	14,791.73	12,526.71	32.33	33.24	149.43	-2,030.58	-376.00	448.33	388.34	60.00	7.473
14,500.00	12,141.57	14,891.73	12,527.58	33.54	34.41	149.43	-2,130.57	-375.14	448.34	387.42	60.91	7.360
14,600.00	12,142.44	14,991.73	12,528.46	34.75	35.60	149.43	-2,230.57	-374.28	448.34	386.48	61.86	7.248
14,700.00	12,143.31	15,091.73	12,529.33	35.98	36.81	149.43	-2,330.56	-373.42	448.34	385.51	62.83	7.135
14,800.00	12,144.18	15,191.73	12,530.20	37.21	38.02	149.43	-2,430.55	-372.56	448.34	384.51	63.83	7.024
14,900.00	12,145.05	15,291.73	12,531.08	38.46	39.24	149.43	-2,530.54	-371.70	448.34	383.49	64.85	6.913
15,000.00	12,145.93	15,391.73	12,531.95	39.71	40.48	149.43	-2,630.54	-370.84	448.34	382.45	65.90	6.804
15,100.00	12,146.80	15,491.73	12,532.82	40.97	41.72	149.43	-2,730.53	-369.98	448.35	381.38	66.96	6.695
15,200.00	12,147.67	15,591.73	12,533.70	42.24	42.97	149.43	-2,830.52	-369.12	448.35	380.30	68.05	6.588
15,300.00	12,148.54	15,691.73	12,534.57	43.51	44.23	149.43	-2,930.51	-368.25	448.35	379.19	69.16	6.483
15,400.00	12,149.41	15,791.73	12,535.44	44.79	45.50	149.43	-3,030.51	-367.39	448.35	378.07	70.29	6.379
15,500.00	12,150.28	15,891.73	12,536.32	46.08	46.77	149.43	-3,130.50	-366.53	448.35	376.92	71.43	6.277
15,600.00	12,151.15	15,991.73	12,537.19	47.37	48.04	149.43	-3,230.49	-365.67	448.35	375.76	72.59	6.176
15,700.00	12,152.02	16,091.73	12,538.06	48.66	49.32	149.43	-3,330.48	-364.81	448.36	374.59	73.77	6.078
15,800.00	12,152.90	16,191.73	12,538.94	49.96	50.61	149.43	-3,430.48	-363.95	448.36	373.40	74.96	5.981
15,900.00	12,153.77	16,291.73	12,539.81	51.26	51.90	149.43	-3,530.47	-363.09	448.36	372.19	76.17	5.886
16,000.00	12,154.64	16,391.73	12,540.68	52.57	53.20	149.43	-3,630.46	-362.23	448.36	370.97	77.39	5.793
16,100.00	12,155.51	16,491.73	12,541.56	53.88	54.50	149.43	-3,730.45	-361.37	448.36	369.73	78.63	5.702
16,200.00	12,156.38	16,591.73	12,542.43	55.19	55.80	149.43	-3,830.45	-360.51	448.36	368.49	79.88	5.613
16,300.00	12,157.25	16,691.73	12,543.30	56.50	57.10	149.43	-3,930.44	-359.65	448.37	367.23	81.14	5.526
16,400.00	12,158.12	16,791.73	12,544.17	57.82	58.41	149.43	-4,030.43	-358.78	448.37	365.96	82.41	5.441
16,500.00	12,158.99	16,891.73	12,545.05	59.14	59.72	149.43	-4,130.42	-357.92	448.37	364.67	83.70	5.357
16,600.00	12,159.87	16,991.73	12,545.92	60.46	61.04	149.43	-4,230.42	-357.06	448.37	363.38	84.99	5.275
16,700.00	12,160.74	17,091.73	12,546.79	61.79	62.35	149.43	-4,330.41	-356.20	448.37	362.08	86.30	5.196
16,800.00	12,161.61	17,191.73	12,547.67	63.11	63.67	149.43	-4,430.40	-355.34	448.38	360.76	87.61	5.118
16,900.00	12,162.48	17,291.73	12,548.54	64.44	64.99	149.43	-4,530.39	-354.48	448.38	359.44	88.94	5.042
17,000.00	12,163.35	17,391.73	12,549.41	65.77	66.31	149.44	-4,630.39	-353.62	448.38	358.11	90.27	4.967
17,100.00	12,164.22	17,491.73	12,550.29	67.10	67.64	149.44	-4,730.38	-352.76	448.38	356.77	91.61	4.894
17,200.00	12,165.09	17,591.73	12,551.16	68.43	68.96	149.44	-4,830.37	-351.90	448.38	355.42	92.96	4.823
17,300.00	12,165.96	17,691.73	12,552.03	69.77	70.29	149.44	-4,930.36	-351.04	448.38	354.07	94.32	4.754
17,400.00	12,166.84	17,791.73	12,552.91	71.10	71.62	149.44	-5,030.36	-350.18	448.39	352.70	95.68	4.686
17,500.00	12,167.71	17,891.73	12,553.78	72.44	72.95	149.44	-5,130.35	-349.31	448.39	351.33	97.05	4.620
17,600.00	12,168.58	17,991.73	12,554.65	73.78	74.29	149.44	-5,230.34	-348.45	448.39	349.96	98.43	4.555
17,700.00	12,169.45	18,091.73	12,555.53	75.12	75.62	149.44	-5,330.33	-347.59	448.39	348.57	99.82	4.492
17,800.00	12,170.32	18,191.73	12,556.40	76.46	76.95	149.44	-5,430.33	-346.73	448.39	347.18	101.21	4.430
17,900.00	12,171.19	18,291.73	12,557.27	77.80	78.29	149.44	-5,530.32	-345.87	448.39	345.79	102.61	4.370
18,000.00	12,172.06	18,391.73	12,558.15	79.14	79.63	149.44	-5,630.31	-345.01	448.40	344.39	104.01	4.311
18,100.00	12,172.93	18,491.73	12,559.02	80.48	80.97	149.44	-5,730.30	-344.15	448.40	342.98	105.42	4.253
18,200.00	12,173.81	18,591.73	12,559.89	81.83	82.31	149.44	-5,830.30	-343.29	448.40	341.57	106.83	4.197
18,300.00	12,174.68	18,691.73	12,560.77	83.17	83.65	149.44	-5,930.29	-342.43	448.40	340.15	108.25	4.142
18,400.00	12,175.55	18,791.73	12,561.64	84.52	84.99	149.44	-6,030.28	-341.57	448.40	338.73	109.68	4.088
18,500.00	12,176.42	18,891.73	12,562.51	85.86	86.33	149.44	-6,130.27	-340.71	448.40	337.30	111.11	4.036
18,600.00	12,177.29	18,991.73	12,563.39	87.21	87.67	149.44	-6,230.27	-339.84	448.41	335.87	112.54	3.984
18,700.00	12,178.16	19,091.73	12,564.26	88.56	89.02	149.44	-6,330.26	-338.98	448.41	334.43	113.98	3.934
18,800.00	12,179.03	19,191.73	12,565.13	89.91	90.36	149.44	-6,430.25	-338.12	448.41	332.99	115.42	3.885
18,900.00	12,179.90	19,291.73	12,566.01	91.26	91.71	149.44	-6,530.24	-337.26	448.41	331.54	116.87	3.837
19,000.00	12,180.78	19,391.73	12,566.88	92.61	93.06	149.44	-6,630.24	-336.40	448.41	330.10	118.32	3.790
19,100.00	12,181.65	19,491.73	12,567.75	93.96	94.40	149.44	-6,730.23	-335.54	448.41	328.64	119.77	3.744
19,200.00	12,182.52	19,591.73	12,568.63	95.31	95.75	149.44	-6,830.22	-334.68	448.42	327.19	121.23	3.699

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 65 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 215H - OH - Plan 1													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)													Offset Well Error:	0.50 usft
Reference		Offset		Semi Major Axis		Offset Wellbore Centre			Rule Assigned:				Warning	
Measured	Vertical	Measured	Vertical	Reference	Offset	Highside	+N/-S	+E/-W	Between	Between	Minimum	Separation		
Depth	Depth	Depth	Depth			Toolface	(usft)	(usft)	Centres	Ellipses	Separation	Factor		
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)			(usft)	(usft)	(usft)			
19,300.00	12,183.39	19,691.73	12,569.50	96.66	97.10	149.44	-6,930.21	-333.82	448.42	325.73	122.69	3.655		
19,400.00	12,184.26	19,791.73	12,570.37	98.01	98.45	149.44	-7,030.21	-332.96	448.42	324.27	124.15	3.612		
19,500.00	12,185.13	19,891.73	12,571.25	99.36	99.80	149.44	-7,130.20	-332.10	448.42	322.80	125.62	3.570		
19,600.00	12,186.00	19,991.73	12,572.12	100.72	101.15	149.44	-7,230.19	-331.24	448.42	321.33	127.09	3.528		
19,700.00	12,186.87	20,091.73	12,572.99	102.07	102.50	149.44	-7,330.18	-330.37	448.43	319.86	128.57	3.488		
19,800.00	12,187.75	20,191.73	12,573.86	103.42	103.85	149.44	-7,430.18	-329.51	448.43	318.38	130.04	3.448		
19,900.00	12,188.62	20,291.73	12,574.74	104.78	105.20	149.44	-7,530.17	-328.65	448.43	316.90	131.52	3.409		
20,000.00	12,189.49	20,391.73	12,575.61	106.13	106.55	149.44	-7,630.16	-327.79	448.43	315.42	133.01	3.371		
20,100.00	12,190.36	20,491.73	12,576.48	107.49	107.91	149.44	-7,730.15	-326.93	448.43	313.94	134.49	3.334		
20,200.00	12,191.23	20,591.73	12,577.36	108.84	109.26	149.44	-7,830.15	-326.07	448.43	312.45	135.98	3.298		
20,300.00	12,192.10	20,691.73	12,578.23	110.20	110.61	149.44	-7,930.14	-325.21	448.44	310.96	137.47	3.262		
20,400.00	12,192.97	20,791.73	12,579.10	111.55	111.97	149.44	-8,030.13	-324.35	448.44	309.47	138.96	3.227		
20,500.00	12,193.85	20,891.73	12,579.98	112.91	113.32	149.44	-8,130.12	-323.49	448.44	307.98	140.46	3.193		
20,600.00	12,194.72	20,991.73	12,580.85	114.27	114.67	149.44	-8,230.12	-322.63	448.44	306.48	141.96	3.159		
20,700.00	12,195.59	21,091.73	12,581.72	115.62	116.03	149.44	-8,330.11	-321.76	448.44	304.99	143.46	3.126		
20,800.00	12,196.46	21,191.73	12,582.60	116.98	117.38	149.44	-8,430.10	-320.90	448.44	303.49	144.96	3.094		
20,900.00	12,197.33	21,291.73	12,583.47	118.34	118.74	149.44	-8,530.09	-320.04	448.45	301.99	146.46	3.062		
21,000.00	12,198.20	21,391.73	12,584.34	119.70	120.10	149.44	-8,630.09	-319.18	448.45	300.48	147.97	3.031		
21,100.00	12,199.07	21,491.73	12,585.22	121.05	121.45	149.44	-8,730.08	-318.32	448.45	298.98	149.47	3.000		
21,200.00	12,199.94	21,591.73	12,586.09	122.41	122.81	149.44	-8,830.07	-317.46	448.45	297.47	150.98	2.970		
21,300.00	12,200.82	21,691.73	12,586.96	123.77	124.17	149.44	-8,930.06	-316.60	448.45	295.96	152.49	2.941		
21,400.00	12,201.69	21,791.73	12,587.84	125.13	125.52	149.44	-9,030.05	-315.74	448.45	294.45	154.01	2.912		
21,500.00	12,202.56	21,891.73	12,588.71	126.49	126.88	149.44	-9,130.05	-314.88	448.46	292.93	155.52	2.884		
21,600.00	12,203.43	21,991.73	12,589.58	127.85	128.24	149.44	-9,230.04	-314.02	448.46	291.42	157.04	2.856		
21,700.00	12,204.30	22,091.73	12,590.46	129.21	129.60	149.44	-9,330.03	-313.16	448.46	289.90	158.56	2.828		
21,800.00	12,205.17	22,191.73	12,591.33	130.57	130.95	149.44	-9,430.02	-312.29	448.46	288.39	160.08	2.802		
21,900.00	12,206.04	22,291.73	12,592.20	131.93	132.31	149.44	-9,530.02	-311.43	448.46	286.87	161.60	2.775		
22,000.00	12,206.91	22,391.73	12,593.08	133.29	133.67	149.44	-9,630.01	-310.57	448.46	285.35	163.12	2.749		
22,100.00	12,207.79	22,491.73	12,593.95	134.65	135.03	149.44	-9,730.00	-309.71	448.47	283.82	164.64	2.724		
22,200.00	12,208.66	22,591.73	12,594.82	136.01	136.39	149.44	-9,829.99	-308.85	448.47	282.30	166.17	2.699		
22,300.00	12,209.53	22,691.73	12,595.70	137.37	137.75	149.44	-9,929.99	-307.99	448.47	280.77	167.69	2.674		
22,400.00	12,210.40	22,791.73	12,596.57	138.73	139.11	149.44	-10,029.98	-307.13	448.47	279.25	169.22	2.650		
22,411.61	12,210.50	22,803.34	12,596.67	138.89	139.27	149.44	-10,041.59	-307.03	448.47	279.07	169.40	2.647	SF	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 66 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 216H - OH - Plan 1														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
5,800.00	5,769.84	5,831.47	5,806.27	12.52	12.69	86.80	595.28	2,256.53	2,429.98	2,406.15	23.83	101.980			
5,900.00	5,869.84	5,930.92	5,905.17	12.61	12.88	87.04	584.91	2,255.75	2,428.62	2,404.54	24.09	100.830			
6,000.00	5,969.84	6,030.37	6,004.08	12.69	13.06	87.29	574.55	2,254.96	2,427.32	2,402.97	24.34	99.708			
6,100.00	6,069.84	6,129.83	6,102.99	12.78	13.24	87.53	564.18	2,254.18	2,426.05	2,401.45	24.60	98.611			
6,200.00	6,169.84	6,229.28	6,201.90	12.87	13.42	87.77	553.82	2,253.40	2,424.83	2,399.97	24.86	97.539			
6,300.00	6,269.84	6,328.73	6,300.81	12.96	13.61	88.02	543.46	2,252.61	2,423.65	2,398.54	25.12	96.492			
6,400.00	6,369.84	6,428.18	6,399.71	13.04	13.79	88.26	533.09	2,251.83	2,422.52	2,397.15	25.38	95.468			
6,500.00	6,469.84	6,527.64	6,498.62	13.13	13.97	88.51	522.73	2,251.05	2,421.43	2,395.80	25.63	94.467			
6,600.00	6,569.84	6,627.09	6,597.53	13.22	14.15	88.75	512.36	2,250.26	2,420.39	2,394.50	25.89	93.488			
6,700.00	6,669.84	6,726.54	6,696.44	13.30	14.33	89.00	502.00	2,249.48	2,419.39	2,393.25	26.14	92.549			
6,800.00	6,769.84	6,823.06	6,792.46	13.39	14.49	89.23	492.29	2,248.74	2,418.47	2,392.11	26.37	91.719			
6,900.00	6,869.84	6,917.52	6,886.62	13.48	14.67	89.40	484.88	2,248.18	2,417.79	2,391.19	26.60	90.905			
7,000.00	6,969.84	7,012.28	6,981.25	13.56	14.84	89.52	479.78	2,247.80	2,417.33	2,390.52	26.81	90.177			
7,100.00	7,069.84	7,107.25	7,076.17	13.65	14.99	89.59	477.02	2,247.59	2,417.09	2,390.09	26.99	89.545			
7,200.00	7,169.84	7,203.92	7,172.84	13.74	15.03	89.60	476.49	2,247.55	2,417.04	2,389.94	27.10	89.187			
7,300.00	7,269.84	7,303.92	7,272.84	13.82	15.05	89.60	476.49	2,247.55	2,417.04	2,389.83	27.21	88.833			
7,400.00	7,369.84	7,403.92	7,372.84	13.91	15.08	89.60	476.49	2,247.55	2,417.04	2,389.72	27.32	88.480			
7,500.00	7,469.84	7,503.92	7,472.84	14.00	15.10	89.60	476.49	2,247.55	2,417.04	2,389.61	27.43	88.129			
7,600.00	7,569.84	7,603.92	7,572.84	14.08	15.13	89.60	476.49	2,247.55	2,417.04	2,389.50	27.54	87.779			
7,700.00	7,669.84	7,703.92	7,672.84	14.17	15.15	89.60	476.49	2,247.55	2,417.04	2,389.39	27.64	87.431			
7,800.00	7,769.84	7,803.92	7,772.84	14.26	15.18	89.60	476.49	2,247.55	2,417.04	2,389.28	27.75	87.085			
7,900.00	7,869.84	7,903.92	7,872.84	14.34	15.21	89.60	476.49	2,247.55	2,417.04	2,389.17	27.87	86.740			
8,000.00	7,969.84	8,003.92	7,972.84	14.43	15.23	89.60	476.49	2,247.55	2,417.04	2,389.06	27.98	86.397			
8,100.00	8,069.84	8,103.92	8,072.84	14.51	15.26	89.60	476.49	2,247.55	2,417.04	2,388.95	28.09	86.056			
8,200.00	8,169.84	8,203.92	8,172.84	14.60	15.29	89.60	476.49	2,247.55	2,417.04	2,388.84	28.20	85.716			
8,300.00	8,269.84	8,303.92	8,272.84	14.69	15.32	89.60	476.49	2,247.55	2,417.04	2,388.73	28.31	85.377			
8,400.00	8,369.84	8,403.92	8,372.84	14.77	15.35	89.60	476.49	2,247.55	2,417.04	2,388.62	28.42	85.040			
8,500.00	8,469.84	8,503.92	8,472.84	14.86	15.37	89.60	476.49	2,247.55	2,417.04	2,388.50	28.53	84.705			
8,600.00	8,569.84	8,603.92	8,572.84	14.94	15.40	89.60	476.49	2,247.55	2,417.04	2,388.39	28.65	84.371			
8,700.00	8,669.84	8,703.92	8,672.84	15.03	15.43	89.60	476.49	2,247.55	2,417.04	2,388.28	28.76	84.039			
8,800.00	8,769.84	8,803.92	8,772.84	15.12	15.46	89.60	476.49	2,247.55	2,417.04	2,388.16	28.87	83.709			
8,900.00	8,869.84	8,903.92	8,872.84	15.20	15.49	89.60	476.49	2,247.55	2,417.04	2,388.05	28.99	83.380			
9,000.00	8,969.84	9,003.92	8,972.84	15.29	15.53	89.60	476.49	2,247.55	2,417.04	2,387.94	29.10	83.052			
9,100.00	9,069.84	9,103.92	9,072.84	15.37	15.56	89.60	476.49	2,247.55	2,417.04	2,387.82	29.22	82.727			
9,200.00	9,169.84	9,203.92	9,172.84	15.46	15.59	89.60	476.49	2,247.55	2,417.04	2,387.71	29.33	82.402			
9,300.00	9,269.84	9,303.92	9,272.84	15.54	15.62	89.60	476.49	2,247.55	2,417.04	2,387.59	29.45	82.080			
9,400.00	9,369.84	9,403.92	9,372.84	15.63	15.65	89.60	476.49	2,247.55	2,417.04	2,387.48	29.56	81.758			
9,500.00	9,469.84	9,503.92	9,472.84	15.71	15.68	89.60	476.49	2,247.55	2,417.04	2,387.36	29.68	81.439			
9,600.00	9,569.84	9,603.92	9,572.84	15.80	15.72	89.60	476.49	2,247.55	2,417.04	2,387.24	29.80	81.121			
9,700.00	9,669.84	9,703.92	9,672.84	15.89	15.75	89.60	476.49	2,247.55	2,417.04	2,387.13	29.91	80.804			
9,800.00	9,769.84	9,803.92	9,772.84	15.97	15.79	89.60	476.49	2,247.55	2,417.04	2,387.01	30.03	80.489			
9,900.00	9,869.84	9,903.92	9,872.84	16.06	15.82	89.60	476.49	2,247.55	2,417.04	2,386.89	30.15	80.176			
10,000.00	9,969.84	10,003.92	9,972.84	16.14	15.85	89.60	476.49	2,247.55	2,417.04	2,386.77	30.26	79.864			
10,100.00	10,069.84	10,103.92	10,072.84	16.23	15.89	89.60	476.49	2,247.55	2,417.04	2,386.66	30.38	79.554			
10,200.00	10,169.84	10,203.92	10,172.84	16.31	15.92	89.60	476.49	2,247.55	2,417.04	2,386.54	30.50	79.245			
10,300.00	10,269.84	10,303.92	10,272.84	16.40	15.96	89.60	476.49	2,247.55	2,417.04	2,386.42	30.62	78.938			
10,400.00	10,369.84	10,403.92	10,372.84	16.48	15.99	89.60	476.49	2,247.55	2,417.04	2,386.30	30.74	78.632			
10,500.00	10,469.84	10,503.92	10,472.84	16.57	16.03	89.60	476.49	2,247.55	2,417.04	2,386.18	30.86	78.328			
10,600.00	10,569.84	10,603.92	10,572.84	16.65	16.07	89.60	476.49	2,247.55	2,417.04	2,386.06	30.98	78.025			
10,700.00	10,669.84	10,703.92	10,672.84	16.74	16.10	89.60	476.49	2,247.55	2,417.04	2,385.94	31.10	77.724			
10,800.00	10,769.84	10,803.92	10,772.84	16.82	16.14	89.60	476.49	2,247.55	2,417.04	2,385.82	31.22	77.424			
10,900.00	10,869.84	10,903.92	10,872.84	16.91	16.18	89.60	476.49	2,247.55	2,417.04	2,385.70	31.34	77.126			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 67 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 216H - OH - Plan 1														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Offset Well Error:	0.50 usft
Reference	Vertical	Offset	Vertical	Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Rule Assigned:		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Depth (usft)	Measured Depth (usft)	Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)					
11,000.00	10,969.84	11,003.92	10,972.84	16.99	16.22	89.60	476.49	2,247.55	2,417.04	2,385.58	31.46	76.829			
11,100.00	11,069.84	11,103.92	11,072.84	17.08	16.25	89.60	476.49	2,247.55	2,417.04	2,385.46	31.58	76.534			
11,200.00	11,169.84	11,203.92	11,172.84	17.16	16.29	89.60	476.49	2,247.55	2,417.04	2,385.34	31.70	76.240			
11,300.00	11,269.84	11,303.92	11,272.84	17.25	16.33	89.60	476.49	2,247.55	2,417.04	2,385.21	31.82	75.948			
11,400.00	11,369.84	11,403.92	11,372.84	17.33	16.37	89.60	476.49	2,247.55	2,417.04	2,385.09	31.95	75.657			
11,500.00	11,469.84	11,503.92	11,472.84	17.42	16.41	89.60	476.49	2,247.55	2,417.04	2,384.97	32.07	75.368			
11,581.16	11,551.00	11,585.08	11,554.00	17.48	16.44	89.60	476.49	2,247.55	2,417.04	2,384.88	32.16	75.156			
11,600.00	11,569.83	11,603.91	11,572.83	17.48	16.45	-89.91	476.49	2,247.55	2,417.04	2,384.87	32.17	75.140	ES		
11,648.57	11,618.25	11,652.33	11,621.25	17.49	16.47	-90.00	476.49	2,247.55	2,417.04	2,384.88	32.16	75.167	CC		
11,650.00	11,619.67	11,653.75	11,622.67	17.49	16.47	-90.00	476.49	2,247.55	2,417.04	2,384.88	32.16	75.168			
11,700.00	11,668.99	11,703.07	11,671.99	17.51	16.49	-90.19	476.49	2,247.55	2,417.05	2,384.93	32.12	75.246			
11,750.00	11,717.40	11,751.48	11,720.40	17.51	16.51	-90.47	476.49	2,247.55	2,417.12	2,385.06	32.07	75.372			
11,800.00	11,764.55	11,798.63	11,767.55	17.52	16.53	-90.82	476.49	2,247.55	2,417.32	2,385.33	32.00	75.546			
11,850.00	11,810.08	11,844.16	11,813.08	17.52	16.54	-91.23	476.49	2,247.55	2,417.73	2,385.82	31.91	75.772			
11,900.00	11,853.63	11,887.71	11,856.63	17.52	16.56	-91.66	476.49	2,247.55	2,418.44	2,386.64	31.81	76.039			
11,950.00	11,894.88	11,938.27	11,907.13	17.53	16.65	-92.19	474.38	2,247.57	2,419.49	2,387.78	31.71	76.299			
12,000.00	11,933.52	11,992.17	11,960.53	17.53	16.79	-92.73	467.24	2,247.63	2,420.83	2,389.18	31.65	76.487			
12,050.00	11,969.24	12,049.72	12,016.55	17.53	16.94	-93.27	454.12	2,247.75	2,422.42	2,390.78	31.64	76.567			
12,100.00	12,001.78	12,111.58	12,074.95	17.53	17.12	-93.83	433.83	2,247.94	2,424.23	2,392.53	31.70	76.476			
12,150.00	12,030.89	12,178.44	12,135.22	17.53	17.31	-94.39	404.97	2,248.20	2,426.21	2,394.36	31.85	76.174			
12,200.00	12,056.34	12,251.05	12,196.37	17.53	17.51	-94.96	365.91	2,248.56	2,428.29	2,396.17	32.12	75.608			
12,250.00	12,077.95	12,330.09	12,256.74	17.54	17.71	-95.51	314.99	2,249.02	2,430.36	2,397.82	32.54	74.690	SF		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 217H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Rule Assigned:	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Distance Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
0.00	0.00	1.00	1.00	0.50	0.50	-6.79	210.00	-25.00	211.48	211.48					
100.00	100.00	101.00	101.00	0.98	0.99	-6.79	210.00	-25.00	211.48	209.52	1.97	107.480			
200.00	200.00	201.00	201.00	1.56	1.57	-6.79	210.00	-25.00	211.48	208.36	3.13	67.644			
300.00	300.00	301.00	301.00	1.98	1.98	-6.79	210.00	-25.00	211.48	207.52	3.97	53.327			
400.00	400.00	401.00	401.00	2.33	2.33	-6.79	210.00	-25.00	211.48	206.82	4.66	45.364			
500.00	500.00	501.00	501.00	2.63	2.64	-6.79	210.00	-25.00	211.48	206.21	5.27	40.116			
600.00	600.00	601.00	601.00	2.91	2.91	-6.79	210.00	-25.00	211.48	205.66	5.82	36.321			
700.00	700.00	701.00	701.00	3.16	3.17	-6.79	210.00	-25.00	211.48	205.15	6.33	33.410			
800.00	800.00	801.00	801.00	3.40	3.40	-6.79	210.00	-25.00	211.48	204.68	6.80	31.085			
900.00	899.99	900.99	900.99	3.68	3.63	13.53	210.00	-25.00	210.21	202.91	7.30	28.790			
1,000.00	999.91	1,001.08	1,001.08	3.94	3.76	13.81	210.00	-24.94	206.39	198.69	7.70	26.807			
1,100.00	1,099.77	1,101.63	1,101.61	4.15	4.01	14.70	209.93	-23.06	201.05	192.96	8.09	24.838			
1,200.00	1,199.63	1,201.92	1,201.79	4.35	4.24	16.41	209.78	-18.56	195.49	187.01	8.48	23.060			
1,250.43	1,250.00	1,252.35	1,252.12	4.40	4.35	17.59	209.66	-15.30	192.66	184.05	8.62	22.358			
1,300.00	1,299.48	1,301.77	1,301.39	4.45	4.46	19.03	209.53	-11.46	189.63	180.87	8.75	21.662			
1,400.00	1,399.17	1,400.85	1,400.09	4.69	4.60	22.59	209.23	-2.85	182.07	172.96	9.12	19.969			
1,500.00	1,498.62	1,499.58	1,498.45	4.93	4.78	26.82	208.93	5.75	172.93	163.42	9.51	18.176			
1,550.47	1,548.70	1,549.26	1,547.94	4.99	4.87	29.29	208.78	10.08	167.83	158.18	9.65	17.386			
1,600.00	1,597.81	1,597.97	1,596.46	5.05	4.95	31.87	208.63	14.32	162.87	153.08	9.79	16.643			
1,700.00	1,696.95	1,696.30	1,694.42	5.25	5.13	37.55	208.33	22.88	153.96	143.82	10.14	15.188			
1,800.00	1,796.09	1,794.64	1,792.39	5.44	5.31	43.84	208.03	31.45	146.77	136.28	10.49	13.998			
1,900.00	1,895.24	1,892.98	1,890.35	5.64	5.48	50.66	207.73	40.01	141.56	130.73	10.83	13.067			
2,000.00	1,994.38	1,991.31	1,988.31	5.83	5.66	57.88	207.43	48.58	138.55	127.37	11.18	12.390			
2,077.70	2,071.42	2,067.72	2,064.43	5.99	5.79	63.63	207.20	55.24	137.83	126.37	11.46	12.031	CC		
2,100.00	2,093.53	2,089.65	2,086.27	6.03	5.83	65.29	207.13	57.15	137.89	126.35	11.54	11.954	ES		
2,200.00	2,192.67	2,187.99	2,184.24	6.22	6.01	72.64	206.83	65.71	139.61	127.71	11.90	11.732			
2,300.00	2,291.82	2,283.33	2,279.14	6.42	6.20	79.51	206.91	74.75	144.48	132.22	12.26	11.787			
2,400.00	2,390.96	2,377.73	2,372.89	6.61	6.39	85.77	208.03	85.76	153.86	141.23	12.62	12.188			
2,500.00	2,490.11	2,471.63	2,465.86	6.81	6.58	91.15	210.18	98.76	167.40	154.41	12.99	12.887			
2,600.00	2,589.25	2,564.92	2,557.89	7.00	6.78	95.55	213.34	113.68	184.64	171.29	13.35	13.830			
2,700.00	2,688.39	2,657.50	2,648.84	7.20	6.98	99.00	217.48	130.48	205.11	191.41	13.70	14.967			
2,800.00	2,787.54	2,749.26	2,738.56	7.39	7.17	101.64	222.57	149.06	228.43	214.38	14.05	16.258			
2,900.00	2,886.68	2,840.12	2,826.91	7.59	7.36	103.60	228.58	169.34	254.31	239.92	14.39	17.674			
3,000.00	2,985.83	2,932.11	2,915.88	7.78	7.55	105.06	235.57	191.66	282.41	267.67	14.73	19.167			
3,100.00	3,084.97	3,027.72	3,008.23	7.98	7.73	106.28	243.04	215.25	311.09	295.98	15.11	20.590			
3,200.00	3,184.12	3,123.33	3,100.59	8.17	7.92	107.29	250.51	238.84	339.87	324.39	15.49	21.948			
3,300.00	3,283.26	3,218.94	3,192.94	8.36	8.10	108.14	257.98	262.43	368.74	352.88	15.86	23.244			
3,400.00	3,382.40	3,314.55	3,285.29	8.56	8.29	108.87	265.46	286.02	397.68	381.43	16.25	24.479			
3,500.00	3,481.55	3,410.16	3,377.64	8.75	8.54	109.50	272.93	309.62	426.66	410.03	16.63	25.658			
3,600.00	3,580.69	3,505.77	3,469.99	8.95	8.81	110.05	280.40	333.21	455.69	438.67	17.01	26.782			
3,700.00	3,679.84	3,601.37	3,562.34	9.14	9.09	110.53	287.87	356.80	484.75	467.35	17.40	27.855			
3,800.00	3,778.98	3,696.98	3,654.69	9.33	9.37	110.96	295.34	380.39	513.84	496.04	17.79	28.880			
3,900.00	3,878.13	3,792.59	3,747.04	9.53	9.65	111.35	302.82	403.98	542.95	524.76	18.18	29.860			
4,000.00	3,977.27	3,888.20	3,839.39	9.72	9.94	111.69	310.29	427.58	572.08	553.50	18.58	30.796			
4,100.00	4,076.42	3,983.81	3,931.74	9.91	10.23	112.00	317.76	451.17	601.23	582.26	18.97	31.691			
4,200.00	4,175.56	4,079.42	4,024.09	10.11	10.52	112.28	325.23	474.76	630.39	611.02	19.37	32.549			
4,300.00	4,274.70	4,175.03	4,116.44	10.30	10.82	112.54	332.71	498.35	659.57	639.80	19.77	33.369			
4,400.00	4,373.85	4,270.64	4,208.79	10.49	11.12	112.78	340.18	521.94	688.76	668.59	20.16	34.156			
4,500.00	4,472.99	4,366.25	4,301.14	10.69	11.42	112.99	347.65	545.53	717.95	697.39	20.57	34.910			
4,600.00	4,572.14	4,461.85	4,393.49	10.88	11.72	113.19	355.12	569.13	747.16	726.19	20.97	35.634			
4,700.00	4,671.28	4,557.46	4,485.85	11.08	12.02	113.38	362.59	592.72	776.37	755.00	21.37	36.325			
4,702.13	4,673.39	4,559.50	4,487.81	11.08	12.03	113.38	362.75	593.22	776.99	755.61	21.38	36.340			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 69 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 217H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)												Rule Assigned:			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Reference (usft)	Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Minimum Separation (usft)	Separation Factor	Warning		
							+N/-S (usft)	+E/-W (usft)							
4,800.00	4,770.58	4,653.23	4,578.35	11.28	12.33	113.87	370.08	616.35	805.11	783.34	21.77	36.984			
4,900.00	4,870.15	4,749.30	4,671.15	11.48	12.64	114.17	377.59	640.06	832.84	810.69	22.15	37.599			
5,000.00	4,969.93	4,845.60	4,764.17	11.67	12.95	114.30	385.11	663.82	859.54	837.02	22.51	38.178			
5,100.00	5,069.85	4,942.07	4,857.34	11.85	13.26	114.27	392.65	687.62	885.23	862.37	22.86	38.727			
5,200.00	5,169.84	5,038.63	4,950.62	11.99	13.58	114.09	400.20	711.45	909.93	886.75	23.18	39.259			
5,202.16	5,172.00	5,040.72	4,952.64	12.00	13.58	93.85	400.36	711.96	910.46	887.27	23.18	39.270			
5,300.00	5,269.84	5,135.22	5,043.92	12.08	13.89	93.28	407.75	735.28	934.18	910.70	23.48	39.788			
5,400.00	5,369.84	5,231.82	5,137.22	12.17	14.21	92.73	415.30	759.12	958.51	934.73	23.78	40.301			
5,500.00	5,469.84	5,328.41	5,230.52	12.26	14.52	92.21	422.85	782.95	982.92	958.84	24.09	40.807			
5,600.00	5,569.84	5,436.20	5,334.71	12.34	14.87	91.66	431.19	809.31	1,007.22	982.78	24.44	41.216			
5,700.00	5,669.84	5,566.43	5,461.41	12.43	15.26	91.10	440.27	837.98	1,029.13	1,004.24	24.89	41.350			
5,800.00	5,769.84	5,698.63	5,591.00	12.52	15.62	90.64	448.15	862.85	1,047.89	1,022.57	25.32	41.391			
5,900.00	5,869.84	5,832.53	5,723.10	12.61	15.93	90.27	454.75	883.67	1,063.42	1,037.70	25.72	41.348			
6,000.00	5,969.84	5,967.83	5,857.28	12.69	16.19	89.98	459.99	900.21	1,075.65	1,049.56	26.09	41.225			
6,100.00	6,069.84	6,104.20	5,993.05	12.78	16.41	89.78	463.81	912.29	1,084.52	1,058.09	26.43	41.026			
6,200.00	6,169.84	6,241.32	6,129.93	12.87	16.58	89.66	466.18	919.77	1,089.99	1,063.25	26.74	40.767			
6,300.00	6,269.84	6,378.81	6,267.39	12.96	16.70	89.61	467.06	922.56	1,092.02	1,065.06	26.96	40.510			
6,400.00	6,369.84	6,482.26	6,370.84	13.04	16.75	89.61	467.07	922.58	1,092.04	1,064.93	27.10	40.294			
6,500.00	6,469.84	6,582.26	6,470.84	13.13	16.81	89.61	467.07	922.58	1,092.04	1,064.79	27.25	40.077			
6,600.00	6,569.84	6,682.26	6,570.84	13.22	16.87	89.61	467.07	922.58	1,092.04	1,064.64	27.39	39.863			
6,700.00	6,669.84	6,782.26	6,670.84	13.30	16.93	89.61	467.07	922.58	1,092.04	1,064.49	27.54	39.650			
6,800.00	6,769.84	6,882.26	6,770.84	13.39	16.99	89.61	467.07	922.58	1,092.04	1,064.35	27.69	39.440			
6,900.00	6,869.84	6,982.26	6,870.84	13.48	17.04	89.61	467.07	922.58	1,092.04	1,064.20	27.84	39.231			
7,000.00	6,969.84	7,082.26	6,970.84	13.56	17.10	89.61	467.07	922.58	1,092.04	1,064.05	27.98	39.025			
7,100.00	7,069.84	7,182.26	7,070.84	13.65	17.16	89.61	467.07	922.58	1,092.04	1,063.90	28.13	38.821			
7,200.00	7,169.84	7,282.26	7,170.84	13.74	17.22	89.61	467.07	922.58	1,092.04	1,063.76	28.28	38.618			
7,300.00	7,269.84	7,382.26	7,270.84	13.82	17.28	89.61	467.07	922.58	1,092.04	1,063.61	28.43	38.418			
7,400.00	7,369.84	7,482.26	7,370.84	13.91	17.34	89.61	467.07	922.58	1,092.04	1,063.46	28.57	38.219			
7,500.00	7,469.84	7,582.26	7,470.84	14.00	17.40	89.61	467.07	922.58	1,092.04	1,063.31	28.72	38.022			
7,600.00	7,569.84	7,682.26	7,570.84	14.08	17.46	89.61	467.07	922.58	1,092.04	1,063.17	28.87	37.827			
7,700.00	7,669.84	7,782.26	7,670.84	14.17	17.52	89.61	467.07	922.58	1,092.04	1,063.02	29.02	37.634			
7,800.00	7,769.84	7,882.26	7,770.84	14.26	17.58	89.61	467.07	922.58	1,092.04	1,062.87	29.17	37.443			
7,900.00	7,869.84	7,982.26	7,870.84	14.34	17.64	89.61	467.07	922.58	1,092.04	1,062.72	29.31	37.254			
8,000.00	7,969.84	8,082.26	7,970.84	14.43	17.70	89.61	467.07	922.58	1,092.04	1,062.57	29.46	37.066			
8,100.00	8,069.84	8,182.26	8,070.84	14.51	17.76	89.61	467.07	922.58	1,092.04	1,062.42	29.61	36.880			
8,200.00	8,169.84	8,282.26	8,170.84	14.60	17.82	89.61	467.07	922.58	1,092.04	1,062.28	29.76	36.696			
8,300.00	8,269.84	8,382.26	8,270.84	14.69	17.88	89.61	467.07	922.58	1,092.04	1,062.13	29.91	36.513			
8,400.00	8,369.84	8,482.26	8,370.84	14.77	17.94	89.61	467.07	922.58	1,092.04	1,061.98	30.06	36.332			
8,500.00	8,469.84	8,582.26	8,470.84	14.86	18.00	89.61	467.07	922.58	1,092.04	1,061.83	30.21	36.153			
8,600.00	8,569.84	8,682.26	8,570.84	14.94	18.07	89.61	467.07	922.58	1,092.04	1,061.68	30.36	35.975			
8,700.00	8,669.84	8,782.26	8,670.84	15.03	18.13	89.61	467.07	922.58	1,092.04	1,061.53	30.50	35.799			
8,800.00	8,769.84	8,882.26	8,770.84	15.12	18.19	89.61	467.07	922.58	1,092.04	1,061.38	30.65	35.625			
8,900.00	8,869.84	8,982.26	8,870.84	15.20	18.25	89.61	467.07	922.58	1,092.04	1,061.23	30.80	35.452			
9,000.00	8,969.84	9,082.26	8,970.84	15.29	18.31	89.61	467.07	922.58	1,092.04	1,061.08	30.95	35.280			
9,100.00	9,069.84	9,182.26	9,070.84	15.37	18.38	89.61	467.07	922.58	1,092.04	1,060.93	31.10	35.111			
9,200.00	9,169.84	9,282.26	9,170.84	15.46	18.44	89.61	467.07	922.58	1,092.04	1,060.78	31.25	34.942			
9,300.00	9,269.84	9,382.26	9,270.84	15.54	18.50	89.61	467.07	922.58	1,092.04	1,060.63	31.40	34.776			
9,400.00	9,369.84	9,482.26	9,370.84	15.63	18.56	89.61	467.07	922.58	1,092.04	1,060.48	31.55	34.610			
9,500.00	9,469.84	9,582.26	9,470.84	15.71	18.63	89.61	467.07	922.58	1,092.04	1,060.33	31.70	34.446			
9,600.00	9,569.84	9,682.26	9,570.84	15.80	18.69	89.61	467.07	922.58	1,092.04	1,060.18	31.85	34.284			
9,700.00	9,669.84	9,782.26	9,670.84	15.89	18.75	89.61	467.07	922.58	1,092.04	1,060.03	32.00	34.123			
9,800.00	9,769.84	9,882.26	9,770.84	15.97	18.82	89.61	467.07	922.58	1,092.04	1,059.88	32.15	33.963			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 70 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 221H - OH - Plan 1														Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)														Offset Well Error:	0.50 usft
Reference Measured Depth (usft)	Vertical Depth (usft)	Offset Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre		Distance Between Centres (usft)		Rule Assigned: Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
							+N/-S (usft)	+E/-W (usft)							
0.00	0.00	1.00	1.00	0.50	0.50	-135.00	-25.00	-25.00	35.36						
100.00	100.00	101.00	101.00	0.98	0.99	-135.00	-25.00	-25.00	35.36	33.39		1.97	17.968		
200.00	200.00	201.00	201.00	1.56	1.57	-135.00	-25.00	-25.00	35.36	32.23		3.13	11.309		
300.00	300.00	301.00	301.00	1.98	1.98	-135.00	-25.00	-25.00	35.36	31.39		3.97	8.915		
400.00	400.00	401.00	401.00	2.33	2.33	-135.00	-25.00	-25.00	35.36	30.69		4.66	7.584		
500.00	500.00	501.00	501.00	2.63	2.64	-135.00	-25.00	-25.00	35.36	30.08		5.27	6.707		
600.00	600.00	601.00	601.00	2.91	2.91	-135.00	-25.00	-25.00	35.36	29.53		5.82	6.072		
700.00	700.00	701.00	701.00	3.16	3.17	-135.00	-25.00	-25.00	35.36	29.03		6.33	5.585		
800.00	800.00	801.06	801.05	3.40	3.46	-132.84	-23.98	-25.86	35.26	28.46		6.80	5.184		
812.15	812.15	813.21	813.19	3.43	3.49	-112.08	-23.71	-26.08	35.26	28.40		6.86	5.140	CC, ES	
900.00	899.99	901.03	900.94	3.68	3.74	-108.20	-20.95	-28.40	35.68	28.43		7.25	4.921		
1,000.00	999.91	1,000.92	1,000.61	3.94	4.00	-103.80	-15.92	-32.62	37.19	29.52		7.67	4.848	SF	
1,100.00	1,099.77	1,100.80	1,100.12	4.15	4.11	-98.78	-9.36	-38.12	39.48	31.50		7.98	4.946		
1,200.00	1,199.63	1,200.71	1,199.65	4.35	4.32	-94.16	-2.69	-43.72	42.08	33.70		8.38	5.020		
1,250.43	1,250.00	1,251.10	1,249.85	4.40	4.42	-92.05	0.67	-46.54	43.48	34.95		8.53	5.097		
1,300.00	1,299.48	1,300.63	1,299.19	4.45	4.52	-90.49	3.98	-49.32	44.92	36.24		8.68	5.178		
1,400.00	1,399.17	1,400.58	1,398.76	4.69	4.72	-89.97	10.65	-54.92	47.87	38.81		9.06	5.284		
1,500.00	1,498.62	1,500.51	1,498.31	4.93	4.92	-92.45	17.33	-60.52	50.86	41.43		9.43	5.393		
1,550.47	1,548.70	1,550.91	1,548.52	4.99	5.02	-94.68	20.69	-63.34	52.48	42.91		9.57	5.482		
1,600.00	1,597.81	1,600.36	1,597.78	5.05	5.12	-97.09	23.99	-66.11	54.18	44.47		9.71	5.577		
1,700.00	1,696.95	1,700.20	1,697.24	5.25	5.32	-101.52	30.66	-71.70	57.88	47.79		10.09	5.736		
1,800.00	1,796.09	1,800.04	1,796.70	5.44	5.51	-105.39	37.32	-77.30	61.89	51.42		10.47	5.911		
1,900.00	1,895.24	1,899.88	1,896.16	5.64	5.70	-108.78	43.99	-82.89	66.14	55.29		10.85	6.097		
2,000.00	1,994.38	1,999.71	1,995.61	5.83	5.89	-111.76	50.66	-88.48	70.60	59.37		11.23	6.288		
2,100.00	2,093.53	2,099.55	2,095.07	6.03	6.09	-114.37	57.32	-94.08	75.22	63.62		11.61	6.482		
2,200.00	2,192.67	2,199.39	2,194.53	6.22	6.28	-116.68	63.99	-99.67	79.99	68.00		11.99	6.671		
2,300.00	2,291.82	2,298.50	2,293.16	6.42	6.48	-117.98	71.01	-106.29	85.27	72.91		12.35	6.902		
2,400.00	2,390.96	2,397.48	2,391.42	6.61	6.69	-117.62	78.92	-115.29	91.49	78.77		12.72	7.194		
2,500.00	2,490.11	2,496.26	2,489.15	6.81	6.91	-115.92	87.71	-126.64	98.68	85.61		13.08	7.546		
2,600.00	2,589.25	2,594.71	2,586.16	7.00	7.12	-113.21	97.36	-140.31	107.04	93.61		13.44	7.966		
2,700.00	2,688.39	2,692.68	2,682.26	7.20	7.33	-109.80	107.82	-156.23	116.83	103.03		13.80	8.468		
2,800.00	2,787.54	2,791.75	2,779.16	7.39	7.53	-106.37	118.88	-173.61	127.71	113.54		14.18	9.010		
2,900.00	2,886.68	2,890.89	2,876.13	7.59	7.72	-103.47	129.94	-191.00	138.98	124.42		14.56	9.542		
3,000.00	2,985.83	2,990.02	2,973.10	7.78	7.92	-101.02	141.01	-208.39	150.55	135.59		14.96	10.063		
3,100.00	3,084.97	3,089.16	3,070.07	7.98	8.13	-98.91	152.07	-225.78	162.35	146.99		15.36	10.570		
3,200.00	3,184.12	3,188.30	3,167.04	8.17	8.33	-97.09	163.14	-243.17	174.34	158.58		15.76	11.061		
3,300.00	3,283.26	3,287.43	3,264.01	8.36	8.54	-95.51	174.20	-260.56	186.48	170.31		16.17	11.535		
3,400.00	3,382.40	3,386.57	3,360.98	8.56	8.75	-94.12	185.27	-277.95	198.74	182.17		16.57	11.992		
3,500.00	3,481.55	3,485.71	3,457.95	8.75	8.97	-92.89	196.33	-295.34	211.11	194.13		16.98	12.433		
3,600.00	3,580.69	3,584.85	3,554.92	8.95	9.19	-91.80	207.40	-312.73	223.56	206.17		17.39	12.856		
3,700.00	3,679.84	3,683.98	3,651.89	9.14	9.41	-90.83	218.46	-330.12	236.08	218.28		17.80	13.264		
3,800.00	3,778.98	3,783.12	3,748.87	9.33	9.64	-89.95	229.53	-347.51	248.66	230.45		18.21	13.656		
3,900.00	3,878.13	3,882.26	3,845.84	9.53	9.88	-89.16	240.60	-364.90	261.30	242.68		18.62	14.033		
4,000.00	3,977.27	3,981.39	3,942.81	9.72	10.12	-88.44	251.66	-382.29	273.98	254.95		19.03	14.397		
4,100.00	4,076.42	4,080.53	4,039.78	9.91	10.36	-87.78	262.73	-399.68	286.70	267.25		19.44	14.745		
4,200.00	4,175.56	4,179.67	4,136.75	10.11	10.61	-87.18	273.79	-417.07	299.45	279.59		19.86	15.080		
4,300.00	4,274.70	4,278.80	4,233.72	10.30	10.85	-86.63	284.86	-434.46	312.23	291.96		20.27	15.403		
4,400.00	4,373.85	4,377.94	4,330.69	10.49	11.11	-86.12	295.92	-451.85	325.04	304.35		20.68	15.715		
4,500.00	4,472.99	4,477.08	4,427.66	10.69	11.36	-85.65	306.99	-469.24	337.87	316.77		21.10	16.015		
4,600.00	4,572.14	4,576.21	4,524.63	10.88	11.62	-85.22	318.05	-486.63	350.72	329.21		21.51	16.304		
4,700.00	4,671.28	4,675.35	4,621.60	11.08	11.87	-84.81	329.12	-504.02	363.59	341.66		21.93	16.581		
4,702.13	4,673.39	4,677.46	4,623.66	11.08	11.88	-84.80	329.35	-504.39	363.87	341.93		21.94	16.587		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 74 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 221H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
9,900.00	9,869.84	9,946.49	9,870.84	16.06	17.85	-90.39	456.00	-703.43	534.01	501.65	32.36	16.501	
10,000.00	9,969.84	10,046.49	9,970.84	16.14	17.92	-90.39	456.00	-703.43	534.01	501.49	32.52	16.421	
10,100.00	10,069.84	10,146.49	10,070.84	16.23	17.99	-90.39	456.00	-703.43	534.01	501.34	32.68	16.342	
10,200.00	10,169.84	10,246.49	10,170.84	16.31	18.07	-90.39	456.00	-703.43	534.01	501.18	32.83	16.264	
10,300.00	10,269.84	10,346.49	10,270.84	16.40	18.14	-90.39	456.00	-703.43	534.01	501.02	32.99	16.186	
10,400.00	10,369.84	10,446.49	10,370.84	16.48	18.21	-90.39	456.00	-703.43	534.01	500.86	33.15	16.109	
10,500.00	10,469.84	10,546.49	10,470.84	16.57	18.29	-90.39	456.00	-703.43	534.01	500.71	33.31	16.033	
10,600.00	10,569.84	10,646.49	10,570.84	16.65	18.36	-90.39	456.00	-703.43	534.01	500.55	33.46	15.957	
10,700.00	10,669.84	10,746.49	10,670.84	16.74	18.43	-90.39	456.00	-703.43	534.01	500.39	33.62	15.883	
10,800.00	10,769.84	10,846.49	10,770.84	16.82	18.51	-90.39	456.00	-703.43	534.01	500.23	33.78	15.808	
10,900.00	10,869.84	10,946.49	10,870.84	16.91	18.58	-90.39	456.00	-703.43	534.01	500.07	33.94	15.735	
11,000.00	10,969.84	11,046.49	10,970.84	16.99	18.66	-90.39	456.00	-703.43	534.01	499.92	34.10	15.662	
11,100.00	11,069.84	11,146.49	11,070.84	17.08	18.73	-90.39	456.00	-703.43	534.01	499.76	34.25	15.590	
11,200.00	11,169.84	11,246.49	11,170.84	17.16	18.80	-90.39	456.00	-703.43	534.01	499.60	34.41	15.518	
11,300.00	11,269.84	11,346.49	11,270.84	17.25	18.88	-90.39	456.00	-703.43	534.01	499.44	34.57	15.447	
11,400.00	11,369.84	11,446.49	11,370.84	17.33	18.95	-90.39	456.00	-703.43	534.01	499.28	34.73	15.377	
11,500.00	11,469.84	11,546.49	11,470.84	17.42	19.03	-90.39	456.00	-703.43	534.01	499.13	34.89	15.308	
11,581.16	11,551.00	11,627.66	11,552.00	17.48	19.09	-90.39	456.00	-703.43	534.01	499.01	35.00	15.255	
11,600.00	11,569.83	11,646.49	11,570.83	17.48	19.10	90.14	456.00	-703.43	534.01	499.00	35.02	15.250	
11,650.00	11,619.67	11,696.33	11,620.67	17.49	19.14	90.54	456.00	-703.43	534.04	499.01	35.02	15.249	
11,700.00	11,668.99	11,745.64	11,669.99	17.51	19.17	91.39	456.00	-703.43	534.18	499.17	35.00	15.261	
11,750.00	11,717.40	11,794.06	11,718.40	17.51	19.21	92.63	456.00	-703.43	534.63	499.66	34.96	15.290	
11,800.00	11,764.55	11,841.21	11,765.55	17.52	19.24	94.20	456.00	-703.43	535.68	500.77	34.91	15.344	
11,850.00	11,810.08	11,886.74	11,811.08	17.52	19.28	96.00	456.00	-703.43	537.70	502.85	34.85	15.430	
11,900.00	11,853.63	11,930.29	11,854.63	17.52	19.31	97.91	456.00	-703.43	541.12	506.33	34.79	15.555	
11,950.00	11,894.88	11,971.54	11,895.88	17.53	19.34	99.83	456.00	-703.43	546.39	511.65	34.73	15.730	
12,000.00	11,933.52	12,010.17	11,934.52	17.53	19.37	101.61	456.00	-703.43	553.97	519.26	34.70	15.963	
12,050.00	11,969.24	12,045.90	11,970.24	17.53	19.40	103.13	456.00	-703.43	564.27	529.57	34.70	16.260	
12,100.00	12,001.78	12,078.44	12,002.78	17.53	19.42	104.28	456.00	-703.43	577.65	542.91	34.74	16.628	
12,150.00	12,030.89	12,107.54	12,031.89	17.53	19.44	104.94	456.00	-703.43	594.33	559.51	34.82	17.071	
12,200.00	12,056.34	12,133.00	12,057.34	17.53	19.46	105.01	456.00	-703.43	614.43	579.50	34.93	17.590	
12,250.00	12,077.95	12,154.61	12,078.95	17.54	19.48	104.39	456.00	-703.43	637.93	602.85	35.08	18.185	
12,300.00	12,095.55	12,172.21	12,096.55	17.55	19.49	102.98	456.00	-703.43	664.67	629.42	35.25	18.853	
12,350.00	12,109.01	12,185.67	12,110.01	17.56	19.50	100.68	456.00	-703.43	694.41	658.97	35.45	19.591	
12,400.00	12,118.22	12,194.88	12,119.22	17.58	19.51	97.43	456.00	-703.43	726.80	691.16	35.64	20.391	
12,450.00	12,123.11	12,199.77	12,124.11	17.60	19.51	93.16	456.00	-703.43	761.42	725.58	35.84	21.244	
12,476.17	12,123.94	12,200.59	12,124.94	17.61	19.51	90.53	456.00	-703.43	780.28	744.34	35.94	21.708	
12,500.00	12,124.14	12,200.80	12,125.14	17.62	19.51	90.55	456.00	-703.43	797.82	761.79	36.03	22.141	
12,600.00	12,125.02	12,201.67	12,126.02	17.69	19.51	90.65	456.00	-703.43	874.68	838.28	36.40	24.031	
12,700.00	12,125.89	13,453.78	12,856.70	17.79	21.08	140.24	-310.04	-770.10	949.82	901.59	48.23	19.693	
12,800.00	12,126.76	13,574.69	12,857.76	17.95	21.54	140.17	-430.94	-770.76	950.68	902.13	48.55	19.581	
12,900.00	12,127.63	13,674.69	12,858.64	18.21	21.97	140.17	-530.93	-769.90	950.68	901.77	48.91	19.437	
13,000.00	12,128.50	13,774.69	12,859.51	18.61	22.46	140.17	-630.92	-769.03	950.69	901.35	49.34	19.268	
13,100.00	12,129.37	13,874.69	12,860.39	19.18	23.00	140.17	-730.92	-768.17	950.69	900.85	49.84	19.075	
13,200.00	12,130.24	13,974.69	12,861.27	19.87	23.61	140.17	-830.91	-767.31	950.70	900.30	50.40	18.862	
13,300.00	12,131.11	14,074.69	12,862.15	20.66	24.27	140.17	-930.90	-766.45	950.70	899.68	51.03	18.631	
13,400.00	12,131.99	14,174.69	12,863.03	21.53	24.99	140.17	-1,030.89	-765.59	950.71	898.99	51.72	18.383	
13,500.00	12,132.86	14,274.69	12,863.90	22.45	25.76	140.17	-1,130.89	-764.73	950.72	898.25	52.47	18.121	
13,600.00	12,133.73	14,374.69	12,864.78	23.43	26.58	140.17	-1,230.88	-763.87	950.72	897.45	53.27	17.847	
13,700.00	12,134.60	14,474.69	12,865.66	24.44	27.45	140.17	-1,330.87	-763.01	950.73	896.60	54.13	17.565	
13,800.00	12,135.47	14,574.69	12,866.54	25.50	28.35	140.17	-1,430.86	-762.15	950.73	895.70	55.04	17.275	
13,900.00	12,136.34	14,674.69	12,867.41	26.58	29.30	140.17	-1,530.86	-761.29	950.74	894.74	55.99	16.979	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 76 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 221H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)												Rule Assigned:			
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
19,200.00	12,182.52	19,974.69	12,913.94	95.31	95.70	140.18	-6,830.46	-715.69	951.03	813.26	137.77	6.903			
19,300.00	12,183.39	20,074.69	12,914.82	96.66	97.04	140.18	-6,930.45	-714.83	951.03	811.49	139.54	6.815			
19,400.00	12,184.26	20,174.69	12,915.70	98.01	98.38	140.18	-7,030.44	-713.97	951.04	809.72	141.32	6.730			
19,500.00	12,185.13	20,274.69	12,916.58	99.36	99.72	140.18	-7,130.43	-713.11	951.04	807.95	143.10	6.646			
19,600.00	12,186.00	20,374.69	12,917.45	100.72	101.06	140.18	-7,230.43	-712.25	951.05	806.17	144.88	6.564			
19,700.00	12,186.87	20,474.69	12,918.33	102.07	102.40	140.18	-7,330.42	-711.39	951.05	804.39	146.66	6.485			
19,800.00	12,187.75	20,574.69	12,919.21	103.42	103.75	140.18	-7,430.41	-710.53	951.06	802.61	148.45	6.407			
19,900.00	12,188.62	20,674.69	12,920.09	104.78	105.09	140.18	-7,530.40	-709.67	951.07	800.83	150.24	6.330			
20,000.00	12,189.49	20,774.69	12,920.97	106.13	106.43	140.18	-7,630.40	-708.81	951.07	799.04	152.03	6.256			
20,100.00	12,190.36	20,874.69	12,921.84	107.49	107.78	140.18	-7,730.39	-707.95	951.08	797.25	153.82	6.183			
20,200.00	12,191.23	20,974.69	12,922.72	108.84	109.13	140.18	-7,830.38	-707.09	951.08	795.46	155.62	6.112			
20,300.00	12,192.10	21,074.69	12,923.60	110.20	110.47	140.18	-7,930.37	-706.23	951.09	793.67	157.42	6.042			
20,400.00	12,192.97	21,174.69	12,924.48	111.55	111.82	140.18	-8,030.37	-705.37	951.09	791.88	159.22	5.974			
20,500.00	12,193.85	21,274.69	12,925.36	112.91	113.17	140.18	-8,130.36	-704.51	951.10	790.08	161.02	5.907			
20,600.00	12,194.72	21,374.69	12,926.23	114.27	114.52	140.18	-8,230.35	-703.65	951.10	788.28	162.82	5.841			
20,700.00	12,195.59	21,474.69	12,927.11	115.62	115.87	140.18	-8,330.34	-702.79	951.11	786.48	164.63	5.777			
20,800.00	12,196.46	21,574.69	12,927.99	116.98	117.22	140.18	-8,430.34	-701.93	951.12	784.68	166.44	5.715			
20,900.00	12,197.33	21,674.69	12,928.87	118.34	118.57	140.18	-8,530.33	-701.07	951.12	782.87	168.25	5.653			
21,000.00	12,198.20	21,774.69	12,929.74	119.70	119.92	140.18	-8,630.32	-700.21	951.13	781.07	170.06	5.593			
21,100.00	12,199.07	21,874.69	12,930.62	121.05	121.27	140.18	-8,730.31	-699.35	951.13	779.26	171.87	5.534			
21,200.00	12,199.94	21,974.69	12,931.50	122.41	122.62	140.19	-8,830.31	-698.49	951.14	777.45	173.69	5.476			
21,300.00	12,200.82	22,074.69	12,932.38	123.77	123.97	140.19	-8,930.30	-697.63	951.14	775.64	175.50	5.420			
21,400.00	12,201.69	22,174.69	12,933.26	125.13	125.32	140.19	-9,030.29	-696.77	951.15	773.83	177.32	5.364			
21,500.00	12,202.56	22,274.69	12,934.13	126.49	126.67	140.19	-9,130.28	-695.90	951.15	772.01	179.14	5.310			
21,600.00	12,203.43	22,374.69	12,935.01	127.85	128.03	140.19	-9,230.28	-695.04	951.16	770.20	180.96	5.256			
21,700.00	12,204.30	22,474.69	12,935.89	129.21	129.38	140.19	-9,330.27	-694.18	951.16	768.38	182.78	5.204			
21,800.00	12,205.17	22,574.69	12,936.77	130.57	130.73	140.19	-9,430.26	-693.32	951.17	766.56	184.61	5.152			
21,900.00	12,206.04	22,674.69	12,937.65	131.93	132.09	140.19	-9,530.25	-692.46	951.18	764.75	186.43	5.102			
22,000.00	12,206.91	22,774.69	12,938.52	133.29	133.44	140.19	-9,630.24	-691.60	951.18	762.92	188.26	5.053			
22,100.00	12,207.79	22,874.69	12,939.40	134.65	134.80	140.19	-9,730.24	-690.74	951.19	761.10	190.08	5.004			
22,200.00	12,208.66	22,974.69	12,940.28	136.01	136.15	140.19	-9,830.23	-689.88	951.19	759.28	191.91	4.956			
22,300.00	12,209.53	23,074.69	12,941.16	137.37	137.51	140.19	-9,930.22	-689.02	951.20	757.46	193.74	4.910			
22,400.00	12,210.40	23,174.69	12,942.04	138.73	138.77	140.19	-10,030.21	-688.16	951.20	755.74	195.46	4.866			
22,411.61	12,210.50	23,186.30	12,942.14	138.89	138.91	140.19	-10,041.83	-688.06	951.20	755.55	195.66	4.862			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 78 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 222H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Major Axis (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
0.00	0.00	0.00	0.00	0.50	0.50	-8.88	160.00	-25.00	161.94				
100.00	100.00	100.00	100.00	0.98	0.98	-8.88	160.00	-25.00	161.94	159.98	1.96	82.531	
200.00	200.00	200.00	200.00	1.56	1.56	-8.88	160.00	-25.00	161.94	158.82	3.12	51.867	
300.00	300.00	300.00	300.00	1.98	1.98	-8.88	160.00	-25.00	161.94	157.98	3.96	40.870	
400.00	400.00	400.00	400.00	2.33	2.33	-8.88	160.00	-25.00	161.94	157.28	4.66	34.760	
500.00	500.00	500.00	500.00	2.63	2.63	-8.88	160.00	-25.00	161.94	156.67	5.27	30.735	
600.00	600.00	600.00	600.00	2.91	2.91	-8.88	160.00	-25.00	161.94	156.12	5.82	27.824	
700.00	700.00	700.00	700.00	3.16	3.16	-8.88	160.00	-25.00	161.94	155.61	6.33	25.593	
800.00	800.00	800.00	800.00	3.40	3.40	-8.88	160.00	-25.00	161.94	155.14	6.80	23.811	
900.00	899.99	899.99	899.99	3.68	3.62	11.45	160.00	-25.00	160.66	153.36	7.30	22.006	
1,000.00	999.91	999.91	999.91	3.94	3.84	11.74	160.00	-25.00	156.81	149.04	7.77	20.171	
1,100.00	1,099.77	1,099.77	1,099.77	4.15	4.04	12.14	160.00	-25.00	151.69	143.51	8.18	18.543	
1,200.00	1,199.63	1,199.63	1,199.63	4.35	4.23	12.57	160.00	-25.00	146.58	138.00	8.57	17.095	
1,250.43	1,250.00	1,250.00	1,250.00	4.40	4.33	12.80	160.00	-25.00	144.00	135.28	8.72	16.516	
1,300.00	1,299.48	1,299.48	1,299.48	4.45	4.42	13.08	160.00	-25.00	141.16	132.30	8.86	15.924	
1,400.00	1,399.17	1,399.17	1,399.17	4.69	4.60	13.87	160.00	-25.00	133.54	124.26	9.28	14.383	
1,500.00	1,498.62	1,498.62	1,498.62	4.93	4.77	15.07	160.00	-25.00	123.43	113.73	9.69	12.732	
1,550.47	1,548.70	1,548.63	1,548.63	4.99	4.88	16.04	160.04	-24.69	117.41	107.57	9.83	11.939	
1,600.00	1,597.81	1,597.61	1,597.60	5.05	4.97	17.44	160.15	-23.76	111.27	101.30	9.97	11.164	
1,700.00	1,696.95	1,696.28	1,696.20	5.25	5.16	21.88	160.61	-20.00	99.37	89.07	10.30	9.645	
1,800.00	1,796.09	1,794.53	1,794.24	5.44	5.35	29.02	161.38	-13.73	88.89	78.26	10.63	8.363	
1,900.00	1,895.24	1,892.80	1,892.15	5.64	5.43	39.16	162.40	-5.43	81.04	70.16	10.88	7.452	
2,000.00	1,994.38	1,991.30	1,990.28	5.83	5.58	51.10	163.45	3.09	76.39	65.22	11.18	6.834	
2,073.34	2,067.10	2,063.55	2,062.25	5.98	5.69	60.48	164.22	9.34	75.34	63.94	11.40	6.608	CC, ES
2,100.00	2,093.53	2,089.81	2,088.41	6.03	5.73	63.91	164.50	11.61	75.48	64.00	11.48	6.573	
2,200.00	2,192.67	2,188.32	2,186.54	6.22	5.89	76.39	165.54	20.14	78.44	66.63	11.80	6.645	
2,300.00	2,291.82	2,285.06	2,282.84	6.42	6.05	87.14	167.16	29.19	85.73	73.60	12.13	7.067	
2,400.00	2,390.96	2,381.29	2,378.41	6.61	6.23	95.31	170.33	40.01	97.85	85.38	12.47	7.845	
2,500.00	2,490.11	2,477.17	2,473.34	6.81	6.41	100.96	175.06	52.61	113.67	100.85	12.82	8.868	
2,600.00	2,589.25	2,572.57	2,567.45	7.00	6.59	104.59	181.30	66.92	132.32	119.16	13.16	10.055	
2,700.00	2,688.39	2,667.38	2,660.57	7.20	6.78	106.76	189.04	82.91	153.28	139.78	13.50	11.352	
2,800.00	2,787.54	2,763.59	2,754.72	7.39	6.95	108.03	198.12	100.55	175.91	162.06	13.85	12.700	
2,900.00	2,886.68	2,860.90	2,849.91	7.59	7.11	108.99	207.41	118.52	198.72	184.51	14.21	13.988	
3,000.00	2,985.83	2,958.22	2,945.10	7.78	7.28	109.75	216.70	136.49	221.58	207.01	14.57	15.212	
3,100.00	3,084.97	3,055.53	3,040.29	7.98	7.45	110.37	226.00	154.45	244.46	229.53	14.93	16.376	
3,200.00	3,184.12	3,152.85	3,135.48	8.17	7.62	110.88	235.29	172.42	267.37	252.08	15.29	17.484	
3,300.00	3,283.26	3,250.16	3,230.66	8.36	7.79	111.32	244.58	190.39	290.30	274.64	15.66	18.538	
3,400.00	3,382.40	3,347.48	3,325.85	8.56	7.97	111.69	253.87	208.35	313.23	297.21	16.03	19.542	
3,500.00	3,481.55	3,444.79	3,421.04	8.75	8.16	112.01	263.16	226.32	336.18	319.78	16.40	20.499	
3,600.00	3,580.69	3,542.11	3,516.23	8.95	8.39	112.28	272.45	244.29	359.14	342.37	16.77	21.411	
3,700.00	3,679.84	3,639.42	3,611.42	9.14	8.61	112.53	281.75	262.25	382.11	364.96	17.15	22.281	
3,800.00	3,778.98	3,736.74	3,706.61	9.33	8.84	112.75	291.04	280.22	405.08	387.55	17.53	23.112	
3,900.00	3,878.13	3,834.05	3,801.80	9.53	9.07	112.94	300.33	298.19	428.06	410.15	17.91	23.906	
4,000.00	3,977.27	3,931.37	3,896.99	9.72	9.30	113.11	309.62	316.15	451.04	432.75	18.29	24.665	
4,100.00	4,076.42	4,028.68	3,992.18	9.91	9.54	113.27	318.91	334.12	474.02	455.35	18.67	25.391	
4,200.00	4,175.56	4,126.00	4,087.37	10.11	9.77	113.41	328.21	352.09	497.01	477.96	19.05	26.087	
4,300.00	4,274.70	4,223.31	4,182.56	10.30	10.01	113.54	337.50	370.05	520.00	500.56	19.44	26.753	
4,400.00	4,373.85	4,320.63	4,277.75	10.49	10.25	113.66	346.79	388.02	542.99	523.17	19.82	27.391	
4,500.00	4,472.99	4,417.94	4,372.94	10.69	10.50	113.77	356.08	405.99	565.98	545.77	20.21	28.004	
4,600.00	4,572.14	4,515.26	4,468.13	10.88	10.74	113.87	365.37	423.95	588.98	568.38	20.60	28.592	
4,700.00	4,671.28	4,612.57	4,563.32	11.08	10.99	113.97	374.66	441.92	611.98	590.99	20.99	29.154	
4,702.13	4,673.39	4,614.65	4,565.35	11.08	10.99	113.97	374.86	442.30	612.47	591.47	21.00	29.166	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 79 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 222H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)							Rule Assigned:				Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Major Axis (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
4,800.00	4,770.58	4,710.01	4,658.63	11.28	11.23	114.26	383.97	459.91	634.48	613.10	21.37	29.685	
4,900.00	4,870.15	4,807.64	4,754.13	11.48	11.48	114.32	393.29	477.93	655.93	634.19	21.74	30.171	
5,000.00	4,969.93	4,905.41	4,849.76	11.67	11.73	114.19	402.63	495.98	676.36	654.27	22.09	30.620	
5,100.00	5,069.85	5,003.25	4,945.46	11.85	11.99	113.86	411.97	514.05	695.79	673.37	22.42	31.039	
5,200.00	5,169.84	5,101.09	5,041.17	11.99	12.24	113.36	421.31	532.11	714.27	691.55	22.72	31.440	
5,202.16	5,172.00	5,103.20	5,043.24	12.00	12.24	93.11	421.51	532.50	714.66	691.94	22.72	31.450	
5,300.00	5,269.84	5,207.29	5,145.12	12.08	12.48	92.25	431.30	551.43	732.12	709.12	23.00	31.825	
5,400.00	5,369.84	5,325.78	5,261.67	12.17	12.76	91.44	441.09	570.35	747.88	724.50	23.38	31.988	
5,500.00	5,469.84	5,445.52	5,380.06	12.26	13.01	90.79	449.28	586.20	761.01	737.28	23.74	32.060	
5,600.00	5,569.84	5,566.27	5,499.97	12.34	13.23	90.28	455.82	598.84	771.45	747.37	24.07	32.045	
5,700.00	5,669.84	5,687.81	5,621.05	12.43	13.41	89.93	460.64	608.15	779.11	754.72	24.39	31.947	
5,800.00	5,769.84	5,809.90	5,742.95	12.52	13.57	89.70	463.69	614.06	783.96	759.28	24.68	31.771	
5,900.00	5,869.84	5,932.29	5,865.31	12.61	13.68	89.61	464.95	616.50	785.96	761.06	24.90	31.558	
6,000.00	5,969.84	6,036.81	5,969.84	12.69	13.73	89.61	464.99	616.57	786.02	760.97	25.05	31.381	
6,100.00	6,069.84	6,136.81	6,069.84	12.78	13.81	89.61	464.99	616.57	786.02	760.81	25.21	31.182	
6,200.00	6,169.84	6,236.81	6,169.84	12.87	13.88	89.61	464.99	616.57	786.02	760.65	25.37	30.985	
6,300.00	6,269.84	6,336.81	6,269.84	12.96	13.95	89.61	464.99	616.57	786.02	760.49	25.53	30.791	
6,400.00	6,369.84	6,436.81	6,369.84	13.04	14.02	89.61	464.99	616.57	786.02	760.33	25.69	30.600	
6,500.00	6,469.84	6,536.81	6,469.84	13.13	14.10	89.61	464.99	616.57	786.02	760.17	25.85	30.410	
6,600.00	6,569.84	6,636.81	6,569.84	13.22	14.17	89.61	464.99	616.57	786.02	760.01	26.01	30.223	
6,700.00	6,669.84	6,736.81	6,669.84	13.30	14.24	89.61	464.99	616.57	786.02	759.85	26.17	30.039	
6,800.00	6,769.84	6,836.81	6,769.84	13.39	14.32	89.61	464.99	616.57	786.02	759.69	26.33	29.856	
6,900.00	6,869.84	6,936.81	6,869.84	13.48	14.39	89.61	464.99	616.57	786.02	759.53	26.49	29.676	
7,000.00	6,969.84	7,036.81	6,969.84	13.56	14.47	89.61	464.99	616.57	786.02	759.37	26.65	29.498	
7,100.00	7,069.84	7,136.81	7,069.84	13.65	14.54	89.61	464.99	616.57	786.02	759.21	26.81	29.322	
7,200.00	7,169.84	7,236.81	7,169.84	13.74	14.61	89.61	464.99	616.57	786.02	759.05	26.97	29.147	
7,300.00	7,269.84	7,336.81	7,269.84	13.82	14.69	89.61	464.99	616.57	786.02	758.89	27.13	28.975	
7,400.00	7,369.84	7,436.81	7,369.84	13.91	14.76	89.61	464.99	616.57	786.02	758.73	27.29	28.805	
7,500.00	7,469.84	7,536.81	7,469.84	14.00	14.84	89.61	464.99	616.57	786.02	758.57	27.45	28.637	
7,600.00	7,569.84	7,636.81	7,569.84	14.08	14.91	89.61	464.99	616.57	786.02	758.41	27.61	28.471	
7,700.00	7,669.84	7,736.81	7,669.84	14.17	14.98	89.61	464.99	616.57	786.02	758.25	27.77	28.307	
7,800.00	7,769.84	7,836.81	7,769.84	14.26	15.06	89.61	464.99	616.57	786.02	758.09	27.93	28.145	
7,900.00	7,869.84	7,936.81	7,869.84	14.34	15.13	89.61	464.99	616.57	786.02	757.93	28.09	27.984	
8,000.00	7,969.84	8,036.81	7,969.84	14.43	15.21	89.61	464.99	616.57	786.02	757.77	28.25	27.825	
8,100.00	8,069.84	8,136.81	8,069.84	14.51	15.28	89.61	464.99	616.57	786.02	757.61	28.41	27.668	
8,200.00	8,169.84	8,236.81	8,169.84	14.60	15.36	89.61	464.99	616.57	786.02	757.45	28.57	27.513	
8,300.00	8,269.84	8,336.81	8,269.84	14.69	15.43	89.61	464.99	616.57	786.02	757.29	28.73	27.360	
8,400.00	8,369.84	8,436.81	8,369.84	14.77	15.51	89.61	464.99	616.57	786.02	757.13	28.89	27.208	
8,500.00	8,469.84	8,536.81	8,469.84	14.86	15.58	89.61	464.99	616.57	786.02	756.97	29.05	27.058	
8,600.00	8,569.84	8,636.81	8,569.84	14.94	15.66	89.61	464.99	616.57	786.02	756.81	29.21	26.909	
8,700.00	8,669.84	8,736.81	8,669.84	15.03	15.73	89.61	464.99	616.57	786.02	756.65	29.37	26.762	
8,800.00	8,769.84	8,836.81	8,769.84	15.12	15.81	89.61	464.99	616.57	786.02	756.49	29.53	26.617	
8,900.00	8,869.84	8,936.81	8,869.84	15.20	15.88	89.61	464.99	616.57	786.02	756.33	29.69	26.473	
9,000.00	8,969.84	9,036.81	8,969.84	15.29	15.96	89.61	464.99	616.57	786.02	756.17	29.85	26.330	
9,100.00	9,069.84	9,136.81	9,069.84	15.37	16.03	89.61	464.99	616.57	786.02	756.01	30.01	26.190	
9,200.00	9,169.84	9,236.81	9,169.84	15.46	16.11	89.61	464.99	616.57	786.02	755.85	30.17	26.050	
9,300.00	9,269.84	9,336.81	9,269.84	15.54	16.19	89.61	464.99	616.57	786.02	755.68	30.33	25.912	
9,400.00	9,369.84	9,436.81	9,369.84	15.63	16.26	89.61	464.99	616.57	786.02	755.52	30.49	25.776	
9,500.00	9,469.84	9,536.81	9,469.84	15.71	16.34	89.61	464.99	616.57	786.02	755.36	30.65	25.641	
9,600.00	9,569.84	9,636.81	9,569.84	15.80	16.41	89.61	464.99	616.57	786.02	755.20	30.82	25.507	
9,700.00	9,669.84	9,736.81	9,669.84	15.89	16.49	89.61	464.99	616.57	786.02	755.04	30.98	25.375	
9,800.00	9,769.84	9,836.81	9,769.84	15.97	16.56	89.61	464.99	616.57	786.02	754.88	31.14	25.244	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 80 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 222H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:				Offset Well Error:		0.50 usft	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
13,900.00	12,136.34	14,666.68	12,870.27	26.58	29.72	-135.91	-1,519.54	558.69	1,021.90	965.23	56.68	18.030	
14,000.00	12,137.21	14,766.68	12,871.14	27.69	30.79	-135.91	-1,619.53	559.55	1,021.90	964.02	57.88	17.656	
14,100.00	12,138.08	14,866.68	12,872.01	28.82	31.89	-135.91	-1,719.52	560.41	1,021.90	962.78	59.12	17.284	
14,200.00	12,138.96	14,966.68	12,872.87	29.98	33.00	-135.91	-1,819.51	561.27	1,021.90	961.49	60.41	16.917	
14,300.00	12,139.83	15,066.68	12,873.74	31.15	34.14	-135.91	-1,919.51	562.14	1,021.89	960.16	61.73	16.554	
14,400.00	12,140.70	15,166.68	12,874.61	32.33	35.29	-135.91	-2,019.50	563.00	1,021.89	958.80	63.09	16.196	
14,500.00	12,141.57	15,266.68	12,875.48	33.54	36.46	-135.91	-2,119.49	563.86	1,021.89	957.40	64.49	15.846	
14,600.00	12,142.44	15,366.68	12,876.35	34.75	37.64	-135.91	-2,219.48	564.72	1,021.89	955.97	65.92	15.503	
14,700.00	12,143.31	15,466.68	12,877.21	35.98	38.84	-135.91	-2,319.48	565.58	1,021.88	954.51	67.37	15.168	
14,800.00	12,144.18	15,566.68	12,878.08	37.21	40.04	-135.91	-2,419.47	566.44	1,021.88	953.02	68.86	14.841	
14,900.00	12,145.05	15,666.68	12,878.95	38.46	41.26	-135.91	-2,519.46	567.30	1,021.88	951.51	70.37	14.522	
15,000.00	12,145.93	15,766.68	12,879.82	39.71	42.49	-135.91	-2,619.45	568.16	1,021.88	949.97	71.90	14.212	
15,100.00	12,146.80	15,866.68	12,880.69	40.97	43.72	-135.91	-2,719.45	569.02	1,021.87	948.41	73.46	13.910	
15,200.00	12,147.67	15,966.68	12,881.55	42.24	44.96	-135.91	-2,819.44	569.88	1,021.87	946.83	75.04	13.617	
15,300.00	12,148.54	16,066.68	12,882.42	43.51	46.21	-135.91	-2,919.43	570.74	1,021.87	945.22	76.65	13.332	
15,400.00	12,149.41	16,166.68	12,883.29	44.79	47.47	-135.91	-3,019.42	571.60	1,021.87	943.60	78.27	13.056	
15,500.00	12,150.28	16,266.68	12,884.16	46.08	48.73	-135.91	-3,119.42	572.46	1,021.86	941.96	79.90	12.789	
15,600.00	12,151.15	16,366.68	12,885.03	47.37	50.00	-135.91	-3,219.41	573.32	1,021.86	940.30	81.56	12.529	
15,700.00	12,152.02	16,466.68	12,885.89	48.66	51.28	-135.91	-3,319.40	574.19	1,021.86	938.63	83.23	12.278	
15,800.00	12,152.90	16,566.68	12,886.76	49.96	52.55	-135.91	-3,419.39	575.05	1,021.86	936.94	84.91	12.034	
15,900.00	12,153.77	16,666.68	12,887.63	51.26	53.84	-135.91	-3,519.39	575.91	1,021.85	935.24	86.61	11.798	
16,000.00	12,154.64	16,766.68	12,888.50	52.57	55.13	-135.91	-3,619.38	576.77	1,021.85	933.53	88.33	11.569	
16,100.00	12,155.51	16,866.68	12,889.37	53.88	56.42	-135.91	-3,719.37	577.63	1,021.85	931.80	90.05	11.348	
16,200.00	12,156.38	16,966.68	12,890.23	55.19	57.71	-135.91	-3,819.36	578.49	1,021.85	930.06	91.79	11.133	
16,300.00	12,157.25	17,066.68	12,891.10	56.50	59.01	-135.91	-3,919.36	579.35	1,021.84	928.31	93.54	10.925	
16,400.00	12,158.12	17,166.68	12,891.97	57.82	60.31	-135.91	-4,019.35	580.21	1,021.84	926.55	95.29	10.723	
16,500.00	12,158.99	17,266.68	12,892.84	59.14	61.62	-135.90	-4,119.34	581.07	1,021.84	924.78	97.06	10.528	
16,600.00	12,159.87	17,366.68	12,893.71	60.46	62.92	-135.90	-4,219.33	581.93	1,021.84	923.00	98.84	10.338	
16,700.00	12,160.74	17,466.68	12,894.57	61.79	64.23	-135.90	-4,319.33	582.79	1,021.83	921.21	100.63	10.155	
16,800.00	12,161.61	17,566.68	12,895.44	63.11	65.55	-135.90	-4,419.32	583.65	1,021.83	919.41	102.42	9.977	
16,900.00	12,162.48	17,666.68	12,896.31	64.44	66.86	-135.90	-4,519.31	584.51	1,021.83	917.60	104.22	9.804	
17,000.00	12,163.35	17,766.68	12,897.18	65.77	68.18	-135.90	-4,619.30	585.37	1,021.83	915.79	106.04	9.637	
17,100.00	12,164.22	17,866.68	12,898.05	67.10	69.50	-135.90	-4,719.30	586.24	1,021.82	913.97	107.85	9.474	
17,200.00	12,165.09	17,966.68	12,898.91	68.43	70.82	-135.90	-4,819.29	587.10	1,021.82	912.14	109.68	9.317	
17,300.00	12,165.96	18,066.68	12,899.78	69.77	72.14	-135.90	-4,919.28	587.96	1,021.82	910.31	111.51	9.164	
17,400.00	12,166.84	18,166.68	12,900.65	71.10	73.47	-135.90	-5,019.27	588.82	1,021.82	908.47	113.35	9.015	
17,500.00	12,167.71	18,266.68	12,901.52	72.44	74.79	-135.90	-5,119.27	589.68	1,021.81	906.62	115.19	8.871	
17,600.00	12,168.58	18,366.68	12,902.39	73.78	76.12	-135.90	-5,219.26	590.54	1,021.81	904.77	117.04	8.730	
17,700.00	12,169.45	18,466.68	12,903.25	75.12	77.45	-135.90	-5,319.25	591.40	1,021.81	902.92	118.89	8.594	
17,800.00	12,170.32	18,566.68	12,904.12	76.46	78.78	-135.90	-5,419.24	592.26	1,021.81	901.05	120.75	8.462	
17,900.00	12,171.19	18,666.68	12,904.99	77.80	80.11	-135.90	-5,519.24	593.12	1,021.80	899.19	122.62	8.333	
18,000.00	12,172.06	18,766.68	12,905.86	79.14	81.45	-135.90	-5,619.23	593.98	1,021.80	897.32	124.49	8.208	
18,100.00	12,172.93	18,866.68	12,906.73	80.48	82.78	-135.90	-5,719.22	594.84	1,021.80	895.44	126.36	8.086	
18,200.00	12,173.81	18,966.68	12,907.59	81.83	84.12	-135.90	-5,819.21	595.70	1,021.80	893.56	128.24	7.968	
18,300.00	12,174.68	19,066.68	12,908.46	83.17	85.45	-135.90	-5,919.21	596.56	1,021.79	891.68	130.12	7.853	
18,400.00	12,175.55	19,166.68	12,909.33	84.52	86.79	-135.90	-6,019.20	597.42	1,021.79	889.79	132.01	7.741	
18,500.00	12,176.42	19,266.68	12,910.20	85.86	88.13	-135.90	-6,119.19	598.29	1,021.79	887.89	133.90	7.631	
18,600.00	12,177.29	19,366.68	12,911.07	87.21	89.47	-135.90	-6,219.18	599.15	1,021.79	886.00	135.79	7.525	
18,700.00	12,178.16	19,466.68	12,911.93	88.56	90.81	-135.90	-6,319.18	600.01	1,021.78	884.10	137.68	7.421	
18,800.00	12,179.03	19,566.68	12,912.80	89.91	92.15	-135.90	-6,419.17	600.87	1,021.78	882.20	139.58	7.320	
18,900.00	12,179.90	19,666.68	12,913.67	91.26	93.50	-135.90	-6,519.16	601.73	1,021.78	880.29	141.49	7.222	
19,000.00	12,180.78	19,766.68	12,914.54	92.61	94.84	-135.90	-6,619.15	602.59	1,021.78	878.38	143.39	7.126	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 82 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 222H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)		Offset		Semi Major Axis		Offset Wellbore Centre			Rule Assigned:		Offset Well Error:		0.50 usft	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
19,100.00	12,181.65	19,866.68	12,915.41	93.96	96.18	-135.90	-6,719.15	603.45	1,021.78	876.47	145.30	7.032		
19,200.00	12,182.52	19,966.68	12,916.27	95.31	97.53	-135.90	-6,819.14	604.31	1,021.77	874.56	147.21	6.941		
19,300.00	12,183.39	20,066.68	12,917.14	96.66	98.87	-135.90	-6,919.13	605.17	1,021.77	872.64	149.13	6.852		
19,400.00	12,184.26	20,166.68	12,918.01	98.01	100.22	-135.90	-7,019.12	606.03	1,021.77	870.72	151.05	6.765		
19,500.00	12,185.13	20,266.68	12,918.88	99.36	101.57	-135.90	-7,119.12	606.89	1,021.77	868.80	152.97	6.680		
19,600.00	12,186.00	20,366.68	12,919.75	100.72	102.91	-135.90	-7,219.11	607.75	1,021.76	866.88	154.89	6.597		
19,700.00	12,186.87	20,466.68	12,920.61	102.07	104.26	-135.90	-7,319.10	608.61	1,021.76	864.95	156.81	6.516		
19,800.00	12,187.75	20,566.68	12,921.48	103.42	105.61	-135.90	-7,419.09	609.47	1,021.76	863.02	158.74	6.437		
19,900.00	12,188.62	20,666.68	12,922.35	104.78	106.96	-135.90	-7,519.09	610.34	1,021.76	861.09	160.67	6.359		
20,000.00	12,189.49	20,766.68	12,923.22	106.13	108.31	-135.90	-7,619.08	611.20	1,021.75	859.15	162.60	6.284		
20,100.00	12,190.36	20,866.68	12,924.09	107.49	109.66	-135.90	-7,719.07	612.06	1,021.75	857.22	164.53	6.210		
20,200.00	12,191.23	20,966.68	12,924.96	108.84	111.01	-135.90	-7,819.06	612.92	1,021.75	855.28	166.47	6.138		
20,300.00	12,192.10	21,066.68	12,925.82	110.20	112.36	-135.90	-7,919.06	613.78	1,021.75	853.34	168.40	6.067		
20,400.00	12,192.97	21,166.68	12,926.69	111.55	113.71	-135.90	-8,019.05	614.64	1,021.74	851.40	170.34	5.998		
20,500.00	12,193.85	21,266.68	12,927.56	112.91	115.06	-135.90	-8,119.04	615.50	1,021.74	849.46	172.28	5.931		
20,600.00	12,194.72	21,366.68	12,928.43	114.27	116.41	-135.90	-8,219.03	616.36	1,021.74	847.52	174.22	5.865		
20,700.00	12,195.59	21,466.68	12,929.30	115.62	117.77	-135.90	-8,319.03	617.22	1,021.74	845.57	176.17	5.800		
20,800.00	12,196.46	21,566.68	12,930.16	116.98	119.12	-135.90	-8,419.02	618.08	1,021.73	843.62	178.11	5.737		
20,900.00	12,197.33	21,666.68	12,931.03	118.34	120.47	-135.90	-8,519.01	618.94	1,021.73	841.67	180.06	5.674		
21,000.00	12,198.20	21,766.68	12,931.90	119.70	121.83	-135.90	-8,619.00	619.80	1,021.73	839.72	182.01	5.614		
21,100.00	12,199.07	21,866.68	12,932.77	121.05	123.18	-135.90	-8,719.00	620.66	1,021.73	837.77	183.95	5.554		
21,200.00	12,199.94	21,966.68	12,933.64	122.41	124.54	-135.90	-8,818.99	621.52	1,021.72	835.82	185.91	5.496		
21,300.00	12,200.82	22,066.68	12,934.50	123.77	125.89	-135.90	-8,918.98	622.38	1,021.72	833.86	187.86	5.439		
21,400.00	12,201.69	22,166.68	12,935.37	125.13	127.25	-135.90	-9,018.98	623.25	1,021.72	831.91	189.81	5.383		
21,500.00	12,202.56	22,266.68	12,936.24	126.49	128.60	-135.90	-9,118.97	624.11	1,021.72	829.95	191.77	5.328		
21,600.00	12,203.43	22,366.68	12,937.11	127.85	129.96	-135.90	-9,218.96	624.97	1,021.71	827.99	193.72	5.274		
21,700.00	12,204.30	22,466.68	12,937.98	129.21	131.31	-135.90	-9,318.95	625.83	1,021.71	826.03	195.68	5.221		
21,800.00	12,205.17	22,566.68	12,938.84	130.57	132.67	-135.90	-9,418.95	626.69	1,021.71	824.07	197.64	5.170		
21,900.00	12,206.04	22,666.68	12,939.71	131.93	134.03	-135.90	-9,518.94	627.55	1,021.71	822.11	199.60	5.119		
22,000.00	12,206.91	22,766.68	12,940.58	133.29	135.38	-135.90	-9,618.93	628.41	1,021.70	820.15	201.56	5.069		
22,100.00	12,207.79	22,866.68	12,941.45	134.65	136.74	-135.90	-9,718.92	629.27	1,021.70	818.18	203.52	5.020		
22,200.00	12,208.66	22,966.68	12,942.32	136.01	138.10	-135.90	-9,818.92	630.13	1,021.70	816.22	205.48	4.972		
22,300.00	12,209.53	23,066.68	12,943.18	137.37	139.46	-135.90	-9,918.91	630.99	1,021.70	814.25	207.45	4.925		
22,400.00	12,210.40	23,166.68	12,944.05	138.73	140.81	-135.90	-10,018.90	631.85	1,021.69	812.28	209.41	4.879		
22,411.61	12,210.50	23,178.29	12,944.15	138.89	140.97	-135.90	-10,030.51	631.95	1,021.69	812.06	209.64	4.874	SF	

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 223H - OH - Plan 1

Offset Site Error: 0.00 usft

Offset Well Error: 0.50 usft

Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)						Rule Assigned:						Offset Well Error:		0.50 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)				
3,000.00	2,985.83	3,395.09	3,378.98	7.78	7.59	93.70	946.69	2,189.99	2,416.24	2,401.35	14.89	162.229		
3,100.00	3,084.97	3,491.35	3,473.56	7.98	7.74	94.23	933.31	2,178.02	2,400.90	2,385.66	15.24	157.569		
3,200.00	3,184.12	3,587.61	3,568.13	8.17	7.90	94.76	919.92	2,166.06	2,385.77	2,370.18	15.58	153.089		
3,300.00	3,283.26	3,683.87	3,662.70	8.36	8.07	95.29	906.53	2,154.09	2,370.85	2,354.91	15.93	148.783		
3,400.00	3,382.40	3,780.14	3,757.28	8.56	8.26	95.84	893.15	2,142.13	2,356.14	2,339.85	16.29	144.652		
3,500.00	3,481.55	3,876.40	3,851.85	8.75	8.46	96.38	879.76	2,130.16	2,341.66	2,325.01	16.65	140.679		
3,600.00	3,580.69	3,972.66	3,946.43	8.95	8.65	96.94	866.38	2,118.19	2,327.40	2,310.39	17.01	136.860		
3,700.00	3,679.84	4,068.92	4,041.00	9.14	8.86	97.50	852.99	2,106.23	2,313.37	2,296.00	17.37	133.188		
3,800.00	3,778.98	4,165.19	4,135.57	9.33	9.06	98.07	839.61	2,094.26	2,299.57	2,281.84	17.74	129.657		
3,900.00	3,878.13	4,261.45	4,230.15	9.53	9.27	98.64	826.22	2,082.30	2,286.01	2,267.91	18.11	126.261		
4,000.00	3,977.27	4,357.71	4,324.72	9.72	9.48	99.23	812.84	2,070.33	2,272.70	2,254.22	18.48	122.994		
4,100.00	4,076.42	4,453.98	4,419.29	9.91	9.69	99.81	799.45	2,058.36	2,259.63	2,240.77	18.85	119.851		
4,200.00	4,175.56	4,550.24	4,513.87	10.11	9.90	100.41	786.07	2,046.40	2,246.81	2,227.57	19.23	116.826		
4,300.00	4,274.70	4,646.50	4,608.44	10.30	10.12	101.01	772.68	2,034.43	2,234.24	2,214.63	19.61	113.914		
4,400.00	4,373.85	4,742.76	4,703.01	10.49	10.34	101.61	759.30	2,022.47	2,221.93	2,201.94	20.00	111.111		
4,500.00	4,472.99	4,839.03	4,797.59	10.69	10.56	102.23	745.91	2,010.50	2,209.89	2,189.51	20.38	108.412		
4,600.00	4,572.14	4,935.29	4,892.16	10.88	10.78	102.84	732.53	1,998.53	2,198.12	2,177.34	20.77	105.812		
4,700.00	4,671.28	5,031.55	4,986.74	11.08	11.00	103.47	719.14	1,986.57	2,186.61	2,165.44	21.17	103.297		
4,702.13	4,673.39	5,033.60	4,988.75	11.08	11.01	103.48	718.86	1,986.31	2,186.37	2,165.19	21.18	103.245		
4,800.00	4,770.58	5,128.08	5,081.56	11.28	11.23	103.91	705.72	1,974.57	2,175.08	2,153.53	21.55	100.914		
4,900.00	4,870.15	5,225.10	5,176.88	11.48	11.46	104.28	692.23	1,962.51	2,163.16	2,141.23	21.93	98.654		
5,000.00	4,969.93	5,322.55	5,272.62	11.67	11.69	104.59	678.68	1,950.39	2,150.78	2,128.49	22.28	96.517		
5,100.00	5,069.85	5,420.36	5,368.72	11.85	11.92	104.83	665.08	1,938.24	2,137.88	2,115.26	22.62	94.494		
5,200.00	5,169.84	5,518.48	5,465.11	11.99	12.15	105.01	651.43	1,926.04	2,124.43	2,101.48	22.95	92.581		
5,202.16	5,172.00	5,520.60	5,467.20	12.00	12.16	84.78	651.14	1,925.78	2,124.13	2,101.18	22.95	92.540		
5,300.00	5,269.84	5,616.72	5,561.64	12.08	12.39	85.11	637.77	1,913.83	2,110.71	2,087.46	23.25	90.765		
5,400.00	5,369.84	5,714.97	5,658.16	12.17	12.63	85.46	624.11	1,901.61	2,097.07	2,073.50	23.57	88.988		
5,500.00	5,469.84	5,813.21	5,754.68	12.26	12.87	85.81	610.45	1,889.40	2,083.50	2,059.62	23.88	87.255		
5,600.00	5,569.84	5,911.46	5,851.20	12.34	13.11	86.17	596.79	1,877.19	2,070.01	2,045.82	24.19	85.565		
5,700.00	5,669.84	6,009.70	5,947.72	12.43	13.35	86.53	583.13	1,864.98	2,056.60	2,032.10	24.51	83.916		
5,800.00	5,769.84	6,107.95	6,044.24	12.52	13.59	86.89	569.47	1,852.76	2,043.28	2,018.46	24.83	82.307		
5,900.00	5,869.84	6,206.19	6,140.76	12.61	13.83	87.26	555.81	1,840.55	2,030.04	2,004.90	25.14	80.737		
6,000.00	5,969.84	6,304.44	6,237.29	12.69	14.07	87.64	542.15	1,828.34	2,016.88	1,991.42	25.46	79.206		
6,100.00	6,069.84	6,402.68	6,333.81	12.78	14.32	88.01	528.49	1,816.13	2,003.82	1,978.03	25.78	77.714		
6,200.00	6,169.84	6,485.32	6,415.04	12.87	14.49	88.33	517.17	1,806.01	1,991.07	1,965.02	26.05	76.436		
6,300.00	6,269.84	6,557.87	6,486.58	12.96	14.65	88.59	508.19	1,797.99	1,979.59	1,953.28	26.31	75.252		
6,400.00	6,369.84	6,630.85	6,558.76	13.04	14.81	88.82	500.18	1,790.83	1,969.47	1,942.91	26.56	74.155		
6,500.00	6,469.84	6,700.00	6,627.34	13.13	14.95	89.01	493.54	1,784.89	1,960.71	1,933.92	26.79	73.180		
6,600.00	6,569.84	6,777.94	6,704.80	13.22	15.08	89.19	487.17	1,779.19	1,953.28	1,926.25	27.03	72.269		
6,700.00	6,669.84	6,851.94	6,778.50	13.30	15.19	89.33	482.21	1,774.76	1,947.19	1,919.95	27.24	71.476		
6,800.00	6,769.84	6,926.17	6,852.55	13.39	15.29	89.45	478.31	1,771.27	1,942.42	1,914.98	27.45	70.775		
6,900.00	6,869.84	7,000.00	6,926.28	13.48	15.38	89.53	475.49	1,768.75	1,938.98	1,911.35	27.63	70.165		
7,000.00	6,969.84	7,075.10	7,001.34	13.56	15.45	89.58	473.71	1,767.16	1,936.85	1,909.04	27.81	69.653		
7,100.00	7,069.84	7,149.69	7,075.93	13.65	15.50	89.60	473.04	1,766.56	1,936.04	1,908.10	27.94	69.295		
7,137.95	7,107.79	7,184.55	7,110.79	13.68	15.50	89.60	473.03	1,766.55	1,936.03	1,908.05	27.98	69.203		
7,200.00	7,169.84	7,246.60	7,172.84	13.74	15.52	89.60	473.03	1,766.55	1,936.03	1,907.98	28.05	69.024		
7,300.00	7,269.84	7,346.60	7,272.84	13.82	15.56	89.60	473.03	1,766.55	1,936.03	1,907.85	28.17	68.717		
7,400.00	7,369.84	7,446.60	7,372.84	13.91	15.60	89.60	473.03	1,766.55	1,936.03	1,907.73	28.30	68.412		
7,500.00	7,469.84	7,546.60	7,472.84	14.00	15.64	89.60	473.03	1,766.55	1,936.03	1,907.60	28.43	68.110		
7,600.00	7,569.84	7,646.60	7,572.84	14.08	15.68	89.60	473.03	1,766.55	1,936.03	1,907.48	28.55	67.809		
7,700.00	7,669.84	7,746.60	7,672.84	14.17	15.72	89.60	473.03	1,766.55	1,936.03	1,907.35	28.68	67.511		
7,800.00	7,769.84	7,846.60	7,772.84	14.26	15.76	89.60	473.03	1,766.55	1,936.03	1,907.22	28.80	67.214		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

3/25/2025 1:26:47AM

Page 84 of 90

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Offset Design: Junior Mint Fed Pad - Junior Mint Fed 223H - OH - Plan 1													
Survey Program: 0-MWD+HRGM+SAG+FDIR (rev.5)										Offset Site Error:		0.00 usft	
Reference										Offset Well Error:		0.50 usft	
Measured	Vertical	Measured	Vertical	Semi Major Axis		Highside	Offset Wellbore Centre		Distance		Minimum	Separation	Warning
Depth	Depth	Depth	Depth	Reference	Offset		+N/-S	+E/-W	Between	Between	Separation	Factor	
(usft)	(usft)	(usft)	(usft)	(usft)	(usft)	(°)	(usft)	(usft)	Centres	Ellipses	(usft)		
									(usft)	(usft)			
22,300.00	12,209.53	23,015.93	12,849.58	137.37	151.12	-107.33	-9,909.54	1,960.93	2,138.12	1,860.29	277.83	7.696	
22,400.00	12,210.40	23,115.93	12,850.11	138.73	152.48	-107.33	-10,009.53	1,961.84	2,138.06	1,857.61	280.45	7.624	
22,411.61	12,210.50	23,127.55	12,850.17	138.89	152.64	-107.32	-10,021.14	1,961.95	2,138.06	1,857.30	280.76	7.615	ES, SF

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to GE 3220 + 26 @ 3246.00usft (26' KB) Coordinates are relative to: Junior Mint Fed 135H


Offset Depths are relative to Offset Datum

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Central Meridian is -104.3333333

Grid Convergence at Surface is: 0.52°

Ladder Plot



LEGEND

Junior Mint Fed 217H, OH, Plan 1 V0	Junior Mint Fed 132H, OH, Plan 1 V0	Junior Mint Fed 221H, OH, Plan 1 V0
Junior Mint Fed 131H, OH, Plan 1 V0	Junior Mint Fed 156H, OH, Plan 1 V0	Junior Mint Fed 151H, OH, Plan 1 V0
Junior Mint Fed 152H, OH, Plan 1 V0	(O) Montera Federal 023H, OH, OH V0	Junior Mint Fed 212H, OH, Plan 1 V0
Junior Mint Fed 133H, OH, Plan 1 V0	Junior Mint Fed 137H, OH, Plan 1 V0	Junior Mint Fed 215H, OH, Plan 1 V0
Junior Mint Fed 213H, OH, Plan 1 V0	Junior Mint Fed 211H, OH, Plan 1 V0	Junior Mint Fed 222H, OH, Plan 1 V0
(O) Montera Federal Com 601H, OH, OH V0	Junior Mint Fed 223H, OH, Plan 1 V0	Junior Mint Fed 216H, OH, Plan 1 V0

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Anticollision Report

Company:	Civitas Resources	Local Co-ordinate Reference:	Well Junior Mint Fed 135H
Project:	Lea County, NM (NAD 83)	TVD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Reference Site:	Junior Mint Fed Pad	MD Reference:	GE 3220 + 26 @ 3246.00usft (26' KB)
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Junior Mint Fed 135H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.50 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	.Total Directional Production DB
Reference Design:	Plan 1	Offset TVD Reference:	Offset Datum

Reference Depths are relative to GE 3220 + 26 @ 3246.00usft (26' KB)Coordinates are relative to: Junior Mint Fed 135H


Offset Depths are relative to Offset Datum

Coordinate System is US State Plane 1983, New Mexico Eastern Zone

Central Meridian is -104.3333333

Grid Convergence at Surface is: 0.52°

Separation Factor Plot



LEGEND

Junior Mint Fed 217H, OH, Plan 1 V0	Junior Mint Fed 132H, OH, Plan 1 V0	Junior Mint Fed 221H, OH, Plan 1 V0
Junior Mint Fed 131H, OH, Plan 1 V0	Junior Mint Fed 156H, OH, Plan 1 V0	Junior Mint Fed 151H, OH, Plan 1 V0
Junior Mint Fed 152H, OH, Plan 1 V0	(O) Monteria Federal 023H, OH, OH V0	Junior Mint Fed 212H, OH, Plan 1 V0
Junior Mint Fed 133H, OH, Plan 1 V0	Junior Mint Fed 137H, OH, Plan 1 V0	Junior Mint Fed 215H, OH, Plan 1 V0
Junior Mint Fed 213H, OH, Plan 1 V0	Junior Mint Fed 211H, OH, Plan 1 V0	Junior Mint Fed 222H, OH, Plan 1 V0
(O) Monteria Federal Com 601H, OH, OH V0	Junior Mint Fed 223H, OH, Plan 1 V0	Junior Mint Fed 216H, OH, Plan 1 V0

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Sante Fe Main Office
Phone: (505) 476-3441

General Information
Phone: (505) 629-6116

Online Phone Directory
<https://www.emnrd.nm.gov/ocd/contact-us>

State of New Mexico
Energy, Minerals and Natural Resources
Oil Conservation Division
1220 S. St Francis Dr.
Santa Fe, NM 87505

CONDITIONS

Action 475361

CONDITIONS

Operator: Civitas Permian Operating, LLC 555 17th Street Denver, CO 80202	OGRID: 332195
	Action Number: 475361
	Action Type: [C-103] NOI Change of Plans (C-103A)

CONDITIONS

Created By	Condition	Condition Date
matthew.gomez	Any previous COA's not addressed within the updated COA's still apply.	6/25/2025