

Submit 1 Copy To Appropriate District
Office
District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Ave., Artesia, NM 88210
District III
1000 Rio Brazos Rd., Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM
87505

State of New Mexico
Energy, Minerals and Natural Resources

Form C-103
October 13, 2009

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)		WELL API NO. 30-021-20233
1. Type of Well: Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other CO2 SUPPLY		5. Indicate Type of Lease STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>
2. Name of Operator HESS Corporation		6. State Oil & Gas Lease No. L-5852
3. Address of Operator PO Box 840 Seminole TX 79360		7. Lease Name or Unit Agreement Name WBDU
4. Well Location Unit Letter A : 990 feet from the north line and 990 feet from the EAST line Section 13 Township 18N Range 29E NMPM County HARDING		8. Well Number 131A
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 4416'		9. OGRID Number 495
		10. Pool name or Wildcat (96387) West Bravo Dome CO2 Gas

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

PERFORM REMEDIAL WORK ☒ PLUG AND ABANDON ☐
TEMPORARILY ABANDON ☐ CHANGE PLANS ☐
PULL OR ALTER CASING ☐ MULTIPLE COMPL ☐
DOWNHOLE COMMINGLE ☐

OTHER: ☐

SUBSEQUENT REPORT OF:

REMEDIAL WORK ☐ ALTERING CASING ☐
COMMENCE DRILLING OPNS. ☐ P AND A ☐
CASING/CEMENT JOB ☐

OTHER: ☐

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

summary of the work planned for changing out wellhead hanger flanges at WBD

Rig up pulling unit, kill well with 4-6%KCL,
unflange meter and B-1 hanger, lift hanger
and place slips under B-1 hanger,
change out hanger with new coated B1 hanger,
bolt up hanger and meter, rig down pulling unit.

Spud Date:

Rig Release Date:

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Rita C. Smith TITLE ENGINEERING TECH DATE 11/6/2009

Type or print name RITA C. SMITH E-mail address: rsmith@hess.com PHONE: 432-758-6726

For State Use Only

APPROVED BY: Ed Martin TITLE DISTRICT SUPERVISOR DATE 11/13/09

Conditions of Approval (if any):