

3R - 438

WORKPLAN

08 / 03 / 2012



Animas Environmental Services, LLC

www.animasenvironmental.com

624 E. Comanche
Farmington, NM 87401
505-564-2281

Durango, Colorado
970-403-3274

Prepared for:

Glenn von Gonten
New Mexico Oil Conservation Division
1220 South St. Francis Drive
Santa Fe, New Mexico 87505

Prepared on behalf of:

Enterprise Products Company
614 Reilly Avenue
Farmington, NM 87401

Groundwater Investigation Workplan
Enterprise Products Company
Lateral 6C
September 2011 Pipeline Release
NE¼ SW¼, Section 26, T28N, R11W
San Juan County, New Mexico

August 3, 2012

Prepared by:

Animas Environmental Services, LLC
624 E. Comanche
Farmington, New Mexico 87401
www.animasenvironmental.com

Contents

1.0	Introduction	1
1.1	Site Location and NMOCD Ranking	1
1.2	Release Information	1
1.3	Initial Release Assessment and Investigation	2
1.3.1	September 2011.....	2
1.3.2	October 2011	2
1.3.3	November 2011	2
2.0	Proposed Groundwater Investigation	3
2.1	Pre-Field Permits and Coordination	3
2.1.1	Access Agreements.....	3
2.1.2	Archaeological Clearances.....	3
2.1.3	Office of State Engineer Permits.....	3
2.1.4	Utilities Notification.....	3
2.1.5	Health and Safety Plan	4
2.2	Installation of Soil Borings.....	4
2.3	Soil Sampling and Analyses	4
2.3.1	Sample Collection	4
2.3.2	Field Screening.....	5
2.3.3	Laboratory Analyses	5
2.4	Groundwater Monitor Well Installation and Sampling.....	5
2.4.1	Groundwater Monitor Well Installation and Construction.....	5
2.4.2	Professional Survey.....	5
2.4.3	Monitor Well Development	6
2.4.4	Groundwater Sampling.....	6
2.4.5	Laboratory Analyses	6
2.5	Equipment Decontamination	6
3.0	Deliverables.....	7
4.0	Implementation Schedule.....	8
5.0	References	9

Figures

- Figure 1. Topographic Site Location Map
- Figure 2. Aerial Site Map
- Figure 3. Proposed Soil Borings and Monitor Well Locations
- Figure 4. Proposed Monitor Well Schematic

1.0 Introduction

Animas Environmental Services, LLC (AES), on behalf of Enterprise Products Company (Enterprise), has prepared a workplan for a groundwater investigation associated with a release of natural gas and condensate, which occurred along the Enterprise 4-inch diameter Lateral 6C pipeline on September 21, 2011. Details of the initial release assessment and investigation were submitted in the AES *Pipeline Release Letter Report* dated October 28, 2011, and *Site Investigation Report* dated December 20, 2011.

1.1 Site Location and NMOCD Ranking

The release is located on Federal land under jurisdiction of the Bureau of Land Management (BLM) within the NE¼ SW¼, Section 26, T28N, R11W, San Juan County, New Mexico. Latitude and longitude of the release were recorded as N36.63202 and W107.97400 respectively. Based on measurements collected during the site investigation, depth to groundwater is approximately 16 feet below ground surface (bgs). A topographic site location map is included as Figure 1, and an aerial map showing the release location is included as Figure 2.

In accordance with the New Mexico Oil Conservation Division (NMOCD) *Guidelines for Remediation of Leaks, Spills, and Releases* (October 1993), the release location was assigned a ranking score to establish release action levels. The ranking score was obtained in part by reviewing available records of nearby oil/gas wells using the NMOCD online database; however, no records were found to aid in the assessment. Additionally, the New Mexico Office of the State Engineer (NMOSE) database was reviewed for the presence of nearby water wells, and no registered water wells were reported to be located within 1,000 feet of the location. Google Earth and the New Mexico Tech Petroleum Recovery Research Center online mapping tool (http://ford.nmt.edu/react/pitrules_index.html) were accessed to aid in the identification of downgradient surface water. Kutz Wash is located approximately 750 feet northeast of the release location. Based on this information and the known depth to groundwater, the release location was assessed a ranking score of 30.

1.2 Release Information

A release was reported at the location on September 21, 2011, by Enterprise Bisti Gathering Area personnel, and on the same date Enterprise personnel were dispatched to locate and isolate the leak. Release excavation and line repair work were completed on September 22 and 23, 2011. The cause of the release was identified as a small (¼-inch) corrosion hole on the underside of the line.

1.3 Initial Release Assessment and Investigation

1.3.1 September 2011

Following the repair on September 23, 2011, AES collected one soil sample from the base of the small repair excavation at 6 feet bgs. Based on the field screening reading (3,974 parts per million (ppm)) and the anticipated shallow depth of groundwater, AES and Enterprise determined that a limited investigation of the release extents would be appropriate prior to implementing further contaminant mitigation measures.

1.3.2 October 2011

On October 11, 2011, the release assessment was continued. Four test holes (TP-1 through TP-4) were excavated in locations around the original release, and soil samples were collected for field screening and laboratory analysis. Groundwater was encountered in two of the test hole excavations at approximately 16 feet bgs; therefore, groundwater samples were collected from these test holes. In TP-2, non-aqueous phase liquid (NAPL) or free product was observed on the groundwater that entered the test hole excavation. Test hole locations are included on Figure 3.

Soil laboratory results reported total benzene, toluene, ethylbenzene, and xylene (BTEX) and total petroleum hydrocarbons (TPH) above the NMOCD action level in two of the test holes (TP-1 and TP-2). TP-2 showed the highest concentrations of benzene (45 mg/kg), BTEX (513 mg/kg), and TPH (5,170 mg/kg) at 15 feet bgs.

Groundwater laboratory results showed concentrations above the New Mexico Water Quality Control Commission (WQCC) standards in TP-2 and TP-4. The highest concentrations for dissolved phase benzene, toluene, and xylenes were reported in TP-2 with 9,800 µg/L benzene, 15,000 µg/L toluene, and 6,700 µg/L xylenes.

Based on field screening and laboratory analytical results, AES recommended that Enterprise conduct further delineation of the soil and groundwater contamination in order to determine the most effective mitigation of the release.

1.3.3 November 2011

On November 30, 2011, eight soil borings (SB-1 through SB-8) were installed in order to define the lateral and vertical extent of soil and groundwater contamination. Soil samples collected showed that contaminant concentrations exceeded NMOCD action levels in borings SB-2, SB-7, and SB-8. The highest benzene and total BTEX concentrations were reported in SB-2 with 31 mg/kg benzene and 580 mg/kg total BTEX. The highest TPH concentration was also reported in SB-2 with 7,500 mg/kg.

Dissolved phase analytical results indicated groundwater is impacted above the WQCC standard in SB-2, SB-3, and SB-7. The highest concentrations for benzene, toluene, and xylenes were reported in SB-2 with 2,800 µg/L benzene, 5,700 µg/L toluene, and 4,000 µg/L xylenes. Dissolved phase concentration contour maps show that the release appears to have migrated primarily northwest along the pipeline corridor, with the highest concentrations noted in test hole TP-2 (October 2011) and in soil boring SB-2.

Based on investigation results, recommendations were made for the installation of permanent groundwater monitor wells and collection of additional data, from which a corrective action plan can be developed.

2.0 Proposed Groundwater Investigation

The groundwater investigation is proposed in order to further delineate the extent of the dissolved phase hydrocarbon contaminants associated with the Lateral 6C pipeline release. The investigation procedures are designed to be protective of both surface water and groundwater and are based upon protocols outlined in AES' Standard Operating Procedures (SOPs). SOPs follow applicable NMOCD guidelines, BLM guidelines, American Society for Testing and Materials (ASTM) standards, and applicable U.S. Environmental Protection Agency (USEPA) methods and guidelines for soil and groundwater sampling.

2.1 *Pre-Field Permits and Coordination*

2.1.1 Access Agreements

Prior to initiating the field work, AES will work with Enterprise and BLM for a Temporary Use Area (TUA) permit.

2.1.2 Archaeological Clearances

In the event that any evidence of artifacts and/or human remains are encountered, all work will be stopped immediately. The BLM Archaeologist and the State Historic Preservation Office (SHPO) will be contacted, and appropriate mitigation measures will be implemented.

2.1.3 Office of State Engineer Permits

Prior to initiating the groundwater investigation, AES will consult with the New Mexico Office of the State Engineer (NMOSE) to determine if groundwater monitor well permits are required.

2.1.4 Utilities Notification

AES will utilize the New Mexico One-Call system to identify and mark all underground utilities at the site before the start of any proposed field activities which could impact buried

utilities. Any local utilities not participating in the New Mexico One-Call system will be contacted separately by AES for utility locations.

2.1.5 Health and Safety Plan

AES has a company health and safety plan in place, and all on-site personnel are 40-hour HazWoper trained in accordance with OSHA regulations outlined in 29 CFR 1910.120(e). Prior to the start of the site investigation, AES will prepare a comprehensive site-specific Job Safety Analysis (JSA) addressing the site investigation activities and associated soil and groundwater sampling. All employees and subcontractors are required to read and sign the JSA to acknowledge their understanding of the information contained within the JSA. The JSA will be implemented and enforced on site by the assigned Site Safety and Health Officer.

2.2 Installation of Soil Borings

AES proposes to install nine soil borings which will be completed as 2-inch diameter groundwater monitor wells to delineate the extent of the dissolved phase petroleum hydrocarbon impacts. Soil borings will be advanced to a total depth of 25 feet bgs with a CME-75 truck mounted drill rig equipped with hollow stem augers and 4-inch outer diameter (OD) core barrel. The drill rig will be operated by Kyvek Energy Services, Inc. of Aztec, New Mexico.

Drill cuttings from the soil borings will be contained in labeled and sealed 55-gallon drums. The drummed cuttings will be transported to Envirotech Landfarm for proper disposal. The locations of the proposed soil borings/monitor wells are shown on Figure 3.

2.3 Soil Sampling and Analyses

2.3.1 Sample Collection

Each soil boring will be continuously sampled using a core-barrel sampler. Soil samples collected will be field screened for volatile organic compounds (VOCs) with a photo-ionization detector (PID) organic vapor meter (OVM). A minimum of two soil samples will be collected from each boring for laboratory analysis. The samples will be collected from the vadose zone where the highest OVM-PID reading is observed and from the capillary fringe just above groundwater. Additional soil samples will be collected and submitted for laboratory analyses if warranted by field observation. Therefore, based on nine proposed soil borings, a minimum of 18 soil samples will be submitted for laboratory analyses.

For each soil boring, a Soil Boring Log will be completed. These logs will record sample identification, depth collected, and method of collection, as well as observations of soil moisture, color, density, grain size, plasticity, contaminant presence, and overall stratigraphy.

2.3.2 Field Screening

Samples will be field screened for VOC vapors utilizing a PID-OVM calibrated with isobutylene gas to obtain preliminary data regarding potential hydrocarbon impacted soil. Once collected, the soil sample to be field-screened will be placed immediately in a clean 16 ounce glass jar, filled approximately half full, and sealed with a threaded ring lid and a sheet of aluminum foil. Approximately 10 minutes will be allowed for the soil to be heated and for any VOCs in the soil to accumulate in the head space of the jar. During the initial stages of headspace development, the sample will be gently shaken for one minute to promote vapor development and disaggregate the sample. Volatile gases will then be measured by piercing the aluminum foil with the sample probe of the PID-OVM. The highest (peak) measurement will be recorded. PID-OVM readings will be recorded onto the soil boring logs.

2.3.3 Laboratory Analyses

Discrete samples for laboratory analysis will be collected and transferred to laboratory-supplied sample containers, labeled, and stored in an insulated cooler containing ice at less than 6°C. Samples will be submitted to Hall Environmental Analysis Laboratory (Hall), Albuquerque, New Mexico, for analysis of the following parameters:

- BTEX per USEPA Method 8021B;
- TPH for gasoline range organics (GRO) and diesel range organics (DRO) per USEPA Method 8015B.

2.4 Groundwater Monitor Well Installation and Sampling

2.4.1 Groundwater Monitor Well Installation and Construction

Groundwater monitor wells will be installed within all of the nine soil borings. Monitor well construction will consist of 2.375-inch outside diameter (OD) [2.067-inch inside diameter (ID)] Schedule 40 PVC screen and 2.0-inch blank riser casing. The screened interval will extend 15 feet across the water table. The wells will be constructed of 2.375-inch OD PVC well screen (0.010-inch slot). Colorado silica sand (filter pack) will be placed from total depth to approximately 2 feet above the top of the well screen. A 2-foot bentonite seal will be placed above the sand pack, and concrete grout with approximately 5 percent bentonite will be poured from the top of the bentonite seal up to within 0.5 feet of ground surface. An above grade locking steel protective casing, enclosed with a shroud of concrete, will be installed on the well to prevent unauthorized access and damage. A proposed monitor well schematic is presented in Figure 4.

2.4.2 Professional Survey

The location and elevation of the top of each well casing will be surveyed to the nearest 0.01 foot with reference to mean sea level by a licensed surveyor in order to accurately determine the local groundwater depth and flow direction beneath the site. Each well will

be tied to an existing USGS benchmark. AES will arrange with a New Mexico Licensed Professional Surveyor to complete the survey upon completion of the monitor well installation.

2.4.3 Monitor Well Development

Following monitor well installation and completion, each well will be developed by a combination of surging and bailing techniques. Groundwater purged from the wells will be contained in labeled and sealed 55-gallon drums and transported to Envirotech Landfarm for proper disposal.

2.4.4 Groundwater Sampling

Upon completion and development, the monitor wells will be allowed to sit undisturbed for a minimum of one week. The monitor wells will then be gauged to determine water table elevation and direction of groundwater flow. The wells will then be purged of a minimum of three well volumes, and a groundwater sample will be collected from each well.

Groundwater samples will be collected from each well with a new disposable bailer equipped with a low-flow release valve. Purging data, including pH, temperature, conductivity, oxidation-reduction potential, and dissolved oxygen, will be measured with a YSI water quality meter and documented on a Water Sample Collection Form along with purged water volume and sample depth. All sampling equipment will be thoroughly decontaminated between uses. Purged water will be contained and labeled in a sealed 55-gallon drum and transported to the Envirotech Landfarm for proper disposal.

2.4.5 Laboratory Analyses

All groundwater analytical samples collected from the monitor wells will be submitted to Hall for analysis of the following parameters:

- BTEX per USEPA Method 8021B;

Once collected, sample containers will be packed per standard protocol with ice in insulated coolers and shipped to the analytical laboratory.

2.5 Equipment Decontamination

In order to prevent cross-contamination between sampling locations, strict decontamination procedures will be employed during the groundwater investigation. All drilling equipment will be decontaminated after completing each soil boring, and sampling equipment (i.e. hand auger, spoon sampler, and other hand tools) will be decontaminated following each use at an individual depth or location.

All decontamination of equipment will be completed within clean 5-gallon plastic buckets, which will contain the effluent. At least two tubs will be used, one designated for push rods and the other for small sampling equipment. On an as-needed basis, effluent from the tubs will be transferred by small pump or bucket into 55-gallon DOT approved drums, which will then be marked with identification labels and sealed. Decontamination procedures to be utilized are outlined below.

For small equipment such as hand tools and spoon samplers:

1. Physical removal of gross contamination and all debris with brushes;
2. Hand wash with non-phosphate detergent;
3. Hand wash with non-phosphate detergent and water using brush;
4. Rinse with water;
5. Second rinse with water;
6. Air dry.

All decontamination procedures will be completed in strict accordance with AES SOPs and applicable USEPA guidelines.

3.0 Deliverables

Following completion of the groundwater investigation activities, a Groundwater Investigation Report summarizing the investigation activities will be submitted to Enterprise. The report will include the following:


1. A summary of all work conducted in the implementation of the investigation;
2. Maps of all sampling locations, including soil and groundwater contaminant concentrations and contours;
3. Geologic cross-sections;
4. All laboratory data and quality assurance and quality control information;
5. Professional survey data; and
6. Recommendations for corrective action.

4.0 Implementation Schedule


AES proposes the following timeline to implement groundwater investigation activities once NMOCD approval has been received. This schedule assumes that no inclement weather occurs, which could result in a delay in implementing field activities.

Task	Days from NMOCD Workplan Concurrence
Task 1. Pre-field permits and coordination	15
Task 2. Complete installation of soil borings and groundwater monitor wells; collect and submit soil and groundwater samples for laboratory analysis. Schedule professional survey of wells.	30
Task 3. Receive laboratory analytical reports for soil and groundwater samples. Receive professional survey data.	45
Task 4. Prepare and submit Groundwater Investigation Report.	60

Respectfully submitted,



Tami C. Ross, CHMM
Project Manager



Elizabeth McNally, PE
Principal

5.0 References

Animas Environmental Services, LLC (AES). *Enterprise Lateral 6C Pipeline Release Letter Report*. October 28, 2011.

AES. *Enterprise Lateral 6C Site Investigation Report*. December 20, 2011.

ASTM International. ASTM D5092 - 04(2010)e1. *Standard Practice for Design and Installation of Groundwater Monitoring Wells*, 2010.


New Mexico Oil Conservation Division. 1993. *Environmental Handbook: Miscellaneous Guidelines: Guidelines for Remediation of Spills, Leaks, and Releases*. August 13, 1993. <http://www.emnrd.state.nm.us/oed/EnvironmentalHandbook.htm>

U.S. Department of Interior (USDI) Bureau of Land Management. 2008. *Natural Resource Damage Assessment and Restoration Handbook*. Release 1-1712. May, 2008.

U.S. Environmental Protection Agency (USEPA). 1982. *Methods for Chemical Analysis for Water and Wastes*. Document EPA-600, July, 1982.

USEPA. 1992. SW-846, 3rd Edition, *Test Methods for Evaluating Solid Waste: Physical Chemical Methods*, dated November, 1986, and as amended by Update One, July, 1992.

USEPA. 2001. Contract Laboratory Program (CLP) Guidance for Field Samplers. OSWER 9240.0-35, EPA 540-R-00-003. June, 2001.



Animas Environmental Services, LLC

DRAWN BY:
C. Lameman

DATE DRAWN:
July 23, 2011

REVISIONS BY:
C. Lameman

DATE REVISED:
July 23, 2011

CHECKED BY:
T. Ross


DATE CHECKED:
July 23, 2011


APPROVED BY:
E. McNally


DATE APPROVED:
July 23, 2011

FIGURE 1

TOPOGRAPHIC SITE LOCATION MAP
ENTERPRISE PRODUCTS COMPANY
LATERAL 6C PIPELINE RELEASE LOCATION
SAN JUAN COUNTY, NEW MEXICO
NE $\frac{1}{4}$, SW $\frac{1}{4}$, SEC. 26, T28N, R11W
N36.63202, W107.97400



 Animas Environmental Services, LLC	DRAWN BY: C. Lameman	DATE DRAWN: September 22, 2011	FIGURE 2 AERIAL SITE MAP ENTERPRISE PRODUCTS COMPANY LATERAL 6C PIPELINE RELEASE LOCATION SAN JUAN COUNTY, NEW MEXICO NE¼, SW¼, SEC. 26, T28N, R11W N36.63202, W107.97400
	REVISIONS BY: C. Lameman	DATE REVISED: July 23, 2011	
	CHECKED BY: T. Ross	DATE CHECKED: July 23, 2011	
	APPROVED BY: E. McNally	DATE APPROVED: July 23, 2011	



Animas Environmental Services, LLC

DRAWN BY:

C. Lameman

DATE DRAWN:

December 27, 2011

REVISIONS BY:

C. Lameman

DATE REVISED:

August 6, 2012

CHECKED BY:

T. Ross

DATE CHECKED:

August 6, 2012

APPROVED BY:


E. McNally

DATE APPROVED:

August 6, 2012

FIGURE 3

PROPOSED SOIL BORINGS AND MONITOR WELL LOCATIONS
 ENTERPRISE PRODUCTS COMPANY
 LATERAL 6C PIPELINE RELEASE LOCATION
 SAN JUAN COUNTY, NEW MEXICO
 NE¼, SW¼, SEC. 26, T28N, R11W
 N36.63202, W107.97400



NOT TO SCALE



DRAWN BY:
C. Lameman

DATE DRAWN:
August 6, 2012

REVISIONS BY:
C. Lameman

DATE REVISED:
August 6, 2012

CHECKED BY:
T. Ross

DATE CHECKED:
August 6, 2012

APPROVED BY:
E. McNally

DATE APPROVED:
August 6, 2012

FIGURE 4

PROPOSED MONITOR WELL SCHEMATIC
ENTERPRISE PRODUCTS COMPANY
LATERAL 6C PIPELINE RELEASE LOCATION
SAN JUAN COUNTY, NEW MEXICO
NE $\frac{1}{4}$, SW $\frac{1}{4}$, SEC. 26, T28N, R11W
N36.63202, W107.97400