

1R - 425-84

# WORKPLANS

Date:

2-8-13

# **RICE** *Operating Company*

112 West Taylor • Hobbs, New Mexico 88240

Phone: (575) 393-9174 • Fax: (575) 397-1471

CERTIFIED MAIL  
RETURN RECEIPT NO. 7007 2560 0000 4569 8838

**RECEIVED**

**FEB 13 2013**

**February 8, 2013**

**Mr. Edward Hansen**

New Mexico Energy, Minerals, & Natural Resources  
Oil Conservation Division, Environmental Bureau  
1220 S. St. Francis Drive  
Santa Fe, New Mexico 87505

**Oil Conservation Division  
1220 S. St. Francis Drive  
Santa Fe, NM 87505**

**RE: Investigation and Characterization Plan (ICP)  
Rice Operating Company – Vacuum SWD System  
Vacuum Jct. C-31 (1R425-84): Unit C, Sec. 31, T17S, R35E**

Mr. Hansen:

ROC is the service provider (agent) for the Vacuum SWD System and has no ownership of any portion of the pipeline, well, or facility. The system is owned by a consortium of oil producers, System Parties, who provide all operating capital on a percentage/usage basis. Environmental projects of this nature require System Party AFE approval prior to work commencing at the site. In general, project funding is not forthcoming until NMOCD approves the work plan. Therefore, your timely review of this submission is greatly appreciated.

For all such environmental projects, ROC will choose the path forward that:

- Protects public health,
- Provides the greatest net environmental benefit,
- Complies with NMOCD Rules, and
- Is supported by good science.

Each site shall generally have three submissions:

1. This Investigation and Characterization Plan (ICP) is proposed for gathering data and site characterization and assessment.
2. Upon evaluating the data and results from the ICP, a recommended remedy will be submitted in a Corrective Action Plan (CAP), if warranted.

3. Finally, after implementing the remedy, a Termination Request with final documentation will be submitted.

### **Background and Previous Work**

The site is located approximately 0.5 miles southwest of Buckeye, New Mexico in Unit C, Section 31, T17S, R35E as shown on the Site Location Map (Figure 1). NM OSE records indicate that groundwater will likely be encountered at a depth of approximately 117 +/- feet.

In 2009, ROC initiated work on the former Vacuum Jct. C-31 junction boxes. The site was delineated using a backhoe to collect soil samples at regular intervals, creating a 30x20x12-ft deep excavation. Each sample was field tested for chloride and organic vapors were measured using a PID, which resulted in elevated chloride concentrations. The excavated soil was blended on site and representative composite samples were sent to a commercial laboratory for analysis of chloride and TPH. Laboratory analysis of the four-wall composite resulted in a chloride concentration of 2,400 mg/kg, a gasoline range organics (GRO) concentration of 69.1 mg/kg, and a diesel range organics (DRO) concentration of 1,110 mg/kg. BTEX analysis of the four-wall composite resulted in benzene and toluene concentrations below detectable limits, an ethyl benzene concentration of 0.363 mg/kg, and a total xylenes concentration of 1.48 mg/kg. Laboratory analysis of the bottom composite resulted in a chloride concentration of 944 mg/kg, a GRO concentration of 158 mg/kg, and a DRO concentration of 1,590 mg/kg. BTEX analysis of the bottom composite resulted in benzene, toluene, and ethyl benzene concentrations below detectable limits, and a total xylenes concentration of 2.77 mg/kg. The blended backfill resulted in a chloride concentration of 1,200 mg/kg, a GRO concentration of 10.4 mg/kg, and a DRO concentration of 1,130 mg/kg. The blended backfill was returned to the excavation up to 5 ft below ground surface (bgs) and a geosynthetic and plastic liner were installed. The remaining backfill was blended with clean, imported soil and analyzed by a commercial laboratory for chloride and TPH. Laboratory analysis of the blended backfill II resulted in a chloride concentration of 400 mg/kg, a GRO concentration below detectable limits, and a DRO concentration of 312 mg/kg. The blended backfill II was returned to the excavation to ground surface and was used to contour the site to the surrounding area. On June 8, 2009, the site was seeded with a blend of native vegetation.

NMOCD was notified of potential groundwater impact on March 12, 2010, and a junction box disclosure report (Appendix A) was submitted to NMOCD with all the 2009 junction box closures and disclosures.

ROC proposes additional investigative work at the site to determine if there is potential for groundwater degradation from residual chlorides and hydrocarbons at the site.

## Proposed Work Elements

1. Conduct vertical and lateral delineation of residual soil chlorides and hydrocarbons from samples taken using a drill rig, hand auger, and/or backhoe (see Appendix B for Quality Procedures).
  - a. Vertical sampling will be conducted until the following criteria are met in the field.
    - i. Three samples in which the chloride concentration decreases and the third sample has a chloride concentration of  $\leq 250$  ppm; and,
    - ii. Three samples in which PID readings decrease and the third sample has a PID reading of  $\leq 100$  ppm; or,
    - iii. The sampling reaches the capillary fringe.
  - b. Lateral sampling will be conducted until the following criteria are met in the field.
    - i. A decrease is observed in chloride concentrations between lateral bores at similar depths; and,
    - ii. A chloride concentration of  $\leq 250$  ppm is observed in a lateral surface sample; or,
    - iii. Safety concerns impede further lateral delineation.
2. If warranted, install a monitor well to provide direct measurement of the potential groundwater impact at the site. Additional monitoring wells may be required to fully delineate groundwater quality. (All monitor wells will be installed by EPA, NMOCD, and industry standards.)
3. Evaluate the risk of groundwater impact based on the information obtained.

If the evaluation of the site shows no threat to groundwater from residual chlorides, then only a vadose zone remedy will be undertaken. However, if groundwater shows impact from residual chlorides, a CAP will be developed to address these concerns.


ROC appreciates the opportunity to work with you on this project. Please call me at (575) 393-9174 if you have any questions or wish to discuss the site.

Sincerely,  
Rice Operating Company




Hack Conder  
Environmental Manager

enclosures




# Figures

**RICE Operating Company (ROC)**  
112 West Taylor Hobbs, NM 88240  
Phone 575.393.9174 Fax 575.397.1471




**Vacuum Jct. C-31**  
Unit C, Section 31, T17S, R35E  
1R425-84

**Figure 1**



Drawing date: 2-8-13



# Appendix A

Junction Box Disclosure Report

**RICE Operating Company (ROC)**  
112 West Taylor Hobbs, NM 88240  
Phone 575.393.9174 Fax 575.397.1471

**RICE OPERATING COMPANY  
JUNCTION BOX DISCLOSURE REPORT**

**BOX LOCATION**

| SWD SYSTEM | JUNCTION               | UNIT | SECTION | TOWNSHIP | RANGE | COUNTY | BOX DIMENSIONS - FEET |       |       |
|------------|------------------------|------|---------|----------|-------|--------|-----------------------|-------|-------|
|            |                        |      |         |          |       |        | Length                | Width | Depth |
| Vacuum     | Jct. C-31<br>(2 boxes) | C    | 31      | 17S      | 35E   | Lea    | Eliminated            |       |       |

LAND TYPE: BLM \_\_\_\_\_ STATE \_\_\_\_\_ FEE LANDOWNER \_\_\_\_\_ Duke Energy \_\_\_\_\_ OTHER \_\_\_\_\_

Depth to Groundwater \_\_\_\_\_ 117 \_\_\_\_\_ feet NMOCD SITE ASSESSMENT RANKING SCORE: \_\_\_\_\_ 0 \_\_\_\_\_

Date Started \_\_\_\_\_ 2/16/2009 \_\_\_\_\_ Date Completed \_\_\_\_\_ 6/8/2009 \_\_\_\_\_ OCD Witness \_\_\_\_\_ no \_\_\_\_\_

Soil Excavated \_\_\_\_\_ 266.7 \_\_\_\_\_ cubic yards Excavation Length \_\_\_\_\_ 30 \_\_\_\_\_ Width \_\_\_\_\_ 20 \_\_\_\_\_ Depth \_\_\_\_\_ 12 \_\_\_\_\_ feet

Soil Disposed \_\_\_\_\_ 156 \_\_\_\_\_ cubic yards Offsite Facility \_\_\_\_\_ Sundance \_\_\_\_\_ Location \_\_\_\_\_ Eunice, NM \_\_\_\_\_

**FINAL ANALYTICAL RESULTS:** Sample Date \_\_\_\_\_ 5/5/2009, 5/6/2009, 5/11/2009, 6/2/2009 \_\_\_\_\_ Sample Depth \_\_\_\_\_ 12 ft \_\_\_\_\_

Procure 5-point composite sample of bottom and 4-point composite sample of sidewalls. TPH, BTEX and Chloride laboratory test results completed by using an approved lab and testing procedures pursuant to NMOCD guidelines.

| Sample Location     | Benzene mg/kg | Toluene mg/kg | Ethyl Benzene mg/kg | Total Xylenes mg/kg | PID (field) ppm | GRO mg/kg | DRO mg/kg | Chlorides mg/kg |
|---------------------|---------------|---------------|---------------------|---------------------|-----------------|-----------|-----------|-----------------|
| 4-WALL COMP.        | <0.050        | <0.050        | 0.363               | 1.48                | 205.0           | 69.1      | 1110      | 2,400           |
| BOTTOM COMP.        | <0.050        | <0.050        | <0.050              | 2.77                | 490.0           | 158       | 1590      | 944             |
| BLENDED BACKFILL I  |               |               |                     |                     | 111.0           | 10.4      | 1130      | 1,200           |
| BLENDED BACKFILL II |               |               |                     |                     | 55.0            | <10.0     | 312       | 400             |

**General Description of Remedial Action:** These junction boxes were addressed during the Vacuum SWD System Abandonment. After the former junction boxes were removed, an investigation was conducted using a backhoe to collect soil samples at regular intervals producing a 30x20x12-ft deep excavation. Chloride field tests were performed on each sample and yielded elevated concentrations. Organic vapors were measured using a PID which yielded some elevated concentrations. The excavated soil was blended on site. Representative composite samples were collected from the blended excavated soil, bottom, and walls and sent to a commercial laboratory for analysis. Laboratory analysis of the representative samples confirmed elevated concentrations of chloride and DRO. The blended excavated soil was returned to the excavation up to 5 ft below ground surface (BGS) where a geosynthetic and plastic liner were installed. The remaining backfill was blended with clean, imported soil and used to backfill the excavation to ground surface and contoured to the surrounding area. On 6/8/2009, the site was seeded with a blend of native vegetation and is expected to return to a productive capacity at a normal rate. NMOCD was notified of potential groundwater impact on 3/12/2010.

**CHLORIDE FIELD TESTS**

| LOCATION  | DEPTH | mg/kg |
|---|-------|-------|
| vertical delineation trench at 5 ft west of the junction (source) | 1'    | 570   |
|   | 2'    | 840   |
|   | 3'    | 504   |
|   | 4'    | 346   |
|   | 5'    | 359   |
|   | 6'    | 360   |
|   | 7'    | 258   |
|   | 8'    | 231   |
|   | 9'    | 227   |
|   | 10'   | 266   |
|   | 11'   | 303   |
|   | 12'   | 331   |

**ADDITIONAL EVALUATION IS LOW PRIORITY**

enclosures: photos, lab results, PID (field) screenings, cross-section, BTEX study, chloride curve

I HEREBY CERTIFY THAT THE INFORMATION ABOVE IS TRUE AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

SITE SUPERVISOR \_\_\_\_\_ Jordan Woodfin \_\_\_\_\_ SIGNATURE \_\_\_\_\_ *Jordan Woodfin* \_\_\_\_\_ COMPANY \_\_\_\_\_ RICE OPERATING COMPANY \_\_\_\_\_

REPORT ASSEMBLED BY \_\_\_\_\_ Katie Jones \_\_\_\_\_ INITIAL \_\_\_\_\_ *KJ* \_\_\_\_\_

PROJECT LEADER \_\_\_\_\_ Larry Bruce Baker Jr. \_\_\_\_\_ SIGNATURE \_\_\_\_\_ *Larry Bruce Baker Jr.* \_\_\_\_\_ DATE \_\_\_\_\_ 3-25-10 \_\_\_\_\_

\*This site is a "DISCLOSURE." It will be placed on a prioritized list of similar sites for further consideration.

# Vacuum Jct C-31

Unit C, Section 31, T17S, R35E



Site prior to excavation (east)

2/16/2009




Sampling source (south west )

2/16/2009



45X20 geosynthetic liner installed

5/28/2009



Seeding backfilled site (north)

6/8/2009



**ARDINAL  
LABORATORIES**

PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

COPY

ANALYTICAL RESULTS FOR  
RICE OPERATING COMPANY  
ATTN: JORDAN WOODFIN  
122 WEST TAYLOR  
HOBBS, NM 88240  
FAX TO: (575) 397-1471

Receiving Date: 05/05/08  
Reporting Date: 05/06/09  
Project Number: NOT GIVEN  
Project Name: VACUUM JCT C-31  
Project Location: VACUUM JCT C-31

Analysis Date: 05/06/09  
Sampling Date: 05/05/09  
Sample Type: SOIL  
Sample Condition: COOL & INTACT  
Sample Received By: ML  
Analyzed By: HM

| LAB NO.                     | SAMPLE ID     | Cl <sup>-</sup><br>(mg/kg) |
|-----------------------------|---------------|----------------------------|
| H17369-1                    | 5 PT BTM COMP | 944                        |
| H17369-7                    | 4 WALL COMP   | 2,400                      |
|                             |               |                            |
|                             |               |                            |
|                             |               |                            |
|                             |               |                            |
|                             |               |                            |
|                             |               |                            |
|                             |               |                            |
| Quality Control             |               | 490                        |
| True Value QC               |               | 500                        |
| % Recovery                  |               | 98.0                       |
| Relative Percent Difference |               | 2.0                        |

METHOD: Standard Methods 4500-Cl<sup>-</sup>B

Note: Analyses performed on 1:4 w:v aqueous extracts.

*Ally Keene*  
Chemist

*05/12/09*  
Date

H17369 RICE

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced or transmitted in any form or by any means, electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Cardinal Laboratories.



**ARDINAL  
LABORATORIES**

PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

**COPY**

ANALYTICAL RESULTS FOR  
RICE OPERATING COMPANY  
ATTN: JORDAN WOODFIN  
122 W. TAYLOR  
HOBBS, NM 88240

Receiving Date: 05/05/09  
Reporting Date: 05/08/09  
Project Number: NOT GIVEN  
Project Name: VACUUM JCT C-31  
Project Location: VACUUM JCT C-31

Sampling Date: 05/05/09  
Sample Type: SOIL  
Sample Condition: COOL & INTACT  
Sample Received By: ML  
Analyzed By: AB

| LAB NUMBER SAMPLE ID        | GRO<br>(C <sub>6</sub> -C <sub>10</sub> )<br>(mg/kg) | DRO<br>(>C <sub>10</sub> -C <sub>28</sub> )<br>(mg/kg) |
|-----------------------------|--|--|
| ANALYSIS DATE               | 05/08/09   | 05/08/09   |
| H17369-1 5PT BTM COMP       | 158  | 1,590  |
| H17369-7 4 WALL COMP        | 69.1   | 1,110  |
|                             |  |  |
|                             |  |  |
|                             |  |  |
|                             |  |  |
| Quality Control             | 567  | 529  |
| True Value QC               | 500  | 500  |
| % Recovery                  | 113  | 106  |
| Relative Percent Difference | 1.9  | <0.1   |

METHODS: TPH GRO & DRO: EPA SW-846 8015 M

*Clay D. Keene*  
Chemist

05/12/09  
Date

H17369-T RICE

PLEASE NOTE: Liability and Damages: Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced, stored in full, with written consent of Cardinal Laboratories.



# ARDINAL LABORATORIES

PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

ANALYTICAL RESULTS FOR  
RICE OPERATING COMPANY  
ATTN: JORDAN WOODFIN  
122 W. TAYLOR  
HOBBS, NM 88240  
FAX TO: (575) 397-1471

COPIY


Receiving Date: 05/05/09  
Reporting Date: 05/11/09  
Project Number: NOT GIVEN  
Project Name: VACCUM JCT C-31  
Project Location: VACCUM JCT C-31


Sampling Date: 05/05/09  
Sample Type: SOIL  
Sample Condition: COOL & INTACT  
Sample Received By: ML  
Analyzed By: ZL

| LAB NUMBER                  | SAMPLE ID                       | BENZENE<br>(mg/kg) | TOLUENE<br>(mg/kg) | ETHYL<br>BENZENE<br>(mg/kg) | TOTAL<br>XYLENES<br>(mg/kg) |
|-----------------------------|---------------------------------|--------------------|--------------------|-----------------------------|-----------------------------|
| ANALYSIS DATE               |                                 | 05/10/09           | 05/10/09           | 05/10/09                    | 05/10/09                    |
| H17369-1                    | 5FT BTM COMP                    | <0.050             | <0.050             | <0.050                      | 2.77                        |
| H17369-C                    | COMPOSITE OF BTM PT. #1 THRU #5 | <0.050             | <0.050             | 0.383                       | 2.10                        |
| H17369-7                    | 4 WALL COMP                     | <0.050             | <0.050             | 0.363                       | 1.48                        |
|                             |                                 |                    |                    |                             |                             |
|                             |                                 |                    |                    |                             |                             |
|                             |                                 |                    |                    |                             |                             |
|                             |                                 |                    |                    |                             |                             |
|                             |                                 |                    |                    |                             |                             |
| Quality Control             |                                 | 0.053              | 0.053              | 0.048                       | 0.152                       |
| True Value QC               |                                 | 0.050              | 0.050              | 0.050                       | 0.150                       |
| % Recovery                  |                                 | 106                | 106                | 96.0                        | 101                         |
| Relative Percent Difference |                                 | 7.5                | 12.0               | 11.1                        | 9.2                         |

METHOD: EPA SW-846 8021B

TEXAS NELAP ACCREDITATION T104704398-08-TX FOR BENZENE, TOLUENE, ETHYL BENZENE,  
AND TOTAL XYLENES.

  
Cheryl Keene  
Chemist

  
Date

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those arising out of negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.





**ARDINAL  
LABORATORIES**

PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

ANALYTICAL RESULTS FOR  
RICE OPERATING COMPANY  
ATTN: JORDAN WOODFIN  
122 W. TAYLOR  
HOBBS, NM 88240  
FAX TO: (575) 397-1471

*OPY*

Receiving Date: 05/05/09  
Reporting Date: 05/11/09  
Project Number: NOT GIVEN  
Project Name: VACCUM JCT C-31  
Project Location: VACCUM JCT C-31

Sampling Date: 05/05/09  
Sample Type: SOIL  
Sample Condition: COOL & INTACT  
Sample Received By: ML  
Analyzed By: ZL

| LAB NUMBER | SAMPLE ID   | BENZENE,<br>(mg/kg) | TOLUENE<br>(mg/kg) | ETHYL<br>BENZENE<br>(mg/kg) | TOTAL<br>XYLENES<br>(mg/kg) |
|------------|---|---------------------|--------------------|-----------------------------|-----------------------------|
|            | ANALYSIS DATE   | 05/11/09            | 05/11/09           | 05/11/09                    | 05/11/09                    |
| H17368-C   | COMPOSITE OF NORTH,<br>SOUTH, EAST, AND WEST<br>WALLS | <0.050              | <0.050             | 0.379                       | 1.48                        |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            |   |                     |                    |                             |                             |
|            | Quality Control                                       | 0.053               | 0.053              | 0.048                       | 0.152                       |
|            | True Value QC   | 0.050               | 0.050              | 0.050                       | 0.150                       |
|            | % Recovery  | 106                 | 106                | 96.0                        | 101                         |
|            | Relative Percent Difference                           | 7.5                 | 12.0               | 11.1                        | 9.2                         |

METHOD: EPA SW-846 8021B

TEXAS NELAP ACCREDITATION T104704398-08-TX FOR BENZENE, TOLUENE, ETHYL BENZENE,  
AND TOTAL XYLENES.

*Cheryl Keene*  
Chemist

*05/12/09*  
Date

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including consequential damage and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



# CARDINAL LABORATORIES

101 East Marland, Hobbs, NM 88240 2111 Beechwood, Abilene, TX 79603  
(505) 393-2326 FAX (505) 393-2476 (325) 673-7001 FAX (325) 673-7020

## CHAIN-OF-CUSTODY AND ANALYSIS REQUEST

|   |             |                    |              |                  |  |             |            |          |     |        |        |            |            |        |
|---|-------------|--------------------|--------------|------------------|--|-------------|------------|----------|-----|--------|--------|------------|------------|--------|
| Company Name: <b>RICE OPERATING</b>                   |             | <b>BILL TO</b>     |              | ANALYSIS REQUEST |  |             |            |          |     |        |        |            |            |        |
| Project Manager: <b>JORDAN WOODFIN</b>                |             | P.O. #:            |              | COPY             |  |             |            |          |     |        |        |            |            |        |
| Address: <b>122 W. TAYLOR</b>                         |             | Company:           |              |                  |  |             |            |          |     |        |        |            |            |        |
| City: <b>HOBBS</b> State: <b>NM</b> Zip: <b>88240</b> |             | Attn:              |              |                  |  |             |            |          |     |        |        |            |            |        |
| Phone #: <b>505-2174</b> Fax #:                       |             | Address:           |              |                  |  |             |            |          |     |        |        |            |            |        |
| Project #: Project Owner:                             |             | City:              |              |                  |  |             |            |          |     |        |        |            |            |        |
| Project Name: <b>Vacuum Jet C-31</b>                  |             | State: Zip:        |              |                  |  |             |            |          |     |        |        |            |            |        |
| Project Location: <b>Vacuum Jet C-31</b>              |             | Phone #:           |              |                  |  |             |            |          |     |        |        |            |            |        |
| Sampler Name: <b>JORDAN WOODFIN</b>                   |             | Fax #:             |              |                  |  |             |            |          |     |        |        |            |            |        |
| FOR LAB USE ONLY                                      |             | MATRIX             |              |                  |  | PRESERV.    |            | SAMPLING |     |        |        |            |            |        |
| Lab I.D.  | Sample I.D. | (C/R)AB OR (C)IMP. | # CONTAINERS |                  |  | GROUNDWATER | WASTEWATER | SOIL     | OIL | SLUDGE | OTHER: | ACID/BASE: | ICE / COOL | OTHER: |
| H17368-1  | North wall  | C                  | 1            |                  |  | X           |            |          |     | X      |        |            | 5-5-09     | 3:00 P |
| -2  | South wall  | C                  | 1            |                  |  | X           |            |          |     | X      |        |            | 5-5-09     | 3:37 P |
| -3  | EAST wall   | C                  | 1            |                  |  | X           |            |          |     | X      |        |            | 5-5-09     | 3:16 P |
| -4  | West wall   | C                  | 1            |                  |  | X           |            |          |     | X      |        |            | 5-5-09     | 2:44 P |

Composite in  
labs BTEX  
ONLY

PLEASE NOTE: Liability and Damages: Cardinal's liability and client's exclusive remedy for any claim arising whether based in contract or tort, shall be limited to the amount paid by the client for the analyses. All claims including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within 30 days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above stated reasons or otherwise.

|   |   |  |  |
|---|---|--|--|
| Relinquished By: <b>JORDAN WOODFIN</b>                  | Date: <b>5-5-09</b><br>Time: <b>4:42</b>  | Received By: <b>Mark L Burt</b>        | Phone Result: <input type="checkbox"/> Yes <input type="checkbox"/> No Add'l Phone #:                              |
| Relinquished By:  | Date:   | Received By:                           | Fax Result: <input type="checkbox"/> Yes <input type="checkbox"/> No Add'l Fax #:                                  |
| Delivered By: (Circle One)<br><b>UPS</b> - Bus - Other: | Sample Condition<br>Cool Intact<br><input checked="" type="checkbox"/> Yes <input type="checkbox"/> No<br><input type="checkbox"/> No <input type="checkbox"/> No | CHECKED BY:<br>(Initials)<br><b>MB</b> | REMARKS:<br><b>Email Results to:<br/>JPURVIS@RICESWD.COM<br/>CC JWOODFIN@RICESWD.COM<br/>CC BBAKER@RICESWP.COM</b> |

† Cardinal cannot accept verbal changes. Please fax written changes to 505-393-2476



PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

ANALYTICAL RESULTS FOR  
 RICE OPERATING COMPANY  
 ATTN: JORDAN WOODFIN  
 122 W. TAYLOR  
 HOBBS, NM 88240


COPY

Receiving Date: 05/11/09  
 Reporting Date: 05/12/09  
 Project Number: NOT GIVEN  
 Project Name: VACUUM JCT C-31  
 Project Location: VACUUM JCT C-31

Sampling Date: 05/11/09  
 Sample Type: SOIL  
 Sample Condition: COOL & INTACT  
 Sample Received By: ML  
 Analyzed By: AB/HM

| LAB NUMBER SAMPLE ID        | GRO   | DRO   | CI*      |
|-----------------------------|---|---|----------|
|                             | (C <sub>6</sub> -C <sub>10</sub> )<br>(mg/kg) | (>C <sub>10</sub> -C <sub>28</sub> )<br>(mg/kg) |          |
| ANALYSIS DATE               | 05/12/09                                      | 05/12/09  | 05/12/09 |
| H17403-1 BLENDED BACKFILL   | 10.4  | 1,130   | 1,200    |
|                             |   |   |          |
|                             |   |   |          |
|                             |   |   |          |
|                             |   |   |          |
| Quality Control             | 518   | 436   | 500      |
| True Value QC               | 500   | 500   | 500      |
| % Recovery                  | 104   | 87.2  | 100      |
| Relative Percent Difference | 1.2   | 1.0   | < 0.1    |

METHODS: TPH GRO & DRO: EPA SW-846 8015 M; CI: Std. Methods 4500-CI/B  
 \*Analysis performed on a 1:4 w:v aqueous extract.

  
 Chemist

05/13/09  
 Date

H17403 TCL RICE

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.



# RICE OPERATING COMPANY COPY

122 West Taylor Hobbs, NM 88240  
 PHONE: (575) 393-9174 FAX: (575) 397-1471  
 PID METER CALIBRATION & FIELD REPORT FORM

Check Model Number:

|                                     |  |
|-------------------------------------|--|
| <input type="checkbox"/>            |  |
| <input checked="" type="checkbox"/> |  |
| <input type="checkbox"/>            |  |

Model: PGM 7300 Serial No: 590-000183  
 Model: PGM 7300 Serial No: 590-000508  
 Model: PGM 7300 Serial No: 590-000504

|                          |  |
|--------------------------|--|
| <input type="checkbox"/> |  |
| <input type="checkbox"/> |  |
| <input type="checkbox"/> |  |

Model: PGM 7600 Serial No: 110-023920  
 Model: PGM 7600 Serial No: 110-013744  
 Model: PGM 7600 Serial No: 110-013676

GAS COMPOSITION: ISOBUTYLENE 100PPM / AIR: BALANCE

|                    |                              |
|--------------------|------------------------------|
| LOT NO: 08-3425    | EXPIRATION DATE: 8-29-09     |
| FILL DATE: 2-29-08 | METER READING ACCURACY: 98.6 |

ACCURACY: +/- 2%

| SYSTEM | JUNCTION | UNIT | SECTION | TOWN SHIP | RANGE |
|--------|----------|------|---------|-----------|-------|
| Vac    | C-31     | C    | 31      | 17        | 35    |

| SAMPLE ID    | PID  | SAMPLE ID        | PID |
|--------------|------|------------------|-----|
| pt 1         | 250  | North            | 94  |
| pt 2         | 22.5 | South            | 414 |
| pt 3         | 575  | EAST             | 97  |
| pt 4         | 75   | WEST             | 203 |
| pt 5         | 55   | 4 Wall Comp      | 205 |
| Spt Btn Comp | 490  |                  |     |
|              |      | Blended Backfill | 111 |
|              |      |                  |     |
|              |      |                  |     |
|              |      |                  |     |
|              |      |                  |     |
|              |      |                  |     |
|              |      |                  |     |

I verify that I have calibrated the above instrument in accordance to the manufacture operation manual.

SIGNATURE:

DATE: 5-5-09



PHONE (575) 393-2326 • 101 E. MARLAND • HOBBS, NM 88240

ANALYTICAL RESULTS FOR  
 RICE OPERATING COMPANY  
 ATTN: JORDAN WOODFIN  
 122 W. TAYLOR  
 HOBBS, NM 88240


COPY


Receiving Date: 06/02/09  
 Reporting Date: 06/05/09  
 Project Number: NOT GIVEN  
 Project Name: VACUUM JCT C-31  
 Project Location: VACUUM JCT C-31

Sampling Date: 06/02/09  
 Sample Type: SOIL  
 Sample Condition: COOL & INTACT  
 Sample Received By: ML  
 Analyzed By: AB

| LAB NUMBER                  | SAMPLE ID           | GRO   | DRO   | CI*      |
|-----------------------------|---------------------|---|---|----------|
|                             |                     | (C <sub>6</sub> -C <sub>10</sub> )<br>(mg/kg) | (>C <sub>10</sub> -C <sub>28</sub> )<br>(mg/kg) | (mg/kg)  |
| ANALYSIS DATE               |                     | 06/04/09                                      | 06/04/09  | 06/03/09 |
| H17539-1                    | BLENDED BACKFILL II | <10.0   | 312   | 400      |
|                             |                     |   |   |          |
|                             |                     |   |   |          |
|                             |                     |   |   |          |
|                             |                     |   |   |          |
| Quality Control             |                     | 486   | 453   | 490      |
| True Value QC               |                     | 500   | 500   | 500      |
| % Recovery                  |                     | 97.2  | 90.6  | 98.0     |
| Relative Percent Difference |                     | 2.5   | 0.6   | 2.0      |

METHODS: TPH GRO & DRO: EPA SW-846 8015 M; CI: Std. Methods 4500-CI'B  
 \*Analysis performed on a 1:4 w:v aqueous extract. Reported on wet weight.

  
 Chemist

  
 Date

H17539.TCL RICE

PLEASE NOTE: Liability and Damages. Cardinal's liability and client's exclusive remedy for any claim arising, whether based in contract or tort, shall be limited to the amount paid by client for analyses. All claims, including those for negligence and any other cause whatsoever shall be deemed waived unless made in writing and received by Cardinal within thirty (30) days after completion of the applicable service. In no event shall Cardinal be liable for incidental or consequential damages, including, without limitation, business interruptions, loss of use, or loss of profits incurred by client, its subsidiaries, affiliates or successors arising out of or related to the performance of services hereunder by Cardinal, regardless of whether such claim is based upon any of the above-stated reasons or otherwise. Results relate only to the samples identified above. This report shall not be reproduced except in full with written approval of Cardinal Laboratories.







Vacuum Jct C-31  
Unit 'C', Sec. 31, T17S, R35E

### Excavation Cross-Section

N

S



# 2009 BTEX Study

# Revised Junction Box Upgrade Plan (2003)

System: Vacuum  
 Site: Jct. C-31

Date: 5/5/2009  
 Sampler: Jordan Woodfin

Laboratory: Cardinal  
 Laboratories

| Location                          | Component  | PID reading (ppm) | FIELD COMPOSITE (mg/kg) |         |               |               |
|-----------------------------------|------------|-------------------|-------------------------|---------|---------------|---------------|
|                                   |            |                   | Benzene                 | Toluene | Ethyl Benzene | Total Xylenes |
| 4-wall composite at 30 ft x 20 ft | North Wall | 94                | <0.050                  | <0.050  | 0.363         | 1.48          |
|                                   | South Wall | 414               |                         |         |               |               |
|                                   | East Wall  | 97                |                         |         |               |               |
|                                   | West Wall  | 203               |                         |         |               |               |
|                                   |            |                   | LAB COMPOSITE (mg/kg)   |         |               |               |
|                                   |            |                   | <0.050                  | <0.050  | 0.379         | 1.48          |

Field PID tests <100 ppm are considered final for BTEX. If PID is >100 ppm, the components of the BTEX composite sample will be collected individually and will be composited under laboratory conditions to prevent excessive volatilization. A 15-box, 30-sample study will be made to compare field-compositing with lab-compositing BTEX samples. Composite components are collected in a skewed 'W' pattern.

Revised Junction Box Upgrade Work Plan (July 16, 2003)

# 2009 BTEX Study

# Revised Junction Box Upgrade Plan (2003)

System: Vacuum  
 Site: Jct. C-31

Date: 5/5/2009  
 Sampler: Jordan Woodfin

Laboratory: Cardinal  
 Laboratories

| Location                      | Component | PID reading (ppm) | FIELD COMPOSITE (mg/kg) |         |               |               |
|-------------------------------|-----------|-------------------|-------------------------|---------|---------------|---------------|
|                               |           |                   | Benzene                 | Toluene | Ethyl Benzene | Total Xylenes |
| bottom composite at 12 ft BGS | 1         | 250               | <0.050                  | <0.050  | <0.050        | 2.77          |
|                               | 2         | 22.5              |                         |         |               |               |
|                               | 3         | 575               |                         |         |               |               |
|                               | 4         | 75                |                         |         |               |               |
|                               | 5         | 55                |                         |         |               |               |
|                               |           |                   | LAB COMPOSITE (mg/kg)   |         |               |               |
|                               |           |                   | <0.050                  | <0.050  | 0.383         | 2.10          |

Field PID tests <100 ppm are considered final for BTEX. If PID is >100 ppm, the components of the BTEX composite sample will be collected individually and will be composited under laboratory conditions to prevent excessive volatilization. A 15-box, 30-sample study will be made to compare field-compositing with lab-compositing BTEX samples. Composite components are collected in a skewed 'W' pattern.


Revised Junction Box Upgrade Work Plan (July 16, 2003)

# Vacuum Jct C-31


Unit 'C', Sec. 31, T17S, R35E

Backhoe samples at 5-ft west of the junction (source)

| Depth bgs (ft) | [Cl] ppm |
|----------------|----------|
| 1              | 570      |
| 2              | 840      |
| 3              | 504      |
| 4              | 346      |
| 5              | 359      |
| 6              | 360      |
| 7              | 258      |
| 8              | 231      |
| 9              | 227      |
| 10             | 266      |
| 11             | 303      |
| 12             | 331      |



Groundwater = 117 ft



# Appendix B

Quality Procedures

**RICE Operating Company (ROC)**  
112 West Taylor Hobbs, NM 88240  
Phone 575.393.9174 Fax 575.397.1471

# Rice Operating Company

## Quality Procedures

### Table of Contents

- QP-1 Soil Samples for Transportation to a Laboratory
- QP-2 Chloride Titration Using 0.282 Normal Silver Nitrate Solution
- QP-3 Development of Cased Water-Monitoring Wells
- QP-4 Sampling of Cased Water-Monitoring Well
- QP- 5 Composite Sampling of Excavation Sidewalls and Bottoms for TPH and Chloride Analysis
- QP-6 Sampling and Testing Protocol for VOC in soil
- QP-7 Composite Sampling of Excavation Sidewalls and Bottoms for BTEX
- QP-8 Procedure for Plugging and Abandonment of Cased Water-Monitoring wells

## Rice Operating Company

---

### Quality Procedure Soil Samples for Transportation to a Laboratory

---

#### 1.0 Purpose

This procedure outlines the methods to be employed when obtaining soil samples to be taken to a laboratory for analysis.

#### 2.0 Scope

This procedure is to be used when collecting soil samples intended for ultimate transfer to a testing laboratory.

#### 3.0 Preliminary

- 3.1 Obtain sterile sampling containers from the testing laboratory designated to conduct analyses of the soil.
- 3.2 If collecting TPH, BTEX, RCRA 8 metals, cation /anions or O&G, the sample jar may be a clear 4 oz. container with Teflon lid. If collecting PAH's, use an amber 4 oz. container.

#### 4.0 Chain of Custody

- 4.1 Prepare a Sample Plan. The plan will list the number, location and designation of each planned sample and the individual tests to be performed on the sample. The sampler will check the list against the available inventory of appropriate sample collection bottles to insure against shortage.
- 4.2 Transfer the data to the Laboratory Chain of Custody Form. Complete all sections of the form except those that relate to the time of delivery of the samples to the laboratory.
- 4.3 Pre-label the sample collection jars. Include all requested information except time of collection. (Use a fine point Sharpie to insure that the ink remains on the label.) Affix the labels to the jars.

#### 5.0 Sampling Procedure

- 5.1 Do not touch the soil with your bare hands. Use new nitrile gloves to help minimize any contamination.
- 5.2 Go to the sampling point with the sample container. If not analyzing for ions or metals, use a trowel to obtain the soil.

5.3 Pack the soil tightly into the container leaving the top slightly domed. Screw the lid down tightly. Enter the time of collection onto the sample collection jar label.

5.4 Place the sample directly on ice for transport to the laboratory if required.

5.5 Complete the Chain of Custody form to include the collection times for each sample. Deliver all samples to the laboratory.

## **6.0 Documentation**

6.1 The testing laboratory shall provide the following minimum information:

- a. Project and sample name.
- b. Signed copy of the original Chain of Custody Form including the time the sample was received by the lab.
- c. Results of the requested analyses
- d. Test Methods employed
- e. Quality Control methods and results

## Rice Operating Company

---

### QUALITY PROCEDURE Chloride Titration Using 0.282 Normal Silver Nitrate Solution

---

#### 1.0 Purpose

This procedure is to be used to determine the concentration of chloride in soil.

#### 2.0 Scope

This procedure is to be used as the standard field measurement for soil chloride concentrations.

#### 3.0 Sample Collection and Preparation

- 3.1 Collect at least 80 grams of soil from the sample collection point. Take care to insure that the sample is representative of the general background to include visible concentrations of hydrocarbons and soil types. If necessary, prepare a composite sample for soils obtained at several points in the sample area. Take care to insure that no loose vegetation, rocks or liquids are included in the sample(s).
- 3.2 The soil sample(s) shall be immediately inserted into a one-quart or larger polyethylene freezer bag. Care should be taken to insure that no cross-contamination occurs between the soil sample and the collection tools or sample processing equipment.
- 3.3 The sealed sample bag should be massaged to break up any clods.

#### 4.0 Sample Preparation

- 4.1 Tare a clean glass vial having a minimum 40 ml capacity. Add at least 10 grams of the soil sample and record the weight.
- 4.2 Add at least 20 grams of reverse osmosis water to the soil sample and shake well.
- 4.3 Allow the sample to set for a period of 5 minutes or until the separation of soil and water.

#### 5.0 Titration Procedure

- 5.1 Using a graduated pipette, remove 10 ml extract and dispense into a clean plastic cup.
- 5.2 Add 2-3 drops potassium chromate ( $K_2CrO_4$ ) to mixture if necessary.

5.3 Using a 1 ml pipette, carefully add .282 normal silver nitrate (one drop at a time) to the sample while constantly agitating it. Stop adding silver nitrate when the solution begins to change from yellow to red. Be consistent with endpoint recognition.

5.4 Record the ml of silver nitrate used.

#### 6.0 Calculation

To obtain the chloride concentration, insert measured data into the following formula:

$$\frac{.282 \times 35,450 \times \text{ml AgNO}_3}{\text{ml water extract}} \times \frac{\text{grams of water in mixture}}{\text{grams of soil in mixture}}$$

Using Step 5.0, determine the chloride concentration of the RO water used to mix with the soil sample. Record this concentration and subtract it from the formula results to find the net chloride in the soil sample.

Record all results on the delineation form.

---

## Rice Operating Company

---

### Quality Procedure Development of Cased Water-Monitoring Wells

---

#### 1.0 Purpose

This procedure outlines the methods to be employed to develop cased monitoring wells.

#### 2.0 Scope

This procedure shall be used for developed, cased water monitoring wells. It is not to be used for standing water samples such as ponds or streams.

#### 3.0 Sample Collection and Preparation

- 3.1 Prior to development, the static water level and height of the water column within the well casing will be measured with the use of an electric D.C. probe.
- 3.2 All measurements will be recorded within a field log notebook.
- 3.3 All equipment used to measure the static water level will be decontaminated after each use by means of Liquinox, a phosphate free laboratory detergent, and water to reduce the possibility of cross-contamination. The volume of water in each well casing will be calculated.

#### 4.0 Purging

- 4.1 Wells will be purged by using a 2" decontaminated submersible pump or dedicated one liter Teflon bailer. Wells should be purged until the pH and conductivity are stabilized and the turbidity has been reduced to the greatest extent possible.
- 4.2 If a submersible is used the pump will be decontaminated prior to use by scrubbing the outside surface of tubing and wiring with a Liquinox water mixture, pumping a Liquinox-water mixture through the pump, and a final flush with fresh water.

#### 5.0 Water Disposal

- 5.1 All purge and decontamination water will be temporarily stored within a portable tank to be later disposed of in an appropriate manner.

#### 6.0 Records

- 6.1 Rice Environmental Consulting and Safety will record the amount of water removed from the well during development procedures. The purge volume will be reported to the appropriate regulatory authority when filing the closure report.

## Rice Operating Company

---

### Quality Procedure Sampling of Cased Water-Monitoring Well

---

#### 1.0 Purpose

This procedure outlines the methods to be employed in obtaining water samples from cased monitoring wells.

#### 2.0 Scope

This procedure shall be used for developed, cased water monitoring wells. It is not to be used for standing water samples such as ponds or streams.

#### 3.0 Preliminary

3.1 Obtain sterile sampling containers from the testing laboratory designated to conduct analyses of the water.

3.2 The following table shall be used to select the appropriate sampling container, preservative method and holding times for the various elements and compounds to be analyzed.

| Compound to be Analyzed | Sample Container Size | Sample Container Description          | Cap Requirements | Preservative         | Maximum Hold Time |
|-------------------------|-----------------------|---------------------------------------|------------------|----------------------|-------------------|
| BTEX                    | 40 ml                 | VOA Container                         | Teflon Lined     | HCL                  | 14 days           |
| TPH (8015 Extended)     | 40 ounces             | (2) 40ml VOA vials                    | Teflon Lined     | HCL and Ice          | 14 days           |
| PAH                     | 1 liter               | amber glass                           | Teflon Lined     | Ice                  | 7 days            |
| Cation/Anion            | 1 liter               | HD polyethylene                       | Any Plastic      | None                 | 48 Hrs            |
| Metals                  | 1 liter               | HD polyethylene                       | Any Plastic      | Ice/HNO <sub>3</sub> | 28 Days           |
| TDS                     | 300 ml                | clear glass or 250 ml HD polyethylene | Any Plastic      | Ice                  | 7 Days            |
| Cl-                     | 500 ml                | HD polyethylene                       | Any Plastic      | None                 | 28 Days           |

#### **4.0 Chain of Custody**

- 4.1 Prepare a Sample Plan. The plan will list the well identification and the individual tests to be performed at that location. The sampler will check the list against the available inventory of appropriate sample collection bottles to insure against shortage.
- 4.2 Transfer the data to the Laboratory Chain of Custody Form. Complete all sections of the form except those that relate to the time of delivery of the samples to the laboratory.
- 4.3 Pre-label the sample collection jars. Include all requested information except time of collection. (Use a fine point Sharpie to insure that the ink remains on the label). Affix the labels to the jars.

#### **5.0 Bailing Procedure**

- 5.1 Identify the well from the sites schematics. Place pre-labeled jar(s) next to the well. Remove the plastic cap from the well bore by first lifting the metal lever and then unscrewing the entire assembly.
- 5.2 Using a dedicated one liter Teflon bailer or submersible pump, purge a minimum of three well volumes. Place the water in storage container for transport to a ROC disposal facility.
- 5.3 If using a bailer, take care to insure that the bailing device and string does not become cross-contaminated. A clean pair of nitrile gloves should be used when handling either the retrieval string or bailer. The retrieval string should not be allowed to come into contact with the ground.

#### **6.0 Sampling Procedure**

- 6.1 Once the well has been bailed in accordance with 5.2 of this procedure, a sample may be decanted into the appropriate sample collection jar directly from the bailer or submersible pump.
- 6.2 Note the time of collection on the sample jar with a fine Sharpie.
- 6.3 Place the sample directly on ice for transport to the laboratory. The preceding table shows the maximum hold times between collection and testing for the various analyses.

6.4 Complete the Chain of Custody form to include the collection times for each sample. Deliver all samples to the laboratory.

## 7.0 Documentation

7.1 The testing laboratory shall provide the following minimum information:

- A. Project and sample name.
- B. Signed copy of the original Chain of Custody Form including the time the sample was received by the lab.
- C. Results of the requested analyses
- D. Test Methods employed
- E. Quality Control methods and results

### Calculation for Determining the Minimum Bailing Volume for Monitor Wells

$$\text{Formula } V = (\pi r^2 h)$$

$$2'' \text{ well } [V/231 = \text{gal}] \times 3 = \text{Purge Volume}$$

V=Volume

$\pi = \text{pi}$

r=inside radius of the well bore

h=maximum height of well bore in water table

Example:

| $\pi$  | $r^2$ | h(in) | V(cu.in) | V(gal) | X 3 Volumes | Actual  |
|--------|-------|-------|----------|--------|-------------|---------|
| 3.1416 | 1     | 180   | 565.488  | 2.448  | 7.34 gal    | >10 gal |

## Rice Operating Company

---

### Quality Procedure Composite Sampling of Excavation Sidewalls and Bottoms For TPH and Chloride Analysis

---

#### 1.0 Purpose

This procedure outlines the methods to be employed when obtaining final composite soil samples for TPH and Chloride analysis.

#### 2.0 Scope

This procedure is to be used in conjunction with *Quality Procedure – 02: Soil Samples for Transportation to a Laboratory* and will be inserted at subparagraph 5.2 of Section 5.0: Sampling Procedure.


#### 3.0 Sampling Procedure

Follow *Quality Procedure – 02: Soil Samples for Transportation to a Laboratory* for all Sections and subparagraphs until subparagraph 5.2 of Section 5.0: Sampling Procedure. Instead of 5.2 instructions, perform the composite sample collection procedure as follows:

3.1 Go to the excavation with a new plastic baggie. If not analyzing for ions or metals, use a trowel to obtain the soil. If the excavation is deeper than 6' BGS, do not enter the pit, but use a backhoe to assist in procurement of the sample. (If a backhoe is used, the backhoe will obtain an amount of soil from each composite point; bring the purchase to the surface staging area where a sample-portion of soil will be extracted from the backhoe purchase. The remainder of the backhoe purchase will be staged on the surface with other staged soils.)

#### 3.2 Sidewall samples

3.2.1 On each sidewall, procure a 5oz sample from each of five distinct points on the sidewall with distinct points resembling the "W" pattern:



- 3.2.2 Thoroughly blend these five samples in a labeled baggie.
- 3.2.3 Repeat steps 3.2.1 through 3.2.4 for each remaining sidewall.
- 3.2.4 From each labeled baggie, procure a 5 oz portion and pour into a baggie labeled "Sidewall Composite". Blend this soil mixture completely.
- 3.2.5 Obtain proper laboratory sample container for "Sidewall Composite" and continue with subparagraph 5.3 of QP – 01.

### 3.3 Bottom Sample

- 3.3.1 From bottom of excavation, procure a 5oz sample from each of five distinct points with distinct points resembling the "W" pattern as illustrated above.
- 3.3.2 Thoroughly blend these five samples in a clean baggie.
- 3.3.3 Obtain proper laboratory sample container for "Bottom Composite" and continue with subparagraph 5.3 of QP – 01.

## Rice Operating Company

---

### QUALITY PROCEDURE

#### Sampling and Testing Protocol for VOC in Soil

---

#### 1.0 Purpose

This procedure is to be used to determine the concentrations of Volatile Organic Compounds in soils.

#### 2.0 Scope

This procedure is to be used as the standard field measurement for soil VOC concentrations. It is not to be used as a substitute for full spectrographic speciation of organic compounds.

#### 3.0 Procedure

##### 3.1 Sample Collection and Preparation

3.1.1 Collect at least 500 g. of soil from the sample collection point. Take care to insure that the sample is representative of the general background to include visible concentrations of hydrocarbons and soil types. If necessary, prepare a composite sample of soils obtained at several points in the sample area. Take care to insure that no loose vegetation, rocks or liquids are included in the sample(s).

3.1.2 The soil sample(s) shall be immediately inserted into a one-quart or larger polyethylene freezer bag and sealed. When sealed, the bag should contain a nearly equal space between the soil sample and trapped air. Record the sample name and the time that the sample was collected on the Field Analytical Report Form.

3.1.3 The sealed samples shall be allowed to set for a minimum of five minutes at a temperature of between 10-15 Celsius, (59-77<sup>0</sup> F). The sample temperatures may be adjusted by cooling the sample in ice, or by heating the sample within a generally controlled environment such as the inside of a vehicle. The samples should not be placed directly on heated surfaces or placed in direct heat sources such as lamps or heater vents.

3.1.4 The sealed sample bag should be massaged to break up any clods, and to provide the soil sample with as much exposed surface area as practically possible.

### 3.2 Sampling Procedure

- 3.2.1 The instrument to be used in conducting VOC concentration testing shall be a RAE Systems Photoionization device. (Device will be identified on VOC Field Test Report Form.) Prior to use, the instrument shall be zeroed-out in accordance with the appropriate maintenance and calibration procedure outlined in the instrument operation manual. The PID device will be calibrated each day it's used.
- 3.2.2 Carefully open one end of the collection bag and insert the probe tip into the bag taking care that the probe tip not touch the soil sample or the sidewalls of the bag.
- 3.2.3 Set the instrument to retain the highest result reading value. Record the reading onto the Field Test Report Form.
- 3.2.4 **If the instrument provides a reading exceeding 100 ppm, proceed to QP-7. If the reading is 100 ppm or less, NMOCDBTEX guideline has been met and no further testing for BTEX is necessary. File the Field Test Report Form in the project file.**

### 4.0 Clean-up

After testing, the soil samples shall be returned to the sampling location, and the bags collected for off-site disposal. **IN NO CASE SHALL THE SAME BAG BE USED TWICE. EACH SAMPLE CONTAINER MUST BE DISCARDED AFTER EACH USE.**

## **Rice Operating Company**

---

### **Quality Procedure Composite Sampling of Excavation Sidewalls and Bottoms For BTEX**

---

#### **1.0 Purpose**

This procedure outlines the methods to be employed when obtaining final composite soil samples for BTEX analysis.

#### **2.0 Scope**

This procedure is to be used when collecting soil samples intended for ultimate transfer to a testing laboratory for BTEX analysis. This procedure is to be used only when the PID field-test results for OVM exceeds 100 ppm.

#### **3.0 Preliminary**

3.1 Obtain sterile, clear, 2 oz. glass containers with Teflon lid from a laboratory supply company or the testing laboratory designated to conduct analyses of the soil.

#### **4.0 Chain of Custody**

4.1 Prepare a Sample Plan. The plan will list the number, location and designation of each planned sample and the individual tests to be performed on the sample. The sampler will check the list against the available inventory of appropriate sample collection bottles to insure against shortage.

4.2 Transfer the data to the Laboratory Chain of Custody Form. Complete all sections of the form except those that relate to the time of delivery of the samples to the laboratory.

4.3 Pre-label the sample collection jars. Include all requested information except time of collection. (Use a fine point Sharpie to insure that the ink remains on the label.) Affix the labels to the jars.

#### **5.0 Sampling Procedure**


5.1. Do not touch the soil with your bare hands. Use new nitrile gloves to help minimize any cross-contamination.

5.2. If safe and within OSHA regulations, go to the sampling point with the sample container. If not analyzing for ions or metals, use a trowel to

obtain the soil. If the excavation is deeper than 6' BGS, do not enter the pit, but use a backhoe to assist in procurement of the sample. (If a backhoe is used, the backhoe will obtain an amount of soil from each composite point; bring the purchase to the surface staging area where a sample-portion of soil will be extracted from the backhoe purchase. The remainder of the backhoe purchase will be staged on the surface with other staged soils.)

### 5.3. Sidewall Samples

5.3.1 On each sidewall, procure a 2oz sample from each of five distinct points on the sidewall with distinct points resembling the "W" pattern:



5.4. Pack the soil tightly into the container leaving the top slightly domed. Screw the lid down tightly. Enter the time of collection onto the sample collection jar label. Repeat for each sampling point.

5.5. Place the samples directly on ice for transport to the laboratory if required.

5.6. Complete the Chain of Custody form to include the collection times for each sample. Deliver all samples to the laboratory.

## 6.0 Documentation

6.1 The testing laboratory shall provide the following minimum information:

- a. Project and sample name.
- b. Signed copy of the original Chain of Custody Form including the time the sample was received by the lab.
- c. Results of the requested analyses
- d. Test Methods employed
- e. Quality Control methods and results

## **Rice Operating Company**

---

### **Procedure for Plugging & Abandonment of Cased Water Monitoring Wells**

---

#### **1.0 Purpose**

This procedure outlines the methods to be employed to plug and abandon cased monitoring wells.

#### **2.0 Scope**

This procedure shall be used for developed, cased water monitoring wells located in the State of New Mexico

#### **3.0 Preliminary**

3.1 No well may be drilled, modified or plugged without NMOCD approval. Additional approvals may be required if the well is situated in a sensitive area, within municipal jurisdictions or on federal or tribal lands.

#### **4.0 Plugging**

4.1 Each bore will be filled with a 1% - 3% bentonite/concrete slurry to three feet bgs. The remaining three feet will be capped with concrete only.

4.2 All wellheads will be removed to below ground surface.

#### **5.0 Records**

5.1 The company plugging the well shall prepare a report on their company letter head listing the site name and describing general well construction including total depth of the well, the diameter of casing, material used to plug the well (e.g. bentonite/cement slurry), and date of the plugging operation.

5.2 It is recommended but not required that photographs of the final surface restoration be taken and included within the records.

5.3 Copies of the plugging report shall be submitted to all appropriate agencies and retained by the well operator for a minimum period of ten years.