1R-427-78

APPROVALS

YEAR(S):

Hansen, Edward J., EMNRD

From: Hansen, Edward J., EMNRD

Sent: Tuesday, June 04, 2013 3:09 PM

To: Hack Conder (hconder@riceswd.com)

Cc: Leking, Geoffrey R, EMNRD; Laura Pena (Ipena@riceswd.com); Katie Jones

<kjones@riceswd.com> (kjones@riceswd.com); Scott Curtis (scurtis@riceswd.com)

Subject: Remediation Plan (1R427-78) Termination - ROC EME M-9-4 Site

RE: Termination Request

for the Rice Operating Company's

EME M-9-4 Site

Unit Letter M, Section 9, T20S, R37E, NMPM, Lea County, New Mexico

Remediation Plan (1R427-78) Termination

Dear Mr. Conder:

The New Mexico Oil Conservation Division (OCD) has received Rice Operating Company's report and request to close the above-referenced site, dated May 22, 2013 (received May 30, 2013). The reports are acceptable to the OCD.

The above-referenced report, submitted in accordance with 19.15.29 NMAC (Rule 29; formally, Rule 116), indicates that Rice Operating Company has met the requirements of 19.15.29 NMAC; therefore, the OCD approves the report and hereby notifies you that the remediation plan (1R427-78) is terminated in accordance with 19.15.29 NMAC.

Please be advised that OCD approval of this report does not relieve the owner/operator of responsibility should operations pose a threat to ground water, surface water, human health or the environment. In addition, OCD approval does not relieve the owner/operator of responsibility for compliance with any OCD, federal, state, or local laws and/or regulations.

If you have any questions regarding this matter, please contact me at 505-476-3489.

Edward J. Hansen Hydrologist Environmental Bureau

RICE Operating Company

122 West Taylor • Hobbs, New Mexico 88240 Phone: (575) 393-9174 • Fax: (575) 397-1471

CERTIFIED MAIL
RETURN RECEIPT NO. 7007 2560 0000 4569 9248

May 22, 2013

Mr. Edward Hansen New Mexico Energy, Minerals, & Natural Resources Oil Conservation Division, Environmental Bureau 1220 S. St. Francis Drive Santa Fe, New Mexico 87505 RECEIVED

MAY 3 0 2013

Oil Conservation Division 1220 S. St. Francis Drive Santa Fe, NM 87505

RE: Termination Request

EME M-9-4 (1R427-78): UL/M, Sec. 9, T20S, R37E

RICE Operating Company - Eunice Monument Eumont SWD System

Mr. Hansen:

Rice Operating Company (ROC) is the service provider (agent) for the EME Saltwater Disposal (SWD) System and has no ownership of any portion of the pipeline, well, or facility. The System is owned by a consortium of oil producers, System Parties, who provide all operating capital on a percentage ownership/usage basis.

Background

In 2002, ROC initiated work on the former M-9-4 junction box. The site is located in UL/M, Sec. 9, T20S, R37E. NM OSE records indicate that groundwater would likely be encountered at a depth of approximately 18 +/- feet. On April 2, 2002, a monitoring well (MW-1) was installed a few feet south of the former junction boxes to further access if groundwater was impacted.

Excavation operations began with the removal of the junction boxes according to the Redwood Tank Replacement/Closure Plan for EME SWD Site M-9, including M-9-4, on June 19, 2002. After the former junction box was removed, the site was delineated using a backhoe to collect soil samples at regular intervals, creating a 110x100x20 ft deep excavation. Each sample was field titrated for chlorides, resulting in low concentrations. Representative composite samples of the excavation bottom and the excavation walls were sent to a commercial for analysis of chloride, TPH and BTEX, resulting in a sidewall chloride concentration of 245 mg/kg and concentrations of gasoline range organics (GRO), diesel range organics (DRO) and BTEX below detectable limits. The bottom composite resulted in a chloride concentration of 95 mg/kg and concentrations of GRO, DRO and BTEX below detectable limits. The site was backfilled to 4 ft below

ground surface (BGS) where a compacted red-bed clay layer was installed and density tested. The clay layer will provide a barrier that will inhibit the downward migration of chlorides to groundwater. The excavation was backfilled with remediated soil to ground surface and contoured to the surrounding area. The remediated soil was tested in 3 ft lifts, resulting in low concentrations of chloride. A new, water-tight junction box was built over the same location within an active facility; therefore, seeding is not necessary.

Due to the horizontal extent of the excavation, MW-1 was lost and a replacement monitor well (MW-1A) was installed adjacent to the southeast corner of the excavated area. From 2003 to 2007, six additional monitor wells were installed under the Stage 1 Abatement Plan for M-9 SWD (AP-65) and have since been plugged and abandoned.

On July 24, 2009, a termination request was submitted to NMOCD for the M-9 SWD facility site, which is inclusive of M-9-4, based on chloride concentrations in the vadose zone of all borings, monitoring wells, and excavations averaging less than 250 mg/kg, which is representative of background levels. The excavation, backfilling, and installation of a clay layer performed by ROC mitigated any potential threat of constituents of concern (BTEX, chlorides, or TDS) from the area into the vadose zone or groundwater. Groundwater quality conditions on site are at or near background levels and six years of groundwater monitoring have supported the conclusions herein. NMOCD approved the termination request on September 22, 2009.

The junction box site location map, area map, final report, laboratory analysis and current photodocumentation are attached.

Recommendations

Site investigation demonstrates that residual chloride and hydrocarbons in the vadose zone will not with reasonable probability contaminate groundwater in excess of NMOCD standards. This site meets the requirements of the NMOCD-approved Revised Junction Box Upgrade Work Plan (July 16, 2003). As such, ROC request termination of the regulatory file, or similar closure status.

Please contact me at (575)393-9174 if you have any questions or wish to discuss this site. Thank you for your time and consideration.

Sincerely,

RICE Operating Company

Hack Conder

Environmental Manager

enclosures

RECEIVED OCD



RICE *Operating Company* (ROC) 112 West Taylor Hobbs, NM 88240 Phone: (575) 393-9174 Fax: (575) 397-1471


Site Location Map

		Total Indiana		Oile	LUCA	LIOII			2-14-1-			
20	21	22	23	24	19	20	21	22	23	24	19	20
29	28	27 19S 36E	26	25	30 Jot	29 322	Monumer		1	25	30 19S 38	
32	33	Childress Rd	Name and Address of the Owner, where the Person of the Owner, where the Person of the Owner, where the Owner, which is the Owner, where the Owner, which is	MON 36	UMEN	T, NM	19S 3	7E 34	35	36	31	32
5	4			Maddox Road	6	5		3	2 Billy Wal	lker Rd.		5
8	9	10.1		12	7	8	THE PERSON NAMED IN	10 M-9-4	n a	12	7	8
37	16	15	14	13	18	17	16 208		14	. 43	18 20S 38	17.02
20	21	20S 36E	23	24	19	20	205	22	25	24	19	20
	28	27,	Tuffy C	ooper Rd. 25	30	29		27	26	25	30	29
32	33	134,	.35	36	31	32	23	34	35	36	31	32
1	3	2		6	5	a Huy 17		2		6	5	A
9	10	- 11	12	7	8	9	10	n	12	7	8	
	215	35E	1000			21	1S 36E			21	S 37E	
16	15	14	13 HV	18 vy 176	17	16	15	14	13 3	18	17	
21	22	23	24 1	19	20	21.0	22	23 HWY 8	24	19	20	The second
28	27	26	25	30	29	28	27	26	7 25	30	29	
											N	




EME M-9-4 (1R427-78)

UL/M SECTION 9 T20S, R37E LEA COUNTY, NM




Area Map





EME M-9-4 (1R427-78)

UL/M SECTION 9 T20S, R37E LEA COUNTY, NM



Junction Box Report

RICE *Operating Company* (ROC) 112 West Taylor Hobbs, NM 88240 Phone: (575) 393-9174 Fax: (575) 397-1471

RICE OPERATING COMPANY JUNCTION BOX FINAL REPORT

BOX LOCATION
SECTION TOWNSHIP RANGE COUNTY

SWD SYSTEM JUNCTION

EME M-9-4 M 9 20S 37E LEA LAND TYPE: BLM STATE FEE LANDOWNER S & W CATTLE OF STATE	Length	Width	
LAND TYPE: BLM STATE FEE LANDOWNER S & W CATTLE O	1		Depth
	CO OTHER		
Depth to Groundwater 18 feet NMOCD SITE ASSESSMEN	-	• •	
Date Started 06/19/2002 Date Completed 09/09/2002 OC	D Witness	YES	3
Soil Excavated 8000 cubic yards Excavation Length 110 Wi	idth <u>100</u>	Depth	20 feet
Soil Disposedcubic yards	Location		
FINAL ANALYTICAL RESULTS: Sample Date 09/09/2002	_ 	·	20
Procure 5-point composite sample of bottom and 4-point co	-		
Sample Benzene Toluene Ethyl Benzene Total Xylenes	GRO	DRO	Chlorides
Location mg/kg mg/kg mg/kg mg/kg SIDEWALLS <0.025	mg/kg <10	mg/kg <10	mg/kg 245
BOTTOM <0.025 <0.025 <0.025 <0.025	<10	<10	95
area excavated and remediated at the M-9 SWD Facility. All samples and test results were		т~	
taken form the M-9 SWD Facility remediation site. The site was excavated to 20' bgs and	LOCATION	DEPTH	mg/kg
then backfilled with 4' of clean overburden soil. A compacted red-bed clay liner was installed	SIDEWALLS	13'	260
and density tested. The excavation was backfilled with remediated soil. The remediated soil was	воттом	20'	100
tested in 3' lifts. A monitor well was installed to sample groundwater constituents. Any remaining,	4' fill above gw	16'	220
hydrocarbon will naturally attenuate.	1st lift above liner	12'	310
	2nd lift	9'	350
	3rd lift	6'	320
	4th lift	3'	360
	Surface	0'	471
	MPLETE TO 1	THE BEST OF	= MY
I HEREBY CERTIFY THAT THE INFORMATION ABOVE IS TRUE AND CO			
KNOWLEDGE AND BELIEF.			
	D. E.	Anderson	

ANALYTICAL REPORT

Prepared for:

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768

Project:

Rice

.

PO#:

Order#:

G0204401

Report Date:

09/04/2002

Certificates

US EPA Laboratory Code TX00158

SAMPLE WORK LIST

RE ENVIRONMENTAL

P.O. BOX 13418

ODESSA, TX 79768

366-0804

Lab ID:

0204401-01

Order#:

G0204401

Project:

Project Name: Rice

Location:

M-9 EME

The samples listed below were submitted to Environmental Lab of Texas and were received under chain of custody. Environmental Lab of Texas makes no representation or certification as to the method of sample collection, sample identification, or transportation/handling procedures used prior to the receipt of samples by Environmental Lab of Texas, unless otherwise noted.

Date / Time Date / Time Sample: Collected Received Container Matrix: Preservative 8/28/02 Bottom Composite @20' SOIL 8/29/02 4 oz Glass Ice 15:00 16:30 Rejected: No 0.5C Lab Testing: Temp:

8015M

8021B/5030 BTEX

Chloride

ANALYTICAL REPORT

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768 Order#:

G0204401

Project:

Project Name:

Rice

Location:

M-9 EME

Lab ID:

0204401-01

Sample ID:

Bottom Composite @20'

8015M

Method Blank Date Prepared Date Analyzed 8/30/02 Sample Amount

1

Dilution Factor

1

Analyst

CK

Method 8015M

 Parameter
 Result mg/kg
 RL

 GRO, C6-C12
 <10.0</td>
 10.0

 DRO, >C12-C35
 <10.0</td>
 10.0

 TOTAL, C6-C35
 <10.0</td>
 10.0

8021B/5030 BTEX

Method Blank	Date Prepared	Date <u>Analyzed</u>	Sample Amount	Dilution <u>Factor</u>	Analyst	Method
0003022-02	•	9/1/02	1	25 ·	CK	8021B
		9:30				

Parameter ·	Result mg/kg	RL .
Benzene	<0.025	0.025
Ethylbenzene	<0.025	0.025
Toluene	<0.025	0.025
p/m-Xylene	<0.025	0.025
o-Xylene	<0.025	0.025

Surrogates	% Recovered	QC Limits (%	
aaa-Toluene	106%	80	120
Bromofluorobenzene	119%	80	120

Approval:

Raland K. Tuttle, Lab Director, QA Officer

Celey D. Keene, Org. Tech. Director Jeanne McMurrey, Inorg. Tech. Director

Sandra Biezugbe, Lab Tech.

Sara Molina, Lab Tech:

.53

Page 1 of 1

ANALYTICAL REPORT

LOGAN ANDERSON RE ENVIRONMENTAL

P.O. BOX 13418 ODESSA, TX 79768 Order#:

G0204401

Project:

Project Name: Location:

Rice M-9 EME

Lab ID:

0204401-01

Sample ID:

Bottom Composite @20'

Test Parameters

Parameter Chloride

Result

mg/kg

94.5

Units

Dilution **Factor**

RL20

Date Method

9253

Analyzed Analyst

SB

9/4/02

Approval:

Raland K. Tuttle, Lab Director, QA Officer Celey D. Keene, Org. Tech. Director Jeanne McMurrey, Inorg. Tech. Director

Sandra Biezugbe, Lab Tech. Sara Molina, Lab Tech.

QUALITY CONTROL REPORT

8015M

BLANK	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg		0003018-02	•		<10.0		·
MS	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg		0204400-04	198	952	1124	97.3%	
MSD	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr,	QC Test Result	Pet (%) Recovery	RPD
TOTAL, C6-C35-mg/kg		0204400-04	198	952	1144	99.4%	1.8%
SRM	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg		0003018-05		1000	1030	103.%	

QUALITY CONTROL REPORT

8021B/5030 BTEX

BLANK	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0003022-02			<0.025		 -
Ethylbenzene-mg/kg		0003022-02			<0.025		
Toluene-mg/kg	•	0003022-02			<0.025	<u> </u>	_
p/m-Xylene-mg/kg		0003022-02	1		<0.025		
o-Xylene-mg/kg		0003022-02			<0.025	-	
MS	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0204388-07	0	0.1	0.089	89.%	
Ethylbenzene-mg/kg		0204388-07	0	0.1	0.090	90.%	
Toluene-mg/kg		0204388-07	0	0.1	0.091	91.%	
p/m-Xylene-mg/kg	·	0204388-07	0	0.2	0.188	94.%	
o-Xylene-mg/kg		0204388-07	0	0.1	0.091	91.%	
MSD	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0204388-07	0	0.1	0.094	94.%	5.5%
Ethylbenzene-mg/kg		0204388-07	0	0.1	0.095	95.%	5.4%
Toluene-mg/kg		0204388-07	0	0.1	0.097	97.%	6.4%
p/m-Xylene-mg/kg		0204388-07	0	0.2	0.198	99.%	5.2%
Kylene-mg/kg		0204388-07	0	0.1	0.095	95.%	4.3%
ن <i>RM</i>	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0003022-05		0.1	0.096	96.%	······
Ethylbenzene-mg/kg		0003022-05		0.1	0.097	97.%	
Toluene-mg/kg		0003022-05		0.1	0.098	98.%	
p/m-Xylene-mg/kg		0003022-05	······	0.2	0.201	100.5%	
o-Xylene-mg/kg		0003022-05		0.1	0.097	97.%	

QUALITY CONTROL REPORT

Test Parameters

Order#; G0204401

BLANK	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pet (%) Recovery	RPD
Chloride-mg/kg		0003049-01			<20.0		
MS	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pet (%) Recovery	RPD
Chloride-mg/kg	-	0204401-01	94.5	667	756	99.2%	
MSD	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg		0204401-01	94.5	667	744	97.4%	1.6%
SRM	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg		0003049-04		5000	4960	99.2%	

Envi mental Lab of Texas I, Ltd. 12600 West I-20 East Phone: 915-563-1800 CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST Odessa, Texas 79763 Fax: 915-563-1713 Project Name: Project Manager: Company Name LE Environmenta Company Address: City/State/Zip: Telephone No: Fax No: Sampler Signature: Analyze For. TOTAL: Preservalive Matrix RUSH TAT (Pre-Schedule) NaOH H₃SO₄ HNO, FIELD CODE Botton Composite @20' 8-28-02 3:00 P Special Instructions Tax Results to Donnie Anderson Received by: Relinguished by: Date 4:300

Relinquished by:

Date

ANALYTICAL REPORT

Prepared for:

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768

Project:

Rice

.PO#:

Order#:

G0204422

Report Date:

09/06/2002

Certificates

US EPA Laboratory Code TX00158

SAMPLE WORK LIST

RE ENVIRONMENTAL

P.O. BOX 13418

ODESSA, TX 79768

366-0804

Order#:

G0204422

Project:

Project Name: Rice

Location:

M-9

The samples listed below were submitted to Environmental Lab of Texas and were received under chain of custody. Environmental Lab of Texas makes no representation or certification as to the method of sample collection, sample identification, or transportation/handling procedures used prior to the receipt of samples by Environmental Lab of Texas, unless otherwise noted.

Lab ID:	Sample:	Matrix:	Date / Time Collected	Date / Time Received	Container	Preservative
0204422-01	5 pt. Wall Comp. @ 13'	SOIL	8/30/02 15:00	9/3/02 11:30	4 oz glass	Ice
<u>L</u> (ab Testing: 8015M 8021B/5030 BTEX Chloride	Rejected: 1	No Tei	np: 16.5 C	· 	
0204422-02	4 pt. Bottom Comp. @ 16'	SOIL Rejected: 1	8/30/02 15:00 No Ter	9/3/02 11:30 np: 16.5 C	4 oz glass	Ice
	8015M 8021B/5030 BTEX Chloride					

ANALYTICAL REPORT

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768

Order#:

G0204422

Project:

Project Name: Location:

Rice M-9

Lab ID:

0204422-01

Sample ID:

5 pt. Wall Comp. @ 13'

8015M

Method Blank

Date Prepared

Date Analyzed

Sample Amount Dilution

Factor Analyst

Method 8015M

9/3/02

1

1 CK

Parameter	Result mg/kg	RL
GRO, C6-C12	<10.0	10.0
DRO, >C12-C35	<10.0	10.0
TOTAL, C6-C35	<10.0	10,0

8021B/5030 BTEX

Method Blank 0003053-02

Date Prepared

Date Analyzed 9/5/02 13:19

Sample Amount Dilution Factor 25

Analyst CK

Method 8021B

Result Parameter RLmg/kg 0.025 Benzene <0.025 0.025 Ethylbenzene < 0.025 Toluene <0.025 0.025 0.025 <0.025 p/m-Xylene 0.025 o-Xylene < 0.025

Surrogates	% Recovered	QC Limits (%	
aaa-Toluene	114%	80	120
Bromofluorobenzene	115%	80	120

ANALYTICAL REPORT

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768

Order#:

G0204422

Project:

Project Name: Location:

Rice M-9

Lab ID:

0204422-02

Sample ID:

4 pt. Bottom Comp. @ 16'.

8015M

Method Blank

Date Prepared

Date Analyzed 9/3/02

Sample Amount

1

Dilution

Factor

Analyst CK

Method 8015M

Parameter	Result mg/kg	RL
GRO, C6-C12	<10.0	10.0
DRO, >C12-C35	50.3	10.0
TOTAL, C6-C35	50.3	10.0

8021B/5030 BTEX

Method Blank	Date Prepared	Date <u>Analyzed</u>	Sample <u>Amount</u>	Dilution <u>Factor</u>	Analyst	Method
0003053-02		9/5/02	1	25	CK	8021B
		14:25				

Parameter	Result mg/kg	RL
Велгепе	<0.025	0.025
Ethylbenzene	<0.025	0.025
Toluene	<0.025	0.025
p/m-Xylene	<0.025	0.025
o-Xylene	<0.025	0.025

Surrogates	% Recovered	QC Li	mits (%)
aaa-Toluene	108%	80	120
Bromofluorobenzene	113%	80	120

Raland K. Tuttle, Lab Director, QA Officer

Celey D. Keene, Org. Tech. Director Jeanne McMurrey, Inorg. Tech. Director Sandra Biezugbe, Lab Tech.

Sara Molina, Lab Tech.

Date

ANALYTICAL REPORT

LOGAN ANDERSON RE ENVIRONMENTAL P.O. BOX 13418 ODESSA, TX 79768

Order#:

G0204422

Project:

Project Name: Location: Rice M-9

Lab ID:

0204422-01

Sample ID:

5 pt. Wall Comp. @ 13'

Test Parameters

Parameter Chloride Result 245 Units mg/kg Dilution <u>Factor</u>

<u>RL</u> 20 Method 9253 Date
Analyzed Analyst
9/4/02 SB

Lab ID:

0204422-02

Sample ID:

Chloride

4 pt. Bottom Comp. @ 16'

Test Parameters

Parameter

Result 354 Units mg/kg Dilution
Factor 1

<u>RL</u> 20 Method 2

Analyzed Analyst
9/4/02 SB

Date

Date

Approval:_

Raland K. Tuttle, Lab Director, QA Officer Celey D. Keene, Org. Tech. Director

Celey D. Keene, Org. Tech. Director Jeanne McMurrey, Inorg. Tech. Director Sandra Biezugbe, Lab Tech.

Sara Molina, Lab Tech.

Page 1 of 1

QUALITY CONTROL REPORT

8015M

BLANK SOIL	LAB-ID#	Sample Concentr,	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg	0003048-02	· · · ·		<10.0		
CONTROL SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg	0003048-03		952	1003	105.4%	
CONTROL DUP SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
TOTAL, C6-C35-mg/kg	0003048-04		952	992	104.2%	1.1%
SRM SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pet (%) Recovery	RPD
TOTAL, C6-C35-mg/kg	0003048-05	,	1000	1040	104.%	

QUALITY CONTROL REPORT

8021B/5030 BTEX

BLANK	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0003053-02		1	<0.025	 	
Ethylbenzene-mg/kg		0003053-02			<0.025	 	
Toluene-mg/kg		0003053-02		,	<0.025		
p/m-Xylene-mg/kg		0003053-02			<0.025	 	
o-Xylene-mg/kg	_	0003053-02	,	Ì	<0.025	 	
MS	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0204422-01	0	0.1	0.093	93.%	
Ethylbenzene-mg/kg		0204422-01	0	0.1	0.095	95.%	
Toluene-mg/kg		0204422-01	0	0.1	0.095	95.%	-
p/m-Xylene-mg/kg		0204422-01	0	. 0.2	0.196	98.%	
o-Xylene-mg/kg		0204422-01	0	0.1	0.095	95.%	
MSD	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0204422-01	0	0.1	0.094	94.%	1.1%
Ethylbenzene-mg/kg		0204422-01	0	0.1	0.096	96.%	1.%
Foluene-mg/kg		0204422-01	0	0.1	0.096	96.%	1.%
o/m-Xylene-mg/kg		0204422-01	0	0.2	0.198	99.%	1.%
(ylene-mg/kg		0204422-01	0	0.1	0.096	96.%	1.%
$\mathcal{L}RM$	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Benzene-mg/kg		0003053-05		0.1	0.105	105.%	
Ethylbenzene-mg/kg	· · · · · · · · · · · · · · · · · · ·	0003053-05		0.1	0.105	105.%	
Foluene-mg/kg		0003053-05	· ···	0.1	0,108	108.%	
n/m-Xylene-mg/kg		0003053-05		0.2	0.215	107.5%	
-Xylene-mg/kg		0003053-05		0.1	0.104	104.%	


QUALITY CONTROL REPORT

Test Parameters

BLANK	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg		0003050-01			<20.0		
MS	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg	 -	0204410-15	5320	5000	10300	99.6%	
MSD	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg		0204410-15	5320	5000	10200	97.6%	1.%
SRM	SOIL	LAB-ID#	Sample Concentr.	Spike Concentr.	QC Test Result	Pct (%) Recovery	RPD
Chloride-mg/kg		0003050-04		5000	. 4960	99.2%	

Envi. mental Lab of Texas I, Ltd. CHAIN OF CUSTODY RECORD AND ANALYSIS REQUEST Phone: 915-563-1800 12600 West I-20 East Fax: 915-563-1713 Odessa, Texas 79763 Project Name: Project Manager: Prolect #: Company Name Project Loc: M-9 Company Address: City/State/Zip: Telephone No: Sampler Signature: Analyze For: TOTAL: Matrix Preservative RUSH TAT (Pre-Schedule) BTEX 80218/5030 Standard TAT N.O.R.M. Shudge HCI NaOH H₂SO₄ LAB # (lab use only) FIELD CODE 8-30002 3:00P 3:00 f Special Instructions Semple Containers Intact (1997) Temperature Upon Receipt (1997) Laboratory Comments (1997) Relinquished by: Received by: Time

Relinguished by:



Current Photodocumentation

RICE *Operating Company* (ROC) 112 West Taylor Hobbs, NM 88240 Phone: (575) 393-9174 Fax: (575) 397-1471

EME M-9-4 (1R427-78) UL/M, Section 9, T20S, R37E



Facing north 3/26/2013



Facing west 3/26/2013