

MAR 16 2017

Form C-141
Revised October 10, 2003

District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

RECEIVED
Submit 2 Copies to appropriate
District Office in accordance
with Rule 116 on back
side of form

~~AB1707636774~~ **Release Notification and Corrective Action**

~~AB1707636998~~ OPERATOR Initial Report Final Report

Name of Company	Plains Pipeline, LP 34053	Contact	Camille Bryant
Address	577 US Hwy 385 N, Seminole, Texas 79360	Telephone No.	(575) 441-1099
Facility Name	Alpha Gathering Seg. 3 LAT. 6E	Facility Type	LACT Unit

Surface Owner	BLM	Mineral Owner	BLM	Lease No.	
---------------	-----	---------------	-----	-----------	--

LOCATION OF RELEASE

Unit Letter	Section	Township	Range	Feet from the	North/South Line	Feet from the	East/West Line	County
K	18	26S	27E					Eddy

Latitude N 32.039556° Longitude W 104.232184°

NATURE OF RELEASE



Type of Release	Crude Oil	Volume of Release	20 bbls	Volume Recovered	5 bbls
Source of Release	LACT Unit 4-Inch Braided Hose	Date and Hour of Occurrence	3/11/2017 @ 09:45	Date and Hour of Discovery	03/11/2017 @ 12:20
Was Immediate Notice Given?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Not Required	If YES, To Whom?	NMOCD Artesia Office Voicemail		
By Whom?	Camille Bryant	Date and Hour			
Was a Watercourse Reached?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If YES, Volume Impacting the Watercourse.			

If a Watercourse was Impacted, Describe Fully.*

Describe Cause of Problem and Remedial Action Taken.* A 4-inch braided rubber hose between the LACT and the suction side of the pump failed. The braided rubber hose has been replaced with steel piping.

Describe Area Affected and Cleanup Action Taken. The release impacted approximately 1,600 square feet. The impact was confined to the caliche pad of the facility. The impacted area will be remediated as per applicable NMOCD guidelines.

I hereby certify that the information given above is true and complete to the best of my knowledge and understand that pursuant to NMOCD rules and regulations all operators are required to report and/or file certain release notifications and perform corrective actions for releases which may endanger public health or the environment. The acceptance of a C-141 report by the NMOCD marked as "Final Report" does not relieve the operator of liability should their operations have failed to adequately investigate and remediate contamination that pose a threat to ground water, surface water, human health or the environment. In addition, NMOCD acceptance of a C-141 report does not relieve the operator of responsibility for compliance with any other federal, state, or local laws and/or regulations.

Signature: 	OIL CONSERVATION DIVISION	
Printed Name: Camille Bryant	Signed By:  Approved by District Supervisor:	
Title: Remediation Coordinator	Approval Date: 3/17/17	Expiration Date: N/A
E-mail Address: cjbyrant@paalp.com	Conditions of Approval: See Attached	Attached <input type="checkbox"/>
Date: 3/16/17	Phone: (575) 441-1099	

* Attach Additional Sheets If Necessary

2RD-4147

Operator/Responsible Party,

The OCD has received the form C-141 you provided on 3/16/2017 regarding an unauthorized release. The information contained on that form has been entered into our incident database and remediation case number 2RD-4147 has been assigned. **Please refer to this case number in all future correspondence.**

It is the Division's obligation under both the Oil & Gas Act and Water Quality Act to provide for the protection of public health and the environment. Our regulations (19.15.29.11 NMAC) state the following,

The responsible person shall complete division-approved corrective action for releases that endanger public health or the environment. The responsible person shall address releases in accordance with a remediation plan submitted to and approved by the division or with an abatement plan submitted in accordance with 19.15.30 NMAC. [emphasis added]

Release characterization is the first phase of corrective action unless the release is ongoing or is of limited volume and all impacts can be immediately addressed. Proper and cost-effective remediation typically cannot occur without adequate characterization of the impacts of any release. Furthermore, the Division has the ability to impose reasonable conditions upon the efforts it oversees. **As such, the Division is requiring a workplan for the characterization of impacts associated with this release be submitted to the OCD District 2 office in ARTESIA on or before 4/16/17. If and when the release characterization workplan is approved, there will be an associated deadline for submittal of the resultant investigation report. Modest extensions of time to these deadlines may be granted, but only with acceptable justification.**

The goals of a characterization effort are: 1) determination of the lateral and vertical extents along with the magnitude of soil contamination. 2) determine if groundwater or surface waters have been impacted. 3) If groundwater or surface waters have been impacted, what are the extents and magnitude of that impact. 4) The characterization of any other adverse impacts that may have occurred (examples: impacts on vegetation, impacts on wildlife, air quality, loss of use of property, etc.). To meet these goals as quickly as possible, the following items must, at a minimum, be addressed in the release characterization workplan and subsequent reporting:

- **Horizontal delineation of soil impacts in each of the four cardinal compass directions.** Adsorbed soil contamination must be characterized for the following constituents using the associated laboratory methods: benzene, toluene, ethylbenzene, and total xylenes by either Method 8260 or 8021, total petroleum hydrocarbons by Method 8015 extended range (GRO+DRO+MRO; C₆ thru C₃₆), and for chloride by Method 300. This is not an exclusive list of potential contaminants. Analyzed parameters should be modified based on the nature of the released substance(s). Soil sampling must be both within the impacted area and beyond.

- **Vertical delineation of soil impacts.** Adsorbed soil contamination must be characterized for the following constituents using the associated laboratory methods: benzene, toluene, ethylbenzene, and total xylenes by either Method 8260 or 8021, total petroleum hydrocarbons by Method 8015 extended range (GRO+DRO+MRO; C₆ thru C₃₆), and for chloride by Method 300. As above, this is not an exclusive list of potential contaminants and can be modified. Vertical characterization samples should be taken at depth intervals no greater than five feet apart. Lithologic description of encountered soils must also be provided. At least ten vertical feet of soils with contaminant concentrations at or below these values must be demonstrated as existing above the water table.

- **Nominal detection limits for field and laboratory analyses must be provided.**

- **Composite sampling is not generally allowed.**

- **Field screening and assessment techniques are acceptable (headspace, titration, EC [include algorithm for validation purposes], EM, etc.), but the sampling and assay procedures must be clearly defined.** Copies of field notes are highly desirable. A statistically significant set of split samples must be submitted for confirmatory laboratory analysis, including the laterally farthest and vertically deepest sets of soil samples. Make sure there are at least two soil samples submitted

for laboratory analysis from each borehole or test pit (highest observed contamination and deepest depth investigated). Copies of the actual laboratory results must be provided including chain of custody documentation.

- Probable depth to shallowest protectable groundwater and lateral distance to nearest surface water. If there is an estimate of groundwater depth, the information used to arrive at that estimate must be provided. If there is a reasonable assumption that the depth to protectable water is 50 feet or less, the responsible party should anticipate the need for at least one groundwater monitoring well to be installed in the area of likely maximum contamination.

- If groundwater contamination is encountered, an additional investigation workplan may be required to determine the extents of that contamination. Groundwater and/or surface water samples, if any, must be analyzed by a competent laboratory for volatile organic hydrocarbons (typically Method 8260 full list), total dissolved solids, pH, major anions and cations including chloride and sulfate, dissolved iron, and dissolved manganese. The investigation workplan must provide the groundwater sampling method(s) and sample handling protocols. To the fullest extent possible, aqueous analyses must be undertaken using nominal method detection limits. As with the soil analyses, copies of the actual laboratory results must be provided including chain of custody documentation.

- Accurately scaled and well-drafted site maps must be provided providing the location of borings, test pits, monitoring wells, potentially impacted areas, and significant surface features including roads and site infrastructure that might limit either the release characterization or remedial efforts. Field sketches may be included in subsequent reporting, but should not be considered stand-alone documentation of the site's layout. Digital photographic documentation of the location and fieldwork is recommended, especially if unusual circumstances are encountered.

Nothing herein should be interpreted to preclude emergency response actions or to imply immediate remediation by removal cannot proceed as warranted. Nonetheless, characterization of impacts and confirmation of the effectiveness of remedial efforts must still be provided to the OCD before any release incident will be closed.

Jim Griswold

OCD Environmental Bureau Chief

1220 South St. Francis Drive

Santa Fe, New Mexico 87505

505-476-3465

jim.griswold@state.nm.us

Bratcher, Mike, EMNRD

From: Camille J Bryant <CJBryant@paalp.com>
Sent: Thursday, March 16, 2017 9:14 AM
To: Bratcher, Mike, EMNRD; 'Tucker, Shelly'
Cc: 'rgrubbs@concho.com'
Subject: Plains Pipeline Initial C-141 Alpha Gathering Release
Attachments: 2.jpg; 6.jpg; 11.jpg; Initial C-141 Plains Pipeline Alpha Crude Gathering.pdf

Mike and Shelly,

Please find attached the Initial C-141 and photos of the Plains Pipeline crude oil release which occurred at the COG Screech Owl CTB on March 11, 2017. The site is located in Unit Letter K, Section 18, Township 26 South, Range 27 East of Eddy County New Mexico. The release was attributed to failure of a 4-inch braided hose on the LACT Unit, approximately 20 barrels of crude oil was released with approximately 5 barrels recovered. With NMOCD and BLM approval Plains will excavate the impacted material and stockpile it on plastic pending final disposal. Soil samples will be collected. Upon laboratory confirmation of BTEX and TPH concentrations less than the NMOCD regulatory guidelines Plains will request NMOCD and BLM approval to backfill the excavated area with import material and transport the stockpiled material off-site to an NMOCD permitted disposal facility.

Please contact me with any questions or concerns.

Respectfully,

Camille J. Bryant
Remediation Coordinator
Plains All American
577 US Highway 385 North
Seminole, Texas 79360
Office: 432.758.8139
Cell: 575.441.1099

Attention:

The information contained in this message and/or attachments is intended only for the person or entity to which it is addressed and may contain confidential and/or privileged material. If you received this in error, please contact the Plains Service Desk at 713-646-4444 and delete the material from any system and destroy any copies.

This footnote also confirms that this email message has been scanned for Viruses and Content and cleared.