

AE Order Number Banner

Report Description

This report shows an AE Order Number in Barcode format for purposes of scanning. The Barcode format is Code 39.

App Number: pCS1828842329

3RF - 29

ENDURING RESOURCES, LLC

10/19/2018

3RF-29 Recycling Facility and/or Recycling Containment
Type of Facility: X Recycling Facility X Recycling Containment* Type of action: X Permit X Registration Modification Extension Closure Other (explain)
* At the time C-147 is submitted to the division for a Recycling Containment, a copy shall be provided to the surface owner.
Be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environmentation of the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.
1. Operator: Enduring Resources IV, LLC (For multiple operators attach page with information) OGRID #: 372286 Address: 200 Energy Court, Farmington, NM 87401
Address: 200 Energy Court, Farmington, NM 87401 Facility or well name (include API# if associated with a well): WLU 2309-24N
OCD Permit Number:
U/L or Qtr/Qtr <u>SE/4 SW/4 & SW/4</u> Section <u>24</u> Township <u>23N</u> Range <u>9W</u> County: <u>San Juan</u>
Surface Owner: X Federal State Private Tribal Trust or Indian Allotment
2. X Recycling Facility:
Location of recycling facility (if applicable): Latitude Longitude Longitude NAD83
Proposed Use: X Drilling* X Completion* X Production* X Plugging *
*The re-use of produced water may NOT be used until fresh water zones are cased and cemented
Other, requires permit for other uses. Describe use, process, testing, volume of produced water and ensure there will be no adverse impact on
groundwater or surface water.
∑ Fluid Storage ∑ Above ground tanks ∑ Recycling containment ☐ Activity permitted under 19.15.17 NMAC explain type
Activity permitted under 19.15.36 NMAC explain type:
For multiple or additional recycling containments, attach design and location information of each containment
Closure Report (required within 60 days of closure completion): Recycling Facility Closure Completion Date:
Closure Report (required within ob days of closure completion): T Recycling Fachity closure Completion Date
3.
X Recycling Containment:
Annual Extension after initial 5 years (attach summary of monthly leak detection inspections for previous year)
Center of Recycling Containment (if applicable): Latitude <u>36.205958</u> Longitude <u>-107.740891</u> NAD83
For multiple or additional recycling containments, attach design and location information of each containment
X Lined Liner type: Thickness 45 mil LLDPE HDPE PVC Other
\boxtimes String-Reinforced Liner Seams: \boxtimes Welded \boxtimes Factory \square Other Volume: $\frac{265,385}{265,385}$ bbl. Dimensions: L. $\frac{350'}{265}$ x W. $\frac{400'}{200'}$ x D. $\frac{25'}{25}$
Liner Seams: X Welded X Factory Other Volume: 265,385 bbl Dimensions: L 350' x W 400' x D 25'



Smith, Cory, EMNRD

From:Smith, Cory, EMNRDSent:Friday, October 19, 2018 10:48 AMTo:'Andrea Felix'Cc:Fields, Vanessa, EMNRDSubject:RE: WLU 2309-24N Assigned 3RF-29

Good Morning Andrea,

OCD has received the C-147 for the Recycling containment at the Enduring WLU 2309-24N on October 17, 2018. Upon further review the application has been approved with the following conditions of approval.

- Enduring will notify the OCD District III at least 48 hours but no more than 1 week prior to the start of construction of the pond.
- Enduring will notify the OCD District III at least 48 hours but no more than 1 week at the completion of the leak detection prior to being covered by any sand/liner.

Enduring may find the approved permit application (once scanned) by searching for 3RF-29 in OCD Online. Please remember Enduring will need the Admin # to report on Form C-148 monthly for all Recycling facilities.

If you have any additional questions please give me a call.

Thank you,

Cory Smith Environmental Specialist Oil Conservation Division Energy, Minerals, & Natural Resources 1000 Rio Brazos, Aztec, NM 87410 (505)334-6178 ext 115 cory.smith@state.nm.us

From: Smith, Cory, EMNRD
Sent: Monday, October 15, 2018 11:33 AM
To: 'Andrea Felix' <AFelix@enduringresources.com>
Cc: Fields, Vanessa, EMNRD <Vanessa.Fields@state.nm.us>
Subject: WLU 2309-24N Assigned 3RF-29

Good morning Andrea,

OCD has received the C-147 for the Recycling containment at the Enduring WLU 2309-24N on October 4, 2018. Upon further review the application is incomplete and has been denied for the following

- The design plan needs to state how the pond is designed to prevent surface water run on.
- The design plan needs to state how the pond inside Levey grade is no steeper than 2H:1V grade
- The design plan needs to state how the ponds outside Levey grade is no steeper than 3H:1V grade.

- The design plan needs to state/describe how the liner is protected from fluid force or mechanical damage
- The primary Liner must be resistant to UV light, petroleum hydrocarbons, salt and acidic/alkaline solutions.
- In the closure plan, the operator shall notify the OCD when reclamation and revegetation are completed.

Please correct the above issues and resubmit a complete and correct registration. Since this application has no API# for record keeping I have assigned it to 3RF-29 the denied application will be scanned into the online file as soon as possible.

If you have any questions please give me a call.

Thanks,

Cory Smith Environmental Specialist Oil Conservation Division Energy, Minerals, & Natural Resources 1000 Rio Brazos, Aztec, NM 87410 (505)334-6178 ext 115 cory.smith@state.nm.us

Bonding:

Covered under bonding pursuant to 19.15.8 NMAC per 19.15.34.15(A)(2) NMAC (These containments are limited to only the wells owned or

operated by the owners of the containment.)

Bonding in accordance with 19.15.34.15(A)(1). Amount of bond \$______ (work on these facilities cannot commence until bonding

amounts are approved)

Attach closure cost estimate and documentation on how the closure cost was calculated.

Fencing:

5.

Four foot height, four strands of barbed wire evenly spaced between one and four feet

X Alternate. Please specify See attached variance request

Signs:

6.

7.

12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers

X Signed in compliance with 19.15.16.8 NMAC

Variances:

Justifications and/or demonstrations that the proposed variance will afford reasonable protection against contamination of fresh water, human health, and the environment.

Check the below box only if a variance is requested:

X Variance(s): Requests must be submitted to the appropriate division district for consideration of approval. If a Variance is requested, include the variance information on a separate page and attach it to the C-147 as part of the application.

If a Variance is requested, it must be approved prior to implementation.

Siting Criteria for Recycling Containment

Instructions: The applicant must provide attachments that demonstrate compliance for each siting criteria below as part of the application. Potential examples of the siting attachment source material are provided below under each criteria.

General siting

Ground water is less than 50 feet below the bottom of the Recycling Containment. NM Office of the State Engineer - iWATERS database search; USGS; Data obtained from nearby wells	☐ Yes X No ☐ NA
 Within incorporated municipal boundaries or within a defined municipal fresh water well field covered under a municipal ordinance adopted pursuant to NMSA 1978, Section 3-27-3, as amended. Written confirmation or verification from the municipality; written approval obtained from the municipality 	☐ Yes X No ☐ NA
 Within the area overlying a subsurface mine. Written confirmation or verification or map from the NM EMNRD-Mining and Minerals Division 	Yes X No
 Within an unstable area. Engineering measures incorporated into the design; NM Bureau of Geology & Mineral Resources; USGS; NM Geological Society; topographic map 	🗌 Yes 🛛 No
Within a 100-year floodplain. FEMA map	Yes X No
 Within 300 feet of a continuously flowing watercourse, or 200 feet of any other significant watercourse, or lakebed, sinkhole, or playa lake (measured from the ordinary high-water mark). Topographic map; visual inspection (certification) of the proposed site 	🗌 Yes 🕅 No
 Within 1000 feet from a permanent residence, school, hospital, institution, or church in existence at the time of initial application. Visual inspection (certification) of the proposed site; aerial photo; satellite image 	Yes X No
 Within 500 horizontal feet of a spring or a fresh water well used for domestic or stock watering purposes, in existence at the time of initial application. NM Office of the State Engineer - iWATERS database search; visual inspection (certification) of the proposed site 	🗌 Yes 🗶 No
 Within 500 feet of a wetland. US Fish and Wildlife Wetland Identification map; topographic map; visual inspection (certification) of the proposed site 	🗌 Yes 🕅 No

Recycling Facility and/or Containment Checklist:

Instructions: Each of the following items must be attached to the application. Indicate, by a check mark in the box, that the documents are attached.

 \boxed{X} Design Plan - based upon the appropriate requirements.

- X Operating and Maintenance Plan based upon the appropriate requirements.
- X Closure Plan based upon the appropriate requirements.
- X Site Specific Groundwater Data -
- Siting Criteria Compliance Demonstrations –
 Certify that notice of the C-147 (only) has been sent to the surface owner(s)

Operator Application Certification:

10.

I hereby certify that the information and attachments submitted with this application are true, accurate and complete to the best of my knowledge and belief.

Name (Print): / Andrea Felix	Title: Regulatory Manager
Signature:	Date: 10-16-2018
e-mail address: afelix@enduringresources.com	Telephone:
A	
OCD Representative Signature:	Approval Date:
Title: Environmental Spec	OCD Permit Number: <u>3RF-29</u>
OCD Conditions	Emil Sent 10/19/18

C-147 Registration Package

Prepared for



Enduring Resources IV, LLC 200 Energy Court Farmington, NM 87401 (505) 386-8205

Developed by



Energy Inspection Services 479 Wolverine Drive Bayfield, Colorado 81122 Phone: (970) 881-4080

TABLE OF CONTENTS

1. Introduction1
2. Variance Explanation
3. Siting Criteria1
3.1. Distance to Groundwater1
3.2. Distance to Surface Water2
3.3. Distance to Structures
3.4. Distance to Non-Public Water Supply2
3.5. Distance to Municipal Boundaries and Defined Fresh Water Fields2
3.6. Distance to Subsurface Mines2
3.7 Distance to 100-Year Floodplain2
4. Design and Construction Plan2
4.1. Foundation Construction
4.2. Liner Construction
4.3. Leak Detection System4
4.4. Signage 5
4.5. Entrance Protection5
4.6. Wildlife Protection
5. Maintenance and Operating Plan5
5.1. Inspection Timing5
5.2. Maintenance
5.3. Cessation of Operations
6. Closure Plan6
6.1 Fluid Removal6
6.2 Soil Sampling6
6.3 Reclamation
7. iWaters Report
8. Aerial Map9
9. Торо Мар10
10. Mines Mills Map11
11. FEMA Map12
12. Hydrology Report
13. Surface Owner Notification15
Attachment A - Migratory Bird Plan16
Attachment B - Containment Construction Plans

Attachment C	- GeoMat Report	21
--------------	-----------------	----

1. INTRODUCTION

Applicant	Enduring Resources IV, LLC
Project Name	WLU 2309-24N
Project Type	Recycling Containment Registration
Legal Location	SE/4 SW/4 & SW/4, Section 24, T23N, R9W
Lease Number(s)	NMNM-135216-A

In accordance with NMAC 19.15.34, Enduring Resources IV, LLC (Enduring) requests the registration of the proposed Recycling Containment through the approval of this C-147 registration package. The facility and containments will be used to treat and recycle produced water for re-use in Enduring Resources IV, LLC completion activities.

This package contains the C-147 form and associated documents for registration of the WLU 2309-24N Recycling Containment.

A copy of the C-147 has been submitted to the land owner, the Bureau of Land Management.

2. VARIANCE EXPLANATION

All requested variance provide equal or better protection of fresh water, public health, and the environment.

C-147 #5 Fencing

19.15.34.12.D(1) NMAC states "Recycling containments shall be fenced with a four foot fence that has at least four strands of barbed wire evenly spaced in the interval between one foot and four feet above ground level."

Enduring will install an eight (8) foot chain link fence with one strand of barbed wire around the facility as requested by the surface owners to allow for greater protection to the facility than the requirements of 19.15.34.12.D(1)

3. SITING CRITERIA

3.1. Distance to Groundwater

The NM State Engineers Office iWaters Database shows a water well within section 25 of township 23N and range 9W. The elevation of the iWaters Data Point SJ01710 is approximately 6827' with a groundwater depth of 173'. The WLU 2309-24N has an elevation of 6870' which is an increase of 43' establishing the estimated groundwater depth for the WLU 2309-24N to be greater than 200'. Therefore, the groundwater depth is greater than 50 feet below the bottom of the recycling containment.

3.2. Distance to Surface Water

There are not any continuously flowing watercourses within 300' nor any other significant watercourse and lakebed or playa lake within 200' of the recycling containment as shown on the Aerial or Topo maps provided.

3.3. Distance to Structures

There are no permanent residence, school, hospital, institution or church at the time of initial registration within 1000' of the recycling containment as shown on the Aerial and Topo maps provided.

3.4. Distance to Non-Public Water Supply

There are no springs or fresh water wells used for domestic or stock water purposes within 500' in existence at the time of initial registration as shown on the Aerial and Topo maps provided.

3.5. Distance to Municipal Boundaries and Defined Fresh Water Fields

The recycling facility is not within any incorporated municipal boundaries within a defined municipal fresh water well field covered by a municipal ordinance adopted pursuant to Section 3-27-3 NMSA 1978, as amended.

3.6. Distance to Subsurface Mines

The recycling containment is not located in an "unstable" area. The location is not over a mine and is not on the side of a hill. The location of the excavated surface material will not be located within 100 feet of a continuously flowing or significant watercourse. According to the NM EMNRD Mining and Mineral Divisions database there are no subsurface mines in Section 24, Township 23N, Range 9W of San Juan County.

3.7 Distance to 100-Year Floodplain

The WLU 2309-24N proposed recycling containment is not located within a 100-year floodplain as demonstrated on the FEMA Map.

4. DESIGN AND CONSTRUCTION PLAN

In accordance with Rule 19.15.34 the following information describes the design and construction of the recycling containment on Enduring's locations.

The Enduring Design and Construction Plan assists Enduring personnel in ensuring compliance with the minimum design and construction requirements for recycling containments as defined by the NMOCD outlined in 19.15.34.12 NMAC. The plan applies to any Enduring Employee(s) and subcontractor(s) whose job requires them to assist with the design and construction of the recycling facility. The plan is designed to ensure compliance with the minimum design and construction requirements for recycling facilities as defined by the NMOCD outlined in 19.15.34.12 NMAC.

Enduring shall design and construct a recycling containment in accordance with the following specifications.

4.1. Foundation Construction

Approximately 6" of topsoil will be stripped and stockpiled for final cover at the time of closure. The topsoil will be stored on the perimeter of the permitted facility.

The recycling containment will have a properly constructed foundation and interior slopes consisting of a firm, unyielding base, smooth and free of rocks, debris, sharp edges or irregularities to prevent the liner's rupture or tear. The containment will ensure confinement of produced water, to prevent releases and to prevent overtopping due to wave action or rainfall. A geotextile under the liner will be used, if needed, to reduce the localized stress-strain or protuberances that otherwise may compromise the liner's integrity. The final sub grade shall be scarified to a minimum depth of 12 inches, moisture conditioned to near Optimum Moisture and compacted to 95% of maximum dry density as determined by a Standard Proctor (ASTM 698).

Positive draining should be provided during construction and maintained throughout the life of the proposed project to prevent surface runoff from entering the pond. Protective slopes should be provided with a minimum grade of approximately 5 percent for at least 10 feet from the structures. Backfill against footings, exterior walls, and in utility trenches should be well compacted and free of all construction debris to reduce the possibility of moisture infiltration.

The pond inside Levey grade will be constructed no steeper than 2H:1V grade and the pond outside Levey grade will be constructed no steeper than 3H:1V grade.

4.2. Liner Construction

Enduring's recycling containment shall incorporate, a primary (upper) liner and a secondary (lower) liner with a leak detection system. The primary (upper) liner will be a 45-mil LLDPE string reinforced liner resistant to UV light, petroleum hydrocarbons, salt and acidic/alkaline solutions with a single sided texture to increase traction for emergency escape from the pit and shall cover the bottom and sides of the pit including the minimum three (3) feet of freeboard per NMOCD 19.15.17.11.G.9. Integrity of the primary liner shall be tested using the Dipole Method - Water Covered Geomembrane (ASTM D7007). The secondary liner will be a 45-mil LLDPE string reinforced liner with a single sided conductive coating for initial leak detection and shall cover the bottom and sides of the pit including the minimum three (3) feet of freeboard per NMOCD 19.15.17.11.G.9. Integrity of the secondary liner shall be tested using the Conductive-Backed Geomembrane Spark Testing Method (ASTM D7240).

A secondary leak detection system will be installed at the designated corner of each pit. The pit bottom will be sloped to the detection system that will be comprised of SDR-17 HDPE solid and perforated pipe with 1-1/2" Type F coarse drain rock bedding. Enduring will install manufacturer recommended Geoconduct 250 geocomposite with a conductive grid between non-woven needle-punched geotextiles produced by Afitex Texel. The product consists of two geotextile layers comprised of short synthetic fibers of 100% polypropylene or polyester which are needle punched together with a structural conductive grid. The conductive grid comprises two conductive inox

cables forming a 50 mm x 50 mm network. Geoconduct is compatible with geoelectrical leak location surveys.

Enduring shall ensure the subcontractor installing the recycling containment minimized liner seams and orient them up and down, not across, a slope of the levee. Enduring shall ensure that factory welded seams shall be used where possible. Enduring shall ensure the subcontractor installing the recycling containment ensures field seams in the geosynthetic material are thermally seamed and that prior to any field seaming, the installer overlaps the liners four to six inches. The subcontractor installing the liner shall minimize the number of field seams and corners and irregularly shaped areas. Enduring will only hire qualified personnel to perform field welding and testing.


Enduring shall install manufacturer recommended DrainTube gas ventilation geocomposite grid produced by Afitex Texel. This layer is intended to vent in situ gases that have potential to create "whale" in the produced water pit that would decrease storage capacity. The product consists of a drainage layer and a filter layer comprised of short synthetic staple fibers of 100% polypropylene needle-punched together with perforated corrugated polypropylene pipes regularly spaced, up to 4 pipes per meter, inside. The pipes have two perforations per corrugation at 180 degrees and alternating at 90 degrees. <u>https://www.draintube.net/docs/en/download/technical_data_sheet/draintube_300p_st_series_fos.pdf</u>

The liner system shall be anchored as designed in a 2 FT x 2.5 FT anchor trench and topped with 6 inches of road base.

At the point of discharge into or suction from the recycling containment, Enduring will insure that the liner is protected from excessive hydrostatic force and potential mechanical damage. External discharge and/or suction lines will not penetrate the liner.

4.3. Leak Detection System

Enduring shall place a leak detection system between the upper and lower geomembrane liners that shall consist of a 200-mil genet to facilitate drainage. The leak detection system shall consist of a properly designed drainage and collection and removal system placed above the lower geomembrane liner in depressions and sloped to facilitate the earliest possible leak detection. A 3 foot wide by 3 foot long by 2 foot deep depression will be contracted to allow for collection of any leaking liquid. A 4 inch PVC liner will be installed in between the primary and secondary liners from the top of the tank to the depression to allow for detection and removal of liquid.



4.4. Signage

Enduring will sign the containment with an upright sign no less than 12" by 24" with lettering not less than 2" in height in a conspicuous place near the containment. Enduring will provide the operator's name, location of the containment by quarter-quarter or unit letter, Section, Township, Range and emergency telephone numbers.

4.5. Entrance Protection

Enduring will surround the containment with an eight foot chain link fence. All gates leading in and out of the containment will be closed and locked when personnel are not on-site. The fencing will be kept in good repair, and shall be inspected as part of the weekly inspection performed at the containment facility.

4.6. Wildlife Protection

Enduring will install a bird deterrent system pursuant to the attached *Migratory Bird Mitigation Plan*. The containment will be inspected weekly for dead migratory birds and will be reported accordingly.

5. MAINTENANCE AND OPERATING PLAN

In accordance with Rule 19.15.34 the following information describes the operation and maintenance of recycling containments on Enduring's locations.

5.1. Inspection Timing

Enduring shall inspect the recycling containment and associated leak detection systems weekly while it contains fluids. A current log of inspections will be maintained and the log will be made available for review upon division request. If fluids are found in the sump, a primary liner test utilizing the Dipole Method - Water Covered Geomembrane (ASTM D7007) will be conducted. In addition to human monitoring the pond fluid level will be determined via two (2) hydrostatic pressure gauges and a float gauge. At a fluid height of 22', an automated valve will close and prevent any more fluid from entering the containment.

5.2. Maintenance

- 1. Enduring shall maintain and operate the recycling containment as follows:
 - A. Removing any visible lay of oil from the surface of the containment.
 - B. Maintaining at least 3' of freeboard at each containment
 - C. The injection or withdrawal of fluids from the containment shall be accomplished through a header, diverter or other hardware that prevents damage to the liner by erosion, fluid jets, or impact from installation and removal of hoses and pipes
 - D. If the containment's primary liner is compromised above the fluid's surface, Enduring will repair the damage or initiate replacement of the primary liner within 48 hours of discovery or seek an extension from the division district office.

- E. If the primary liner is compromised below the fluid's surface, Enduring will remove all fluid above the damage or leak within 48 hours of discovery, notify the divisions distraction office and repair the damage or replace the primary liner.
- F. The containment will be operated to prevent the collection of surface water run-on with containment walls of 9.5' height.
- G. Enduring will install, or maintain on site, an oil absorbent boom or other device to contain an unanticipated release.
- H. Enduring will not store or discharge any hazardous waste at the facility or within the containment.

5.3. Cessation of Operations

Enduring will report the cessation of operations or if less than 20% of the total fluid capacity is used every six months following the first withdrawal of produced water for use to the appropriate division district office. If additional time is needed for closure, Enduring will request an extension from the appropriate division district office prior to the expiration of the initial six month time period.

6. Closure Plan

In accordance with Rule 19.15.34 the following information describes the closure requirements of recycling containments on Enduring's locations.

All closure activities will include proper documentation and be available for review upon request and will be submitted to the OCD within 60 days of closure. Closure report will be filed on C-147 and incorporate the following:

- Details on capping and covering, where applicable
- Inspection Reports
- Sampling Results

Once Enduring has ceased operations, all fluids will be removed within 60 days and the containment shall be closed within six months.

6.1 Fluid Removal

The containment will be closed by first removing all fluids, contents and synthetic liners and disposed of in a division-approved facility or recycle, reuse or reclaim the liquids in a manner that the appropriate division district office approves.

6.2 Soil Sampling

Enduring will test the soils beneath the containment for contamination with a five-point composite sample which includes stained or wet soils, if any, and that sample shall be analyzed for the constituents listed in Table I below:

Components	Test Method	51' - 100' GW Depth Limit (mg/kg)	>100' GW Depth Limit (mg/kg)
Chloride	EPA 300.0	10,000	20,000
TPH (GRO+DRO+MRO)	EPA SW-846 Method 8015M	2,500	2,500
GRO + DRO	EPA SW-846 Method 8015M	1,000	1,000
BTEX	EPA SW-846 Method 8021B or 8260B	50	50
Benzene	EPA SW-846 Method 8021B or 8260B	10	10

- a. If any containment concentration is higher than the parameters listed in Table I, Enduring will receive approval before proceeding with closures as the division may required additional delineation upon review of the results.
- b. If all contaminant concentrations are less than or equal to the parameters listed in Table I then Enduring will proceed to backfill with non-waste containing, uncontaminated, earthen material.

6.3 Reclamation

The topsoil and subsoil will be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Enduring will reclaim and reseed the recycling containment area pursuant to the requirements listed in 19.15.34.14. Once Enduring has closed the recycling containment, we will reclaim the containment's location to a safe and stable condition that blends with the surrounding undisturbed area and matches the existing grade. Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to prevent ponding and erosion. The disturbed area shall then be reseeded in the first favorable growing season following closure of a recycling containment. Enduring will restore the impacted surface area to the condition that existed prior to the construction of the recycling containment.


Reclamation of all disturbed areas no longer in use shall be considered completed when all ground surface disturbing activities at the site have been completed, and a uniform vegetative cover has been established that reflects a life-form ratio of plug or minus fifty percent (50%) of predisturbance levels and a total percent plant cover of at least seventy percent (70%) of predisturbance levels, excluding noxious weeds.

The re-vegetation and reclamation obligations imposed by federal, state trust land or tribal agencies on lands managed by those agencies shall supersede these provisions and govern the obligations of any operator subject to those provisions, provided that the other requirements provide equal or better protection of fresh water, human health and the environment. Enduring will notify the OCD district office when reclamation and revegetation have been completed.


7. IWATERS REPORT


(A CLW##### in the POD suffix indicates the POD has been replaced & no longer serves a water right file.)	(R=POD replaced, O=orpha C=the file closed)	ned,	~ 1					E 3=SW argest)		83 UTM	in met	ers)		(In t	feet)	
		POD		0												
POD Number SJ 01710	Code	Sub- basin SJ	County SJ			Sec	Tws 23N	0	X 252985	40092	Y 203* (De	pthWell 550		W Water Col 173	umi 37
										Average	e Depti	h to W	ater:		173 feet	
											Mini	mum D	epth:		173 feet	
											Maxir	num D	epth:		173 feet	
Record Count: 1																
PLSS Search:																
Section(s): 13, 1 23, 2 27	4, 15, 22, 4, 25, 26,	Townsh	<mark>ip:</mark> 23N	R	ange	e: 091	N									
*UTM location was derived	from PLSS	• see Helr	r.													

8. AERIAL MAP




9. Торо Мар





11. FEMA MAP



12. HYDROLOGY REPORT

Hydrogeological Report for WLU 2309-24N Water Recycle Facility

Regional Geological context:

The Nacimiento Formation is of Paleocene age (Baltz, 1967, p. 35). It crops out in a broad band inside the southern and western margins of the central basin and in a narrow band along the west face of the Nacimiento Uplift. The Nacimiento is a nonresistant unit and typically erodes to low, rounded hills or forms badland topography.

The Nacimiento Formation occurs in approximately only the southern two-thirds of the San Juan Basin where it conformably overlies and intertongues with the Ojo Alamo Sandstone (Fassett, 1974, p. 229). The Nacimiento Formation grades laterally into the main part of the Animas Formation (Fassett and Hinds, 1971, p. 34); thus, in this area, the two formations occupy the same stratigraphic interval.

Strata of the Nacimiento Formation were deposited in lakebeds in the central basin area with lesser deposition in stream channels (Brimhall, 1973, p. 201). In general, the Nacimiento consists of drab, interbedded black and gray shale with discontinuous, white, medium- to very coarse grained arkosic sandstone (Stone e al., 1983, p.30). Stone et al. indicated that the formation may contain more sandstone than commonly reported because some investigators assume the slope-forming strata in the unit area shales, whereas in many places the strata actually are poorly consolidated sandstones. Total thickness of the Nacimiento Formation ranges from about 500 to 1,300 feet. The unit generally thickens from the basin margins toward the basin center (Steven et al., 1974). The sandstone deposits within the Nacimiento Formation are much thinner than the total thickness of the formation because their environment of deposition was localized stream channels (Brimhall, 1973, p. 201). The thickness of the combined San Jose, Animas, and Nacimiento Formations ranges from 500 to more than 3.500 feet.

Hydraulic Properties:

Reported well yields for 53 wells completed in either the Animas or Nacimiento Formations range from 2 to 90 gallons per minute and the median yield is 7.5 gallons per minute. The primary use of water from Nacimiento and Animas Formations is domestic and livestock supplies. There are no known aquifer tests for the Animas or Nacimiento Formations, but specific capacities reported for six wells range from 0.24 to 2.30 gallons per minute per foot of drawdown (Levings et al., 1990).

The Animas and Nacimiento Formations are in many ways hydrologically similar to the San Jose Formation because sands in both units produce approximately the same quantities of water. However, the greater percentage of fine materials in the Animas and Nacimiento Formations may restrict downward vertical leakage to the Ojo Alamo Sandstone or Kirtland Shale. The poorly cemented fine material is highly erodible, forms a badland terrain, and supports only spotty vegetation. These conditions are more conductive to runoff than retention of precipitation.

References:

Baltz, E.H., 1967, Stratigraphy and regional tectonic implications of part of Upper Cretaceous rocks, east-central San Juan Basin, New Mexico: USGS Professional Paper 552, 101 p.

Brimhall, R.M., 1973, Ground-water hydrology of Tertiary rocks of the San Juan Basin, New Mexico, in Fassett, J.E., ed., Cretaceous and Tertiary rocks of the Southern Colorado Plateau: Four Corners Geological Society Memoir, p. 197-207.

Fassett, J.E., 1974, Cretaceous and Tertiary rocks of the eastern San Juan Basin, New Mexico and Colorado, in Guidebook of Ghost Ranch, central-northern New Mexico: New Mexico Geological Society, ₂₅th Field Conference, p. 225-230.

Fassett, J.E., and Hinds, J.S., 1971, Geology and fuel resources of the Fruitland Formation and Kirtland Shale of the San Juan Basin, New Mexico and Colorado: USGS Professional Paper 676, 76 p.

Levings, G.W., Craigg, S.d., Dam, W.L., Kernodle, J.M., and Thorn, C.R., 1990, Hydrogeology of the San Jose, Nacimiento, and Animas Formations in the San Juan structural basin, New Mexico, Colorado, Arizona, and Utah: USGS Hydrologic Investigations Atlas HA-720-A, 2 sheets.

Stone, W.J., Lyford, F.P., Frenzel, P.F., Mizell, N.H., and Padgett, E.T., 1983, Hydrogeology and water resources of San Juan Basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources, Hydrologic Report 6.

13. SURFACE OWNER NOTIFICATION

			RECEIVED
	DEPARTME BUREAU OF SUNDRY NOTICES not use this form for	ITED STATES NT OF THE INTERIOR LAND MANAGEMENT S AND REPORTS ON W proposals to drill or to m 3160-3 (APD) for suc	re-enter an
	SUBMIT IN TRIPLICA	TE - Other instructions on page	7. If Unit of CA/Agreement, Name and/or No. NMNM 135216A
Type of Well Oil Name of Operator		Other	8. Well Name and No. W Lybrook Unit 9. API Well No.
nduring Resources, 1. Address 32 Cr 3100 Az	LLC tec, NM 87410	3b Phone No (505-636-9741	clude area code) 10. Field and Pool or Exploratory Area Lybrook Mancos W
Location of Well (1	Cootage. Sec. T. R. M. or Sur	vey Description)	11. Country or Parish, State San Juan, NM

TYPE OF SUBMISSION		TYPE OF ACTION						
Notice of Intent	Acidize	Deepen	Production (Start/Resume)	Water ShutOff				
Minotice of intent	Alter Casing	Hydraulic Fracturing	Reclamation	Well Integrity				
Subsequent Report	Casing Repair	New Construction	Recomplete	Other W				
Final Abandonment Notice	Change Plans	Plug and Abandon	Temporarily Abandon	LYBROOK				
Trinan Abandonineni Nonce	Convert to Injection	Plug Back	Water Disposal	STAGING				
				AREA				

13 Describe Proposed or Completed Operation Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally appr unburface locations and measured and true vertical depths of all perinent markers and zones. Attach the Bond ander which the work will be performed or provide the Bond No on file with BLMBIA. Required subsequent reports must be filed within 10 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

W LYBROOK UNIT-

Enduring Resources IV, LLC is changing the well completion operation from a nitrogen to a slick water completion operation. This change in completion operations will allow for the use and reuse of nonpotable water and will significantly reduce the amount of flaring needed to clean a well up to pipeline quality.

Enduring would like to utilize the approved West Lybrook Unit staging area as a Water Recycling Facility in order to achieve the goal of a slick water completion operation.

The facility will consist of a water supply well sourcing nonpotable water from the Entrada formation for oil and gas completion and recycling purposes which will be permitted with the Office of the State Engineer. This facility will supply water for Enduring Resources IV, LLC operations only and within the approved West Lybrook, Rodeo and Kimbeto units. Surface water lines will be utilized within the already approved pipeline ROW corridors to transfer the water to each location for completion activities. No new surface approvals are necessary for this request, Enduring will follow all existing stipulations and COA'so **OPERATOR FROM OBTAINING ANY OTHER** A C102 of the approved West Lybrook staging area is attached.

14 Thereby certify that the foregoing is true and correct Name (Printed Typed)	AUTHORIZATION REQUIRED FOR OPERATIONS
Andrea Felix	ON FEDERAL AND INDIAN LANDS Title Regulatory Manager
Signature	Date 7/2/18
THE SPACE FOR FEL	DERAL OR STATE OFICE USE
Approved by Conditions of approval of are, are attached. Approval of this notice does not warra certify that the applicant holds legal or contrable title to those rights in the subject which would curitle the applicant to conduct operations thereon	
Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for ai any false, fictitious or fraudulent statements or representations as to any matter wit	ny person knowingly and willfully to make to any department or agency of the United S thin its jurisdiction

OPERATOR

Enduring Resources, LLC's Recycling Containment Migratory Bird Mitigation Plan

Enduring Resources, LLC (Enduring) is proposing this Migratory Bird Mitigation Plan (Mitigation Plan) in compliance with the New Mexico Oil Conservation Division (NMOCD) Rule 19.15.34.12.E Enduring shall ensure that the recycling containment is protective of wildlife by implementing the following proposed Mitigation Plan. Enduring employees will inspect the containment weekly for and, within 30 days of discovery, report the discovery of dead migratory birds or other wildlife to the appropriate wildlife agency and to the division district office in order to facilitate assessment and implementation of measures to prevent incidents from reoccurring. This Mitigation Plan will utilize a combination of visual and audio deterrents to discourage wildlife, particularly birds and bats, from the recycling containment in order to mitigate potential impacts. This Mitigation Plan would be implemented while the Recycling Containment is active and in use, as to not desensitize birds to the deterrents.

The following mitigations will be implemented to reduce any wildlife impacts that may occur from the Recycling Containment:

- The following visual bird deterrents will be installed (Appendix A):
 - Bird-X Prowler Owl decoys will be installed at all four corners of the Containment.
 - Scare-Eye Balloons will be installed along the perimeter of the Containment.
- A Bird-X BroadBand PRO System will be installed at the Containment facility. It utilizes sonic (naturally-recorded bird destress calls & predator cries) to deter birds; as well as, ultrasonic high-frequency sound waves to deter bats. Bird propane cannons were avoided, so as not to disturb other wildlife species.
- The containment will be inspected on a monthly basis when water is present in the containment. All inspectors will insure the containment is receiving only filtered produced water with no hydrocarbons, as well as being trained to inspect the premises for, and respond to any wildlife incident, should it occur.
- Inspection will include:
 - An inspection of the filtration system and all visual and audio deterrents to insure they are in working order and functioning properly.
 - A thorough search of the entire containment facility, and just beyond, for the presence of any wildlife (entrapped, injured, dead, etc.).
- In the event a wildlife incident should occur, James McDaniel with Enduring will be contacted immediately and he will notify the appropriate wildlife agency and division district office. Enduring, appropriate wildlife agency, and division district office will then work collaboratively to address the incident appropriately to insure the incident does not reoccur.

SIRD-X		Search	2
t control for today's ensur	annest 3 5 5 5	Call Us 888.683.18	34 Home About News Blog International GS4 RetainProducts Contact
Bird Products	Animal/Rodent Products	Insect Products	Interactive Problem Solver Knowledge Center FREE Evaluation
ill Bird-X Products			BroadBand PRO
ectronic Bird Control	>		
Sonic Bird Control			Combines SONIC and ULTRASONIC Bird Control Technology
Ultrasonic Bird Contro			Creates Uninviting Environment For Birds
Other Electronic Bird Deterrents		5	Covers Up To SIX ACRES
Solar Panel Products			IN STOCK - AVAILABLE IMMEDIATELY!
and Spikes	1 A A	1 1 1 1 1	Deter Birds With Multi-Faceted Sonic and Ultrasonic Attack! The
Bird Spikes Kits		10000	BroadBand PRO's 4-speaker system simultaneously emits sounds that are
Stainless Steel Spikes			both audible and inaudible to humans that confuse disorient and intimidate
Plastic Spikes			pest birds, keeping them away
- and shorts			Starting at \$850.00 NOW \$725.00 (15% SAVINGS!)
ird Netting	0.770		Voltage Options BroadBand PRO 110v (\$725
rones	0 CAR 21		Quantity 1
	accessing.		Proce \$725.00
aser Bird Control			Product Total \$725.00
	and the second se		
hock Track Systems			ADD TO CART >
ird Balls			
ird Wire	Reviews	Details Applica	tons Benefits Add & Combine Specs Case Studies
isual Scares and Preda ecoys	tor Backed by our 3 Against Material	0 Day Electronics Perfo	rmance Satsfaction Guarantee AND our 6-Month Manufacturer's Warranty
rd Gels, Taste Aversion	· Option to a	dd 3 Visual Scares to p	ackage for added efficacy
OvoControl [®] P			
			s & high-frequency sound waves that are silent-to-most-humans
or Songbird Lovers			l brd distress calls & predator cnes, covers up to 6 acres ency sound waves, covers up to 3 600 sq. ft
	 4 speakers in 	noluded - 4 independent	speakers with 100 ft of wire each
emote Control Drone			I sound delays. & daylight / night operation
etail Products			is designed to withstand outdoor use
ties Products	· Onten in an		(3) high-quality visual scare products

N-DOIS		Search	>		
st control for today's envir	Comment 3 5	Call Us 888.683.18	34 nome About	News Blog Internet	tonai GSA Retail Products Co
Bird Products	Animal/Rodent Products	Insect Product	s Interactive Prob	olem Solver Know	ledge Center FREE Evaluation
All Bird-X Products			Prowle	er Owl	
Electronic Bird Control Sonic Bird Control			10000	oven Visual Scare Ives Money on Clear	up & Repair
Ultrasonic Bird Contro		CALL C		minates Bird & Small P	
Other Electronic Bird Determents			- Mo	oney-Back Guarantee	
Solar Panel Products	A THE R		movemen	ť Scare away birds & smal	nproved with dynamic realism & I pests with this predator replica of th
Bird Spikes					t Horned Owl, which catches & eats
Bird Spikes Kits			nearly eve	rything it can catch	
Stainless Steel Spikes				e, wind-catching design inc	
Plastic Spikes				ate plumage & hunting fligh	
				dating glassy eyes 'follow'	
Bird Netting		1000		le wrigs move & flap in the	
	A PA				seless - don't be fooled by imitations coy in any open outdoor area whe
Drones	Can and a		180	or small critters are a pr	
Laser Bird Control				Quantity 1	
	and the second s			Price \$ 39.25	
Shock Track Systems	ALC: NOT	THE I	0 ,	Product Total \$ 39 25	
Bird Balls	*				
BITO BATTS				ADD TO CA	RT >
Bird Wire	Quality Gu	arantee			
Visual Scares and Pred	Guaranteed to be	manufactured to spec	fications &		
Decoys >		at the time of purchase			
Deroys					
Bird Gels, Taste Aversio	Reviews	Oetais Applic	ations Benefits	Add & Combine	Specs
& OvoControl [®] P					
	· Predator or	N replica life-size owl			
For Songbird Lovers	 Owl scare r 	epeis pest birds & othe	r small animals		
		ving "hunting" posture k			
Remote Control Drone		span & accurate markin	gs.		
		ine non-toxic silent			
Retail Products	 Covers up 	to 6 000 sq. ft.			

Accessories

IRD-X		Search Call Us: 888.683.183) 34 nove About News Bog International GSA Ratal Products. Caritad			
Bird Products	Animal/Rodent Products	Insect Products	Interactive Problem Solver Knowledge Center FREE Evaluation			
All Bird-X Products			Scare-Eye Balloons			
Electronic Bird Control Sonic Bird Control Ultrasonic Bird Contro Other Electronic Bird Deterrents	0	0	 Simple, Highly Effective Bird Repellent Reduce Time & Energy Spent on Cleanup Reflective Mylar Eyes and Tails included 			
Solar Panel Products Bird Spikes Bird Spikes Kits Stainless Steel Spikes Plastic Spikes			 (3 Ppck); Keep brds away with these simple writy bail visual deterrents that move with the wind & internatate pest birds within visible range. Includes three balloons - one white lone yellow one black. Easy to use, cost-effective solution - hang the ballocis anywhere. Ballocin move in the wind for fear of movement. 			
Bird Netting Drones	20		Scare Eye [®] balkoons are useful in many applications - homes gardens barns trees garages mannas doorways & many more			
Laser Bird Control			Quantity 1 Proce \$ 32.55 Procest Total \$ 32.55			
Shock Track Systems		arantee a manufactured to specified to specified to specified to the speci	ADD TO CART >			
Bird Wire	Reviews	Deters Applice				
Visual Scares and Predu Decoys >	Precator de	eccy 3D balloons ons included lone (1) wh	tts, one $\left(1\right)$ black, and one $\left(1\right)$ yellow			
Bird Gels, Taste Aversio & OvoControl [®] P	 Weatherpro 	oof vinyi inflatable ballor	d strings for each balloon on w and gaping mouth of natural predators			
For Songbird Lovers		 Wind causes the Scare-Eye Balloons to move in the wind increasing efficacy Easy installation 				

Remote Control Drone

ATTACHMENT B - CONTAINMENT CONSTRUCTION PLANS

ENDURING RESOURCES 24N RECYCLING CONTAINMENT PIT PROJECT CONSTRUCTION PLANS

SITE CONTROL


CENTER OF PRODUCED WATER PIT


Lat 36°12'21"N Long 107°44'26"W

SECTION 24, TOWNSHIP 23 NORTH, RANGE 9 WEST, NEW MEXICO PRINCIPAL MERIDIAN SAN JUAN COUNTY, NEW MEXICO

SAN JUAN COUNTY, NEW MEXICO September 2018

PROJECT DESCRIPTION: WEST LYBROOK RECYCLING PIT





Sheet List	lable
------------	-------

Sheet Title

- COVER
- G101 GENERAL NOTES AND LEGEND
- C101 SITE MAP
- C102 SITE GRADING AND DRAINAGE PLAN
- C103 SITE PROFILE

Sheet Number

G100

- C104 SITE CROSS-SECTIONS
- C105 SITE HORIZONTAL CONTROL PLAN
- C106 LINER BALLAST TUBES AND PIT GEOCOMPOSITE VENTILATION GRID LAYOUT

HEATHER D. MCDANIEL P.E. NM #2204

PROJECT MANAGER

- C107 GEOCOMPOSITE DETAILS
- C108 LINER AND BALLAST TUBE DETAILS

v# Date

- C109 LEAK DETECTION SYSTEM AND PIT MAINTENANCE ROAD DETAILS
- C110 CHAIN LINK SECURITY FENCE DETAILS
- C111 SITE EROSION AND SEDIMENT CONTROL PLAN
- C112 SITE EROSION AND SEDIMENTATION CONTROL DETAILS

THESE DETAILED PLANS AND SPECIFICATIONS WERE PREPARED UNDER MY DIRECTION AND SUPERVISION ON BEHALF OF SOUDER, MILLER & ASSOCIATES

tember 28,2018

SOUDER, MILLER & ASSOCIATE 8000 W. 14th Avenue Lakewood, CO 80214 Phone (x0) 250-9011 Ratios 200-074 www.woodanatom. Serving the Southward & Rocky Montanta Magazare Celefa Promote, Riche Lough Southants

DATE

ARE PREPARED BASED ON EXISTING SITE CONDITIONS AND REGULATIONS PER THE SEALED S TO THE SITE COES REGULATIONS UNDERGOUND UTILES ETC DETWEEN THE SEALED IN COMMENCEMENT. THE DESIGN AND RECOMMENDATIONS PROVIDED ARE LIMITED TO THE

PLACE AND COMPACT FILL IN HORIZONTAL LIFTS, USING EQUIPMENT AND PROCEDURES THAT WILL PRODUCE RECOMMENDED MOISTURE CONTENTS AND DENSITIES THROUGHOUT THE LIFT.

UN-COMPACTED FILL LIFTS SHOULD NOT EXCEED 10 INCHES LOOSE THICKNESS

MATERIALS SHOULD BE COMPACTED TO THE FOLLOWING

MATERIAL AND HAUL ASSETS TO EMPLACE AND REMOVE THE CORRECT VOLUMES USING LOOSE SOL CORRECTION FACTORS. NO SEPARATE MEASUREMENT OR PAYMENT MILL BE MADE THEREFORE.

- CLARPICATIONS AND/OR RECAESTS REGARDING PROJECT INTENT AND MODIFICATIONS SHALL BE SUBMITTED TO THE ENAINEER PRIOR OR DURING CONSTRUCTION A COMMA, MORTTEN REQUEST FOR INFORMATION (RPT), THE ENAINEER SHALL NOT BE HELD LINBLE (F RECOMMENDATION(S) ARE ALTERED BY OTHERS.
- SAFE SAFE CONTINUES, EACH SUBCONTRACTOR DONING MEXICA ON THE PROJECT SHALL ASSUME SOLE AND ADVENTE THE RESOLVAND HOWEN ON THE PROJECT SHALL ASSUME SOTH WORKING AND NOWNORKING HOURS TY OF ALL PERSONS AND PROPERTY WITHIN THEIR WORK ALERS, DAY, AND NIGHT CURRING BOTH WORKING AND NOWNORKING HOURS SHALL PROVIDE ALL BARRICADES, SHORING, FLAG MEN, SIGNS, LIGHTING AND OTHER DEVICES REQUIRED THEREOF.

LINER SUBGRADE MATERIAL

PER

(ASTM D698) LINER MANUFACTURER'S RECOMMENDATIONS

HEATHER D. MCDANIEL, P.E. SOUDER, MILLER & ASSOCIATES (S 8000 WEST FOURTEENTH AVENUE LAKEWOOD, COLORADO 80214 (303) 239-9011

(SMA

BUREAU OF LAND MANAGEMENT 6251 COLLEGE BLVD, SUITE A FARMINGTON, NEW MEXICO 87402 (505) 564-7600

SURFACE OWNER

ENDURING RESOURCES 332 COUNTY ROAD 3100 AZTEC, NEW MEXICO, 87410 (505) 386-8887

ACILITY/PIT OWNER

CIVIL ENGINEER

MINIMUM PERCENT

MISCELLANEOUS BACKFILL.

- THE CONTRACTOR WALL BE RESPONSIBLE FOR THE REPARA MOOR REPLACEMENT OF ANY COMMENT ONE CASED BY THE CONSTRUCTION OF THE PROSENT OF ROADS, FEVERS, COMMARKES, DREMARKES TORE LOUR DREAD TO BE CASED BY THE ECUMPMENT, MAP REPROPENDENTS, THE CONTRACTOR SMALL REPLAR AND/OR REPLACE ALL DESTROYED OR DAMAGED SURFACE MIRROYEMENTS ECUMPMENT, MAP REPROPENDENTS, THE CONTRACTOR SMALL REPLAR AND/OR REPLACE ALL DESTROYED OR DAMAGED SURFACE MIRROYEMENTS WITH MIRROYEMENTS CAULT, DTHOSE REMOVED.
- STOXPUING OF TOP SOL: CONTRACTOR SHALL SEDEGATE AND STOCKNELAL TOPSOL OUTSIGE OF THE CONSTRUCTION AREA WITH APPROPRIATE SEDMENT CONTROL. TOP SOL SHALL BE REBSTRUITED ON THE OUTSIDE OF CONSTRUCTED BERMS, AND ETHER SEEDED, AND MULCHED OR PROTEED WITH RECORD CONTROL AND ANALYRES, REFER TO CONSTRUCTION PLANS FOR DETAILS.
- ALL ESCHING TRAFFE CARS MILEOST MARKES AND DELINEATORS WITHIN CONSTRUCTION LIMPS SHALL BE REMOVED OR OFFERT AND CONTRACTOR AS DIRECTED BY THE OWNER'S DESIDER. INFORMATION SHOUSA BET TO BE OFFERT AND ALL OTHERS ARE TO BE REMOVED THIS WORK MILL BE INCLUDED IN THE UNIT BID PRICE FOR REMOVAL OF STRUCTURES AND OBSTRUCTIONS.
- Т не сонтрастоя вниц минтии не космые, костов то иц дидети георетите ви у Реогламо базу телико коместнов то типноить яки реператор за ретеграние посетателе от не омерете велеяетатити со резпонет. Типноить каки реператор сонзретер инсиретити, то сомръетном от тне продест мир но межиливыето грамменит миц ве мире тнетеголе:
- BE ALLOWED. CONTRACTOR SHULT PRODUCE PROFILES CONTINUENT RELOCATION BY UTILITY COMPARES VAL. BE DORE CONCIDENT THE SUB-CONTRACTOR SHULT PROFILES AND ADDRESS AND ADDRESS ADDRESS ADDRESS DE TOUTINTY WORK IN COMPARES VAL. BE DORE CONCIDENT OF ADDRESS ADDRE ADDRESS ADD

33

Компититичиство не дороди, от тнезе водомо рыма, пе сонтластоя и везорозвые теор тне ревелятом ограммае то надисти проректу, но ревои яные всимите он цию 50 ссозе то тне рефректу ше из то ещомозе му заси проректу произеттими селонома, всязона катима сосоле об отвер падиона, инсинимант пези, т прои тне сарализо везорево он тне THE PROJECT MULHAVE ALTERATION VERIFICATION AND SUBGRADE DENSITY TESTS COMPLETED BY A GEOTECHNEAL ENAIMEERING COMPARY TO VERIFY COMPACTION. PROCE ROLLING MULL BE COMPLETED ALONG THE PROJECT SUBGRADE AND ANY SOFT SPOTS WILL REMOVED AND RECONSTRUCTED BEFORE THE COMPACTOR BEGINS WERK.

ABBREVIATIONS

BACKFILL MATERIALS TO BE PLACED UNDER CONCRETE SLABS SHALL COMPLY WITH ALL APPLICABLE TECHNICAL SPECIFICATIONS, EXPANSIV TYPE SOLLS ARE PROHIBITED AS BACKFILL MATERIALS.

THE EARTHWORK HAUL ON THIS PROJECT WILL BE CONSIDERED AS INCLUDED IN THE CONTRACT PRICE BORROW AS APPLICABLE, AND NO SEPARATE MEASUREMENT OR PAYMENT WILL BE MADE THEREFORE.

FOR UNCLASSIFIED EXCAVATION /

EMBANKMENT FILLS SHOULD BE COMPACTED TO A MINIMUM 95 PERCENT OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D698 AT NEAR OPTIMUM MOISTURE CONTENT IN LIFTS NOT EXCEEDING IOUNCHES IN LOOSE THICKNESS.

ON-SITE AND IMPORTED SOILS SHOULD BE COMPACTED AT MOISTURE CONTENTS NEAR OPTIMUM

32

4

SPECIAL CONDITION: IF ANY ARCHEOLOGICAL RESOURCES ARE DISCOVERED ON THE SITE OF MILL CEASE IMMEDIATELY, AND THE PERMITTEE MILL NOTIFY THE OWNER'S REPRESENTATIVE.

THIS GRADING OPERATION, SUCH OPERATION

CUBIC FEET

SQ. FT 0.C. N.T.S.

SOUDER, MILLER & ASSOCIATES Engineering + Environmental + Surveying Serving the Southwest & Rocky Mountain 8000 West Fourteenth A venue Lakewood, CO 80214 (103) 239-001 Tell-Free (877) 299-0942 Fax (303 www.soutemulter.com

STATION

CORRUGATED METAL BUREAU OF LAND MANAGEMENT

DIAMETER (Ø CUBIC YARDS

STA. TOP TOP

PLAN

- тнеете на усомотячиствои съря доже поя тне колосит, тне сонтячистоя выди, мот этоне се сонимент от митявы, онтзое от тне подест воилюменез он тыз пораст, т тне може ниц, ве соказетеля испорати, то тне сониме етоно ит не подест имо заприлет висучившент ор пливит миц, не миде тнепероке, сонтярстоя то осоополимте мити омнеп он site stоravae.
- EMERGENCY ACCESS SHALL REMAIN OPEN AT ALL TIMES
- THE CONTRACTOR WILL REMOVE AND PROTECT ROAD NAME SIGNS DURING CONSTRUCTION AND REPLACE AS SOON AS POSSIBLE AFTER CONSTRUCTION.
- THE CONTINUETOR SHALL BE RESPONSIBLE FOR REPORTING AND CLEAN UP OF SPILLS ASSOCIATED MITH PROBLET CONSINCTION AND SHALL REPORT AND RESPONSID TO SHLL SOF MAXIODIS MITERIAL SCH-MA GACIAL BLEEL. MOTA CLEAN STORE AND SHALL REPORT AND RESPONSIDE CONTRACTION AND THE MATTERIAL SCH-MA GACIAL CLEAN. THIS ASSOCIATED CONTRACT TO PLUC FEALTH OF THE REPORTING FOR REPORTING PART SHLLS INFORMATION. THE CONTRACT OF SHALLS NOT ASSOCIATED SHALL BE RESPONDED FOR REPORTING SHALL BE MADE MMEDIATELY TO THE DIMINIONAMENT. THE CONTRACT TO PLUC FEALTH AND OF CURRENT SHALL BE CONTRACT AND AND ASSOCIATED DIMINIONALIS DERIVIDED AND OF CURRENT SHALL BE AND THE MALTELY TO THE DIMINIONAMENT. DERIVICATION AND ASSOCIATED MITH CONSTRUCTION. REPORTS SHALL BE MADE MMEDIATELY TO THE DIMINIONAMENT. DERIVICATION FOR AND ASSOCIATED AND TO THE OWARDS REPRESENTATIVE DE DESIGNER. AND MERIORITED SUIS DERIVIDED AND ASSOCIATED DIMINIONALIS DERIVIDED AND ASSOCIATED MONTO THE OWARDS REPRESENTATIVE DE DESIGNER. AND ASSOCIATED DIMINIONALIS DERIVIDED AND ASSOCIATED DIMINIONALIS DERIVIDED AND ASSOCIATED DIMINIONALIS DERIVIDED AND AND ASSOCIATED DIMINIONALIS DERIVIDED ASSOCIATED DIMINIONALIS DERIVIDED ASSOCIATED DIMINIONALIS DERIVIDED ASSOCIATED DIMINIONALIS DERIVIDED AND ASSOCIATED DIMINIONALIS DERIVIDED ASSOCIATED DIMINIONALIS DERIVALIS DERIVIDE

8 37.

ALL EXISTING DRAINAGE COURSES ON THE PROJECT SITE MUST CONTINUE TO FUNCTION DURING STORM CONDITIONS, PROTECTIVE MEASURERS AND TEMPORARY DRAINAGE PROVISIONS MUST BE USED TO PROTECT CONTIGUOUS PROPERTIES DURING GRADING OPERATIONS

FEET EXISTING ELEVATION

HLIM TYPICAL TOP OF BANK TOE OF BANK SQUARE FEET ON CENTER NOT TO SCALE

LINEAR FEET

POLYETHYLENE

THE FINISHED GRADE SHALL BE SLOPED AWAY FROM ALL EXTERIOR BUILDING WALLS AND FACILITIES TO PROMOTE POSITIVE DRAINAGE AWAY FROM FOUNDATIONS.

NO OBSTRUCTION OF FLOOD PLAINS OR NATURAL WATER COURSES WILL BE PERMITTED

DURING ROUGH GRADING OPERATIONS AND PRIOR TO THE CONSTRUCTION OF ANY PERMANENT DRAINAGE STRUCTURES, TEMPORARY DRAINAGE CONTROL SHALL BE PROVIDED TO PREVENT PONDING WATER AND DAMAGE TO CONTIGUOUS PROPERTIES.

ALL PROJECT LIMITS AND CONSTRUCTION AREAS SHALL BE CLEARLY DELINEATED IN THE FIELD PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION AND/OR GRADING.

- FINL PAYNERY OF CANCET FAND REIN-CORING BARS SHALL BE BASED ON PLAN CAUNTITIES. IF THE DESIGN IS REVISED DURING CONSTRUCTION OR IF A CAUNTITY CHANCE IS RECURRED DUE TO ERRORS ON THE PLANS, THE PAYNENT SHALL BE BASED ON COMPUTED FIELD CAUNTITES MEASURED TO REAT LINES.
- EXISTING FRACE SIANS AND OTHER ITEMS OF PRIVATE PROPERTY FOUND TO BE WITHIN THE RIGHT-OF-WAY ARE TO BE REMAYED AND REPLACED AT THE ECOC OF RIGHT-OF-WAY BY THE COMPACTOR. IT WAS WORK WILL BE CONSIDERED INCIDENTIAL TO THE COMPLETION OF THE PROJECT AND NO MEASUREMENT OF PAYMENT WILL BE IMADE THEREFORE.
- THROUGHOUT THE LIFE OF THE PROJECT THE CONTRACTOR SHALL KEEP LOCAL LANDOWNERS INFORMED IN TIMELY FASHION OF ANY LAVE CLOSURES WHICH WILL RESTRICT THE NORMAL FLOW OF TRAFFIC. THERE WILL BE NO DIRECT PAYMENT FOR THIS WORK.

45 \$ t 42 4 40

PERMIT

EGOION AND SEDMENTATIVO CONTRO MESSINES SHALL DE MAREMENTED AND SHALL DE KETY INN ACE MATE. REVOIR SOLONAND SEDMENTATION POTENTIAL IS MITGATED. REMOVAL OF SILT AND SEDMENT IS REGURED CHOCES IN AND SEDMENT HAS REACHED MAE HEGHT OF THE SILT FERGE. EROSION AND SEDMENTATION CONTROL CENTES SHALL DE CHOCES IN AND MANTANED PER THE OWNERS OWNER WILL ENSURE THAT ALL INSTALLED EROSION AND SEDMENTATION CONTROL MEASURES COMPLY WITH THEIR EXISTING ASSET STORMMATER POLLUTION PREVENTION PLAN (SMPPP).

HE.

LEGEND

ENDURING RESOURCES WLU 2309-24N

WATER RECYCLE FACILITY GENERAL NOTES AND LEGEND

MIN. MIL or MM MCC ME MAX. LLDPE 5 HORIZ FG 긔 Ň ELEV. DIA CU. YD. CU. FT. CMP BUM

MINIMUM

MILLIMETER

MECHANICAL CONTROL CENTER

SAN JUAN COUNTY

MATCH EXISTING MAXIMUM LINEAR LOW-DENSITY HORIZONTAL FINISH GRAD

IN THE EVENT A SERVICE OUTAGE IS REQUIRED, CONTRACTOR WILL NOTIFY ALL AFFECTED PARTIES

WHEN AND HOW LONG THEY

WILL BE

MINOU

SERVICE

RECORD DRAWINGS OR WORK COMPLETED SHALL BE SUBMITTED TO ENGINEER PRIOR TO FINAL ACCEPTANCE OF THE INSTALLATIONS. ROADWAY SECTION REPLACEMENT SHALL MEET CURRENT SAN JUAN COUNTY AND UNTED STATES BUREAU OF LAND MANAGEMENT GOLD BOOK STANDARDS FOR DEPTH OR MATCH EXISTING DEPTH, VMICHEVER IS THICKER, SAN JUAN COUNTY SHALL BE NOTIFIED 72 HOURS PRIOR TO COMMENCING ANY WORK IN THE PUBLIC RIGHT OF WAY.

- ALL WORK IN THE KICHINT OF UNE STEEMAK, MITER NEO-DIDAETRI NETLANGS OR RERAINTING SAPELIE AT KICHING SAPELIE AND KICHING SAPELIE SISTERICI TO POORIETTI AND SAPELIE AND KICHING SAPELIE AND KICHING SAPELIE SISTERICI TO POORIETI AND SAPELIE SISTERICI TO SAPELIESIS SISTERICI TO SAPELIESI SISTERICI TO SAPE CEMEN
- TOPOGRAPHY SHOWN ON THESE PLANS IS ACCORDING TO FIELD LOCATION BY NCE SURVEYS, INC. JAMES C. EDWARDS P.L.S. #19289. DATED AUGUST 22, 2018.
- THE CONTRACTOR SHALL SEE SAVISBLE FOR ALL REMOVALS RECARED TO COORDELTE THE REPROJECT TO CONTRAL REMOVAL SNOT SHOWN ON THE CONTRACTOR SHALL SEE SAVISBLE FOR ALL REMOVALS RECARED CO COORDELTE THE REPROJECT. SAVISBLE SAVISBLE SAVI CONTRACT PREFERSE FOR REMOVELS AND OBSTRUCTIONS AND THE CONTRACTOR WILL NOT RECEIVE MONTRAVE COMPRISATION FOR WAINTED REMOVELS.
- UNSUITABLE CONSTRUCTION MATERIALS AND DEBRIS FROM CLEARING AND GRUBBING ARE TO BE PLACED IN AN ENVIRONMENTALLY SUITABLE DISPOSAL SITE.
- UTUTLY LOCATIONS SHOWN WITHIN THE PROJECT BOUNDARY ARE BASED LIPON THE BEST MUNAULE EROPEKTER BUT WARRANTED TO BE ACCHART. CONTACT. UTULY PRODUCES BEFORE STREPTION ANY ESCAVITANTIWORS, SHOLD CO IN ITERETEANCE REPORTED AS APERAR IN THE CONSTRUCTION FORMWAST. THE CONTRACTOR SHALL BEING THAT INFO ATTENTION OF THE ENGINEER MMEDIATELY PRIOR TO INSTRUCTION. FALURE TO DO SO SHALL NOT BE A BASIS OF E CONTRACTOR. LABLE EVIDENCE, BUT THE POSITIONS ARE NOT TON WORK, SHOULD CONFLICTING INFORMATION HALL BRING THAT INFORMATION TO THE L NOT BE A BASIS OF EXTRA PAYMENT TO THE

5

ENGINEER HAS NO CONTROL OVER COST OF LABOR MARKET CONDITIONS.

MATERIALS

EQUIPMEN

F OR SERVICES FURNISHED BY OTHERS.

COMPETITIVE BIDDING OF

þ

PROPOSED CHAIN LINK FENCE PROPOSED MAN WAY PEDESTRIAN GATE PROPOSED DRAINAGE PIPE PROPOSED INTERMEDIATE CONTOURS PROPOSED INDEX CONTOURS EXISTING INTERMEDIATE CONTOURS EQISTING INDEX CONTOURS

9 þ

50

CONTRACTOR SHALL COMPLY WITH ANY AND ALL CONDITIONS OF APPROVALS ISSUED BY THE REGULATORY AGENCIES AS DETERMINED BY OWNER. THE OWNER WALL PROVIDE CONSTRUCTION OBSERVERS AND WATERIAL TESTERS TO OBSERVE AND TEST LL CONTINUELLE DERIMINORYS. THE CONSTRUCTION OBSERVERS AND WATERIAL TESTERS SHALL NOTIRE CONTINUOUS ONASTE ODSERVATIONA MUD TESTING DURING CONSTRUCTION OBSERVERS AND MATERIAL TESTERS AND ANOTHE CONSTRUCTION OBSERVERS AND MATERIAL TESTERS AT LEAST TWO WORKING AND IN AUAVAGE WAY FELLO DEVINIONS OF THE CONSTRUCTION OBSERVERS AND MATERIAL TESTERS AT LEAST TWO WORKING AND IN AUAVAGE WAY FELLO DEVINIONS OF THE CONSTRUCTION CONSERVERS AND MATERIAL TESTERS AT LEAST TWO WORKING AND IN AUAVAGE WAY FELLO DEVINIONS OF THE CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTION OF CONSTRUCTION OF CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTION OF CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTION OF CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTIONS AND THE CONSTRUCTIONS AND THE CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTION CONSTRUCTIONS AND THE CONSTRUCTION THE CONTRACTOR SHALL COORDINATE STRUCTURAL DRAWINGS WITH OTHER DRAVININGS FOR INDIVIDUAL ITEMS, DISCREPANCIES UNCOVERED IF ANY, SHALL BE REPORTED BEFORE PROCEEDING WITH THE WORK SO THAT PROPER ADJUSTMENT CAN BE MADE.

THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN THE FIELD

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE AND ADEQUATE SHORING FOR ALL PARTS OF THE PROJECT DURING CONSTRUCTION. ALL STRUCTURES SHOWN ON THE DRAWINGS HAVE BEEN DESIGNED FOR STABILITY UNDER FINAL CONFIGURATION.

49 48 47 46

- 2 THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANES REFORE COMMENCING WORK AND SHALL BE RESPONSIBLE FOR COMPAVING WITH NEW MERICO ONE-CALL PROCEDURES. ANY DAMAGE TO EXISTING UTILITIES MUST BE IMMEDIATELY REPORTED TO THE APPROPRIATE UTILITY COMPAY.
- NEW MEXICO 811 LOCATES SHALL BE FIELD VERIFIED BY THE CONTRACTOR THROUGH POTHOUNG AND COORDINATION WITH UTILITY OWNER

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING THE RESPECTIVE UTILITY COMPANIES PRIOR TO GRADING OR TRENCHING.
- 25

- TO ALL REQUIREMENTS SET FORTH BY THE TECHNICAL SPECIFICATIONS LOCATED IN THE PROJECT

opyright 28

2018 Souder, Miller & Associates - All Rights EARTHWORK ESTIMATES 27

TRENCHES DEEPER THAN 5' IN DEPTH MUST BE SHORED, SLOPED, OR SHIELDED PER OSHA REGULATIONS

ARE BASED ON COMPACTED AND IN-PLACE MATERIAL.

CONTRACTOR IS RESPONSIBLE FOR

NDNNG


THE REQUIRED


G101


GJF


- THE CONTRACTOR SHALL REVEW AND FOLLOW THE RECOMMENDATIONS PROVIDED IN THE "CRETONIADE, MANAEEMINA REPORT STUDY WU DEMOLE FACILITY FRANKA WITER PORTS ANL ANAL CONTRACT, NEWNERDO, DREPARED VOCEMATING, CANED AULY 6, 2018 FOR MOSITURE CONTENT, MAXIMAM COMPACTED LIFT DEFITIS, AND MINIMAM COMPACTION RECURREMENTS FOR THE PROJECT.

- THE CONTRACTOR SHALL MANUAL.













© Copyright 2018 Souder, Miller & Associates - All Rights Reserved

P:IS-Enduring Resources - 16B Pond Design (5127383)/CAD/CivilW LYBROOK/5127383 WLU GRADING AND DRAINAGE.dwg, 9/27/2018 1:48:47 PM GJF











© Copyright 2018 Souder, Miller & Associates - All Rights Reserved


P:15-Enduring Resources - 16B Pond Design (5127383)/CAD/Civil/W LYBROOK/5127383 WLU_Details.dvrg, 9/27/2018 2:02:54 PM GJF





© Copyright 2018 Souder, Miller & Associates - All Rights Reserved

P:/5-Enduring Resources - 16B Pond Design (5127383)/CAD/Civil/W LYBROOK/5127383 WLU EROSION CONTROL.dwg, 9/27/2018 1:51:07 PM GJF



© Copyright 2018 Souder, Miller & Associates - All Rights Reserved

P:15-Enduring Resources - 16B Pond Design (5127383)/CADICivil/WLYBROOK/5127383 WLU_Erosion Control Details.dwg, 9/27/2018 1:51:42 PM GJF



GEOTECHNICAL ENGINEERING REPORT WLU REMOTE FACILITY FRACKING WATER POND SAN JUAN COUNTY, NEW MEXICO

Submitted To:

James McDaniel Enduring Resources 332 CR 3100 Aztec, New Mexico 87410

Submitted By:

GEOMAT Inc. 915 Malta Avenue Farmington, New Mexico 87401

NMOCD OCT 19 2018 DISTRIGT III

July 6, 2018 GEOMAT Project 182-3038



July 6, 2018

James McDaniel

Enduring Resources 332 CR 3100 Aztec, New Mexico 87410

RE: Geotechnical Engineering Study WLU Remote Facility Fracking Water Pond San Juan County, New Mexico GEOMAT Project No. 182-3038

GEOMAT Inc. (GEOMAT) has completed the geotechnical engineering exploration for the proposed WLU Remote Facility fracking water pond to be located in San Juan County, New Mexico. This study was performed in general accordance with the scope of services in our Proposal No. 182-04-22 dated April 20, 2018.

The results of our engineering study, including the geotechnical recommendations, site plan, boring records, and laboratory test results are attached. Based on the geotechnical engineering analyses, subsurface exploration and laboratory test results, the proposed pond could be constructed as an incised, double synthetic-lined pond as proposed. Other design and construction details, based upon geotechnical conditions, are presented in the report.

We have appreciated being of service to you in the geotechnical engineering phase of this project. If you have any questions concerning this report, please contact us.

Sincerely yours, **GEOMAT** Inc.

Seth D. Yokel Staff Geologist

Copies to: Addressee (1) via E-mail



Matthew J. Cramer, P.E. Vice President

TABLE OF CONTENTS

Page No.
INTRODUCTION
PROPOSED CONSTRUCTION
SITE EXPLORATION
Field Exploration
Laboratory Testing 2
SITE CONDITIONS
SUBSURFACE CONDITIONS
Soil Conditions
Groundwater Conditions
Laboratory Test Results
OPINIONS AND RECOMMENDATIONS
Geotechnical Considerations
Pond Design and Construction 4
Slope Stability Analysis 4
Seismic Considerations
Lateral Earth Pressures
Earthwork
General Considerations
Site Clearing
Excavation7
Fill Materials7
Placement and Compaction
Compliance 8
Drainage
Surface Drainage
Subsurface Drainage
GENERAL COMMENTS

TABLE OF CONTENTS (continued)

APPENDIX A

Vicinity Map Site Plan Logs of Borings Unified Soil Classification Drilling and Exploration Procedures

APPENDIX B

Laboratory Test Results Laboratory Test Procedures

APPENDIX C

Important Information About This Geotechnical Engineering Report (Taken From GBA)

GEOTECHNICAL ENGINEERING REPORT WLU REMOTE FACILITY FRACKING WATER POND SAN JUAN COUNTY, NEW MEXICO GEOMAT PROJECT NO. 182-3038

INTRODUCTION

This report contains the results of our geotechnical engineering exploration for the proposed WLU Remote Facility fracking water pond to be located in San Juan County, New Mexico, as depicted on the Vicinity Map and Site Plan in Appendix A of this report.

The purpose of these services is to provide information and geotechnical engineering recommendations about:

• subsurface soil conditions

slopes for pond walls

• groundwater conditions

• drainage

- lateral soil pressures
- earthwork

The opinions and recommendations contained in this report are based upon the results of field and laboratory testing, engineering analyses, and experience with similar soil conditions, structures, and our understanding of the proposed project as stated below.

PROPOSED CONSTRUCTION

The WLU Remote Facility fracking water pond will have dimensions of approximately 350 feet by 350 feet and will be located at 36.210370° north latitude / 107.831582° west longitude. We understand the pond will be excavated (incised) into the existing grade at the site. The total depth of the pond will be 20 to 25 feet and it will be lined with a double HDPE liner system. The pond is located on relatively flat terrain.

SITE EXPLORATION

Our scope of services performed for this project included a site reconnaissance by a staff geologist, a subsurface exploration program, laboratory testing and engineering analyses.

Field Exploration:

Subsurface conditions at the site were explored on June 15, 2018, by drilling four exploratory borings, designated B-1 through B-4, at the approximate locations shown on the Site Plan in Appendix A. Borings B-2 through B-4 were drilled to depths of 35 feet below existing ground surface. Boring B-1 was terminated short of the planned depth of 35 feet due to auger refusal on sandstone at 30 feet below existing ground surface.

The borings were advanced using a CME-55 truck-mounted drill rig with continuous-flight, 7.25inch O.D. hollow-stem auger. The borings were continuously monitored by a geologist from our office who examined and classified the subsurface materials encountered, obtained representative samples, observed groundwater conditions, and maintained a continuous log of each boring.

Soil samples were obtained from the borings using a combination of standard 2-inch O.D. split spoon and 3-inch O.D. modified California ring barrel samplers. The samplers were driven using a 140-pound hammer falling 30 inches. The standard penetration resistance was determined by recording the number of hammer blows required to advance the sampler in six-inch increments. Representative bulk samples of subsurface materials were also obtained.


Groundwater evaluations were made in each boring at the time of site exploration. Soils were classified in accordance with the Unified Soil Classification System described in Appendix A. Boring logs were prepared and are presented in Appendix A.

Laboratory Testing:

Samples retrieved during the field exploration were transported to our laboratory for further evaluation. At that time, the field descriptions were confirmed or modified as necessary, and laboratory tests were performed to evaluate the engineering properties of the subsurface materials.

SITE CONDITIONS

The site of the proposed pond is located roughly 300 feet east of an existing unnamed dirt road in a currently undeveloped area approximately 6 miles southwest of US Highway 550 by Nageezi, NM and Counselor, NM. The ground surface across the site of the proposed pond was generally flat with a gentle slope to the southwest. The area was vegetated by a significant growth of native weeds, sage brush, shrubs, and small trees at the time of our exploration. No evidence of prior structural development was noted at the site. The photo below depicts the site's condition at the time of our exploration.



Drill Rig at Boring B-2 View Toward the West

SUBSURFACE CONDITIONS

Soil Conditions:

As presented on the Boring Logs in Appendix A, in all four borings, B-1 through B-4, we encountered predominantly sandy soil conditions underlain by rock. Sandy soils were encountered in borings B-1 through B-4, to depths ranging from 2 to 6 feet below existing ground surface (bgs). Sandstone/Siltstone interlayered with shale lenses were encountered below the sandy soils in all the borings. The sandy soils were medium dense and were generally dry to damp. The sandstone/siltstone rock was generally slightly too moderately weathered.

Groundwater Conditions:

Groundwater was not encountered in any of the borings. Groundwater elevations can fluctuate over time depending upon precipitation, irrigation, runoff and infiltration of surface water. We do not have any information regarding the historical fluctuation of the groundwater level in this vicinity.

Laboratory Test Results:

Laboratory analyses of samples tested indicate the sandy and clayey soils have fines contents (silt- and/or clay-sized particles passing the U.S. No. 200 sieve) ranging from approximately 18 to 19 percent. Plasticity indices ranged from non-plastic to an index of 2. In-place dry densities of the soil and rock samples tested ranged from approximately 103 to 114 pounds per cubic foot (pcf), with natural moisture contents between approximately 3 and 12 percent.

Results of all laboratory tests are presented in Appendix B.

OPINIONS AND RECOMMENDATIONS

Geotechnical Considerations:

The site is considered suitable for the proposed fracking water pond based on the geotechnical conditions encountered and tested for this report and our understanding of the project. If there are any significant deviations from the assumed finished elevations and/or pond locations noted at the beginning of this report, the opinions and recommendations of this report should be reviewed and confirmed/modified as necessary to reflect the final planned design conditions.

Pond Design and Construction:

The fracking water pond could be constructed as an incised basin as proposed. The double HDPE liner system should be installed in accordance with the manufacturer's recommendations.

Our recommendations are based on the information obtained from the borings performed during our subsurface exploration. It should be realized that subsurface conditions could vary across the extent of the pond area, and these variations may not become apparent until construction is underway. If, during construction, soil types other than those encountered during our exploration are encountered, we should be contacted to observe the actual conditions and confirm/modify our recommendations, as appropriate.

Slope Stability Analysis:

A slope stability analysis was performed for the site to develop recommendations for the cut slope inclinations for the incised pond. Galena Slope Stability software (version 6.1) was used as an aid in developing our recommendations. Printouts of the software analyses are available upon request.

Based on the results of our subsurface exploration, laboratory testing, and engineering analyses, the maximum recommended inclinations for the pond walls are 2.5:1 in soils and 1:1 in rock.

We understand that no above-grade embankments are planned for the project. If the project scope changes to include embankments, GEOMAT should be notified to review the plans and confirm or modify our recommendations as necessary.

Seismic Considerations:

Based on the subsurface conditions encountered in the borings, we estimate that Site Class B is appropriate for the site according to Table 1613.5.2 of the 2009 International Building Code. This parameter was estimated based on extrapolation of data beyond the deepest depth explored, using methods allowed by the code. Actual shear wave velocity testing/analysis and/or exploration to a depth of 100 feet were not performed as part of our scope of services for this project.

Lateral Earth Pressures:

For soils above any free water surface, recommended equivalent fluid pressures for unrestrained foundation elements are presented in the following table:

• Active:

Granular soil backfill	(on-site sand)	35 psf/ft
Undisturbed subsoil		30 psf/ft

• Passive:

Shallow foundation walls	250 psf/ft
Shallow column footings	350 psf/ft
Sump walls	400 psf/ft

conjunction with passive pressure.

Where the design includes restrained elements, the following equivalent fluid pressures are recommended:

At rest:	
Granular soil backfill (on-site sand)	50 psf/ft
Undisturbed subsoil	60 psf/ft

Earthwork:

General Considerations:

.

The opinions contained in this report for the proposed construction are contingent upon compliance with recommendations presented in this section. Although underground facilities such as foundations, septic tanks, cesspools, basements and irrigation systems were not encountered during site reconnaissance, such features could exist and might be encountered during construction.

Site Clearing:

- 1. Strip and remove all existing fill, debris and other deleterious materials from the proposed construction areas.
- 2. If unexpected fills or underground facilities are encountered during site clearing, we should be contacted for further recommendations. All excavations should be observed by GEOMAT prior to backfill placement.
- 3. Stripped materials consisting of vegetation and organic materials should be removed from the site, or used to re-vegetate exposed slopes after completion of grading operations. If it is necessary to dispose of organic materials on-site, they should be placed in non-structural areas, and in fill sections not exceeding 5 feet in height.
- 4. Sloping areas steeper than 5:1 (horizontal:vertical) should be benched to reduce the potential for slippage between existing slopes and fills. Benches should be level and wide enough to accommodate compaction and earth moving equipment.
- 5. All exposed areas which will receive fill, once properly cleared and benched where necessary, should be scarified to a minimum depth of eight inches, conditioned to near optimum moisture content, and compacted to at least 95% of standard proctor (ASTM D698).

Excavation:

We present the following general comments regarding our opinion of the excavation conditions for the designers' information with the understanding that they are opinions based on our boring data. More accurate information regarding the excavation conditions should be evaluated by contractors or other interested parties from test excavations using the equipment that will be used during construction.

Based on our subsurface evaluation it appears that shallow excavations in soils at the site will be possible using standard excavation equipment, however, rock was encountered at relatively shallow depths across the site. Excavations that encounter formational rock are expected to be difficult and may necessitate the use of heavy-duty equipment and/or specialized techniques.

On-site soils may pump or become unstable or unworkable at high water contents. Dewatering may be necessary to achieve a stable excavation. Workability may be improved by scarifying and drying. Over-excavation of wet zones and replacement with granular materials may be necessary. Lightweight excavation equipment may be required to reduce subgrade pumping.

Fill Materials:

- 1. Native soils could be used in any areas cut for facilitation of the pond excavation.
- 2. Select granular materials should be used as backfill behind walls that retain earth.
- 3. On site or imported soils to be used in structural fills should conform to the following:

	Percent finer by weight
Gradation	(ASTM C136)
3"	
No. 4 Sieve	
No. 200 Sieve	50 Max
 Maximum expansive potential (%)* * Measured on a sample compacted to approxid D698 maximum dry density at about 3 percent The sample is confined under a 144-psf surch 	mately 95 percent of the ASTM nt below optimum water content.

4. Aggregate base should conform to Type I Base Course as specified in Section 303 of the 2014 New Mexico Department of Transportation (NMDOT) "Standard Specifications for Road and Bridge Construction."

Placement and Compaction:

- 1. Place and compact fill in horizontal lifts, using equipment and procedures that will produce recommended moisture contents and densities throughout the lift.
- 2. Un-compacted fill lifts should not exceed 10 inches loose thickness.
- 3. Materials should be compacted to the following:

	Minimum Percent
<u>Material</u>	(ASTM D698)
Liner Subgrade Per Liner Manufacturer's Re-	commendations
Subgrade soils beneath fill areas	95
On site or imported soil fills:	
Beneath footings and slabs on grade	95
Aggregate base beneath slabs and pavements	95
Miscellaneous backfill	90

4. On-site and imported soils should be compacted at moisture contents near optimum.

Compliance:

To assess compliance, observation and testing should be performed by GEOMAT.

Drainage:

Surface Drainage:

Positive drainage should be provided during construction and maintained throughout the life of the proposed project to prevent surface runoff from entering the pond.

Protective slopes should be provided with a minimum grade of approximately 5 percent for at least 10 feet from the structures. Backfill against footings, exterior walls, and in utility trenches should be well compacted and free of all construction debris to reduce the possibility of moisture infiltration.

Subsurface Drainage:

Free-draining, granular soils containing less than five percent fines (by weight) passing a No. 200 sieve should be placed adjacent to walls which retain earth. A drainage system consisting of either weep holes or perforated drain lines (placed near the base of the wall) should be used to

intercept and discharge water which would tend to saturate the backfill. Where used, drain lines should be embedded in a uniformly graded filter material and provided with adequate clean-outs for periodic maintenance. An impervious soil should be used in the upper layer of backfill to reduce the potential for water infiltration.

GENERAL COMMENTS

It is recommended that GEOMAT be retained to provide a general review of final design plans and specifications in order to confirm that grading recommendations in this report have been interpreted and implemented. In the event that any changes of the proposed project are planned, the opinions and recommendations contained in this report should be reviewed and the report modified or supplemented as necessary.

GEOMAT should also be retained to provide services during excavation, grading, and construction phases of the work. Construction testing, including field and laboratory evaluation of fill, backfill, and compacted slopes should be performed to determine whether applicable project requirements have been met.

The analyses and recommendations in this report are based in part upon data obtained from the field exploration. The nature and extent of variations beyond the location of test borings may not become evident until construction. If variations then appear evident, it may be necessary to re-evaluate the recommendations of this report.


Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by reputable geotechnical engineers practicing in this or similar localities at the same time. No warranty, express or implied, is intended or made. We prepared the report as an aid in design of the proposed project. This report is not a bidding document. Any contractor reviewing this report must draw his own conclusions regarding site conditions and specific construction equipment and techniques to be used on this project.

This report is for the exclusive purpose of providing geotechnical engineering and/or testing information and recommendations. The scope of services for this project does not include, either specifically or by implication, any environmental assessment of the site or identification of contaminated or hazardous materials or conditions. If the owner is concerned about the potential for such contamination, other studies should be undertaken. This report has also not addressed any geologic hazards that may exist on or near the site.

This report may be used only by the Client and only for the purposes stated, within a reasonable time from its issuance. Land use, site conditions (both on and off site), or other factors may change over time and additional work may be required with the passage of time. Any party,

other than the Client, who wishes to use this report, shall notify GEOMAT in writing of such intended use. Based on the intended use of the report, GEOMAT may require that additional work be performed and that an updated report be issued. Non-compliance with any of these requirements, by the Client or anyone else, will release GEOMAT from any liability resulting from the use of this report by an unauthorized party.

Appendix A



	B-3	B-2	
	B-4	B-1 7890	
	SITE PLAN	PROJECT	
	Boring Locations (approximate)	WLU Remote Facility Pond	
Approximate	GEOMAT Project No. 182-3038	Enduring Resources	
Not to Scale	Date of Exploration: June 15, 2018	San Juan County, New Mexico	'

GEO	MA	Tinc.		Farm Tel (Malta Aver ington, N 505) 327- (505) 326-	VI 87401 7928	Borehole B-1 Page 1 of 1
Project Name: Project Number Client: Site Location: Rig Type: Drilling Method: Sampling Method Hammer Weigh Hammer Fall:	E E S C 7. od: <u>R</u> t: <u>1</u>	82-3(nduri an Ju ME-5 .25" (ing a 40 lb)38 ng F Jan (55 D.D. nd S s	Resou Count Hollo Split s	urces ty, New ow Stem spoon sa	Mexico Auger amples	Latitude: Not Determined Longitude: Not Determined Elevation: Not Determined Boring Location: See Site Plan
Plasticy (pcf) (pcf) (pcf) #200 Sleve Plasticity Index Moisture Content (%)	Blows per 6"	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description
18 NP 110.6 18 NP 12.0	7-13-16 13-19-21 25-31- 50/5" 50/2" 50/4" 20-50/2" 50/1"	SS 18		SM SC RK		15 _	Silty SAND, tan/orange, fine grained, medium dense, slightly damp to dry Clayey SAND, tan/orange, fine grained, medium dense, slightly damp, contains caliche SILTSTONE, tan/gray, fine grained, weakly to moderately cemented Contains intermittent shale lenses (tan/gray with orange mottling) Contains intermittent sandstone/shale lenses SANDSTONE, gray/white with orange mottling, fine grained, moderately cemented, slightly weathered Well cemented, purple layer Contains intermittent shale lenses Well cemented, purple layer, hard drilling Auger Refusal on well cemented sandstone Total Depth 30½ feet

-(915 Malta Avenue Farmington, NM 87401 Tel (505) 327-7928 Fax (505) 326-5721								M 87401 7928	Borehole B-2 Page 1 of 1			
P	roiec	t Nar	ne:	V	VLU F	Rem	ote F	acility P	ond	Date Drilled:6/15/2018			
				1									
								irces					
Client: <u>Enduring Resources</u> Site Location: <u>San Juan County, New Mexico</u>										Elevation: Not Determined			
Rig Type: CME-55										Boring Location: See Site Plan			
								w Stem					
		-								Logged By: SY			
			•							Remarks: <u>NE Corner</u>			
н	amm	er Fa	all: _	3	0 incl	nes							
Labo	orator	y Res	sults	.9	0 ~		be	Ы	-				
6	ng	Ę	e (%)	per	Typ.	lod	I Ty	dm/	n (ft				
(pcf)	% Passing #200 Sieve	sticit	Moisture Content (%)	Blows per	Sample Type & Length (in)	Symbol	eria	Soil Symbol	Depth (ft)	Soil Description			
	% P	Pla	Mo	Blo	Sam & Le	S	Material Type	Soi	ŏ				
-	++								1 _	Silty SAND, tan/brown, fine grained, medium dense, slightly			
		~	10.5	19-29-41	R		SM		2 _ 3 _	damp to dry			
14.3	19	2	10.5	.0 20-41	18	X			4	SANDSTONE, tan/gray, fine- to medium grained, weakly to			
				50/6"	SS	\geq			5 _ 6 _	moderately cemented, slightly weathered			
					6				7 _				
									8_	Contains intermittent shale lenses			
				50/3"	R				10 _				
					0				11 _ 12 _				
									13 _				
				50/2"	P				14 _ 15 _				
				50/2"	R 0				16				
									17 _ 18 _				
									19				
				14-23-27	SS 18	$\mathbf{\mathbf{x}}$	RK		20 _ 21 _				
						$ \rightarrow $		* * * * * * * *	22	Contains intermittent shale lenses (gray/green shale at base			
									23 24	sample)			
				50/2"	R				25 _ 26 _				
					0				27 _				
									28 29				
				50/4"	SS	~			30 _				
					4				31 _ 32 _				
									33				
								* * * * * * * * *	34 _ 35 _				
				50/2"	SS 2				36 _	Total Depth 35½ feet			
									37 _ 38 _				
									39				
					1			E 1	40				

Project Name: WLU Remote Facility Pond Project Number: 182-3038 Client: Enduring Resources Site Location: San Juan County, New Mexico Rig Type: CME-55 Drilling Method: 7.25" O.D. Hollow Stem Auger Sampling Method: Ito Ibs Hammer Fall: 30 inches								ington, NI 505) 327-	M 87401 7928	Borehole B-3				
								urces ty, New ow Stem poon sa	Mexico Auger amples	Latitude: Not Determined Longitude: Not Determined Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY				
	orator	-		r 6") ee	_	ype	loo	t)					
Ury Density (pcf)	% Passing #200 Sieve	Plasticity Index	Moisture Content (%)	Blows per	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description				
				8-12-16	SS 18	\times	SM		1 _ 2 _ 3 _ 4	Silty SAND, tan/brown, fine grained, medium dense, slightly damp				
102.9			5.7	29-50/5"	R 11				4 - 5 _ 6 - 7 - 8 - 9 _	SANDSTONE, tan/gray, fine- to medium grained, slightly damp, slightly weathered, weakly to moderately cemented				
				28-50/5"	SS 11	\times			10 _ 11 _ 12 _ 13 _ 14 _					
107.5			10.1	50/6"	R 6	×			15 _ 16 _ 17 _ 18 _ 19 _	Contains intermittent shale lenses				
				50/5"	SS 5	\times	RK		20 21 _ 22 _ 23 _ 24 _					
				50/6"	R 6	×			25 26 27 28	Contains intermittent shale lenses				
				50/6"	SS 6	×			29 _ 30 _ 31 _ 32 _ 33 _					
				50/5"	SS 5	\times			34 - 35 - 36 - 37 - 38 - 39 -	Total Depth 35½ feet				
A =	= Auge	r Cuttir	ngs R	= Ring-L	ined Ba	arrel S	ampler	SS = Spl	40 it Spoon (GRAB = Manual Grab Sample D = Disturbed Bulk Sample				

Project Name: WLU Remote Facility Pond								ington, NI 505) 327-	M 87401 7928	Borehole B-4 Page 1 of 1			
P C S R D S H	rojec lient: ite Lo ig Ty rilling	t Nun ocatic pe: Met ing N er W	nber: on: _ hod: /eigh	1 S 7 7 7 7 1 1	82-30 nduri an Ju ME-5	038 ing F uan (55 0.D. and S s	Resou Count Hollo Split s	acility P Irces ty, New ow Stem poon sa	Longitude: Not Determined Elevation: Not Determined Boring Location: See Site Plan Groundwater Depth: None Encountered Logged By: SY				
	orator			r 6"	e (c		/pe	loc	£				
(pcf)	% Passing #200 Sieve	Plasticity Index	Moisture Content (%)	Blows per	Sample Type & Length (in)	Symbol	Material Type	Soil Symbol	Depth (ft)	Soil Description			
5 110.7 104.4			2.9	13-17-23 14-15-25 19-50/3" 32-50/5"	R SM 1 Silty 18 3 SAN SS 4 We SS 6 7 18 9 9 10 10	Silty SAND, tan/orange, fine grained, slightly damp to dry SANDSTONE, tan, fine- to medium grained, slightly damp, weakly cement, moderately weathered							
				50/5"	R 5	×	RK		18 19 20 21 22 23 24 24	SHALE, gray with orange mottling, slightly damp, moderately weathered SANDSTONE, tan, fine- to medium grained, slightly damp, weakly to moderately cemented, moderately weathered			
				50/4"	SS 4 SS 5	X	RK		25 26 _ 27 _ 28 _ 30 _ 31 _ 33 _ 33 _ 34 _	Contains intermittent shale lenses Contains intermittent shale lenses			
				50/2"	SS 2				35 36 _ 37 _ 38 _ 39 _	Total Depth 35½ feet			

	UNIFIE	D SOIL CLASSIF		TEM	CONSI	STENCY OR	RELATIVE	
	Major Divisions		Group Symbols	Typical Names	D	ENSITY CRIT	ERIA	
		Clean Gravels	GW	Well-graded gravels and gravel-sand mixtures, little or no fines		Standard Penetration Test Density of Granular Soils		
	Gravels 50% or more of	Clean Graveis	GP	Poorly graded gravels and gravel-sand mixtures, little or no fines	Penetration Resistance, N (blows/ft.)	Relative Density	ý	
	coarse fraction retained on No. 4 sieve	Gravels with	GM	Silty gravels, gravel-sand-silt mixtures	0-4	Very Loose		
Coarse- Grained Soils		Fines	GC	Clayey gravels, gravel-sand-clay mixtures	5-10	Loose		
More than 50% retained on No. 200 sieve		Clean Sands	SW	Well-graded sands and gravelly sands, little or no fines	11-30	Medium De	ense	
	Sands More than 50% of	Clean Ganus	SP	Poorly graded sands and gravelly sands, little or no fines	31-50	Dense		
	coarse fraction passes No. 4 sieve	Sands with	SM	Silty sands, sand-silt mixtures	>50	Very Dense	9	
		Fines	SC	Clayey sands, sand-clay mixtures	Standard Penetration Test Density of Fine-Grained Soils			
			ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands	Penetration Resistance, N (blows/ft.)	Consistency	Unconfined Compressive Strength (Tons/ft	
	Silts an Liquid Limi		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	<2	Very Soft	<0.25	
Fine-Grained Soils		-	OL	Organic silts and organic silty clays of low plasticity	2-4	Soft	0.25-0.50	
50% or more passes No. 200 sieve			MH	Inorganic silts, micaceous or diatomaceous free sands or silts, elastic silts	4-8	Firm	0.50-1.00	
	Silts an Liquid Limit gr		СН	Inorganic clays of high plasticity, fat clays	8-15	Stiff	1.00-2.00	
			ОН	Organic clays of medium to high plasticity	15-30	Very Stiff	2.00-4.00	
Н	ighly Organic Soi	ils	PT	Peat, mucic & other highly organic soils	>30	Hard	>4.0	
U.S. Standar	d Sieve Sizes							
>12"	12" 3"	3/4" #4	#10	#40	#200			
Boulders	Cobbles	Gravel coarse fine	Sand coarse medium		fine	Silt	or Clay	
ριγ	MOISTURE COI Absence of moist, dust			MATERIAL QU		OTHER SY		

			MATERIAL GO		OTTIEROTIND	
	Dry	Absence of moist, dusty, dry to the touch	trace	0-5%	R Ring Sample	
	Slightly Damp	Below optimum moisture content for compaction	few	5-10%	S SPT Sample	
	Moist	Near optimum moisture content, will moisten the hand	little	10-25%	B Bulk Sample	
	Very Moist	Above optimum moisture content	some	25-45%	 Ground Water 	
	Wet	Visible free water, below water table	mostly	50-100%		

BASIC LOG FORMAT:

Group name, Group symbol, (grain size), color, moisture, consistency or relative density. Additional comments: odor, presence of roots, mica, gypsum, coarse particles, etc.

EXAMPLE:

SILTY SAND w/trace silt (SM-SP), Brown, loose to med. Dense, fine to medium grained, damp

UNIFIED SOIL CLASSIFICATION SYSTEM

TEST DRILLING EQUIPMENT & PROCEDURES

Description of Subsurface Exploration Methods

Drilling Equipment – Truck-mounted drill rigs powered with gasoline or diesel engines are used in advancing test borings. Drilling through soil or softer rock is performed with hollow-stem auger or continuous flight auger. Carbide insert teeth are normally used on bits to penetrate soft rock or very strongly cemented soils which require blasting or very heavy equipment for excavation. Where refusal is experienced in auger drilling, the holes are sometimes advanced with tricone gear bits and NX rods using water or air as a drilling fluid.

Sampling Procedures - Dynamically driven tube samples are usually obtained at selected intervals in the borings by the ASTM D1586 test procedure. In most cases, 2" outside diameter, 1 3/8" inside diameter, samplers are used to obtain the standard penetration resistance. "Undisturbed" samples of firmer soils are often obtained with 3" outside diameter samplers lined with 2.42" inside diameter brass rings. The driving energy is generally recorded as the number of blows of a 140-pound, 30-inch free fall drop hammer required to advance the samplers in 6-inch increments. These values are expressed in blows per foot on the boring logs. However, in stratified soils, driving resistance is sometimes recorded in 2- or 3-inch increments so that soil changes and the presence of scattered gravel or cemented layers can be readily detected and the realistic penetration values obtained for consideration in design. "Undisturbed" sampling of softer soils is sometimes performed with thin-walled Shelby tubes (ASTM D1587). Tube samples are labeled and placed in watertight containers to maintain field moisture contents for testing. When necessary for testing, larger bulk samples are taken from auger cuttings. Where samples of rock are required, they are obtained by NX diamond core drilling (ASTM D2113).

Boring Records - Drilling operations are directed by our field engineer or geologist who examines soil recovery and prepares boring logs. Soils are visually classified in accordance with the Unified Soil Classification System (ASTM D2487), with appropriate group symbols being shown on the logs.

Appendix B

	BORING NO.	SAMPLE DEPTH (ft)	ASTM D698		MOISTURE	DENSITY		ATTERBERG LIMITS		SWELL	CONSOL	% PASS		
LAB NO.			Density	Moisture	CONT. (%)	WET (pcf) DRY (pcf)		LL PL PI		(%)	TEST	#200 SIEVE	CLASSIFICATION	
6636	B-1	2.5	-		-			NLL	NPL	NP			18	Silty SAND (SM)
6637	B-1	5		-	12.0	123.9	110.6	-	-	-	-		-	Clayey SAND (SC)/SILTSTONE
6638	B-2	2.5		-	10.5	126.3	114.3	24	22	2	-		19	Silty SAND (SM)/SANDSTONE
6639	B-3	5			5.7	108.7	102.9		-	-			-	SANDSTONE
6640	B-3	15		-	10.1	118.3	107.5		-				-	SANDSTONE
6641	B-4	2.5			2.9	114.0	110.7						-	SANDSTONE
6642	B-4	10.0		-	12.8	117.7	104.4	-	-	-		-	-	SANDSTONE
1										Project			WLU Remote Facility Pond	
	GF	-0			SUMMARY OF SOIL TESTS			Job No.			182-3038			
					INC.	SUMMART OF SUL 12515				Location			San Juan County, NM	
'												Date of Explo	ration	6/15/2018

LABORATORY TESTING PROCEDURES

Consolidation Tests: One-dimensional consolidation tests are performed using "Floating-ring" type consolidometers. The test samples are approximately 2.5 inches in diameter and 1.0 inch high and are usually obtained from test borings using the dynamically-driven ring samplers. Test procedures are generally as outlined in ASTM D2435. Loads are applied in several increments to the upper surface of the test specimen and the resulting deformations are recorded at selected time intervals for each increment. Samples are normally loaded in the in-situ moisture conditions to loads which approximate the stresses which will be experienced by the soils after the project is completed. Samples are usually then submerged to determine the effect of increased moisture contents on the soils. Each load increment is applied until compression/expansion of the sample is essentially complete (normally movements of less than 0.0003 inches/hour). Porous stones are placed on the top and bottom surfaces of the samples to facilitate introduction of the moisture.

Expansion Tests: Tests are performed on either undisturbed or recompacted samples to evaluate the expansive potential of the soils. The test samples are approximately 2.5 inches in diameter and 1.0 inch high. Recompacted samples are typically remolded to densities and moisture contents that will simulate field compaction conditions. Surcharge loads normally simulate those which will be experienced by the soils in the field. Surcharge loads are maintained until the expansion is essentially complete.

Atterberg Limits/Maximum Density/Optimum Moisture Tests: These tests are performed in accordance with the prescribed ASTM test procedures.

Appendix C

Important Information about This Geotechnical-Engineering Report

Subsurface problems are a principal cause of construction delays, cost overruns, claims, and disputes.

While you cannot eliminate all such risks, you can manage them. The following information is provided to help.

The Geoprofessional Business Association (GBA) has prepared this advisory to help you - assumedly a client representative - interpret and apply this geotechnical-engineering report as effectively as possible. In that way, clients can benefit from a lowered exposure to the subsurface problems that, for decades, have been a principal cause of construction delays, cost overruns, claims, and disputes. If you have questions or want more information about any of the issues discussed below, contact your GBA-member geotechnical engineer. Active involvement in the Geoprofessional Business Association exposes geotechnical engineers to a wide array of risk-confrontation techniques that can be of genuine benefit for everyone involved with a construction project.

Geotechnical-Engineering Services Are Performed for Specific Purposes, Persons, and Projects

Geotechnical engineers structure their services to meet the specific needs of their clients. A geotechnical-engineering study conducted for a given civil engineer will not likely meet the needs of a civilworks constructor or even a different civil engineer. Because each geotechnical-engineering study is unique, each geotechnicalengineering report is unique, prepared *solely* for the client. *Those who rely on a geotechnical-engineering report prepared for a different client can be seriously misled*. No one except authorized client representatives should rely on this geotechnical-engineering report without first conferring with the geotechnical engineer who prepared it. *And no one – not even you – should apply this report for any purpose or project except the one originally contemplated*.

Read this Report in Full

Costly problems have occurred because those relying on a geotechnicalengineering report did not read it *in its entirety*. Do not rely on an executive summary. Do not read selected elements only. *Read this report in full*.

You Need to Inform Your Geotechnical Engineer about Change

Your geotechnical engineer considered unique, project-specific factors when designing the study behind this report and developing the confirmation-dependent recommendations the report conveys. A few typical factors include:

- the client's goals, objectives, budget, schedule, and risk-management preferences;
- the general nature of the structure involved, its size, configuration, and performance criteria;
- the structure's location and orientation on the site; and
- other planned or existing site improvements, such as retaining walls, access roads, parking lots, and underground utilities.

Typical changes that could erode the reliability of this report include those that affect:

- the site's size or shape;
- the function of the proposed structure, as when it's changed from a parking garage to an office building, or from a light-industrial plant to a refrigerated warehouse;
- the elevation, configuration, location, orientation, or weight of the proposed structure;
- the composition of the design team; or
- project ownership.

As a general rule, *always* inform your geotechnical engineer of project changes – even minor ones – and request an assessment of their impact. The geotechnical engineer who prepared this report cannot accept responsibility or liability for problems that arise because the geotechnical engineer was not informed about developments the engineer otherwise would have considered.

This Report May Not Be Reliable

Do not rely on this report if your geotechnical engineer prepared it:

- for a different client;
- for a different project;
- for a different site (that may or may not include all or a portion of the original site); or
- before important events occurred at the site or adjacent to it; e.g., man-made events like construction or environmental remediation, or natural events like floods, droughts, earthquakes, or groundwater fluctuations.

Note, too, that it could be unwise to rely on a geotechnical-engineering report whose reliability may have been affected by the passage of time, because of factors like changed subsurface conditions; new or modified codes, standards, or regulations; or new techniques or tools. *If your geotechnical engineer has not indicated an "apply-by" date on the report, ask what it should be*, and, in general, *if you are the least bit uncertain* about the continued reliability of this report, contact your geotechnical engineer before applying it. A minor amount of additional testing or analysis – if any is required at all – could prevent major problems.

Most of the "Findings" Related in This Report Are Professional Opinions

Before construction begins, geotechnical engineers explore a site's subsurface through various sampling and testing procedures. *Geotechnical engineers can observe actual subsurface conditions only at those specific locations where sampling and testing were performed.* The data derived from that sampling and testing were reviewed by your geotechnical engineer, who then applied professional judgment to form opinions about subsurface conditions throughout the site. Actual sitewide-subsurface conditions may differ – maybe significantly – from those indicated in this report. Confront that risk by retaining your geotechnical engineer to serve on the design team from project start to project finish, so the individual can provide informed guidance quickly, whenever needed.

This Report's Recommendations Are Confirmation-Dependent

The recommendations included in this report – including any options or alternatives – are confirmation-dependent. In other words, *they are not final*, because the geotechnical engineer who developed them relied heavily on judgment and opinion to do so. Your geotechnical engineer can finalize the recommendations *only after observing actual subsurface conditions* revealed during construction. If through observation your geotechnical engineer confirms that the conditions assumed to exist actually do exist, the recommendations can be relied upon, assuming no other changes have occurred. *The geotechnical engineer who prepared this report cannot assume responsibility or liability for confirmationdependent recommendations if you fail to retain that engineer to perform construction observation*.

This Report Could Be Misinterpreted

Other design professionals' misinterpretation of geotechnicalengineering reports has resulted in costly problems. Confront that risk by having your geotechnical engineer serve as a full-time member of the design team, to:

- confer with other design-team members,
- help develop specifications,
- review pertinent elements of other design professionals' plans and specifications, and
- be on hand quickly whenever geotechnical-engineering guidance is needed.

You should also confront the risk of constructors misinterpreting this report. Do so by retaining your geotechnical engineer to participate in prebid and preconstruction conferences and to perform construction observation.

Give Constructors a Complete Report and Guidance

Some owners and design professionals mistakenly believe they can shift unanticipated-subsurface-conditions liability to constructors by limiting the information they provide for bid preparation. To help prevent the costly, contentious problems this practice has caused, include the complete geotechnical-engineering report, along with any attachments or appendices, with your contract documents, *but be certain to note conspicuously that you've included the material for informational purposes only.* To avoid misunderstanding, you may also want to note that "informational purposes" means constructors have no right to rely on the interpretations, opinions, conclusions, or recommendations in the report, but they may rely on the factual data relative to the specific times, locations, and depths/elevations referenced. Be certain that constructors know they may learn about specific project requirements, including options selected from the report, *only* from the design drawings and specifications. Remind constructors that they may perform their own studies if they want to, and *be sure to allow enough time* to permit them to do so. Only then might you be in a position to give constructors the information available to you, while requiring them to at least share some of the financial responsibilities stemming from unanticipated conditions. Conducting prebid and preconstruction conferences can also be valuable in this respect.

Read Responsibility Provisions Closely

Some client representatives, design professionals, and constructors do not realize that geotechnical engineering is far less exact than other engineering disciplines. That lack of understanding has nurtured unrealistic expectations that have resulted in disappointments, delays, cost overruns, claims, and disputes. To confront that risk, geotechnical engineers commonly include explanatory provisions in their reports. Sometimes labeled "limitations," many of these provisions indicate where geotechnical engineers' responsibilities begin and end, to help others recognize their own responsibilities and risks. *Read these provisions closely*. Ask questions. Your geotechnical engineer should respond fully and frankly.

Geoenvironmental Concerns Are Not Covered

The personnel, equipment, and techniques used to perform an environmental study – e.g., a "phase-one" or "phase-two" environmental site assessment – differ significantly from those used to perform a geotechnical-engineering study. For that reason, a geotechnical-engineering report does not usually relate any environmental findings, conclusions, or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. *Unanticipated subsurface environmental problems have led to project failures*. If you have not yet obtained your own environmental information, ask your geotechnical consultant for risk-management guidance. As a general rule, *do not rely on an environmental report prepared for a different client, site, or project, or that is more than six months old.*

Obtain Professional Assistance to Deal with Moisture Infiltration and Mold

While your geotechnical engineer may have addressed groundwater, water infiltration, or similar issues in this report, none of the engineer's services were designed, conducted, or intended to prevent uncontrolled migration of moisture – including water vapor – from the soil through building slabs and walls and into the building interior, where it can cause mold growth and material-performance deficiencies. Accordingly, *proper implementation of the geotechnical engineer's recommendations will not of itself be sufficient to prevent moisture infiltration*. Confront the risk of moisture infiltration by including building-envelope or mold specialists on the design team. *Geotechnical engineers are not building envelope or mold specialists.*



Telephone: 301/565-2733 e-mail: info@geoprofessional.org www.geoprofessional.org

Copyright 2016 by Geoprofessional Business Association (GBA). Duplication, reproduction, or copying of this document, in whole or in part, by any means whatsoever, is strictly prohibited, except with GBA's specific written permission. Excerpting, quoting, or otherwise extracting wording from this document is permitted only with the express written permission of GBA, and only for purposes of scholarly research or book review. Only members of GBA may use this document or its wording as a complement to or as an element of a report of any kind. Any other firm, individual, or other entity that so uses this document without being a GBA member could be committing negligent