					DT/		
	-10 SUSPENSE	ENGINEER DB	LOGGED IN 7-1-1(TYPE NSL	APP NO. /	0/87	57.579
<u> </u>		ABC	OVE THIS LINE FOR DIVISION USE C	DNLY			<u>-</u>
		MEXICO OIL CO - Enginee 220 South St. Francis	ering Bureau -	SEAL .		Ap TR	$ach e^{(873)}$
	AD	MINISTRATIV			KLIST		6732
THIS CH		ORY FOR ALL ADMINISTRA					
	Acronyms:		CESSING AT THE DIVISI				
	[PC-Pool Con [WFX-] {	Commingling] [CT/ nmingling] [OLS - (Waterflood Expansio SWD-Salt Water Disp Enhanced Oil Recove	Dff-Lease Storage] n] [PMX-Pressu osal] [IPI-Injectio	[OLM-Off-Leas re Maintenance Ex on Pressure Incre	e Measure (pansion] ase]	ment]	-
1] TY	PE OF APPLIC	ATION - Check Tho	se Which Annly fo	r [A]			
	$\begin{bmatrix} A \end{bmatrix} \text{Loca} \\ & \boxtimes \\ & \swarrow \\ & \swarrow \\ & \mathbb{C} \\ \\ \hline \\ & \mathbb{C} \\ \\ & \mathbb{C} \\ \end{bmatrix} \\ \\ & \mathbb{C} \\ \\ & \mathbb{C} \\ \end{bmatrix} \\ \\ & \mathbb{C} \\ \\ & \mathbb{C} \\ \end{bmatrix} \\ \\ & \mathbb{C} \\ \\ &$	ation - Spacing Unit - NSL NSP <u>evised Bottom-Hole I</u> Only for [B] or [C] umingling - Storage -	Simultaneous Ded SD Location	ication	OLM	100 JUN	RECE
	[C] Injea	ction - Disposal - Pres	ssure Increase - Enl			2010 JUN 31 P 2:	RECEIVED OCD
					·		U.
2] NC	TIFICATION F	REQUIRED TO: - C Working, Royalty or			Not Apply	201	P
	[B]	Offset Operators, Lea	aseholders or Surfa	ce Owner		jų o	ECE
	[C]	Application is One W	Which Requires Pub	lished Legal Notic	e	• 1	
		Notification and/or C U.S. Bureau of Land Manageme				С ?:	CEIVED OC
	[E]	For all of the above,	Proof of Notificatio	on or Publication is	Attached,		B
	[F]	Waivers are Attached	1				

SUBMIT ACCURATE AND COMPLETE INFORMATION REQUIRED TO PROCESS THE TYPE [3] OF APPLICATION INDICATED ABOVE.

[4] **CERTIFICATION:** I hereby certify that the information submitted with this application for administrative approval is accurate and complete to the best of my knowledge. I also understand that no action will be taken on this application until the required information and notifications are submitted to the Division.

Note: Statement must be completed by an individual with managerial and/or supervisory capacity.

Michelle Hanson	Michelest	Landman	6/30/10
Print or Type Name	Signature	Title	Date
		Michelle hongen@eneehe	

Michelle.hanson@apachecorp.com e-mail Address

Application of Apache Corporation for administrative approval of an unorthodox well location:

40 acres – 1280' FNL & 467' FEL Section 1, Township 20 South, Range 36 East, NMPM Lea County, New Mexico

PRIMARY OBJECTIVES: Paddock

In support:

,

- 1. Apache Corporation (Apache) is the operator of the proposed J R Phillips #11 well (Exhibit 1).
- Pool rules that apply to the proposed location is the Monument; Paddock. The proposed unorthodox location encroaches on spacing unit 1H, which currently has one well producing from the aforementioned zone (Exhibit 1). The cumulative and daily production values are displayed on Exhibit 2.

ΑΡΙ					Cum thru 12-09	Daily
30025	Op.	Well	Loc	Pool	O/G/W	O/G/W
04134	Apache Corp	J R Phillips #5	A	Monument; Paddock	205 / 0 / 0	4/1/2
04134	Apache Corp	J R Phillips #5	Α	Monument; Abo	18 / 132 / 7	5/3/2
04134	Apache Corp	J R Phillips #5	A	Monument; McKee- Ellenburger	80 / 8,342 / 0	P&A'd
04136	Apache Corp	J R Phillips #7	H	Monument; Paddock	141 / 25 / 106	12 / 410 / 1,117
04136	Apache Corp	J R Phillips #7	Н	Monument; Abo	61 / 130 / 9	TA'd
04138	Apache Corp	J R Phillips #9	A	Monument; Paddock	113 / 143 / 388	13 / 14 / 40
04138	Apache Corp	J R Phillips #9	А	Eunice Monument; Grbg-San Andres	27 / 26 / 568	TA'd
				Monument;		
04138	Apache Corp	J R Phillips #9	А	Blinebry	3/0/0	TA'd
39148	Apache Corp	J R Phillips #10	A	Monument; Paddock	0/10/0	152 / 225 / 195
					MBO MMCFG MBW	BOPD MCFGPD BWPD

3. The proposed J R Phillips #11 unorthodox location of 1280' from north line and 467' from the east line is based upon drainage considerations.

Location and Drainage

The proposed JR Phillips #11 is a 20 acre infill location between existing Paddock producers. It is approximately equidistant from those wells and should encounter an undrained reservoir volume.

The following table provides drainage areas of the offset wells calcuated from SophiH taken off contoured isopach maps or from log calculations.

		21S 37E		SophiH	Area	EUR	EUR
Oper.	Well	Loc	Reservoir	ft	ac	MBO	MMCFG
Apache	J R Phillips #5	A	Paddock	7	39	205	0
Apache	J R Phillips #7	Н	Paddock	12.5	15	141	25
Apache	J R Phillips #9	A	Paddock	6	25	113	143
Apache	J R Phillips #10	A	Paddock	11	60	433	654


Reserves for the proposed location were calculated by averaging the offset drainage areas and SophiH and applying it to the new location. Any competitive drainage is shared between the proposed well and the existing offset wells. The results are as follows:


				SophiH	Area	EUR	EUR
Oper.	Well	Loc	Reservoir	ft	ac	MBO	MMCFG
Apache	J R Phillips #11	A	Paddock	10	8	57.7	57.7

4. Notice

The proposed **J R Phillips #11** only encroaches toward Apache operated Paddock wells. Further, Apache owns 100% leasehold interest, and revenue interest ownership is common, as to the Paddock, in the NE/4 of Section 1-T20S-R36E.

5. Approval of this application will afford the interest owners in these spacing units an opportunity to recover oil and gas which would not otherwise be recovered and will do so without violating correlative rights.





Brooks, David K., EMNRD

From:	Brooks, David K., EMNRD
Sent:	Tuesday, July 06, 2010 9:58 AM
То:	'Hanson, Michelle'
Subject:	JR Phillips #11; NSL Application

Dear Ms. Hanson

We have received the referenced application for the JR Phillips Well #11, proposed in the Paddock at 1280 FNL & 467 FEL, 1-20S-36E.

Previously, on 9-4-08, we issued Order NSL-5914, approving a NSL for the JR Phillips #11 well at 1310 feet FNL & FEL, 1-20S-36E, in the Paddock, Blinebry and Abo. Apparently that well was never drilled, as I do not find a well file for it.

Does the present request supersede that which was approved in 2008?

Sincerely

David K. Brooks Legal Examiner

Brooks, David K., EMNRD

From: Sent: To: Subject: Hanson, Michelle [Michelle.Hanson@apachecorp.com] Tuesday, July 06, 2010 10:21 AM Brooks, David K., EMNRD RE: JR Phillips #11; NSL Application

Hi David,

NSL-5914 was actually for the JR Phillips #10. Please see NSL Order No. 5914-B. It amended the Well Number.

However, I did submit a previous NSL application for the #11 well (was never approved), but that application located the well at 330' FEL which was too close to the SE corner of Unit Letter H (Sec 1). As a result, we re-staked this well to be 467' FEL to make it far enough away from the SE corner of Unit Letter H to not have to notify offset owners.

Michelle Hanson

Landman **Apache Corporation** 6120 S. Yale Ave., Suite 1500 Tulsa, OK 74136 (918) 491-4838 office (918) 491-4854 fax michelle.hanson@apachecorp.com

From: Brooks, David K., EMNRD [mailto:david.brooks@state.nm.us]
Sent: Tuesday, July 06, 2010 10:58 AM
To: Hanson, Michelle
Subject: JR Phillips #11; NSL Application

Dear Ms. Hanson

We have received the referenced application for the JR Phillips Well #11, proposed in the Paddock at 1280 FNL & 467 FEL, 1-20S-36E.

Previously, on 9-4-08, we issued Order NSL-5914, approving a NSL for the JR Phillips #11 well at 1310 feet FNL & FEL, 1-20S-36E, in the Paddock, Blinebry and Abo. Apparently that well was never drilled, as I do not find a well file for it.

Does the present request supersede that which was approved in 2008?

Sincerely

David K. Brooks Legal Examiner

Confidentiality Notice: This e-mail, including all attachments is for the sole use of the intended recipient(s) and may contain confidential and privileged information. Any unauthorized review, use, disclosure or distribution is prohibited unless specifically provided under the New Mexico Inspection of Public Records Act. If you are not the intended recipient, please contact the sender and destroy all copies of this message. -- This email has been scanned by the Sybari - Antigen Email System.