


AVALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

REPORT OF THE TECHNICAL COMMITTEE FOR THE

WORKING INTEREST OWNERS

VOLUME II - MAPS AND CROSS SECTIONS



EXXON COMPANY, USA

SOUTHWESTERN PRODUCTION DIVISION
RESERVOIR TECHNOLOGY GROUP

AUGUST, 1992

AVALON (DELAWARE) FIELD
Eddy County, New Mexico

REPORT OF THE TECHNICAL COMMITTEE
FOR THE WORKING INTEREST OWNERS

VOLUME II - TEXT AND EXHIBITS

With Contributions By:


G. G. Beuhler
T. W. Brannon
A. C. Brummert
D. L. Cantrell
J. M. Goodwin
F. M. Haynes
T. V. Kane
R. M. Stuart

August 1992

VOLUME II - MAPS ANDS CROSS SECTIONS

Map 1	Avalon (Delaware) Field Basemap
Map 2	Lower Cherry/Upper Brushy Canyon Top Reservoir (LCHT) Structure Map
Map 3	Top Bone Spring - Base Delaware (BSPG) Structure Map
Map 4	Lower Cherry/Upper Brushy Canyon Gross Thickness
Map 5	Upper Cherry Canyon - Top Reservoir (UCH-DLS) Structure Map
Map 6	Upper Cherry Canyon - Base Reservoir (UCHB) Structure Map
Map 7	Upper Cherry Canyon - Gross Thickness
Map 8	Lower Cherry/Upper Brushy Canyon - Net to Gross Ratio
Map 9	Lower Cherry/Upper Brushy Canyon - Net Thickness
Map 10	Lower Cherry/Upper Brushy Canyon - Average Porosity
Map 11	Lower Cherry/Upper Brushy Canyon - Porosity Thickness
Map 12	Lower Cherry/Upper Brushy Canyon - Average Water Saturation
Map 13	Lower Cherry/Upper Brushy Canyon - Hydrocarbon Porosity Thickness with Limits of Primary Production
Map 14	Lower Cherry/Upper Brushy Canyon - Top Reservoir (LCHT) Structure Map with Limits of Primary Production
Map 15	Upper Cherry Canyon - Net to Gross Ratio
Map 16	Upper Cherry Canyon - Net Thickness
Map 17	Upper Cherry Canyon - Average Porosity
Map 18	Upper Cherry Canyon - Porosity Thickness
Map 19	Upper Cherry Canyon - Average Water Saturation
Map 20	Upper Cherry Canyon - Hydrocarbon Porosity Thickness with Limits of Primary Production
Map 21	Upper Cherry Canyon - Top Reservoir (UCH-DLS) Structure Map with Limits of Primary Production
Map 22	Total Reservoir - Hydrocarbon Porosity Thickness
Map 23	Avalon Field Well-Tracts
North-South Structural Cross Section B1	
North-South Structural Cross Section 1	
Northwest-Southeast Structural Cross Section A2	
Northwest-Southeast Structural Cross Section 2	
Northwest-Southeast Structural Cross Section 3	
Northwest-Southeast Structural Cross Section A3	
Northwest-Southeast Structural Cross Section B3	
Northwest-Southeast Structural Cross Section 4	

AVALON (DELAWARE) FIELD BASEMAP



WELL STATUS SYMBOL LEGEND

- | | |
|---|--------------------------------|
|  | UNEQUIPPED |
|  | PRODUCING GAS WELL |
|  | SHUT IN OIL WELL |
|  | TEMPORARILY ABANDONED OIL WELL |
|  | ABANDONED OIL WELL |
|  | PRODUCING GAS WELL |
|  | TEMPORARILY ABANDONED GAS WELL |
|  | ABANDONED GAS WELL |
|  | ACTIVE INJECTION WELL |
|  | SALT WATER INJECTION WELL |
|  | SALT WATER DISPOSAL WELL |
|  | DRY HOLE |
|  | DRY HOLE, JUNKED AND ABANDONED |

Proposed Unit Outline

Map 1

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP

BASE MAP

AMALCO (DELAWARED FIELD
EDDY COUNTY, NEW MEXICO,
API REFINOS, WELLS AND NEW WELL NUMBERS
ARE ANNOTATED AT EACH WELL SPOT

PRODUCED BY AMALCO (DELAWARED FIELD)
AMALCO (DELAWARED FIELD) 1487

0 1000 2000 FEET

SCALE - 1000 FEET/INCH

D.L. CANTRELL

AUGUST 18, 1982

This is a detailed contour map of the Los Angeles area, showing elevation in feet. The map includes major roads like the 10 Freeway (I-5) and the 60 Freeway (I-10), and numerous labeled locations such as Los Angeles, Pasadena, and San Gabriel. Contour lines are labeled with values ranging from 200 to 6000 feet. The map is oriented with North at the top.

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED

COMMENT CODE LEGEND

Map 2

EXXON COMPANY USA

PRODUCTION DEPARTMENT - NORTHWESTERN DIVISION
RENEWABLE TECHNOLOGY GROUP - CRODACT


STRUCTURE (F7) MAP, DATUM = MSL

LIMBER CHERRY CANYON TOP
MALLON (DEADWAXED) FIELD
ECHO COUNTRY NEW HORIZON
PACIFIC SLOPE AND RAINBOW CANYON
HILLTOP
SANDY CREEK
SOUTH-SEEDED EIGHTHORN

0 1000 2000 FEET

TERRAZZO, D. DONNELLY, WYOMING JULY 29, 1986

TOP BONE SPRING - Base Delaware (BSPG)



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED

NOTE: WELL SYMBOLS ARE PLACED AT THE WELL HEAD LOCATION FOR CONVENTIONAL, SMALL SYMBOLS ARE USED FOR UNUSUAL WELL HEAD LOCATIONS.

COMMENT CODE LEGEND

NA : PICK NOT AVAILABLE

Map 3

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHEASTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURE (FT) MAP, DATUM = MSL

BONE SPRINGS TOP

ANCON OIL FIELD

EDDY COUNTY, NEW MEXICO

PRODUCTION DEPARTMENT - SOUTHEASTERN DIVISION


RESERVOIR TECHNOLOGY GROUP - GEOLOGY

SCALE: 1:100,000

DATE: 10/1/82

LOWER CHERRY / UPPER BRUSHY CANYON

Gross Thickness



WELL STATUS SYMBOL LEGEND


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CORRELATION. SMALL SYMBOLS REFLECT WELLS NOT USED IN CORRELATING THIS MAP.

Map 4

EXXON COMPANY USA	
PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION	
RESERVOIR TECHNOLOGY GROUP - GEOLOGY	
TOTAL GROSS THICKNESS MAP	
ANALYSIS OF ZONES LEFT FROM BARS	
ANALYSIS (DETAILED) FIELD	
EDDY COUNTY, NEW MEXICO	
ANALYSIS: WELLS, THICKNESS (FT)	
PRODUCTION: WELLS, THICKNESS (FT)	
1000	
2000	
3000	
4000	
5000	
6000	
7000	
8000	
9000	
10000	
11000	
12000	
13000	
14000	
15000	
16000	
17000	
18000	
19000	
20000	
21000	
22000	
23000	
24000	
25000	
26000	
27000	
28000	
29000	
30000	
31000	
32000	
33000	
34000	
35000	
36000	
37000	
38000	
39000	
40000	
41000	
42000	
43000	
44000	
45000	
46000	
47000	
48000	
49000	
50000	
51000	
52000	
53000	
54000	
55000	
56000	
57000	
58000	
59000	
60000	
61000	
62000	
63000	
64000	
65000	
66000	
67000	
68000	
69000	
70000	
71000	
72000	
73000	
74000	
75000	
76000	
77000	
78000	
79000	
80000	
81000	
82000	
83000	
84000	
85000	
86000	
87000	
88000	
89000	
90000	
91000	
92000	
93000	
94000	
95000	
96000	
97000	
98000	
99000	
100000	
101000	
102000	
103000	
104000	
105000	
106000	
107000	
108000	
109000	
110000	
111000	
112000	
113000	
114000	
115000	
116000	
117000	
118000	
119000	
120000	
121000	
122000	
123000	
124000	
125000	
126000	
127000	
128000	
129000	
130000	
131000	
132000	
133000	
134000	
135000	
136000	
137000	
138000	
139000	
140000	
141000	
142000	
143000	
144000	
145000	
146000	
147000	
148000	
149000	
150000	
151000	
152000	
153000	
154000	
155000	
156000	
157000	
158000	
159000	
160000	
161000	
162000	
163000	
164000	
165000	
166000	
167000	
168000	
169000	
170000	
171000	
172000	
173000	
174000	
175000	
176000	
177000	
178000	
179000	
180000	
181000	
182000	
183000	
184000	
185000	
186000	
187000	
188000	
189000	
190000	
191000	
192000	
193000	
194000	
195000	
196000	
197000	
198000	
199000	
200000	
201000	
202000	
203000	
204000	
205000	
206000	
207000	
208000	
209000	
210000	
211000	
212000	
213000	
214000	
215000	
216000	
217000	
218000	
219000	
220000	
221000	
222000	
223000	
224000	
225000	
226000	
227000	
228000	
229000	
230000	
231000	
232000	
233000	
234000	
235000	
236000	
237000	
238000	
239000	
240000	
241000	
242000	
243000	
244000	
245000	
246000	
247000	
248000	
249000	
250000	
251000	
252000	
253000	
254000	
255000	
256000	
257000	
258000	
259000	
260000	
261000	
262000	
263000	
264000	
265000	
266000	
267000	
268000	
269000	
270000	
271000	
272000	
273000	
274000	
275000	
276000	
277000	
278000	
279000	
280000	
281000	
282000	
283000	
284000	
285000	
286000	
287000	
288000	
289000	
290000	
291000	
292000	
293000	
294000	
295000	
296000	
297000	
298000	
299000	
300000	
301000	
302000	
303000	
304000	
305000	
306000	
307000	
308000	
309000	
310000	
311000	
312000	
313000	
314000	
315000	
316000	
317000	
318000	
319000	
320000	
321000	
322000	
323000	
324000	
325000	
326000	
327000	
328000	
329000	
330000	
331000	
332000	
333000	
334000	
335000	
336000	
337000	
338000	
339000	
340000	
341000	
342000	
343000	
344000	
345000	
346000	
347000	
348000	
349000	
350000	
351000	
352000	
353000	
354000	
355000	
356000	
357000	
358000	
359000	
360000	
361000	
362000	
363000	
364000	
365000	
366000	
367000	
368000	
369000	
370000	
371000	
372000	
373000	
374000	
375000	
376000	
377000	
378000	
379000	
380000	
381000	
382000	
383000	
384000	
385000	
386000	
387000	
388000	
389000	
390000	
391000	
392000	
393000	
394000	
395000	
396000	
397000	
398000	
399000	
400000	
401000	
402000	
403000	
404000	
405000	
406000	
407000	
408000	
409000	
410000	
411000	
412000	
413000	
414000	
415000	
416000	
417000	
418000	
419000	
420000	
421000	
422000	
423000	
424000	
425000	
426000	
427000	
428000	
429000	
430000	
431000	
432000	
433000	
434000	
435000	
436000	
437000	
438000	
439000	
440000	
441000	
442000	
443000	
444000	
445000	
446000	
447000	
448000	
449000	
450000	
451000	
452000	
453000	
454000	
455000	
456000	
457000	
458000	
459000	
460000	
461000	
462000	
463000	
464000	
465000	
466000	
467000	
468000	
469000	
470000	
471000	
472000	
473000	
474000	
475000	
476000	
477000	
478000	
479000	
480000	
481000	
482000	
483000	
484000	
485000	
486000	
487000	
488000	
489000	
490000	
491000	
492000	
493000	
494000	
495000	
496000	
497000	
498000	
499000	
500000	
501000	
502000	
503000	
504000	
505000	
506000	
507000	
508000	
509000	
510000	
511000	

UPPER CHERRY CANYON - Top Reservoir (UCH-DLS)



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR COMPARISON. SMALL SYMBOLS REPRESENT WELLS NOT USED IN OPERATIONS THIS MAP.

COMMENT CODE LEGEND

EROD : PICK MISSING DUE TO EROSION, DEPTH OF UNCONFORMITY POSTED
NA : PICK NOT AVAILABLE

Map 5

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURE (FT) MAP, DATUM = MSL

UPPER CHERRY CANYON DOWNSIDE SURFACE

OUTCROPS AND ERODED AREAS ARE BASE OF COAT SEEP REEF

AMALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

1000 2000 3000

1:25,000

SCALE=1000 FEET/INCH

DATE: 2/28/82


0 1000 2000 3000

1:25,000

SCALE=1000 FEET/INCH

DATE: 2/28/82

UPPER CHERRY CANYON - Base Reservoir (UCHB)



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR COMPARISON. SMALL SYMBOLS NOT LIST WILL NOT BE USED IN OILFIELD THIS MAP.

COMMENT CODE LEGEND

NA : PICK NOT AVAILABLE

Map 6

EXXON COMPANY USA
PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURE (FT) MAP, DATUM = MSL
UPPER CHERRY CANYON BASE
ANALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO
PRODUCTION GEOLOGIST: J. L. BROWN
DATE: 1982
SCALE: 1000 FEET/INCH
BY: J. L. BROWN, D. C. BROWN, T. V. WALKER
JULY 28, 1982


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAMINATING. SMALL SYMBOLS REFLECT WELLS NOT USED IN OPERATING THIS MAP.

EXXON COMPANY USA PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION RESERVOIR TECHNOLOGY GROUP - GEOLOGY	
TOTAL GROSS THICKNESS MAP ANALOGATION OF ZONES FROM OILS MILTON DELANEY FIELD EDDY COUNTY, NEW MEXICO ANNOTATIONS: FIELD THICKNESS (FT) FROM PRODUCTION DATA (SEE REQUESTED BY)	
0	1000
FEET	SCALE = 25 CM = 400 FT
THE PROPERTY OF: CONTROL, V. NAME DATE: 28, 1982	

LOWER CHERRY / UPPER BRUSHY CANYON

Net To Gross Ratio



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED
- ✱ ABANDONED LOCATION


NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN ORIGINATING THIS MAP.

Map 8

[illegible]

LOWER CHERRY / UPPER BRUSHY CANYON

Net Thickness



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- ◐ TEMPORARILY ABANDONED OIL WELL
- ✖ ABANDONED OIL WELL
- ✧ PRODUCING GAS WELL
- ✧ TEMPORARILY ABANDONED GAS WELL
- ✖ ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- ✧ DRY HOLE
- ✧ DRY HOLE, JUNKED AND ABANDONED
- ✖ ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN OREGONIAN THIS MAP.

Map 9

[illegible]


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- ◌ TEMPORARILY ABANDONED OIL WELL
- ✂ ABANDONED OIL WELL
- ☼ PRODUCING GAS WELL
- ☼ TEMPORARILY ABANDONED GAS WELL
- ✂ ACTIVE INJECTION WELL
- ☼ SALT WATER INJECTION WELL
- ☼ SALT WATER DISPOSAL WELL
- ☼ DRY HOLE
- ✂ DRY HOLE, JUNKED AND ABANDONED
- ✂ ABANDONED LOCATION

Map 10

[illegible]

LOWER CHERRY/UPPER BRUSHY CANYON

Porosity Thickness



- WELL STATUS SYMBOL LEGEND**
- PRODUCING OIL WELL
 - SHUT IN OIL WELL
 - TEMPORARILY ABANDONED OIL WELL
 - ABANDONED OIL WELL
 - PRODUCING GAS WELL
 - TEMPORARILY ABANDONED GAS WELL
 - ACTIVE INJECTION WELL
 - SALT WATER INJECTION WELL
 - SALT WATER DISPOSAL WELL
 - DRY HOLE
 - DRY HOLE, JUNKED AND ABANDONED
 - ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR COMPARISON. SMALL SYMBOLS REPRESENT WELLS NOT USED IN DETERMINING THIS MAP.


Map 11

EXXON COMPANY USA
PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOSCIENCE

TOTAL NET POROSITY THICKNESS MAP
LOWER CHERRY - 10' AND DEEPER - 72' SHOWN - 250'
UPPER BRUSHY - 11' AND DEEPER - 72' SHOWN - 250'
ANALYST: J. J. DUNCAN, JR.
APPROVED: J. J. DUNCAN, JR.
DATE: 10/1/82
SCALE: 1:50,000 (1" = 1/2 MI.)
DRAWN: J. J. DUNCAN, JR.
CHECKED: J. J. DUNCAN, JR.
DATE: 10/1/82


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DEEP HOLE, JUNKED AND ABANDONED
- ✱ ABANDONED LOCATION

Map 12



LOWER CHERRY / UPPER BRUSHY CANYON

Hydrocarbon Porosity Thickness



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- ABANDONED LOCATION

NOTE: ABOVE STABOLDS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAMINATING. SMALL STABOLDS REFLECT WELLS NOT USED IN OREZING THIS MAP.

Map 13

[illegible]


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED

COMMENT CODE LEGEND

Map 14

EXXON COMPANY USA	PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION <u>RESERVOIR TECHNOLOGY GROUP - GEOLOGY</u>	STRUCTURE (FT) MAP, DATUM = MSL	LOWER CHERRY CANYON TOP ALAYMON (DELAWARE) FIELD EDDY COUNTY, NEW MEXICO RECORDS SECTION, ALBUQUERQUE (NEW MEXICO) 1788
	0 1000 2000 FEET	0 1000 2000 FEET	0 1000 2000 FEET
DATE: 1982	DATE: 1982	DATE: 1982	DATE: 1982

UPPER CHERRY CANYON - Net To Gross Ratio




WELL STATUS SYMBOL LEGEND


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN OREGONIAN THIS MAP.

Map 15



UPPER CHERRY CANYON - Net Thickness



WELL STATUS SYMBOL LEGEND


- | | |
|---|--------------------------------|
| ● | UNDEFINED |
| ● | PRODUCING OIL WELL |
| ● | SHUT IN OIL WELL |
| ● | TEMPORARILY ABANDONED OIL WELL |
| ● | ABANDONED OIL WELL |
| ● | PRODUCING GAS WELL |
| ● | TEMPORARILY ABANDONED GAS WELL |
| ● | ACTIVE INJECTION WELL |
| ● | SALT WATER INJECTION WELL |
| ● | SALT WATER DISPOSAL WELL |
| ● | DRY HOLE |
| ● | DRY HOLE, JUNKED AND ABANDONED |
| ● | ABANDONED LOCATION |

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTOURING. SMALL SYMBOLS REFLECT WELLS NOT USED IN CREATING THIS MAP.

Map 16

[illegible]

UPPER CHERRY CANYON - Average Porosity



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED
- ✱ ABANDONED LOCATION


NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTINUING. SMALL SYMBOLS REFLECT WELLS NOT USED IN CREATING THIS MAP.

Map 17

[illegible]

UPPER CHERRY CANYON - Porosity Thickness

*Top of Upper Cherry Res. to
the top of the lower
Cherry Canyon
Res.*



- WELL STATUS SYMBOL LEGEND**
- UNDEFINED
 - PRODUCING OIL WELL
 - SHUT IN OIL WELL
 - TEMPORARILY ABANDONED OIL WELL
 - ABANDONED OIL WELL
 - PRODUCING GAS WELL
 - TEMPORARILY ABANDONED GAS WELL
 - ACTIVE INJECTION WELL
 - SALT WATER INJECTION WELL
 - SALT WATER DISPOSAL WELL
 - DRY HOLE
 - DRY HOLE, JUNKED AND ABANDONED
 - ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN OILFIELD THIS MAP.

Map 18

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

TOTAL NET POROSITY THICKNESS MAP

UPPER CHERRY RES. - 10' AND DEEPER - 75' SURVEY - 200

UPPER CHERRY RES. - 10' AND DEEPER - 75' SURVEY - 200

APPROXIMATION OF 2000' COAL COAL

ANALYST (OILFIELD) FIELD

EDDY COUNTY, NEW MEXICO

ANALYSTS WELLS, FIELD

CNT-4, CNT-400

SCALE=1000 FEET/INCH


JUNE 22, 1982

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR COUNTOURING. SMALL SYMBOLS REFLECT WELLS NOT USED IN CREATING THIS MAP.

[illegible]

UPPER CHERRY CANYON - Hydrocarbon Porosity Thickness



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- JUNKED AND ABANDONED
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTINUOUS. SMALL SYMBOLS REFLECT WELLS NOT USED IN OREGONIAN TMS MAP.

LIMITS OF PRIMARY PRODUCTION

Map 20


EXXON COMPANY USA
PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOLOGY

TOTAL NET RESERVOIR HYDROCARBON POROSITY THICKNESS AT RESY COND MAP

1000 2000
FEET SCALE=1000 FEET/INCH

CHIT=2 CHIT=400
JULY 28, 1992

UPPER CHERRY CANYON - Top Reservoir (UCH-DLS)



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ★ PRODUCING GAS WELL
- ★ TEMPORARILY ABANDONED GAS WELL
- ★ ACTIVE INJECTION WELL
- ★ SALT WATER INJECTION WELL
- ★ SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED

NOTE: SOME SYMBOLS ARE ADOPTED FROM THE U.S. GEOLOGICAL SURVEY. FOR CONVENTION, SMALL SYMBOLS ARE USED IN THIS MAP. USED IN OIL FIELD MAPS.

COMMENT CODE LEGEND

EROD : PICK MISSING DUE TO EROSION, DEPTH OF UNCONFORMITY POSTED
NA : PICK NOT AVAILABLE

LIMITS OF PRIMARY PRODUCTION

Map 21

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGIST GROUP - GEOLOGIST

STRUCTURE (F) MAP, DATUM = MSL

UPPER CHERRY CANYON DOWNSIDE SURFACE

CONTOURS INSIDE ENDED AREAS ARE BASE OF GOM SEEP REEF


ANALON (OILWATER) FIELD

EDDY COUNTY, NEW MEXICO

REVISIONS: 1.000 2.000 3.000 4.000 5.000 6.000 7.000 8.000 9.000 10.000

DATE: 23, 1982

TOTAL RESERVOIR - Hydrocarbon Porosity Thickness



- WELL STATUS SYMBOL LEGEND**
- PRODUCING OIL WELL
 - SHUT IN OIL WELL
 - TEMPORARILY ABANDONED OIL WELL
 - ABANDONED OIL WELL
 - PRODUCING GAS WELL
 - TEMPORARILY ABANDONED GAS WELL
 - ACTIVE INJECTION WELL
 - SALT WATER INJECTION WELL
 - SALT WATER DISPOSAL WELL
 - DRY HOLE
 - DRY HOLE, JUNKED AND ABANDONED
 - ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTROLLING. SMALL SYMBOLS REFLECT WELLS NOT USED IN OILFIELD 788 MAP.

Map 22

EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY


TOTAL NET RESERVOIR HYDROCARBON POROSITY THICKNESS AT NEW COND MAP

1000 2000 3000

1" = 1000 FEET/INCH

DATE: 7/1/82

AVALON FIELD WELL-TRACTS



LEGEND

- TOP LINE = OPERATOR
- SECOND LINE = WELL TRACT NUMBER
- THIRD LINE = TOWNSHIP
- FOURTH LINE = RANGE
- FIFTH LINE = SECTION NUMBER
- SIXTH LINE = QUARTER-QUARTER OR LOT NUMBER

Map 23

EXXON COMPANY USA

PRODUCTION DEVELOPMENT - SOUTHERNEASTERN DIVISION

RESERVE/RE-TECHNOLOGY GROUP - CAROLINA

PROPOSED UNIT AREA

SHOWING 140-ACRE WELL-TRACTS

AVAILON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

PROBABLE/ALREADY DRILLED/PLANNED 311

1000 2000 FEET

SCALE=1000 FEET/INCH

GRIND=400

MADE BY: J. L. CANTRELL, V. J. WHITE

DATE: 10, 1982

NORTH AVALON (DELAWARE) FIELD STRUCTURAL CROSS SECTION B1 SOUTH

GWA1



OPERATOR: MMJ PRODUCING LEASE: STATE "GWA"
WELLNO: 1
STWCO: 30015 REFNO: 234430

GWA2

OPERATOR: MMJ PRODUCING LEASE: STATE "GWA"
WELLNO: 2
STWCO: 30015 REFNO: 247480

MS3

OPERATOR: MOBIL PROD. TX & NM LEASE: BURTON FLAT "SEC 6" ST
WELLNO: 3
STWCO: 30015 REFNO: 247510



EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURAL CROSS SECTION B1

AYALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO
GAMMA RAY SHADED ABOVE 75 API UNITS

PICK COMMENT LEGEND

EROD : PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN
ONLAP: PICK MISSING DUE TO ONLAP, ONLY ONLAPPED SURFACE SHOWN
GENZ : PICK ESTIMATED FROM GRID MODEL, BECAUSE NOT ORIGINALLY PICKED

PROJ. NO. 17726
VERTICAL SCALE = 250 FEET/INCH
HORIZONTAL SCALE = 1500 FEET/INCH

TW BRAUNTON, DL CANTRELL, IV KANE


AUGUST 18, 1992

513

C15

MST

TA



PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOLOGY

PICK COMMENT LEGEND

PICK COMMENT LEGEND

EROD : PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN
ONLAP: PICK MISSING DUE TO ONLAP, ONLY ONLAPPED SURFACE SHOWN
GENZ : PICK ESTIMATED FROM GRID MODEL BECAUSE NOT ORIGINALLY PICKED

PRODMODEL/MAN/DEVELOP APL (QXSECT) 17:10
VERTICAL SCALE = 250 FEET/INCH
HORIZONTAL SCALE = 1500 FEET/INCH

TW BRANNON, DL CANTRELL, TV KANE	AUGUST 18, 1992
----------------------------------	-----------------

NORTHWEST

AVALON (DELAWARE) FIELD STRUCTURAL CROSS SECTION A2

SOUTHEAST

ZG1

OPERATOR: YATES PET LEASE: CITRIL "ZG"
WELLNO: 1
STAGE: 30015 REFNO: 247940



C8



OPERATOR: EXXON CORP LEASE: YATES "C" FEDERAL
WELLNO: 8
STAGE: 30018 REFNO: 243380

C10

OPERATOR: EXXON CORP LEASE: YATES "C" FEDERAL
WELLNO: 10
STAGE: 30019 REFNO: 243780

C11

OPERATOR: EXXON CORP LEASE: YATES "C" FEDERAL
WELLNO: 11
STAGE: 30018 REFNO: 243770



EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURAL CROSS SECTION A2

AVALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

GAMMA RAY SHOWN ABOVE 73 API UNITS

PICK COMMENT LEGEND

EROD - PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN

ONLAP - PICK MISSING DUE TO ONLAP, ONLY ONLAPED SURFACE SHOWN

GENZ - PICK ESTIMATED FROM GRID MODEL BECAUSE NOT ORIGINALLY PICKED

VERICAL SCALE = 250 FEET/INCH

HORIZONTAL SCALE = 1500 FEET/INCH



TW BRANNON, DL CANTRELL, TV KANE

AUGUST 18, 1992

NORTHWEST

AVALON (DELAWARE) FIELD STRUCTURAL CROSS SECTION 2

SOUTHEAST



EXXON COMPANY USA

 PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
 RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURAL CROSS SECTION 2

 AVALON (DELAWARE) FIELD
 EDDY COUNTY, NEW MEXICO
 GAMMA RAY SHADED ABOVE 75 API UNITS

PICK COMMENT LEGEND

 EROD: PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN
 ONLAP: PICK MISSING DUE TO ONLAP, ONLY ONLAPPED SURFACE SHOWN
 GENZ: PICK ESTIMATED FROM GRID MODEL BECAUSE NOT ORIGINALLY PICKED

 PROGRAM: AVALON/DEVELOP/PROJECTS/17/14
 VERTICAL SCALE = 250 FEET/INCH
 HORIZONTAL SCALE = 1500 FEET/INCH

 TW BRANNON, DL CANTRELL, TV KANE
 AUGUST 18, 1992

NORTHWEST

AVALON (DELAWARE) FIELD STRUCTURAL CROSS SECTION 3

SOUTHEAST

WM4

OPERATOR: VATES PET. LEASE: STONEMAN-WINSTATE
WELLNO: 4
STOCK: 20015 REFNO: 245400

C7

OPERATOR: EXCON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 17
STOCK: 20015 REFNO: 245240

C7

OPERATOR: EXCON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 17
STOCK: 20015 REFNO: 245300

C12



OPERATOR: EXCON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 12
STOCK: 20015 REFNO: 245720

HS4

OPERATOR: WELLS PET. LEASE: HONOLD "W" STATE
WELLNO: 4
STOCK: 20015 REFNO: 244720

C35

OPERATOR: EXCON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 35
STOCK: 20015 REFNO: 245800



EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURAL CROSS SECTION 3

AVALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

GAMMA RAY SHAPED ABOVE 75 API UNITS

PICK CONTOUR LINES

PRODUCTION TEST DATA SHOWN

ONLY PICK MISSING DUE TO CRASH. ONLY OUTLINED SURFACE SHOWN

GEN: PICK ESTIMATED FROM GRD MODE BECAUSE NOT ORIGINALLY PICKED

PROLOG: 1000, 1000, 1000, 1000, 1000, 1000, 1000, 1000, 1000, 1000

VERTICAL SCALE = 250 FEET/INCH

HORIZONTAL SCALE = 1500 FEET/INCH

TM BRANNON, DL CANTRELL, TV KANE

AUGUST 18, 1992

NORTHWEST

AVALON (DELAWARE) FIELD STRUCTURAL CROSS SECTION A3

SOUTHEAST

WM6

OPERATOR: VATES PET. LEASE: STONEWALL-TW-SW-1E
WELLNO: 6
STWOC: 30015 REFNO: 246370

WM3

OPERATOR: VATES PET. LEASE: STONEWALL-TW-SW-1E
WELLNO: 3
STWOC: 30015 REFNO: 244870

C3

OPERATOR: EXXON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 3
STWOC: 30015 REFNO: 241840

C36



OPERATOR: EXXON CORP. LEASE: VATES FEDERAL "C"
WELLNO: 36
STWOC: 30015 REFNO: 263700

C9

OPERATOR: EXXON CORP. LEASE: VATES "C" FEDERAL
WELLNO: 9
STWOC: 30015 REFNO: 243370

HS3

OPERATOR: MESA PET. LEASE: HONONO TW-SW-1E
WELLNO: 3
STWOC: 30015 REFNO: 244000



EXXON COMPANY USA

PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION

RESERVOIR TECHNOLOGY GROUP - GEOLOGY

STRUCTURAL CROSS SECTION A3

AVALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

QUANTA RAY SHOWN ABOVE 75 API UNITS

PICK COMMENT LEGEND

ERRO: PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN

ONLAP: PICK MISSING DUE TO ONLAP, ONLY ONLAPPED SURFACE SHOWN

GENV: PICK ESTIMATED FROM GENO MODEL BECAUSE NOT ORIGINALLY PICKED


VERTICAL SCALE = 250 FEET/INCH

HORIZONTAL SCALE = 1500 FEET/INCH

TM BRAUNHOL, DL CANTRELL, TV KAME

AUGUST 18, 1992

SOUTHEAST



EXXON COMPANY USA
PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION
RESERVOIR TECHNOLOGY GROUP - GEOLOGY


LEO J. COONIN, NEW MEXICO
GAMMA RAY SHADED ABOVE 75 API UNITS
POK COMMENT LEGEND

EROD : PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN
ONLAP: PICK MISSING DUE TO ONLAP, ONLY ONLAPPED SURFACE SHOWN
GEN2 : PICK ESTIMATED FROM GRID MODEL, BECAUSE NOT ORIGINALLY PICKED

VERTICAL SCALE = 250 FEET/INCH

HORIZONTAL SCALE = 1500 FEET/INCH	
TW BRANNON, DL CANTRELL, TV KANE	AUGUST 18, 1992

SOUTHEAST



EXXON COMPANY USA PRODUCTION DEPARTMENT - SOUTHWESTERN DIVISION RESERVE/IR TECHNOLOGY GROUP - GEOLOGY STRUCTURAL CROSS SECTION 4 MAJON (DEWAMED FIELD EDDY COUNTY, NEW MEXICO CANADA RLY SHARED ABOVE 75 AD UIMS PICK CONTACT LEGEND BRD - PICK MISSING DUE TO EROSION, ONLY ERODED SURFACE SHOWN ON-PAV PICK MISSING DUE TO OULU, ONL, ON-PAVED SURFACE SHOWN GRNT - PICK ESTIMATED FROM GROUND BECAUSE NOT ORIGINALLY PICKED POSSIBLE SOURCE AND DATING OF THE CONTACTS 1 mi VERTICAL SCALE = .250 FEET/INCH HORIZONTAL SCALE = 1500 FEET/INCH JR BRANNON, DL. CONTROL, TV NAME AUGUST 19, 1982	
--	--

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

NO. OF COPIES RECEIVED	6
DISTRIBUTION	
SANTA FE	/
FILE	/
U.S.G.S.	2
LAND OFFICE	/
OPERATOR	/

NEW MEXICO OIL CONSERVATION COMMISSION

DEC 22 1976

O. C. C.
ARTESIA, OFFICE

30-015-2200

Form C-101
Revised 1-1-65

5A. Indicate Type of Lease
STATE ☒ FEE ☐
5. State Oil & Gas Lease No.
K-5115

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work		7. Unit Agreement Name	
b. Type of Well DRILL ☒ DEEPEN ☐ PLUG BACK ☐ OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐		8. Farm or Lease Name	
2. Name of Operator		Stonewall "EP" S	
Yates Petroleum Corporation ✓		9. Well No.	
3. Address of Operator		2	
207 South Fourth Street - Artesia, NM 88210		10. Field and Loc., or Wildcat	
4. Location of Well		Undesignated	
UNIT LETTER N LOCATED 660 FEET FROM THE South LINE		12. County	
AND 1980 FEET FROM THE West LINE OF SEC. 19 TWP. 20S RSP. 28E N40PM		Eddy	
BEFORE THE OIL CONSERVATION DIVISION Case No. 11298 Exhibit No. 5 Submitted By: PREMIER OIL & GAS INC. Hearing Date: June 29, 1995		19A. Formation	
		Morrow	
21. Elevations (Show whether DT, RT, etc.)		20. Rotary or C.T.	
3300' GR		Rotary	
21A. Kind & Status Plug, Bond		22. Approx. Date Work will start	
Blanket		December 26, 19	
21B. Drilling Contractor			
Moran Drilling Co.			

PROPOSED CASING AND CEMENT PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
17½"	13-3/8"	48#	600'	400	circulate
12½ & 11"	8-5/8"	24#	2900'	1000	circulate
7-7/8"	5½ or 4½"	17.20# or 11.6-13.5#	11500'	300	*

Propose to drill an 11500' well and test the Morrow & intermediate horizons. Approx. 600' of surface casing will be set & cemented to surface. Approx. 2900' of intermediate casing will be set & cemented to surface. Production casing will be 5½" or 4½", and will be cemented with some 600' of cement covering the pay.

Mud Program: FW Gel & LCM to 600', fresh water & LCM to 8500'. Brine to 10700'. Flosal-driskpak-Brine mud to TD.

BOP Program: BOP's and hydril will be installed on 8-5/8" casing & tested daily.

Gas not committed.

APPROVAL VALID
FOR 30 DAYS UNLESS
EXPIRES 3-23-77

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAMS IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW PRODUCTIVE ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

Signed Eddie L. Kuchel Title Engineer Date 12-21-76

(This space for State Use)

APPROVED BY M. A. Grassie TITLE SUPERVISOR, DISTRICT II DATE DEC 23 1976

CONDITIONS OF APPROVAL, IF ANY:

* 100% completion

**NEW MEXICO OIL CONSERVATION COMMISSION
WELL LOCATION AND ACREAGE DEDICATION PLAT**

Form O-111
Supersedes O-1
Effective 1-1-65

All distances must be from the outer boundaries of the Section.


Operator YATES PETROLEUM Corporation			Lessee STONEWALL "E.P." STATE		Well No. 2
Unit Letter N	Section 19	Township 20 S.	Range 28 E.	County Eddy	
Actual Location Location of Well: 660 feet from this South line and 1980 feet from the West line					
Ground Level Elev. 3300	Estimated Elevation Morrow	Pool Undesignated	Estimated Acreage 320 3/4		

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☐ Yes ☐ No If answer is "yes," type of consolidation _____

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) _____

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Eddie M. Mahfood
Name

Eddie M. Mahfood

Position
Engineer

Company
Yates Petroleum Corp.

Date
12-21-76

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

Date Surveyed
Aug. 28, 1976

Registered Professional Engineer and/or Land Surveyor

Herschel Jones
3640

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

NO. OF COPIES RECEIVED	6
DISTRIBUTION	
SANTA FE	/
FILE	/
U.S.G.S.	2
LAND OFFICE	/
OPERATOR	/

RECEIVED
NEW MEXICO OIL CONSERVATION COMMISSION

DEC 22 1976

O. C. C.
ARTESIA, OFFICE

30-015-270
Form C-101
Revised 1-4-65

5A. Indicate Type of Lease
STATE ☒ FEDERAL ☐
5. State Oil & Gas Lease No.
K-5115

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work DRILL ☒ DEEPEN ☐ PLUG BACK ☐		7. Unit Agreement Name
b. Type of Well OIL WELL ☐ GAS WELL ☒ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐		8. Firm or Lease Name Stonewall "EP"
2. Name of Operator Yates Petroleum Corporation ✓		9. Well No. 2
3. Address of Operator 207 South Fourth Street - Artesia, NM 88210		10. Field and Pool, or Wildcat Undesignated
4. Location of Well UNIT LETTER <u>N</u> LOCATED <u>660</u> FEET FROM THE <u>South</u> LINE AND <u>1980</u> FEET FROM THE <u>West</u> LINE OF SEC. <u>19</u> TWP. <u>20S</u> RCP. <u>28E</u> NMPM		12. County Eddy
BEFORE THE OIL CONSERVATION DIVISION Case No. 11298 Exhibit No. <u>5</u> Submitted By: PREMIER OIL & GAS INC. Hearing Date: June 29, 1995		13. Proposed Depth 11500'
21. Elevation (Show whether D.P., R.H., etc.) 3300' GR		14. Kind & Status Plug, Bond Blanket
21A. Drilling Contractor Moran Drilling Co.		15. Formation Morrow
22. Approx. Date Work will start December 26,		16. Rotary or C.T. Rotary

PROPOSED CASING AND CEMENT PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
17½"	13-3/8"	48#	600'	400	circulat
12½ & 11"	8-5/8"	24#	2900'	1000	circulat
7-7/8"	5½ or 4½"	17.20# or 11.6-13.5#	11500'	300	*

Propose to drill an 11500' well and test the Morrow & intermediate horizons. Approx. 600' of surface casing will be set & cemented to surface. Approx. 2900' of intermediate casing will be set & cemented to surface. Production casing will be 5½" or 4½", and will be cemented with some 600' of cement covering the pay.

Mud Program: FW Gel & LCM to 600', fresh water & LCM to 8500'. Brine to 10700'. Flosal-driskpak-Brine mud to TD.

BOP Program: BOP's and hydril will be installed on 8-5/8" casing & tested daily.

Gas not committed.

APPROVAL VALID

FOR 30 DAYS UNLESS

EXPIRES 3-23-77

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAMS IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

Signed Eddie L. McWhorter Title Engineer Date 12-21-76

(This space for State Use)

APPROVED BY M. A. Gressitt TITLE SUPERVISOR, DISTRICT II DATE DEC 23 1976

CONDITIONS OF APPROVAL, IF ANY:

* See 11-26-76

WELL LOCATION AND ACREAGE DEDICATION PLAT

Superseded
Effective 1

All distances must be from the outer boundaries of the Section.


Operator YATES PETROLEUM Corporation			Lease STONEWALL "E.P." STATE		Well No. #2
Unit Letter N	Section 19	Township 20 S.	Range 28 E.	County Eddy	
Actual Eastern Location of Well: 660 feet from the South line 1980 feet from the West line					
Ground Level Elev. 3300	Producing Formation Morrow	Pool Undesignated	Estimated Acreage 320 3/4		

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☐ Yes ☐ No If answer is "yes," type of consolidation _____

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) _____

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Eddie M. Mahfood
Name

Eddie M. Mahfood

Position
Engineer

Company
Yates Petroleum Corp

Date
12-21-76

I hereby certify that the well location shown on this plat was plotted from notes of actual surveys made by me under my supervision, and that the same is true and correct to the best of my knowledge and belief.

Date Surveyed
Aug. 28, 1976

Registered Professional Engineer and/or Land Surveyor


Herschel L. Jones
Certificate No.
3640

UPPER CHERRY CANYON WATERFLOOD TARGET OIL IN PLACE (KBO)

JUNE, 1995

PAUL ~~_____~~ **Hearing Date**

UPPER CHERRY CANYON - Hydrocarbon Porosity Thickness



WELL STATUS SYMBOL LEGEND

- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- PRODUCING GAS WELL
- TEMPORARILY ABANDONED GAS WELL
- ACTIVE INJECTION WELL
- SALT WATER INJECTION WELL
- SALT WATER DISPOSAL WELL
- DRY HOLE
- DRY HOLE, JUNKED AND ABANDONED
- ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN CREATING THIS MAP.


BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 6A
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

Map 20

The Exxon Company USA logo is prominently displayed at the top. Below it, the text "PRODUCTION DEPARTMENT - SOUTHERN DIVISION" and "RESERVOIR TECHNOLOGY GROUP - GEOLOGY" are listed. A large, stylized "X" logo is centered. To the right of the "X" is a vertical scale from 0 to 1000. Below the scale is a horizontal line with the text "1000" and "1000" at the ends. To the right of the scale is the text "CSE-72 CAT - 00" and "X-1000 LIT/SEC". At the bottom right, the address "100 BRIDGE PL. CANTON, N.Y. 14516" is printed.

R 2 7 E

R 2 8 E



R 2 6 E

R 2 7 E

BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 6
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

PREMIER OIL & GAS, INC.

UPPER CHERRY CANYON HYDROCARBON POROSITY THICKNESS

AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO

CONTOUR INTERVAL: 2

SCALE: 2000 FEET / INCH

GEOLOGY BY: G. E. HARRINGTON

JUNE, 1995

Exh. #5



- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED
- ✱ ABANDONED LOCATION

USED IN COUNTRIES THAT MAY

OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 4A

Case No. 11298 Exhibit No. 44

PREMIER OIL & GAS INC.

Hearing Date: June 29, 1995

Map 7

TV SPECIAL, D. O'NEILL, TV HOST	1994, 1995, 1996
---------------------------------	------------------

AVALON (DELAWARE) UNIT
BY WELL RESERVES

*** RUR AS OF 1/1/93 ***

*** EUR AND RUR UNITS ARE KBO ***

UNIT WELL NUMBER	---- PRIMARY ----		--- WORKOVERS ---		--- WATERFLOOD ---		--- CO2 FLOOD ---	
	RUR	EUR	EUR	DELTA	EUR	DELTA	EUR	DELTA
1109	0.0	0.0	0.0	0.0	0.0	0.0	296.9	296.9
1111	0.0	0.0	266.6	266.6	411.9	145.3	1043.9	632.0
1113	0.0	0.0	0.0	0.0	0.0	0.0	548.2	548.2
1309	0.0	0.0	0.0	0.0	0.0	0.0	763.2	763.2
1311	27.2	163.6	377.2	213.6	661.9	284.6	2604.2	1942.3
1313	18.1	137.1	278.7	141.6	571.0	292.3	1878.6	1307.6
1315	0.0	0.0	0.0	0.0	0.0	0.0	498.6	498.6
1509	0.0	0.0	0.0	0.0	0.0	0.0	720.1	720.1
1511	53.4	137.1	303.5	166.4	572.3	268.8	1790.3	1218.0
1513	33.8	154.6	371.4	216.8	921.8	550.5	2921.9	2000.0
1515	0.0	1.7	1.7	0.0	1.7	0.0	882.2	880.5
1517	0.0	0.0	0.0	0.0	0.0	0.0	294.6	294.6
1709	0.0	5.1	5.1	0.0	5.1	0.0	280.1	275.1
1711	19.3	127.6	127.6	0.0	291.2	163.7	1367.7	1076.4
1713	40.3	164.8	164.8	0.0	647.1	482.3	2338.6	1691.5
1715	20.2	66.3	118.8	52.6	225.0	106.2	1039.2	814.2
1717	0.0	0.0	68.8	68.8	84.9	16.1	578.9	494.0
1719	0.0	0.0	0.0	0.0	0.0	0.0	242.7	242.7
1909	0.0	0.0	0.0	0.0	0.0	0.0	345.5	345.5
1911	66.4	190.7	190.7	0.0	419.0	228.3	2006.4	1587.4
1913	80.9	268.8	268.8	0.0	863.2	594.4	2557.4	1694.2
1915	160.9	356.4	470.7	114.2	1456.1	985.4	3682.4	2226.3
1917	53.0	233.8	233.8	0.0	379.4	145.6	1063.9	684.5
1919	24.1	68.4	68.4	0.0	80.1	11.7	529.2	449.1
1921	0.0	0.0	0.0	0.0	0.0	0.0	151.8	151.8
2016	45.6	45.6	45.6	0.0	45.6	0.0	45.6	0.0
2109	0.0	0.0	0.0	0.0	0.0	0.0	84.5	84.5
2111	50.7	138.9	138.9	0.0	209.5	70.6	1310.9	1101.4
2113	120.3	360.8	424.3	63.5	908.1	483.8	2349.3	1441.2
2115	38.0	257.6	257.6	0.0	666.8	409.2	2665.0	1998.2
2117	76.6	275.8	275.8	0.0	829.3	553.5	2956.9	2127.6
2119	126.9	258.2	258.2	0.0	524.9	266.6	1515.8	991.0
2121	0.0	0.0	0.0	0.0	0.0	0.0	335.8	335.8
2123	0.0	0.0	0.0	0.0	0.0	0.0	55.3	55.3
2309	0.4	10.9	10.9	0.0	10.9	0.0	50.5	39.6
2311	19.3	150.6	150.6	0.0	285.7	135.1	1367.3	1081.6
2313	56.7	199.5	199.5	0.0	474.2	274.7	1534.8	1060.7
2315	0.0	22.7	76.8	54.1	119.8	42.9	632.9	513.1
2317	0.0	29.5	41.8	12.3	49.5	7.7	938.8	889.3
2319	29.3	173.6	175.7	2.2	315.8	140.0	1056.4	740.6
2321	3.1	23.2	76.1	52.9	127.7	51.6	969.4	841.7
2323	0.0	0.0	0.0	0.0	0.0	0.0	149.5	149.5
2509	0.3	6.0	6.0	0.0	6.0	0.0	140.2	134.1
2511	0.0	11.9	11.9	0.0	11.9	0.0	542.2	530.2
2513	0.0	0.0	0.0	0.0	0.0	0.0	215.7	215.7
2515	0.0	0.0	0.0	0.0	0.0	0.0	430.0	430.0
2517	0.0	24.6	41.4	16.8	55.5	14.1	514.6	459.2
2519	22.5	114.1	139.6	25.5	215.8	76.2	936.6	720.8
2521	0.0	0.0	0.0	0.0	0.0	0.0	365.0	365.0
2523	0.0	0.0	0.0	0.0	0.0	0.0	22.1	22.1
2709	0.0	3.1	3.1	0.0	3.1	0.0	199.8	196.7
2711	0.0	0.0	0.0	0.0	0.0	0.0	251.8	251.8
2717	0.0	0.0	0.0	0.0	0.0	0.0	99.5	99.5
2719	0.0	0.0	0.0	0.0	0.0	0.0	138.9	138.9
2721	0.0	0.0	0.0	0.0	0.0	0.0	32.7	32.7
TOTAL	1187.4	4182.4	5650.5	1468.1	12451.7	6801.2	52334.5	39882.8

Case 11-293

DRILLING TIME & SAMPLE LOG


GERALD E. HARRINGTON
P.O. Box 216

GEOLOGICAL CONSULTANT
Roswell, New Mexico

OPERATOR: GULF OIL EXPLORATION AND PRODUCTION COMPANY
WELL: EDDY "FV" STATE #3
FIELD: AVALON DELAWARE COUNTY: EDDY STATE: NEW MEXICO

LOCATION: Section 25 Twp 20-S Rge 27-E Elev. KB 3315.5
Footage 660' FSL & 330' FEL DF 3314.5
TD: 4975 CASING: _____ GL 3302.5
BIT SIZE: _____ CONTRACTOR: _____

REMARKS: DRILLING TIME - MINUTES/ 5 FEET



**BEFORE THE
OIL CONSERVATION DIVISION**
Case No. 11298 Exhibit No. 10
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE


LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE



PREMIER OIL & GAS, INC.

**LOWER CHERRY CANYON -
UPPER BRUSHY CANYON
HYDROCARBON POROSITY
THICKNESS**

AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO



CONTOUR INTERVAL: 2

GEOLOGY BY: G. E. HARRINGTON

NOVEMBER, 1995

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

AVALON (DELAWARE) FIELD COMPLETION ZONES



 Upper Cherry Canyon
 Middle Cherry Canyon
 Upper Brushy Canyon
 Lower Brushy Canyon

Exhibit No.: _____
 Operator: Premier Oil & Gas, Inc.
 Case No.: 11298
 Date: December 14, 1995

Comparison of Waterflood Target Reserves


to

Current Tract Participation

Operator	Waterflood Target Reserves (MMSTBO)	Percentage of Field Target (%)	Assigned Participation Factor
Premier	2.95	8.29%	0.00%
Exxon	14.62	41.09%	59.71%
Yates	17.63	49.55%	40.29%
MWJ	0.38	1.07%	0.00%
Field Total	35.58	100.00%	100.00%

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Avalon (Delaware) Field Waterflood Analysis



Comparison of CO2 Target Reserves


to

Current Tract Participation

Operator	CO2 Target Reserves (MMSTBO)	Percentage of Field Target (%)	Assigned Participation Factor
Premier	10.07	5.88%	4.08%
Exxon	96.71	56.49%	60.26%
Yates	61.65	36.01%	35.25%
MWJ	2.78	1.62%	0.42%
Field Total	171.21	100.00%	100.00%

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Avalon (Delaware) Field CO2 Flood Analysis



Effect of Reserve Categorization on Participation Percentage

Avalon (Delaware) Field

Given:

Total Future Production From Premier Tracts = 1,626.0 MSTBO

Case 1 - All Production From CO2 Flood

Primary barrels = 0 MSTBO
Waterflood Barrels = 0 MSTBO
CO2 barrels = 1,626.0 MSTBO

Participation % = $((0/1,192.2)*0.25) + ((0/8,269.4)*0.50) + ((1,626.0/39,883.0)*0.25)$

Participation % = 1.019

Case 2 - 25% of Production From Waterflood and 75% of Production From CO2 Flood

Primary barrels = 0 MSTBO
Waterflood Barrels = 406.5 MSTBO
CO2 barrels = 1,219.5 MSTBO

Participation % = $((0/1,192.2)*0.25) + ((406.5/8,675.9)*0.50) + ((1,219.5/39,476.5)*0.25)$

Participation % = 3.115

Exhibit No.: _____
Operator: <u>Premier Oil & Gas, Inc.</u>
Case No.: <u>11298</u>
Date: <u>December 14, 1995</u>

AVALON (DELAWARE) UNIT BY WELL RESERVES

RUR AS OF 01/01/93
EUR AND RUR UNITS ARE KBO
(As amended in 2-15-93 letter)

Unit Well Number	Primary		Secondary				Tertiary		Resulting Participation Factor
	PRIMARY RUR	EUR	WORKOVERS and WATERFLOOD DELTA	WORKOVERS DELTA	WATERFLOOD DELTA	EUR	CO2 FLOOD DELTA	EUR	
1109	0.0	0.0	0.0	0.0	0.0	0.0	265.4	265.4	0.17%
1111	0.0	0.0	345.1	266.6	78.5	345.1	530.6	875.7	2.42%
1113	0.0	0.0	0.8	0.0	0.8	0.8	446.7	447.5	0.28%
1309	0.0	0.0	0.0	0.0	0.0	0.0	607.3	607.3	0.38%
1311	43.4	179.8	403.6	213.6	190.0	583.4	1,693.0	2,276.4	4.41%
1313	33.4	152.4	373.3	141.6	231.7	525.7	1,045.9	1,571.6	3.61%
1315	0.0	0.0	0.0	0.0	0.0	0.0	362.5	362.5	0.23%
1509	0.0	0.0	0.0	0.0	0.0	0.0	579.0	579.0	0.36%
1511	53.4	137.1	368.1	166.4	201.7	505.2	1,425.9	1,931.1	4.24%
1513	33.8	154.6	741.5	216.8	524.7	896.1	2,177.2	3,073.3	6.56%
1515	0.0	1.7	0.0	0.0	0.0	1.7	852.5	854.2	0.53%
1517	0.0	0.0	0.0	0.0	0.0	0.0	247.4	247.4	0.16%
1709	0.0	5.1	0.0	0.0	0.0	5.1	174.3	179.4	0.11%
1711	19.3	127.6	174.5	0.0	174.5	302.1	1,189.7	1,491.8	2.21%
1713	40.3	164.8	698.4	0.0	698.4	863.2	2,009.3	2,872.5	6.33%
1715	20.2	66.3	157.5	52.5	105.0	223.8	966.2	1,190.0	1.98%
1717	0.0	0.0	69.3	68.8	0.5	69.3	481.0	550.3	0.72%
1719	0.0	0.0	0.0	0.0	0.0	0.0	203.9	203.9	0.13%
1909	0.0	0.0	0.0	0.0	0.0	0.0	336.2	336.2	0.21%
1911	66.4	190.7	252.6	0.0	252.6	443.3	1,687.4	2,130.7	3.98%
1913	80.9	268.8	648.3	0.0	648.3	917.1	1,861.6	2,778.7	6.78%
1915	113.5	309.0	1,101.1	114.3	986.8	1410.1	2,271.4	3,681.5	10.46%
1917	119.4	388.5	156.3	0.0	156.3	544.8	739.5	1,284.3	3.91%
1919	24.1	68.4	11.3	0.0	11.3	79.7	448.6	528.3	0.85%
1921	0.0	0.0	0.0	0.0	0.0	0.0	143.8	143.8	0.09%
2109	0.0	0.0	0.0	0.0	0.0	0.0	91.4	91.4	0.06%
2111	50.7	138.9	102.5	0.0	102.5	241.4	1,195.1	1,436.5	2.43%
2113	120.3	360.8	553.9	63.5	490.4	914.7	1,496.8	2,411.5	6.81%
2115	38.0	257.6	397.1	0.0	397.1	654.7	1,933.6	2,588.3	4.41%
2117	76.6	275.8	587.5	0.0	587.5	863.3	2,241.8	3,105.1	6.56%
2119	126.9	258.2	232.2	0.0	232.2	490.4	925.2	1,415.6	4.64%
2121	0.0	0.0	0.0	0.0	0.0	0.0	308.9	308.9	0.19%
2123	0.0	0.0	0.0	0.0	0.0	0.0	51.5	51.5	0.03%
2309	0.4	10.9	0.0	0.0	0.0	10.9	46.7	57.6	0.04%
2311	19.3	150.6	157.9	0.0	157.9	308.5	1,207.9	1,516.4	2.12%
2313	56.7	199.5	264.9	0.0	264.9	464.4	1,064.2	1,528.6	3.46%
2315	0.0	22.7	73.4	54.1	19.3	96.1	523.1	619.2	0.77%
2317	0.0	29.5	28.6	12.3	16.3	58.1	881.0	939.1	0.73%
2319	29.3	173.6	167.5	2.1	165.4	341.1	823.6	1,164.7	2.14%
2321	3.1	23.2	69.7	52.9	16.8	92.9	741.6	834.5	0.95%
2323	0.0	0.0	0.0	0.0	0.0	0.0	120.1	120.1	0.08%
2509	0.3	6.0	0.0	0.0	0.0	6.0	119.1	125.1	0.08%
2511	0.0	11.9	0.0	0.0	0.0	11.9	522.4	534.3	0.33%
2513	0.0	0.0	0.0	0.0	0.0	0.0	219.4	219.4	0.14%
2515	0.0	0.0	0.4	0.0	0.4	0.4	353.9	354.3	0.22%
2517	0.0	24.6	43.7	16.8	26.9	68.3	525.1	593.4	0.59%
2519	22.5	114.1	88.3	25.5	62.8	202.4	710.5	912.9	1.45%
2521	0.0	0.0	0.1	0.0	0.1	0.1	299.2	299.3	0.19%
2523	0.0	0.0	0.0	0.0	0.0	0.0	19.5	19.5	0.01%
2709	0.0	3.1	0.0	0.0	0.0	3.1	239.4	242.5	0.15%
2711	0.0	0.0	0.0	0.0	0.0	0.0	204.9	204.9	0.13%
2717	0.0	0.0	0.0	0.0	0.0	0.0	148.9	148.9	0.09%
2719	0.0	0.0	0.0	0.0	0.0	0.0	111.9	111.9	0.07%
2721	0.0	0.0	0.0	0.0	0.0	0.0	10.0	10.0	0.01%
Totals =	1,192.2	4,275.8	8,269.4	1,467.8	6,801.6	12,545.2	39,883.0	52,428.2	100.00%

AVALON (DELAWARE) UNIT BY WELL RESERVES

RUR AS OF 01/01/93
EUR AND RUR UNITS ARE KBO
(As amended in 2-15-93 letter)


Unit Well Number	Primary		Secondary				Tertiary		Resulting Participation Factor
	PRIMARY RUR	EUR	WORKOVERS and WATERFLOOD		WORKOVERS WATERFLOOD		CO2 FLOOD		
			DELTA	DELTA	DELTA	EUR	DELTA	EUR	
1109	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.00%
1111	0.0	0.0	345.1	266.6	78.5	345.1	530.6	875.7	2.43%
1113	0.0	0.0	0.8	0.0	0.8	0.8	446.7	447.5	0.30%
1309	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.00%
1311	43.4	179.8	403.6	213.6	190.0	583.4	1,693.0	2,276.4	4.46%
1313	33.4	152.4	373.3	141.6	231.7	525.7	1,045.9	1,571.6	3.64%
1315	0.0	0.0	0.0	0.0	0.0	0.0	362.5	362.5	0.24%
1509	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.00%
1511	53.4	137.1	368.1	166.4	201.7	505.2	1,425.9	1,931.1	4.28%
1513	33.8	154.6	741.5	216.8	524.7	896.1	2,177.2	3,073.3	6.61%
1515	0.0	1.7	0.0	0.0	0.0	1.7	852.5	854.2	0.56%
1517	0.0	0.0	0.0	0.0	0.0	0.0	247.4	247.4	0.16%
1709	0.0	5.1	0.0	0.0	0.0	5.1	0.0	5.1	0.00%
1711	19.3	127.6	174.5	0.0	174.5	302.1	1,189.7	1,491.8	2.24%
1713	40.3	164.8	698.4	0.0	698.4	863.2	2,009.3	2,872.5	6.38%
1715	20.2	66.3	157.5	52.5	105.0	223.8	966.2	1,190.0	2.01%
1717	0.0	0.0	69.3	68.8	0.5	69.3	481.0	550.3	0.73%
1719	0.0	0.0	0.0	0.0	0.0	0.0	203.9	203.9	0.13%
1909	0.0	0.0	0.0	0.0	0.0	0.0	336.2	336.2	0.22%
1911	66.4	190.7	252.6	0.0	252.6	443.3	1,687.4	2,130.7	4.02%
1913	80.9	268.8	648.3	0.0	648.3	917.1	1,861.6	2,778.7	6.83%
1915	113.5	309.0	1,101.1	114.3	986.8	1410.1	2,271.4	3,681.5	10.52%
1917	119.4	388.5	156.3	0.0	156.3	544.8	739.5	1,284.3	3.93%
1919	24.1	68.4	11.3	0.0	11.3	79.7	448.6	528.3	0.87%
1921	0.0	0.0	0.0	0.0	0.0	0.0	143.8	143.8	0.09%
2109	0.0	0.0	0.0	0.0	0.0	0.0	91.4	91.4	0.06%
2111	50.7	138.9	102.5	0.0	102.5	241.4	1,195.1	1,436.5	2.46%
2113	120.3	360.8	553.9	63.5	490.4	914.7	1,496.8	2,411.5	6.85%
2115	38.0	257.6	397.1	0.0	397.1	654.7	1,933.6	2,588.3	4.46%
2117	76.6	275.8	587.5	0.0	587.5	863.3	2,241.8	3,105.1	6.62%
2119	126.9	258.2	232.2	0.0	232.2	490.4	925.2	1,415.6	4.67%
2121	0.0	0.0	0.0	0.0	0.0	0.0	308.9	308.9	0.20%
2123	0.0	0.0	0.0	0.0	0.0	0.0	51.5	51.5	0.03%
2309	0.4	10.9	0.0	0.0	0.0	10.9	46.7	57.6	0.04%
2311	19.3	150.6	157.9	0.0	157.9	308.5	1,207.9	1,516.4	2.15%
2313	56.7	199.5	264.9	0.0	264.9	464.4	1,064.2	1,528.6	3.49%
2315	0.0	22.7	73.4	54.1	19.3	96.1	523.1	619.2	0.79%
2317	0.0	29.5	28.6	12.3	16.3	58.1	881.0	939.1	0.75%
2319	29.3	173.6	167.5	2.1	165.4	341.1	823.6	1,164.7	2.17%
2321	3.1	23.2	69.7	52.9	16.8	92.9	741.6	834.5	0.97%
2323	0.0	0.0	0.0	0.0	0.0	0.0	120.1	120.1	0.08%
2509	0.3	6.0	0.0	0.0	0.0	6.0	119.1	125.1	0.08%
2511	0.0	11.9	0.0	0.0	0.0	11.9	522.4	534.3	0.34%
2513	0.0	0.0	0.0	0.0	0.0	0.0	219.4	219.4	0.14%
2515	0.0	0.0	0.4	0.0	0.4	0.4	353.9	354.3	0.23%
2517	0.0	24.6	43.7	16.8	26.9	68.3	525.1	593.4	0.61%
2519	22.5	114.1	88.3	25.5	62.8	202.4	710.5	912.9	1.47%
2521	0.0	0.0	0.1	0.0	0.1	0.1	299.2	299.3	0.20%
2523	0.0	0.0	0.0	0.0	0.0	0.0	19.5	19.5	0.01%
2709	0.0	3.1	0.0	0.0	0.0	3.1	239.4	242.5	0.16%
2711	0.0	0.0	0.0	0.0	0.0	0.0	204.9	204.9	0.13%
2717	0.0	0.0	0.0	0.0	0.0	0.0	148.9	148.9	0.10%
2719	0.0	0.0	0.0	0.0	0.0	0.0	111.9	111.9	0.07%
2721	0.0	0.0	0.0	0.0	0.0	0.0	10.0	10.0	0.01%
Totals =	1 192.2	4 275.8	8 269.4	1 467.8	6 801.6	12 545.2	38 257.0	50 802.2	100.00%

AVALON (DELAWARE) UNIT

Result of Removal of Premier Tracts

Unit Well Number	Existing Formula Resulting Participation Factor	Removing Premier Tracts Resulting Participation Factor	Change in Participation Factor
1109	0.17%	0.00%	-0.17%
1111	2.42%	2.43%	0.01%
1113	0.28%	0.30%	0.01%
1309	0.38%	0.00%	-0.38%
1311	4.41%	4.46%	0.05%
1313	3.61%	3.64%	0.03%
1315	0.23%	0.24%	0.01%
1509	0.36%	0.00%	-0.36%
1511	4.24%	4.28%	0.04%
1513	6.56%	6.61%	0.06%
1515	0.53%	0.56%	0.02%
1517	0.16%	0.16%	0.01%
1709	0.11%	0.00%	-0.11%
1711	2.21%	2.24%	0.03%
1713	6.33%	6.38%	0.05%
1715	1.98%	2.01%	0.03%
1717	0.72%	0.73%	0.01%
1719	0.13%	0.13%	0.01%
1909	0.21%	0.22%	0.01%
1911	3.98%	4.02%	0.04%
1913	6.78%	6.83%	0.05%
1915	10.46%	10.52%	0.06%
1917	3.91%	3.93%	0.02%
1919	0.85%	0.87%	0.01%
1921	0.09%	0.09%	0.00%
2016	0.06%	0.06%	0.00%
2109	2.43%	2.46%	0.03%
2111	6.81%	6.85%	0.04%
2113	4.41%	4.46%	0.05%
2115	6.56%	6.62%	0.06%
2117	4.64%	4.67%	0.02%
2119	0.19%	0.20%	0.01%
2121	0.03%	0.03%	0.00%
2123	0.04%	0.04%	0.00%
2309	2.12%	2.15%	0.03%
2311	3.46%	3.49%	0.03%
2313	0.77%	0.79%	0.01%
2315	0.73%	0.75%	0.02%
2317	2.14%	2.17%	0.02%
2319	0.95%	0.97%	0.02%
2321	0.08%	0.08%	0.00%
2323	0.08%	0.08%	0.00%
2509	0.33%	0.34%	0.01%
2511	0.14%	0.14%	0.01%
2513	0.22%	0.23%	0.01%
2515	0.59%	0.61%	0.01%
2517	1.45%	1.47%	0.02%
2519	0.19%	0.20%	0.01%
2521	0.01%	0.01%	0.00%
2523	0.15%	0.16%	0.01%
2709	0.13%	0.13%	0.01%
2711	0.09%	0.10%	0.00%
2717	0.07%	0.07%	0.00%
2719	0.01%	0.01%	0.00%
2721	0.00%	0.00%	0.00%
Totals =	100.00%	100.00%	

Change in Participation Factor Comparison




AVALON (DELAWARE) UNIT
COMPARISON OF BY WELL RESERVES TO ACTUAL PRODUCTION

RUR AS OF 01/01/93
EUR AND RUR UNITS ARE KBO
(As amended in 2-15-93 letter)


Unit Well Number	Exxon Estimates		Actual Current Production	Overstated Reserve Estimates
	RUR	EUR		
1109	0.0	0.0	0.0	
1111	0.0	0.0	1.6	
1113	0.0	0.0	0.0	
1309	0.0	0.0	0.0	
1311	43.4	179.8	152.7	
1313	33.4	152.4	131.7	
1315	0.0	0.0	0.0	
1509	0.0	0.0	0.0	
1511	53.4	137.1	89.4	
1513	33.8	154.6	140.1	
1515	0.0	1.7	1.7	
1517	0.0	0.0	0.0	
1709	0.0	5.1	5.1	
1711	19.3	127.6	114.9	
1713	40.3	164.8	142.5	
1715	20.2	66.3	51.6	
1717	0.0	0.0	0.0	
1719	0.0	0.0	0.0	
1909	0.0	0.0	0.0	
1911	66.4	190.7	136.0	
1913	80.9	268.8	215.0	
1915	113.5	309.0	209.7	
1917	119.4	388.5	324.1	
1919	24.1	68.4	46.9	
1921	0.0	0.0	0.0	
2109	0.0	0.0	0.0	
2111	50.7	138.9	94.2	
2113	120.3	360.8	275.9	
2115	38.0	257.6	249.0	
2117	76.6	275.8	239.3	
2119	126.9	258.2	158.1	
2121	0.0	0.0	0.0	
2123	0.0	0.0	0.0	
2309	0.4	10.9	10.9	
2311	19.3	150.6	154.2	
2313	56.7	199.5	164.8	
2315	0.0	22.7	22.7	
2317	0.0	29.5	29.5	
2319	29.3	173.6	161.9	
2321	3.1	23.2	24.5	
2323	0.0	0.0	0.0	
2509	0.3	6.0	7.7	
2511	0.0	11.9	11.9	
2513	0.0	0.0	0.0	
2515	0.0	0.0	0.0	
2517	0.0	24.6	24.6	
2519	22.5	114.1	105.9	
2521	0.0	0.0	0.0	
2523	0.0	0.0	0.0	
2709	0.0	3.1	3.1	
2711	0.0	0.0	0.0	
2717	0.0	0.0	0.0	
2719	0.0	0.0	0.0	
2721	0.0	0.0	0.0	

Comparison of Actual Production to Report Production Stonewall WM State #6 (1511)




AVALON FIELD DECLINE CURVES


WELL = STONEWALL WM STATE #06 (1511)



WELL = STONEWALL WM STATE #06 (1511)




Comparison of Actual Production to Report Production Yates C Federal #3 (1915)




AVALON FIELD DECLINE CURVES


WELL = YATES C FEDERAL #03 (1915)



WELL = YATES C FEDERAL #03 (1915)




Comparison of Actual Production to Report Production Hondo A State #1 (1919)




AVALON FIELD DECLINE CURVES


WELL = HONDO A STATE #01 (1919)



WELL = HONDO A STATE #01 (1919)




Comparison of Actual Production to Report Production Yates C Federal #8 (2111)




AVALON FIELD DECLINE CURVES

WELL = YATES C FEDERAL #08 (2111)




Legend . . . INCLUDED ° ° ° EXCLUDED
 ——— FILTERED FIT - - - - - RAW FIT

WELL = YATES C FEDERAL #08 (2111)




Legend . . . INCLUDED ° ° ° EXCLUDED
 ——— FILTERED FIT - - - - - RAW FIT

Comparison of Actual Production to Report Production Yates C Federal #6 (2113)




AVALON FIELD DECLINE CURVES


WELL = YATES C FEDERAL #06 (2113)



WELL = YATES C FEDERAL #06 (2113)




Comparison of Actual Production to Report Production Yates C Federal #4 (1917)




AVALON FIELD DECLINE CURVES

WELL = YATES C FEDERAL #04 (1917)



WELL = YATES C FEDERAL #04 (1917)



Exxon's Calculation of Fractional Recovery of Original Oil in Place by Tract

Avalon Field, Eddy County, New Mexico





Exhibit No.: _____
 Operator: Premier Oil & Gas, Inc.
 Case No.: 11298
 Date: December 14, 1995

Exxon's Calculation of Primary Recovery of Original Oil in Place by Tract


Avalon Field, Eddy County, New Mexico



4:44 PM
12/12/95

Exxon's Calculation of Secondary Recovery of Original Oil in Place by Tract


Avalon Field, Eddy County, New Mexico




**Analysis of Workover Reserves
Avalon (Delaware) Field**

<u>Well</u>	<u>Tract</u>	<u>Zone</u>	<u>Report 00IP (MBO)</u>	<u>Workover Reserves (MBO)</u>	<u>Recovery Factor (%)</u>	<u>Remarks</u>
EP 7	1111	UCC	2550	266.6	10.5	Already done
EP 5	1311	UCC	2600	213.6	8.2	
EP 8	1313	UCC	2050	141.6	6.9	
WM 6	1511	UCC	1700	166.4	9.8	
WM 5	1513	UCC	2220			
WM 5	1513	UBC	5450	216.8	2.8	
WM 1	1715	UBC	3630	52.5	1.4	
WM 2	1717	UCC	1590	68.8	4.3	
C 3	1915	UCC	3050	114.3	3.8	
C 6	2113	UCC	2540	63.5	1.2	
C 18	2315	UCC	1220	54.1	4.4	
C 12	2317	UCC	3580	12.3	0.3	
HS 3	2319			2.1		Not on AFE
HF 2	2321			52.9		Not on AFE
C 14	2517	UCC	2600	16.8	0.7	
HS 4	2519			25.5		Not on AFE

OIL RECOVERY VS INITIAL WATER SATURATION SIMULATION MODEL: UPPER CHERRY PROTOTYPE



THEORETICAL RECOVERY FACTORS




SORWF=0.35, SORM=0.10, EV SEC=0.70, EV TERT=0.40

Exhibit G-20

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Recovery Factor vs. Water Saturation Avalon Field, Eddy County, New Mexico



1:40 PM
12/11/95

Comparison Of Future Production

to

Assigned Participation Percentage

Operator	Formula Assigned Participation	Percentage of Future Production
Premier	1.02%	3.30%
Exxon	64.79%	60.63%
Yates	34.07%	35.74%
MWJ	0.12%	0.34%
	100.00%	100.00%

Avalon (Delaware) Field



Comparison Of Reserve Category


to

Assigned Participation Percentage

Reserve Category	Percentage of Future Production	Formula Assigned Participation
Primary	2.42%	25.00%
Secondary	16.76%	50.00%
Tertiary	80.83%	25.00%
	100.00%	100.00%

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Avalon (Delaware) Field



Comparison of Relative Value

to the

Proposed Participation Formula Weighting

Avalon (Delaware) Field

Case	Value (\$)	% of Total (%)	Participation Formula Weighting (%)
Future Primary Reserves and Waterflood	263,952,629	19.99%	75.00%
CO2 Flood	1,056,349,142	80.01%	25.00%
Total	1,320,301,771	100.00%	100.00%

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Economic Analysis

of the

Proposed Waterflood

Avalon (Delaware) Field

Year	Daily Oil (BOPD)	Daily Gas (MCFD)	Yearly Oil (BOPD)	Yearly Gas (MCFD)	Oil Price (\$/bbl)	Gas Price (\$/MCF)	Oil Revenue (\$)	Gas Revenue (\$)	Total Revenue (\$)	Capital Expenses (\$)	Operating Expenses (\$)	Overhead Expenses (\$)	Production Taxes (\$)	Advalorem Taxes (\$)	BFT NCF (\$)	Cumulative BFT NCF (\$)	Discounted BFT NCF (\$)
1996	1,021	1,263	372,665	460,995	18.02	1.59	6,716,690	733,674	7,450,364	7,200,000	1,114,500	775,725	513,569	149,007	-2,302,437	-2,302,437	-2,093,125
1997	1,121	656	409,165	239,440	19.00	1.69	7,772,770	404,314	8,177,084	7,200,000	1,096,800	774,840	572,582	163,542	-1,630,180	-3,932,617	-1,347,256
1998	1,245	565	454,425	206,225	20.02	1.79	9,098,717	369,470	9,468,187	0	1,120,000	56,000	664,482	189,364	7,438,341	3,505,723	5,588,535
1999	1,227	600	447,855	219,000	21.10	1.90	9,451,396	416,291	9,867,687	0	1,134,000	56,700	691,864	197,354	7,787,770	11,293,493	5,319,152
2000	1,211	720	442,015	262,800	22.24	2.02	9,831,871	530,022	10,361,893	0	1,144,900	57,245	724,564	207,238	8,227,946	19,521,439	5,108,907
2001	1,164	863	424,960	314,995	23.44	2.14	9,960,603	674,042	10,634,645	0	1,152,900	57,645	740,905	212,693	8,470,502	27,991,941	4,781,378
2002	1,098	939	400,770	342,735	24.71	2.27	9,903,201	778,139	10,681,340	0	1,158,300	57,915	742,034	213,627	8,509,464	36,501,406	4,366,701
2003	1,052	955	383,980	348,575	26.04	2.41	10,000,682	839,674	10,840,355	0	1,163,900	58,195	752,032	216,907	8,649,421	45,150,827	4,035,019
2004	1,000	966	365,000	352,590	27.45	2.56	10,019,694	901,155	10,920,850	0	1,168,400	58,420	756,456	218,417	8,719,157	53,869,983	3,697,774
2005	951	959	347,115	350,035	28.93	2.71	10,043,281	949,197	10,992,478	0	1,173,100	58,655	760,533	219,850	8,780,341	62,650,324	3,385,201
2006	897	953	327,405	347,845	30.50	2.88	9,984,542	1,000,798	10,985,339	0	1,161,700	58,085	758,942	219,707	8,786,905	71,437,229	3,079,757
2007	845	944	308,425	344,560	32.14	3.05	9,913,637	1,051,818	10,965,455	0	1,123,800	56,190	756,459	219,309	8,809,697	80,246,927	2,807,041
2008	801	926	292,365	337,990	33.88	3.24	9,904,885	1,094,700	10,999,585	0	1,126,800	56,340	757,982	219,992	8,838,471	89,085,398	2,560,190
2009	768	898	280,320	327,770	35.71	3.44	10,009,647	1,126,356	11,136,003	0	1,130,100	56,505	767,003	222,720	8,959,675	98,045,073	2,359,363
2010	726	870	264,990	317,550	37.64	3.65	9,973,205	1,157,802	11,131,007	0	1,134,200	56,710	765,988	222,620	8,951,489	106,996,562	2,142,915
2011	684	862	249,860	314,630	39.67	3.87	9,903,640	1,217,132	11,120,772	0	1,127,800	56,390	764,015	220,415	8,950,151	115,946,713	1,947,814
2012	640	847	233,600	309,155	41.81	4.10	9,766,958	1,288,905	11,035,863	0	1,105,100	55,255	756,899	220,717	8,897,892	124,844,605	1,760,400
2013	602	834	219,730	304,410	44.07	4.35	9,683,146	1,325,645	11,008,790	0	1,093,900	54,685	753,786	220,176	8,886,234	133,730,839	1,598,267
2014	568	828	207,320	302,220	46.45	4.62	9,629,615	1,396,390	11,026,005	0	1,087,400	54,370	753,522	220,520	8,910,193	142,641,032	1,456,888
2015	530	805	193,450	293,825	48.96	4.90	9,470,591	1,440,415	10,811,006	0	1,069,400	54,470	744,433	218,220	8,804,483	151,445,514	1,308,730
2016	489	691	178,485	252,215	51.60	5.20	9,209,810	1,311,853	10,521,663	0	1,090,000	54,500	719,489	210,433	8,447,241	159,892,755	1,141,480
2017	436	464	159,140	169,360	54.39	5.52	8,655,036	934,632	9,589,668	0	1,090,000	54,500	661,239	191,793	7,592,136	167,484,891	932,663
2018	406	442	148,190	161,330	57.32	5.86	8,494,720	944,627	9,439,347	0	1,090,000	54,500	650,356	188,787	7,455,703	174,940,594	832,639
2019	386	417	140,890	152,205	60.42	6.21	8,512,379	945,561	9,457,939	0	1,090,000	54,500	651,657	189,159	7,472,624	182,413,218	758,663
2020	365	409	133,225	149,285	63.68	6.59	8,483,931	983,993	9,467,924	0	1,090,000	54,500	651,559	189,358	7,482,507	189,895,724	690,605
2021	338	393	123,370	143,445	67.12	6.99	8,280,595	1,003,175	9,283,770	0	1,090,000	54,500	638,081	185,675	7,315,514	197,211,238	613,811
2022	326	382	118,990	139,430	70.74	7.42	8,417,887	1,034,577	9,452,464	0	1,090,000	54,500	649,399	189,049	7,469,516	204,680,753	569,757
2023	310	363	113,150	132,495	74.56	7.87	8,496,995	1,043,089	9,480,084	0	1,090,000	54,500	651,181	189,602	7,494,801	212,175,555	519,715
2024	297	353	108,405	128,845	78.59	8.35	8,519,677	1,076,230	9,595,907	0	1,090,000	54,500	658,709	191,918	7,600,780	219,776,335	479,149
2025	285	347	104,025	126,655	82.84	8.86	8,616,922	1,122,471	9,739,393	0	1,090,000	54,500	667,925	194,788	7,732,180	227,508,515	443,120
2026	273	335	99,645	122,275	87.31	9.40	8,699,826	1,148,756	9,848,582	0	1,090,000	54,500	675,175	196,992	7,832,915	235,341,430	408,085
2027	246	322	89,790	117,530	92.02	9.98	8,262,731	1,172,552	9,435,284	0	1,090,000	54,500	645,282	188,706	7,456,797	242,798,227	353,172
2028	225	304	82,125	110,960	96.99	10.59	7,965,475	1,174,533	9,140,008	0	1,090,000	54,500	624,275	182,800	7,188,432	249,986,659	309,511
2029	213	291	77,745	106,215	102.23	11.23	7,947,844	1,192,889	9,140,734	0	1,090,000	54,500	623,941	182,815	7,189,478	257,176,136	281,414
2030	190	279	69,350	101,835	107.75	11.92	7,472,466	1,213,464	8,685,930	0	1,090,000	54,500	591,218	173,719	6,776,493	263,952,629	241,135

Totals =

351,994,404 14,400,000 38,957,000 3,387,850 24,257,037 7,039,888

Economic Analysis

of the

Proposed CO2 Flood


Avalon (Delaware) Field

Year	Daily Oil (BOPD)	Daily Gas (MCFD)	Yearly Oil (MMbbl)	Yearly Gas (MMCF)	Oil Price (\$/bbl)	Gas Price (\$/MCF)	Revenue (\$)	Total Revenue (\$)	Capital Expenses (\$)	Total Expenses (\$)	Production Taxes (\$)	Advalorem Taxes (\$)	BFT NCF (\$)	Cumulative BFT NCF (\$)
1996	1,021	1,263	372,665	460,995	18.02	1.59	733,674	7,450,364	7,200,000	2,000,000	513,569	149,007	-2,412,212	-2,412,212
1997	1,121	656	408,165	239,440	19.00	1.69	772,770	8,177,084	7,600,000	1,900,000	572,082	163,542	-2,058,540	-4,470,752
1998	1,372	623	500,780	227,395	20.02	1.79	10,026,859	10,434,257	200,000	1,900,000	732,277	208,685	7,793,295	3,322,542
1999	1,702	681	621,230	248,565	21.10	1.90	13,110,250	13,582,740	14,400,000	4,400,000	954,452	271,655	-6,443,367	-3,120,824
2000	2,157	903	787,305	329,595	22.24	2.02	17,512,259	18,176,984	28,600,000	11,000,000	1,276,607	363,540	-23,063,153	-26,183,977
2001	2,702	1,432	986,230	522,680	23.44	2.14	23,121,605	24,240,063	17,300,000	13,400,000	1,697,557	484,801	-8,642,295	-34,826,272
2002	3,404	2,230	1,242,460	813,950	24.71	2.27	30,701,727	32,549,704	0	12,700,000	2,272,221	650,994	-17,899,784	-52,726,056
2003	4,009	2,817	1,463,285	1,028,205	26.04	2.41	38,110,963	40,587,780	0	12,900,000	2,829,719	811,756	24,046,305	-28,680,351
2004	4,435	3,903	1,618,775	1,424,595	27.45	2.56	44,437,344	48,078,348	0	13,200,000	3,337,102	981,567	30,579,680	-1,100,671
2005	4,530	4,848	1,653,450	1,769,520	28.93	2.71	47,840,233	49,948,446	0	13,200,000	3,636,579	1,052,774	34,749,326	11,648,709
2006	4,634	4,780	1,691,410	1,744,700	30.50	2.88	51,581,234	56,600,974	0	13,300,000	3,913,255	1,132,019	38,255,700	50,004,419
2007	4,694	4,859	1,713,310	1,773,535	32.14	3.05	55,070,547	60,484,514	0	13,900,000	4,180,707	1,209,690	41,294,117	91,300,536
2008	4,658	4,467	1,700,170	1,630,455	33.88	3.24	57,599,193	62,879,997	0	14,200,000	4,353,583	1,257,600	43,068,815	134,369,351
2009	4,701	4,169	1,715,865	1,521,685	35.71	3.44	61,269,986	66,499,139	0	15,100,000	4,611,627	1,329,983	45,457,530	179,826,881
2010	4,667	4,114	1,703,455	1,501,610	37.64	3.65	64,111,500	69,596,438	0	15,800,000	4,825,663	1,391,729	47,569,046	227,395,927
2011	4,569	4,111	1,667,685	1,500,515	39.67	3.87	66,154,579	71,959,251	0	16,300,000	4,987,209	1,439,185	49,232,858	276,628,785
2012	4,394	4,037	1,603,810	1,473,505	41.81	4.10	67,056,273	73,104,170	0	16,100,000	5,063,390	1,462,083	50,478,687	327,107,472
2013	4,233	3,992	1,543,045	1,457,080	44.07	4.35	68,087,633	74,432,925	0	16,500,000	5,151,487	1,488,658	51,292,780	378,400,262
2014	4,102	3,953	1,497,230	1,442,845	46.45	4.62	69,543,451	76,210,033	0	16,900,000	5,270,914	1,524,201	52,514,918	430,915,180
2015	3,953	3,759	1,442,845	1,372,035	48.96	4.90	70,636,310	77,362,423	0	17,500,000	5,351,484	1,547,248	52,963,681	483,878,861
2016	3,754	3,517	1,370,210	1,283,705	51.60	5.20	70,702,712	78,676,972	0	17,300,000	5,353,741	1,547,594	53,178,349	537,057,200
2017	3,621	3,369	1,321,665	1,229,685	54.39	5.52	71,880,475	79,666,627	0	18,000,000	5,442,821	1,573,333	53,650,473	590,707,673
2018	3,477	3,377	1,269,105	1,232,605	57.32	5.86	72,749,115	79,966,320	0	18,900,000	5,526,047	1,599,326	53,940,946	644,648,619
2019	3,319	3,411	1,211,435	1,245,015	60.42	6.21	73,193,226	80,927,776	0	19,600,000	5,583,447	1,618,556	54,125,774	698,774,393
2020	3,093	3,387	1,128,945	1,236,255	63.68	6.59	71,892,596	80,041,213	0	17,900,000	5,511,805	1,600,824	53,527,803	752,296,196
2021	2,867	3,223	1,048,455	1,176,395	67.12	6.99	70,238,067	78,465,122	0	15,300,000	5,398,256	1,569,302	56,197,564	808,493,760
2022	2,652	3,114	967,980	1,136,610	70.74	7.42	68,479,249	76,912,948	0	15,100,000	5,283,712	1,538,259	54,990,977	863,484,737
2023	2,468	2,957	900,820	1,079,305	74.56	7.87	67,169,364	75,666,375	0	15,000,000	5,193,875	1,513,328	53,359,172	916,843,910
2024	2,303	2,769	840,595	1,010,685	78.59	8.35	66,063,355	74,505,508	0	16,000,000	5,112,606	1,490,110	51,902,792	968,746,702
2025	2,170	2,607	792,050	951,555	82.84	8.86	65,609,546	74,042,635	0	16,800,000	5,079,932	1,480,853	50,681,850	1,019,428,552
2026	2,026	2,551	739,490	931,115	87.31	9.40	64,563,543	73,518,852	0	18,100,000	5,021,777	1,466,377	48,730,698	1,068,159,250
2027	1,891	2,537	690,215	926,005	92.02	9.98	63,515,548	72,753,951	0	17,800,000	4,971,524	1,455,079	48,527,348	1,116,686,600
2028	1,789	2,468	652,985	900,820	96.99	10.59	63,334,373	72,869,377	0	18,200,000	4,973,508	1,457,395	48,238,827	1,164,925,427
2029	1,687	2,381	615,755	869,065	102.23	11.23	62,948,419	72,708,796	0	18,900,000	4,957,357	1,454,176	47,397,263	1,212,322,690
2030	1,600	2,311	584,000	843,515	107.75	11.92	62,926,031	72,977,337	0	19,800,000	4,970,313	1,459,547	46,747,477	1,259,070,167


Totals =

2,086,238,751 75,300,000 505,000,000 143,912,205 41,724,775

Avalon (Delaware) Field Comparison of Waterflood and CO2 Flood Net Cash Flows



Avalon (Delaware) Field Comparison of Waterflood and CO2 Flood Discounted Cash Flows



Avalon (Delaware) Field

Listing of Potential Tract Participation Factors

Parameter		Premier Acreage	Esso Acreage	Yates Acreage	MMA Acreage	Field Total
Original Oil in Place (MSTBO)	Tract Value	13.73	146.70	82.87	4.91	248.21
	% of Field Total	5.53%	59.10%	33.39%	1.98%	100.00%
Cumulative Oil Production to 1-1-93 (MSTBO)	Tract Value	5	2,234	741	16	2,995
	% of Field Total	0.17%	74.57%	24.72%	0.54%	100.00%
January 1993 Oil Production Rate (BOPM)	Tract Value	0	13,244	3,450	54	16,748
	% of Field Total	0.00%	79.08%	20.60%	0.32%	100.00%
Initial Potential Oil Rate (BOPD)	Tract Value	72	2,479	1,118	31	3,700
	% of Field Total	1.95%	67.00%	30.22%	0.84%	100.00%
Number of Wells	Tract Value	2	22	11	2	37
	% of Field Total	5.41%	59.46%	29.73%	5.41%	100.00%
Remaining Primary Reserves (MSTBO)	Tract Value	0.00	1,289.20	1,370.10	0.70	2,660.00
	% of Field Total	0.00%	48.47%	51.51%	0.03%	100.00%
Total Lease Acreage (acres)	Tract Value	160	1,232	646	80	2,119
	% of Field Total	7.55%	58.17%	30.50%	3.78%	100.00%
Waterflood Target (MSTBO)	Tract Value	2.95	14.62	17.63	0.38	35.58
	% of Field Total	8.29%	41.09%	49.55%	1.07%	100.00%
CO2 Target (MSTBO)	Tract Value	10.07	96.71	61.65	2.78	171.21
	% of Field Total	5.88%	56.49%	36.01%	1.62%	100.00%
Waterflood Reserves (MSTBO)	Tract Value	0.0	4,595.8	2,205.8	0.0	6,801.6
	% of Field Total	0.00%	67.57%	32.43%	0.00%	100.00%
CO2 Reserves (MSTBO)	Tract Value	1,626.0	24,031.8	14,059.4	165.8	39,883.0
	% of Field Total	4.08%	60.26%	35.25%	0.42%	100.00%
Future Barrels Produced (MSTBO)	Tract Value	1,626.0	29,916.8	17,635.3	166.5	49,344.6
	% of Field Total	3.30%	60.63%	35.74%	0.34%	100.00%
Total Barrels Produced (MSTBO)	Tract Value	1,631.1	32,150.3	18,375.8	182.7	52,339.9
	% of Field Total	3.12%	61.43%	35.11%	0.35%	100.00%
Average	% of Field Total	3.48%	61.02%	34.21%	1.28%	100.00%
Proposed Participation Factor (50% OOIP, 10% 1/93 Rate, 20% Rem Primary, 20% Future Prod)		3.42%	59.28%	36.20%	1.09%	100.00%

Exhibit No.: _____
 Operator: Premier Oil & Gas, Inc.
 Case No.: 11298
 Date: December 14, 1995

Comparison of Hydrocarbon Pore Volume Avalon Field, Eddy County, New Mexico

Tract	Operator	Lower Cherry/Upper Brushy		Upper Cherry		Change from Exxon's	
		Exxon Calc. (acre-ft)	Premier Map (acre-ft)	Exxon Calc. (acre-ft)	Premier Map (acre-ft)	Calculations (MSTBO)	(%)
1109	Premier	295.4	310.0	222.7	253.6	293.7	8.77%
1111	Yates			394.4	399.1	30.2	1.18%
1113	Yates			324.8	330.0	33.5	1.59%
1309	Premier	275.3	284.5	298.5	272.1	-111.6	-3.01%
1311	Yates			402.2	362.7	-255.1	-9.81%
1313	Yates			317.1	314.0	-20.0	-0.98%
1315	Yates			250.6	227.2	-151.2	-9.33%
1509	Premier	278.4	287.7	273.8	322.8	376.9	10.56%
1511	Yates			263.0	278.1	97.9	5.76%
1709	Premier			244.4	408.8	1,062.9	67.27%
1909	Yates			280.0	358.0	504.5	27.87%
	Total	849.2	882.2	3271.5	3526.4	1,861.6	6.99%
	Premier	849.2	882.2	1039.4	1257.3	1,621.9	13.28%
	Yates	0.0	0.0	2232.0	2269.1	239.7	1.66%

AVALON FIELD WELL-TRACTS




Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Comparison of Primary Recoveries

Offset Tracts to 1709

Avalon (Delaware) Field

Tract	Report OOIP (MSTBO)	Report Primary Recovery (MSTBO)	Recovery Factor (%)
-------	---------------------------	--	---------------------------

1511	5,980	303.5	5.08%
1711	4,960	127.6	2.57%
1713	6,770	164.8	2.43%
1911	4,720	190.7	4.04%

Field Average = 4.60%

1709	3,100	62.0	2.00%
------	-------	------	-------

Ultimate primary reserves = 62.0 MSTBO

Cumulative production = 5.0 MSTBO

Remaining primary reserves = 57.0 MSTBO

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Flood Factor Scenarios

in the

Avalon (Delaware) Field







Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Flood Factor Scenarios

in the

Avalon (Delaware) Field



Effect of Revised Flood Patterns

on

Recoverable Reserves

Avalon (Delaware) Field

Tract	Report		Proposed	
	Flood Factor	CO2 Reserves (MSTBO)	Flood Factor	CO2 Reserves (MSTBO)
1109	0.25	265.4	0.50	530.80
1111	0.50	530.6	0.75	795.90
1113	0.25	446.7	0.50	893.40
1309	0.50	607.3	0.75	910.95
1315	0.25	362.5	0.50	725.00
1509	0.50	579.0	0.75	868.50
1517	0.25	247.4	0.50	494.80
1719	0.25	203.9	0.50	407.80
1921	0.25	143.8	0.50	287.60
2109	0.25	91.4	0.50	182.80
2123	0.25	51.5	0.50	103.00
2323	0.50	120.1	0.75	180.15
2513	0.50	219.4	0.75	329.10
2523	0.25	19.5	0.50	39.00
Totals =		3,888.5		6,748.8

Exhibit No.: _____
Operator: Premier Oil & Gas, Inc.
Case No.: 11298
Date: December 14, 1995

Example Reservoir Pressure Profile

Producing Well




Exhibit No.:

Operator: Premier Oil & Gas, Inc.

Case No.: 11298

Date: December 14, 1995

Avalon (Delaware) Field
Listing of Potential Tract Participation Factors
Using Premier HCPV Maps

Parameter		Premier Acreage	Exxon Acreage	Yates Acreage	MWJ Acreage	Field Total
Original Oil in Place (MSTBO)	Tract Value	15.35	146.70	83.11	4.91	250.07
	% of Field Total	6.14%	58.66%	33.23%	1.96%	100.00%
January 1993 Oil Production Rate (BOPM)	Tract Value	0	13,244	3,450	54	16,748
	% of Field Total	0.00%	79.08%	20.60%	0.32%	100.00%
Remaining Primary Reserves (MSTBO)	Tract Value	57.00	1,289.20	1,370.10	0.70	2,717.00
	% of Field Total	2.10%	47.45%	50.43%	0.03%	100.00%
Waterflood Reserves (MSTBO)	Tract Value	0.00	4,595.8	2,200.9	0.0	6,796.7
	% of Field Total	0.00%	67.62%	32.38%	0.00%	100.00%
CO2 Reserves (MSTBO)	Tract Value	2,655.1	24,416.4	15,670.0	165.8	42,907.3
	% of Field Total	6.19%	56.90%	36.52%	0.39%	100.00%
Future Barrels Produced (MSTBO)	Tract Value	2,712.1	30,301.4	19,241.0	166.5	52,420.9
	% of Field Total	5.17%	57.80%	36.70%	0.32%	100.00%
Proposed Participation Factor (50% OOIP, 10% 1/93 Rate, 20% Rem Primary, 20% Future Prod)		4.52%	58.29%	36.10%	1.08%	100.00%

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

*Priemer
Exhibits
1-40 +*

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

GULF OIL EXPLORATION & PRODUCTION COMPANY

EDDY "FV" NO. 3

AVALON (DELAWARE) FIELD

EDDY COUNTY, NEW MEXICO

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. ____
Submitted By: 5-A
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995



March 3, 1984

GULF OIL EXPLORATION & PRODUCTION COMPANY
P.O. Box 670
Hobbs, New Mexico 88240

File : 3202-14008
Subject: Core Analysis
Eddy "FV" No. 3
Avalon Field
Eddy County, New Mexico

Gentlemen:

Sidewall Core Analysis was made on 10 sidewall core samples received from Schlumberger.

Fluid removal and fluid saturations were determined using Dean Stark techniques.

Gas expansion porosity and grain density were determined using Boyle's Law.

Gas detections was measured using a "Hot Wire Gas Detector" on gas in the sealed jars.

Permeability values for percussion type sidewall cores are determined empirically.

Descriptions and fluorescence were visually determined microscopically.

The samples are being held at our Midland lab as we await further disposition instructions.

We trust these data will be useful in the evaluation of your property and thank you for the opportunity of serving you.

Very truly yours,

CORE LABORATORIES, INC.

A handwritten signature in black ink, reading "Jack H. Neff". The signature is written in a cursive, flowing style.

Jack H. Neff
Laboratory Manager

JHN/do/yn

Petroleum Reservoir Engineering
DALLAS, TEXAS

CORE ANALYSIS REPORT

FOR

GULF OIL EXPL. & PROD. CO.

EDDY "FV" NO. 3
AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO

REC IN	DEPTH FEET	PERM(Ka) MD(*)	FLD POR	OIL% WTR% FORE FORE	PROB PROD	OIL% BULK	GAS% BULK	GAS DET	DESCRIPTION
0.1	2591.5	0.18	11.8	5.0 65.0	OIL	0.6	3.5	2	SD VFG LT-GRY
0.5	2714.0	310.	28.0	25.9 67.7	OIL	7.3	1.8	75	SD VFG LT-GRY-WH
0.1	2739.0							65	NA SD VFG LT-GRY TBFA
0.5	2744.0	48.	23.8	8.9 57.1	OIL	2.1	8.1	55	SD VFG LT-GRY SHY
0.3	2745.0	315.	28.1	9.1 50.7	OIL	2.6	11.3	50	SD VFG LT-GRY
0.1	2746.0							45	NA SD VFG LT-GRY TBFA
0.1	2747.0							40	NA SD VFG LT-GRY TBFA
0.1	2781.0							90	NA SD VFG LT-GRY-WH TBFA
0.1	2783.0							95	NA SD VFG LT-GRY-WH TBFA
0.5	2869.0	22.	22.6	0.0 82.4	WTR	0.0	4.0	20	SD VFG LT-GRY
0.8	2873.0	400.	29.2	0.0 88.8	WTR	0.0	3.3	20	SD VFG LT-GRY
0.3	2878.0	35.	23.6	3.4 54.8	OIL	0.8	9.6	20	SD VFG LT-GRY-WH
0.1	3488.0							0	NA SD CONTAMINATE TBFA
0.1	3501.0							0	NA SD CONTAMINATE TBFA
0.1	3507.0							0	NA SD CONTAMINATE TBFA
0.1	3758.0	14.	20.8	0.0 66.7	WTR	0.0	6.9	0	SD VFG LT-GRY
0.1	3767.0							0	NA SD VFG LT-GRY TBFA
0.1	3845.0							0	NA SD VFG LT-GRY TBFA
0.3	3850.0	6.0	19.4	0.0 72.5	WTR	0.0	5.3	20	SD VFG LT-GRY-WH
0.1	3934.0							0	NA SD VFG LT-GRY-WH TBFA
0.1	3936.0							0	NA SD VFG LT-GRY-WH TBFA
0.3	4829.5	0.70	8.7	0.0 81.1	WTR	0.0	1.6	0	LM VFXLN DK-BRN VF
0.1	4880.0							20	NA LM DK-BRN-BLK V/SHY
0.1	4886.0							40	NA LM DK-BRN-BLK V/SHY
0.1	4949.5							10	NA LM BLK-DK-BRN V/SHY
0.1	4950.0							0	NA LM BLK-DK-BRN V/SHY

(*) Permeability values for percussion type sidewall cores determined empirically.

These analyses, opinions or interpretations are based on observations and materials supplied by the client to whom, and for whose exclusive and confidential use, this report is made. The Interpretations or expressed represent the best judgment of Core Laboratories, Inc. (all errors and omissions excepted), but Core Laboratories, Inc. and its officers and employees, assume no responsibility and make no warranty representations, as to the productivity, proper operations, or profitability of any oil, gas or other mineral well or land in connection with which such report is used or relied upon.

CORE LABORATORIES, INC.
Petroleum Reservoir Engineering
DALLAS, TEXAS

PAGE 1

GULF OIL EXPL. & PROD. CO.
EDDY "FV" NO. 3
AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO

DATE : 3-31-84
FORMATION : DELAWARE SD.
URLG. FLUID: BRINE WATER
LOCATION : 660' FSL & 330' FEL, SEC. 25, CORES
T-20-S, R-27-E

FILE NO : 3202-14008
LABORATORY: MIDLAND, TEXAS
ANALYSTS : REINHEIMER
: SCHLUMBERGER

SIDEWALL CORE ANALYSIS

REC IN	DEPTH FEET	PERM(Ka) MD(*)	FLD POR	OIL% PORE	WTR% PORE	PROD	OIL% BULK	GAS% BULK	GAS DET	DESCRIPTION
0.1	2591.5	0.18	11.8	5.0	65.0	OIL	0.6	3.5	2	SD VFG LT-GRY
0.5	2714.0	310.	28.0	25.9	67.7	OIL	7.3	1.8	75	SD VFG LT-GRY-WH
0.1	2739.0								65	NA SD VFG LT-GRY TBFA
0.5	2744.0	48.	23.8	8.9	57.1	OIL	2.1	8.1	55	SD VFG LT-GRY SHY
0.3	2745.0	315.	28.1	9.1	50.7	OIL	2.6	11.3	50	SD VFG LT-GRY
0.1	2746.0								45	NA SD VFG LT-GRY TBFA
0.1	2747.0								40	NA SD VFG LT-GRY TBFA
0.1	2781.0								90	NA SD VFG LT-GRY-WH TBFA
0.1	2783.0								95	NA SD VFG LT-GRY-WH TBFA
0.5	2869.0	22.	22.6	0.0	82.4	WTR	0.0	4.0	20	SD VFG LT-GRY
0.8	2873.0	400.	29.2	0.0	88.8	WTR	0.0	3.3	20	SD VFG LT-GRY
0.3	2878.0	35.	23.6	3.4	54.8	OIL	0.8	9.6	20	SD VFG LT-GRY-WH
0.1	3488.0								0	NA SD CONTAMINATE TBFA
0.1	3501.0								0	NA SD CONTAMINATE TBFA
0.1	3507.0								0	NA SD CONTAMINATE TBFA
0.1	3758.0	14.	20.8	0.0	66.7	WTR	0.0	6.9	0	SD VFG LT-GRY
0.1	3767.0								0	NA SD VFG LT-GRY TBFA
0.1	3845.0								0	NA SD VFG LT-GRY TBFA
0.3	3850.0	6.0	19.4	0.0	72.5	WTR	0.0	5.3	20	SD VFG LT-GRY-WH
0.1	3934.0								0	NA SD VFG LT-GRY-WH TBFA
0.1	3936.0								0	NA SD VFG LT-GRY-WH TBFA
0.3	4829.5	0.70	8.7	0.0	81.1	WTR	0.0	1.6	0	LM VFXLN DK-BRN VF
0.1	4880.0								20	NA LM DK-BRN-BLK V/SHY
0.1	4886.0								40	NA LM DK-BRN-BLK V/SHY
0.1	4949.5								10	NA LM BLK-DK-BRN V/SHY
0.1	4950.0								0	NA LM BLK-DK-BRN V/SHY

(*) Permeability values for percussion type sidewall cores determined empirically.

LITHOLOGICAL ABBREVIATIONS

ANH(Y)	ANHYDRITE, ANHYDRITIC	LM(Y)	LIMESTONE, LIMY
ARK	ARKOSE, ARKOSIC	MG	MEDIUM GRAINED
BAN	BAND, BANDED	MTX	MATRIX
BREG	BRECCIA, BRECCIATED	NA	INTERVAL NOT ANALYZED (AT REQUEST OF CLIENT)
CALC	CALCITE, CALCAREOUS	NOD	NODULE, NODULAR
CARB	CARBONACEOUS	OOL	OOLITIC
CG	COARSE GRAINED	PISO	PISOLITIC
CHK(Y)	CHALK, CHALKY	PP	PINPOINT POROSITY
CHT(Y)	CHERT, CHERTY	PT	PARTING
CONGL	CONGLOMERATE, CONGLOMERITIC	PYR	PYRITE, PYRITIC
CXLN	COARSELY CRYSTALLINE	SD(Y)	SANDSTONE, SANDY
DNS	DENSE	SH(Y)	SHALE, SHALY
DOL(C)	DOLOMITE, DOLOMITIC	SHR	SOLID HYDROCARBON RESIDUE
F	RANDOMLY ORIENTED FRACTURES	SL/	SLIGHTLY
FG	FINE GRAINED	SLT(Y)	SILT, SILTY
FOSS	FOSSILIFEROUS	STY	STYLOLITE, STYLOLITIC
FR	FRIABLE	SUC	SUCROSLIC
FXLN	FINELY CRYSTALLINE	SUL	SULPHUR
GAL	GALENA	TBFA	TOO BROKEN FOR ANALYSIS
GLAUC	GLAUCONITE, GLAUCONITIC	TRIP	TRIPOLITE
GRAN	GRANITE	V/	VERY
GYP	GYPNUM, GYPSIFEROUS	VF	PREDOMINANTLY VERTICALLY FRACTURED
HF	PREDOMINANTLY HORIZONTALLY FRACTURED	V	VUGULAR
INC	INCLUSION	XBD	CROSSBEDDED
INTBD	INTERBEDDED	XLN	MEDIUM CRYSTALLINE
LAM	LAMINATED	XTL	CRYSTAL

THE FIRST WORD IN THE DESCRIPTION COLUMN OF THE CORE ANALYSIS REPORT DESCRIBES THE ROCK TYPE. FOLLOWING ARE ROCK MODIFIERS IN DECREASING ABUNDANCE AND MISCELLANEOUS DESCRIPTIVE TERMS.

CORE LABORATORIES, INC.
Petroleum Reservoir Engineering
DALLAS, TEXAS

GULF OIL EXPL. & PROD. CO.
EDDY "FV" NO. 3
EDDY COUNTY, NEW MEXICO

DATE : 3-31-84
FIELD: AVALON (DELAWARE) FIELD

FILE NO: 3202-14008
ANALYST: REINHEIMER

DISTRIBUTION OF FINAL REPORTS


COPIES TO:

3 cc GULF OIL EXPL. & PROD. CO.
P.O. BOX 670
HOBBS, NM 88240
ATTN: MR. A.N. BUDGE

1 cc MR. ARNOLD BOUMA
P.O. BOX 37048
HOUSTON, TEXAS 77236

1 cc GULF OIL EXPL. & PROD. CO.
P.O. BOX 1150
MIDLAND, TEXAS 79702
ATTN: MR. C.D. STENBURG

3 cc AMOCO PRODUCTION COMPANY
EXPLORATION DEPARTMENT
P.O. BOX 3092
HOUSTON, TEXAS 77253
ATTN: MR. R.L. EVANS



R26E

BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 2
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

R27E

PREMIER OIL & GAS, INC.

**UPPER CHERRY CANYON
THICKNESS
DOWNLAP - BASE INTERVAL**

AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO
CONTOUR INTERVAL: 25 FEET
SCALE: 2000 FEET / INCH


GEOLOGY BY: G. E. HARRINGTON

JUNE, 1995

900


(25 ft)
30 mi

2181
30
2751



46

2738




2943 -14

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. 5
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

1.048

3 mi
3.2 mi
1.3
1.5
2.0
2.7
1.4
1.3
1.25 -26 65
1.2
1.1
1.2
1.2
1.1
3
1.8
2.4
1.75
1.8

8
33 mi



PREMIER OIL & GAS, INC.


UPPER CHERRY CANYON THICKNESS DOWNLAP - BASE INTERVAL

AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO
CONTOUR INTERVAL: 25 FEET
SCALE: 2000 FEET / INCH

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. 6
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

GEOLOGY BY: G. E. HARRINGTON NOVEMBER, 1995

UPPER CHERRY CANYON - Gross Thickness




WELL STATUS SYMBOL LEGEND


- PRODUCING OIL WELL
- SHUT IN OIL WELL
- TEMPORARILY ABANDONED OIL WELL
- ABANDONED OIL WELL
- ✱ PRODUCING GAS WELL
- ✱ TEMPORARILY ABANDONED GAS WELL
- ✱ ACTIVE INJECTION WELL
- ✱ SALT WATER INJECTION WELL
- ✱ SALT WATER DISPOSAL WELL
- ✱ DRY HOLE
- ✱ DRY HOLE, JUNKED AND ABANDONED
- ✱ ABANDONED LOCATION

NOTE: ABOVE SYMBOLS ARE ACTUAL SIZE FOR WELLS USED FOR CONTAINING. SMALL SYMBOLS REFLECT WELLS NOT USED IN CREATING THIS MAP.

Map 7



**BEFORE THE
OIL CONSERVATION COMMISSION**
Case No. 11298 DeNovo Exhibit No. **6-A**
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995



PREMIER OIL & GAS, INC.

UPPER CHERRY CANYON HYDROCARBON POROSITY THICKNESS

AVALON (DELAWARE) FIELD
EDDY COUNTY, NEW MEXICO


CONTOUR INTERVAL: 2

SCALE: 2000 FEET / INCH

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. **7**
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

GEOLOGY BY: G. E. HARRINGTON NOVEMBER, 1995

UPPER CHERRY CANYON - Hydrocarbon Porosity Thickness



**UPPER CHERRY CANYON
WATERFLOOD TARGET OIL
IN PLACE (KBO)**

JUNE, 1995

PAUL: WHILE

DRILLING TIME & SAMPLE LOG


GERALD E. HARRINGTON
P.O. Box 216

GEOLOGICAL CONSULTANT
Roswell, New Mexico

OPERATOR: GULF OIL EXPLORATION AND PRODUCTION COMPANY
WELL: EDDY "FV" STATE #3
FIELD: AVALON DELAWARE COUNTY: EDDY STATE: NEW MEXICO

LOCATION: Section 25 Twp 20-S Rge 27-E Elev. KB 3315.5
Footage 660' FSL & 330' FEL DF 3314.5
TD: 4975 CASING: GL 3302.5
BIT SIZE: CONTRACTOR:

REMARKS: DRILLING TIME - MINUTES/ 5 FEET



BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 10
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit

LARGE FORMAT
EXHIBIT HAS
BEEN REMOVED
AND IS LOCATED
IN THE NEXT FILE

KELLAHIN AND KELLAHIN

ATTORNEYS AT LAW

EL PATIO BUILDING

117 NORTH GUADALUPE

POST OFFICE BOX 2265

SANTA FE, NEW MEXICO 87504-2265

W. THOMAS KELLAHIN*

*NEW MEXICO BOARD OF LEGAL SPECIALIZATION
RECOGNIZED SPECIALIST IN THE AREA OF
NATURAL RESOURCES-OIL AND GAS LAW

JASON KELLAHIN (RETIRED 1991)

TELEPHONE (505) 982-4285
TELEFAX (505) 982-2047

December 11, 1995

HAND DELIVERED

Mrs. Jamie Bailey
Office of the Commissioner of Public Lands
State Land Office Building
310 Old Santa Fe Trail
Santa Fe, New Mexico 87501

RECEIVED

DEC 11 1995

Oil Conservation Division

Re: *NMOCD Cases 11297 and 11298*
Application of Exxon Corporation for Waterflood Project,
Carbon Dioxide Project and Statutory Unitization
Avalon-Delaware Unit, Eddy County, New Mexico

Dear Mrs. Bailey:

On December 14, 1995, the New Mexico Oil Conservation Commission is scheduled to hearing the subject case which involves Exxon's desire to include State of New Mexico Oil & Gas Lease No. K-6527-1 (E/2E/2 of Section 25, T20S, R27E) in both its proposed waterflood project and its carbon dioxide flood project.

My client is Premier Oil & Gas Inc. who is the current lessee of this lease and who is opposed to its inclusion in the unit.

I am aware that your responsibilities as an employee of the Commissioner of Public Lands ("Land Office") have involved gathering information and making recommendations concerning whether it is in the best interests of the Land Office to include certain State of New Mexico oil & gas leases in units such as this.

While I have the greatest respect for your expertise and your professionalism, I am concerned that your responsibilities to the Land Office this particular case have created a conflict of interest which would preclude you from participating as a member of the Oil Conservation Commission.


BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. **A**
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

Mrs. Jamie Bailey
December 11, 1995
Page 2

The Land Office has already granted preliminary approval of this unit which includes the disputed tract. Should you ultimately decide in favor of my client, then your actions would be contrary to the decision made by the Land Office.

I would appreciate knowing (a) if you have any reservations about participating in this case, and (b) if you have had any personal involvement on behalf of the Land Office with this unitization effort by Exxon. If so, can you ignore that past involvement and decide this case regardless of the affect that decision might have upon the Land Office and its prior approval to include this tract in this unit.

Very truly yours,

A handwritten signature in black ink, appearing to read 'W. Thomas Kellahin', written over the closing 'yours,'.

W. Thomas Kellahin

cc: Ken Jones (Premier)
cc: William J. LeMay (Chairman-OCC)
cc: *Jim Bruce, Esq. (Exxon)*
cc: *William F. Carr, Esq. (Yates)*



RAY POWELL, M.S., D.V.M.
COMMISSIONER

State of New Mexico
Commissioner of Public Lands

310 OLD SANTA FE TRAIL P.O. BOX 1148
SANTA FE, NEW MEXICO 87504-1148

Legal Division
(505) 827-5713
Fax (505) 827-5833

December 13, 1995

VIA FACSIMILE & U.S. MAIL

W. Thomas Kellahim, Esq.
Kellahin & Kellahin
117 North Guadalupe
P.O. Box 2265
Santa Fe, NM 87504-2265

Re: *NMOCD cases 11297 and 11298, Application of Exxon Corporation for Waterflood Project, Carbon Dioxide Project and Statutory Unitization Avalon-Delaware Unit, Eddy County, New Mexico*

Dear Mr. Kellahin:

Your letter of December 11, 1995 to Jami Bailey has been referred to me for reply. In your letter you raise certain questions about Ms. Bailey's participation in a State Land Office decision to approve this particular Unit. You are concerned that her participation may have created a conflict of interest precluding her from sitting on the Oil Conservation Commission as the Commissioner of Public Lands' designee. See Sec. 70-2-4 NMSA 1978.

We share your concern that procedural due process of law be accorded parties appearing before this agency and any others on which a designee of the Commissioner sits. We are mindful of our responsibilities to the public in this regard. See *Santa Fe Exploration Co. v. Oil Conservation Comm'n*, 114 NM 103 (S.Ct. 1992).

In this instance Ms. Bailey and I are satisfied that she can participate as a member of the Commission and hear the matter with complete professionalism and impartiality. In response to the first two questions you pose in your letter, Ms. Bailey has no reservations about participating in this case. Any decision she may make as the Commissioner's designee will be based on the evidence in the record of the case. She had very little personal involvement in the Land Office process concerning this particular unitization. She attended one meeting internally and as a formality signed a letter of preliminary approval prepared by staff. The documents

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. **B**
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

10.
DEC 13 1995 16:20 NO.005 P.04
W. Thomas Kellahin, Esq.

Page 2

December 13, 1995

concerning the unitization in question are, of course, public records and you are free to examine them if you wish. In that event please call me at 827-5715 to arrange a time for you to inspect the documents.

Your letter is the first occasion that this particular conflict of interest question has come to my attention. As you may know, I have been general counsel here for a relatively short time, and I am continually discovering new areas requiring legal attention. This is one of them.


It seems to me that the Legislature created a statutory conflict of interest, or at least a potential one, when it provided for the Commissioner to participate as a member of the Oil Conservation Commission under Sec. 70-2-4 NMSA 1978. It seems to me that the Legislature was concerned enough for the welfare and protection of public lands that, as a secondary consequence of its action, it created this form of institutional conflict. One of the purposes of having the Commissioner of Public Lands or his designee on the Oil Conservation Commission is to look after the interests of public land trust beneficiaries. There is nothing, of course, that the Land Office can do about this legislative framework.

At the same time, however, as we stated earlier, we do recognize that parties litigating before the Oil Conservation Commission are entitled to have their constitutional rights, including procedural due process, respected. As a transactional matter, this means that the Commissioner's designee should be free from bias and prejudgment. We are satisfied that such is the case with Ms. Bailey in this case. In addition, as to the future, we will try to make sure that the Commissioner's designee has not participated in the Land Office decision or transaction that is the subject of the Oil Conservation Commission hearing. The issues before the Land Office may be different from the questions before the Commission, which would mean that participating in a Land Office decision would not preclude a designee from hearing a different issue, albeit arising out of the same facts, before a different administrative body. We haven't researched this issue at this point, partly in the interest of turning around your letter request as soon as possible. We understand that you have a hearing in this matter before the Oil Conservation Commission tomorrow and we would not want to delay that by our review. In any case, we think it is the wiser choice for the Land Office to simply avoid any transactional conflict whenever it can by making sure the Commissioner's designee has not worked directly on the matter before the Commission.

W. Thomas Kellahin, Esq.
Page 3
December 13, 1995

If there is anything further we can do for you on this matter, please give me a call.



Sincerely,



Jan Unna
General Counsel

JU/jc

cc: Jami Bailey
Rand Carroll, Esq.



CARDINAL



SURVEYS COMPANY

GAMMA-TROL

Well No. 4808	COMPANY GULF OIL EXPLORATION & PRODUCTION COMPANY	
	WELL EDDY "EV" STATE #3	
	FIELD AVALON DELAWARE	
	COUNTY EDDY	STATE NEW MEXICO
	Location: 660' FSL & 330' FEL	Other Service
	Sec. 25 Twp. 20-S Rge. 27-E	
Permit Date	G.I.	Elev. 3302.5'
Measured From	K.B.	DF 3316.5'
Measured From	K.B.	GL 3302.5'
Date	4-14-84	
Driller	CLE	
Logger	3300	
Logged Interval	3300	
Logged Interval	2500	
Fluid in Hole	WATER	
Temp. Rec. Temp. Deg. F		
Recorded By	SCOTT	
Witnessed By	MR. MOORE	
Tool Size	1 3/8"	
Tool Configuration	COIL/TAMP	
Tool Size	8 5/8" (C&S) FROM 1-14-84 TO 1 1/2" (15.5") FROM 0-1075	
Tool Size	2 7/8" FROM SURFACE TO 2617'	

TREATMENT REPORT:

CONCLUSION: GAMMA RAY AND TEMPERATURES INDICATE TREATED INTERVAL FROM 2710'-2740', AND CHANNEL UP TO 2665'.

BEFORE THE
OIL CONSERVATION COMMISSION
Case No. 11298 DeNovo Exhibit No. ____
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: December 14, 1995

AVALON (DELAWARE) UNIT
BY WELL RESERVES

*** RUR AS OF 1/1/93 ***

*** EUR AND RUR UNITS ARE KBO ***

UNIT WELL NUMBER	----- PRIMARY -----		--- WORKOVERS ---		--- WATERFLOOD ---		--- CO2 FLOOD ---	
	RUR	EUR	EUR	DELTA	EUR	DELTA	EUR	DELTA
1109	0.0	0.0	0.0	0.0	0.0	0.0	296.9	296.9
1111	0.0	0.0	266.6	266.6	411.9	145.3	1043.9	632.0
1113	0.0	0.0	0.0	0.0	0.0	0.0	548.2	548.2
1309	0.0	0.0	0.0	0.0	0.0	0.0	763.2	763.2
1311	27.2	163.6	377.2	213.6	661.9	284.6	2604.2	1942.3
1313	18.1	137.1	278.7	141.6	571.0	292.3	1878.6	1307.6
1315	0.0	0.0	0.0	0.0	0.0	0.0	498.6	498.6
1509	0.0	0.0	0.0	0.0	0.0	0.0	720.1	720.1
1511	53.4	137.1	303.5	166.4	572.3	268.8	1790.3	1218.0
1513	33.8	154.6	371.4	216.8	921.8	550.5	2921.9	2000.0
1515	0.0	1.7	1.7	0.0	1.7	0.0	882.2	880.5
1517	0.0	0.0	0.0	0.0	0.0	0.0	294.6	294.6
1709	0.0	5.1	5.1	0.0	5.1	0.0	280.1	275.1
1711	19.3	127.6	127.6	0.0	291.2	163.7	1367.7	1076.4
1713	40.3	164.8	164.8	0.0	647.1	482.3	2338.6	1691.5
1715	20.2	66.3	118.8	52.6	225.0	106.2	1039.2	814.2
1717	0.0	0.0	68.8	68.8	84.9	16.1	578.9	494.0
1719	0.0	0.0	0.0	0.0	0.0	0.0	242.7	242.7
1909	0.0	0.0	0.0	0.0	0.0	0.0	345.5	345.5
1911	66.4	190.7	190.7	0.0	419.0	228.3	2006.4	1587.4
1913	80.9	268.8	268.8	0.0	863.2	594.4	2557.4	1694.2
1915	160.9	356.4	470.7	114.2	1456.1	985.4	3682.4	2226.3
1917	53.0	233.8	233.8	0.0	379.4	145.6	1063.9	684.5
1919	24.1	68.4	68.4	0.0	80.1	11.7	529.2	449.1
1921	0.0	0.0	0.0	0.0	0.0	0.0	151.8	151.8
2016	45.6	45.6	45.6	0.0	45.6	0.0	45.6	0.0
2109	0.0	0.0	0.0	0.0	0.0	0.0	84.5	84.5
2111	50.7	138.9	138.9	0.0	209.5	70.6	1310.9	1101.4
2113	120.3	360.8	424.3	63.5	908.1	483.8	2349.3	1441.2
2115	38.0	257.6	257.6	0.0	666.8	409.2	2665.0	1998.2
2117	76.6	275.8	275.8	0.0	829.3	553.5	2956.9	2127.6
2119	126.9	258.2	258.2	0.0	524.9	266.6	1515.8	991.0
2121	0.0	0.0	0.0	0.0	0.0	0.0	335.8	335.8
2123	0.0	0.0	0.0	0.0	0.0	0.0	55.3	55.3
2309	0.4	10.9	10.9	0.0	10.9	0.0	50.5	39.6
2311	19.3	150.6	150.6	0.0	285.7	135.1	1367.3	1081.6
2313	56.7	199.5	199.5	0.0	474.2	274.7	1534.8	1060.7
2315	0.0	22.7	76.8	54.1	119.8	42.9	632.9	513.1
2317	0.0	29.5	41.8	12.3	49.5	7.7	938.8	889.3
2319	29.3	173.6	175.7	2.2	315.8	140.0	1056.4	740.6
2321	3.1	23.2	76.1	52.9	127.7	51.6	969.4	841.7
2323	0.0	0.0	0.0	0.0	0.0	0.0	149.5	149.5
2509	0.3	6.0	6.0	0.0	6.0	0.0	140.2	134.1
2511	0.0	11.9	11.9	0.0	11.9	0.0	542.2	530.2
2513	0.0	0.0	0.0	0.0	0.0	0.0	215.7	215.7
2515	0.0	0.0	0.0	0.0	0.0	0.0	430.0	430.0
2517	0.0	24.6	41.4	16.8	55.5	14.1	514.6	459.2
2519	22.5	114.1	139.6	25.5	215.8	76.2	936.6	720.8
2521	0.0	0.0	0.0	0.0	0.0	0.0	365.0	365.0
2523	0.0	0.0	0.0	0.0	0.0	0.0	22.1	22.1
2709	0.0	3.1	3.1	0.0	3.1	0.0	199.8	196.7
2711	0.0	0.0	0.0	0.0	0.0	0.0	251.8	251.8
2717	0.0	0.0	0.0	0.0	0.0	0.0	99.5	99.5
2719	0.0	0.0	0.0	0.0	0.0	0.0	138.9	138.9
2721	0.0	0.0	0.0	0.0	0.0	0.0	32.7	32.7
TOTAL	1187.4	4182.4	5650.5	1468.1	12451.7	6801.2	52334.5	39882.8

Exhibit G-19

ExH 9

Case 11298
Premier Oil & Gas

DRILLING TIME & SAMPLE LOG

GERALD E. HARRINGTON
P.O. Box 216

GEOLOGICAL CONSULTANT
Roswell, New Mexico

OPERATOR: GULF OIL EXPLORATION AND PRODUCTION COMPANY

WELL: EDDY "FV" STATE #3

FIELD: AVALON DELAWARE COUNTY: EDDY STATE: NEW MEXICO


LOCATION: Section 25 Twp 20-S Rge 27-E Elev. KB 3315.5

Footage 660' FSL & 330' FEL DF 3314.5

TD: 4975 CASING: GL 3302.5

BIT SIZE: CONTRACTOR:

REMARKS: DRILLING TIME - MINUTES/ 5 FEET



BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 10
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

DRILLING TIME & SAMPLE LOG

GERALD E. HARRINGTON
P.O. Box 216

GEOLOGICAL CONSULTANT
Roswell, New Mexico

OPERATOR: GULF OIL EXPLORATION AND PRODUCTION COMPANY

WELL: EDDY "FV" STATE #3

FIELD: AVALON DELAWARE COUNTY: EDDY STATE: NEW MEXICO


LOCATION: Section 25 Twp 20-S Rge 27-E Elev. KB 3315.5

Footage 660' FSL & 330' FEL DF 3314.5

TD: 4975 CASING: GL 3302.5

BIT SIZE: CONTRACTOR:

REMARKS: DRILLING TIME - MINUTES/ 5 FEET



BEFORE THE
OIL CONSERVATION DIVISION
Case No. 11298 Exhibit No. 10
Submitted By:
PREMIER OIL & GAS INC.
Hearing Date: June 29, 1995

NO. OF COPIES RECEIVED	6
DISTRIBUTION	
SANTA FE	1
FILE	1
U.S.G.S.	2
LAND OFFICE	1
OPERATOR	1

NEW MEXICO OIL CONSERVATION COMMISSION

AUG 2 1977

C.E.C.

30-015-22235
Form C-101
Revised 1-1-65

5A. Indicate Type of Lease	STATE ☒ FEE ☐
5. State Oil & Gas Lease No.	K-5115

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work b. Type of Well OIL WELL ☒ GAS WELL ☐ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐	DRILL ☒ DEEPEN ☐ PLUG BACK ☐	7. Unit Agreement Name	8. Farm or Lease Name Stonewall "EP" Sta
2. Name of Operator Yates Petroleum Corporation ✓	3. Address of Operator 207 South 4th Street - Artesia, NM 88210	9. Well No. 3	10. Field and Pool, or Wildcat Wildcat Delaware
4. Location of Well UNIT LETTER N LOCATED 545 FEET FROM THE South LINE AND 1960 FEET FROM THE West LINE OF SEC. 19 TWP. 20S RGE. 28E NMPM	11. Proposed Depth Approx 4800'	12. County Eddy	19A. Formation Delaware
21. Elevation (Show whether L.P., K.T., etc.) 3300' GR	21A. Kind & Status Plug, Bond Blanket	21B. Drilling Contractor Byrd Drilling Co.	22. Approx. Date Work will start August 2, 1977

PROPOSED CASING AND CEMENT PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
17½"	13-3/8"	61#	Approx 550'	350 sx	Circulate
12½ or 11"	8-5/8"	24#	" 2900'	1000 sx	Circulate
7-7/8"	5½"	15.5#	" 4800'	200 sx	3800'

Propose to drill a Brushy Canyon oil test to approx 4800'. Surface casing will be set at about 550' and cement circulated. Intermediate casing will be set at about 2900' and cement circulated. Will log well, case, perforate and stimulate as needed for production.

Mud Program: - FW Gel and LCM to 2900', native mud to 4300', Lo fluid loss gel mud to TD.

BOP Program: - 10" Series 900 BOP's will be installed on 8-5/8" casing and tested.

APPROVAL VALID
FOR 90 DAYS UNLESS
DRILLING IS COMPLETED

EXPIRES 11-3-77

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM. IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW PRODUCTIVE ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

Signed Eddie M. Maltby Title Engineer Date 8-1-77

(This space for State Use)

APPROVED BY W. A. Gressett TITLE SUPERVISOR, DISTRICT II DATE AUG 3 1977

CONDITIONS OF APPROVAL, IF ANY:

NE MEXICO OIL CONSERVATION COMMISSION
WELL LOCATION AND ACREAGE DEDICATION PLAT

Form C-102
Supersedes C-128
Effective 1-1-65

All distances must be from the outer boundaries of the Section.


Operator Yates Petroleum Corp		Lease Stonewall "EP" State		Well No. 3
Unit Letter N	Section 19	Township 20-S	Range 28-E	County Eddy
Actual Footage Location of Well: 545 feet from the South line and 1960 feet from the West line				
Ground Level Elev: 3300'	Producing Formation Delaware	Pool Wildcat	Dedicated Acreage: 40 Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

☐ Yes ☐ No If answer is "yes," type of consolidation _____

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) _____

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Eddie M. Mahfood

Name
Eddie M. Mahfood

Position
Engineer

Company
Yates Petroleum Corp.

Date
7-29-77

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

7-29-77

Date Surveyed
Eddie M. Mahfood



Registered Professional Engineer
and/or Land Surveyor

Certificate No. **4605**

AVALON (DELAWARE) UNIT

GEOLOGIC OVERVIEW

PERMIAN BASIN
PRINCIPAL GEOLOGIC PROVINCES



PRODUCTIVE
INTERVALS

*No Bell Corp's
interest in this
area*


RESERVOIR DESCRIPTION

PRODUCING FORMATION	UPPER CHERRY CANYON	LOWER CHERRY CANYON/ UPPER BRUSHY CANYON
DEPTH	2600 FT	3400 FT
RESERVOIR LITHOLOGIES	SAND	SAND & SILTSTONE
NET THICKNESS	131 FT	272 FT
AVERAGE POROSITY	14.4%	14.8%
AVERAGE PERMEABILITY	2.3 md	1.1 md
OIL ORIGINALLY IN PLACE	107 MMBO	141 MMBO

MM = Million

AVALON (DELAWARE) UNIT

STRATIGRAPHY



DATABASE

- 4 cored wells
- 71 wells with modern-vintage digital log data
- 35 wells with mudlog data
- 13 wells with dipmeter information
- Production data from 32 wells




Exhibit No. **12**
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

June, 1995

NMOCD Hearing

EXXON
Yates "C" Federal #36

Type log

31-205-28E





Exhibit No. 13
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995


AVALON (DELAWARE) UNIT

**BRUSHY CANYON FORMATION
SCHEMATIC CROSS SECTION**




AVALON (DELAWARE) UNIT

**UPPER CHERRY CANYON
SCHEMATIC CROSS SECTION**



AVALON (DELAWARE) UNIT


**LOWER CHERRY/UPPER BRUSHY CANYON
TOP STRUCTURE MAP**



Proposed Unit Area

● Wells

— Limits of Proven Primary Production



NMOCD Hearing


June, 1995

Exhibit No. 17

**Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995**


AVALON (DELAWARE) UNIT

**UPPER CHERRY CANYON
TOP STRUCTURE MAP**



Proposed Unit Area

● Wells
— Limits of Proven Primary Production




NMOCD Hearing

June, 1995

Exhibit No. 18
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

AVALON (DELAWARE) UNIT

AVALON UNIT TRACT MAP



Delaware Oil Completions

-  Delaware (UCC/UBC) Completion
Currently Active
-  Delaware Completion
UCC/UBC shut-in or has never
produced from UCC or UBC

PROPOSED UNIT AREA



NMOCD Hearing


June, 1995

Exhibit No. **19**
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

AVALON (DELAWARE) UNIT

BASE MAP

*25 producers
in proposed unit*



Proposed Unit Area

- Wells Owned by Unit
- Wells Owned by Unit (Injector)
- Other Wells

Note: See Map 1, Technical Report for lease/well designations


NMOCD Hearing

June, 1995


Exhibit No. **20**
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

AVALON (DELAWARE) UNIT

HISTORICAL PRODUCTION RATES




HISTORICAL PRODUCTION RATIOS



AVALON (DELAWARE) UNIT

DEVELOPMENT PLAN: WATERFLOOD



• Scope

- 19 water injection patterns, 1100 acres in developed area
- 18 injector drillwells/1 conversion
- Water treating and injection facilities
- Estimated start 2 months after unit approval

WELL SYMBOL LEGEND	
●	Oil Well
●	Injector (Conversion)
●	Injector (Proposed)
X	Water Source Well
○	Well for Future Use
*	Disposal Well

NMOCD Hearing

June, 1995

Exhibit No.

25


Exxon Corporation
 NMOCD Cases 11297 & 11298
 Hearing Date: June 29, 1995

PROJECT FLOWSTREAM METHODOLOGY

- **From Geologic Model**
 - Layering model
 - Volumetrics by pattern (PV, Soi, OOI^P)
- **Numerical Simulator**
 - 3-phase, 2-dimension simulator
 - 312 gridblocks per 10 acres
- **Calibration**
 - Historical production performance by well used to calibrate simulation model
 - Only small overall modifications in geologic model required to match field performance
 - Continued operations projection matched with decline curve analysis
- **Used with Development Plan to Predict Future Performance**
 - Continued operations
 - Waterflood
 - CO₂ flood

AVALON (DELAWARE) UNIT

FUTURE PRODUCTION WITH WATERFLOOD PROJECT




AVALON (DELAWARE) UNIT

POTENTIAL DEVELOPMENT PLAN: CO₂ FLOOD

NMOCD Hearing

June, 1995



Scope

- 37 patterns, 2100 acres expanding into outer ring
- Earliest start 1999

Issues

- Attain miscibility pressure and reduce gas saturation: 3+ years
- CO₂ injectivity test
- Oil price


WELL SYMBOL LEGEND

- Oil Well
- Oil Well (Proposed for CO₂ Flood)
- ▲ Water Phase Injector (Conversion)
- ▲ Water Phase Injector (Proposed)
- ▲ CO₂ Phase Injector (Proposed for CO₂ Flood)
- ▲ Water Source Well
- ▲ Disposal Well

Exhibit No. **28**

Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

FUTURE PRODUCTION WITH CO₂ PROJECT



ESTIMATED ECONOMICS

- **Assumptions**

- 100% working interest/80% net interest
- Product pricing:
 - Oil @ \$17.10/BO escal. @ 5.4%/year
 - Gas @ \$1.50/MCF escal. @ 6.1%/year

- **Results**

- Investments = \$14,400,000
- Additional reserves = 8.2 MMBO
- Present value profit discounted @ 10% = \$21,500,000
- Payout = 5 years
- Rate of Return = 30%

AVALON (DELAWARE) UNIT

PROPOSED UNORTHODOX WELL LOCATIONS ALL IN EDDY COUNTY, NEW MEXICO

WELL NAME AND NUMBER	SECTION	FOOTAGE LOCATION
AVALON DELAWARE UNIT 1212	31-20S-28E	1668 FNL & 1455 FWL
AVALON DELAWARE UNIT 1412	31-20S-28E	* 2310 FSL & 1485 FWL
AVALON DELAWARE UNIT 1612	31-20S-28E	* 992 FSL & 1489 FWL
AVALON DELAWARE UNIT 1614	31-20S-28E	* 1046 FSL & 2677 FWL
AVALON DELAWARE UNIT 1812	31-20S-28E	* 183 FNL & 1397 FWL
AVALON DELAWARE UNIT 1814	31-20S-28E	* 123 FNL & 2673 FEL
AVALON DELAWARE UNIT 1816	31-20S-28E	* 46 FNL & 1402 FEL
AVALON DELAWARE UNIT 2012	31-20S-28E	* 1386 FNL & 1314 FWL
AVALON DELAWARE UNIT 2014	31-20S-28E	* 1335 FNL & 2681 FWL
AVALON DELAWARE UNIT 2018	31-20S-28E	1317 FNL & 97 FEL
AVALON DELAWARE UNIT 2212	31-20S-28E	* 2600 FSL & 1322 FWL
AVALON DELAWARE UNIT 2214	31-20S-28E	* 2699 FSL & 2549 FWL
AVALON DELAWARE UNIT 2216	31-20S-28E	2566 FNL & 1377 FEL
AVALON DELAWARE UNIT 2218	31-20S-28E	2423 FSL & 78 FEL
AVALON DELAWARE UNIT 2220	31-20S-28E	2648 FSL & 1127 FWL
AVALON DELAWARE UNIT 2412	31-20S-28E	* 1337 FSL & 1324 FWL
AVALON DELAWARE UNIT 2418	31-20S-28E	1356 FSL & 99 FEL
AVALON DELAWARE UNIT 2420	31-20S-28E	1323 FSL & 1107 FWL

* Unstaked location: Actual location may vary

NMOCD Hearing

June, 1995

** Converted to injector wells after initial prod. & initial*

Exhibit No.

31

Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995

APPLICATION FOR AUTHORIZATION TO INJECT

- I. Purpose: ☒ Secondary Recovery ☐ Pressure Maintenance ☐ Disposal ☐ Storage
Application qualifies for administrative approval? ☒ yes ☐ no
- II. Operator: Exxon Corp.
Address: PO Box 1600 Midland, TX 79702
Contact party: Marsha Wilson Phone: (915) 688-7871
- III. Well data: Complete the data required on the reverse side of this form for each well proposed for injection. Additional sheets may be attached if necessary.
- IV. Is this an expansion of an existing project? ☐ yes ☒ no
If yes, give the Division order number authorizing the project _____.
- V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review.
- * VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.
- VII. Attach data on the proposed operation, including:
1. Proposed average and maximum daily rate and volume of fluids to be injected;
 2. Whether the system is open or closed;
 3. Proposed average and maximum injection pressure;
 4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and
 5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).
- *VIII. Attach appropriate geological data on the injection zone including appropriate lithologic detail, geological name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such source known to be immediately underlying the injection interval.
- IX. Describe the proposed stimulation program, if any.
- * X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division they need not be resubmitted.)
- * XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.
- XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground source of drinking water.
- XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form.
- XIV. Certification
- I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.
- Name: Marsha Wilson Title Staff Office Assistant
Signature: Marsha Wilson Date: 5-8-95
- * If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be duplicated and resubmitted. Please show to Exhibit No. 32
of the earlier submittal. Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995
- DISTRIBUTION: Original and one copy to Santa Fe with one copy to the district office.

III. WELL DATA

- A. The following well data must be submitted for each injection well covered by this application. The data must be both in tabular and schematic form and shall include:

- (1) Lease name; Well No.; location by Section, Township, and Range; and footage location within the section.
- (2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined.
- (3) A description of the tubing to be used including its size, lining material, and setting depth.
- (4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used.

Division District offices have supplies of Well Data Sheets which may be used or which may be used as models for this purpose. Applicants for several identical wells may submit a "typical data sheet" rather than submitting the data for each well.

- B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

- (1) The name of the injection formation and, if applicable, the field or pool name.
- (2) The injection interval and whether it is perforated or open-hole.
- (3) State if the well was drilled for injection or, if not, the original purpose of the well.
- (4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations.
- (5) Give the depth to and name of the next higher and next lower oil or gas zone in the area of the well, if any.

XIV. PROOF OF NOTICE

All applicants must furnish proof that a copy of the application has been furnished, by certified or registered mail, to the owner of the surface of the land on which the well is to be located and to each leasehold operator within one-half mile of the well location.

Where an application is subject to administrative approval, a proof of publication must be submitted. Such proof shall consist of a copy of the legal advertisement which was published in the county in which the well is located. The contents of such advertisement must include:

- (1) The name, address, phone number, and contact party for the applicant;
- (2) the intended purpose of the injection well; with the exact location of single wells or the section, township, and range location of multiple wells;
- (3) the formation name and depth with expected maximum injection rates and pressures; and
- (4) a notation that interested parties must file objections or requests for hearing with the Oil Conservation Division, P. O. Box 2088, Santa Fe, New Mexico 87501 within 15 days.

NO ACTION WILL BE TAKEN ON THE APPLICATION UNTIL PROPER PROOF OF NOTICE HAS BEEN SUBMITTED.

NOTICE: Surface owners or offset operators must file any objections or requests for hearing of administrative applications within 15 days from the date this application was mailed to them.

**ATTACHMENT TO INJECTION WELL DATA SHEET
AVALON UNIT
EDDY COUNTY, NEW MEXICO**

Listed below are the wells in this permit application. All wells are located in T-20-S, R-28-E.

T-20-S, R-28-E

Current Proposed Locations for New Drill Wells:

Section 30

#1212	1495 FWL	1662 FNL
#1412	1485 FWL	2310 FSL
#1612	1489 FWL	992 FSL
#1614	2677 FWL	1046 FSL

Section 31

#1812	1397 FWL	183 FNL
#1814	2673 FEL	123 FNL
#1816	1402 FEL	46 FNL
#2012	1314 FWL	1386 FNL
#2014	2681 FWL	1335 FNL
#2018	56 FEL	1320 FNL
#2212	1322 FWL	2600 FSL
#2214	2549 FWL	2699 FSL
#2216	1375 FEL	2564 FNL
#2218	73 FEL	2648 FSL
#2412	1324 FWL	1337 FSL
#2418	94 FEL	1320 FSL

Section 32

#2220	1128 FWL	2648 FSL
#2420	1107 FWL	1323 FSL

Conversion:

Section 31

#2016	1305 FWL	1305 FNL
-------	----------	----------

(formerly Yates "C" Federal #36)

INJECTION WELL DATA SHEET

Exxon Corp.	Avalon Unit			
OPERATOR	LEASE			
2016	1305' FNL & 1305' FEL	31	T-20-S	R-28-E
WELL NO.	FOOTAGE LOCATION	SECTION	TOWNSHIP	RANGE

Schematic

See Attached

Tubular Data

Surface Casing

Size 13 3/8" " Cemented with 750 sx.
 TOC Surface feet determined by Circulation
 Hole size 17 1/2"

Intermediate Casing

Size 8 5/8" " Cemented with 1385 sx.
 TOC Surface feet determined by Circulation
 Hole size 11"

Long string

Size 5 1/2" " Cemented with 1000 sx.
 TOC Surface feet determined by Circulation
 Hole size 7 7/8"
 Total depth 4970

Injection interval

2478 feet to 4880 feet
 (perforated or open-hole, indicate which)

Tubing size 2 7/8" lined with cement set in a
 (material)
Baker Model A packer at 2340 feet.
 (brand and model)
 (or describe any other casing-tubing seal).

Other Data

- Name of the injection formation Delaware
- Name of Field or Pool (if applicable) Avalon
- Is this a new well drilled for injection? ☐ Yes ☒ No
 If no, for what purpose was the well originally drilled? Oil producer
- Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail (sacks of cement or bridge plug(s) used)
No
- Give the depth to and name of any overlying and/or underlying oil or gas zones (pools) in this area. Depths are approximate:
Yates 350-400', Bone Spring 5000-7000', Atoka 7800-10800',
Wolfcamp 9000-10000', Strawn 10000, Morrow 11000'

WELLBORE SKETCH AND WELL HISTORY

AFE# 16020

Avalon #2016

API# 30-105-76

ELEV.: KB _____, 12.1' ABOVE CHF
10' ABOVE G.L.

Independent
Wellhead hookup
(2000 psi.
w.p.)

HOLE SIZE: 17 1/2"
TOC: Surf.

13 3/8" • 613
CMT 750 SX

HOLE SIZE: 11"
TOC: Surf.

8 5/8" • 2419
CMT 980 SX (primary)
405 SX (one-inch ops)

HOLE SIZE: 7 7/8"
TOC: Surf.

Perfs 2546'-2810' U. Cherry Canyon
CIBP @ 2280'

m. Cherry Canyon perfs
@ 3038-3189'

RBP 4/30' sand @ 3360' ±
U. Brushy Canyon
perfs @ 3406'-3624'

CIBP @ 4690'

L. Brushy Canyon
perfs - 4708-4736

5 1/2" • 4924. (29 shots)
CMT 1000 SX Class C + 4% Gel
Circ 193 SX to
surf

Unit: (formerly)

LEASE & WELL NAME: Yates Federal "C" 36

FIELD: Avalon COUNTY: Eddy ST.: A

LOCATION: 1305' FNL: FEL

Sec 31; T-20-S; R-28-E

DATE: 10/14/90 BY: JLC REV.: BY:

CASING RECORD

SURFACE CASING

O.D.	WT/FT	GRADE	SET A
13 3/8"	48	K-55	613

INTERMEDIATE CASING

8 5/8"	32#	K-55	22
	24#	J:K 55	126
	32#	J:K 55	241
5 1/2"	15.5#	K-55	10
	14#	K-55	492

TUBING

NO. JTS.	O.D.	THD.	TYPE	WT.	GDE.	SE
	2 7/8"	API	EUE	6.5	J55	

WELL HISTORY:

New Drill well - FRW'd 9/90
Perf L. Brushy Canyon @ 4708-4736 w/ 29
shots. Frac w/ 36,000# 14/30 Sand in
14,000 gals gelled water. Tested w/ET
P/B to U. Brushy Canyon. Perf 3406-
3624'. Acid w/ 4600 gals HCl w/
PFT tool. Frac w/ 18,500# of 20/40
plus 62,500# 12/20 sand in
49,000 gals gelled water. Well came
in flowing. FRW - 142 oil 261 wats. U.B.
L.B.C. oil.

12/90 - perfed cherry canyon - (RBP) 3
3038-3189' - MERV. Pj - water
wash & acid wash pipe w 2850
15% HCL. Frased well D/S
70,000 # sand 12/20. Helled Fluid.
FRW - 104 Bb 500 Bw.

2/91 perf C.F.B. @ 2280' perfed
well 2546-2810' - PFT acid job
6720' gal 15% HCL. Frased well
D/S. 105,000 # 13/20. Helled.
PWOP - FRW'd 180 oil 170 wats.

TD: 4970' PBD: 4660±

INJECTION WELL DATA SHEET

Exxon Corp.		Avalon Unit	
OPERATOR		LEASE	
(See attached list)	30, 31, & 32	T-20-S	R-28-E
WELL NO.	FOOTAGE LOCATION	SECTION	TOWNSHIP
			RANGE

Schematic

See attached
typical schematic

Tubular Data

Surface Casing

Size 10 3/4 " Cemented with 600 sx.
TOC Surface feet determined by Circulation
Hole size 14 3/4"

Intermediate Casing

Size 7 5/8 " Cemented with 1400 sx.
TOC Surface feet determined by Circulation
Hole size 9 1/2"

Long string

Size 4 1/2" Fiberglass lnrCemented with 500 sx.
TOC 2340 feet determined by Circulation
Hole size 6 1/2" underreamed to 7"
Total depth 4000'

Injection interval

* feet to * feet
(perforated or open-hole, indicate which)

Perforation


* See attached summary on question VII.3.

Tubing size 2 3/8" lined with cement set in a
(material)
Baker Model A packer at 2340 feet.
(brand and model)
(or describe any other casing-tubing seal).

Other Data

- Name of the injection formation Delaware
- Name of Field or Pool (if applicable) Avalon
- Is this a new well drilled for injection? ☒ Yes ☐ No
If no, for what purpose was the well originally drilled? _____
- Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail (sacks of cement or bridge plug(s) used) _____
No
- Give the depth to and name of any overlying and/or underlying oil or gas zones (pools) in this area. Depths are approximate:
Yates 350-400', Bone Spring 5000-7000', Atoka 7800-10,800',
Wolfcamp 9000-10,000', Strawn 10,000' Morrow 11,000'

Avalon Project Proposed Drillwell Waterflood



**SUPPLEMENT TO APPLICATION FOR AUTHORIZATION TO INJECT
AVALON UNIT
EDDY COUNTY, NEW MEXICO**

V. Two maps are attached.

VI. Attached is a typical wellbore sketch and tabular data on wells within the area of review.

VII. Proposed Operations

1. Average daily injection rate = 500 BPD
Maximum daily injection rate = 2000 BPD
Volume of fluids to be injected = 141,200,000 Bbls

2. System is open

3. The average and maximum injection pressures are as follows:

		Avg. Press.	Max. Press.
Section 30			
#1212	2486-4817	493	497
#1412	2509-4832	493	502
#1612	2492-4798	493	498
#1614	2498-4853	493	500
Section 31			
#1812	2467-4774	493	493
#1814	2496-4844	493	499
#1816	2520-4902	493	504
#2012	2481-4800	493	496
#2014	2495-4843	493	499
#2018	2501-4924	493	500
#2212	2496-4817	493	499
#2214	2509-4841	493	502
#2216	2505-4885	493	501
#2218	2477-4918	493	495
#2412	2535-4826	493	507
#2418	2478-4911	493	496
Section 32			
#2220	2489-4945	493	498
#2420	2479-4935	493	496
Conversion - Section 31			
#2016	2478-4880	493	496
(formerly Yates "C" Federal #36)			

4. The source of water that will be injected is from the Delaware.

The water will be produced from Avalon Unit wells and 2 or 3 source water wells completed in non-productive intervals of the Lower Delaware.

5. NA

VIII. Geological Data

The proposed interval for injection at the Avalon (Delaware) Field is a porous and permeable zone within the Delaware Mountain Group, which in the Avalon area consists of fine sandstones and coarse siltstones of the Cherry Canyon and Brushy Canyon Formations. The estimated average top and base for the Delaware at Avalon are:

	<u>Top</u>	<u>Base</u>
Delaware Mountain Group	2494 ft. (767 ft. subsea)	4860 ft (-1599 ft. subsea) (top of the Bone Spring Fm.), 2366 ft. thick

Fresh water in this area occurs primarily in the Capitan aquifer, which occurs at approximately 750 feet deep (2500 feet subsea) (Hiss, 1976, New Mexico Bureau of Mines and Mineral Resources Resource Map 6). At Avalon, approximately 600 feet of low porosity Goat Seep Reef separate the Delaware from porous zones within the Capitan aquifer. Other potential fresh water zones (primarily the Rustler Formation) occur above the Salado salt and anhydrite. The top of the anhydrite/salt at this location is generally less than 300 feet deep. This unit serves as an effective barrier between injected and fresh water zones near the surface. No fresh water occurs below the proposed injection zone.

IX. Proposed stimulation program


- Perforate Upper Brushy Canyon
- Spot acid across the perforations
- Frac Brushy Canyon with 30-50K # 20/40 sand. Water based frac gel.
- Isolate Brushy Canyon
- Perforate Upper Cherry Canyon
- Spot acid across the perforations
- Frac Cherry Canyon with 30-50K # 20/40 sand. Water based frac gel.
- Put wells on injection
- Run post completion injection profile


X. Log attached for Yates Federal "C" #36

XI. Chemical analysis on the fresh water well that is within one mile of the proposed wells will be forwarded separately.

XII. There are no indications of open faults or other hydrological connections between the proposed disposal interval and the shallower fresh water zones.

XIII. A signed statement of mailing of notice along with proof of publication will be submitted later.





12

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)
T-20-S, R-28-E										
Yates Pet.	Stonewall "EP" State #2	Gas	19	660 FS, 1980 FW	02/15/77	11500	11060-11070	13 3/8"	588	500
								8 5/8"	2750	1920
								5 1/2"	11458	265
Yates Pet.	Stonewall "EP" State #3	Oil	19	545 FS, 1960 FW	10/29/77	4800	4369-4399	13 3/8"	512	450
								8 5/8"	2900	1300
								5 1/2"	4797	240
Yates Pet.	Federal "DC" #1	Gas	29	1980 FS, 660 FW	09/02/78	11540	10168-10176	13 3/8"	585	550
								8 5/8"	2845	1840
								5 1/2"	11495	650
Exxon Corp.	Yates "C" Federal #6	Oil	31	1980 FNL, 1980 FWL	02/20/83	4700	3550-3595 3606-3624	8 5/8"	634	500
								5 1/2"	4699	950
Exxon Corp.	Yates "C" Federal #1	Gas	31	660 FNL, 1980 FWL	06/19/82	11470	11040-11110	13 3/8"	584	950
								9 5/8"	3154	985
								7	10395	550
Exxon Corp.	Yates "C" Federal #2	Disposal	31	1980 FS, 1980 FE	10/13/82	11901	9004-9130	13 3/8"	588	600
								9 5/8"	3027	1250
								5 1/2"	11901	1780
Exxon Corp.	Yates "C" Federal #3	Oil	31	660 FN, 1980 FE	10/20/82	4702	3400-3608	8 5/8"	605	425
								5 1/2"	4702	1050
Exxon Corp.	Yates "C" Federal #4	Oil	31	660 FNL, 660 FEL	01/06/83	4701	2574-2818	8 5/8"	618	400
								5 1/2"	4701	1050
Exxon Corp.	Yates "C" Federal #5	Oil	31	660 FNL, 660 FWL	06/08/83	4710	2506-2726 3494-3676	8 5/8"	627	1300
								5 1/2"	4704	750
Exxon Corp.	Yates "C" Federal #7	Oil	31	1980 FN, 1980 FE	05/17/83	4700	3448-3650	8 5/8"	618	400
								5 1/2"	4693	1215
Exxon Corp.	Yates "C" Federal #8	Oil	31	2180 FN, 660 FW	07/01/83	4725	2570-2690	8 5/8"	602	1200
								5 1/2"	4720	904
Exxon Corp.	Yates "C" Federal #9	Oil	31	1980 FNL, 560 FEL	05/16/83	4712	2538-2788 3580-3662	8 5/8"	617	450
								5 1/2"	4700	905
Exxon Corp.	Yates "C" Federal #12	TA	31	1980 FSL, 660 FEL	08/03/83	5000		13 3/8"	598	670
								8 5/8"	2495	850
								5 1/2"	4992	900
Exxon Corp.	Yates "C" Federal #10	Oil	31	1980 FSL, 1980 FWL	07/01/83	5000	2548-2714	13 3/8"	632	525
								8 5/8"	2525	850
								5 1/2"	4988	950
Exxon Corp.	Yates "C" Fed. #WD-11	Disposal	31	660 FS, 1980 FE	03/13/84	5000	3955-3982	13 3/8"	600	525
								8 5/8"	2448	850
								5 1/2"	4990	900
Exxon Corp.	Yates "C" Federal #14	TA	31	660 FS, 660 FE	10/27/83	3890		13 3/8"	590	930
								8 5/8"	2493	1025
								5 1/2"	3890	500
Exxon Corp.	Yates "C" Federal #15	TA	31	660 FSL, 660 FWL	12/10/83	4930		13 3/8"	596	1000
								8 5/8"	2513	1300
								5 1/2"	4923	1150

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)
T-20-S, R-28-E (continued)										
Exxon Corp.	Yates "C" Federal #13	Oil	31	1980 FSL, 660 FWL	07/31/83	4930	2596-2732 3602-3634	13 3/8" 8 5/8" 5 1/2"	619 2493 4924	750 1700 1800
Exxon Corp.	Yates "C" Federal #17	Oil	31	760 FNL, 1980 FWL	09/19/83	3897	2568-2605 3562-3626	13 3/8" 8 5/8" 5 1/2"	606 2482 3887	1050 930 750
Exxon Corp.	Yates "C" Federal #18	TA	31	2310 FS, 2310 FE	10/20/83	3885		13 3/8" 8 5/8" 5 1/2"	593 2491 3876	700 925 525
Yates Pet	Stonewall "EP" State #1	Gas	30	1980 FN, 1980 FW	09/25/75	11478	10079-10097	13 3/8" 8 5/8" 5 1/2"	612 2799 11380	550 1650 1300
Yates Pet	Stonewall "WM" State #1	Oil	30	560 FS, 1980 FE	06/02/83	4953	2587-2680	20" 10 3/4" 8 5/8" 5 1/2"	40 545 2485 4953	--- 500 1350 700
Yates Pet	Stonewall "WM" State #3	Oil	30	330 FS, 1980 FW	07/22/83	4865	2530-2622 3422-3602	13 3/8" 8 5/8" 5 1/2"	545 2470 4864	650 550 500
Yates Pet	Stonewall "WM" State #2	Inact. Oil	30	450 FS, 990 FE	08/07/84	5450	4960-5216	13 3/8" 8 5/8" 5 1/2"	546 2410 4960	550 1050 750
Yates Pet	Stonewall "WM" State #4	Oil	30	330 FS, 990 FW	11/22/83	4860	2524-2727 3620-3671	20" 13 3/8" 8 5/8" 5 1/2"	40 535 2642 4860	--- 500 1300 750
Yates Pet	Stonewall "WM" State #5	Oil	30	1650 FS, 1980 FW	11/10/83	4900	3330-3367 3487-3515 3570-3576	13 3/8" 8 5/8" 5 1/2"	535 2404 4900	600 1355 700
Yates Pet	Stonewall "YE" State #1	Oil	30	1650 FS, 1980 FE	12/29/83	4950	2595-2732	20" 13 3/8" 8 5/8" 5 1/2"	40 543 2415 4950	--- 550 900 750
Yates Pet	Stonewall "EP" State #5	Oil	30	2310 FN, 990 FW	03/14/84	4870	3361-3730 4142-4346	13 3/8" 8 5/8" 5 1/2"	544 2420 4870	500 1600 800
Yates Pet	Stonewall "WM" State #6	Oil	30	1650 FS, 990 FW	12/27/83	4860	3349-3527	20" 13 3/8" 8 5/8" 5 1/2"	40 535 2410 4860	--- 550 800 800
Yates Pet	Stonewall "EP" State #7	Oil	30	990 FNL, 990 FWL	01/19/84	5107	4979-4983	20" 13 3/8" 8 5/8" 5 1/2"	40 538 2372 5100	--- 500 1120 900
Yates Pet	Stonewall "EP" State #6	Gas	30	990 FNL, 2080 FWL	04/20/85	5100	4983-4992	13 3/8" 8 5/8" 5 1/2"	537 2469 5098	400 1050 600
Yates Pet	Stonewall "EP" State #8	Oil	30	2310 FN, 1980 FW	04/04/84	5303	3384-3412 3434-3541 3622-3688	13 3/8" 8 5/8" 5 1/2"	540 2404 5303	425 950 750

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)
T-20-S, R-28-E (continued)										
Exxon Corp.	Hondo-State Com #1	Gas	32	1980 FN, 660 FW	05/02/77	11475	10385-10705	13 3/8" 9 5/8" 5 1/2"	565 2790 11475	800 1750 825
Maralo	Keystone #1	Gas	32	1980 NL, 1980 FEL	01/25/78	11600	6298-6503	13 3/8" 8 5/8" 4 1/2"	608 3010 11600	695 1100 875
Exxon Corp.	Hondo "A" State #1	Oil	32	660 FN, 660 FW	02/14/83	4050	2654-2709	8 5/8" 5 1/2"	610 4042	400 780
Exxon Corp.	Hondo "A" State #3	Oil	32	1980 FS, 610 FW	05/24/83	4050	2506-2598	13 3/8" 8 5/8" 5 1/2"	590 2410 4050	880 1450 550
Exxon Corp.	Hondo "A" State #2	Oil	32	1980 FN, 330 FW	03/05/83	4047	2605-2620 2640-2660 3622-3636	8 5/8" 5 1/2"	610 4047	400 770
Exxon Corp.	Hondo "A" State #4	Oil	32	660 FS, 330 FW	06/12/83	3808	2585-2620	13 3/8" 8 5/8" 5 1/2"	590 2445 3808	800 1330 450
Exxon Corp.	Hondo Fee #2	Oil	32	1980 FS, 1650 FW	07/15/83	2813	2542-2556 2602-2612 2628-2640	13 3/8" 8 5/8" 5 1/2"	588 2422 2813	630 1300 135
Maralo Inc	Keystone #2	---	32	1980 FSL, 1980 FEL	08/29/94	6700	6307-6514	13 3/8" 8 5/8" 5 1/2"	502 2557 6700	875 1300 890
Maralo Inc	Keystone #4	---	32	1650 FNL, 1980 FWL	01/22/95	6650	6283-6484	13 3/8" 8 5/8" 5 1/2"	504 2518 6650	550 1200 750
T-20-S, R-27-E										
MWJ Prod.	State "GWA" #1	Oil	36	2180 FS, 660 FE	12/10/80	4845	4724-4731 4740-4758 4764-4766	13 3/8" 8 5/8" 5 1/2"	410 2405 4845	400 1200 600
MWJ Prod.	State "GWA" #2	Oil	36	660 FS, 660 FE	09/13/84	4825	4367-4373	13 3/8" 8 5/8" 5 1/2"	502 2400 4825	500 1350 550
Yates Pet.	Citdale "ZG" #1	Gas	36	330 RN, 330 FE	08/03/84	5100	4871-4880 5023-5026	13 3/8" 8 5/8" 4 1/2"	408 2390 5100	325 800 710
Premier Prod.	Eddy "FV" State Com #1	Gas	25	1980 FN, 990 FE	05/12/76	11450	10014-10028	20" 13 3/8" 9 5/8" 5 1/2"	30 642 3050 11450	--- 650 1350 1070
Premier Prod.	Eddy "FV" State #3	Inact. Oil	25	660 FS, 330 FE	04/29/84	4975	2710-2716 2723-2725 2738-2740	13 3/8" 8 5/8" 5 1/2"	500 2450 4975	500 1800 800

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)
T-21-S, R-27-E										
Mobil Producing	Burton Flat "Sec 6" St #1	D & A	6	660 FNL, 660 FEL	02/19/87	5500		13 3/8"	457	600
								8 5/8"	2599	1300
								5 1/2"	5500	1000
Mobil Producing	Burton Flat "Sec 6" St # 3	Inact. Oil	6	660 FN, 1980 FE	07/27/84	6100	4642-4652	13 3/8"	463	600
								9 5/8"	2500	1500
								7"	6100	1375
Exxon Corp.	Yates "C" Federal #35	Disposal	5	563 FNL, 560 FEL	10/30/85	3110	2702-2898 2950-3098	13 3/8"	629	950
								8 5/8"	2592	1300
								5 1/2"	3110	550

--- = Information not available

Data Source: Petroleum Information, Scout Tickets, Well Files

Schlumberger		COMPENSATED NEUTRON LITHO-DENSITY			
COUNTY FIELD LOCATION WELL COMPANY	EDDY	COMPANY EXXON COMPANY USA			
	AVALON (DELAWARE)	WELL YATES "C" FEDERAL NO. 38			
	1305' FNL & FEL	FIELD AVALON (DELAWARE)			
	YATES "C" FEDERAL NO. 38	COUNTY EDDY STATE NEW MEXICO			
	EXXON COMPANY USA	LOCATION 1305' FNL & FEL API SERIAL NO. 30-015-263700 SECT. 31 TWP. 20-S RANGE 28-E Other Services: LDT/CNL, DLL/RXO, NGT/EPT, PHASOR/BHC, RFT, LOGNET			
Permanent Datum GL		Elev. 3237.0 F		Elev.: K.B. 3247	
Log Measured From KB		10.0 F above Perm. Datum		D.F.	
Drilling Measured From KB				G.L. 3237	
Date	14-SEP-1990				
Run No.	ONE				
Depth Driller	4970.0 F				
Depth Logger (Schl.)	4972.0 F				
Stm. Log Interval	4939.0 F				
Top Log Interval	2419.0 F				
Casing-Driller	8 5/8 @ 2419.0 F				
Casing-Logger	2419.0 F				
BHT Size	7 7/8"				
Type Fluid in Hole	CUT BRINE				
Dens.	Visc.	9.40 LB/G 32.0 S			
pH	Fid. Loss	7.5 10.0 C3			
Source of Sample	FLOWLINE				
Rm @ Meas. Temp.	.156 OHMM @ 71.0 DEGF				
Rmf @ Meas. Temp.	.126 OHMM @ 71.0 DEGF				
Rmc @ Meas. Temp.	.244 OHMM @ 71.0 DEGF				
Source: Rmf	Rmc	PRESS PRESS			
Rm @ BHT	.106 OHMM @ 108. DEGF				
Circulation Ended	SEE LOG				
Logger on Bottom	SEE LOG				
Max. Rec. Temp.	108. DEGF				
Equip.	Location	8326 ROSWELL			
Recorded By	PAT SULLIVAN				
Witnessed By	CANTRELL/LUKAS/GANAPATHY/THOMAS				

The well name, location and borehole reference data were furnished by the customer.			
All interpretations are opinions based on inferences from electrical or other measurements and we cannot, and do not guarantee the accuracy or correctness of any interpretations, and we shall not, except in the case of gross or willful negligence on our part, be liable or responsible for any loss, costs, damages or expenses incurred or sustained by anyone resulting from any interpretations made by any of our officers, agents or employees. These interpretations are also subject to Clause 4 of our General Terms and Conditions as set out in our current Price Schedule.			
Run No.	ONE		
Service Order No.	555843		
Drilling Fluid Level			
Salinity	115500. PPM		
Rim @ BHT	.085 OHMM	108. DEGF	
Rim @ BHT	.105 OHMM	108. DEGF	
Logging Speed	2000.0 F/HR		
EQUIPMENT DATA			
Tool Number 1	LDT SEE CALS		
Tool Number 2	CNL SEE CALS		
Tool Number 3	OLS 978		
Tool Number 4	DLC 1718		
Tool Number 5	SRS 800		
Tool Number 6	SRE 755		
Tool Number 7	SGC 206		
Tool Number 8	NGT SEE CALS		
Tool Number 9	HOBS DITE		
Tool Number 10	SGC 206		
Tool Number 11	TCC 373		
Tool Number 12	TCM 1267		
REMARKS:			
CHLORIDES 70K FROM MUD REPORT.			
MDEN=2.71 FD=1.05			
CGR NOT VALID FILES 10 & 11 DUE TO HIRS (HIGH RESOLUTION) ACQUISITION.			
KALMAN FILTER DOES NOT WORK OTHER THAN ON 6" DATA FRAMES.			
CGR OK ON PASSES 12 & 13.			

AFTER SURVEY TOOL CHECK SUMMARY

PERFORMED: 14-SEP-1990 19:59
PROGRAM FILE: TOH (VERSION 32.4 90/06/12 90/06/06)

LDTD TOOL CHECK

DENSITY RESISTIVITY SONDE NUMBER : 3946
NUCLEAR SERVICE CARTRIDGE NUMBER : 2839
POWERED DETECTOR HOUSING NUMBER : 1736
POWERED GAMMA-GAMMA DETECTOR NUMBER : 2713
LDT LOGGING SOURCE NUMBER : 1756
LDT CALIBRATION MODE : HATE

	MEASURED BACKGROUND		UNITS	TOLERANCE ON BEFORE-AFTER
	BEFORE	AFTER		
LL	18.7	18.6	CPS	+/- 1.0
LU	72.7	72.9	CPS	+/- 1.0
LS	55.0	55.0	CPS	+/- 1.0
LITH	5.4	5.4	CPS	+/- 0.3
SS1	15.8	15.8	CPS	+/- 0.5
SS2	10.7	10.7	CPS	+/- 0.5

HV SETTINGS		DETECTOR RESOLUTIONS	
HV LS:	1266.8 V	LS:	8.4 %
HV SS:	1285.0 V	SS:	8.7 %

BKGD BKGD
BEFORE SURVEY: 14-SEP-1990 11:47 AFTER SURVEY: 14-SEP-1990 19:50

NGTC TOOL CHECK

NGTC CARTRIDGE NUMBER : 935
 NGTC DETECTOR NUMBER : 949
 NGTC CALIBRATOR NUMBER : 11
 GSR-U/Y REFERENCE (GAPI) : 164

SGR	BEFORE 164		AFTER 165		UNITS GAPI	
	MEASURED	AFTER	SURVEY		BEFORE	
	BKG	JIG	NORM VAL		NORM VAL	UNITS
W1NG	59.0	456.8	388.2		387.6	CPS
W2NG	20.6	200.2	175.2		173.7	CPS
W3NG	5.9	31.5	25.0		23.2	CPS
W4NG	1.5	16.7	14.8		14.8	CPS
W5NG	1.4	26.2	24.2		24.2	CPS

PCSL -208 KEY OFFSET

DETECTOR RESOLUTION : 11.5 %
 P.M. HIGH VOLTAGE : 1603.8 V
 THORIUM PEAK FORM FACTOR : -.16
 SHOP QUALITY WINDOWS RATIO: 2.24
 QUALITY WINDOWS RATIO : 2.23

BEFORE SURVEY: BACK: 14-SEP-1990 11:47 JIG: 14-SEP-1990 11:57
 AFTER SURVEY CHECK: BACK: 14-SEP-1990 19:50 JIG: 14-SEP-1990 19:57

CNTH TOOL CHECK

INPUT	BEFORE JIG	AFTER JIG
CNTC	2842.84	2827.46
CFTC	1193.21	1194.21

CHANGE IN THERMAL POROSITY AT 20 PU IS -.212 PU

BEFORE SURVEY: BACK: 14-SEP-1990 11:47 JIG: 14-SEP-1990 11:57
 AFTER SURVEY CHECK: BACK: 14-SEP-1990 19:50 JIG: 14-SEP-1990 19:57

ACCUMULATED INTEGRATION VALUES SUMMARY:

IHV: 1093.57 F3 FROM 4972.00 F TO 2419.00 F
 ICV: 672.355 F3 FROM 4972.00 F TO 2419.00 F

EVENT MARK SUMMARY:


OUTPUT	INTERVAL BETWEEN PIPS	DEPTH TRACK EDGE
IHV	10.0000 F3	LEFT EDGE
ICV	10.0000 F3	RIGHT EDGE



CALI(IN)			
6.0000	16.000		
SGR (GAPI)		DRHQ(G/C3)	
0.0	100.00	-.0500	.45000
CGR (GAPI)		RHQB(G/C3)	
0.0	100.00	2.0000	3.0000
TENS(LBF)		NPOR(Y/Y)	
10000.	0.0	.30000	-.1000
SGR (GAPI)		NPOR(Y/Y)	
100.00	200.00	.70000	.30000


CP 32.4


FILE 7


14-SEP-1990 21:15

INPUT FILE(S)
13DATA ACQUIRED
14-SEP-1990 15:50









CP 32.4

FILE 7

14-SEP-1990 21:07

INPUT FILE(S)
13DATA ACQUIRED
14-SEP-1990 15:50

CALI(IN)		DRHO(G/C3)	
6.0000	16.000	-.0500	.45000
SGR (GAPI)		RHOB(G/C3)	
0.0	100.00	2.0000	3.0000
CGR (GAPI)		NPOR(V/V)	
0.0	100.00	.30000	-.1000
TENS(LBF)		NPOR(V/V)	
10000.	0.0	.70000	.30000
SGR (GAPI)			
100.00	200.00		

SENSOR MEASURE POINT TO TOOL ZERO

DV1 14.9 FEET	CAL1 2.8 FEET
SV0 14.9 FEET	SI0 14.9 FEET
DV0 14.9 FEET	DIO 14.9 FEET
CALS 3.1 FEET	DLCS .6 FEET
W2NG 62.7 FEET	W1NG 62.7 FEET
W4NG 62.7 FEET	W3NG 62.7 FEET
CFTC 50.9 FEET	W5NG 62.7 FEET
LITH 33.3 FEET	CNTC 50.4 FEET
LS 33.3 FEET	LL 33.3 FEET
PARI 32.8 FEET	LU 33.3 FEET
SS2 32.8 FEET	SS1 32.8 FEET
TENS .6 FEET	CALI 33.4 FEET
CMSF 1.1 FEET	I1 1.3 FEET
TNRA 51.4 FEET	SGR 62.7 FEET

PARAMETERS

NAME	VALUE	UNIT	NAME	VALUE	UNIT
PP	NORM		DO	0.0	F
WMUD	9.40000	LB/G	TD	4972.00	F
FCD	5.50000	IN	DHC	NONE	
BFM	LIQU		MDEN	2.71000	G/C3
FD	1.05000	G/C3	DPPM	STAN	
MATR	LIME		HC	CALI	
NPDC	0		HSCD	YES	
SQCD	NO		MCCD	NO	
BSCD	NO		FSCD	NO	
MWCD	NO		PTCD	NO	
SDAT	SOCH		MCOR	NATU	
SOCH	.500000	IN	FSAL	-50000.0	PPM
ANGL	0.0	DEG	GGRD	.0100000	DF/F
BHFL	WATE		PCSL	-208	KEY
NFD	KALM		CBAR	1.00000	
PMUD	0.0	%	GTSE	TEMP	

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

Exhibit No. **33**
Exxon Corporation
NMDCD Cases 11297 & 11298
Hearing Date: June 29, 1995

T-20-S, R-28-E

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG.	DEPTH	CMT (SX)	TOC	HOW TOC DETERMINED
Yates Pet.	Stonewall "EP" State #2	Gas	19	660 FS, 1980 FW	02/15/77	11500	11060-11070	13 3/8"	588	500	Surface	Circ
						8 5/8"	2750	1920	Surface			Circ
						5 1/2"	11458	265	9900			Temp Survey
Yates Pet.	Stonewall "EP" State #3	Oil	19	545 FS, 1960 FW	10/29/77	4800	4369-4399	13 3/8"	512	450	Surface	Circ
						8 5/8"	2900	1640	Surface			Circ
						5 1/2"	4797	240	3290			Temp Surv. CBL
Yates Pet.	Federal "DC" #1	Gas	29	1980 FS, 660 FW	09/02/78	11540	10168-10176	13 3/8"	585	550	Surface	Circ
						8 5/8"	2845	1840	Surface			Circ
						5 1/2"	11495	650	7000			CBL
												SQ - <2700 CBL
Exxon Corp.	Yates "C" Federal #6	Oil	31	1980 FNL, 1980 FWL	02/20/83	4700	3550-3595	8 5/8"	634	500		Circ
							3606-3624	5 1/2"	4699	950	Surface	Circ
Exxon Corp.	Yates "C" Federal #1	Gas	31	660 FNL, 1980 FWL	06/19/82	11470	11040-11110	13 3/8"	584	950	Surface	Circ
								9 5/8"	3154	985	Surface	Circ
								7	10395	550	7497	Calculated
								5" liner	9901-	160	9901	Circ
									11467			
Exxon Corp.	Yates "C" Federal #2	Disposal	31	1980 FS, 1980 FE	10/13/82	11901	9004-9130	13 3/8"	588	600		Circ
								9 5/8"	3027	1250	Surface	Circ
								5 1/2"	11901	1780	3980	Temp Survey
Exxon Corp.	Yates "C" Federal #3	Oil	31	660 FN, 1980 FE	10/20/82	4702	3400-3608	8 5/8"	605	425		Temp Survey
								5 1/2"	4702	1050	1730	
Exxon Corp.	Yates "C" Federal #4	Oil	31	660 FNL, 660 FEL	01/06/83	4701	2574-2818	8 5/8"	618	400		Circ
								5 1/2"	4701	1050	Surface	Circ
Exxon Corp.	Yates "C" Federal #5	Oil	31	660 FNL, 660 FWL	06/08/83	4710	2506-2726	8 5/8"	627	1300		Temp Survey
							3494-3676	5 1/2"	4704	750	280	
Exxon Corp.	Yates "C" Federal #7	Oil	31	1980 FN, 1980 FE	05/17/83	4700	3448-3650	8 5/8"	618	400		Circ
								5 1/2"	4693	1215	Surface	Circ
Exxon Corp.	Yates "C" Federal #8	Oil	31	2180 FN, 660 FW	07/01/83	4725	2570-2690	8 5/8"	602	1200		Circ
								5 1/2"	4720	904	Surface	Circ
Exxon Corp.	Yates "C" Federal #9	Oil	31	1980 FNL, 560 FEL	05/16/83	4712	2538-2788	8 5/8"	617	450		Circ
							3580-3662	5 1/2"	4700	905	Surface	Circ

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH (PERFS)	COMPLETION CSG.	DEPTH (SX)	CMT	TOC	HOW TOC DETERMINED
Exxon Corp.	Yates "C" Federal #12	TA	31	1980 FSL, 660 FEL	08/03/83	5000 2528-2624 3655-3684	13 3/8" 8 5/8" 5 1/2"	598 2495 4992	670 865 900	Surface Surface Surface	Circ Circ Circ
Exxon Corp.	Yates "C" Federal #10	Oil	31	1980 FSL, 1980 FWL	07/01/83	5000 2548-2714	13 3/8" 8 5/8" 5 1/2"	632 2525 4988	525 850 950	Surface Surface 620	Circ Circ Calculated
Exxon Corp.	Yates "C" Fed. #WD-11	Disposal	31	660 FS, 1980 FE	03/13/84	5000 3955-3982	13 3/8" 8 5/8" 5 1/2"	600 2448 4990	525 850 900	Surface Surface 2550	Circ Circ Squeeze job
Exxon Corp.	Yates "C" Federal #14	TA	31	660 FS, 660 FE	10/27/83	3890 2598-2636	13 3/8" 8 5/8" 5 1/2"	590 2493 3890	930 1025 500	Surface Surface 2446	Circ Circ Temp Survey
Exxon Corp.	Yates "C" Federal #15	TA	31	660 FSL, 660 FWL	12/10/83	4930 2704-2597 4422-4429 4714-4718	13 3/8" 8 5/8" 5 1/2"	596 2513 4923	1000 1300 1150	410 Surface	Temp Survey Circ
Exxon Corp.	Yates "C" Federal #13	Oil	31	1980 FSL, 660 FWL	07/31/83	4930 2596-2732 3602-3634	13 3/8" 8 5/8" 5 1/2"	619 2493 4924	750 1980 1800	Surface Surface Surface	Circ Circ Circ
Exxon Corp.	Yates "C" Federal #17	Oil	31	760 FNL, 1980 FWL	09/19/83	3897 2568-2605 3562-3626	13 3/8" 8 5/8" 5 1/2"	606 2482 3887	1050 930 750	Surface Surface Surface	Circ Circ Circ
Exxon Corp.	Yates "C" Federal #18	TA	31	2310 FS, 2310 FE	10/20/83	3885 2596-2757 3630-3640	13 3/8" 8 5/8" 5 1/2"	593 2491 3876	700 925 525	Surface Surface 1367	Circ Circ Temp Survey
Yates Pet	Stonewall "EP" State #1	Gas	30	1980 FN, 1980 FW	09/25/75	11478 10079-10097	13 3/8" 8 5/8" 5 1/2"	612 2799 11380	550 1650 1300	Surface Surface 4800	Circ Circ Temp Surv
Yates Pet	Stonewall "WM" State #1	Oil	30	560 FS, 1980 FE	06/02/83	4953 2587-2680	13 3/4" 8 5/8" 5 1/2"	545 2485 4953	500 1350 700	Surface Surface 1475	Circ Circ Temp Surv

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)	TOC	HOW TOC DETERMINED
Yates Pet	Stonewall "WM" State #3	Oil	30	330 FS, 1980 FW	07/22/83	4865	2530-2622 3422-3602	13 3/8" 8 5/8" 5 1/2"	545 2470 4864	650 550 500	Surface Surface 2430	Circ Circ CBL
Yates Pet	Stonewall "WM" State #2	Inact. Oil	30	450 FS, 990 FE	08/07/84	5450	4960-5216	13 3/8" 8 5/8" 5 1/2"	546 2410 4960	550 1050 750	Surface Surface 1500	Circ Circ Temp Surv
Yates Pet	Stonewall "WM" State #4	Oil	30	330 FS, 990 FW	11/22/83	4860	2524-2727 3620-3671	20" 13 3/8" 8 5/8" 5 1/2"	40 535 2642 4860	--- 500 1300 750	Surface Surface Surface 600	Circ Circ Circ CBL
Yates Pet	Stonewall "WM" State #5	Oil	30	1650 FS, 1980 FW	11/10/83	4900	3330-3367 3487-3515 3570-3576	13 3/8" 8 5/8" 5 1/2"	535 2404 4900	600 1355 700	Surface Surface 930	Circ Circ CBL
Yates Pet	Stonewall "YE" State #1	Oil	30	1650 FS, 1980 FE	12/29/83	4950	2595-2732	20" 13 3/8" 8 5/8" 5 1/2"	40 543 2415 4950	--- 550 900 750	Surface Surface Surface <2100	Circ Circ Circ CBL
Yates Pet	Stonewall "EP" State #5	Oil	30	2310 FN, 990 FW	03/14/84	4870	3361-3730 4142-4346	13 3/8" 8 5/8" 5 1/2"	544 2420 4870	500 1600 800	Surface Surface 880	Circ Circ CBL
Yates Pet	Stonewall "WM" State #6	Oil	30	1650 FS, 990 FW	12/27/83	4860	3349-3527	20" 13 3/8" 8 5/8" 5 1/2"	40 535 2410 4860	--- 550 800 800	Surface Surface Surface 190	Circ Circ Circ CBL
Yates Pet	Stonewall "EP" State #7	Oil	30	990 FNL, 990 FWL	01/19/84	5107	4979-4983	20" 13 3/8" 8 5/8" 5 1/2"	40 538 2372 5100	--- 500 1120 900	Surface Surface Surface <2300	Circ Circ Circ CBL
Yates Pet	Stonewall "EP" State #6	Gas	30	990 FNL, 2080 FWL	04/20/85	5100	4983-4992	13 3/8" 8 5/8" 5 1/2"	537 2469 5098	400 1725 600	Surface Surface 1950	Circ Circ CBL
Yates Pet	Stonewall "EP" State #8	Oil	30	2310 FN, 1980 FW	04/04/84	5303	3384-3412 3434-3541 3622-3688	13 3/8" 8 5/8" 5 1/2"	540 2404 5303	425 950 750	Surface Surface 1890	Circ Circ CBL

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

Page 4


OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)	TOC	HOW TOC DETERMINED
Exxon Corp.	Hondo-State Corn #1	Gas	32	1980 FN, 660 FW	05/02/77	11475	10385-10705	13 3/8"	565	800	Surface	Circ
								9 5/8"	2790	1750	Surface	Circ
								5 1/2"	11475	825	2433	Calculated
									+sqz w/ 1200 sx			
Maralo	Keystone #1	Gas	32	1980 NL, 1980 FEL	01/25/78	11600	6298-6503	13 3/8"	608	695	Surface	Circ
								8 5/8"	3010	1100	Surface	Circ
								4 1/2"	11600	875	5678	Calculated
Exxon Corp.	Hondo "A" State #1	Oil	32	660 FN, 660 FW	02/14/83	4050	2654-2709	8 5/8"	610	400	190	Temp Survey
								5 1/2"	4042	780		
Exxon Corp.	Hondo "A" State #3	Oil	32	1980 FS, 610 FW	05/24/83	4050	2506-2598	13 3/8"	590	880	Surface	Circ
								8 5/8"	2410	1450	Surface	Circ
								5 1/2"	4050	550	1292	Calculated
Exxon Corp.	Hondo "A" State #2	Oil	32	1980 FN, 330 FW	03/05/83	4047	2605-2620 2640-2660 3622-3636	8 5/8"	610	400	Surface	Circ
								5 1/2"	4047	770		
Exxon Corp.	Hondo "A" State #4	Oil	32	660 FS, 330 FW	06/12/83	3808	2585-2620	13 3/8"	590	800	Surface	Circ
								8 5/8"	2445	1330	Surface	Circ
								5 1/2"	3808	450	1551	Calculated
Exxon Corp.	Hondo Fee #2	Oil	32	1980 FS, 1650 FW	07/15/83	2813	2542-2556 2602-2612 2628-2640	13 3/8"	588	630	Surface	Circ
								8 5/8"	2422	1300	Surface	Circ
								5 1/2"	2813	135	2136	Calculated
Maralo Inc	Keystone #2	---	32	1980 FSL, 1980 FEL	08/29/94	6700	6307-6514	13 3/8"	502	875	Surface	Circ
								8 5/8"	2557	1300	Surface	Circ
								5 1/2"	6700	890	2236	Calculated
Maralo Inc	Keystone #4	---	32	1650 FNL, 1980 FWL	01/22/95	6650	6283-6484	13 3/8"	504	550	Surface	Circ
								8 5/8"	2518	1200	Surface	Circ
								5 1/2"	6650	750	2650	Temp Survey
Maralo Inc	Keystone #5	---	32	660 FNL, 1980 FEL		6331-6523		13 3/8"	530	550	Surface	Circ
								8 5/8"	2500	950	Surface	Circ
								5 1/2"	6680	630	2470	Temp Survey

WELLS WITHIN 1/2 MILE RADIUS OF
PROPOSED AVALON (DELAWARE) INJECTORS
EDDY COUNTY, NEW MEXICO

OPERATOR	WELL NAME	STATUS	SECT. #	FOOTAGE	DATE DRILLED	DEPTH	COMPLETION (PERFS)	CSG	DEPTH	CMT (SX)	TOC	HOW TOC DETERMINED
T-20-S, R-27-E												
MMU Prod.	State "GWA" #1	Oil	36	2180 FS, 660 FE	12/10/80	4845	4724-4766	13 3/8"	410	400		
								8 5/8"	2405	1200	Surface	Circ
								5 1/2"	4845	600	2270	Temp Survey
MMU Prod.	State "GWA" #2	Oil	36	660 FS, 660 FE	09/13/84	4825	4367-4373	13 3/8"	502	500		
								8 5/8"	2400	1350	1480 T. S.	Final TOC @ 833'
								5 1/2"	4825	550	2620	Temp Survey
Yates Pet.	Citdel "ZG" #1	Gas	36	330 RN, 330 FE	08/03/84	5100	4871-4880	13 3/8"	408	325		
							5023-5026	8 5/8"	2390	800	Surface	Circ
								4 1/2"	5100	710	<2100	CBL
Premier Prod.	Eddy "FV" State Com #1	Gas	25	1980 FN, 990 FE	05/12/76	11450	10014-10028	20"	30	---		
								13 3/8"	642	650		
								9 5/8"	3050	1350	1017	Calculated
								5 1/2"	11450	1070	6084	Calculated
Premier Prod.	Eddy "FV" State #3	Inact. Oil	25	660 FS, 330 FE	04/29/84	4975	2710-2716	13 3/8"	500	500		
							2723-2725	8 5/8"	2450	1800	Surface	Calculated
							2738-2740	5 1/2"	4975	800	963	Calculated
T-21-S, R-27-E												
Exxon Corp.	Burton Flat "Sec 6" St #1	Inact. Oil	6	660 FNL, 660 FEL	02/19/87	5500		13 3/8"	457	600		
								8 5/8"	2599	1300	Surface	Circ
								5 1/2"	5500	1000	1050	Temp Survey
Exxon Corp.	Burton Flat "Sec 6" St #3	Inact. Oil	6	660 FN, 1980 FE	07/27/84	6100	4642-4652	13 3/8"	463	600		
								9 5/8"	2500	1500	Surface	Circ
								7"	6100	1575	Surface	Circ
Exxon Corp.	Yates "C" Federal #35	Disposal	5	563 FNL, 560 FEL	10/30/85	3110	2702-2898	13 3/8"	629	950		
							2950-3098	8 5/8"	2592	1300	Surface	Circ
								5 1/2"	3110	550	Surface	Circ


--- = Information not available


FRESH WATER WELLS



Proposed Unit Area

- Wells
- ◆ Fresh Water Wells





Laboratory Services, Inc.

1331 Tasker Drive
Hobbs, New Mexico 88240

Telephone: (505) 397-3713

WATER ANALYSIS

COMPANY Exxon Company USA

SAMPLE Riggs/Hood

SAMPLED BY Exxon

DATE TAKEN 6-6-95 7:00 AM

REMARKS

Barium as Ba	0.00
Carbonate alkalinity PPM	0
Bicarbonate alkalinity PPM	116
pH at Lab	7.02
Specific Gravity @ 60° F	1.004
Magnesium as Mg	1,218
Total Hardness as CaCO ₃	2,100
Chlorides as Cl	372
Sulfate as SO ₄	2,625
Iron as Fe	0.10
Potassium	0.31
Hydrogen Sulfide	0.00
Resistivity Ohms	22.2° C
Total Dissolved Solids	2,040
Calcium as CA	882
Nitrate	17.60

Results reported as Parts per Million unless stated

Langelier Saturation Index -0.01

Analysis by Rolland Perry
Date: 06-07-95

Exhibit No. **35**
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995



Laboratory Services, Inc.

1331 Tasker Drive
Hobbs, New Mexico 88240

Telephone: (505) 397-3713

WATER ANALYSIS

COMPANY Exxon Company USA

SAMPLE Don Rains

SAMPLED BY Exxon

DATE TAKEN 06-05-95

REMARKS

Barium as Ba 0.00

Carbonate alkalinity PPM 0

Bicarbonate alkalinity PPM 144

pH at Lab 7.06

Specific Gravity @ 60° F 1.004

Magnesium as Mg 1,376

Total Hardness as CaCO₃ 2,372

Chlorides as Cl 760

Sulfate as SO₄ 2,500

Iron as Fe 0.65

Potassium 0.47

Hydrogen Sulfide 0.00

Resistivity Ohms 22.2° C

Total Dissolved Solids 2,720

Calcium as CA 996

Nitrate 15.40

Results reported as Parts per Million unless stated

Langelier Saturation Index +0.19

Analysis by Rolland Perry

Date: 06-07-95

AVALON (DELAWARE) UNIT

RESERVES BY TRACT*

TRACT	REMAINING PRIMARY RESERVES	WATERFLOOD RESERVES	TERTIARY RESERVES
1	0.00	0.00	203.90
2	741.80	4,368.20	18,995.00
3-A	0.00	345.10	530.60
3-B	43.40	403.60	1,693.00
3-C	0.00	0.80	446.70
3-D	33.40	373.30	1,045.90
3-E	0.00	0.00	362.50
4-A	0.00	0.00	852.50
4-B	0.00	0.00	247.40
5-A	53.40	368.10	1,425.90
5-B	19.30	174.50	1,189.70
5-C	33.80	741.50	2,177.20
5-D	40.30	698.40	2,009.30
5-E	20.20	157.50	966.20
5-F	0.00	69.30	481.00
6	0.00	0.00	1,626.00
7	0.00	0.00	427.60
8	0.70	0.00	165.80
9	0.00	0.00	444.30
10	202.80	499.40	3,350.90
11	3.10	69.70	1,050.50
12	0.00	0.00	191.10
TOTAL	1,192.20	8,269.40	39,883.00

RESERVE DATA

UNITS ARE THOUSAND OF BARRELS

* From Exhibit D in the Unit Agreement.

Exhibit No. **36**

Exxon Corporation

NMOCD Cases 11297 & 11298

Hearing Date: June 29, 1995

NMOCD Hearing

June, 1995

AVALON (DELAWARE) UNIT

EQUITY FORMULA SUMMARY

- **Tract participation = 25% (Primary) + 50% (Secondary) + 25% (Tertiary)**

Where: Primary = Tract Remaining Primary Reserves as of 1/1/93

Secondary = Tract Waterflood Reserves

Tertiary = Tract CO₂ Reserves

- **Reserve Weighting Rationale**

^{20%}
^{18%}
^{60%}
Primary: Small reserves, but highest value per barrel with lowest risk (already developed, established decline)

Secondary: Main objective of unit, large reserves, low risk (same project area as primary, moderate development and operating costs)


Tertiary: Largest reserve target, but lowest value per barrel with highest risk (large expansions, high development and operating costs, very sensitive to future pricing)

AVALON (DELAWARE) UNIT

EFFECT OF PROPOSED UNIT ON PREMIER

- Premier Tracts Cumulative Production = 5,100 BO
- Premier Without Unit
 - Current Production = 0 BOPD
 - Remaining Continued Operations Reserves = 0 BO
- Premier Share With Unit
 - 1% of Future Production
 - Remaining Primary Reserves (1/1/95) = 8,000 BO
 - Primary + Secondary = 90,000 BO
 - Primary + Secondary + Tertiary = 489,000 BO

WATERFLOOD PROJECT AREA



WELL SYMBOL LEGEND	
●	Oil Well
→	Injector (Conversion)
→	Injector (Proposed)
X	Water Source Well
○	Well for Future Use
*	Disposal Well


Proposed Unit Area Outline

Waterflood Project Area Outline

WATERFLOOD PROJECT AREA

WELL SYMBOL LEGEND

●	Oil Well
⦿	Injector (Conversion)
⦿	Injector (Proposed)
X	Water Source Well
○	Well for Future Use
*	Disposal Well



Proposed Unit Area Outline

Waterflood Project Area Outline

Allowables set @ well capacities

Exhibit No. **39**

Exxon Corporation

NMOCD Cases 11297 & 11298

Hearing Date: June 29, 1995

June, 1995

NMOCD Hearing

EXXON
SURVEYED LOCATIONS

MIDLAND MAP
PERMITTED LOCATIONS



500 250 0 500 1000 1500

Plot Scale: 1" = 500'

EXXON COMPANY, U.S.A.

A DIVISION OF EXXON CORPORATION

PRODUCTION DEPARTMENT

MIDLAND PRODUCTION ORGANIZATION

AVALON AREA CONFLICTING WELL POSITIONS

SECTION 19, T20S, R28E, N.M.P.M.

AVALON (DELAWARE) FLD.

EDDY CO., N.M.

DRAWN M.L.HOSTAS	REVISION DATE -	SCALE 1"=500' 6/14/95	BOOK: XX XX PAGE:	FILE NO. A10975
ENGR. SECTION SURVEY GROUP	BY -			



Exhibit No. **40**
Exxon Corporation
NMOCD Cases 11297 & 11298
Hearing Date: June 29, 1995