M-E-M-O-R-A-N-D-U-M (3-99-13)

To:

All Operators, San Juan Basin

From:

Charlie T. Perrin, Deputy Oil & Gas Inspector

Subject:

2000 District III Bradenhead Test Schedule

Date:

December 15, 1999

You will conduct Bradenhead tests on all wells in the following areas before November 1, 2000:

- A. All wells in San Juan County not tested in 1999, consisting of all wells from 21N-08W to 29N-08W, but not including 29-08W and to the Arizona state line.
- B. All wells from 29N and 30N-12W to the Arizona State line.
- C. All wells from 31N and 32N-13W to the Arizona State line.
- D. Those portions of 31N and 32N-06W within San Juan County and all wells in 32N-07W and 08W

Tests will be conducted in the following manner:

- 1. Indicate whether the well is shut in or producing. Record the pressures measured on the tubing and each casing string including the intermediate casing, using a deadweight tester or a calibrated pressure gauge.
- 2. Open the bradenhead valve to the atmosphere. If a gas or liquid flow is observed or indicated, flow the bradenhead for a minimum of 15 minutes. Record pressures at five-minute intervals on the PRODUCTION AND EACH INTERMEDIATE CASING STRING.
- 3. Describe any discharge from the bradenhead including measured or estimated rates of flow. If the intermediate casing has pressure, repeat the procedure by flowing the intermediate casing and recording the production.
- 4. The original and one copy (total of two) of each test must be SUBMITTED TO THIS OFFICE WITHIN 30 DAYS OF THE TEST COMPLETION.

 | BEFORE EXAMINE

BEFORE EXAMINER CATANACH

OIL CONSERVATION DIVISION

OCD

EXHIBIT NO.



Page 2
Memo 3-99-13
December 15, 1999

Tests shall be completed before November 1, 2000.

Each operator of wells in the referenced areas will submit a schedule to this office before April 1, 2000, indicating when the individual wells will be tested. Identify the wells by API number, property name, well number and location using unit letter, section, township and range. INDICATE BY ASTERISK (*) WELLS THAT ARE IN THE VULNERABLE AREA AS DEFINED BY DIVISION ORDER R-7940-C.

Division personnel will witness the tests as our schedules permit.

All buried valves MUST be dug out and checked BEFORE testing begins.

NOTE: THE BRADENHEAD TEST REPORTING PROCEDURE HAS BEEN REVISED. SUBMIT ALL REQUIRED INFORMATION