




Union Texas
Petroleum



Southwest Division
4000 North Big Spring
Suite 500
Midland, TX 79705
Telephone (915) 684-0600

February 13, 1985

New Mexico Oil Conservation Commission
P. O. Box 2088
Santa Fe, New Mexico 87501

Re: Application to Convert the Post No. 1 Well to Salt Water Disposal

Gentlemen:

Attached is the application by Union Texas Petroleum Corporation to convert subject well to Salt Water Disposal purposes. Copies of this application have also been sent to all offset operators and surface owners by certified mail and to the Hobbs Daily News Sun for publication under legal notices. Copies of newspaper clipping and affidavit of publication will be sent to you at a later date.

Thank you for your services.

UNION TEXAS PETROLEUM CORPORATION


W. A. Higgins
Regulatory Compliance Coordinator

WAH/gad
Attachment

NO. OF COPIES RECEIVED	
DISTRIBUTION	
SANTA FE	
FILE	
U.S.G.S.	
LAND OFFICE	
OPERATOR	

NEW MEXICO OIL CONSERVATION COMMISSION

Form C-101
Revised 1-1-85

5A. Indicate Type of Lease
STATE FEE

5. State Oil & Gas Lease No.

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work		7. Unit Agreement Name	
b. Type of Well DRILL <input type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/>		8. Farm or Lease Name	
OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER Salt Water Disposal <input type="checkbox"/> SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		Post	
2. Name of Operator		9. Well No.	
Union Texas Petroleum Corporation		1	
3. Address of Operator		10. Field and Pool, or Wildcat	
4000 N. Big Spring, Suite 500, Midland, Texas 79705		King, South (Dev)	
4. Location of Well		17. County	
UNIT LETTER <u>N</u> LOCATED <u>990</u> FEET FROM THE <u>South</u> LINE		Lea	
AND <u>1650</u> FEET FROM THE <u>West</u> LINE OF T1C <u>1</u> T10R <u>14S</u> R3E <u>37E</u> NMPM			
21. Elevation (show whether DT, RT, etc.)		19. Formation	20. Rotary or C.T.
3831 Gr.		12,810	Devonian Rotary
21A. Kind of rock (see note)	Blanket	21B. Frilling Contractor	Unknown
		22. Approx. Date Work will start	
		March, 1985	

PROPOSED CASING AND CEMENT PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	SACKS OF CEMENT	EST. TOP
17-1/2	13-3/8	48	416	500 "C"	Circ.
12-1/4	8-5/8	32	4650	2000 "C"	2160 T.S.
7-7/8	5-1/2	17	12,865	1300 "H"	8260 T.S.

Union Texas Petroleum Corporation proposes to re-enter and convert subject well to SWD after CO to TD of 12,810'. Casing perforations 12,790'-802' will be made in addition to existing perforations 12,729'-750'. Following acid treatment of perforations, 2-7/8" IPC tubing will be run with Baker A-3 Loc-Set packer set at 12,650' and disposal begun.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM. IF PROPOSAL IS TO DEEPEN OR PLUG BACK, GIVE DATA ON PRESENT PRODUCTIVE ZONE AND PROPOSED NEW PRODUCTIVE ZONE. GIVE BLOWOUT PREVENTER PROGRAM, IF ANY.

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

Signed [Signature] Title Regul. Compl. Coordinator Date 2-13-85

(This space for State Use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

NE MEXICO OIL CONSERVATION COMMISSIC
WELL LOCATION AND ACREAGE DEDICATION PLAT

Form C-102
Supersedes C-128
Effective 1-1-65

All distances must be from the outer boundaries of the Section.


Operator UNION TEXAS PETROLEUM CORPORATION		Lease POST		Well No. 1
Unit Letter N	Section 1	Township 145	Range 37E	County LEA
Actual Footage Location of Well: 990 feet from the SOUTH line and 1650 feet from the WEST line				
Ground Level Elev. 3831'	Producing Formation	Pool	Dedicated Acreage: Acres	

1. Outline the acreage dedicated to the subject well by colored pencil or hachure marks on the plat below.
2. If more than one lease is dedicated to the well, outline each and identify the ownership thereof (both as to working interest and royalty).
3. If more than one lease of different ownership is dedicated to the well, have the interests of all owners been consolidated by communitization, unitization, force-pooling, etc?

Yes No If answer is "yes," type of consolidation _____

If answer is "no," list the owners and tract descriptions which have actually been consolidated. (Use reverse side of this form if necessary.) _____

No allowable will be assigned to the well until all interests have been consolidated (by communitization, unitization, forced-pooling, or otherwise) or until a non-standard unit, eliminating such interests, has been approved by the Commission.



CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief.

Name
Richard B. Duniver

Position
Registered Professional Engineer

Company
Le 13, 1955

Date

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my knowledge and belief.

October 7, 1982

Date Surveyed

RICHARD B. DUNIVER

Registered Professional Engineer
and/or Land Surveyor

Certificate No.

4882B

STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENT

OIL CONSERVATION DIVISION
P. O. BOX 2088
SANTA FE, NEW MEXICO 87501

Form C-103
Revised 10-1-78

NO. OF COPIES RECEIVED	
DISTRIBUTION	
SANTA FE	
FILE	
U.S.G.S.	
LAND OFFICE	
OPERATOR	

3a. Indicate Type of Lease
State Fee

5. State Oil & Gas Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS

(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT -" (FORM C-101) FOR SUCH PROPOSALS.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER: Salt Water Disposal	7. Unit Agreement Name
2. Name of Operator Union Texas Petroleum Corporation	8. Farm or Lease Name Post
3. Address of Operator 4000 N. Big Spring, Suite 500, Midland, Texas 79705	9. Well No. 1
4. Location of Well UNIT LETTER N 990 FEET FROM THE South LINE AND 1650 FEET FROM THE West LINE, SECTION 1 TOWNSHIP 14S RANGE 37E N.M.P.M.	10. Field and Pool, or WHdcat King South (Dev)
15. Elevation (Show whether DF, RT, GR, etc.) 3831 Gr.	12. County Lea

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
PERFORM REMEDIAL WORK <input type="checkbox"/>	PLUG AND ABANDON <input type="checkbox"/>	REMEDIAL WORK <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
TEMPORARILY ABANDON <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	COMMENCE DRILLING OPNS. <input type="checkbox"/>	PLUG AND ABANDONMENT <input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	OTHER: Convert to SWD <input checked="" type="checkbox"/>	CASING TEST AND CEMENT JOB <input type="checkbox"/>	OTHER <input type="checkbox"/>

17. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work) SEE RULE 1103.

- MIRUSU, Install BOP. POH and lay down tbg.
- Clean out to TD 12,810'.
- Perforate 5-1/2' casing 12,790-802' (26).
- Acidize 12,790' to 802' w/2000 gal 15% HCl NEFE.
- Test injection rates on all perforations.
- Run 2-7/8" IPC tubing on Baker A-3.
Loc-Set packer and set at 12, 650'.
- Commence disposal.
- RDMOSU, clean up location.

18. I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNED [Signature] TITLE Regul. Compl. Coordinator DATE 2-13-85

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:

Sun Oil
I-N.M. St. "Y"
TD 11,600

Cayman
I-McCrory
TD 10,170

Lone Star
I-A Brady-Lowe
TD 12,641

T
13
S

28

27

26

25

30

29

Forest
I-State
TD 13,496

Cotton Pet.
I-Lowe Land
TD 12,546

Williams
I-"B" 25
TD 13,145

33

34

35

36

31

32

Houston
I-AB St.
TD 11,570

Kerr-McGee

TXO

R 37 E

R 38 E

Mary McCrory Min.

4

3

2

1

6

5

Amerada
I-Hobbs
TD 11,754

Skelton
I-A St.
TD 12,664

(ARCO)
I-Reed
TD 12,865

Helmerich
I-Love
TD 12,860

Anson
I-McRory

Mary E. Love

(TPC 80)
I-St
TD 10,715

E Exxon
I-N.M. E. St.

UTP
Barnhill

(Tex-Or)
I-Heidel
TD 13,805

F B Cressy

Edsel
I-Edsel St.

Read, et al
I-S. King
TD 13,100

UTP
1

9

10

11

12

7

8

F. Kershner

Post

D. L. Love

T
14
S

Superior
I-Malone
TD 13,200

(TPC 80)
I-Schenck
TD 13,110

O. T. Spears

16

15

14

13

18

17

Enstar
I-Smith
TD 10,800

Sinclair
I-A Smith
TD 10,850

21

22

23

24

19

20

Sunmark
I-Lowe
TD 9550

28

27

23

24

19

20

33

34

23

24

19

20

 = UTP Operator

UNION TEXAS PETROLEUM CORPORATION

**KING SOUTH AREA
LEA COUNTY, NEW MEXICO**

**PROPOSED SWD
POST NO. 1**

SCALE IN FEET



W.A.H. SOUTHWEST DIVISION

2/85

OFFSET OPERATOR AND SURFACE OWNERS

Skelton Oil Company
Box 176
Hobbs, New Mexico 88240

Mrs. Mary McCrory (NE/4 Sec. 1, 14S, 37E)
C/O James R. McCrory
P. O. Box 25764
Albuquerque, New Mexico 87125

Mr. Dave E. Williams
Rt. 1, Box 344
Lovington, N.M. 88260

APPLICATION FOR AUTHORIZATION TO INJECT

I. Purpose: Secondary Recovery Pressure Maintenance Disposal Storage
Application qualifies for administrative approval? yes no

II. Operator: Union Texas Petroleum Corporation

Address: 4000 N. Big Spring Street, Suite 500

Contact party: William A. Higgins Phone: 915-684-0600

III. Well data: Complete the data required on the reverse side of this form for each well proposed for injection. Additional sheets may be attached if necessary.

IV. Is this an expansion of an existing project? yes no
If yes, give the Division order number authorizing the project _____.

V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review.

* VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.

VII. Attach data on the proposed operation, including:

1. Proposed average and maximum daily rate and volume of fluids to be injected;
2. Whether the system is open or closed;
3. Proposed average and maximum injection pressure;
4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and
5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).

*VIII. Attach appropriate geological data on the injection zone including appropriate lithologic detail, geological name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such source known to be immediately underlying the injection interval.

IX. Describe the proposed stimulation program, if any.

* X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division they need not be resubmitted.)

* XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.

XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground source of drinking water.

XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form.

XIV. Certification

I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.

Name: Gary R. Hendricks Title Division Operations Engineer

Signature: Gary R. Hendricks Date: 2-4-85

* If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be duplicated and resubmitted. Please show the date and circumstance of the earlier submittal.

III. WELL DATA

A. The following well data must be submitted for each injection well covered by this application. The data must be both in tabular and schematic form and shall include:

- (1) Lease name; Well No.; location by Section, Township, and Range; and footage location within the section.
- (2) Each casing string used with its size, setting depth, sacks of cement used, hole size, top of cement, and how such top was determined.
- (3) A description of the tubing to be used including its size, lining material, and setting depth.
- (4) The name, model, and setting depth of the packer used or a description of any other seal system or assembly used.

Division District offices have supplies of Well Data Sheets which may be used or which may be used as models for this purpose. Applicants for several identical wells may submit a "typical data sheet" rather than submitting the data for each well.

B. The following must be submitted for each injection well covered by this application. All items must be addressed for the initial well. Responses for additional wells need be shown only when different. Information shown on schematics need not be repeated.

- (1) The name of the injection formation and, if applicable, the field or pool name.
- (2) The injection interval and whether it is perforated or open-hole.
- (3) State if the well was drilled for injection or, if not, the original purpose of the well.
- (4) Give the depths of any other perforated intervals and detail on the sacks of cement or bridge plugs used to seal off such perforations.
- (5) Give the depth to and name of the next higher and next lower oil or gas zone in the area of the well, if any.

XIV. PROOF OF NOTICE

All applicants must furnish proof that a copy of the application has been furnished, by certified or registered mail, to the owner of the surface of the land on which the well is to be located and to each leasehold operator within one-half mile of the well location.

Where an application is subject to administrative approval, a proof of publication must be submitted. Such proof shall consist of a copy of the legal advertisement which was published in the county in which the well is located. The contents of such advertisement must include

- (1) The name, address, phone number, and contact party for the applicant;
- (2) the intended purpose of the injection well; with the exact location of single wells or the section, township, and range location of multiple wells;
- (3) the formation name and depth with expected maximum injection rates and pressures; and
- (4) a notation that interested parties must file objections or requests for hearing with the Oil Conservation Division, P. O. Box 2088, Santa Fe, New Mexico 87501 within 15 days.

NO ACTION WILL BE TAKEN ON THE APPLICATION UNTIL PROPER PROOF OF NOTICE HAS BEEN SUBMITTED.

NOTICE: Surface owners or offset operators must file any objections or requests for hearing of administrative applications within 15 days from the date this application was mailed to them.

The deepest fresh water (10,000 mg/l or less solids) overlying the proposed zone of injection is the top of the Triassic at approximately 300'. The Santa Rosa (located to a depth of 2050' is not believed to be potable in the area).

- IX. The well will be stimulated with 15% HCl (if required) to remove near wellbore damage caused by drilling operations.
- X. No logging programs are planned. The Post #1 has a GR-CNL-LDL log dated 12-26-82.
- XI. A chemical analysis of water taken from three fresh water wells near the proposed well is attached. Also attached is a map showing the location of the fresh water wells from which the samples were taken.
- XII. Union Texas Petroleum Corporation has examined engineering and geologic data and finds no evidence of open faults or any other hydrologic connection between the disposal zone and any underground source of drinking water.

GRH/gad
2-4-85

**Water Analysis of Fresh Water Wells
Surrounding Proposed SWD Well**

Analysis performed by Halliburton Services Laboratory, Hobbs, New Mexico on 3-3-1983


Well No. as shown on attached map	1	2	3
Resistivity	5.7 at 74°F	11.6 at 74°F	11.4 at 74°F
Specific Gravity	1.004	1.001	1.001
pH	6.6	7.0	7.0
Calcium (dpl)	150	80	105
Magnesium	21	15	14
Chlorides	450	100	150
Sulfates	450	300	380
Bicarbonates	315	290	270
Soluble Fe	Nil	Nil	Nil
Sodium (calc)	414	198	232
Total Dissolved Solids Milligrams per liter	1800	983	1152

UNION TEXAS PETROLEUM
ANALYSIS OF WATER TO BE DISPOSED
POST #1 WELL

Reservoir	Devonian
Specific Gravity	1.0620
HCO ₃	200 mg/l
CaCO ₃	15,000 mg/l
Ca	3560 mg/l
Mg	1482 mg/l
Na, K	26926 mg/l
SO ₄	1704 mg/l
Cl	50,779 mg/l
Fe	43.7
Total Solids	84,651 mg/l
H ₂ S	0
Rw at 77°F	0.110

Grt.
2-28-83

UNION TEXAS PETROLEUM		POST		
OPERATOR		LEASE		
1	1650'FWL and 990'FSL	1	T-14-S	R-37-E
WELL NO.	FOOTAGE LOCATION	SECTION	TOWNSHIP	RANGE



Tabular Data

Surface Casing

Size 13-3/8 " Cemented with 500 sx.
 TOC Sur feet determined by Circulations
 Hole size 17-1/2

Intermediate Casing

Size 8-5/8 " Cemented with 2000 sx.
 TOC 2160' feet determined by Temp. Survey
 Hole size 12-1/4

Long string

Size 5-1/2 " Cemented with 1300 sx.
 TOC 8280 feet determined by Cement Bond Log
 Hole size 7-7/8"
 Total depth 12807

Injection interval

12,729' feet to 12,802' feet
 (perforated or open-hole, indicate which)

Tubing size 2-7/8 lined with Plastic set in a
 (material)
Baker A-3 Lok-Set packer at 12650' feet
 (brand and model)
 (or describe any other casing-tubing seal).

Other Data

- Name of the injection formation Devonian
- Name of Field or Pool (if applicable) South King Devonian
- Is this a new well drilled for injection? Yes No
 If no, for what purpose was the well originally drilled? Devonian Oil Well
- Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail (sacks of cement or bridge plug(s) used) No
- Give the depth to and name of any overlying and/or underlying oil or gas zones (pools) in this area. The Wolfcamp reservoir 9400' produces in the King Devonian Field located one mile to the north.

UNION TEXAS PETROLEUM

FIELD: SOUTH KING DEKONIAN

LEASE: BARNHILL WELL NO. 1

DATE: 1-85 SPUDDED: _____ COMP 9-83


ELEV: 3831 GL

LOCATION: 1650' FSL AND 990' FWL

SEC 1, T-14-S, R-37-E

LEA COUNTY, New Mexico

Currently
Producing



13 3/8 " 48 # CSG. at 405 w/ 500 SX.
17 1/2 " HOLE TOC CIRC

8 5/8 " 32 # CSG AT 466' w/ 2200 SX
12 1/2 " HOLE TOC 2700 b. TS'

12557-670
Casing at 12695'
12706-18


5 1/2 " 17 # CSG. at 12744 w/ 2775 SX.
7 7/8 " HOLE TOC 6400 b. TS

TD 12745
PBTD 12700

Currently
Producing

UNION TEXAS PETROLEUM

FIELD: SOUTH KING DEVONIAN
LEASE: Post WELL NO. 2
DATE: 1-85 SPUDDED: _____ COMP. 11-83
ELEV: 3832 GL
LOCATION: 467' FWL AND 700' FSL
SECTION 1, T-14-S, R-37-E
LEA COUNTY, New Mexico



13 3/8 " 68 * CSG. at 406 w/ 500 sx. _____
17 1/4 " HOLE TOC Circ

8 3/8 " 32 * CSG AT 4650 w/ 2000 sx _____
12 1/4 " HOLE TOC 200' by 'Temp Surve

12022-42
RTISP # 12,655
12666-686

5 1/2 " 17 # CSG. at 12745 w/ 3025 sx. _____
7 7/8 " HOLE TOC 3140' by T.S.

TD 12745
PBTD 12700

Currently
Producing

UNION TEXAS PETROLEUM

FIELD: SOUTH KING DEVONIAN

LEASE: Post WELL NO. 3

DATE: 1-85 SPUDDED: _____ COMP. 5-84

ELEV: 3833 G

LOCATION: 330 FNL AND FWL

SEC 12, T-14-S, R-37-E

LEA COUNTY, N.M.

13 3/8 " 48 # CSG. at 420 w/ 500 SX. _____
17 1/4 " HOLE TOC CIRC

8 5/8 " 32 # CSG AT 4671 w/ 2000 SX _____
12 1/4 " HOLE TOC SURFACE

PERFORATIONS 12688-12808

5 1/2 " 17 # CSG. at 14,000 w/ 2900 SX. _____
7 7/8 " HOLE TOC 1000' by T.S.

TD 14,000
PBD 13,955

UNION TEXAS PETROLEUM

FIELD: WILDCAT
LEASE: TRAINER WELL NO. #1-KING
DATE: 1-85 SPUDDED: _____ COMP 7-65
ELEV: 3844 DF
LOCATION: 660' PSL AND 330' FEL
SECTION 2 T-14-S, R-37-E
LEA COUNTY, New Mexico

10 SXS AT SURFACE

255s 275-325

1 3/8" # CSG. AT 308 W/ 300 SX.
1 1/2" HOLE TOC SURFACE

50 SXS ACROSS 9 5/8" STUB AT 1109

255s 4625-4700

9 5/8" # CSG AT 4681 W/ 500 SX
12 1/4" HOLE TOC 3276' CALCULATION

255s AT 5600

255s AT 7300


60 SXS ACROSS 4 1/2" STUB AT 815

255s 12,300-12,633

9 12520-12,633

4 1/2" # CSG. AT 12785 W/ 400 SX.
7 3/4" HOLE TOC 11,242 CAL


TD 13000
PBTD _____



UNION TEXAS PETROLEUM

FIELD: WILDCAT
LEASE: SOUTH KING WELL NO. 1
DATE: 1-85 SPUDDED: _____ COMP _____
ELEV: 3837' GL
LOCATION: 1200' FSL AND 660' FEL
SEC. 2 T-14-S, R-37-E
LEA COUNTY, N.M.

10 Sxs AT SFC



1 3/4 " _____ *CSG. AT 380 W/ 400 SX. _____
1 7/8 " HOLE TOC CIRC

Cut 8 5/8" at 1228
50 Sxs 1260-1160

35 Sxs 4740-4640
8 5/8 " _____ *CSG AT 4690 W/ 425 SX _____
11 " HOLE TOC 3845 'CALC

35 Sxs 6150-6050

35 Sxs 8010-7910

35 Sxs 9480-380

35 Sxs 11,550-450

35 Sxs AT 12570-470


PRODUCTION CASINGS NOV _____
" _____ *CSG. AT _____ W/ _____ SX. _____
" HOLE TOC _____

TD 13,100
PBTD _____

UNION TEXAS PETROLEUM

FIELD: King
 LEASE: McCromy WELL NO. 1
 DATE: 5/23 SPUDED: 9/28 COMP. 12/28
 ELEV.: 3837 GR
 LOCATION: 2321 FNL & 330 FNL
Sec. 1, T14. S. R. 37-E
Lea County, New Mexico

P & A 9.14.70



15 SX plug at surface

50 SX plug at 5400

13 3/4 # CSG. at 328 w/ 400 SX.
 " HOLE TOC

25 SX plug at 1130

8 5/8 # CSG. at 4265 w/ 535 SX.
 " HOLE TOC

25 SX plug at 4265

25 SX plug at 5208 across 5 1/2" casing stub

C.B.P. at 10820 w/ 20' plug on top

5 1/2 # CSG. at 11220 w/ 300 SX.
 " HOLE TOC

TD 12900
 PBD 11/00