


ROBERT L. BAYLESS

PETROLEUM PLAZA BUILDING
P. O. BOX 168
FARMINGTON, NEW MEXICO 87499
(505) 326-2659



July 2, 1987

William J. Lemay, Chairman
Oil Conservation Commission
P.O. Box 2088
Santa Fe, New Mexico 87501

*Set for
hearing
Case 9190*

RE: Request for Administrative
Approval to Downhole Commingle
Robert L. Bayless
Jicarilla 519 #1
Unit O, Sec. 18, T30N-R2W
Undesignated Gallup and
Undesignated Pictured Cliffs Fields
Jicarilla Contract #519
Rio Arriba County, New Mexico

Dear Mr. Lemay:

By this letter, we request administrative approval to commingle production from the Gallup and Pictured Cliffs formations within the wellbore of the above captioned well.

The Jicarilla 519 #1 well was drilled by Amoco Production Company in November and December of 1985. A complete daily activity report for this well is presented as Attachment #1. Production casing, (5-1/2") was set and cemented at the total depth of the well, 8703 feet. The Dakota interval, (8578-8597 ft.) was tested and abandoned by setting a cast iron bridge plug at 8150 feet and capping it with 2 sacks of cement. This is the current PBTD for this well. The Gallup interval (7280-7704 ft.) was perforated and fracture stimulated with 254,730 gallons of 30# crosslinked gelled fluid containing 400,000 lbs. of 20-40 sand. Amoco determined this well to be uneconomical and turned operations of this well over to Robert L. Bayless.

Bayless ran a 3 hour flow test for the Gallup formation on May 28, 1987, which resulted in an AOF of 1032 MCFGPD (Attachment #2). A retrievable bridge plug was set at 4000 feet, and the Pictured Cliffs formation was perforated from 3723 to 3728 feet. The Pictured Cliffs formation was then fracture stimulated with 16,5000 gallons of 70 quality foam containing 20,000 lbs. of sand. A 3 hour flow test was conducted on the Pictured Cliffs formation on June 15, 1987, which resulted in an AOF of 762 MCFGPD (Attachment #3). In addition to the AOF tests performed on each zone by Bayless, a 12 day flow test was performed on the Gallup formation by Amoco in June of 1986, and Bayless performed an 8 day flow test on the Pictured Cliffs formation in June of 1987. The Gallup zone averaged 149 MCFGPD with 18 BWPD, while the Pictured Cliffs zone averaged 75 MCFGPD with 3 BWPD. Both tests were run against 50-60 psi backpressure. These tests are presented as Attachments #4 and #5.

William J. Lemay, Chairman

Page 2

July, 1987

The flow test results from each zone indicate that each zone has marginal gas production capabilities and some associated water production. These tested flow rates are performed against 50-60 psi backpressure, while line pressures in the area can get as high as 450-500 psi. The actual gas sales production rates from each zone will be even lower against this higher backpressure, with the possibility of the backpressure stopping flow from the zone, which would result in compression expenses to re-establish the flow. The water production seen from each zone could also restrict gas production from each zone, or possibly log off the flow from the zone. This would necessitate artificially lifting this fluid, resulting in further expenditures. If commingling is granted in this wellbore, the combined zones would have a better chance of production against higher line pressures without compression and would be better able to lift the fluid in these zones without artificial lift. The gas produced from the Gallup and Pictured Cliffs formations is very similar in this area. The average gas gravity for the Pictured Cliff zone in this area is .653 with an average BTU value of 1131, while the average gas gravity for the Gallup interval is .628, with an average BTU of 1072. The gas gravities used for each zone were taken from the closest offsetting wells having this data available. A summary of this data is presented in Attachment #6. The small difference in these values indicate that the gas produced from both zones is very similar and should not cause any damage should crossflow occur between zones.

From the AOF tests discussed earlier, the 1065 psi surface shutin pressure taken on the Pictured Cliff zone corresponds to a calculated bottomhole pressure of 1178 psi at 3725 ft.(mid perf of the P.C. zone). The 2957 psi surface shutin pressure taken on the Gallup zone corresponds to a calculated bottomhole pressure of 3600 psi at 7492 ft.(mid perf of the Gallup interval). Even though the Pictured Cliffs bottomhole pressure is less than 50% of the Gallup bottomhole pressure, the gas from both zones is very similar, and any crossflow occurring between zones will cause no damage to the formation.

The production from the Pictured Cliffs and Gallup zones could be allocated using the ratios of the rate of flow calculated during the AOF tests performed by Bayless. Using these tests, 57% of the commingled gas production should be allocated to the Gallup formation and 43% of the gas should be allocated to the Pictured Cliffs formation. This allocation formula is shown in Attachment #7. The value of the gas from each zone is approximately the same, so the commingling of this natural gas will not decrease its sales value.


Attachment #8 is an acreage plot showing the ownership of leases in the vicinity of the Jicarilla 519 #1 well. The ownership (working interest, royalty, and overriding royalty) of both the Pictured Cliffs and Gallup formations is common in this well. The operation of each of the leases

William J. Lemay, Chairman
Page 3
July 2, 1987

around this well is controlled by or will be controlled by Robert L. Bayless through farmout agreements. At this time, Union Oil Company of California controls Jicarilla Contract #516. They have been notified of this commingling application by certified mail. A copy of this letter is enclosed as Attachment #9. By copy of this application, we have also advised the BLM of our plans to downhole commingle the Gallup and Pictured Cliffs formation in this well.

It is obvious from the production tests taken on the Pictured Cliffs and Gallup zones that gas production from this well will be low, resulting in marginal gas reserves and economics for the well. The high pipeline pressures in the area could force Bayless to compress this gas to produce it, or the water produced from each zone could force more expenditures to artificially lift this produced fluid. Either or both of these expenditures could possibly be avoided by approval of downhole commingling in this well.

Sincerely,

A handwritten signature in dark ink, appearing to read "Kevin H. McCord". The signature is fluid and cursive, with the first name "Kevin" and last name "McCord" clearly distinguishable.

Kevin H. McCord
Petroleum Engineer

KHM:blk

Attachments

ATTACHMENT #1

DENVER REGION WYO FARMINGTON DISTRICT *** 02/13/87 *** PAGE 2

*** 11/07/83 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMCCC-PRODUCTION,

 FLAC 346167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMCCC W.I. 1.0000
 REMARKS: BR X LOG 100% COMP; WCCR
 JOB INITIATION REPORT: RELEASED DRILL 10/26/83,
 FORM 46 RECEIVED BY DIST 09/27/83

*** 11/19/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMCCC PRODUCTION,

 FLAC 346167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMCCC W.I. 1.0000
 OPERATIONS: TO 459 FT, REAM, FM CN X SH, 459
 PERTINENT DATA: RIG MOVE CN 11/16/85, RIG RELEASED 12/10/85,
 SUSPENDED 01/09/84, INDEFINITE SUSPENSION
 MUD: DEPTH 459 FT, NATIVE MUD, 8.8 PPG
 BIT AND HYDRAULICS: BIT #000001, 12.250 IN, CSC3, JETS 12/12/8 /-,
 DEPTH OUT 459 FT, 459 FT, 10.00 HRS, 110 RPM, CONDITION 8/8/-/-,
 SERIAL #RT, PP 1500 PSI, PMP #1: SIZE 6.00 X 8.00 X 102 SPM,
 COMMENTS LOST 3 CONES
 BIT #000002, 12.250 IN, F2
 DEVIATION: DEPTH 220 FT, INCL 0.50 DEG, DIR NOOE
 DEPTH 344 FT, INCL 0.75 DEG, DIR NOOE
 TIME: DRL 10.00, TRIP 0.25, SURVEY 0.50, SERVICE RIG 0.25, REAMING 1.50,
 RIG UP 9.00, OTHER: 2.50 HRS
 COSTS: DAILY WELL \$4100, CUM WELL \$4100
 CASING: SURFACE, SET 508 FT, 11/12/85
 REMARKS: SPUD 1730 HR 11/09/85; LOST 3 CONES AT BOT OF HOLE
 MUD ADDITIVES: TYPE-VISCOUSIFIERS, 3000.00 GEL LB,
 TYPE-VISCOUSIFIERS, 200.00 LIME LB,
 CHRON TIME DISTRIBUTION (HRS):
 6.00 - 000035, RD MIRU
 1.00 - 000035, RU
 3.00 - 000037, WC CAT
 3.00 - 000035, FIN RU
 0.50 - 000035, DRL RXM HOLE
 0.50 - 000002, DRL 12-1/4 HOLE
 0.25 - 000006, SURVEY
 3.25 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 1.75 - 000002, DRL
 0.25 - 000006, SURVEY
 2.00 - 000002, DRL
 0.25 - 000004, TRIP
 1.00 - 000024, REAM 270 FT
 RIG CONTRACT DATA: CONTRACTOR BA CODE 586386, FOUR-CORNERS, RIG #0004, ROTARY

ATTACHMENT #1

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/37 *** PAGE 3

DETAIL: BOTTOM 482.0 FT, 9.625 IN, WT 36.00 #/FT,
 GRADE J55, CONNECTION 8 RD STEC, NC OF JTS. 11
 TOP 482.0 FT, BOTTOM 507.0 FT, 9.625 IN, WT 36.00 #/FT,
 GRADE J55, CONNECTION 8 RD STEC, NC OF JTS. 1
 TOP 507.0 FT, BOTTOM 508.0 FT, 9.625 IN, WT 36.00 #/FT,
 GRADE J55, CONNECTION 8 RD STEC, NC OF JTS. 1

TOOLS: TYPE-GUIDE SHOE, TOP 508.9 FT, BOTTOM 503.0 FT,
 NO. OF TOOLS 1, NAME-GUIDE SHOE
 TYPE-OTHER, TOP 481.6 FT, BOTTOM 508.9 FT,
 NO. OF TOOLS 1, NAME-SPRT JT X INSR TOP COLLR

PRIMARY CEMENTING REPORT: STAGE 1, BATCH 1,
 PORTLAND, VOL 300 SX,
 SLURRY DENSITY 15.6 PPG,
 HOLE FLUID DENSITY 8.4 PPG,
 AVG. DISPLACEMENT PRES 250 PSI,
 AVG. DISPLACEMENT RATE 3.0 BPM,
 PRE-FLUSH WATER, 30 BBLs, DENSITY 8.4 PPG,
 DISPLACEMENT FLUID-WATER, DENSITY 8.4 PPG,
 VCL CIRC. CUT 20 BBLs,
 RETURN FLOW 100.0%

ADDITIVES:
 TYPE-ACCELERATOR, 2% CALCIUM CHLORIDE 560.00 LB

*** 11/20/35 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.T. 1.0000

OPERATIONS: TD 512 FT, WOC, FM SN X SH, 53

MUD: DEPTH 459 FT, NATIVE MUD, 9.5 PPG, VISC. 38, PH 8.5, CL 350, CA 260,
 PF 0.3, MF 0.9

BIT AND HYDRAULICS: BIT #00002, 12.250 IN, J22, JETS 11/11/11/-,
 DEPTH CUT 514 FT, 55 FT, 1.00 HRS, 102 RPM, CONDITION 2/2/1/-,

SERIAL NRERUN, PP 1800 PSI, 296 GPM, PMP #1: SIZE 6.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 498 FT, INCL 1.00 DEG, DIR NOOE

TIME: DRL 2.00, TRIP 3.00, CSS & CMT 3.25, WOC 7.00, CIRC 0.50,

SERVICE RIG 0.25, REAMING 3.00, OTHER: 5.00 HRS

COSTS: DAILY WELL \$9560, CUM WELL \$13660

REMARKS: TI X BIT #2; BIT TORQED UP; TO: NO MAGNET X JUNK SUB; MADE
 3 MAGNET RUNS; REC 3 PIECES OF CONES; LAST MAGNET RUN CLEAN PU
 12-1/4 INCH BIT DRL LAST 55 FT SURF HOLE; NO TORQ; PLUG DN
 11:00 PM

MUD ADDITIVES: TYPE-VISCOSIFIERS, 5800.00 AQUA GEL,
 TYPE-FLUCCULANTS, 150.00 LIME,
 TYPE-ALKALINITY, PH CONTROL, 100.00 SCDA ASH,
 TYPE-MATERIAL-FGR-LOST-CIRCULATION, 200.00 CEDAR FIBER,

CHRON TIME DISTRIBUTION (-RS):

2.00 - 000024, REAM
 0.25 - 000021, SERVICE RIG
 1.00 - 000024, REAM TO BTM

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/97 *** PAGE

4

1.00 - 000020, CIRC X COND MUD
 0.50 - 000032, LDDP
 1.00 - 000037, WC MAGNET
 0.50 - 000004, TI
 0.50 - 000004, TC X MAGNET
 0.25 - 000004, TI X MAGNET
 0.25 - 000004, TD REC CONES
 0.25 - 000004, TI X MAGNET
 0.25 - 000004, TC NC REC
 2.00 - 000002, DRL
 0.50 - 000020, CIRC
 0.25 - 000004, TC X BIT
 1.00 - 000012, RUN CSG
 2.25 - 000011, CMT X WOODCO
 7.00 - 000013, WC CMT

*** 11/21/95 ***

JICARILLA TRIBAL 519 NG. 1, WILDEAT, FOUR CORNERS 4, AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TO 1514 FT, DRL, FM SXC, 1002
 MUD: DEPTH 784 FT, LSND POLYMER, 9.7 PPG, VISC. 41, FL 7.2, PH 10.0, PV 10,
 YP 12, GELS 7/16, SCLIDS 2.7%, CL 450, PF 0.7, MF 1.4
 BIT AND HYDRAULICS: BIT #00003, 8.750 IN, HP11, JETS 11/11/-/-, 1000 FT,
 15.00 HRS, WOB 27, 80 RPM, SERIAL #0000003899, PP 2000 PSI, 296 GPM,
 PMP #1: SIZE 6.00 X 8.00 X 102 SPM
 DEVIATION: DEPTH 726 FT, INCL 2.00 DEG, DIR NOOE
 DEPTH 1181 FT, INCL 2.50 DEG, DIR NOOE
 DEPTH 1337 FT, INCL 2.00 DEG, DIR NOOE
 TIME: DRL 15.50, TRIP 1.00, SURVEY 1.00, SERVICE RIG 0.50, OTHER: 6.00 HRS
 COSTS: DAILY WELL \$15946, CUM WELL \$29606
 MUD ADDITIVES: TYPE-VISCOUSIFIERS, 5000.00 GEL,
 TYPE-MATERIAL FOR LOST CIRCULATION, 50.00 HULLS,
 TYPE-FLOCCULANTS, 200.00 SODA ASH,
 TYPE-OTHER, 7.00 LOSOL QT,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 700.00 STARCH,
 TYPE-OTHER, 200.00 ALDACE.

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000013, WOC
 0.25 - 000021, RIG SERVICE
 4.00 - 000013, WOC
 3.75 - 000002, DRL
 1.00 - 000004, TRIP
 1.75 - 000002, DRL
 0.25 - 000006, SURVEY
 2.50 - 000002, DRL
 0.50 - 000006, SURVEY
 1.00 - 000002, DRL
 0.25 - 000021, RIG SERVICE

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

5

0.00 - 000002, DRL
0.25 - 000003, SURVEY
0.50 - 000002, DRL

DATE 11/22/85 ***

JICAPILLA TRIJAL 519 NG-1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-0, API 300292333100, AUTH TO 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TO 2590 FT, DRL, FM 3N X SH, 1076
MUD: DEPTH 1595 FT, LSND POLYMER, 8.8 PPG, VISC. 43, FL 10.6, PH 7.2, PV 13,

YP 10, GELS 7/19, SOLIDS 3.7%, CL 420, CA 140, MF 0.6

BIT AND HYDRAULICS: BIT #000003, 8.750 IN, HP11S, JETS 11/11/-/-,

DEPTH CUT 1675 FT, 1162 FT, 19.25 HRS, WOB 30, 80 RPM, CONDITION 6/3/1/-,

SERIAL #0000003899, PP 2000 PSI, PMP #1: SIZE 6.00 X 8.00 X 102 SPM,

COMMENTS 2966 PM FLW RATE

BIT #000004, 8.750 IN, HP51S, JETS 11/12/-/-, 904 FT, 15.75 HRS, WOB 40,

75 RPM, SERIAL #0000013986, PP 1800 PSI,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM, COMMENTS 2966 PM FLW RATE

DEVIATION: DEPTH 1548 FT, INCL 1.75 DEG, DIR NOOE

DEPTH 1931 FT, INCL 1.25 DEG, DIR NOOE

DEPTH 2178 FT, INCL 0.75 DEG, DIR NOOE

TIME: DRL 20.00, TRIP 2.00, SURVEY 1.00, SERVICE RIG 0.75, CTER: 0.25 HRS

COSTS: DAILY WELL \$7529, CUM WELL \$37135

MUD ADDITIVES: TYPE-VISCOFIFIERS, 5300.00 GEL LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 400.00 STARCH LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 20.00 B-466 GAL,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EASY MUD GAL,

TYPE-MATERIAL FOR LOST CIRCULATION, 100.00 COTTON HULLS LB,

TYPE-OTHER, 5.00 LGSOL QT,

TYPE-ALKALINITY, PH CONTROL, 200.00 SCDA ASH LB,

TYPE-BICCIDES, 50.00 ALDACIDE LB,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
0.25 - 000021, RIG SERVICE
2.25 - 000002, DRL
0.25 - 000006, SURVEY
2.00 - 000004, TRIP CUT
0.25 - 000007, WASH 48 FT TO BTM
0.50 - 000007, DRL
0.25 - 000021, RIG SERVICE
2.00 - 000002, DRL
0.25 - 000006, SURVEY
3.25 - 000002, DRL
0.50 - 000006, SURVEY
1.75 - 000002, DRL
0.25 - 000021, RIG SERVICE
5.75 - 000002, DRL

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/97 *** PAGE

6

*** 11/23/95 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 3440 FT, DRL, 350

MUD: DEPTH 2730 FT, LSND POLYMER, 8.7 PPG, VISC. 50, FL 10.0, PH 8.0, PV 8,

YP 7, GELS 4/11, SOLIDS 3.4%, CL 450, CA 160, PF 0.4, MF 0.8

BIT AND HYDRAULICS: BIT #00004, 8.750 IN, HPS15, JETS 11/12/-/-, 1764 FT,

38.00 HRS, WOB 40, 75 RPM, SERIAL #0000013986, PP 1800 PSI, 7 GPM,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 2685 FT, INCL 0.50 DEG, DIR NOOE

DEPTH 3176 FT, INCL 0.25 DEG, DIR NOOE

TIME: DRL 22.25, SURVEY 1.00, SERVICE RIG 0.75

COSTS: DAILY WELL \$19144, CUM WELL \$47279

MUD ADDITIVES: TYPE-VISCOSSIFIERS, 3400.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 450.00 STARCH LB,
 TYPE-INHIBITORS FOR CORROSION, 10.00 777 GAL,
 TYPE-CALCIUM TREATMENT, 1.00 EZ MUD GAL,
 TYPE-BIOCIDES, 50.00 ABLACADE LB,
 TYPE-OTHER, 5.00 LOSOL QT,
 TYPE-ALKALINITY, PH CONTROL, 200.00 SODA ASH,
 TYPE-INHIBITORS FOR CORROSION, 4.00 B466 GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 1.00 - 000032, DRL
 0.50 - 000036, SURVEY
 6.25 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 5.00 - 000002, DRL
 0.30 - 000036, SURVEY
 2.25 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 5.75 - 000032, DRL

*** 11/24/95 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 3661 FT, DRL, 221

MUD: DEPTH 3561 FT, LSND POLYMER, 8.7 PPG, VISC. 52, FL 7.6, PH 8.5, PV 17,

YP 17, GELS 8/19, SOLIDS 3.4%, CL 360, CA 60, MBT 13.0, PF 0.1, MF 0.2

BIT AND HYDRAULICS: BIT #00004, 8.750 IN, HPS15, JETS 11/12/-/-,

DEPTH OUT 3561 FT, 1805 FT, 42.50 HRS, WOB 40, 75 RPM, CONDITION -/2/1/-,

SERIAL #0000013986, PP 1800 PSI, 295 GPM,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM

BIT #00005, 8.750 IN, SVC, JETS 12/12/12/-, DEPTH OUT 3650 FT, 89 FT,

ATTACHMENT #1

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/87 *** PAGE 7

7.25 HRS, WOB 20, 75 RPM, SERIAL #13024A, PP 1200 PSI, 3 GPM,
 PMP #1: SIZE 5.00 X 8.00 X 102 SPM
 BIT #00005, 8.750 IN, 283T, JETS 12/12/-/-, 11 FT, 0.25 HRS, WOB 22,
 80 RPM, SERIAL #10-T13B, PP 1200 PSI, 3 GPM,
 PMP #1: SIZE 5.00 X 8.00 X 102 SPM
 DEVIATION: DEPTH 3549 FT, INCL 0.75 DEG, DIR NOGE
 TIME: DRL 11.75, TRIP 7.50, SURVEY 0.25, CIRC 0.75, SERVICE RIG 0.25,
 REAMING 0.75, OTHER: 2.75 HRS
 COSTS: DAILY WELL \$7000, CUM WELL \$54367
 BOTTOM HOLE ASSEMBLY: DEPTH IN 3650 FT,
 DP OR TBG: CD 4.500

BHA DETAIL: OTHER, 1.000 FT, CD 8.750 IN, MANUFACTURER STRATBIT-PC283T
 OTHER, 10.340 FT, MANUFACTURER SHOCK SUB
 OTHER, 619.000 FT, CD 6.313 IN, ID 2.250 IN, MANUFACTURER 20 DCS
 OTHER, 121.000 FT, CD 4.500 IN, ID 2.875 IN,
 MANUFACTURER WEIGHT PIPE
 OTHER, CD 4.500 IN, ID 3.250 IN, MANUFACTURER DP

MUD ADDITIVES: TYPE-VISCOUSIFIERS, AQUA GEL 107004
 TYPE-INHIBITORS FOR CORROSION, 10.00 415 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), 1500.00 STARCH LB,
 TYPE-BIOCIDES, 10.00 B-466 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), 10.00 EZ MUD GAL,
 TYPE-ALKALINITY, PH CONTROL, 100.00 CAUSTIC SODA LB,
 TYPE-VISCOUSIFIERS, 16.00 LB SOL QT,
 TYPE-MATERIAL FOR LOST CIRCULATION, 150.00 C/F,
 TYPE-ALKALINITY, PH CONTROL, 500.00 SODA ASH LB,
 TYPE-MATERIAL FOR WEIGHTING, 1100.00 BARGID LB,
 TYPE-OTHER, 50.00 ALUMIN STARITE,
 TYPE-INHIBITORS FOR CORROSION, 10.00 777 GAL,

CHRON TIME DISTRIBUTION (HRS):
 2.00 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 2.50 - 000002, DRL
 0.50 - 000015, CIRC SAMP
 0.25 - 000006, SURVEY
 4.25 - 000004, TRIP
 0.75 - 000024, REAM 72 FT TO BTM
 0.25 - CIRC
 7.25 - 000002, DRL
 1.25 - 000002, TRY TO DRL
 3.25 - 000004, TC
 1.25 - 000037, WASH TO BTM 45 FT
 0.25 - 000022, DRL

*** 11/25/85 ***

JICARILLA TRIBAL 519 NG-1, WILDEAT, FOUR CORNERS 4, AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TO 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TO 4503 FT, DRL, 902

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/37 *** PAGE

8

MUD: DEPTH 4493 FT, LSND POLYMER, 8.8 PPG, VISC. 55, FL 7.2, PH 9.3, PV 20,
 YP 12, GELS 10/25, SOLIDS 3.7%, CL 400, CA 50, MST 13.0, PF 3.3, MF 0.7
 BIT AND HYDRAULICS: BIT #00006, 8.750 IN, 283T, JETS 12/12/12/-, 913 FT,
 22.75 HRS, WOB 22, 75 RPM, SERIAL #101413B, PP 1200 PSI,

PMP #1: SIZE 5.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 3806 FT, INCL 0.75 DEG, DIR NOOE

DEPTH 4336 FT, INCL 1.00 DEG, DIR NOOE

TIME: DRL 22.25, SURVEY 1.00, SERVICE RIG 0.75

COSTS: DAILY WELL \$5839, CUM WELL \$60206

MUD ADDITIVES: TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 3800.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 310.00 STARCH LB,
 TYPE-THINNERS, DISPERSANTS, 7.00 777 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 3.00 LOSOL QT,
 TYPE-ALKALINITY, PH CONTROL, 100.00 SCDA ASH LB,
 TYPE-ALKALINITY, PH CONTROL, 50.00 CAUSTIC LB,
 TYPE-BIOCIDES, 10.00 8446 GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 1.25 - 000002, DRL
 0.50 - 000006, SURVEY
 6.00 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 7.25 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 0.75 - 000002, DRL
 0.50 - 000006, SURVEY
 1.50 - 000002, DRL

*** 11/26/35 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMCCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMCCO W.I. 1.0000

OPERATIONS: TD 5435 FT, DRL, 872

MUD: DEPTH 5356 FT, LSND POLYMER, 8.7 PPG, VISC. 64, FL 8.8, PH 7.0, PV 25,

YP 12, SOLIDS 3.1%, CL 400, CA 160, MST 13.5, PF 0.7, LCM CONC 6 LB/BBL

BIT AND HYDRAULICS: BIT #00006, 8.750 IN, 283T, JETS 12/12/12/-, 1785 FT,

45.00 HRS, WOB 22, 75 RPM, SERIAL #101413B, PP 1200 PSI, 7 GPM,

PMP #1: SIZE 5.00 X 8.00 X 120 SPM

DEVIATION: DEPTH 4867 FT, INCL 1.50 DEG, DIR NOOE

DEPTH 5115 FT, INCL 1.75 DEG, DIR NOOE

TIME: DRL 22.25, SURVEY 1.00, SERVICE RIG 0.75

COSTS: DAILY WELL \$9591, CUM WELL \$69797

REMARKS: 5250 FT: WELL DPANK 75 B2L MUD

MUD ADDITIVES: TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 6800.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 800.00 STARCH LB,
 TYPE-INHIBITORS FOR CORROSION, 5.00 777 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 9.00 LOSOL QT,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EZ-MUD GAL,

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

9

TYPE-ALKALINITY, PH CONTROL, 200.00 SODA ASH LB,
 TYPE-MATERIAL FOR LOST CIRCULATION, 5500.00 MULTISEAL LB,
 TYPE-ALKALINITY, PH CONTROL, 50.00 CAUSTIC LB,
 TYPE-MATERIAL FOR LOST CIRCULATION, 1240.00 CEDAR FIBER LB,
 TYPE-OTHER, 10.00 B446 GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 0.25 - 000002, DRL
 0.50 - 000005, SURVEY
 1.75 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 3.25 - 000002, DRL
 0.50 - 000005, SURVEY
 2.00 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 5.75 - 000002, DRL

*** 11/27/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAG 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 5766 FT, DRL, 331

MUD: DEPTH 5729 FT, LSND POLYMER, 8.8 PPG, VISC. 54, FL 7.2, PH 7.6, PV 19,

YP 15, GELS 6/8, SELIDS 3.7%, CL 300, CA 100, MBT 13.0, MF 1.2

BIT AND HYDRAULICS: BIT #00006, 8.750 IN, 2B3T, JETS 12/12/12/-,

DEPTH OUT 5498 FT, 1848 FT, 48.00 HRS, WOB 22, 75 RPM, SERIAL #104TBD,

PP 1200 PSI, 7 GPM, PMP #1: SIZE 6.00 X 8.00 X 102 SPM

BIT #00007, 8.750 IN, FPS2, JETS 12/12/-/-, 268 FT, 13.00 HRS, WOB 42,

75 RPM, SERIAL #043010, PP 1800 PSI, 7 GPM,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 5458 FT, INCL 1.25 DEG, DIR N00E

TIME: DRL 16.00, TRIP 5.25, SURVEY 0.25, CIRC 0.75, SERVICE RIG 0.25,

CUT DRL LINE 0.75, OTHER: 0.75 HRS

COSTS: DAILY WELL \$7431, CUM WELL \$77223

MUD ADDITIVES: TYPE-VISCOIFIERS, 3500.00 GEL LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EZ MUD GAL,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 1450.00 STARCH LB,

TYPE-MATERIAL FOR LOST CIRCULATION, 120.00 CEDAR FIBER LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 2.00 LJSOL QT,

TYPE-MATERIAL FOR LOST CIRCULATION, 150.00 COTTON HULLS#,

TYPE-ALKALINITY, PH CONTROL, 600.00 SODA ASH LB,

TYPE-DEFOAMERS, 50.00 ALUM STARATE LB,

TYPE-BIOCIDES, 5.00 B466 GAL,

TYPE-OTHER, 25.00 CRISTO LB,

TYPE-ALKALINITY, PH CONTROL, 100.00 CAUSTIC LB,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 1.00 - 000002, DRL

ATTACHMENT #1

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/97 *** PAGE 10

0.75 - 000019, CIRC FOR SAMP
 0.25 - 000003, SURVEY
 0.30 - 000004, PULL CUT HOLE
 0.25 - 000022, CUT DRL LINE
 0.25 - 000004, TI
 0.75 - 000024, WASH 52 FT TO 2TM
 7.15 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 5.75 - 000002, DRL

*** 11/28/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

 FLAG 846167-01-3, API 390392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000

OPERATIONS: TD 6146 FT, DRL, FM PT LOCKOUT, 380
 MUD: DEPTH 6111 FT, LSND POLYMER, 8.9 PPG, VISC. 55, FL 6.4, PH 9.5, PV 16,
 YP 15, GELS 3/24, SOLIDS 4.1%, CL 400, CA 100, MBT 13.0, FILTER CAKE 2,
 PF 8.3, MF 2.4

BIT AND HYDRAULICS: BIT #00007, 8.750 IN, FP52, JETS 12/12/-/-, 148 FT,
 35.75 HRS, WOB 40, 75 RPM, SERIAL #U43010, PP 1800 PSI, 7 GPM,
 PMP #1: SIZE 6.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 3960 FT, INCL 0.50 DEG, DIR NOOE
 TIME: DRL 22.75, SURVEY 0.50, SERVICE RIG 0.75

COSTS: DAILY WELL \$16448, CUM WELL \$93676

MUD ADDITIVES: TYPE-VISCOFIFIERS, 5600.00 GEL LB,
 TYPE-INHIBITORS FOR CORROSION, 7.00 415 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRGL), 10.00
 EASY MUD GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRGL), 1450.00 STARCH LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRGL), 12.00 LOSOL QT,
 TYPE-ALKALINITY, PH CONTROL, 5000.00 SODA ASH LB,
 TYPE-OTHER, 15.00 777 GAL,
 TYPE-BIGGIDES, 25.00 8466 GAL,
 TYPE-ALKALINITY, PH CONTROL, 350.00 CAUSTIC LB,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 7.75 - 000002, DRL
 0.25 - 000021, SERVICE RIG
 4.00 - 000002, DRL
 0.50 - 000006, SURVEY
 3.25 - 000002, DRL
 0.50 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 5.25 - 000002, DRL

*** 11/29/85 ***

ATTACHMENT #1

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/87 *** PAGE 11

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CGST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 5432 FT, PSTD 6146, TRIP, FM SN X MANCOR SH, 295
MUD: DEPTH 5432 FT, LSND POLYMER, 8.8 PPG, VISC. 53, FL 7.4, PH 9.5, PV 19,
YP 13, GELS 3/23, SOLIDS 3.82, CL 400, CA 30, MBT 13.0, FILTER CAKE 2,
PH 9.5, MF 1.9BIT AND HYDRAULICS: BIT #00007, 8.750 IN, FP52, JETS 12/12/-/-,
DEPTH CUT 5432 FT, 934 FT, 14.90 HRS, WOB 40, 70 RPM, SERIAL #U43010,
PP 1300 PSI, 7 GPM, PMP #1: SIZE 6.00 X 6.00 X 102 SPM

BIT #00008, 8.750 IN, SBC, JETS 12/12/12/-, SERIAL #12828A

DEVIATION: DEPTH 5418 FT, INCL 1.50 DEG, DIR NOOE

TIME: DRL 20.25, TRIP 1.50, SURVEY 0.50, CIRC 1.00, SERVICE RIG 0.75

COSTS: DAILY WELL \$7220, CUM WELL \$100895

MUD ADDITIVES: TYPE-VISCOIFIERS, 5400.00 GEL LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 300.00 STARCH LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 6.00 LOSOL QT,

TYPE-ALKALINITY, PH CONTROL, 300.00 SODA ASH LB,

TYPE-BIGGIDES, 120.00 B466 GAL,

TYPE-THINNERS, DISPERSANTS, 350.00 ALDACIDE LB,

TYPE-MATERIAL FOR LOST CIRCULATION, 200.00 MULTISEAL,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EASY MUD GAL,

TYPE-INHIBITORS FOR CORROSION, 10.00 415 GAL,

TYPE-MATERIAL FOR LOST CIRCULATION, 200.00 CEDER FIBER LB,

TYPE-MATERIAL FOR LOST CIRCULATION, 100.00 COTTON HULLS LB,

TYPE-OTHER, 15.00 777 GAL,

TYPE-MATERIAL FOR WEIGHTING, 2000.00 BAREID,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL

0.25 - 000021, SERVICE RIG

7.75 - 000032, DRL

0.25 - 000021, SERVICE RIG

7.75 - 000002, DRL

0.25 - 000021, SERVICE RIG

2.75 - 000032, DRL

1.00 - 000019, CIRC SAMPLES

0.50 - 000006, DROP SURVEY

1.50 - 000004, TRIP

*** 11/30/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CGST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 7190 FT, DRL, FM GLLP, 758

MUD: DEPTH 7132 FT, LSND POLYMER, 3.8 PPG, VISC. 57, FL 7.0, PH 9.5, PV 27,
YP 23, GELS 15/37, SOLIDS 3.5%, CL 300, CA 30, MBT 15.0, PF 7.2, MF 2.4
BIT AND HYDRAULICS: BIT #00008, 8.750 IN, SBC, JETS 12/12/12/-, 758 FT,
10.50 HRS, WOB 22, 75 RPM, SERIAL #12828A, PP 1200 PSI, 7 GPM,

ATTACHMENT #1

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/87 *** PAGE 12

PMP #1: SIZE 6.00 X 8.00 X 102 SPM
 DEVIATION: DEPTH 6670 FT, INCL 0.75 DEG, DIR NOOE
 DEPTH 6823 FT, INCL 0.25 DEG, DIR NOOE
 TIME: DRL 18.50, TRIP 3.50, SURVEY 1.00, SERVICE RIG 0.50, OTHER: 0.50 HRS
 COSTS: DAILY WELL \$9912, CUM WELL \$110808
 MUD ADDITIVES: TYPE-VISCOSSIFIERS, 4100.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 300.00 STARCH LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 6.00 LOSOL QT,
 TYPE-ALKALINITY, PH CONTROL, 400.00 SODA ASH LB,
 TYPE-ALKALINITY, PH CONTROL, 200.00 CAUSTIC LB,
 TYPE-THINNERS, DISPERSANTS, 200.00 ALDACIDE LB,
 TYPE-OTHER, 25.00 ALUM SFEK LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EASY MUD GAL,
 TYPE-INHIBITORS FOR CORROSION, 12.00 415 GAL,
 TYPE-INHIBITORS FOR CORROSION, 18.00 777 GAL,

CHRON TIME DISTRIBUTION (HRS):
 2.00 - 000004, TRIP
 1.50 - 000004, TRIP
 0.50 - 000037, WASH 54 FT TO BTM
 5.50 - 000002, DRL
 0.50 - 000006, SURVEY
 0.25 - 000021, RIG SERVICE
 5.00 - 000002, DRL
 0.50 - 000005, SURVEY
 2.25 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 5.75 - 000002, DRL

*** 12/01/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8579, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 7940 FT, DRL, FM GLLP, 750
 MUD: DEPTH 7362 FT, LSND POLYMER, 9.2 PPG, VISC. 58, FL 7.2, PH 9.5, PV 26,
 YP 20, GELS 8/24, SOLIDS 6.5%, CL 400, CA 90, MBT 16.0, PF 1.5, MF 1.0,
 LCM CONC 4 LB/88L
 BIT AND HYDRAULICS: BIT #000008, 8.750 IN, SBC, JETS 12/12/12/, 1598 FT,
 40.50 HRS, WOB 180, 75 RPM, SERIAL #12828A, PP 1200 PSI, 7 GPM,
 PMP #1: SIZE 6.00 X 8.00 X 102 SPM
 DEVIATION: DEPTH 7321 FT, INCL 2.25 DEG, DIR NOOE
 DEPTH 7448 FT, INCL 2.25 DEG, DIR NOOE
 DEPTH 7544 FT, INCL 2.00 DEG, DIR NOOE
 TIME: DRL 21.75, SURVEY 1.50, SERVICE RIG 0.75
 COSTS: DAILY WELL \$12150, CUM WELL \$122958
 REMARKS: 1100 HR 1600 UNITS GAS; SURVEY 7644 2900 UNITS CONN GAS
 MUD ADDITIVES: TYPE-VISCOSSIFIERS, 4000.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 200.00 STARCH LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 6.00 LOSOL QT,
 TYPE-ALKALINITY, PH CONTROL, 300.00 SODA ASH LB,

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

12

TYPE-INHIBITORS FOR CORROSION, 100.00 DESCO LB,
 TYPE-SIDECIDES, 300.00 BICARB LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRCL), 5.00 EASY MUD GAL,
 TYPE-ALKALINITY, PH CONTRCL, 150.00 CAUSTIC LB,
 TYPE-INHIBITORS FOR CORROSION, 9.00 35 GAL,
 TYPE-INHIBITORS FOR CORROSION, 20.00 777 GAL,
 TYPE-OTHER, 8.00 415 GAL,
 TYPE-MATERIAL FOR LOST CIRCULATION, 1200.00 CEDER FIBER,
 TYPE-MATERIAL FOR LOST CIRCULATION, 8950.00 MULTISEAL,
 TYPE-OTHER, 120.00 ALUM STERATE LB,

CHRON TIME DISTRIBUTION (HRS):

0.50 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 1.50 - 000002, DRL
 0.50 - 000006, SURVEY
 4.25 - 000002, DRL
 0.50 - 000006, SURVEY
 1.00 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 4.50 - 000002, DRL
 0.50 - 000006, SURVEY
 2.75 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 5.75 - 000002, DRL

*** 12/02/85 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH ID 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8333 FT, TRIP, FM GREENHORH, 393
 MUD: DEPTH 8333 FT, LSND POLYMER, 8.9 PPG, VISC. 57, FL 8.0, PH 8.9, PV 14,
 YP 11, GELS 5/27, SOLIDS 4.9%, CL 400, CA 100, MBT 15.0, PF 0.3, MF 1.3
 BIT AND HYDRAULICS: BIT #000008, 8.750 IN, STRATA, JETS 12/12/12/-,
 DEPTH OUT 8333 FT, 1905 FT, 54.75 HRS, WOB 20, 75 RPM, SERIAL #12828A,
 PP 1300 PSI, 7 GPM, PMP #1: SIZE 6.00 X 8.00 X 102 SPM
 BIT #000009, 8.750 IN, HP53, JETS 13/13/-/-, SERIAL #0000071393
 DEVIATION: DEPTH 7947 FT, INCL 0.75 DEG, DIR NOOE
 DEPTH 8293 FT, INCL 1.25 DEG, DIR NOOE
 TIME: DRL 14.25, TRIP 7.00, SURVEY 1.00, CIRC 1.50, SERVICE RIG 0.25
 COSTS: DAILY WELL \$6572, CUM WELL \$129530
 MUD ADDITIVES: TYPE-VISCOIFIERS, 5000.00 GEL LB,
 TYPE-INHIBITORS FOR CORROSION, 7.00 415 GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRCL), 250.00 STARCH LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRCL), 5.00 EASY MUD GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRCL), 6.00 LOSOL QT,
 TYPE-MATERIAL FOR LOST CIRCULATION, 200.00 CEDER FIBER,
 TYPE-ALKALINITY, PH CONTRCL, 300.00 SCDA ASH LB,
 TYPE-MATERIAL FOR LOST CIRCULATION, 520.00 MULTISEAL LB,
 TYPE-ALKALINITY, PH CONTRCL, 150.00 CAUSTIC LB,

ATTACHMENT #1

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

14

TYPE-BIOCIDES, 350.00 ALDISIDE LB,
 TYPE-INHIBITORS FOR CORROSION, 25.00 777 GAL,
 TYPE-INHIBITORS FOR CORROSION, 8.00 H35 GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
 0.75 - 000006, SURVEY
 7.75 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 4.50 - 000002, DRL
 1.50 - 000019, CIRC
 0.50 - 000006, SURVEY
 7.00 - 000004, TRIP

*** 12/03/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, FOUR CORNERS 4, AMOCC PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 9520, AUTH COST \$1323000,
 AMOCC W-I-1-0000

OPERATIONS: TO 8399 FT, REAM TO BTM, 66

MUD: DEPTH 8399 FT, LSND POLYMER, 8.7 PPG, VISC. 80, FL 7.8, PH 9.5, PV 27,
 YF 25, GELS 12/33, SOLIDS 3.1%, CL 400, CA 150, MFT 16.0, FILTER CAKE 2,
 PF 0.7, HF 2.4

BIT AND HYDRAULICS: BIT #00009, 8.75 IN, HP53, JETS 13/13/13/-,
 DEPTH OUT 8399 FT, 66 FT, 8.25 HRS, WOB 40, 60 RPM, CCNDITION 8/8/-/-,
 SERIAL #0000071393, PP 1700 PSI, 7 GPM,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM

BIT #00010, 8.750 IN, F4, JETS 13/13/8 /- , SERIAL #EX8593, PP 1700 PSI,
 7 GPM, PMP #1: SIZE 6.00 X 8.00 X 102 SPM

TIME: DRL 9.25, TRIP 10.25, SERVICE RIG 0.25, CUT DRL LINE 1.25, REAMING 2.00,
 OTHER: 1.00 HRS

COSTS: DAILY WELL \$11442, CUM WELL \$140972

REMARKS: -/-/4300 BG/CG/TG: WORE BIT #9 CUT IN 66 FT

MUD ADDITIVES: TYPE-VISCOUSIFIERS, 3000.00 GEL LB,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EZE MUD GAL,
 TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRCL), 900.00 STARCH LB,
 TYPE-VISCOUSIFIERS, 4.00 LOSOL QT,
 TYPE-CALCIUM TREATMENT, 150.00 ALDACIDE LB,
 TYPE-INHIBITORS FOR CORROSION, 16.00 777 GAL,
 TYPE-ALKALINITY, PH CONTROL, 50.00 CAUSTIC LB,
 TYPE-FOAMING AGENTS, 10.00 J5 GAL,
 TYPE-ALKALINITY, PH CONTROL, 100.00 SODA ASH LB,
 TYPE-INHIBITORS FOR CORROSION, 6.00 415 GAL,
 TYPE-MATERIAL FOR WEIGHTING, 3900.00 BARCID LB,

CHRON TIME DISTRIBUTION (HRS):

1.50 - 000004, TRIP
 1.00 - 000037, WASH 63 FT TO BTM
 2.75 - 000002, DRL
 0.25 - 000021, RIG SERVICE
 4.50 - 000002, DRL
 2.00 - 000002, DRL

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

15

0.30 - 000004, TRIP
 1.00 - 000021, CUT DRL LINE
 1.00 - 000004, TRIP
 4.00 - 000004, TRIP
 2.00 - 000024, REAM 40 FT TO BTM

*** 12/04/85 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMCCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH ID 8520, AUTH COST \$1323000,

AMCCO W.I. 1.0000

OPERATIONS: TD 8517 FT, DRL, FM DKGT, 118

MUD: DEPTH 8509 FT, LSND POLYMER, 9.1 PPG, VISC. 50, FL 6.6, PH 9.3, PV 22,

YP 19, GELS 9/27, SOLIDS 6.0%, CL 400, CA 80, MBT 15.0, FILTER CAKE 2,

PF 0.4, HF 0.2

BIT AND HYDRAULICS: BIT #00010, 9.750 IN, F4, JETS 13/13/-/-, 118 FT,

21.25 HRS, WOB 40, 60 RPM, SERIAL #EX6593, PP 1500 PSI, 7 GPM,

PMP #1: SIZE 8.00 X 8.00 X 102 SPM

DEVIATION: DEPTH 8482 FT, INCL 0.50 DEG, DIR NOPE

TIME: DRL 21.25, TRIP 0.75, SERVICE RIG 0.50, REAMING 0.50, OTHER: 1.00 HRS

COSTS: DAILY WELL \$18216, CUM WELL \$159188

MUD ADDITIVES: TYPE-VISCOSSIFIERS, 4400.00 GEL LB,

TYPE-OTHER, 25.00 ALUM ST LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), 350.00 STARCH LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), 5.00 EZ MUD GAL,

TYPE-BIGCIES, 450.00 ALDACIDE LB,

TYPE-VISCOSSIFIERS, 5.00 LOSCL QT,

TYPE-ALKALINITY, PH CONTROL, 200.00 CAUSTIC LB,

TYPE-INHIBITORS FOR CORROSION, 28.00 777 GAL,

TYPE-ALKALINITY, PH CONTROL, 400.00 SCDA ASH LB,

TYPE-INHIBITORS FOR CORROSION, 14.00 H-35 GAL,

TYPE-INHIBITORS FOR CORROSION, 4.00 415 GAL,

TYPE-OTHER, 5.00 DEFOAM GAL,

TYPE-OTHER, 45.00 DIESEL GAL,

CHRON TIME DISTRIBUTION (HRS):

0.30 - REAM TO BTM

1.50 - 000002, DRL

0.30 - 000004, PULL 5 STDS

1.00 - 000031, REPLACE KELLY HOSE

0.25 - 000004, TI 5 STDS

3.75 - 000002, DRL

4.75 - 000002, DRL

0.25 - 000021, RIG SERVICE

3.00 - 000002, DRL

1.50 - 000002, DRL

0.25 - 000021, RIG SERVICE

5.75 - 000002, DRL

*** 12/05/85 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMOCC PRODUCTION,

FLAG 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CGST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TO 8615 FT, DRL, 98

MUD: DEPTH 8619 FT, LSNC POLYMER, 8.9 PPG, VISC. 65, FL 7.0, PH 9.5, PV 23,

YP 21, GELS 12/39, SOLIDS 4.1%, CL 400, EA 120, MBT 15.0, FILTER CAKE 2,

PF 0.0, MF 2.0

BIT AND HYDRAULICS: BIT #00010, 6.750 IN, F4, JETS 13/13/-/-,

DEPTH OUT 8519 FT, 120 FT, 21.75 HRS, WOB 40, 60 RPM, CONDITION 6/2/-/-,

SERIAL #EX0593, PP 1600 PSI, 7 GPM, PMP #1: SIZE 6.00 X 8.00 X 102 SPM

BIT #00011, 8.750 IN, F57, JETS 13/13/-/-, 96 FT, 12.50 HRS, WOB 40,

60 RPM, SERIAL #FC2147, PP 1600 PSI, 7 GPM,

PMP #1: SIZE 6.00 X 8.00 X 102 SPM

TIME: DRL 14.25, TRIP 7.25, SURVEY 0.25, CIRC 1.50, SERVICE RIG 0.25,

OTHER: 0.25 HRS

COSTS: DAILY WELL \$15177, CUM WELL \$174365

BOTTOM HOLE ASSEMBLY: DEPTH IN 3519 FT,

DP GR TBG: GD 4.500

BHA DETAIL: COLLAR, 1.000 FT, OD 8.314 IN, MANUFACTURER BIT SMITH F-S7

COLLAR, 3.000 FT, STEEL, OD 6.000 IN, ID 3.250 IN,

MANUFACTURER JUNK BASKET

SHOCK SUB, 10.340 FT, STEEL, OD 6.000 IN, ID 2.250 IN,

MANUFACTURER SHOCK SUB

OTHER, 3.000 FT, STEEL, OD 6.250 IN, ID 2.250 IN,

MANUFACTURER BIT SUB

COLLAR, 618.200 FT, STEEL, OD 6.313 IN, ID 3.250 IN,

MANUFACTURER 20 DCS

DRILL PIPE & HW, 121.360 FT, STEEL, OD 4.500 IN, ID 2.500 IN,

MANUFACTURER WEIGHT PIPE

OTHER, STEEL, OD 4.500 IN, MANUFACTURER DP

MUD ADDITIVES: TYPE-VISCOUSIFIERS, 3000.00 GEL LB,

TYPE-MATERIAL FOR WEIGHTING, 2000.00 BAR LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), 300.00 STARCH LB,

TYPE-FILTRATE REDUCERS (FLUID LOSS CONTRL), EZ MUD GAL

TYPE-BICCIDES, 450.00 ALDACIDE LB,

TYPE-VISCOUSIFIERS, 3.00 LOSOL QT,

TYPE-ALKALINITY, PH CONTROL, 150.00 CAUSTIC LB,

TYPE-INHIBITORS FOR CORROSION, 20.00 777 GAL,

TYPE-ALKALINITY, PH CONTROL, 300.00 SCDA ASH LB,

TYPE-INHIBITORS FOR CORROSION, 8.00 H-35 GAL,

TYPE-DEFCAMERS, 25.00 ALUM STARATE LB,

TYPE-DEFCAMERS, 10.00 DEFCAMER GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL

1.50 - 000019, CIRC FOR SAMP

0.25 - 000037, SLUG PIPE

0.25 - 000036, SURVEY

6.00 - 000034, TRIP BIT

1.25 - 000004, TI

0.75 - 000002, DRL

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/87 *** PAGE 17

0.25 - 000021, RIG SERVICE
0.75 - 000002, DRL

*** 12/06/85 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMCCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMCCC W.I. 1.0000

OPERATIONS: TD 8700 FT, TRIP, 85

MUD: DEPTH 3700 FT, LSND POLYMER, 8.9 PPG, VISC. 54, FL 6.6, PH 9.5, PV 20,

YP 15, GELS 9/32, SOLIDS 4.6%, CL 400, CA 120, MBT 15.0, PF 0.4, MF 2.3

BIT AND HYDRAULICS: BIT #00011, 8.750 IN, F57, JETS 13/13/-/-,

DEPTH OUT 8700 FT, 181 FT, 28.00 HRS, WCB 40, 60 RPM, SERIAL #FC2147,

PP 1600 PSI, 296 GPM, PMP #1, SIZE 6.00 X 8.00 X 102 SPM

TIME: DRL 15.50, TRIP 4.50, SURVEY 0.25, CIRC 3.50, SERVICE RIG 0.25

COSTS: DAILY WELL \$15735, CUM WELL \$190100

MUD ADDITIVES: TYPE-VISCOUSIFIERS, 8000.00 GEL LB,
TYPE-MATERIAL FOR WEIGHTING, 50.00 COTTON HULL LB,
TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 550.00 STARCH LB,
TYPE-MATERIAL FOR LCST CIRCULATION, 400.00 CEDAR FIBER,
TYPE-FILTRATE REDUCERS (FLUID LOSS CONTROL), 5.00 EZ MUD GAL,
TYPE-BIOCIDES, 250.00 ALDACIDE LB,
TYPE-VISCOUSIFIERS, 14.00 LBSOL QT,
TYPE-DEFCAMERS, 50.00 ALUM STARATE LB,
TYPE-ALKALINITY, PH CONTROL, 250.00 CAUSTIC LB,
TYPE-INHIBITORS FOR CORROSION, 30.00 777 GAL,
TYPE-ALKALINITY, PH CONTROL, 900.00 SODA ASH LB,
TYPE-INHIBITORS FOR CORROSION, 11.00 H-35 GAL,
TYPE-DEFCAMERS, DEFCAMER GAL,
TYPE-THINNERS, DISPERSANTS, 75.00 DESCC LB,
TYPE-OTHER, 5.00 415 GAL,

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000002, DRL
0.25 - 000021, RIG SERVICE
7.75 - 000002, DRL
5.75 - 000002, DRL
1.25 - 000019, CIRC SAMPLE
1.00 - 000004, SHORT TRIP
2.00 - 000019, CIRC
0.25 - 000005, SURVEY
4.75 - 000004, TC FOR LOGS

*** 12/07/85 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, FOUR CORNERS 4, AMCCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMCCC W.I. 1.0000

OPERATIONS: TD 8700 FT, LOG, FM DKOT

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

18

MUD: DEPTH 8700 FT, LONG POLYMER, 8.9 PPG, VISC. 69, FL 6.4, PH 9.5, PV 22,
YP 20, GELS 3/32, SOLIDS 4.24, CL 270, CA 40, MBT 15.0, PF 0.5, MF 2.3,
PM 1.2

TIME: TRIP 6.50, LOGGING 12.50, CIRC 3.00

CCSTS: DAILY WELL \$5760, CUM WELL \$195868

REMARKS: LOGGERS HIT BRIDGE AT 4205 FT; TI; CIRC X COND

MUD ADDITIVES: TYPE-VISCOUSIFIERS, 10.00 EZMUD GAL,
TYPE-RHODIDES, 300.00 ALDIDIDE LB,
TYPE-ALKALINITY, PH CONTROL, 50.00 CAUSTIC LB,
TYPE-THINNERS, DISPERSANTS, 25.00 DESCO LB,

CHRON TIME DISTRIBUTION (HRS):

1.35 - 000004, TO FOR LOG
1.00 - 000017, RU LOGGERS
1.75 - 000017, BRIDGE AT 4205
3.25 - 000004, TI BREAK CIRC 4787
3.00 - 000020, CIRC X COND MUD
4.25 - 000004, TO FOR LOGS
3.75 - 000017, RU LOGGERS
6.00 - 000017, LOG

LOGS: 12/07/85, ACOUSTIC LOG,
TOP DEPTH 508 FT, BTM DEPTH 7830 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, CALIPER LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, NEUTRON POROSITY LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, DENSITY LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, GAMMA RAY LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, DIPMETER,
TOP DEPTH 8300 FT, BTM DEPTH 7830 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, INDUCTION LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER
12/07/85, SPONTANEOUS POTENTIAL LOG,
TOP DEPTH 508 FT, BTM DEPTH 8700 FT, BHT 198 F,
SERVICE COMPANY-SCHLUMBERGER

*** 12/08/85 ***

JICARILLA TRIBAL-519 NG-1, WILDCAT, FOUR CORNERS 4, AMOCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TO 8700 FT, REPAIR RIG

DENVER REGION *** FARMINGTON DISTRICT *** 02/13/37 *** PAGE 19

TIME: TRIP 2.50, RIG REPAIR 5.00, LOGGING 15.75, CUT DRL LINE 3.75
COSTS: DAILY WELL \$5217, CUM WELL \$201085
CHRON TIME DISTRIBUTION (HRS):

2.00	-	000017, LOG
3.00	-	000017, LOG
5.75	-	000017, LOG
0.25	-	000004, TI
3.75	-	000022, CUT DRL LINE
1.00	-	000004, TI
1.00	-	000004, TI
5.00	-	000005, RIG REPAIR

*** 12/09/35 ***

JICARILLA TRIBAL 519 NG. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, TI, FM BKST

MUD: DEPTH 8700 FT, LSND POLYMER, 8.9 PPG, VISC. 80, FL 7.2, PH 9.0, PV 25,
YP 20, GELS 3/30, SOLIDS 4.2%, CL 250, CA 60, MBT 15.0, PF 0.4, MF 2.0,
PM 2.2

TIME: TRIP 8.50, RIG REPAIR 6.00, LOGGING 6.00, COND MUD 3.50

COSTS: DAILY WELL \$12656, CUM WELL \$213741

MUD ADDITIVES: TYPE-OTHER, 150.00 SPA LB,
TYPE-ALKALINITY, PH CONTROL, 50.00 CAUSTIC LB,
TYPE-INHIBITORS FOR CORROSION, 175.00 DRISCOLL LB,

CHRON TIME DISTRIBUTION (HRS):

2.00	-	000005, RIG REPAIR
4.00	-	000005, RIG REPAIR
2.00	-	000004, TI
2.00	-	000020, CIRC MUD
0.50	-	000020, CIRC MUD
4.00	-	000004, TD
2.50	-	000017, RU X LOG
3.00	-	000017, LOG
0.50	-	000017, RD LOGGERS
2.50	-	000004, TI

*** 12/10/35 ***

JICARILLA TRIBAL 519 NG. 1, WILDCAT, FOUR CORNERS 4, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, CIRC BETWEEN STAGES

MUD: DEPTH 8700 FT, LSND POLYMER, 9.0 PPG, VISC. 45, FL 6.6, PH 9.0, PV 19,
YP 9, GELS 2/11, SOLIDS 4.3%, CL 230, CA 60, MBT 13.7, FILTER CAKE 2,
PF 0.4, MF 2.1, PM 1.2

TIME: TRIP 2.50, CSG & CMT 4.50, CMT SQZ 2.00, CIRC 7.00, LD UP & DC 7.00,

OTHER: 1.00 HRS

COSTS: DAILY WELL \$5150, CUM WELL \$218901

CASING: PRODUCTION, SET 8703 FT, 12/10/85

MUD ADDITIVES: TYPE-INHIBITORS FOR CORROSION, 400.00 DRISCO LB,

CHRON TIME DISTRIBUTION (HRS):

2.30 - 000004, TRIP
3.00 - 000019, CIRC X COND MUD
7.00 - 000029, LOOP X DC
1.00 - 000037, CHANGE RAMS
4.50 - 000011, RUN 1-1/2 INCH CSG
2.50 - 000019, CIRC
2.00 - 000011, CMT 1ST STAGE
1.50 - 000019, OPEN DV X CIRC

DETAIL: BOTTOM 37.4 FT, 5.500 IN, WT 17.00 #/FT,
GRADE P110, CONNECTION HYDRIL S EU, NO OF JTS. 1
TOP 37.4 FT, BOTTOM 3779.0 FT, 5.500 IN, WT 17.00 #/FT,
GRADE N80, CONNECTION HYDRIL S EU, NO OF JTS. 88
TOP 3779.0 FT, BOTTOM 8703.1 FT, 5.500 IN, WT 17.00 #/FT,
GRADE P110, CONNECTION HYDRIL S EU, NO OF JTS. 124

TOOLS: TYPE-DV TOOL, TOP 5602.2 FT, BOTTOM 5603.4 FT,
NO. OF TOOLS 1, NAME-DV TOOL
TYPE-FLOAT COLLAR, TOP 8659.9 FT, BOTTOM 8660.9 FT,
NO. OF TOOLS 1, NAME-FLOAT COLLAR
TYPE-FLOAT SHOE, TOP 8701.1 FT, BOTTOM 8703.1 FT,
NO. OF TOOLS 1, NAME-FLOAT GUIDE SHOE

PRIMARY CEMENTING REPORT: STAGE 1, BATCH 1, API CLASS B,
IDEAL, VOL 157 SX,
SLURRY DENSITY 12.0 PPG,
HOLE FLUID DENSITY 9.0 PPG, TYPE-MUD,
AVG. DISPLACEMENT PRES 1000 PSI,
AVG. DISPLACEMENT RATE 6.0 BPM,
PRE-FLUSH WATER, 33 BBLs, DENSITY 8.4 PPG,
DISPLACEMENT FLUID-MUD, DENSITY 9.0 PPG,
PIPE MOVEMENT-RECIPROATE,
RETURN FLOW 99.0%
STAGE 1, BATCH 2, API CLASS B,
IDEAL, VOL 637 SX,
SLURRY DENSITY 13.9 PPG,
HOLE FLUID DENSITY 9.0 PPG, TYPE-MUD,
AVG. DISPLACEMENT PRES 1000 PSI,
AVG. DISPLACEMENT RATE 6.0 BPM,
DISPLACEMENT FLUID-MUD, DENSITY 9.0 PPG,
PIPE MOVEMENT-RECIPROATE,
RETURN FLOW 99.0%
STAGE 2, BATCH 3, API CLASS B,
IDEAL, VOL 1100 SX,
SLURRY DENSITY 12.0 PPG,
HOLE FLUID DENSITY 9.0 PPG, TYPE-MUD,
AVG. DISPLACEMENT PRES 1000 PSI,
AVG. DISPLACEMENT RATE 4.5 BPM,
PRE-FLUSH WATER, 20 BBLs, DENSITY 8.4 PPG,
DISPLACEMENT FLUID-WATER, DENSITY 8.4 PPG,

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

21

VOL CIRC. CUT 338 BBLs,
RETURN FLOW 75.0%

ADDITIVES:

TYPE-WEIGHT REDUCER, FLY ASH 35.00 %
TYPE-WEIGHTING MATERIAL, GEL 6.00 %
TYPE-LOST CIRCULATION CONTROL, CELLOFLAKE 0.25 LB PER SX
TYPE-DISPERSANT OR FRICTION REDUCER, D-19 0.50 %
TYPE-OTHER, 50-50 PCZ 50.00 %
TYPE-WEIGHT REDUCER, FLY ASH 35.00 %
TYPE-WEIGHTING MATERIAL, GEL 6.00 %
TYPE-LOST CIRCULATION CONTROL, TUFF PLUG 2.00 LB PER SX

*** 12/11/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, RREL: SI: WDSU

TIME: CSG 2.00, CIRC 2.50, ND 1.50, RIG DOWN 4.00

COSTS: DAILY WELL \$135601, CUM WELL \$354502

REMARKS: RREL 1500 HR 122085; BMP PLUG ON 1ST STAGE CMT: HELD OK;

OPEN DV TOOL: CIRC 4 HR AFTER PLUG ON; MIX X PMP STAGE 2

388 BBL SLURRY X GOOD RETURNS; SD; DROP PLUG PMP 30 BBL OF

1300 BBL DISP: LOST RETURNS; BMP PLUG: PLUG HELD OK; SET

SLIPS X 132000#; CUT OFF CSG; RDRT; RAN TEMP SURVEY; FOUND

CMT TOP 3300 FT; TAG CMT ON TOP OF DV 5573; DV TOOL AT 5600

CHRON TIME DISTRIBUTION (HRS):

2.00 - 000019, CIRC MUD STAGE 2

0.50 - 000019, CIRC MUD STAGE 2

2.00 - 000011, CMT STAGE 2

1.50 - 000027, ND SET SLIPS X CUT OFF

4.00 - 000036, RD

*** 12/13/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, SI: WDSU

COSTS: CUM WELL \$354502

*** 12/16/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

*** 12/17/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

*** 12/18/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

*** 12/19/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

*** 12/20/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

*** 12/26/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

 FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
 AMOCO W.I. 1.0000
 OPERATIONS: TD 8700 FT, SI: WOSU
 COSTS: CUM WELL \$354502

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

23

*** 12/27/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, SI; WOSU

COSTS: CUM WELL \$354502

*** 12/30/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, SI; WOSU

COSTS: CUM WELL \$354502

*** 12/31/85 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 9700 FT, SI; WOSU

PERTINENT DATA: SUSPENDED 12/31/85, RESUMED 04/27/86

COSTS: CUM WELL \$354502

*** 01/02/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, SI; WOSU

COSTS: CUM WELL \$354502

*** 04/23/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8700 FT, MIRUSU

COSTS: DAILY WELL \$341, CUM WELL \$354843

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

24

*** 04/29/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, WD LCC TO DRY

COSTS: CUM WELL \$354843

REMARKS: ROAD RIG TO LCC; LAST 1 MILE OF ACCESS ROAD X 40 FT AROUND WELL
HEAD MUDDY; TOO MUDDY TO RU

*** 04/30/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, RUSU

PERTINENT DATA: RIG MOVE ON 04/30/86, RIG RELEASED 05/07/86

COSTS: CUM WELL \$354843

REMARKS: PUSH MUD AWAY FROM WELLHEAD; BUILD GRAVEL PAD; INSTALL FRAC

SPG3L: SPOT RIG NEXT TO WELLHEAD ON PAD

RIG CONTRACT DATA: CONTRACTOR BA CODE 433158, BIG A, RIG #022, SERVICE

*** 05/01/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, DRL OUT DV TOOL

COSTS: DAILY WELL \$705, CUM WELL \$355548

REMARKS: MIRUSU; UNLOAD X TALLY TBG; RU 80P; 4 INCH BLOW SPOOL X 4 INCH
BLW LINES: PU X TI X 4-3/4 INCH BIT X SCRAPER; BIT SER # T153670
TI: PU X RABBIT 2-7/8 TBG; TAG CMT AT 5518; CLEAN CUT TO 5638;
CIRC CLEAN: SIFN

*** 05/02/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBD 8658, SWB DN TO 8000

COSTS: DAILY WELL \$2118, CUM WELL \$357666

REMARKS: DRL DV TOOL; T1: DRL 75 FT CMT; DRL TO 8658; RECIPROCATATE X
ROTATE PIPE X CIRC CLEAN; PR TST CSG 6200; DISP FRESH WTR X
2X KEL; PULL 1 JT; RU SWB EQUIP; MADE 10 RUNS; SWB DN TO 3500

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

25

*** 05/03/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TD 8703 FT, PSTD 8658, SI

COSTS: DAILY WELL \$1919, CUM WELL \$359585

REMARKS: SWB FL DN TO 3000; TO X BIT X SCRAPER: SI

*** 05/04/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TD 8703 FT, PSTD 8658, SI

COSTS: CUM WELL \$359585

*** 05/05/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TD 8703 FT, PSTD 8658, SI

COSTS: DAILY WELL \$2886, CUM WELL \$362471

PERFORATIONS: 05/05/86, TOP 8578 FT, BOTTOM 8597 FT, TYPE-OPEN,
SHOTS/FT. 4, PERF DIAM. 0.480 IN, TOTAL NO. SHOT 72,
GUN-NON-EXPENDABLE, SIZE 4.000 IN, PHASING 120 DEG,
FLUID TRT-WATER, DENSITY 8.4 PPG, LEVEL 7700 FT

*** 05/06/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCC PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCC W.I. 1.0000

OPERATIONS: TD 8703 FT, PSTD 8650, SWB: FLW TST, FM DAKOTA

COSTS: DAILY WELL \$1552, CUM WELL \$364023

REMARKS: 54 BNW: RUWL RAN 4-3/4 INCH GAUGE RING: UNABLE TO PASS THRU
DV TQOL AT 5631 FT: PU X RUN 4-1/2 INCH GAUGE RING TO BTM
AT 8650 FT: 53 FT RAT HOLE: RAN CORR GR LOG FROM TD TO 7000 FT
PERF ZONE 8573-8597 FT: RD WL PICK UP 2-7/8 INCH NOTCHED
COLLAR: 1 JT 2-7/8 INCH TBG: BAKER RETR-A-MATIC PKR X TI: SET
PKR 8528: TBG END 8570 FT: IFL SURF: MADE 10 SWB RUNS: REC
54 BNW: FFL 790 FT

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

26

*** 05/07/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 9650, RDSU, FM DAKOTA

COSTS: DAILY WELL \$4848, CUM WELL \$368871

REMARKS: 72 BNW TOTAL; SITP 0; IFL 30C FT; MADE 3 SWB RUNS PULLING FROM

1600 FT; FFL 400 FT; CAUGHT WT SAMPLES FIRST X LAST RUNS; REC

18 BNW; NO SHOW OF OIL OR GAS; REL PKR; TC; SET CIBP AT

8150; CAP X 2 SX CMT; PR TST CIBP TO 1000 LB 15 MIN; TI X

250 JT 2-7/8 INCH TBG; TBG END AT 7586; LAND TBG HANGER; CLOSE

X LOCK BOPS

*** 05/08/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 3703 FT, PBTD 8650, SI

COSTS: DAILY WELL \$2877, CUM WELL \$371748

*** 05/09/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8650, SI

COSTS: CUM WELL \$371748

*** 05/12/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8650, SI

COSTS: CUM WELL \$371748

*** 05/13/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

27

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8650, SI
COSTS: CUM WELL \$371748

*** 05/14/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8650, SI
COSTS: CUM WELL \$371748

*** 05/15/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8650, SI
COSTS: CUM WELL \$371748

*** 05/16/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8650, SI
COSTS: CUM WELL \$371748

*** 05/19/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8650, SI
COSTS: CUM WELL \$371748

*** 05/20/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

28

OPERATIONS: TD 8703 FT, P8TD 8650, SI
COSTS: CUM WELL \$371748

*** 05/21/86 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, MIRUSU

PERTINENT DATA: RIG MOVE ON 05/21/86, RIG RELEASED 05/28/86

COSTS: CUM WELL \$371748

REMARKS: ROAD RIG TO LOCATION

RIG CONTRACT DATA: CONTRACTOR BA CODE 433158, BIG A, RIG #22A, SERVICE

PERFORATIONS: 05/21/86, TOP 7511 FT, BOTTOM 7704 FT, TYPE-OPEN,

SHOTS/FT. 1, PERF DIAM. 0.430 IN, TOTAL NO. SHOT 194,

GUN-NON-EXPENDABLE, SIZE 4.000 IN, PHASING 120 DEG,

DENSITY 8.4 PPG, LEVEL 6300 FT

*** 05/22/86 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, P8TD 8510, PERF, FM GLLP

COSTS: DAILY WELL \$8689, CUM WELL \$380437

REMARKS: MIRUSU: PULL OUT OF HOLE X TBG TO 6700; BLW DRY X N2; TO X TBG;

RU PERF; PERF 7704-7511; 6 RUNS; SIFN

PERFORATIONS: 05/22/86, TOP 7280 FT, BOTTOM 7510 FT, TYPE-OPEN,

SHOTS/FT. 1, PERF DIAM. 0.480 IN, TOTAL NO. SHOT 231,

GUN-NON-EXPENDABLE, SIZE 4.000 IN, PHASING 120 DEG,

FLUID TRT-WATER, DENSITY 8.4 PPG, LEVEL 6200 FT

*** 05/23/86 ***

JICARILLA TRIBAL 519 NC. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, P8TD 8510, FRAC THE GLLP

COSTS: DAILY WELL \$2310, CUM WELL \$382747

REMARKS: SICP 10; CONT PERF GLLP; 7 RUNS 7510 TO 7280 FT; FL 6200 FT

THROUGHOUT JOB; CHECK FRAC WT X SN MASTER; SI FOR NIGHT

CHRON TIME DISTRIBUTION (HRS):

8.00 - PERF

COMPL, RECOMPL, REPAIR OPERATIONS: 05/23/86, TYPE-FLUID TREATMENT,

TOP DEPTH 7280 FT, BOTTOM 7704 FT

FLUID TREATMENT: NO. 1, WATER FRAC, 6800 GALS.

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

29

BREAKDOWN PRES 3200 PSI, BREAKDOWN RATE 35.00 BPM,
INJ PRES 4000 PSI, INJ RATE 58.00 BPM,
INJ STRING-CASING, TBC CD 5.500 IN, ID 4.892 IN,
INIT SITP 2700 PSI,
SITP AFT 2350 PSI

TREATMENT COMPONENTS: BASE FLUID,
2% KCL WTR
GELLING AGENT,
J2C GEL, 9150.00 LB
CROSSLINK AGENT,
TIC XLINK, 250.00 GAL
PROPPING AGENT,
20-40 BRADY SN, 400.00 M LB
TRACER MATERIAL,
RA TRACER MAT., 133.00 MILL
EMULSIFIER,
ACUA FLW, 304.00 GAL
OTHER,
BS BREAKER, 250.00 LB
OTHER,
FRAC SIDE, 86.00 GAL

*** 05/24/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CGST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, SI TO HEAL FRAC, FM GLLP

COSTS: DAILY WELL \$13030, CUM WELL \$395777

REMARKS: BLW 6065: FRAC GLLP ON CSG X 254730 GAL 30% XLINK GEL 2%
X 400000# 20-40 BRADY SN; TAG SN X MILLICURIES RA MATERIAL;
FLUSH X 162 BBL GEL 2% KCL WTR; ISIP 2700; 5 MIN 2400;
10 MIN 2350; 15 MIN 2350; SI TO HEAL FRAC; MAX PR 4150;
AVG PR 3100

CHRON TIME DISTRIBUTION (HRS):

6.00 -	PREP TO FRAC
2.50 -	FRAC
3.00 -	RD FRAC
11.00 -	SI

*** 05/25/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CGST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW BACK FRAC

COSTS: CUM WELL \$395777

REMARKS: BLW 6065: BLWTR 5465; SICP 1700; OPEN TO PIT THRU 1/4 CH

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/97 *** PAGE

30

12 HR REC EST 600 BLW TO PIT; NO SHOW OF OIL; BURNABLE GAS

*** 05/26/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8510, FLW BACK FRAC
COSTS: CUM WELL \$395777
REMARKS: FCP 700; 1/4 CH; REC TO PIT EST 800 BLW; NO OIL; BURNABLE GAS

*** 05/27/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8510, TI X TBG
COSTS: DAILY WELL \$1151, CUM WELL \$396928
REMARKS: CP 590; 1/4 CH; OPEN CH 3/4; CP 70; REC 675 BLW; NO OIL;
BURNABLE GAS

*** 05/28/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, BIG A 22A, AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8510, ND BOP; CHG WELLHEAD
COSTS: DAILY WELL \$849, CUM WELL \$397777
CASING: SET 7499 FT, 05/28/86
REMARKS: BLW 6065; BLWTR 3940; TI X 2-7/8 INCH TBG; RAN GAMMA RAY
TRACER SURVEY; TAG SN AT 7985; BTM PERF 7704; 281 FT RAT HOLE;
LAND END OF TBG 7499; MIDDLE OF PERFS: FLW TBG TO PIT FULL
OPEN 2 INCH; REC EST 50 BLW; BURNABLE GAS; CP 420
DETAIL: BOTTOM 7499.0 FT, 2.875 IN, WT 6.50 #/FT,
GRADE J55, CONNECTION 8 RD EUE, NC OF JTS. 237
TOOLS: TYPE-NIPPLE, TOP 7498.0 FT, BOTTOM 7499.0 FT,
NO. OF TOOLS 1, NAME-STAND SEAT NIPPLE

*** 05/29/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

31

COSTS: DAILY WELL \$1014, CUM WELL \$398791

REMARKS: ND 5000# WELLHEAD X INSTALL 3000# WELLHEAD; RD; MCSU; HOOK UP
FLW LINE X SEP; FLW TO PIT 50 BLW; CP 650; TP 0; EQUALIZED
T8G X CSG; SIGN

CHRON TIME DISTRIBUTION (HRS):

3.00 - CHANGE WELLHEAD
3.00 - RDMCSU

*** 05/30/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW, FM GLLP

COSTS: DAILY WELL \$1856, CUM WELL \$400647

REMARKS: TBG LOGGED CF; SLIGHT BLW; 1250 CP; EQUALIZED TBG X CSG;
DROP SOAP BAR; WELL WOULD NOT COME AROUND; HOOK UP; BLOW WELL
X N2; KICK TBG OFF; FTP 160; CP 460; STATIC 3.1; DIFF 6;
MCFD 188.7; 24/64 CH; .875 ORFICE; TEMP 55 DEG; 50# SEP PR;
REC TO TANK 35 BLW; FLW TO PIT 35 BLW; REC 70 BLW; NO OIL

CHRON TIME DISTRIBUTION (HRS):

9.00 - 000037, LOG TBG X CSG EQUALIZED
2.00 - 000037, BLOW AROUND X N2
11.00 - 000037, FLW TST

*** 05/31/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: CUM WELL \$400647

REMARKS: FTP 60; CP 425; CH 24/64; STATIC 3.1; DIFF 4.3; TEMP 55;
MCFD 135; BLW 43; BND 0

*** 06/01/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: CUM WELL \$400647

REMARKS: FTP 78; CP 390; 24/64 CH; STATIC 3; DIFF 5.5; TEMP 50;
MCFD 167; BLW 41; BND 0

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

32

*** 06/02/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: CUM WELL \$400647

REMARKS: FTP 100; CP 400; MCFD 156; STATIC 2.9; DIFF 5.3; CH 24/64;
24 HR; BLW 19; PLATE .875; SPRING 500; SEP TEMP 50

*** 06/03/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST, FM GLLP

COSTS: DAILY WELL \$20342, CUM WELL \$420989

REMARKS: FTP 95; CP 400; PLATE .875; 4 INCH METER RUN; SEP PR 50;
24/64 CH; TEMP 57; 23 BLW; STATIC 2.9; DIFF 4.7; MCFD 140;

BLW 6065; BLWTR 3695

CHRON TIME DISTRIBUTION (HRS):

24.00 - FLW TST

*** 06/04/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: DAILY WELL \$56462, CUM WELL \$477451

REMARKS: FTP 30; CP 420; 57 MCFD; 24/64 CH; 27 BLW; 0 BNG; STATIC 3.1;
DIFF 5; PLATE .875; 4 INCH METER RUN; SEP TEMP 60 DEG;

SEP PR 50; 24 HR

CHRON TIME DISTRIBUTION (HRS):

24.00 - 000037, FLW TST

*** 06/05/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: DAILY WELL \$575, CUM WELL \$473026

REMARKS: FTP 70; CP 350; MCFD 143; 24/64 CH; 15 BLW; STATIC 3.1;

DIFF 4.5; TEMP 60; PLATE .875

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

33

CHRON TIME DISTRIBUTION (HRS):
24.00 - 000037, FLW

*** 06/06/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW

COSTS: DAILY WELL \$336, CUM WELL \$478362

REMARKS: FTP 75; CP 360; 157 MCFD; 24/64 CH; 15 BLW; STATIC 3.1;
DIFF 5; TEMP 65; 24 HR; PLATE .875; REC 15 BLW; 0 BND

*** 06/07/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: CUM WELL \$478362

REMARKS: FTP 70; CP 340; MCFD 157; 24 HR; BND 0; BLW 17; TEMP 60
STATIC 3.1; DIFF 5; PLATE .875; SEP PR 50; 24/64 CH

*** 06/08/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: DAILY WELL \$234, CUM WELL \$478596

REMARKS: FTP 70; CP 360; STATIC 3.1; DIFF 4.8; TEMP 70; 152 MCFD;
SEP PR 50; 15 BLW; 0 BND; .875 PLATE; 24/64 CH

CHRON TIME DISTRIBUTION (HRS):

24.00 - 000037, FLW

*** 06/09/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH COST \$1323000,

AMOCO W.I. 1.0000

OPERATIONS: TD 8703 FT, PBTD 8510, FLW TST

COSTS: CUM WELL \$478596

REMARKS: BLWTR 3252; FTP 70; CP 360; STATIC 3.1; DIFF 4.6;
CH 24/64; 24 HR; MCFD 148; SEP PR 50; BLW 16

DENVER

REGION *** FARMINGTON

DISTRICT *** 02/13/87 *** PAGE

34

*** 06/10/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8510, SI
COSTS: CUM WELL \$478596
REMARKS: FTP 73; CP 350; 24 HR; CH 24/64; BNC 0; BLW 12; SEP PR 50;
STATIC 3; DIFF 4.5; PLATE .875; TEMP 60; SPRING 500;
RANGE 0-100; 4 INCH METER RUN; MCFD 136

*** 06/11/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8501, SI
COSTS: CUM WELL \$478596

*** 06/12/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8501, SI
COSTS: CUM WELL \$478596

*** 06/13/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8501, SI
COSTS: CUM WELL \$478596

*** 06/16/86 ***

JICARILLA TRIBAL 519 NO. 1, WILDCAT, , AMOCO PRODUCTION,

FLAC 846167-01-3, API 300392333100, AUTH TD 8520, AUTH CCST \$1323000,
AMOCO W.I. 1.0000
OPERATIONS: TD 8703 FT, PBTD 8501, SI

ATTACHMENT #1

ROBERT L. BAYLESS

PETROLEUM PLAZA BUILDING
P. O. BOX 168
FARMINGTON, NEW MEXICO 87499
(505) 326-2659

JICARILLA 519 #1
SE/4, Sec. 18, T30N-R2W
Rio Arriba County, New Mexico
RE-COMPLETION REPORT

- 5-29-87 Move in and rig up Bayless Rig 4. Shut down for the night.
- 5-30-87 Shut down - Saturday
- 5-31-87 Shut Down - Sunday
- 6-01-87 Lay down 242 jts. of 2-7/8" EUE tubing on float. Sent float to Amoco yard. Rigged up Basin Perforators - set wireline, set retrievable bridge plug at 4000 ft. RKB. Pressure tested bridge plug to 3000 psi - held ok for 5 minutes. Dropped 10 gallons of sand on top of bridge plug. Shut down for night.
- 6-02-87 Rigged up Basin Perforators. Ran GR-CLL-CBL from 3991 ft. to 3000 ft. under 1,000 psi pressure. Top of cement at 3311 ft. RKB. Pictured Cliffs interval and Fruitland interval had good bond, but poor bond below and above. Pictured Cliffs perforations have no bond below and 47 feet of bond above. Perforated Pictured Cliffs interval with 4" casing gun and 4 JSPF as follows:
- 3723 - 3728' 5' 20 holes (.50" diameter)
- Lost perforating gun and 500 ft. of wireline when coming out of hole with gun run (line parted). Trip in hole with grapple type spear on tubing, recovered fish first try. Lay down wireline and perforating gun. Shut down for night.
- 6-03-87 Trip in hole with 4-1/2" X 2-3/8" swage on end of tubing. Rigged up The Western Company. Circulate hole clean with 2% KCL water, move tubing to 3423'. Broke down Pictured Cliffs perforations at 3300 psi. Established an injection rate into perforations down the tubing of 4.0 BPM @ 2200 psi. ISIP - 350 psi. Re-established an injection rate into perforations down the tubing of 4.0 BPM @ 2200 psi. ISIP = 350 psi. Acidized down the tubing with 250 gallons of 7-1/2% DI weighted HCL acid containing 30 l.1 sg RCN ball sealers. 4.0 BPM @ 2200 psi, had good ball action. Balled off to 3500 psi. Bled off pressure. Final injection rate of 4.0 BPM @ 1300 psi. ISIP = 350 psi. Moved tubing with swage below perforations to knock off ball sealers. Trip tubing out of hole. Fracture stimulated the Pictured Cliffs interval with 16,500 gallons of 70 quality foam containing 20,000 lbs. of 20/40 sand as follows:

4000 gallons of pad	30 BPM @ 1600 psi
5000 gallons of 1 ppg 20-40 sand	30 BPM @ 1900-2100 psi
7500 gallons of 2 ppg 20-40 sand	30 BPM @ 2100-1800 psi
3627 gallons of flush	30 BPM @ 1800 psi

ISIP = 1500 psi, 5 min = 1300 psi, 10 min = 1300 psi, 15 min = 1300 psi. (All water contained 2% KCL and 1/2 gal/1000 clay stabilization agent.) Average rate - 30 BPM; Average pressure - 1900 psi; Maximum pressure - 2200 psi; Minimum pressure - 1600 psi. Average Nitrogen injection rate - 18,000 SCF/min, total Nitrogen pumped 272,395 SCF, total fluid to recover - 162 bbls. Shut in well for 3 hours. Opened well to atmosphere through 1/2" bull plug. Shut down for night.

6-04-87 Well flowing to cleanup after frac.
 9:00 AM - 1/2" opening flowing pressure = 140 psi - no sand, gas won't burn.
 5:00 PM - 1/2" opening flowing pressure = 140 psi - no sand, gas burns.

6-05-87 Well flowing - 7:30 AM - 1/2" opening flowing pressure = 50 psi - gas burns. Approximate flow rate = 337 MCFGPD. Kill well, trip in hole with 2-3/8" tubing. Tag sand fill at 3958 ft. RKB. Landed Tubing as follows:

DESCRIPTION	LENGTH	DEPTH
KB to landing point	10.60	0-11
121 jts., 2-3/8", 4.7#/ft, J-55 and N-80 used tubing	3696.34	11-3707
1 - seating nipple	1.00	3707-3708
1 jt., 2-3/8", 4.7#/ft., N-80 used tubing	31.63	3708-3739
	3739.57	

Nipple down BOP - nipple up wellhead. Released rig.

6-06-87 Well shutin - Building pressure for AOF test.

6-07-87 Well shutin - Building pressure for AOF test.

6-08-87 Well shutin - Building pressure for AOF test.

6-09-87 Well shutin - Building pressure for AOF test.

6-10-87 Well shutin - Building pressure for AOF test.

6-11-87 Well shutin - Building pressure for AOF test.

6-12-87 Well shutin - Building pressure for AOF test.

6-13-87 Well shutin - Building pressure for AOF test.

6-14-87 Well shutin - Building pressure for AOF test.

6-15-87 Conducted AOF test on well - SICP = 1065 psi, SITP = 1062 psi. Flow for 3 hours through 3/4" choke, 2" tester, CP = 110 psi,

FTP = 51 psi. Calculated Q = 754 MCFGPD, Calculated AOF = 762 MCFGPD

- 6-16-87 Testing P.C. interval through test separator -
FTP = 140 psi Static = 2.2 Backpressure = psi
CP = 205 psi Differential = 10.0 Water Prod. = 0 Bbls.
Orifice = 1.250 in. Gas Prod(MCFGPD) = 720
- 6-17-87 Testing P.C. interval through test separator -
FTP = 50 psi Static = 2.0 Backpressure = 50 psi
CP = 90 psi Differential = 2.5 Water Prod. = 0 Bbls.
Orifice = 1.250 in. Gas Prod(MCFGPD) = 163
- 6-18-87 Testing P.C. interval through test separator -
FTP = 64 psi Static = 2.4 Backpressure = 64 psi
CP = 128 psi Differential = 4.8 Water Prod. = 0 Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 125
- 6-19-87 Testing P.C. interval through test separator -
FTP = psi Static = 2.4 Backpressure = psi
CP = 128 psi Differential = 3.8 Water Prod. = Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 99
- 6-20-87 Testing P.C. interval through test separator -
FTP = psi Static = 2.4 Backpressure = psi
CP = psi Differential = 3.3 Water Prod. = Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 86
- 6-21-87 Testing P.C. interval through test separator -
FTP = psi Static = 2.4 Backpressure = psi
CP = psi Differential = 3.1 Water Prod. = Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 81
- 6-22-87 Testing P.C. interval through test separator -
FTP = 63 psi Static = 2.5 Backpressure = 63 psi
CP = 159 psi Differential = 2.8 Water Prod. = 3.3 Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 76
- 6-23-87 Testing P.C. interval through test separator -
FTP = 57 psi Static = 2.3 Backpressure = 57 psi
CP = 152 psi Differential = 2.8 Water Prod. = 2.5 Bbls.
Orifice = .750 in. Gas Prod(MCFGPD) = 70
- 6-24-87 Shut in well - wait on results of downhole commingle request.

OIL CONSERVATION DIVISION

STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENT

P. O. BOX 2088

SANTA FE, NEW MEXICO 87501

Form C-122
Revised 10-1-78

ATTACHMENT #2

MULTIPOINT AND ONE POINT BACK PRESSURE TEST FOR GAS WELL

Type Test ☒ Initial ☐ Annual ☐ Special					Test Date 5/28/87				
Company Robert L. Bayless				Connection None					
Pool Undesignated				Formation Gallup				Unit	
Completion Date 6/10/86		Total Depth 8703		Plug Back TD 8150		Elevation 7437 RKB		Farm or Lease Name Jicarilla	
Csq. Size 5-1/2"	Wt. 17#	d 4.892	Set At 8703	Perforations: From 7280 To 7704				Well No. 519 #1	
Tng. Size 2-7/8"	Wt. 6.5#	d 2.441	Set At 7499	Perforations: From To				Unit Sec. Twp. Rge. 0 18 30N 2W	
Type Well - Single - Bradenhead - G.G. or G.O. Multiple Gas-Single					Packer Set At None			County Rio Arriba	
Producing Thru tubing		Reservoir Temp. °F #		Mean Annual Temp. °F		Baro. Press. - P _a est. 12.0		State New Mexico	
L	H	Gg est. .63	% CO ₂	% N ₂	% H ₂ S	Prover	Meter Run	Taps	

FLOW DATA						TUBING DATA		CASING DATA		Duration of Flow
NO.	Prover Line Size	X	Orifice Size	Press. p.s.i.g.	Diff. h _w	Temp. °F	Press. p.s.i.g.	Temp. °F	Press. p.s.i.g.	
SI	352 days						2952		2957	
1.	2" x .750						71	60°F	453	
2.										
3.										
4.										
5.										

RATE OF FLOW CALCULATIONS							
NO.	Coefficient (24 Hour)	$\sqrt{h_w P_m}$	Pressure P _m	Flow Temp. Factor F _t	Gravity Factor F _g	Super Compress. Factor, F _{pv}	Rate of Flow Q, Mcfd
1	12.3650		83	1.000	.9759	1.011	1013
2.							
3.							
4.							
5.							

NO.	P _t	Temp. °R	T _r	Z	Gas Liquid Hydrocarbon Ratio _____ Mcf/bbl.	
1					A.P.I. Gravity of Liquid Hydrocarbons _____ Deg.	
2.					Specific Gravity Separator Gas _____ X X X X X X X X	
3.					Specific Gravity Flowing Fluid _____ X X X X X	
4.					Critical Pressure _____ P.S.I.A. _____ P.S.I.A.	
5.					Critical Temperature _____ R _____ R	

P _c 2969	P _c ² 8,814,961		
NO.	P _t ²	P _w	P _w ²
1		465	216,225
2			
3			
4			
5			

$$(1) \frac{P_c^2}{P_c^2 - P_w^2} = 1.0251$$

$$AOF = Q \left[\frac{P_c^2}{P_c^2 - P_w^2} \right]^n = 1032$$

$$(2) \left[\frac{P_c^2}{P_c^2 - P_w^2} \right]^n = 1.0188$$

Absolute Open Flow _____ 1032 _____ Mcfd @ 15.025	Angle of Slope θ _____	Slope, n _____ .75 _____
---	------------------------	--------------------------

Remarks: Slight mist of fluid during test

Approved By Division	Conducted By: David Ball	Calculated By: Kevin McGord	Checked By:
----------------------	-----------------------------	--------------------------------	-------------

OIL CONSERVATION DIVISION

STATE OF NEW MEXICO
ENERGY AND MINERALS DEPARTMENT

P.O. BOX 2088

SANTA FE, NEW MEXICO 87501

Form C-122
Revised 10-1-78

ATTACHMENT #3

MULTIPOINT AND ONE POINT BACK PRESSURE TEST FOR GAS WELL

Type Test ☒ Initial ☐ Annual ☐ Special					Test Date 6/15/87				
Company Robert L. Bayless				Connection None					
Pool Undesignated				Formation Pictured Cliffs				Unit	
Completion Date 6/5/87		Total Depth 8703		Plug Back TD 4000		Elevation 7437 RKB		Farm or Lease Name Jicarilla	
Csq. Size 5-1/2"	Wt. 17#	d 4.892	Set At 8703	Perforations: From 3723 To 3728			Well No. 519 #1		
Tng. Size 2-3/8"	Wt. 4.7#	d 1.995	Set At 3739	Perforations: From To			Unit Sec. Twp. Rge. 0 18 30N 2W		
Type Well - Single - Bradenhead - G.G. or G.O. Multiple Gas-Single					Packer Set At None		County Rio Arriba		
Producing Thru Tubing		Reservoir Temp. °F #		Mean Annual Temp. °F		Baro. Press. - P _a est. 12.0		State New Mexico	
L	H	Gg est. .65	% CO ₂	% N ₂	% H ₂ S	Prover	Meter Run	Taps	

FLOW DATA							TUBING DATA		CASING DATA		Duration of Flow
NO.	Prover Line Size	X	Orifice Size	Press. p.s.i.g.	Diff. h _w	Temp. °F	Press. p.s.i.g.	Temp. °F	Press. p.s.i.g.	Temp. °F	
SI	10 days						1062		1065		
1.	2" x .750						51	60°	110		3 hrs.
2.											
3.											
4.											
5.											

RATE OF FLOW CALCULATIONS							
NO.	Coefficient (24 Hour)	$\sqrt{h_w P_m}$	Pressure P _m	Flow Temp. Factor F _t	Gravity Factor F _g	Super Compress. Factor, F _{pv}	Rate of Flow Q, Mcfd
1	12.3650		63	1.0000	.9608	1.008	754
2.							
3.							
4.							
5.							

NO.	P _t	Temp. °R	T _r	Z	Gas Liquid Hydrocarbon Ratio _____ Mcf/bbl.
1					A.P.I. Gravity of Liquid Hydrocarbons _____ Deg.
2					Specific Gravity Separator Gas _____ X X X X X X X X
3					Specific Gravity Flowing Fluid _____ X X X X X
4					Critical Pressure _____ P.S.I.A. _____ P.S.I.A.
5					Critical Temperature _____ R _____ R

P _c 1077 P _c ² 1,159,929				
NO.	P _t ²	P _w	P _w ²	P _c ² - P _w ²
1		122	14,884	1,145,045
2				
3				
4				
5				

(1) $\frac{P_c^2}{P_c^2 - P_w^2} = 1.0130$ (2) $\left[\frac{P_c^2}{P_c^2 - P_w^2} \right]^n = 1.0110$

AOF = Q $\left[\frac{P_c^2}{P_c^2 - P_w^2} \right]^n = 762$

Absolute Open Flow 762 Mcfd @ 15.025	Angle of Slope θ _____	Slope, n .85
--	------------------------	--------------

Remarks: Slight mist of fluid during test.

Approved By Division	Conducted By: David Ball	Calculated By: Kevin McCord	Checked By:
----------------------	-----------------------------	--------------------------------	-------------

ATTACHMENT #4

ROBERT L. BAYLESS
JICARILLA 519 #1

GALLUP PRODUCTION TEST INFORMATION

<u>DATE</u>	<u>FLOWING TUBING PRESSURE (psi)</u>	<u>ANNULUS PRESSURE (psi)</u>	<u>ORIFICE SIZE (IN.)</u>	<u>STATIC READING</u>	<u>DIFFERENTIAL READING</u>	<u>PRODUCTION (MCFGPD)</u>	<u>SEPERATOR PRESSURE (psi)</u>	<u>WATER PRODUCTION (Bbls)</u>
5/30/86	160	460	.875	3.1	6.0	189	50	70
5/31/86	60	425	.875	3.1	4.3	135		43
6/1/86	78	390	.875	3.0	5.5	167		41
6/2/86	100	400	.875	2.9	5.3	156	60	18
6/3/86	85	400	.875	2.9	4.7	140	50	23
6/4/86	80	420	.875	3.1	5.0	157	50	27
6/5/86	70	350	.875	3.1	4.5	143		15
6/6/86	75	360	.875	3.1	5.0	157		15
6/7/86	70	340	.875	3.1	5.0	157	50	17
6/8/86	70	360	.875	3.1	4.8	152	50	15
6/9/86	70	360	.875	3.1	4.6	148	50	16
6/10/86	70	350	.875	3.0	4.5	136	50	12

Tested 12 Days

Average Gas Production
(Last 8 days)

= 149 MCFGPD (Against 50 psi Backpressure)

Associated Water Production

= 18 BWPD

ATTACHMENT #5

ROBERT L. BAYLESS
JICARILLA 519 #1

PCITURED CLIFFS PRODUCTION TEST INFORMATION

<u>DATE</u>	<u>FLOWING TUBING PRESSURE (psi)</u>	<u>ANNULUS PRESSURE (psi)</u>	<u>ORIFICE SIZE (IN)</u>	<u>STATIC READING</u>	<u>DIFFERENTIAL READING</u>	<u>GAS PRODUCTION (MCFPD)</u>	<u>SEPERATOR PRESSURE (psi)</u>	<u>WATER PRODUCTION (Bbls.)</u>
6/16/87	140	205	1.250	2.2	10.0	720		0
6/17/87	50	90	1.250	2.0	2.5	163	50	0
6/18/87	64	128	.750	2.4	4.8	125	64	0
6/19/87			.750	2.4	3.8	99		
6/20/87			.750	2.4	3.3	86		
6/21/87			.750	2.4	3.1	81		
6/22/87	63	159	.750	2.5	2.8	76	63	3.3
6/23/87	57	152	.750	2.3	2.8	70	57	2.5

Tested 8 Days

Average Gas Production

(Last 3 Days)

= 75 MCFGPD (Against 60 psi Backpressure)

Associated Water Production

= 3 BWPD

ATTACHMENT #6

ROBERT L. BAYLESS
JICARILLA 519 #1

SUMMARY OF
GALLUP AND PICTURED CLIFFS GAS ANALYSIS

NOTE: GAS ANALYSIS WERE COMPARED FROM CLOSEST OFFSET WELL INFORMATION FOUND.

GALLUP FORMATION

<u>WELL</u>	<u>OPERATOR</u>	<u>LOCATION (T-R-S-U)</u>	<u>GAS SPECIFIC GRAVITY</u>	<u>GAS BTU CONTENT</u>
1. San Juan 29-4, Unit #24	Meridian Oil	29-4-8-B	.611	1055
2. Burns Ranch #1	Meridian Oil	29-4-13-A	.683	1181
3. Chicosa Canyon #1	Meridian Oil	31-4-35-M	.591	981
	AVERAGE		.628	1072

PCITURED CLIFFS FORMATION

<u>METER</u>	<u>WELL LOCATIONS</u>	<u>GAS SPECIFIC GRAVITY</u>	<u>GAS BTU CONTENT</u>
1. Bayless Delivery Meter #1	T30NR3W-A11 (8 Wells)	.658	1139
2. Bayless Delivery Meter #2	T29NR3W-N $\frac{1}{2}$ N $\frac{1}{2}$ (2 Wells)	.648	1123
	AVERAGE	.653	1131

ATTACHMENT #7


ROBERT L. BAYLESS
JICARILLA 519 #1 - COMMINGLING APPLICATION

PROPOSED ALLOCATION FORMULA: Rates calculated after 3 hour flow through a 3/4" choke during One Point Back Pressure Test.

<u>FORMATION</u>	<u>Q (MCFPD)</u>	<u>% OF TOTAL FLOW</u>
Undesignated Pictured Cliffs	754	43%
Undesignated Gallup	<u>1013</u>	<u>57%</u>
TOTAL	1767	100%

ATTACHMENT #8

LEASES IN VICINITY OF JICARILLA 519 #1



note: BOTH THE GALLUP AND PICTURED CLIFFS FORMATIONS ARE SPACED AT 160 ACRES. THE OWNERSHIP OF THE JICARILLA 519 #1 IS COMMON FOR ALL ZONES (INCLUDES WORKING INTEREST, ROYALTY, AND OVERRIDING ROYALTY).

ATTACHMENT #9

ROBERT L. BAYLESS

PETROLEUM PLAZA BUILDING
P. O. BOX 168
FARMINGTON, NEW MEXICO 87499
(505) 326-2659

July 2, 1987

Union Oil Company of California
900 Werner Court
P.O. Box 2620
Casper, Wyoming 82602

RE: Proposed Downhole Commingling
Jicarilla 519 #1 Well
Unit 0, Sec. 18 T30N R2W
Rio Arriba County, New Mexico

Gentlemen:

The Jicarilla 519 #1 well is an offset well to your JICARILLA CONTRACT #516. We plan to downhole commingle the Gallup and Pictured Cliffs formation in this well and have requested the New Mexico Oil Conservation Division to administratively approve this commingling of production. A copy of this application is attached.

In order to obtain approval from the Oil Conservation Division Director, we must obtain waivers of objections from offset lease holders. If you have no objections to our plans, please execute the waiver protion of this letter and return one copy to us at the above address and another copy to the Division Director, Oil Conservation Division, P.O. Box 2088, Santa Fe, NM 87501.

If you require additional information, please advise.

Yours truly,

Original Signed By
ROBERT L. BAYLESS

Robert L. Bayless

RLB:blk

Enclosure:


I have no objection to the above stated plans.

Union Oil Company of California

Date

Twp. 30 N Rge. 2 W County State

Fee



30N-3W

Description of
Lands

Total Acres