

1R - 427 - 188

REPORTS

DATE:

3-2-04

1R0427-188

Final Report

**RICE OPERATING COMPANY
JUNCTION BOX FINAL REPORT**

BOX LOCATION

| SWD SYSTEM | JUNCTION | UNIT | SECTION | TOWNSHIP | RANGE | COUNTY | BOX DIMENSIONS - FEET | | |
|------------|------------------------|------|---------|----------|-------|--------|-----------------------|-------|-------|
| EME | Conoco St. A-2A EOL | P | 2 | 20S | 37E | Lea | Length | Width | Depth |
| | | | | | | | 8 | 6 | 4 |

LAND TYPE: BLM _____ STATE X FEE LANDOWNER _____ OTHER _____

Depth to Groundwater none feet NMOCD SITE ASSESSMENT RANKING SCORE: 0

Date Started 11/9/2005 Date Completed 11/29/2005 NMOCD Witness no

Soil Excavated 11 cubic yards Excavation Length 8 Width 3 Depth 12 feet

Soil Disposed 0 cubic yards Offsite Facility n/a Location n/a

FINAL ANALYTICAL RESULTS: Sample Date 11/9/2005 Sample Depth 12 ft

TPH and chloride laboratory test results completed by using an approved laboratory and testing procedures pursuant to NMOCD guidelines.

CHLORIDE FIELD TESTS

| Sample Location | PID ppm | GRO mg/kg | DRO mg/kg | Chloride mg/kg |
|------------------|---------|-----------|-----------|----------------|
| GRAB @ 12 ft BGS | 0.1 | <10.0 | <10.0 | 11.6 |
| REMED. BACKFILL | 0.0 | <10.0 | <10.0 | 99.1 |

| LOCATION | DEPTH (ft) | ppm |
|---|------------|-----|
| vertical delineation trench at junction | 1 | 206 |
| | 2 | 209 |
| | 3 | 330 |
| | 4 | 209 |
| | 5 | 251 |
| | 6 | 269 |
| | 7 | 226 |
| | 8 | 235 |
| | 9 | 163 |
| | 10 | 241 |
| | 11 | 160 |
| | 12 | 188 |

General Description of Remedial Action:

This junction box site was addressed

with the pipeline replacement. The old junction box was removed and a delineation trench was

made using a backhoe to 12 ft BGS while soil samples were collected every ft of depth. PID

screenings performed on the soil samples were all very low (<= 0.2 ppm) and chloride

concentrations from the field tests were also very low. A grab sample at 12 ft BGS was submitted

to a laboratory for confirmation analysis and confirmed the field tests. There were no indications

of hydrocarbon in the soil and the lab analysis indicated that TPH was not present with the lab's

detection limit (<10.0 ppm), meeting NMOCD guidelines. The excavated soil was blended on site and then backfilled into the trench. A new watertight

junction box has been built over this location. The disturbed surface resulting from these activities is expected to return to productive capacity at a

normal rate.

enclosures: photos, lab results, PID field screenings

I HEREBY CERTIFY THAT THE INFORMATION ABOVE IS TRUE AND COMPLETE TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

SITE SUPERVISOR Kevin Collins SIGNATURE not available COMPANY RICE Operating Company

REPORT ASSEMBLED BY Kristin Farris Pope SIGNATURE _____

DATE 3/2/2006 TITLE Project Scientist

EME Conoco St. A-2A EOL

Unit 'P', Section 2, T20S, R37E



undisturbed junction box

2/1/2005



delineation trench at junction

Nov. 2005



open hole prior to backfill

Nov. 2005



backfilling trench

11/29/2005




backfilled to pipeline

11/29/2005



floor of new junction box with new plumbing

12/12/2005



12600 West I-20 East - Odessa, Texas 79765

COPY

Analytical Report

Prepared for:

Roy Rascon
Rice Operating Co.
122 W. Taylor
Hobbs, NM 88240

EME

Project: Conoco St. A-2-~~A~~
Project Number: None Given
Location: None Given

Lab Order Number: 5K14014

Report Date: 11/18/05

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon

Fax: (505) 397-1471

Reported:
11/18/05 12:21

ANALYTICAL REPORT FOR SAMPLES

| Sample ID | Laboratory ID | Matrix | Date Sampled | Date Received |
|-------------------|---------------|--------|----------------|----------------|
| Vert@ Source@ 12' | 5K14014-01 | Soil | 11/09/05 10:50 | 11/11/05 17:30 |
| Backfill Comp. | 5K14014-02 | Soil | 11/09/05 11:00 | 11/11/05 17:30 |

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon

Fax: (505) 397-1471

Reported:
11/18/05 12:21

Organics by GC
Environmental Lab of Texas

| Analyte | Result | Reporting Limit | Units | Dilution | Batch | Prepared | Analyzed | Method | Notes |
|--|--------|--------------------|-----------|----------|---------|----------|----------|-----------|-------|
| Vert@ Source@ 12' (5K14014-01) Soil | | | | | | | | | |
| Gasoline Range Organics C6-C12 | ND | 10.0 | mg/kg dry | 1 | EK51508 | 11/15/05 | 11/16/05 | EPA 8015M | |
| Diesel Range Organics >C12-C35 | ND | 10.0 | " | " | " | " | " | " | |
| Total Hydrocarbon C6-C35 | ND | 10.0 | " | " | " | " | " | " | |
| Surrogate: 1-Chlorooctane | | 117 % | 70-130 | | " | " | " | " | |
| Surrogate: 1-Chlorooctadecane | | 92.6 % | 70-130 | | " | " | " | " | |
| Backfill Comp. (5K14014-02) Soil | | | | | | | | | |
| Gasoline Range Organics C6-C12 | ND | 10.0 | mg/kg dry | 1 | EK51508 | 11/15/05 | 11/16/05 | EPA 8015M | |
| Diesel Range Organics >C12-C35 | ND | 10.0 | " | " | " | " | " | " | |
| Total Hydrocarbon C6-C35 | ND | 10.0 | " | " | " | " | " | " | |
| Surrogate: 1-Chlorooctane | | 111 % | 70-130 | | " | " | " | " | |
| Surrogate: 1-Chlorooctadecane | | 97.2 % | 70-130 | | " | " | " | " | |

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon

Fax: (505) 397-1471

Reported:
11/18/05 12:21

General Chemistry Parameters by EPA / Standard Methods
Environmental Lab of Texas

| Analyte | Result | Reporting Limit | Units | Dilution | Batch | Prepared | Analyzed | Method | Notes |
|--|--------|--------------------|-------|----------|---------|----------|----------|---------------|-------|
| Vert@ Source@ 12' (5K14014-01) Soil | | | | | | | | | |
| Chloride | 11.6 | 5.00 | mg/kg | 10 | EK51809 | 11/17/05 | 11/18/05 | EPA 300.0 | |
| % Moisture | 11.4 | 0.1 | % | 1 | EK51501 | 11/14/05 | 11/15/05 | % calculation | |
| Backfill Comp. (5K14014-02) Soil | | | | | | | | | |
| Chloride | 99.1 | 5.00 | mg/kg | 10 | EK51809 | 11/17/05 | 11/18/05 | EPA 300.0 | |
| % Moisture | 11.1 | 0.1 | % | 1 | EK51501 | 11/14/05 | 11/15/05 | % calculation | |

Environmental Lab of Texas

The results in this report apply to the samples analyzed in accordance with the samples received in the laboratory. This analytical report must be reproduced in its entirety, with written approval of Environmental Lab of Texas.

Page 3 of 6

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon

Fax: (505) 397-1471

Reported:
11/18/05 12:21

Organics by GC - Quality Control
Environmental Lab of Texas

| Analyte | Result | Reporting Limit | Units | Spike Level | Source Result | %REC | %REC Limits | RPD | RPD Limit | Notes |
|---------|--------|--------------------|-------|----------------|------------------|------|----------------|-----|--------------|-------|
|---------|--------|--------------------|-------|----------------|------------------|------|----------------|-----|--------------|-------|

Batch EK51508 - Solvent Extraction (GC)

Blank (EK51508-BLK1)

Prepared: 11/15/05 Analyzed: 11/16/05

| | | | | | | | | | | |
|--------------------------------|------|------|-----------|------|--|------|--------|--|--|--|
| Gasoline Range Organics C6-C12 | ND | 10.0 | mg/kg wet | | | | | | | |
| Diesel Range Organics >C12-C35 | ND | 10.0 | " | | | | | | | |
| Total Hydrocarbon C6-C35 | ND | 10.0 | " | | | | | | | |
| Surrogate: 1-Chlorooctane | 49.8 | | mg/kg | 50.0 | | 99.6 | 70-130 | | | |
| Surrogate: 1-Chlorooctadecane | 48.0 | | " | 50.0 | | 96.0 | 70-130 | | | |

LCS (EK51508-BS1)

Prepared: 11/15/05 Analyzed: 11/16/05

| | | | | | | | | | | |
|--------------------------------|------|------|-----------|------|--|------|--------|--|--|--|
| Gasoline Range Organics C6-C12 | 400 | 10.0 | mg/kg wet | 500 | | 80.0 | 75-125 | | | |
| Diesel Range Organics >C12-C35 | 514 | 10.0 | " | 500 | | 103 | 75-125 | | | |
| Total Hydrocarbon C6-C35 | 914 | 10.0 | " | 1000 | | 91.4 | 75-125 | | | |
| Surrogate: 1-Chlorooctane | 53.7 | | mg/kg | 50.0 | | 107 | 70-130 | | | |
| Surrogate: 1-Chlorooctadecane | 52.5 | | " | 50.0 | | 105 | 70-130 | | | |

Calibration Check (EK51508-CCV1)

Prepared: 11/15/05 Analyzed: 11/16/05

| | | | | | | | | | | |
|--------------------------------|------|--|-------|------|--|-----|--------|--|--|--|
| Gasoline Range Organics C6-C12 | 524 | | mg/kg | 500 | | 105 | 80-120 | | | |
| Diesel Range Organics >C12-C35 | 587 | | " | 500 | | 117 | 80-120 | | | |
| Total Hydrocarbon C6-C35 | 1110 | | " | 1000 | | 111 | 80-120 | | | |
| Surrogate: 1-Chlorooctane | 64.4 | | " | 50.0 | | 129 | 70-130 | | | |
| Surrogate: 1-Chlorooctadecane | 61.1 | | " | 50.0 | | 122 | 70-130 | | | |

Matrix Spike (EK51508-MS1)

Source: 5K14011-04

Prepared: 11/15/05 Analyzed: 11/16/05

| | | | | | | | | | | |
|--------------------------------|------|------|-----------|------|----|------|--------|--|--|--|
| Gasoline Range Organics C6-C12 | 432 | 10.0 | mg/kg dry | 571 | ND | 75.7 | 75-125 | | | |
| Diesel Range Organics >C12-C35 | 557 | 10.0 | " | 571 | ND | 97.5 | 75-125 | | | |
| Total Hydrocarbon C6-C35 | 989 | 10.0 | " | 1140 | ND | 86.8 | 75-125 | | | |
| Surrogate: 1-Chlorooctane | 56.0 | | mg/kg | 50.0 | | 112 | 70-130 | | | |
| Surrogate: 1-Chlorooctadecane | 52.9 | | " | 50.0 | | 106 | 70-130 | | | |

Matrix Spike Dup (EK51508-MSD1)

Source: 5K14011-04

Prepared: 11/15/05 Analyzed: 11/16/05

| | | | | | | | | | | |
|--------------------------------|------|------|-----------|------|----|------|--------|------|----|--|
| Gasoline Range Organics C6-C12 | 454 | 10.0 | mg/kg dry | 571 | ND | 79.5 | 75-125 | 4.97 | 20 | |
| Diesel Range Organics >C12-C35 | 583 | 10.0 | " | 571 | ND | 102 | 75-125 | 4.56 | 20 | |
| Total Hydrocarbon C6-C35 | 1040 | 10.0 | " | 1140 | ND | 91.2 | 75-125 | 5.03 | 20 | |
| Surrogate: 1-Chlorooctane | 57.9 | | mg/kg | 50.0 | | 116 | 70-130 | | | |
| Surrogate: 1-Chlorooctadecane | 53.9 | | " | 50.0 | | 108 | 70-130 | | | |

Environmental Lab of Texas

The results in this report apply to the samples analyzed in accordance with the samples received in the laboratory. This analytical report must be reproduced in its entirety, with written approval of Environmental Lab of Texas.

Page 4 of 6

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon

Fax: (505) 397-1471

Reported:
11/18/05 12:21

General Chemistry Parameters by EPA / Standard Methods - Quality Control
Environmental Lab of Texas

| Analyte | Result | Reporting Limit | Units | Spike Level | Source Result | %REC | %REC Limits | RPD | RPD Limit | Notes |
|---------|--------|--------------------|-------|----------------|------------------|------|----------------|-----|--------------|-------|
|---------|--------|--------------------|-------|----------------|------------------|------|----------------|-----|--------------|-------|

Batch EK51501 - General Preparation (Prep)

Blank (EK51501-BLK1)

Prepared: 11/14/05 Analyzed: 11/15/05

% Solids 100 %

Duplicate (EK51501-DUP1)

Source: 5K14002-01

Prepared: 11/14/05 Analyzed: 11/15/05

% Solids 78.8 % 79.9 1.39 20

Batch EK51809 - Water Extraction

Blank (EK51809-BLK1)

Prepared: 11/17/05 Analyzed: 11/18/05

Chloride ND 0.500 mg/kg

LCS (EK51809-BS1)

Prepared: 11/17/05 Analyzed: 11/18/05

Chloride 8.17 mg/L 10.0 81.7 80-120

Calibration Check (EK51809-CCV1)

Prepared: 11/17/05 Analyzed: 11/18/05

Chloride 8.38 mg/L 10.0 83.8 80-120

Duplicate (EK51809-DUP1)

Source: 5K14010-01

Prepared: 11/17/05 Analyzed: 11/18/05

Chloride 135 5.00 mg/kg 133 1.49 20

Environmental Lab of Texas

The results in this report apply to the samples analyzed in accordance with the samples received in the laboratory. This analytical report must be reproduced in its entirety, with written approval of Environmental Lab of Texas.

Page 5 of 6

Rice Operating Co.
122 W. Taylor
Hobbs NM, 88240

Project: Conoco St. A-2-2
Project Number: None Given
Project Manager: Roy Rascon


Fax: (505) 397-1471

Reported:
11/18/05 12:21

Notes and Definitions

DET Analyte DETECTED
ND Analyte NOT DETECTED at or above the reporting limit
NR Not Reported
dry Sample results reported on a dry weight basis
RPD Relative Percent Difference
LCS Laboratory Control Spike
MS Matrix Spike
Dup Duplicate

Report Approved By:



Date:

11/18/2005

Raland K. Tuttle, Lab Manager
Celey D. Keene, Lab Director, Org. Tech Director
Peggy Allen, QA Officer

Jeanne Mc Murrey, Inorg. Tech Director
La Tasha Cornish, Chemist
Sandra Sanchez, Lab Tech.

This material is intended only for the use of the individual (s) or entity to whom it is addressed, and may contain information that is privileged and confidential.

If you have received this material in error, please notify us immediately at 432-563-1800.

Environmental Lab of Texas

The results in this report apply to the samples analyzed in accordance with the samples received in the laboratory. This analytical report must be reproduced in its entirety, with written approval of Environmental Lab of Texas.

Page 6 of 6

Environmental Lab of Texas
Variance / Corrective Action Report – Sample Log-In

Client: Rice Op.
Date/Time: 11/11/05 17:30
Order #: 5K14017
Initials: CL

Sample Receipt Checklist

| | | | |
|---|-------------------------------------|----|----------------|
| Temperature of container/cooler? | Yes | No | -2.0 C |
| Shipping container/cooler in good condition? | <input checked="" type="checkbox"/> | No | |
| Custody Seals intact on shipping container/cooler? | <input checked="" type="checkbox"/> | No | Not present |
| Custody Seals intact on sample bottles? | <input checked="" type="checkbox"/> | No | Not present |
| Chain of custody present? | <input checked="" type="checkbox"/> | No | |
| Sample Instructions complete on Chain of Custody? | <input checked="" type="checkbox"/> | No | |
| Chain of Custody signed when relinquished and received? | <input checked="" type="checkbox"/> | No | |
| Chain of custody agrees with sample label(s) | <input checked="" type="checkbox"/> | No | |
| Container labels legible and intact? | <input checked="" type="checkbox"/> | No | |
| Sample Matrix and properties same as on chain of custody? | <input checked="" type="checkbox"/> | No | |
| Samples in proper container/bottle? | <input checked="" type="checkbox"/> | No | |
| Samples properly preserved? | <input checked="" type="checkbox"/> | No | |
| Sample bottles intact? | <input checked="" type="checkbox"/> | No | |
| Preservations documented on Chain of Custody? | <input checked="" type="checkbox"/> | No | |
| Containers documented on Chain of Custody? | <input checked="" type="checkbox"/> | No | |
| Sufficient sample amount for indicated test? | <input checked="" type="checkbox"/> | No | |
| All samples received within sufficient hold time? | <input checked="" type="checkbox"/> | No | |
| VOC samples have zero headspace? | <input checked="" type="checkbox"/> | No | Not Applicable |

Other observations:

Variance Documentation:

Contact Person: - _____ Date/Time: _____ Contacted by: _____
Regarding: _____

Corrective Action Taken:

122 WEST TAYLOR
HOBBS, NEW MEXICO 88240
PHONE: (505) 393-9174 FAX: (505) 397-1471
VOC FIELD TEST REPORT FORM
MINI RAE PLUS CLASSIC PHOTOIONIZATION GAS DETECTOR

MODEL NO: PGM 761S
CALIBRATION GAS
GAS COMPOSITION: ISOBUTYLENE
AIR
LOT NO: 05-2859
EXP. DATE: 11/19/07
METER READING
ACCURACY: 100.8

SERIAL NO: 104412

100 PPM
BALANCE
FILL DATE: 7/19/05
ACCURACY: ± 2%

| SYSTEM | JUNCTION | UNIT | SECTION | TOWNSHIP | RANGE |
|--------|-----------------------------|------|---------|----------|-------|
| EME | CONOCO STATE A-2A EOL | P | 2 | 20S | 37E |

VERT. @ SOURCE @

| SAMPLE | PID RESULT | SAMPLE | PID RESULT |
|--------|-------------------|--------|------------|
| 1 | 0.0 | | |
| 2 | 0.0 | | |
| 3 | 0.0 | | |
| 4 | 0.0 | | |
| 5 | 0.2 | | |
| 6 | 0.1 | | |
| 7 | 0.1 | | |
| 8 | 0.1 | | |
| 9 | 0.2 | | |
| 10 | 0.2 HC | | |
| 11 | 0.1 | | |
| 12 | 0.1 | | |

COPY

I certify that I have calibrated the above instrument in accordance to the manufacture operation manual.

Kevin O. Collins
Signature
Kevin O. Collins

11-9-05
Date