

OIL CONSERVATION DIVISION

P. O. BOX 2088

SANTA FE, NEW MEXICO 87501

Form C-103
Revised 10-1-78

NO. OF COPIES RECEIVED	
DISTRIBUTION	
SANTA FE	
FILE	☒
U.S.G.S.	
LAND OFFICE	
OPERATOR	

5a. Indicate Type of Lease	
State ☐	Fee ☒
5. State Oil & Gas Lease No.	

SUNDRY NOTICES AND REPORTS ON WELLS

(DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT -" (FORM C-101) FOR SUCH PROPOSALS.)

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐	7. Unit Agreement Name
2. Name of Operator PUBLIC LANDS EXPLORATION COMPANY, INC.	8. Farm or Lease Name JEANNE
3. Address of Operator 4835 LBJ FREEWAY, SUITE 635, DALLAS, TEXAS 75234	9. Well No. 3
4. Location of Well UNIT LETTER <u>C</u> <u>800</u> FEET FROM THE <u>North</u> LINE AND <u>2310</u> FEET FROM THE <u>West</u> LINE, SECTION <u>17</u> TOWNSHIP <u>11N</u> RANGE <u>26E</u> NMPM.	10. Field and Pool, or Wildcat Wildcat
15. Elevation (Show whether DF, RT, GR, etc.) 4771.0' GR	12. County Guadalupe

Check Appropriate Box To Indicate Nature of Notice, Report or Other Data
NOTICE OF INTENTION TO:


SUBSEQUENT REPORT OF:

PERFORM REMEDIAL WORK ☐	PLUG AND ABANDON ☐	REMEDIAL WORK ☐	ALTERING CASING ☐
TEMPORARILY ABANDON ☐	CHANGE PLANS ☐	COMMENCE DRILLING OPNS. ☒	PLUG AND ABANDONMENT ☐
PULL OR ALTER CASING ☐	OTHER ☐	CASING TEST AND CEMENT JOB ☒	OTHER ☐

17. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 1103.

Spudded 11" hole at 9:45 a.m. 5/19/81 (TD 27.5'). Ran 27.75' of 8 5/8" 23# J-55 casing and cemented with 7 sacks of neat cement from TD to surface. Drilled well to 875' TD with a 7 7/8" bit. Ran 844' of 4 1/2" 11.6 #J-55 casing. Centralizers installed at 830' 785', 744' and at 681'. Cemented well as follows: Pumped 40 bbls of gelled 5% KCl water containing 2 gallons of marflo and followed with 5 bbls of fresh water. Pumped 160 sacks of class "H" cement containing 0.5% Halad-9 and followed with 160 sacks of class "H" cement containing 2% calcium chloride. Circulated cement.

Cored well as follows: 700' - 727'; 727' - 753'; 753' - 778'; 778' - 805' and 805' - 830'.



18. I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNED Charles C Joy TITLE Agent DATE 9/30/81

APPROVED BY Carl Miller TITLE REGISTER DATE 10-9-81

CONDITIONS OF APPROVAL, IF ANY: