

7. Expected Bottom Hole Pressure and Potential Hazards

- a. EXPECTED BHP: 1600 psi.
- b. Anticipated abnormal temperatures: We do not expect to encounter any abnormal temperatures.
- c. Hydrogen sulfide potential: This test is not expected to penetrate any formation containing hydrogen sulfide in hazardous quantities; however, precautions for H₂S will be taken.

8. Duration of Operations

Location building operations are anticipated to take one week. Drilling operations are expected to take fifteen (15) days (including P & A operations). Completion and testing operations (hopefully needed) are anticipated to take approximately thirty (30) days.