Form 3160-5 (June 2015)

### OCD - Artesia - REC'D 6/11/2020

**UNITED STATES** DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED OMB NO. 1004-0137 Expires: January 31, 2018

# 5. Lease Serial No. NMLC061705B

**SUNDRY NOTICES AND REPORTS ON WELLS** 

Do not use thi	ia farm far prapasala ta drill ar ta	va antav an			
abandoned wel	is form for proposals to drill or to II. Use form 3160-3 (APD) for sucl	h proposals.		6. If Indian, Allottee or Tri	be Name
SUBMIT IN T	TRIPLICATE - Other instructions of	on page 2		7. If Unit or CA/Agreemer 891000303X	nt, Name and/or No.
1. Type of Well				8. Well Name and No. POKER LAKE UNIT 1	7 TWR 707H
Oil Well Gas Well Oth  Name of Operator	Contact: KELLY KA	PDOS		9. API Well No.	
XTO PERMIAN OPERATING				30-015-46659-00-X	1
3a. Address 6401 HOLIDAY HILL ROAD B MIDLAND, TX 79707		No. (include area code) 620-4374		10. Field and Pool or Explo PURPLE SAGE WOL	•
4. Location of Well (Footage, Sec., T.	., R., M., or Survey Description)			11. County or Parish, State	;
Sec 20 T24S R31E NENE 95F 32.209824 N Lat, 103.794640				EDDY COUNTY, N	M
12. CHECK THE AF	PPROPRIATE BOX(ES) TO INDIC	CATE NATURE OF	F NOTICE, I	REPORT, OR OTHER	DATA
TYPE OF SUBMISSION		TYPE OF	ACTION		
	☐ Acidize ☐ D	eepen	☐ Production	on (Start/Resume)	Water Shut-Off
■ Notice of Intent	☐ Alter Casing ☐ H	ydraulic Fracturing	☐ Reclamat	ion	Well Integrity
☐ Subsequent Report	☐ Casing Repair ☐ N	ew Construction	☐ Recomple	ete 🛭 🗷	Other
☐ Final Abandonment Notice	☐ Change Plans ☐ P	lug and Abandon	☐ Temporar		hange to Original A
	☐ Convert to Injection ☐ P	lug Back	■ Water Di		_
Attach the Bond under which the wor following completion of the involved testing has been completed. Final Abdetermined that the site is ready for fix XTO Permian Operating, LLC, Casing/Cement design per the Change BHL from 2440FNL & Change formation from Wildca XTO also requests the following	requests permission to make the fore attached drilling program. 990FEL in Sec. 32-T24S-R31E to 2 at Bone Spring (oil) to Purple Sage Ving variances: ig to pre-set surface casing per the a	on file with BLM/BIA tiple completion or recould requirements, including the second sec	. Required subsimpletion in a neing reclamation, the original A	equent reports must be filed w interval, a Form 3160-4 in have been completed and the APD:	l within 30 days nust be filed once
14. Thereby certify that the folegoing is	Electronic Submission #518137 veri For XTO PERMIAN OPERA	fied by the BLM Well TING LLC, sent to the	I Information : he Carlsbad	System	
	nmitted to AFMSS for processing by P		-		
Name(Printed/Typed) KELLY KA	ARDOS	Title REGUL	ATORY COC	RDINATOR	
Signature (Electronic S	Submission)	Date 06/08/20	020		
	THIS SPACE FOR FEDER	RAL OR STATE (	OFFICE US	E	
Approved By JENNIFER SANCHE	<u>z </u>	TitlePETROLE	UM ENGINE	ER	Date 06/11/2020
Conditions of approval, if any, are attached certify that the applicant holds legal or equivalent would entitle the applicant to condu	d. Approval of this notice does not warrant of itable title to those rights in the subject lease act operations thereon.	Office Carlsbac	t		
	U.S.C. Section 1212, make it a crime for any statements or representations as to any matter		willfully to mak	e to any department or ager	ncy of the United

### Additional data for EC transaction #518137 that would not fit on the form

### 32. Additional remarks, continued

Batch drill this well if necessary. In doing so, XTO will set each casing string and ensure that the well is cemented properly and the well is static. With floats holding, no pressure on the csg annulus, and the installation of a 10K TA cap as per GE recommendations, XTO will contact the BLM to skid the rig to drill the remaining wells on the pad. Once surface and intermediate strings are all completed, XTO will begin drilling the production hole on each of the wells.

ONLY test broken pressure seals on the BOP equipment per the attached procedure.

Attachments: C102 & Supplement Drilling Program Multibowl Diagram Spudder Rig Description of Operations BOP Break Test Procedure

### Revisions to Operator-Submitted EC Data for Sundry Notice #518137

**Operator Submitted BLM Revised (AFMSS)** 

APDCH **APDCH** Sundry Type: NOI NOI

NMLC061705B Lease: NMLC061705B

Agreement: NMNM71016X 891000303X (NMNM71016X)

XTO PERMIAN OPERATING LLC 6401 HOLIDAY HILL ROAD BLDG 5 MIDLAND, TX 79707 Ph: 432.683 2277 Operator:

XTO PERMIAN OPERATING LLC 6401 HOLIDAY HILL RD BLDG 5 MIDLAND, TX 79707 Ph: 432-620-4374

**KELLY KARDOS** Admin Contact:

KELLY KARDOS REGULATORY COORDINATOR REGULATORY COORDINATOR E-Mail: kelly\_kardos@xtoenergy.com E-Mail: kelly\_kardos@xtoenergy.com

Ph: 432-620-4374 Ph: 432-620-4374

Tech Contact:

KELLY KARDOS REGULATORY COORDINATOR KELLY KARDOS REGULATORY COORDINATOR E-Mail: kelly\_kardos@xtoenergy.com E-Mail: kelly\_kardos@xtoenergy.com

Ph: 432-620-4374 Ph: 432-620-4374

Location:

NM EDDY State: NM County: **EDDY** 

Field/Pool: WILDCAT BONE SPRING PURPLE SAGE WOLFCAMP

POKER LAKE UNIT 17 TWR 707H POKER LAKE UNIT 17 TWR 707H Well/Facility:

Sec 20 T24S R31E Mer NMP NENE 95FNL 1035FEL Sec 20 T24S R31E NENE 95FNL 1035FEL 32.209824 N Lat, 103.794640 W Lon

# PECOS DISTRICT DRILLING DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME: LEASE NO.: NMLC-0061705B
WELL NAME & NO.: Poker Lake Unit 17 TWR 707H
SURFACE HOLE FOOTAGE: 0095' FNL & 1035' FEL
BOTTOM HOLE FOOTAGE 0220' FSL & 1155' FEL Sec. 29, T. 24 S., R 31 E.
LOCATION: Section 20, T. 24 S., R 31 E., NMPM

**COUNTY:** Eddy County, New Mexico

COA

H2S	• Yes	C No	
Potash	None	Secretary	© R-111-P
Cave/Karst Potential	• Low	Medium	C High
Cave/Karst Potential	Critical		
Variance	O None	© Flex Hose	Other
Wellhead	Conventional	© Multibowl	O Both
Other	☐4 String Area	☐ Capitan Reef	□WIPP
Other	☐ Fluid Filled	☐ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	□ СОМ	✓ Unit

Possibility of water flows in the Salado and Castile.

Possibility of lost circulation in the Red Beds, Rustler, and Delaware.

Abnormal pressure may be encountered in the 3rd Bone Spring and all subsequent formations.

### A. HYDROGEN SULFIDE

1. Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

### **B. CASING**

- 1. The 11-3/4 inch surface casing shall be set at approximately 872 feet (a minimum of 70 feet (Eddy County) into the Rustler Anhydrite and above the salt) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job will be a minimum of **8** hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the **7-5/8** inch intermediate casing is:
  - Cement as proposed. Report Echo meter results on subsequent sundry. Excess calculates to 19% Additional cement may be required.
- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
  - Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification.

### C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).

- 2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000** (**5M**) psi.
  - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
  - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
  - c. Manufacturer representative shall install the test plug for the initial BOP test.
  - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
  - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

## **BOP Break Testing Variance**

- Shelll testing is not approved for any portion of the hole with a MASP of 5000 psi or greater.
- While in transfer between wells, the BOPE shall be secured by the hydraulic carrier or cradle.
- Any well control event while drilling require notification to the BLM Petroleum Engineer prior to the commencement of any BOP Break Testing operations.
- A full BOP test is required prior to drilling the first deep intermediate hole section. If any subsequent hole interval is deeper than the first, a full BOP test will be required.

# D. SPECIAL REQUIREMENTS

## **Unit Wells**

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

# **Commercial Well Determination**

A commercial well determination shall be submitted after production has been established for at least six months.

# GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)
  - Eddy County
    Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822
- 1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
  - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
  - b. When the operator proposes to set surface casing with Spudder Rig
    - Notify the BLM when moving in and removing the Spudder Rig.
    - Notify the BLM when moving in the 2<sup>nd</sup> Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
    - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
- 2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

### A. CASING

- 1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
- 2. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.
- 3. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
- 4. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
- 5. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- 6. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

### B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

- 2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
- 3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
- 5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - d. The results of the test shall be reported to the appropriate BLM office.

- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

### C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

### D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

### JAM 06112020

### District I

1625 N. French Dr., Hobbs, NM 88240 Phone: (575) 393-6161 Fax: (575) 393-0720 District II

811 S. First St., Artesia, NM 88210 Phone: (575) 748-1283 Fax: (575) 748-9720

District III

1000 Rio Brazos Road, Aztec, NM 87410 Phone: (505) 334-6178 Fax: (505) 334-6170 District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505 Phone: (505) 476-3460 Fax: (505) 476-3462

# State of New Mexico

# Energy, Minerals & Natural Resources Department OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe, NM 87505

Form C-102 Revised August 1, 2011 Submit one copy to appropriate District Office

AMENDED REPORT

### WELL LOCATION AND ACREAGE DEDICATION PLAT


<sup>1</sup> API Numbe	er	:	<sup>2</sup> Pool Code	<sup>3</sup> Pool Name					
30-015-2	46659	98220		PURPLE SAGE; WOLFCAMP					
<sup>4</sup> Property Code <sup>5</sup> Pr				operty Name	<sup>6</sup> Well Number				
			POKER LA	AKE UNIT 17 TWR	707H				
<sup>7</sup> OGRID No.			8 OI	perator Name	<sup>9</sup> Elevation				
373075			XTO PERMIA	AN OPERATING, LLC. 3,52					

### <sup>10</sup> Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	North/South line Feet from the Ea		County					
A	20	24 S	31 E		95	NORTH	1,035	EAST	EDDY					
<sup>11</sup> Bottom Hole Location If Different From Surface														
UL or lot no. Section Township Range Lot Idn Feet from the						North/South line	Feet from the	County						
P	29	24 S	31 E		220	SOUTH	1,155	EAST	EDDY					

12 Dedicated Acres | 13 Joint or Infill | 14 Consolidation Code | 15 Order No. | 640

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



Inten	t X	As Dril	led												
API #	)15-466														
Ope	rator Nai		ERATIN	G, LL	C		erty N KER L			T 17	7 TW	'R		Well Number 707H	
Kick C	Off Point	(KOP)													
UL A	Section 20	Township 24S	Range 31E	Lot	Feet 95		From N		Feet 1035	;	From	n E/W ST	County EDDY		
132.2	<sup>ide</sup> 209822	<u> </u>	l		Longitu -103		641		l				NAD 83		
		. /===:			•										
First 1	Section	t (FTP)	Range	Lot	Feet		From N	1/S	Feet		Fron	n E/W	County		
A Latitu	20	24S	31E		330 Longitu		NOR		1155	j	EAS		EDDY NAD		
32.2	209051				-103.		544						83		
Last T	ake Poin	t (LTP)													
UL P	Section 29	Township 24S	Range 31E	Lot	Feet 330		m N/S UTH	Feet		From EAS		Count			
Latitu 32.2	ide 209822	2			Longitu	ıde						NAD 83	IAD		
Ic thic	wall the	defining v	vell for th	a Hori:	zontal Sr	nacino	ı Unit?	Г	N						
13 (1113	Well tile	. acming v	ven for th	C 110112	zontai S <sub>i</sub>	pacing	5 Ome:	Ľ	•						
Is this	well an	infill well?		Υ											
	l is yes p ng Unit.	lease prov	ide API if	availab	ole, Opei	rator	Name	and v	vell nu	ımbe	r for I	Definir	ng well fo	r Horizontal	
API #	)15-466	 356													
	rator Nai	me: IIAN OPI	ERATIN	G, LL	C		erty N KER L			T 17	7 TW	'R		Well Number 127H	

### Poker Lake Unit 17 TWR 707H

Projected TD: 21818' MD / 11792' TVD SHL: 95' FNL & 1035' FEL , Section 20, T24S, R31E BHL: 220' FSL & 1155' FEL, Section 29, T24S, R31E Eddy County, NM

### **Casing Design**

The surface fresh water sands will be protected by setting 11-3/4" casing @ 872' (100' above the salt) and circulating cement back to surface. The 7-5/8" intermediate casing will be set at 10961' and bring TOC back to surface. A 6-3/4 inch curve and lateral hole will be drilled to MD/TD and 5-1/2" x 5-1/2" semi-flush casing will be set at TD and cemented back 300' into the 7-5/8" casing shoe.

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
14-3/4"	0' - 872'	11-3/4"	54	втс	J-55	New	1.31	5.25	18.05
9-7-8"	0' - 10961'	7-5/8"	29.7	втс	HCL-80	New	1.59	2.09	2.10
6-3/4"	0' - 10861'	5-1/2"	23	FreedomHT Q	RYP-110	New	1.21	2.10	2.04
6-3/4"	10861' - 21818'	5-1/2"	23	EagleSFH	RYP-110	New	1.21	2.10	2.04

XTO requests to not utilize centralizers in the curve and lateral

7-5/8" Collapse analyzed using 50% evacuation based on regional experience.

5-1/2'' Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35

Test on Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less

5-1/2" 23 ppf casing will be run from surface to 10,861' and crossed over to 5-1/2" 23 ppf semi-flush casing from 10,861' to TD.

Request to use 5" BTC Float equipment for the the production casing

### WELLHEAD:

Permanent Wellhead - Multibowl System

A. Starting Head: 13-5/8" 10M top flange x 11-3/4" Hanger

B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange

Wellhead will be installed by manufacturer's representatives.

Manufacturer will monitor welding process to ensure appropriate temperature of seal.

Operator will test the 7-5/8" casing per Onshore Order 2.

Wellhead manufacturer representative may not be present for BOP test plug installation

### **Cement Program**

### Surface Casing:

Lead: 260 sxs Halcem-C + 2% CaCl (mixed at 12.8 ppg, 1.87 ft3/sx, 10.13 gal/sx water) Tail: 190 sxs Halcem-C + 2% CaCl (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water) Compressives: 12-hr = 900 psi 24 hr = 1500 psi

### **Intermediate Casing:**

Tail: 880 sxs Halcem - Class C (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water) Compressives: 12-hr = 900 psi 24 hr = 1150 psi

### 2nd Stage

Tail: 1310 sxs Halcem-Class C (mixed at 14.8 ppg, 1.33 ft3/sx, 5.29 gal/sx water) Compressives: 12-hr = 900 psi 24 hr = 1150 psi

XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brush Canyon (6,510') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If necessary, a top out consisting of 1,500 sack of Class C cement + 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. The final cement top will be verified by Echo-meter.

XTO will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

### **Production Casing:**

Lead: 20 sxs VersaCem (mixed at 11.5 ppg, 2.69 ft3/sx, 15.00 gal/sx water) Tail: 760 sxs VersaCem (mixed at 13.2 ppg, 1.51 ft3/sx, 7.20 gal/sx water) 24 hr = 1500psi Compressives: 12-hr = izg 008

### **Mud Circulation Program**

INTERVAL	Hole Size	Mud Type	MW (ppg)	Viscosity (sec/qt)	Fluid Loss (cc)
0' - 872'	14-3/4"	FW / Native	8.4-8.8	35-40	NC
872' - 10961'	9-7/8"	Brine / Cut Brine / Direct Emuslion	8.3-9.5	30-32	NC
10961' to 21818'	6-3/4"	Cut Brine / WBM / OBM	10.8-11.8	32-36	NC

# DRILLING PLAN: BLM COMPLIANCE (Supplement to BLM 3160-3)

XTO Energy Inc.
Poker Lake Unit 17 TWR 707H
Projected TD: 21818' MD / 11792' TVD
SHL: 95' FNL & 1035' FEL , Section 20, T24S, R31E
BHL: 220' FSL & 1155' FEL , Section 29, T24S, R31E
Eddy County, NM

### 1. Geologic Name of Surface Formation

A. Permian

### 2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas

Formation	Well Depth (TVD)	Water/Oil/Gas
Rustler	602'	Water
Top of Salt	972'	Water
Base of Salt	4102'	Water
Delaware	4322'	Water
Bone Spring	8172'	Water
1st Bone Spring Ss	9242'	Water/Oil/Gas
2nd Bone Spring Ss	9952'	Water/Oil/Gas
3rd Bone Spring Ss	11122'	Water/Oil/Gas
Wolfcamp	11522'	Water/Oil/Gas
Wolfcamp X	11607'	Water/Oil/Gas
Target/Land Curve	11792'	Water/Oil/Gas

<sup>\*\*\*</sup> Hvdrocarbons @ Brushv Canvon

No other formations are expected to yield oil, gas or fresh water in measurable volumes. The surface fresh water sands will be protected by setting 11-3/4" casing @ 872' (100' above the salt) and circulating cement back to surface. The 7-5/8" intermediate casing will be set at 10961' and bring TOC back to surface. A 6-3/4 inch curve and lateral hole will be drilled to MD/TD and 5-1/2"  $\times$  5-1/2" semi-flush casing will be set at TD and cemented back 300' into the 7-5/8" casing shoe.

### 3. Casing Design

Hole Size	Depth	OD Csg	Weight	Collar	Grade	New/Used	SF Burst	SF Collapse	SF Tension
14-3/4"	0' - 872'	11-3/4"	54	ВТС	J-55	J-55 New		5.25	18.05
9-7-8"	0' – 10961'	7-5/8"	29.7	BTC	HCL-80	New	1.59	2.09	2.10
6-3/4"	0' – 10861'	5-1/2"	23	FreedomHTQ	RYP-110	New	1.21	2.10	2.04
6-3/4"	10861' - 21818'	5-1/2"	23	EagleSFH	RYP-110	New	1.21	2.10	2.04

- $\cdot$  XTO requests to not utilize centralizers in the curve and lateral
- ·7-5/8" Collapse analyzed using 50% evacuation based on regional experience.
- $\cdot$  5-1/2" Tension calculated using vertical hanging weight plus the lateral weight multiplied by a friction factor of 0.35
- · Test on Casing will be limited to 70% burst of the casing or 1500 psi, whichever is less
- 5-1/2" 23 ppf casing will be run from surface to 10,861 and crossed over to 5-1/2" 23 ppf semi-flush casing from 10,861 to TD. Request to use 5" BTC Float equipment for the the production casing

### Wellhead:

Permanent Wellhead - Multibowl System

- A. Starting Head: 13-5/8" 10M top flange x 11-3/4" Hanger
- B. Tubing Head: 13-5/8" 10M bottom flange x 7-1/16" 15M top flange
  - · Wellhead will be installed by manufacturer's representatives.
  - · Manufacturer will monitor welding process to ensure appropriate temperature of seal.
  - Operator will test the 7-5/8" casing per BLM Onshore Order 2
  - · Wellhead Manufacturer representative will not be present for BOP test plug installation

<sup>\*\*\*</sup> Groundwater depth 40' (per NM State Engineers Office).

### 4. Cement Program

### Surface Casing: 11-3/4", 54 New J-55, BTC casing to be set at +/- 872'

Lead: 260 sxs Halcem-C + 2% CaCl (mixed at 12.8 ppg, 1.87 ft3/sx, 10.13 gal/sx water)

Tail: 190 sxs Halcem-C + 2% CaCl (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

Compressives: 12-hr = 900 psi 24 hr = 1500 psi

TOC: Surface

### Intermediate Casing: 7-5/8", 29.7 New HCL-80, BTC casing to be set at +/- 10961'

1st Stage

Tail: 880 sxs Halcem - Class C (mixed at 14.8 ppg, 1.35 ft3/sx, 6.39 gal/sx water)

Compressives: 12-hr = 900 psi 24 hr = 1150psi

TOC: Brushy Canyon (6,510')

### 2nd Stage

Tail: 1310 sxs Halcem-Class C (mixed at 14.8 ppg, 1.33 ft3/sx, 5.29 gal/sx water)

Compressives: 12-hr = 900 psi 24 hr = 1150 psi

TOC: Surface

XTO requests to pump a two stage cement job on the 7-5/8" intermediate casing string with the first stage being pumped conventionally with the calculated top of cement at the Brush Canyon (6,510') and the second stage performed as a bradenhead squeeze with planned cement from the Brushy Canyon to surface. If necessary, a top out consisting of 1,500 sack of Class C cement + 3% Salt + 1% PreMag-M + 6% Bentonite Gel (2.30 yld, 12.91 ppg) will be executed as a contingency. The final cement top will be verified by Echo-meter.

XTO will include the Echo-meter verified fluid top and the volume of displacement fluid above the cement slurry in the annulus in all post-drill sundries on wells utilizing this cement program.

XTO will report to the BLM the volume of fluid (limited to 5 bbls) used to flush intermediate casing valves following backside cementing procedures.

### Production Casing: 5-1/2", 23 New RYP-110, EagleSFH casing to be set at +/- 21818'

Lead: 20 sxs VersaCem (mixed at 11.5 ppg, 2.69 ft3/sx, 15.00 gal/sx water)

Tail: 760 sxs VersaCem (mixed at 13.2 ppg, 1.51 ft3/sx, 7.20 gal/sx water)

Compressives 12-hr = 800 psi 24 hr = 1500 psi

TOC: 300' inside previous shoe

### 5. Pressure Control Equipment

Once the permanent WH is installed on the 11-3/4" casing, the blow out preventer equipment (BOP) will consist of a 13-5/8" minimum 5M Hydril and a 13-5/8" minimum 5M 3-Ram BOP. MASP should not exceed 4335 psi. In any instance where 10M BOP is required by BLM, XTO requests a variance to utilize 5M annular with 10M ram preventers (a common BOP configuration, which allows use of 10M rams in unlikely event that pressures exceed 5M). Also a variance is requested to test the 5M annular to 70% of working pressure at 3500 psi.

All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 70% of the working pressure. When nippling up on the 11-3/4", 5M bradenhead and flange, the BOP test will be limited to 5000 psi. All BOP tests will include a low pressure test as per BLM regulations. The 5M BOP diagrams are attached. Blind rams will be functioned tested each trip, pipe rams will be functioned tested each day.

A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors.

XTO requests a variance to be able to batch drill this well if necessary. In doing so, XTO will set each casing string and ensure that the well is cemented properly and the well is static. With floats holding, no pressure on the csg annulus, and the installation of a 10K TA cap as per wellhead company recommendations, XTO will contact the BLM on each rig skid on the pad. Once surface and intermediate strings are all completed, XTO will begin drilling the production hole on each of the wells.

A variance is requested to ONLY test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- 1. After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the had will be the deenest. All of the remaining hole sections will be the same

2. The first intermediate hole section unlied on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.

3. Full BOP test will be required prior to drilling the production hole.

A variance is requested to cement offline for the surface and intermediate casing strings.

### 6. Proposed Mud Circulation System

INTERVAL	Hole Size	Mud Type	MW (ppg)	Viscosity (sec/qt)	Fluid Loss (cc)
0' - 872'	14-3/4"	FW / Native	8.4-8.8	35-40	NC
872' - 10961'	9-7/8"	Brine / Cut Brine / Direct Emuslion	8.3-9.5	30-32	NC
10961' to 21818'	Cut B 6-3/4" WBI OB		10.8-11.8	32-36	NC

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Spud with fresh water/native mud and set 11-3/4" surface casing, isolating the fresh water aquifer. Drill out from under 11-3/4" surface casing with a brine/oil direct emulsion mud system. Use fibrous materials as needed to control seepage and lost circulation. Pump viscous sweeps as needed for hole cleaning. Pump speed will be recorded on a daily drilling report after mudding up. A Pason or Totco will be used to detect changes in loss or gain of mud volume. A mud test will be performed every 24 hours to determine: density, viscosity, strength, filtration and pH as necessary. Use available solids controls equipment to help keep mud weight down after mud up. Rig up solids control equipment to operate as a closed loop system.

### 7. Auxiliary Well Control and Monitoring Equipment

- A. A Kelly cock will be in the drill string at all times.
- B. A full opening drill pipe stabbing valve having appropriate connections will be on the rig floor at all times.
- C. H2S monitors will be on location when drilling below the 11-3/4" casing.

### 8. Logging, Coring and Testing Program

Mud Logger: Mud Logging Unit (2 man) below intermediate casing.


Open hole logging will not be done on this well.

### 9. Abnormal Pressures and Temperatures / Potential Hazards

None Anticipated. BHT of 155 to 175 F is anticipated. No H2S is expected but monitors will be in place to detect any H2S occurrences. Should these circumstances be encountered the operator and drilling contractor are prepared to take all necessary steps to ensure safety of all personnel and environment. Lost circulation could occur but is not expected to be a serious problem in this area and hole seepage will be compensated for by additions of small amounts of LCM in the drilling fluid. The maximum anticipated bottom hole pressure for this well is 6929 psi.

### 10. Anticipated Starting Date and Duration of Operations

Road and location construction will begin after Santa Fe and BLM have approved the APD. Anticipated spud date will be as soon after Santa Fe and BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 45 days. If production casing is run, an additional 30 days will be needed to complete well and construct surface facilities and/or lay flow lines in order to place well on production.



DRILLING SKID COMPLETION

ALL DIMENSIONS APPROXIMATE

CACTUS WELLHEAD LLC	XTO ENERGY INC POKER LAKE, NM			
30" x 11-3/4" x 7-5/8" x 5-1/2" MBU-3T-SF SOW Wellhead System	DRAWN	DLE	09DEC19	
	APPRV			
With 13-5/8" 10M x 7-1/16" 15M CTH-DBLHPS-SB Tubing Head		005000	0004	
And 7-5/8" & 5-1/2" Fluted Mandrel Casing Hangers	DRAWING N	o. <b>ODE000</b>	3261	

INFORMATION CONTAINED HEREIN IS THE PROPERTY OF CACTUS WELLHEAD, LLC. REPRODUCTION, DISCLOSURE, OR USE THEREOF IS PERMISSIBLE ONLY AS PROVIDED BY CONTRACT OR AS EXPRESSLY AUTHORIZED BY CACTUS WELLHEAD, LLC.



### XTO Poker Lake Unit 17 TWR 707H Rev0 LP 02Jun20 Proposal Geodetic Report



(Def Plan)

June 03, 2020 - 10:53 AM Report Date: Client:

Field:

XTO Energy NM Eddy County (NAD 27) XTO Poker Lake Unit 17 TWR 707H / XTO Poker Lake Unit 17 TWR

Structure / Slot:

Well: XTO Poker Lake Unit 17 TWR 707H XTO Poker Lake Unit 17 TWR 707H

Borehole: UWI / API#:

Unknown / Unknown

Survey Name: Survey Date: XTO Poker Lake Unit 17 TWR 707H Rev0 LP 02Jun20 June 02, 2020

Tort / AHD / DDI / ERD Ratio: 100.007 ° / 10421.735 ft / 6.285 / 0.884

Coordinate Reference System: NAD27 New Mexico State Plane, Eastern Zone, US Feet

Location Lat / Long: Location Grid N/E Y/X: N 32° 12' 34.91337", W 103° 47' 38.96824" N 440425.900 ftUS, E 666761.100 ftUS

0.2874 ° 0.99994094 CRS Grid Convergence Angle: **Grid Scale Factor:** Version / Patch: 2.10.811.0

Survey / DLS Computation: Minimum Curvature / Lubinski Vertical Section Azimuth: Vertical Section Origin: 179.650 ° (Grid North) 0.000 ft, 0.000 ft

TVD Reference Datum:

TVD Reference Elevation: 3552.000 ft above MSL 3522.000 ft above MSL Seabed / Ground Elevation:

Magnetic Declination:

6.646 ° 998.4270mgn (9.80665 Based) Total Gravity Field Strength: Gravity Model: GARM

47791.410 nT 59.871 ° Total Magnetic Field Strength: Magnetic Dip Angle: June 02, 2020 HDGM 2020 Declination Date:
Magnetic Declination Model: Grid North 0.2874 ° North Reference: Grid Convergence Used: Total Corr Mag North->Grid

6.3587° North: Local Coord Referenced To: Well Head

0		(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(ftUS)	Easting (ftUS)	(N/S ° ' ")	Longitude (E/W ° ' ")
Surface	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	440425.90			W 103 47 38.97
	100.00	0.00	290.14	100.00	0.00	0.00	0.00	0.00	440425.90		N 32 12 34.91	
	200.00 300.00	0.00	290.14 290.14	200.00 300.00	0.00 0.00	0.00	0.00	0.00	440425.90 440425.90		N 32 12 34.91 N 32 12 34.91	W 103 47 38.97 W 103 47 38.97
	400.00	0.00	290.14	400.00	0.00	0.00	0.00	0.00	440425.90			W 103 47 38.97 W 103 47 38.97
	500.00	0.00	290.14	500.00	0.00	0.00	0.00	0.00	440425.90			W 103 47 38.97
	600.00	0.00	290.14	600.00	0.00	0.00	0.00	0.00	440425.90	666761.10	N 32 12 34.91	W 103 47 38.97
Magenta Dolomite	672.00	0.00	290.14	672.00	0.00	0.00	0.00	0.00	440425.90	666761.10	N 32 12 34.91	W 103 47 38.97
Dolomike	700.00	0.00	290.14	700.00	0.00	0.00	0.00	0.00	440425.90	666761.10	N 32 12 34.91	W 103 47 38.97
	800.00	0.00	290.14	800.00	0.00	0.00	0.00	0.00	440425.90	666761.10	N 32 12 34.91	W 103 47 38.97
T O. #	900.00	0.00	290.14	900.00	0.00	0.00	0.00	0.00	440425.90		N 32 12 34.91	
Top Salt	<i>972.00</i> 1000.00	0.00 0.00	290.14 290.14	972.00 1000.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	440425.90 440425.90		N 32 12 34.91 N 32 12 34.91	
	1100.00	0.00	290.14	1100.00	0.00	0.00	0.00	0.00	440425.90		N 32 12 34.91	
	1200.00	0.00	290.14	1200.00	0.00	0.00	0.00	0.00	440425.90		N 32 12 34.91	
	1300.00	0.00	290.14	1300.00	0.00	0.00	0.00	0.00	440425.90			W 103 47 38.97
N. J., B. 2.1	1400.00	0.00	290.14	1400.00	0.00	0.00	0.00	0.00	440425.90	666761.10	N 32 12 34.91	W 103 47 38.97
Nudge, Build 2°/100' DLS	1500.00	0.00	290.14	1500.00	0.00	0.00	0.00	0.00	440425.90		N 32 12 34.91	
	1600.00	2.00 4.00	290.14	1599.98	-0.61 -2.44	0.60 2.40	-1.64	2.00 2.00	440426.50			W 103 47 38.99
Hold	1700.00 1750.14	4.00 5.00	290.14 290.14	1699.84 1749.82	-2.44 -3.82	2.40 3.76	-6.55 -10.25	2.00	440428.30 440429.66			W 103 47 39.04 W 103 47 39.09
riold	1800.00	5.00	290.14	1799.49	-5.34	5.25	-14.33	0.00	440431.15			W 103 47 39.13
	1900.00	5.00	290.14	1899.11	-8.39	8.26	-22.52	0.00	440434.16			W 103 47 39.23
	2000.00	5.00	290.14	1998.73	-11.45	11.26	-30.70	0.00	440437.16			W 103 47 39.32
	2100.00	5.00	290.14	2098.35	-14.50	14.26	-38.89	0.00	440440.16			W 103 47 39.42
	2200.00	5.00	290.14	2197.97	-17.55	17.26	-47.08	0.00	440443.16			W 103 47 39.52
	2300.00 2400.00	5.00 5.00	290.14 290.14	2297.59 2397.21	-20.60 -23.65	20.26 23.27	-55.27 -63.45	0.00 0.00	440446.16 440449.16		N 32 12 35.12 N 32 12 35.15	W 103 47 39.61 W 103 47 39.71
	2500.00	5.00	290.14	2496.83	-26.71	26.27	-71.64	0.00	440452.17	666689.46	N 32 12 35.15 N 32 12 35 18	W 103 47 39.80
	2600.00	5.00	290.14	2596.44	-29.76	29.27	-79.83	0.00	440455.17			W 103 47 39.90
	2700.00	5.00	290.14	2696.06	-32.81	32.27	-88.02	0.00	440458.17			W 103 47 39.99
	2800.00	5.00	290.14	2795.68	-35.86	35.27	-96.20	0.00	440461.17			W 103 47 40.09
D 00 (400)	2900.00	5.00	290.14	2895.30	-38.91	38.28	-104.39	0.00	440464.17	666656.72	N 32 12 35.30	W 103 47 40.18
Drop 2° /100' DLS	2965.51 3000.00	5.00 4.31	290.14 290.14	2960.56 2994.94	-40.91 -41.89	40.24 41.21	-109.75 -112.38	0.00 2.00	440466.14 440467.10		N 32 12 35.32 N 32 12 35.33	W 103 47 40.24
	3100.00	2.31	290.14 290.14	2994.94 3094.77	-41.89 -43.92	41.21 43.20	-112.38 -117.81	2.00	440467.10			W 103 47 40.27 W 103 47 40.34
	3200.00	0.31	290.14	3194.73	-44.72	43.99	-119.96	2.00	440469.88			W 103 47 40.36
Hold Vertical	3215.65	0.00	290.14	3210.38	-44.73	44.00	-120.00	2.00	440469.90		N 32 12 35.35	W 103 47 40.36
	3300.00	0.00	290.14	3294.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	3400.00	0.00	290.14	3394.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	3500.00 3600.00	0.00	290.14 290.14	3494.73 3594.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90			W 103 47 40.36 W 103 47 40.36
	3700.00	0.00	290.14	3694.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36 W 103 47 40.36
	3800.00	0.00	290.14	3794.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	3900.00	0.00	290.14	3894.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4000.00	0.00	290.14	3994.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4100.00	0.00	290.14	4094.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
Base Salt	4107.27 4200.00	0.00 0.00	290.14 290.14	4102.00 4194.73	-44.73 -44.73	<i>44.00</i> 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90		N 32 12 35.35	W 103 47 40.36 W 103 47 40.36
	4300.00	0.00	290.14	4294.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36 W 103 47 40.36
Delaware	4327.27	0.00	290.14	4322.00	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4400.00	0.00	290.14	4394.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4500.00	0.00	290.14	4494.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4600.00	0.00	290.14	4594.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	4700.00	0.00	290.14	4694.73	-44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90			W 103 47 40.36
	4800.00 4900.00	0.00	290.14 290.14	4794.73 4894.73	-44.73 -44.73	44.00	-120.00	0.00	440469.90 440469.90			W 103 47 40.36 W 103 47 40.36
	5000.00	0.00	290.14	4994.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	5100.00	0.00	290.14	5094.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	5200.00	0.00	290.14	5194.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35	W 103 47 40.36
Cherry Canyon	5217.27	0.00	290.14	5212.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35	
	5300.00	0.00	290.14	5294.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	5400.00 5500.00	0.00	290.14 290.14	5394.73 5494.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90			W 103 47 40.36 W 103 47 40.36
	5600.00	0.00	290.14 290.14	5494.73 5594.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90			W 103 47 40.36 W 103 47 40.36
	5700.00	0.00	290.14	5694.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	5800.00	0.00	290.14	5794.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	5900.00	0.00	290.14	5894.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35	W 103 47 40.36
	6000.00	0.00	290.14	5994.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	6100.00	0.00	290.14	6094.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36
	6200.00	0.00	290.14	6194.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90			W 103 47 40.36
	6300.00 6400.00	0.00	290.14 290.14	6294.73 6394.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90			W 103 47 40.36 W 103 47 40.36
	6500.00	0.00	290.14	6494.73	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36 W 103 47 40.36
Brushy Canyon	6517.27	0.00	290.14	6512.00	-44.73	44.00	-120.00	0.00	440469.90			W 103 47 40.36

Comments	MD	Incl	Azim Grid	TVD	VSEC	NS	EW	DLS	Northing	Easting	Latitude Longitude
	(ft) 6600.00	(°) 0.00	(°) 290.14	(ft) 6594.73	-44.73	(ft) 44.00	-120.00	(°/100ft) 0.00	(ftUS) 440469.90	(ftUS) 666641.11	(N/S ° ' ") (E/W ° ' ") N 32 12 35.35 W 103 47 40.36
	6700.00	0.00	290.14	6694.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	6800.00 6900.00	0.00 0.00	290.14 290.14	6794.73 6894.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	7000.00	0.00	290.14	6994.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	7100.00 7200.00	0.00 0.00	290.14 290.14	7094.73 7194.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	7300.00	0.00	290.14	7294.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	7400.00	0.00	290.14	7394.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	7500.00 7600.00	0.00 0.00	290.14 290.14	7494.73 7594.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	7700.00	0.00	290.14	7694.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	7800.00 7900.00	0.00 0.00	290.14 290.14	7794.73 7894.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90	666641.11	N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
Basal Brushy	7907.27	0.00	290.14	7902.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Canyon	8000.00	0.00	290.14	7994.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	8100.00	0.00	290.14	8094.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Bone Spring Lime	8177.27	0.00	290.14	8172.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
Lime	8200.00	0.00	290.14	8194.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
Avalon Sand	8287.27	0.00	290.14	8282.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Upper Avalon	8300.00	0.00	290.14	8294.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Shale	8317.27	0.00	290.14	8312.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	8400.00	0.00 0.00	290.14	8394.73	-44.73 -44.73	44.00 44.00	-120.00	0.00 0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	8500.00 8600.00	0.00	290.14 290.14	8494.73 8594.73	-44.73 -44.73	44.00	-120.00 -120.00	0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	8700.00	0.00	290.14	8694.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
Lower Avalon Shale	8717.27	0.00	290.14	8712.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	8800.00	0.00	290.14	8794.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
4nt Dama Continu	8900.00	0.00	290.14	8894.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
1st Bone Spring Lime	8937.27	0.00	290.14	8932.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	9000.00	0.00	290.14	8994.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	9100.00	0.00	290.14	9094.73	-44.73 -44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
1st Bone Spring	9200.00	0.00	290.14	9194.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Ss	9247.27	0.00	290.14	9242.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	9300.00 9400.00	0.00 0.00	290.14 290.14	9294.73 9394.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	9500.00	0.00	290.14	9394.73	-44.73 -44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	9600.00	0.00	290.14	9594.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
2nd Bone Spring Lime	9637.27	0.00	290.14	9632.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
Spring Lime	9700.00	0.00	290.14	9694.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	9800.00	0.00	290.14	9794.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
2nd Bone	9900.00	0.00	290.14	9894.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
Spring Ss	9957.27	0.00	290.14	9952.00	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	10000.00 10100.00	0.00 0.00	290.14 290.14	9994.73 10094.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	10200.00	0.00	290.14	10194.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	10300.00	0.00	290.14	10294.73	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
3rd Bone Spring Lm	10347.27	0.00	290.14	10342.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
	10400.00	0.00	290.14	10394.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	10500.00 10600.00	0.00 0.00	290.14 290.14	10494.73 10594.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00 0.00	440469.90 440469.90		N 32 12 35.35 W 103 47 40.36 N 32 12 35.35 W 103 47 40.36
	10700.00	0.00	290.14	10694.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	10800.00	0.00	290.14	10794.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	10900.00 11000.00	0.00 0.00	290.14 290.14	10894.73 10994.73	-44.73 -44.73	44.00 44.00	-120.00 -120.00	0.00	440469.90 440469.90	666641.11 666641.11	
	11100.00	0.00	290.14	11094.73	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
3rd Bone Spring Ss	11127.27	0.00	290.14	11122.00	-44.73	44.00	-120.00	0.00	440469.90	666641.11	N 32 12 35.35 W 103 47 40.36
KOP, Build	44460.65	0.00	200.44	44455.20	44.70	44.00	420.00	0.00	440400.00	000044.44	N 22 42 25 25 W 402 47 40 20
9°/100' DLS	11160.65	0.00	290.14	11155.38	-44.73	44.00	-120.00	0.00	440469.90		N 32 12 35.35 W 103 47 40.36
	11200.00 11300.00	3.54 12.54	179.65 179.65	11194.71 11293.62	-43.52 -29.54	42.78 28.81	-119.99 -119.91	9.00 9.00	440468.68 440454.71		N 32 12 35.34 W 103 47 40.36 N 32 12 35.20 W 103 47 40.36
	11400.00	21.54	179.65	11389.14	-0.26	-0.47	-119.72	9.00	440425.43	666641.38	N 32 12 34.91 W 103 47 40.36
Red Hills SS	11457.96	26.76	179.65	11442.00	23.44	-24.17	-119.58	9.00	440401.73		N 32 12 34.68 W 103 47 40.36
Wolfcamp	11500.00 11551.33	30.54 35.16	179.65 179.65	11478.89 11522.00	43.59 71.43	-44.32 -72.16	-119.45 -119.28	9.00 9.00	440381.58 440353.74		N 32 12 34.48 W 103 47 40.36 N 32 12 34.21 W 103 47 40.36
•	11600.00	39.54	179.65	11560.68	100.95	-101.68	-119.10	9.00	440324.22	666642.01	N 32 12 33.91 W 103 47 40.36
Wolfcamp X	11662.72 11700.00	45.19 48.54	<i>179.65</i> 179.65	11607.00 11632.49	143.20 170.40	<i>-14</i> 3.92 -171.13	-118.84 -118.67	9.00 9.00	440281.98 440254.78		N 32 12 33.50 W 103 47 40.36 N 32 12 33.23 W 103 47 40.36
Wolfcamp Y	11763.35	54.24	179.65	11672.00	219.88	-220.61	-118.36	9.00	440205.30		N 32 12 32.74 W 103 47 40.36
14/-1/	11800.00	57.54	179.65	11692.55	250.22	-250.95	-118.17	9.00	440174.96		N 32 12 32.44 W 103 47 40.36
Wolfcamp A	<i>1184</i> 8.51 11900.00	61.91 66.54	<i>179.65</i> 179.65	11717.00 11739.38	292.11 338.46	-292.83 -339.19	-117.91 -117.63	9.00 9.00	440133.08 440086.73		N 32 12 32.02 W 103 47 40.36 N 32 12 31.56 W 103 47 40.36
	12000.00	75.54	179.65	11771.84	432.94	-433.66	-117.04	9.00	439992.26		N 32 12 30.63 W 103 47 40.36
andina Daint	12100.00	84.54	179.65	11789.11	531.33	-532.05	-116.43	9.00	439893.88		N 32 12 29.65 W 103 47 40.35 N 32 12 29.06 W 103 47 40.35
Landing Point Hold to TD	12160.65 12160.70	90.00 90.00	179.65 179.65	11792.00 11792.00	591.89 591.94	-592.61 -592.66	-116.06 -116.06	9.00 2.00	439833.33 439833.27		N 32 12 29.06 W 103 47 40.35 N 32 12 29.05 W 103 47 40.35
	12200.00	90.00	179.65	11792.00	631.24	-631.96	-115.81	0.00	439793.98	666645.29	N 32 12 28.67 W 103 47 40.35
	12300.00 12400.00	90.00 90.00	179.65 179.65	11792.00 11792.00	731.24 831.24	-731.96 -831.96	-115.19 -114.58	0.00 0.00	439693.99 439593.99		N 32 12 27.68 W 103 47 40.35 N 32 12 26.69 W 103 47 40.35
	12500.00	90.00	179.65	11792.00	931.24	-931.96	-113.96	0.00	439494.00		N 32 12 25.70 W 103 47 40.35
	12600.00	90.00	179.65	11792.00	1031.24	-1031.95	-113.34	0.00	439394.01		N 32 12 24.71 W 103 47 40.35
	12700.00 12800.00	90.00 90.00	179.65 179.65	11792.00 11792.00	1131.24 1231.24	-1131.95 -1231.95	-112.72 -112.11	0.00 0.00	439294.02 439194.03		N 32 12 23.72 W 103 47 40.35 N 32 12 22.73 W 103 47 40.34
	12900.00	90.00	179.65	11792.00	1331.24	-1331.95	-111.49	0.00	439094.03	666649.62	N 32 12 21.74 W 103 47 40.34
	13000.00	90.00	179.65	11792.00	1431.24	-1431.95	-110.87	0.00	438994.04		N 32 12 20.75 W 103 47 40.34
	13100.00 13200.00	90.00 90.00	179.65 179.65	11792.00 11792.00	1531.24 1631.24	-1531.94 -1631.94	-110.25 -109.64	0.00 0.00	438894.05 438794.06		N 32 12 19.76 W 103 47 40.34 N 32 12 18.77 W 103 47 40.34
	13300.00	90.00	179.65	11792.00	1731.24	-1731.94	-109.02	0.00	438694.07	666652.09	N 32 12 17.78 W 103 47 40.34
	13400.00 13500.00	90.00 90.00	179.65 179.65	11792.00 11792.00	1831.24 1931.24	-1831.94 -1931.94	-108.40 -107.78	0.00 0.00	438594.07 438494.08		N 32 12 16.79 W 103 47 40.34 N 32 12 15.80 W 103 47 40.34
	13600.00	90.00	179.65	11792.00	2031.24	-1931.94 -2031.93	-107.78 -107.16	0.00	438494.08		N 32 12 15.80 W 103 47 40.34 N 32 12 14.81 W 103 47 40.33
	13700.00	90.00	179.65	11792.00	2131.24	-2131.93	-106.55	0.00	438294.10	666654.56	N 32 12 13.82 W 103 47 40.33
	13800.00 13900.00	90.00 90.00	179.65 179.65	11792.00 11792.00	2231.24 2331.24	-2231.93 -2331.93	-105.93 -105.31	0.00	438194.11 438094.11		N 32 12 12.83 W 103 47 40.33 N 32 12 11.84 W 103 47 40.33
	14000.00	90.00	179.65	11792.00	2431.24	-2331.93 -2431.93	-105.31 -104.69	0.00	438094.11		N 32 12 11.84 W 103 47 40.33 N 32 12 10.85 W 103 47 40.33
	14100.00	90.00	179.65	11792.00	2531.24	-2531.93	-104.08	0.00	437894.13	666657.03	N 32 12 9.86 W 103 47 40.33
	14200.00 14300.00	90.00 90.00	179.65 179.65	11792.00 11792.00	2631.24 2731.24	-2631.92 -2731.92	-103.46 -102.84	0.00 0.00	437794.14 437694.15		N 32 12 8.87 W 103 47 40.33 N 32 12 7.89 W 103 47 40.32
	14400.00	90.00	179.65	11792.00	2831.24	-2731.92 -2831.92	-102.84	0.00	437594.15		N 32 12 7.89 W 103 47 40.32 N 32 12 6.90 W 103 47 40.32

Comments	MD	Incl	Azim Grid	TVD	VSEC	NS	EW	DLS	Northing	Easting	Latitude	Longitude
	(ft) 14500.00	90.00	(°) 179.65	(ft) 11792.00	(ft) 2931.24	-2931.92	(ft)	(°/100ft) 0.00	(ftUS) 437494.16	(ftUS) 666659.50	(N/S ° ' ") N 32 12 5.91 \	(E/W ° ' ")
							-101.61 -100.99			666659.50	N 32 12 5.91 V N 32 12 4.92 V	V 103 47 40.32
	14600.00 14700.00	90.00 90.00	179.65 179.65	11792.00 11792.00	3031.24 3131.24	-3031.92 -3131.91		0.00 0.00	437394.17 437294.18		N 32 12 4.92 V N 32 12 3.93 V	
	14800.00	90.00	179.65	11792.00	3231.24	-3131.91	-100.37 -99.75	0.00	437294.18		N 32 12 3.93 V N 32 12 2.94 V	
	14900.00	90.00	179.65	11792.00	3331.24	-3331.91	-99.13	0.00	437194.19		N 32 12 2.94 V	
	15000.00	90.00	179.65	11792.00	3431.24	-3431.91	-98.52	0.00	436994.20			V 103 47 40.32
	15100.00	90.00	179.65	11792.00	3531.24	-3531.91	-97.90	0.00	436894.21		N 32 11 59.97 V	
	15200.00	90.00	179.65	11792.00	3631.24	-3631.90	-97.28	0.00	436794.22		N 32 11 58.98 V	
	15300.00	90.00	179.65	11792.00	3731.24	-3731.90	-96.66	0.00	436694.23		N 32 11 57.99 V	
	15400.00	90.00	179.65	11792.00	3831.24	-3831.90	-96.05	0.00	436594.23	666665.06	N 32 11 57.00 V	V 103 47 40.31
	15500.00	90.00	179.65	11792.00	3931.24	-3931.90	-95.43	0.00	436494.24	666665.68	N 32 11 56.01 V	
	15600.00	90.00	179.65	11792.00	4031.24	-4031.90	-94.81	0.00	436394.25		N 32 11 55.02 V	
	15700.00	90.00	179.65	11792.00	4131.24	-4131.89	-94.19	0.00	436294.26		N 32 11 54.03 V	
	15800.00	90.00	179.65	11792.00	4231.24	-4231.89	-93.58	0.00	436194.27	666667.53	N 32 11 53.04 V	
	15900.00	90.00	179.65	11792.00	4331.24	-4331.89	-92.96	0.00	436094.27		N 32 11 52.05 V	
	16000.00	90.00	179.65	11792.00	4431.24	-4431.89	-92.34	0.00	435994.28		N 32 11 51.06 V	
	16100.00	90.00	179.65	11792.00	4531.24	-4531.89	-91.72	0.00	435894.29		N 32 11 50.07 V	
	16200.00 16300.00	90.00 90.00	179.65 179.65	11792.00 11792.00	4631.24 4731.24	-4631.89 -4731.88	-91.10 -90.49	0.00 0.00	435794.30 435694.31		N 32 11 49.08 V N 32 11 48.09 V	V 103 47 40.30 V 103 47 40.30
	16400.00	90.00	179.65	11792.00	4831.24	-4831.88	-89.87	0.00	435594.31			V 103 47 40.30
	16500.00	90.00	179.65	11792.00	4931.24	-4931.88	-89.25	0.00	435494.32			V 103 47 40.30
	16600.00	90.00	179.65	11792.00	5031.24	-5031.88	-88.63	0.00	435394.33		N 32 11 45.13 V	
	16700.00	90.00	179.65	11792.00	5131.24	-5131.88	-88.02	0.00	435294.34			V 103 47 40.29
	16800.00	90.00	179.65	11792.00	5231.24	-5231.87	-87.40	0.00	435194.35		N 32 11 43.15 V	
	16900.00	90.00	179.65	11792.00	5331.24	-5331.87	-86.78	0.00	435094.35		N 32 11 42.16 V	V 103 47 40.29
	17000.00	90.00	179.65	11792.00	5431.24	-5431.87	-86.16	0.00	434994.36	666674.94		V 103 47 40.29
	17100.00	90.00	179.65	11792.00	5531.24	-5531.87	-85.55	0.00	434894.37	666675.56	N 32 11 40.18 V	
	17200.00	90.00	179.65	11792.00	5631.24	-5631.87	-84.93	0.00	434794.38	666676.18	N 32 11 39.19 V	V 103 47 40.29
	17300.00	90.00	179.65	11792.00	5731.24	-5731.86	-84.31	0.00	434694.39	666676.79	N 32 11 38.20 V	V 103 47 40.28
	17400.00	90.00	179.65	11792.00	5831.24	-5831.86	-83.69	0.00	434594.39			V 103 47 40.28
	17500.00	90.00	179.65	11792.00	5931.24	-5931.86	-83.07	0.00	434494.40		N 32 11 36.22 V	
	17600.00	90.00	179.65	11792.00	6031.24	-6031.86	-82.46	0.00	434394.41		N 32 11 35.23 V	
	17700.00	90.00	179.65	11792.00	6131.24	-6131.86	-81.84	0.00	434294.42			V 103 47 40.28
	17800.00	90.00	179.65	11792.00	6231.24	-6231.85	-81.22	0.00	434194.43			V 103 47 40.28
	17900.00	90.00	179.65	11792.00	6331.24	-6331.85	-80.60	0.00	434094.43		N 32 11 32.26 V	
	18000.00 18100.00	90.00 90.00	179.65 179.65	11792.00 11792.00	6431.24 6531.24	-6431.85 -6531.85	-79.99 -79.37	0.00 0.00	433994.44 433894.45		N 32 11 31.27 V N 32 11 30.28 V	V 103 47 40.27 V 103 47 40.27
	18200.00	90.00	179.65	11792.00	6631.24	-6631.85	-79.37 -78.75	0.00	433794.46		N 32 11 30.26 V	
	18300.00	90.00	179.65	11792.00	6731.24	-6731.84	-78.13	0.00	433694.47			V 103 47 40.27
	18400.00	90.00	179.65	11792.00	6831.24	-6831.84	-77.52	0.00	433594.47			V 103 47 40.27
	18500.00	90.00	179.65	11792.00	6931.24	-6931.84	-76.90	0.00	433494.48		N 32 11 26.32 V	
	18600.00	90.00	179.65	11792.00	7031.24	-7031.84	-76.28	0.00	433394.49		N 32 11 25.33 V	
	18700.00	90.00	179.65	11792.00	7131.24	-7131.84	-75.66	0.00	433294.50		N 32 11 24.34 V	
	18800.00	90.00	179.65	11792.00	7231.24	-7231.84	-75.04	0.00	433194.51	666686.06	N 32 11 23.36 V	V 103 47 40.26
	18900.00	90.00	179.65	11792.00	7331.24	-7331.83	-74.43	0.00	433094.51	666686.68	N 32 11 22.37 V	V 103 47 40.26
	19000.00	90.00	179.65	11792.00	7431.24	-7431.83	-73.81	0.00	432994.52		N 32 11 21.38 V	
	19100.00	90.00	179.65	11792.00	7531.24	-7531.83	-73.19	0.00	432894.53			V 103 47 40.26
	19200.00	90.00	179.65	11792.00	7631.24	-7631.83	-72.57	0.00	432794.54		N 32 11 19.40 V	
	19300.00	90.00	179.65	11792.00	7731.24	-7731.83	-71.96	0.00	432694.55		N 32 11 18.41 V	
	19400.00	90.00	179.65	11792.00	7831.24	-7831.82	-71.34	0.00	432594.55			V 103 47 40.26
	19500.00 19600.00	90.00 90.00	179.65 179.65	11792.00 11792.00	7931.24 8031.24	-7931.82 -8031.82	-70.72 -70.10	0.00 0.00	432494.56 432394.57		N 32 11 16.43 N N 32 11 15.44 N	
	19700.00	90.00	179.65	11792.00	8131.24	-8131.82	-69.49	0.00	432294.58			V 103 47 40.25
	19800.00	90.00	179.65	11792.00	8231.24	-8231.82	-68.87	0.00	432194.59			V 103 47 40.25
	19900.00	90.00	179.65	11792.00	8331.24	-8331.81	-68.25	0.00	432094.59		N 32 11 12.47 V	
	20000.00	90.00	179.65	11792.00	8431.24	-8431.81	-67.63	0.00	431994.60		N 32 11 11.48 V	
	20100.00	90.00	179.65	11792.00	8531.24	-8531.81	-67.02	0.00	431894.61		N 32 11 10.49 V	
	20200.00	90.00	179.65	11792.00	8631.24	-8631.81	-66.40	0.00	431794.62		N 32 11 9.50 V	
	20300.00	90.00	179.65	11792.00	8731.24	-8731.81	-65.78	0.00	431694.63		N 32 11 8.51 V	
	20400.00	90.00	179.65	11792.00	8831.24	-8831.80	-65.16	0.00	431594.63	666695.94	N 32 11 7.52 V	V 103 47 40.24
	20500.00	90.00	179.65	11792.00	8931.24	-8931.80	-64.54	0.00	431494.64			V 103 47 40.24
	20600.00	90.00	179.65	11792.00	9031.24	-9031.80	-63.93	0.00	431394.65		N 32 11 5.54 V	
	20700.00	90.00	179.65	11792.00	9131.24	-9131.80	-63.31	0.00	431294.66		N 32 11 4.55 V	
	20800.00	90.00	179.65	11792.00	9231.24	-9231.80	-62.69	0.00	431194.67		N 32 11 3.56 V	
	20900.00	90.00	179.65	11792.00	9331.24	-9331.80	-62.07	0.00	431094.67		N 32 11 2.57 V	
	21000.00	90.00	179.65	11792.00	9431.24	-9431.79	-61.46	0.00	430994.68		N 32 11 1.59 V	
	21100.00	90.00	179.65	11792.00	9531.24	-9531.79	-60.84	0.00	430894.69		N 32 11 0.60 V	
	21200.00	90.00	179.65	11792.00	9631.24	-9631.79	-60.22	0.00	430794.70		N 32 10 59.61 V	
	21300.00	90.00	179.65	11792.00	9731.24	-9731.79	-59.60	0.00	430694.71		N 32 10 58.62 V	
	21400.00	90.00	179.65	11792.00	9831.24	-9831.79	-58.99	0.00	430594.71		N 32 10 57.63 V	
	21500.00 21600.00	90.00 90.00	179.65 179.65	11792.00	9931.24 10031.24	-9931.78 -10031.78	-58.37 -57.75	0.00	430494.72 430394.73		N 32 10 56.64 V	
	21600.00	90.00	179.65 179.65	11792.00 11792.00	10031.24	-10031.78 -10131.78	-57.75 -57.13	0.00 0.00	430394.73		N 32 10 55.65 N N 32 10 54.66 N	
	21800.00	90.00	179.65	11792.00	10131.24	-10131.78	-57.13 -56.51	0.00	430294.74		N 32 10 54.66 V	
	21000.00	33.00	173.00	11132.00	10201.24	10231.70	30.31	0.00	700134.70	000704.08	02 10 00.07 1	. 100 -1 -0.22
XTO Poker Lake Unit 17 TWR 707H - BHL	21817.95	90.00	179.65	11792.00	10249.19	-10249.73	-56.40	0.00	430176.80	666704.70	N 32 10 53.49 \	V 103 47 40.22

Survey Type:

Def Plan

Survey Error Model: Survey Program:

ISCWSA Rev 0 \*\*\* 3-D 95.000% Confidence 2.7955 sigma

 Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size Casi (in)	ing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	30.000	1/100.000	14.750	11.750	•	NAL_MWD_1.0_DEG-Depth Only	XTO Poker Lake Unit 17 TWR 707H / XTO Poker Lake Unit 17 TWR 707H Rev0 LP 02Jun20
	1	30.000	900.000	1/100.000	14.750	11.750		NAL_MWD_1.0_DEG	XTO Poker Lake Unit 17 TWR 707H / XTO Poker Lake Unit 17
	1	900.000	11160.000	1/100.000	9.875	7.625		NAL_MWD_1.0_DEG	XTO Poker Lake Unit 17 TWR 707H / XTO Poker Lake Unit 17
	1	11160.000	21817.948	1/100.000	6.750	5.500		NAL_MWD_IFR1+MS	XTO Poker Lake Unit 17 TWR 707H / XTO Poker Lake Unit 17

Subject: Request for a Variance Allowing break Testing of the Blowout Preventer Equipment (BOPE)

XTO Energy requests a variance to ONLY test broken pressure seals on the BOPE and function test BOP when skidding a drilling rig between multiple wells on a pad.

### **Background**

Onshore Oil and Gas Order (OOGO) No. 2, Drilling Operations, Sections III.A.2.i.iv.B states that the BOP test must be performed whenever any seal subject to test pressure is broken. The current interpretation of the Bureau of Land Management (BLM) requires a complete BOP test and not just a test of the affected component. OOGO No. 2, Section I.D.2 states, "Some situation may exist either on a well-by-well basis or field-wide basis whereby it is commonly accepted practice to vary a particular minimum standard(s) established in this order. This situation can be resolved by requesting a variance...". XTO Energy feels the break testing the BOPE is such a situation. Therefore, as per OOGO No. 2, Section IV., XTO Energy submits this request for the variance.

### **Supporting Documentation**

OOGO No. 2 became effective on December 19, 1988 and has remained the standard for regulating BLM onshore drilling operations for over 30 years. During this time there have been significant changes in drilling technology. BLM continues to use the variance request process to allow for the use of modern technology and acceptable engineering practices that have arisen since OOGO No. 2 was originally released. The XTO Energy drilling rig fleet has many modern upgrades that allow the intact BOP stack to be moved between well slots on a multi-well pad, as well as, wellhead designs that incorporate quick connects facilitating release of the BOP from the wellhead without breaking any BOP stack components apart. These technologies have been used extensively offshore, and other regulators, API, and many operators around the world have endorsed break testing as safe and reliable.



Figure 1: Winch System attached to BOP Stack



Figure 2: BOP Winch System

American Petroleum Institute (API) standards, specification and recommended practices are considered the industry standard and are consistently utilized and referenced by the industry. OOGO No. 2 recognizes API recommended Practices (RP) 53 in its original development. API Standard 53, *Well Control Equipment Systems for Drilling Wells* (Fifth Edition, December 2018, Annex C, Table C.4) recognizes break testing as an acceptable practice. Specifically, API Standard 53, Section 5.3.7.1 states "A pressure test of the pressure containing component shall be performed following the disconnection or repair, limited to the affected component." See Table C.4 below for reference.

	Pressure Test—Low	Pressure Test—High Pressure					
Component to be Pressure Tested	Pressure <sup>ac</sup> psig (MPa)	Change Out of Component, Elastomer, or Ring Gasket	No Change Out of Component, Elastomer, or Ring Gasket				
Annular preventer <sup>b</sup>	250 to 350 (1.72 to 2.41)	RWP of annular preventer	MASP or 70% annular RWP, whichever is lower.				
Fixed pipe, variable bore, blind, and BSR preventers <sup>bd</sup>	250 to 350 (1.72 to 2.41)	RWP of ram preventer or wellhead system, whichever is lower	ITP				
Choke and kill line and BOP side outlet valves below ram preventers (both sides)	250 to 350 (1.72 to 2.41)	RWP of side outlet valve or wellhead system, whichever is lower	ITP				
Choke manifold—upstream of chokes <sup>e</sup>	250 to 350 (1.72 to 2.41)	RWP of ram preventers or wellhead system, whichever is lower	ITP				
Choke manifold—downstream of chokese	250 to 350 (1.72 to 2.41)	RWP of valve(s), line(s), or M whichever is lower	MASP for the well program,				
Kelly, kelly valves, drill pipe safety valves, IBOPs	250 to 350 (1.72 to 2.41)	MASP for the well program					
	during the evaluation period. The p	oressure shall not decrease below the					
	from one wellhead to another within when the integrity of a pressure sea	n the 21 days, pressure testing is req	uired for pressure-containing an				

The Bureau of Safety and Environmental Enforcement (BSEE), Department of Interior, has also utilized the API standards, specification and best practices in the development of its offshore oil and gas regulations and incorporates them by reference within its regulations.

Break testing has been approved by the BLM in the past with other operators based on the detailed information provided in this document.


XTO Energy feels break testing and our current procedures meet the intent of OOGO No. 2 and often exceed it. There has been no evidence that break testing results in more components failing than seen on full BOP tests. XTO Energy's internal standards requires complete BOPE tests more often than that of OOGO No. 2 (Every 21 days). In addition to function testing the annular, pipe rams and blind rams after each BOP nipple up, XTO Energy performs a choke drill with the rig crew prior to drilling out every casing shoe. This is additional training for the rig crew that exceeds the requirements of the OOGO No.2.

### **Procedures**

- XTO Energy will use this document for our break testing plan for New Mexico Delaware basin.
  The summary below will be referenced in the APD or Sundry Notice and receive approval prior
  to implementing this variance.
- 2. XTO Energy will perform BOP break testing on multi-wells pads where multiple intermediate sections can be drilled and cased within the 21-day BOP test window.
  - a. A full BOP test will be conducted on the first well on the pad.
  - b. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
    - i. Our Lower WC targets set the intermediate casing shoe no deeper than the Wolfcamp B.
    - ii. Our Upper WC targets set the intermediate casing shoe shallower than the Wolfcamp B.
  - c. A Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
  - d. A full BOP test will be required prior to drilling any production hole.
- 3. After performing a complete BOP test on the first well, the intermediate hole section will be drilled and cased, two breaks would be made on the BOP equipment.
  - a. Between the HCV valve and choke line connection
  - b. Between the BOP quick connect and the wellhead
- 4. The BOP is then lifted and removed from the wellhead by a hydraulic system.
- 5. After skidding to the next well, the BOP is moved to the wellhead by the same hydraulic system and installed.
- 6. The connections mentioned in 3a and 3b will then be reconnected.
- 7. Install test plug into the wellhead using test joint or drill pipe.
- 8. A shell test is performed against the upper pipe rams testing the two breaks.
- 9. The shell test will consist of a 250 psi low test and a high test to the value submitted in the APD or Sundry (e.g. 5,000 psi or 10,000psi).
- 10. Function test will be performed on the following components: lower pipe rams, blind rams, and annular.

- 11. For a multi-well pad the same two breaks on the BOP would be made and on the next wells and steps 4 through 10 would be repeated.
- 12. A second break test would only be done if the intermediate hole section being drilled could not be completed within the 21 day BOP test window.

Note: Picture below highlights BOP components that will be tested during batch operations




### **Summary**

A variance is requested to **ONLY** test broken pressure seals on the BOP equipment when moving from wellhead to wellhead which is in compliance with API Standard 53. API Standard 53 states, that for pad drilling operation, moving from one wellhead to another within 21 days, pressure testing is required for pressure-containing and pressure-controlling connections when the integrity of a pressure seal is broken.

The BOP will be secured by a hydraulic carrier or cradle. The BLM will be contacted if a Well Control event occurs prior to the commencement of a BOPE Break Testing operation.

Based on discussions with the BLM on February 27th 2020 and the supporting documentation submitted to the BLM, we will request permission to ONLY retest broken pressure seals if the following conditions are met:

- 1. After a full BOP test is conducted on the first well on the pad.
- 2. The first intermediate hole section drilled on the pad will be the deepest. All of the remaining hole sections will be the same depth or shallower.
- 3. Full BOP test will be required if the intermediate hole section being drilled has a MASP over 5M.
- 4. Full BOP test will be required prior to drilling the production hole.



XTO respectfully requests approval to utilize a spudder rig to pre-set surface casing.

### Description of Operations:

- 1. Spudder rig will move in to drill the surface hole and pre-set surface casing on the well.
  - a. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
  - b. The spudder rig will utilize fresh water-based mud to drill the surface hole to TD. Solids control will be handled entirely on a closed loop basis. No earth pits will be used.
- 2. The wellhead will be installed and tested as soon as the surface casing is cut off and WOC time has been reached.
- 3. A blind flange at the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wing valves.
  - a. A means for intervention will be maintained while the drilling rig is not over the well.
- 4. Spudder rig operations are expected to take 2-3 days per well on the pad.
- 5. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
- 6. Drilling Operations will begin with a larger rig and a BOP stack equal to or greater than the pressure rating that was permitted will be nippled up and tested on the wellhead before drilling operations resume on each well.
  - a. The larger rig will move back onto the location within 180 days from the point at which the wells are secured and the spudder rig is moved off location.
  - b. The BLM will be notified 24 hours before the larger rig moves back on the pre-set locations
- 7. XTO will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
- 8. Once the rig is removed, XTO will secure the wellhead area by placing a guard rail around the cellar area.