Form 3160-3
(June 2015)

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No.
NMNM045235

6. If Indian, Allotee or Tribe Name

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other

1c. Type of Completion: ☐ Hydraulic Fracturing ☑ Single Zone ☐ Multiple Zone

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.
FIJI 17-5 FED COM
334H

2. Name of Operator
DEVON ENERGY PRODUCTION COMPANY LP

9. API Well No.
30 015 47635

3a. Address
333 West Sheridan Avenue, Oklahoma City, OK 73102

3b. Phone No. *(include area code)*
(800) 583-3866

10. Field and Pool, or Exploratory
LOS MEDANOS; BONE SPRING

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*
At surface SENE / 2480 FNL / 1280 FEL / LAT 32.3049196 / LONG -103.7954833
At proposed prod. zone LOT 1 / 20 FNL / 330 FEL / LAT 32.3406961 / LONG -103.7924362

11. Sec., T. R. M. or Blk. and Survey or Area
SEC 17/T23S/R31E/NMP

14. Distance in miles and direction from nearest town or post office*

12. County or Parish
EDDY

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)
1280 feet

16. No of acres in lease
480

17. Spacing Unit dedicated to this well
400.0

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft.
189 feet

19. Proposed Depth
11190 feet / 23922 feet

20. BLM/BIA Bond No. in file
FED: NMB000801

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3343 feet

22. Approximate date work will start*
04/29/2021

23. Estimated duration
45 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be requested by the BLM.

25. Signature
(Electronic Submission)

Name *(Printed/Typed)*
JENNY HARMS / Ph: (800) 583-3866

Date
05/04/2020

Title
Regulatory Compliance Professional

Approved by *(Signature)*
(Electronic Submission)

Name *(Printed/Typed)*
Cody Layton / Ph: (575) 234-5959

Date
11/03/2020

Title
Assistant Field Manager Lands & Minerals

Office
Carlsbad Field Office

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Oil base muds are not to be used until fresh water zones are cased and cemented providing isolation from the oil or diesel. This includes synthetic oils. Oil based mud, drilling fluids and solids must be contained in a steel closed loop system.

- Will require a directional survey with the C-104

Once the well is spud, to prevent ground water contamination through whole or partial conduits from the surface, the operator shall drill without interruption through the fresh water zone or zones and shall immediately set in cement the water protection string

SL

KP 11/5/2020 GEO Review

(Continued on page 2)

*(Instructions on page 2)

APPROVED WITH CONDITIONS

Approval Date: 11/03/2020

Entered - KMS NMOCD

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

[1] API Number	[2] Pool Code	[3] Pool Name
30 015 47635	40295	Los Medanos Bone Spring

[4] Property Code	[5] Property Name	[6] Well Number
329787	FIJI 17-5 FED COM	334H

[7] OGRID No.	[8] Operator Name	[9] Elevation
6137	DEVON ENERGY PRODUCTION COMPANY, L.P.	3343.3

[10] Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	17	23 S	31 E		2480	NORTH	1280	EAST	EDDY

[11] Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
1	5	23 S	31 E		20	NORTH	330	EAST	EDDY

[12] Dedicated Acres	[13] Joint or Infill	[14] Consolidation Code	[15] Order No.
399.82			

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.



[17] OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Jenny Harms 4-30-2020

Signature Date

JENNY HARMS

Printed Name

JENNY.HARMS@DVN.COM

E-mail Address

[18] SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

MARCH 12, 2020

Date of Survey

Signature and Seal of Professional Surveyor:

Certificate Number: EDMOND F. JARAMILLO, PLS 12797
SURVEY NO. 8045

Intent [X] As Drilled [ ]

API #

Operator Name:	Property Name:	Well Number
DEVON ENERGY PRODUCTION COMPANY, L.P.	FIJI 17-5 FED COM	334H

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
H	17	23S	31E		2380 FNL		330 FEL		EDDY

Latitude	Longitude	NAD
32.30518100		83

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
H	17	23S	31E		2540	NORTH	330	EAST	EDDY

Latitude	Longitude	NAD
32.3047563	103.7924089	83

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
A	5	23S	31E	1	100	NORTH	330	EAST	EDDY

Latitude	Longitude	NAD
32.3404763	103.7924363	83

Is this well the defining well for the Horizontal Spacing Unit? [NO]

Is this well an infill well? [YES]

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #

Operator Name:	Property Name:	Well Number

KZ 06/29/2018

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department

Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office

GAS CAPTURE PLAN

Date: April 30, 2020

☒ Original Devon & OGRID No.: Devon Energy Production Co., L.P. 6137

☐ Amended - Reason for Amendment: _____

This Gas Capture Plan outlines actions to be taken by the Devon to reduce well/production facility flaring/venting for new completion (new drill, recomplete to new zone, re-frac) activity.

Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).

Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location	Footages	Expected MCF/D	Flared or Vented	Comments
FIJI 17-5 FED COM 124H		LOT G, 17-23S-31E	2180 FNL 1670 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 125H		LOT G, 17-23S-31E	2180 FNL 1640 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 126H		LOT G, 17-23S-31E	2180 FNL 1610 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 233H		LOT H, 17-23S-31E	2330 FNL 1310 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 234H		LOT H, 17-23S-31E	2330 FNL 1280 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 333H		LOT G, 17-23S-31E	2330 FNL 1610 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 334H		LOT H, 17-23S-31E	2480 FNL 1280 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 623H		LOT G, 17-23S-31E	2330 FNL 1670 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 624H		LOT G, 17-23S-31E	2480 FNL 1340 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 713H		LOT G, 17-23S-31E	2330 FNL 1640 FEL			FIJI 17 CTB 1
FIJI 17-5 FED COM 714H		LOT H, 17-23S-31E	2480 FNL 1310 FEL			FIJI 17 CTB 1

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if DCP system is in place. The gas produced from production facility is dedicated to DCP and will be connected to DCP low/high pressure gathering system located in Lea County, New Mexico. It will require 0' of pipeline to connect the facility to low/high pressure gathering system. Devon provides (periodically) to DCP a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Devon and DCP have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at DCP Processing Plant located in the reference table. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on DCP system at that time. Based on current information, it is Devon's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease
  - Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
  - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
  - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines

Reference Table:

DCP Plant locations
Artesia Sec. 7, T18S, R28E,
Eunice Sec. 5, T21S, R36E
Linam Sec. 6, T19S, R37E
Zia II Sec. 19, T19S, R32E

APD ID: 10400056770 **Submission Date:** 05/04/2020

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: FIJI 17-5 FED COM **Well Number:** 334H

Well Type: OIL WELL **Well Work Type:** Drill

Highlighted data reflects the most recent changes

Show Final Text

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
728693	UNKNOWN	3339	0	0	OTHER : SURFACE	NONE	N
728694	RUSTLER	2929	410	410	SANDSTONE	NONE	N
728695	SALADO	2619	720	720	SALT	NONE	N
728696	BASE OF SALT	-491	3830	3830	ANHYDRITE	NATURAL GAS, OIL	N
728697	BELL CANYON	-741	4080	4080	SANDSTONE	NATURAL GAS, OIL	N
728698	CHERRY CANYON	-1671	5010	5010	SANDSTONE	NATURAL GAS, OIL	N
728699	BRUSHY CANYON	-2971	6310	6310	SANDSTONE	NATURAL GAS, OIL	N
728706	BONE SPRING LIME	-4645	7984	7984	LIMESTONE	NATURAL GAS, OIL	N
728700	BONE SPRING	-5744	9083	9083	SANDSTONE	NATURAL GAS, OIL	N
728702	BONE SPRING 2ND	-6278	9617	9617	SANDSTONE	NATURAL GAS, OIL	N
728707	BONE SPRING LIME	-6816	10155	10155	LIMESTONE	NATURAL GAS, OIL	N
728703	BONE SPRING 3RD	-7461	10800	10800	SANDSTONE	NATURAL GAS, OIL	Y
728704	WOLFCAMP	-7891	11230	11230	SHALE	NATURAL GAS, OIL	N
728705	STRAWN	-9511	12850	12850	LIMESTONE	NATURAL GAS, OIL	N

Section 2 - Blowout Prevention

1. Geologic Formations

TVD of target	11190	Pilot hole depth	N/A
MD at TD:	23922	Deepest expected fresh water	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone?	Hazards*
Rustler	410		
Salt	720		
Base of Salt	3830		
Delaware	4080		
Bone Spring 1st	9083		
Bone Spring 2nd	9617		
Bone Spring 3rd	10800		
Wolfcamp	11230		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

2. Casing Program (Primary Design)

Hole Size	Csg. Size	Wt (PPF)	Grade	Conn	Casing Interval		Casing Interval	
					From (MD)	To (MD)	From (TVD)	To (TVD)
17 1/2	13 3/8	48.0	H40	STC	0	435	0	435
9 7/8	8 5/8	32.0	P110	TLW	0	9642	0	9642
7 7/8	5 1/2	17.0	P110	BTC	0	23922	0	11190

• All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 IILB.1.h Must have table for continengcy casing.

3. Cementing Program (Primary Design)

Casing	# Sks	TOC	Wt. ppg	Yld (ft3/sack)	Slurry Description
Surface	353	Surf	13.2	1.44	Lead: Class C Cement + additives
Int 1	500	Surf	9	3.27	Lead: Class C Cement + additives
	67	4000' above	13.2	1.44	Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.44	Squeeze Lead: Class C Cement + additives
	500	Surf	9	3.27	Lead: Class C Cement + additives
	67	4000' above	13.2	1.44	Tail: Class H / C + additives
Production	89	9142	9.0	3.3	Lead: Class H /C + additives
	1753	10675	13.2	1.4	Tail: Class H / C + additives

Casing String	% Excess
Surface	50%
Intermediate 1	30%
Intermediate 1 (Two Stage)	25%
Prod	10%

4. Pressure Control Equipment (Three String Design)

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-58"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram		
			Double Ram	X	
			Other*		
			Annular (5M)		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
Y	A variance is requested to run a 5 M annular on a 10M system

5. Mud Program (Three String Design)

Section	Type	Weight (ppg)
Surface	FW Gel	8.5-9
Intermediate	DBE / Cut Brine	10-10.5
Production	OBM	8.5-9

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well - vertical portion of hole). Stated logs run will be in the Completion Rpeort and sbumitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain.
	Coring? If yes, explain.

Additional logs planned		Interval
	Resistivity	Int. shoe to KOP
	Density	Int. shoe to KOP
X	CBL	Production casing
X	Mud log	Intermediate shoe to TD
	PEX	

7. Drilling Conditions

Condition	Specfiy what type and where?
BH pressure at deepest TVD	5237
Abnormal temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogren Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S plan attached.

8. Other facets of operation

Is this a walking operation? Potentially

1 If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
2 The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
3 The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed

from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

1. Spudder rig will move in and batch drill surface hole.
    a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.,
2. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
3. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
4. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
5. Spudder rig operations is expected to take 4-5 days per well on a multi-well pa.
6. The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
7. Drilling operations will be performed with drilling rig. A that time an approved BOP stack will be nippled up and tested on the wellhead before drilling operations commences on each well.
    a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.

Attachments

X Directional Plan

_____ Other, describe

WCDSC Permian NM

Eddy County (NAD 83 NM Eastern)
Sec 17-T23S-R31E
Fiji 17-5 Fed Com 334H

Wellbore #1

Plan: Permit Plan 1

Standard Planning Report - Geographic

26 April, 2020

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Project Eddy County (NAD 83 NM Eastern)

Map System:	US State Plane 1983	**System Datum:**	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site Sec 17-T23S-R31E

Site Position:		**Northing:**	477,535.44 usft	**Latitude:**	32.311726
From:	Map	**Easting:**	703,511.29 usft	**Longitude:**	-103.808392
Position Uncertainty:	0.00 ft	**Slot Radius:**	13-3/16 "	**Grid Convergence:**	0.28 °

Well Fiji 17-5 Fed Com 334H

Well Position	**+N/-S**	0.00 ft	**Northing:**	475,079.05 usft	**Latitude:**	32.304920
	+E/-W	0.00 ft	**Easting:**	707,511.52 usft	**Longitude:**	-103.795484
Position Uncertainty		0.50 ft	**Wellhead Elevation:**		**Ground Level:**	3,343.30 ft

Wellbore Wellbore #1

Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2015	4/13/2020	6.76	60.06	47,672.82438857

Design Permit Plan 1

Audit Notes:

Version:		**Phase:**	PROTOTYPE	**Tie On Depth:**	0.00

Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	3.85

Plan Survey Tool Program **Date** 4/26/2020

	Depth From (ft)	Depth To (ft)	Survey (Wellbore)	Tool Name	Remarks
1	0.00	23,922.04	Permit Plan 1 (Wellbore #1)	MWD+HDGM	
				OWSG MWD + HDGM	

Plan Sections

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,709.47	7.09	83.99	2,707.66	4.59	43.63	1.00	1.00	0.00	83.99	
9,851.73	7.09	83.99	9,795.23	96.94	920.91	0.00	0.00	0.00	0.00	
10,324.70	0.00	0.00	10,267.00	100.00	950.00	1.50	-1.50	0.00	180.00	
10,674.74	0.00	0.00	10,617.04	100.00	950.00	0.00	0.00	0.00	0.00	
11,574.75	90.00	359.67	11,190.00	672.95	946.71	10.00	10.00	0.00	359.67	PBHL - Fiji 17-5 Fed (
23,922.04	90.00	359.67	11,190.00	13,020.04	875.75	0.00	0.00	0.00	0.00	PBHL - Fiji 17-5 Fed (

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
100.00	0.00	0.00	100.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
200.00	0.00	0.00	200.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
300.00	0.00	0.00	300.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
400.00	0.00	0.00	400.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
500.00	0.00	0.00	500.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
600.00	0.00	0.00	600.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
700.00	0.00	0.00	700.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
800.00	0.00	0.00	800.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
900.00	0.00	0.00	900.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,000.00	0.00	0.00	1,000.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,100.00	0.00	0.00	1,100.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,200.00	0.00	0.00	1,200.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,300.00	0.00	0.00	1,300.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,400.00	0.00	0.00	1,400.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,500.00	0.00	0.00	1,500.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,600.00	0.00	0.00	1,600.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,700.00	0.00	0.00	1,700.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,800.00	0.00	0.00	1,800.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
1,900.00	0.00	0.00	1,900.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
2,000.00	0.00	0.00	2,000.00	0.00	0.00	475,079.05	707,511.52	32.304920	-103.795484
2,100.00	1.00	83.99	2,099.99	0.09	0.87	475,079.14	707,512.38	32.304920	-103.795481
2,200.00	2.00	83.99	2,199.96	0.37	3.47	475,079.42	707,514.99	32.304921	-103.795472
2,300.00	3.00	83.99	2,299.86	0.82	7.81	475,079.87	707,519.32	32.304922	-103.795458
2,400.00	4.00	83.99	2,399.68	1.46	13.88	475,080.51	707,525.40	32.304923	-103.795439
2,500.00	5.00	83.99	2,499.37	2.28	21.68	475,081.33	707,533.20	32.304926	-103.795413
2,600.00	6.00	83.99	2,598.90	3.29	31.21	475,082.34	707,542.73	32.304928	-103.795382
2,700.00	7.00	83.99	2,698.26	4.47	42.47	475,083.52	707,553.99	32.304931	-103.795346
2,709.47	7.09	83.99	2,707.66	4.59	43.63	475,083.64	707,555.14	32.304932	-103.795342
2,800.00	7.09	83.99	2,797.50	5.76	54.75	475,084.81	707,566.26	32.304935	-103.795306
2,900.00	7.09	83.99	2,896.73	7.06	67.03	475,086.11	707,578.55	32.304938	-103.795266
3,000.00	7.09	83.99	2,995.96	8.35	79.31	475,087.40	707,590.83	32.304942	-103.795227
3,100.00	7.09	83.99	3,095.20	9.64	91.60	475,088.69	707,603.11	32.304945	-103.795187
3,200.00	7.09	83.99	3,194.43	10.93	103.88	475,089.99	707,615.40	32.304948	-103.795147
3,300.00	7.09	83.99	3,293.67	12.23	116.16	475,091.28	707,627.68	32.304952	-103.795107
3,400.00	7.09	83.99	3,392.90	13.52	128.45	475,092.57	707,639.96	32.304955	-103.795068
3,500.00	7.09	83.99	3,492.14	14.81	140.73	475,093.86	707,652.24	32.304958	-103.795028
3,600.00	7.09	83.99	3,591.37	16.11	153.01	475,095.16	707,664.53	32.304962	-103.794988
3,700.00	7.09	83.99	3,690.60	17.40	165.30	475,096.45	707,676.81	32.304965	-103.794948
3,800.00	7.09	83.99	3,789.84	18.69	177.58	475,097.74	707,689.09	32.304969	-103.794909
3,900.00	7.09	83.99	3,889.07	19.99	189.86	475,099.04	707,701.38	32.304972	-103.794869
4,000.00	7.09	83.99	3,988.31	21.28	202.14	475,100.33	707,713.66	32.304975	-103.794829
4,100.00	7.09	83.99	4,087.54	22.57	214.43	475,101.62	707,725.94	32.304979	-103.794789
4,200.00	7.09	83.99	4,186.78	23.86	226.71	475,102.91	707,738.23	32.304982	-103.794749
4,300.00	7.09	83.99	4,286.01	25.16	238.99	475,104.21	707,750.51	32.304986	-103.794710
4,400.00	7.09	83.99	4,385.24	26.45	251.28	475,105.50	707,762.79	32.304989	-103.794670
4,500.00	7.09	83.99	4,484.48	27.74	263.56	475,106.79	707,775.08	32.304992	-103.794630
4,600.00	7.09	83.99	4,583.71	29.04	275.84	475,108.09	707,787.36	32.304996	-103.794590
4,700.00	7.09	83.99	4,682.95	30.33	288.13	475,109.38	707,799.64	32.304999	-103.794551
4,800.00	7.09	83.99	4,782.18	31.62	300.41	475,110.67	707,811.92	32.305002	-103.794511
4,900.00	7.09	83.99	4,881.42	32.91	312.69	475,111.97	707,824.21	32.305006	-103.794471
5,000.00	7.09	83.99	4,980.65	34.21	324.98	475,113.26	707,836.49	32.305009	-103.794431
5,100.00	7.09	83.99	5,079.89	35.50	337.26	475,114.55	707,848.77	32.305013	-103.794391
5,200.00	7.09	83.99	5,179.12	36.79	349.54	475,115.84	707,861.06	32.305016	-103.794352
5,300.00	7.09	83.99	5,278.35	38.09	361.82	475,117.14	707,873.34	32.305019	-103.794312

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,400.00	7.09	83.99	5,377.59	39.38	374.11	475,118.43	707,885.62	32.305023	-103.794272
5,500.00	7.09	83.99	5,476.82	40.67	386.39	475,119.72	707,897.91	32.305026	-103.794232
5,600.00	7.09	83.99	5,576.06	41.97	398.67	475,121.02	707,910.19	32.305030	-103.794193
5,700.00	7.09	83.99	5,675.29	43.26	410.96	475,122.31	707,922.47	32.305033	-103.794153
5,800.00	7.09	83.99	5,774.53	44.55	423.24	475,123.60	707,934.75	32.305036	-103.794113
5,900.00	7.09	83.99	5,873.76	45.84	435.52	475,124.89	707,947.04	32.305040	-103.794073
6,000.00	7.09	83.99	5,972.99	47.14	447.81	475,126.19	707,959.32	32.305043	-103.794033
6,100.00	7.09	83.99	6,072.23	48.43	460.09	475,127.48	707,971.60	32.305046	-103.793994
6,200.00	7.09	83.99	6,171.46	49.72	472.37	475,128.77	707,983.89	32.305050	-103.793954
6,300.00	7.09	83.99	6,270.70	51.02	484.65	475,130.07	707,996.17	32.305053	-103.793914
6,400.00	7.09	83.99	6,369.93	52.31	496.94	475,131.36	708,008.45	32.305057	-103.793874
6,500.00	7.09	83.99	6,469.17	53.60	509.22	475,132.65	708,020.74	32.305060	-103.793835
6,600.00	7.09	83.99	6,568.40	54.90	521.50	475,133.95	708,033.02	32.305063	-103.793795
6,700.00	7.09	83.99	6,667.63	56.19	533.79	475,135.24	708,045.30	32.305067	-103.793755
6,800.00	7.09	83.99	6,766.87	57.48	546.07	475,136.53	708,057.58	32.305070	-103.793715
6,900.00	7.09	83.99	6,866.10	58.77	558.35	475,137.82	708,069.87	32.305074	-103.793675
7,000.00	7.09	83.99	6,965.34	60.07	570.64	475,139.12	708,082.15	32.305077	-103.793636
7,100.00	7.09	83.99	7,064.57	61.36	582.92	475,140.41	708,094.43	32.305080	-103.793596
7,200.00	7.09	83.99	7,163.81	62.65	595.20	475,141.70	708,106.72	32.305084	-103.793556
7,300.00	7.09	83.99	7,263.04	63.95	607.49	475,143.00	708,119.00	32.305087	-103.793516
7,400.00	7.09	83.99	7,362.28	65.24	619.77	475,144.29	708,131.28	32.305090	-103.793477
7,500.00	7.09	83.99	7,461.51	66.53	632.05	475,145.58	708,143.57	32.305094	-103.793437
7,600.00	7.09	83.99	7,560.74	67.82	644.33	475,146.88	708,155.85	32.305097	-103.793397
7,700.00	7.09	83.99	7,659.98	69.12	656.62	475,148.17	708,168.13	32.305101	-103.793357
7,800.00	7.09	83.99	7,759.21	70.41	668.90	475,149.46	708,180.41	32.305104	-103.793317
7,900.00	7.09	83.99	7,858.45	71.70	681.18	475,150.75	708,192.70	32.305107	-103.793278
8,000.00	7.09	83.99	7,957.68	73.00	693.47	475,152.05	708,204.98	32.305111	-103.793238
8,100.00	7.09	83.99	8,056.92	74.29	705.75	475,153.34	708,217.26	32.305114	-103.793198
8,200.00	7.09	83.99	8,156.15	75.58	718.03	475,154.63	708,229.55	32.305117	-103.793158
8,300.00	7.09	83.99	8,255.38	76.88	730.32	475,155.93	708,241.83	32.305121	-103.793119
8,400.00	7.09	83.99	8,354.62	78.17	742.60	475,157.22	708,254.11	32.305124	-103.793079
8,500.00	7.09	83.99	8,453.85	79.46	754.88	475,158.51	708,266.40	32.305128	-103.793039
8,600.00	7.09	83.99	8,553.09	80.75	767.16	475,159.80	708,278.68	32.305131	-103.792999
8,700.00	7.09	83.99	8,652.32	82.05	779.45	475,161.10	708,290.96	32.305134	-103.792959
8,800.00	7.09	83.99	8,751.56	83.34	791.73	475,162.39	708,303.25	32.305138	-103.792920
8,900.00	7.09	83.99	8,850.79	84.63	804.01	475,163.68	708,315.53	32.305141	-103.792880
9,000.00	7.09	83.99	8,950.02	85.93	816.30	475,164.98	708,327.81	32.305145	-103.792840
9,100.00	7.09	83.99	9,049.26	87.22	828.58	475,166.27	708,340.09	32.305148	-103.792800
9,200.00	7.09	83.99	9,148.49	88.51	840.86	475,167.56	708,352.38	32.305151	-103.792761
9,300.00	7.09	83.99	9,247.73	89.80	853.15	475,168.86	708,364.66	32.305155	-103.792721
9,400.00	7.09	83.99	9,346.96	91.10	865.43	475,170.15	708,376.94	32.305158	-103.792681
9,500.00	7.09	83.99	9,446.20	92.39	877.71	475,171.44	708,389.23	32.305161	-103.792641
9,600.00	7.09	83.99	9,545.43	93.68	890.00	475,172.73	708,401.51	32.305165	-103.792602
9,700.00	7.09	83.99	9,644.67	94.98	902.28	475,174.03	708,413.79	32.305168	-103.792562
9,800.00	7.09	83.99	9,743.90	96.27	914.56	475,175.32	708,426.08	32.305172	-103.792522
9,851.73	7.09	83.99	9,795.23	96.94	920.91	475,175.99	708,432.43	32.305173	-103.792501
9,900.00	6.37	83.99	9,843.17	97.53	926.54	475,176.58	708,438.06	32.305175	-103.792483
10,000.00	4.87	83.99	9,942.69	98.56	936.28	475,177.61	708,447.80	32.305178	-103.792452
10,100.00	3.37	83.99	10,042.43	99.31	943.43	475,178.36	708,454.94	32.305180	-103.792428
10,200.00	1.87	83.99	10,142.32	99.79	947.98	475,178.84	708,459.49	32.305181	-103.792414
10,300.00	0.37	83.99	10,242.30	99.99	949.92	475,179.04	708,461.43	32.305181	-103.792407
10,324.70	0.00	0.00	10,267.00	100.00	950.00	475,179.05	708,461.51	32.305181	-103.792407
10,400.00	0.00	0.00	10,342.30	100.00	950.00	475,179.05	708,461.51	32.305181	-103.792407
10,500.00	0.00	0.00	10,442.30	100.00	950.00	475,179.05	708,461.51	32.305181	-103.792407
10,600.00	0.00	0.00	10,542.30	100.00	950.00	475,179.05	708,461.51	32.305181	-103.792407

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
10,674.74	0.00	0.00	10,617.04	100.00	950.00	475,179.05	708,461.51	32.305181	-103.792407
KOP & FTP @ 10675' MD, 2380' FNL, 330' FEL									
10,700.00	2.53	359.67	10,642.29	100.56	950.00	475,179.61	708,461.51	32.305183	-103.792407
10,800.00	12.53	359.67	10,741.30	113.64	949.92	475,192.69	708,461.44	32.305219	-103.792407
10,900.00	22.53	359.67	10,836.54	143.71	949.75	475,222.76	708,461.26	32.305302	-103.792407
11,000.00	32.53	359.67	10,925.11	189.87	949.48	475,268.92	708,461.00	32.305428	-103.792407
11,100.00	42.53	359.67	11,004.31	250.70	949.13	475,329.75	708,460.65	32.305596	-103.792408
11,200.00	52.53	359.67	11,071.75	324.36	948.71	475,403.41	708,460.22	32.305798	-103.792408
11,300.00	62.53	359.67	11,125.38	408.62	948.23	475,487.67	708,459.74	32.306030	-103.792408
11,400.00	72.53	359.67	11,163.56	500.90	947.70	475,579.95	708,459.21	32.306283	-103.792408
11,500.00	82.53	359.67	11,185.13	598.42	947.14	475,677.47	708,458.65	32.306551	-103.792408
11,574.75	90.00	359.67	11,190.00	672.95	946.71	475,752.00	708,458.22	32.306756	-103.792409
11,600.00	90.00	359.67	11,190.00	698.20	946.56	475,777.25	708,458.08	32.306826	-103.792409
11,700.00	90.00	359.67	11,190.00	798.20	945.99	475,877.25	708,457.50	32.307101	-103.792409
11,800.00	90.00	359.67	11,190.00	898.20	945.41	475,977.25	708,456.93	32.307376	-103.792409
11,900.00	90.00	359.67	11,190.00	998.20	944.84	476,077.25	708,456.35	32.307650	-103.792409
12,000.00	90.00	359.67	11,190.00	1,098.20	944.26	476,177.24	708,455.78	32.307925	-103.792409
12,100.00	90.00	359.67	11,190.00	1,198.19	943.69	476,277.24	708,455.20	32.308200	-103.792410
12,200.00	90.00	359.67	11,190.00	1,298.19	943.11	476,377.24	708,454.63	32.308475	-103.792410
12,300.00	90.00	359.67	11,190.00	1,398.19	942.54	476,477.24	708,454.05	32.308750	-103.792410
12,400.00	90.00	359.67	11,190.00	1,498.19	941.96	476,577.24	708,453.48	32.309025	-103.792410
12,500.00	90.00	359.67	11,190.00	1,598.19	941.39	476,677.24	708,452.90	32.309300	-103.792411
12,600.00	90.00	359.67	11,190.00	1,698.19	940.82	476,777.23	708,452.33	32.309575	-103.792411
12,700.00	90.00	359.67	11,190.00	1,798.18	940.24	476,877.23	708,451.75	32.309849	-103.792411
12,800.00	90.00	359.67	11,190.00	1,898.18	939.67	476,977.23	708,451.18	32.310124	-103.792411
12,900.00	90.00	359.67	11,190.00	1,998.18	939.09	477,077.23	708,450.61	32.310399	-103.792412
13,000.00	90.00	359.67	11,190.00	2,098.18	938.52	477,177.23	708,450.03	32.310674	-103.792412
13,100.00	90.00	359.67	11,190.00	2,198.18	937.94	477,277.22	708,449.46	32.310949	-103.792412
13,200.00	90.00	359.67	11,190.00	2,298.18	937.37	477,377.22	708,448.88	32.311224	-103.792412
13,300.00	90.00	359.67	11,190.00	2,398.17	936.79	477,477.22	708,448.31	32.311499	-103.792412
13,382.00	90.00	359.67	11,190.00	2,480.17	936.32	477,559.22	708,447.84	32.311724	-103.792413
Cross section @ 13382' MD, 0' FSL, 330' FEL									
13,400.00	90.00	359.67	11,190.00	2,498.17	936.22	477,577.22	708,447.73	32.311774	-103.792413
13,500.00	90.00	359.67	11,190.00	2,598.17	935.64	477,677.22	708,447.16	32.312048	-103.792413
13,600.00	90.00	359.67	11,190.00	2,698.17	935.07	477,777.22	708,446.58	32.312323	-103.792413
13,700.00	90.00	359.67	11,190.00	2,798.17	934.49	477,877.21	708,446.01	32.312598	-103.792413
13,800.00	90.00	359.67	11,190.00	2,898.17	933.92	477,977.21	708,445.43	32.312873	-103.792414
13,900.00	90.00	359.67	11,190.00	2,998.16	933.34	478,077.21	708,444.86	32.313148	-103.792414
14,000.00	90.00	359.67	11,190.00	3,098.16	932.77	478,177.21	708,444.28	32.313423	-103.792414
14,100.00	90.00	359.67	11,190.00	3,198.16	932.20	478,277.21	708,443.71	32.313698	-103.792414
14,200.00	90.00	359.67	11,190.00	3,298.16	931.62	478,377.20	708,443.13	32.313973	-103.792414
14,300.00	90.00	359.67	11,190.00	3,398.16	931.05	478,477.20	708,442.56	32.314247	-103.792415
14,400.00	90.00	359.67	11,190.00	3,498.16	930.47	478,577.20	708,441.99	32.314522	-103.792415
14,500.00	90.00	359.67	11,190.00	3,598.15	929.90	478,677.20	708,441.41	32.314797	-103.792415
14,600.00	90.00	359.67	11,190.00	3,698.15	929.32	478,777.20	708,440.84	32.315072	-103.792415
14,700.00	90.00	359.67	11,190.00	3,798.15	928.75	478,877.19	708,440.26	32.315347	-103.792416
14,800.00	90.00	359.67	11,190.00	3,898.15	928.17	478,977.19	708,439.69	32.315622	-103.792416
14,900.00	90.00	359.67	11,190.00	3,998.15	927.60	479,077.19	708,439.11	32.315897	-103.792416
15,000.00	90.00	359.67	11,190.00	4,098.15	927.02	479,177.19	708,438.54	32.316172	-103.792416
15,100.00	90.00	359.67	11,190.00	4,198.15	926.45	479,277.19	708,437.96	32.316446	-103.792416
15,200.00	90.00	359.67	11,190.00	4,298.14	925.87	479,377.19	708,437.39	32.316721	-103.792417
15,300.00	90.00	359.67	11,190.00	4,398.14	925.30	479,477.18	708,436.81	32.316996	-103.792417
15,400.00	90.00	359.67	11,190.00	4,498.14	924.72	479,577.18	708,436.24	32.317271	-103.792417
15,500.00	90.00	359.67	11,190.00	4,598.14	924.15	479,677.18	708,435.66	32.317546	-103.792417

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
15,600.00	90.00	359.67	11,190.00	4,698.14	923.58	479,777.18	708,435.09	32.317821	-103.792418
15,700.00	90.00	359.67	11,190.00	4,798.14	923.00	479,877.18	708,434.51	32.318096	-103.792418
15,800.00	90.00	359.67	11,190.00	4,898.13	922.43	479,977.17	708,433.94	32.318371	-103.792418
15,900.00	90.00	359.67	11,190.00	4,998.13	921.85	480,077.17	708,433.37	32.318645	-103.792418
16,000.00	90.00	359.67	11,190.00	5,098.13	921.28	480,177.17	708,432.79	32.318920	-103.792419
16,100.00	90.00	359.67	11,190.00	5,198.13	920.70	480,277.17	708,432.22	32.319195	-103.792419
16,200.00	90.00	359.67	11,190.00	5,298.13	920.13	480,377.17	708,431.64	32.319470	-103.792419
16,300.00	90.00	359.67	11,190.00	5,398.13	919.55	480,477.17	708,431.07	32.319745	-103.792419
16,400.00	90.00	359.67	11,190.00	5,498.12	918.98	480,577.16	708,430.49	32.320020	-103.792419
16,500.00	90.00	359.67	11,190.00	5,598.12	918.40	480,677.16	708,429.92	32.320295	-103.792420
16,600.00	90.00	359.67	11,190.00	5,698.12	917.83	480,777.16	708,429.34	32.320570	-103.792420
16,700.00	90.00	359.67	11,190.00	5,798.12	917.25	480,877.16	708,428.77	32.320845	-103.792420
16,800.00	90.00	359.67	11,190.00	5,898.12	916.68	480,977.16	708,428.19	32.321119	-103.792420
16,900.00	90.00	359.67	11,190.00	5,998.12	916.11	481,077.15	708,427.62	32.321394	-103.792421
17,000.00	90.00	359.67	11,190.00	6,098.11	915.53	481,177.15	708,427.04	32.321669	-103.792421
17,100.00	90.00	359.67	11,190.00	6,198.11	914.96	481,277.15	708,426.47	32.321944	-103.792421
17,200.00	90.00	359.67	11,190.00	6,298.11	914.38	481,377.15	708,425.90	32.322219	-103.792421
17,300.00	90.00	359.67	11,190.00	6,398.11	913.81	481,477.15	708,425.32	32.322494	-103.792421
17,400.00	90.00	359.67	11,190.00	6,498.11	913.23	481,577.14	708,424.75	32.322769	-103.792422
17,500.00	90.00	359.67	11,190.00	6,598.11	912.66	481,677.14	708,424.17	32.323044	-103.792422
17,600.00	90.00	359.67	11,190.00	6,698.10	912.08	481,777.14	708,423.60	32.323318	-103.792422
17,700.00	90.00	359.67	11,190.00	6,798.10	911.51	481,877.14	708,423.02	32.323593	-103.792422
17,800.00	90.00	359.67	11,190.00	6,898.10	910.93	481,977.14	708,422.45	32.323868	-103.792423
17,900.00	90.00	359.67	11,190.00	6,998.10	910.36	482,077.14	708,421.87	32.324143	-103.792423
18,000.00	90.00	359.67	11,190.00	7,098.10	909.78	482,177.13	708,421.30	32.324418	-103.792423
18,100.00	90.00	359.67	11,190.00	7,198.10	909.21	482,277.13	708,420.72	32.324693	-103.792423
18,200.00	90.00	359.67	11,190.00	7,298.09	908.63	482,377.13	708,420.15	32.324968	-103.792424
18,300.00	90.00	359.67	11,190.00	7,398.09	908.06	482,477.13	708,419.57	32.325243	-103.792424
18,400.00	90.00	359.67	11,190.00	7,498.09	907.49	482,577.13	708,419.00	32.325517	-103.792424
18,500.00	90.00	359.67	11,190.00	7,598.09	906.91	482,677.12	708,418.42	32.325792	-103.792424
18,600.00	90.00	359.67	11,190.00	7,698.09	906.34	482,777.12	708,417.85	32.326067	-103.792424
18,670.00	90.00	359.67	11,190.00	7,768.09	905.93	482,847.12	708,417.45	32.326260	-103.792425
Cross section @ 18670' MD, 0' FSL, 330' FEL									
18,700.00	90.00	359.67	11,190.00	7,798.09	905.76	482,877.12	708,417.28	32.326342	-103.792425
18,800.00	90.00	359.67	11,190.00	7,898.08	905.19	482,977.12	708,416.70	32.326617	-103.792425
18,900.00	90.00	359.67	11,190.00	7,998.08	904.61	483,077.12	708,416.13	32.326892	-103.792425
19,000.00	90.00	359.67	11,190.00	8,098.08	904.04	483,177.12	708,415.55	32.327167	-103.792425
19,100.00	90.00	359.67	11,190.00	8,198.08	903.46	483,277.11	708,414.98	32.327442	-103.792426
19,200.00	90.00	359.67	11,190.00	8,298.08	902.89	483,377.11	708,414.40	32.327716	-103.792426
19,300.00	90.00	359.67	11,190.00	8,398.08	902.31	483,477.11	708,413.83	32.327991	-103.792426
19,400.00	90.00	359.67	11,190.00	8,498.07	901.74	483,577.11	708,413.25	32.328266	-103.792426
19,500.00	90.00	359.67	11,190.00	8,598.07	901.16	483,677.11	708,412.68	32.328541	-103.792426
19,600.00	90.00	359.67	11,190.00	8,698.07	900.59	483,777.10	708,412.10	32.328816	-103.792427
19,700.00	90.00	359.67	11,190.00	8,798.07	900.01	483,877.10	708,411.53	32.329091	-103.792427
19,800.00	90.00	359.67	11,190.00	8,898.07	899.44	483,977.10	708,410.95	32.329366	-103.792427
19,900.00	90.00	359.67	11,190.00	8,998.07	898.87	484,077.10	708,410.38	32.329641	-103.792427
20,000.00	90.00	359.67	11,190.00	9,098.06	898.29	484,177.10	708,409.80	32.329915	-103.792428
20,100.00	90.00	359.67	11,190.00	9,198.06	897.72	484,277.09	708,409.23	32.330190	-103.792428
20,200.00	90.00	359.67	11,190.00	9,298.06	897.14	484,377.09	708,408.66	32.330465	-103.792428
20,300.00	90.00	359.67	11,190.00	9,398.06	896.57	484,477.09	708,408.08	32.330740	-103.792428
20,400.00	90.00	359.67	11,190.00	9,498.06	895.99	484,577.09	708,407.51	32.331015	-103.792428
20,500.00	90.00	359.67	11,190.00	9,598.06	895.42	484,677.09	708,406.93	32.331290	-103.792429
20,600.00	90.00	359.67	11,190.00	9,698.05	894.84	484,777.09	708,406.36	32.331565	-103.792429
20,700.00	90.00	359.67	11,190.00	9,798.05	894.27	484,877.08	708,405.78	32.331840	-103.792429

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
20,800.00	90.00	359.67	11,190.00	9,898.05	893.69	484,977.08	708,405.21	32.332114	-103.792429
20,900.00	90.00	359.67	11,190.00	9,998.05	893.12	485,077.08	708,404.63	32.332389	-103.792430
21,000.00	90.00	359.67	11,190.00	10,098.05	892.54	485,177.08	708,404.06	32.332664	-103.792430
21,100.00	90.00	359.67	11,190.00	10,198.05	891.97	485,277.08	708,403.48	32.332939	-103.792430
21,200.00	90.00	359.67	11,190.00	10,298.04	891.39	485,377.07	708,402.91	32.333214	-103.792430
21,300.00	90.00	359.67	11,190.00	10,398.04	890.82	485,477.07	708,402.33	32.333489	-103.792431
21,400.00	90.00	359.67	11,190.00	10,498.04	890.25	485,577.07	708,401.76	32.333764	-103.792431
21,500.00	90.00	359.67	11,190.00	10,598.04	889.67	485,677.07	708,401.18	32.334039	-103.792431
21,600.00	90.00	359.67	11,190.00	10,698.04	889.10	485,777.07	708,400.61	32.334313	-103.792431
21,700.00	90.00	359.67	11,190.00	10,798.04	888.52	485,877.07	708,400.04	32.334588	-103.792431
21,800.00	90.00	359.67	11,190.00	10,898.03	887.95	485,977.06	708,399.46	32.334863	-103.792432
21,900.00	90.00	359.67	11,190.00	10,998.03	887.37	486,077.06	708,398.89	32.335138	-103.792432
22,000.00	90.00	359.67	11,190.00	11,098.03	886.80	486,177.06	708,398.31	32.335413	-103.792432
22,100.00	90.00	359.67	11,190.00	11,198.03	886.22	486,277.06	708,397.74	32.335688	-103.792432
22,200.00	90.00	359.67	11,190.00	11,298.03	885.65	486,377.06	708,397.16	32.335963	-103.792433
22,300.00	90.00	359.67	11,190.00	11,398.03	885.07	486,477.05	708,396.59	32.336238	-103.792433
22,400.00	90.00	359.67	11,190.00	11,498.02	884.50	486,577.05	708,396.01	32.336512	-103.792433
22,500.00	90.00	359.67	11,190.00	11,598.02	883.92	486,677.05	708,395.44	32.336787	-103.792433
22,600.00	90.00	359.67	11,190.00	11,698.02	883.35	486,777.05	708,394.86	32.337062	-103.792433
22,700.00	90.00	359.67	11,190.00	11,798.02	882.77	486,877.05	708,394.29	32.337337	-103.792434
22,800.00	90.00	359.67	11,190.00	11,898.02	882.20	486,977.04	708,393.71	32.337612	-103.792434
22,900.00	90.00	359.67	11,190.00	11,998.02	881.63	487,077.04	708,393.14	32.337887	-103.792434
23,000.00	90.00	359.67	11,190.00	12,098.01	881.05	487,177.04	708,392.56	32.338162	-103.792434
23,100.00	90.00	359.67	11,190.00	12,198.01	880.48	487,277.04	708,391.99	32.338437	-103.792435
23,200.00	90.00	359.67	11,190.00	12,298.01	879.90	487,377.04	708,391.42	32.338711	-103.792435
23,300.00	90.00	359.67	11,190.00	12,398.01	879.33	487,477.04	708,390.84	32.338986	-103.792435
23,400.00	90.00	359.67	11,190.00	12,498.01	878.75	487,577.03	708,390.27	32.339261	-103.792435
23,500.00	90.00	359.67	11,190.00	12,598.01	878.18	487,677.03	708,389.69	32.339536	-103.792435
23,600.00	90.00	359.67	11,190.00	12,698.00	877.60	487,777.03	708,389.12	32.339811	-103.792436
23,700.00	90.00	359.67	11,190.00	12,798.00	877.03	487,877.03	708,388.54	32.340086	-103.792436
23,800.00	90.00	359.67	11,190.00	12,898.00	876.45	487,977.03	708,387.97	32.340361	-103.792436
23,842.00	90.00	359.67	11,190.00	12,940.00	876.21	488,019.03	708,387.73	32.340476	-103.792436
LTP @ 23842' MD, 100' FNL, 330' FEL									
23,900.00	90.00	359.67	11,190.00	12,998.00	875.88	488,077.02	708,387.39	32.340636	-103.792436
23,922.03	90.00	359.67	11,190.00	13,020.03	875.75	488,099.05	708,387.27	32.340696	-103.792436
PBHL; 20' FNL, 330' FEL									
23,922.04	90.00	359.67	11,190.00	13,020.04	875.75	488,099.06	708,387.27	32.340696	-103.792436

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL - Fiji 17-5 Fed Cor	0.00	0.00	0.00	13,020.04	875.75	488,099.06	708,387.27	32.340696	-103.792436
- plan misses target center by 11190.00ft at 23922.04ft MD (11190.00 TVD, 13020.04 N, 875.75 E)									
- Point									

Database:	EDM r5000.141_Prod US	**Local Co-ordinate Reference:**	Well Fiji 17-5 Fed Com 334H
Company:	WCDSC Permian NM	**TVD Reference:**	RKB @ 3368.30ft
Project:	Eddy County (NAD 83 NM Eastern)	**MD Reference:**	RKB @ 3368.30ft
Site:	Sec 17-T23S-R31E	**North Reference:**	Grid
Well:	Fiji 17-5 Fed Com 334H	**Survey Calculation Method:**	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Permit Plan 1		

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	Local Coordinates +E/-W (ft)	Comment
10,674.74	10,617.04	100.00	950.00	KOP & FTP @ 10675' MD, 2380' FNL, 330' FEL
13,382.00	11,190.00	2,480.17	936.32	Cross section @ 13382' MD, 0' FSL, 330' FEL
18,670.00	11,190.00	7,768.09	905.93	Cross section @ 18670' MD, 0' FSL, 330' FEL
23,842.00	11,190.00	12,940.00	876.21	LTP @ 23842' MD, 100' FNL, 330' FEL
23,922.03	11,190.00	13,020.03	875.75	PBHL; 20' FNL, 330' FEL

Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015

Hydrogen Sulfide (H_2S) Contingency Plan

For

Fiji 17-5 Fed Com 334H

Sec-17 T-23S R-31E
2480’ FNL & 1280’ FEL
LAT. = 32.3049196’ N (NAD83)
LONG = 103.7954833’ W

Eddy County NM

Fiji 17-5 Fed Com 334H

This is an open drilling site. H_2S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H_2S, including warning signs, wind indicators and H_2S monitor.



Assumed 100 ppm ROE = 3000' (Radius of Exposure)
100 ppm H2S concentration shall trigger activation of this plan.

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H_2S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H_2S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H_2S monitors and air packs in order to control the release.**
- **Use the "buddy system" to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
  - **Detection of H_2S, and**
  - **Measures for protection against the gas,**
  - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO_2). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H_2S and SO_2

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H_2S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO_2	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H_2S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H_2S)

2. The proper use and maintenance of personal protective equipment and life support systems.

3. The proper use of H_2S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.

4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H_2S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.

2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.

3. The contents and requirements of the H_2S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H_2S zone (within 3 days or 500 feet) and weekly H_2S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H_2S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H_2S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H_2S.

1. **Well Control Equipment**

   A. Flare line

   B. Choke manifold – Remotely Operated

   C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit

   D. Auxiliary equipment may include if applicable: annular preventer and rotating head.

   E. Mud/Gas Separator

2. **Protective equipment for essential personnel:**

   30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. **H_2S detection and monitoring equipment:**

   Portable H_2S monitors positioned on location for best coverage and response. These units have warning lights which activate when H_2S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

   - **Bell nipple**
   - **Rig floor**
   - **Cellar**
   - **Possum Belly/Shale shaker**
   - **Choke manifold**

   Visual warning systems:

   A. Wind direction indicators as shown on well site diagram

   B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. **Mud program:**

   The mud program has been designed to minimize the volume of H_2S circulated to surface. Proper mud weight, safe drilling practices and the use of H_2S scavengers will minimize hazards when penetrating H_2S bearing zones.

5. **Metallurgy:**

   A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H_2S trim.

   B. All elastomers used for packing and seals shall be H_2S trim.

6. **Communication:**

   A. Company personnel have/use cellular telephones in the field.

   B. Land line (telephone) communications at Office

7. **Well testing:**

   A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H_2S environment will use the closed chamber method of testing.

   B. There will be no drill stem testing.

Devon Energy Corp. Company Call List		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
Agency Call List		
Lea County (575)	**Hobbs**	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	**911**
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
Eddy County (575)	**Carlsbad**	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	Ambulance	**911**
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	Emergency Services	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control (915) 699-0139	(915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
Give GPS position:	Native Air – Emergency Helicopter – Hobbs (TX & NM)	(800) 642-7828
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small


Devon Energy - Well Pad
Rig Location Layout
Safety Equipment Location
N
Prevailing Wind
Direction S, SW
CAUTION
H2S Poison Gas
May Be Present
Secondary Egress
FLARE
IGNITER
Flare stack with
Electronic Igniter
450 ft.
Frac Tank & Water Storage
Mud Storage
Closed Loop
Equip
Mud Logger
4" Panic line 150ft from wellbore
Mud/Gas Separator
Volume Tanks
Process Tanks
Shakers
Pipe Racks
Water Tank
Trip
Tank
Choke
Choke Manifold
(with Remotely Operated
Choke)
Diesel Tank
Generator
Generator
Generator
VFD House
Parts House
Mud Pump
Mud Pump
Rig
Floor
Draw
works
570 ft.
180 ft.
Spool
H2S Sensor Beneath
Rig Floor
BOP Skid
Driller's
Cabin
Parts
House
HPU/Accumulator
150 ft.
Location Dimensions
600 ft x 750 ft
Not to Scale
Wellhead Location
Wind Indicators
Location Entrance Warning
Sign used to control location
in event of an emergency
Safe Briefing Area
Self-Contained Breathing
Apparatus (SCBA)
H2S Sensors Located
Around the Rig
H2S Monitor Control/
Alarm box
Primary Briefing Area
Crew Housing
Change House
Rig Manager House
Potable
Water
Co Man Housing
Directional Housing

PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	**Devon Energy Production Company LP**
LEASE NO.:	**NMNM045235**
LOCATION:	Section 17, T.23 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

WELL NAME & NO.:	Fiji 17-5 Fed Com 333H
SURFACE HOLE FOOTAGE:	2330'/N & 1610'/E
BOTTOM HOLE FOOTAGE	20'/N & 1650'/E

WELL NAME & NO.:	Fiji 17-5 Fed Com 334H
SURFACE HOLE FOOTAGE:	2480'/N & 1280'/E
BOTTOM HOLE FOOTAGE	20'/N & 330'/E

WELL NAME & NO.:	Fiji 17-5 Fed Com 623H
SURFACE HOLE FOOTAGE:	2330'/N & 1670'/E
BOTTOM HOLE FOOTAGE	20'/N & 2310'/E

WELL NAME & NO.:	Fiji 17-5 Fed Com 624H
SURFACE HOLE FOOTAGE:	2480'/N & 1340'/E
BOTTOM HOLE FOOTAGE	20'/N & 990'/E

WELL NAME & NO.:	Fiji 17-5 Fed Com 713H
SURFACE HOLE FOOTAGE:	2330'/N & 1640'/E
BOTTOM HOLE FOOTAGE	20'/N & 1750'/E

WELL NAME & NO.:	Fiji 17-5 Fed Com 714H
SURFACE HOLE FOOTAGE:	2480'/N & 1310'/E
BOTTOM HOLE FOOTAGE	20'/N & 430'/E

COA

H2S	◉ Yes	○ No	
Potash	○ None	◉ Secretary	○ R-111-P
Cave/Karst Potential	◉ Low	○ Medium	○ High
Cave/Karst Potential	○ Critical		
Variance	○ None	◉ Flex Hose	○ Other
Wellhead	○ Conventional	◉ Multibowl	○ Both
Other	☐ 4 String Area	☐ Capitan Reef	☐ WIPP
Other	☑ Fluid Filled	☑ Cement Squeeze	☐ Pilot Hole
Special Requirements	☐ Water Disposal	☑ COM	☐ Unit

Approval Date: 11/03/2020

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Triste Draw/Sand Dune** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **525 feet** (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.

    a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
    b. Wait on cement (WOC) time for a primary cement job will be a minimum of **24 hours in the Potash Area** or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

    c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
    d. If cement falls back, remedial cementing will be done prior to drilling out that string.

    Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

2. The minimum required fill of cement behind the **8-5/8** inch intermediate casing is:

    - Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.**
      Cement excess is less than 25%, more cement might be required.

    ❖ In Secretary Potash Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

Operator has proposed to pump down 13-3/8" X 8-5/8" annulus. Operator must run a CBL from TD of the 8-5/8" casing to surface. Submit results to BLM.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:

    - Cement should tie-back at least **500 feet** into previous casing string. Operator shall provide method of verification.
      Cement excess is less than 25%, more cement might be required.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M)** psi.

    a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
    b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
    c. Manufacturer representative shall install the test plug for the initial BOP test.
    d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
    e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Santa Fe Office, 301 Dinosaur Trail Santa Fe, New Mexico 87508, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

☒ Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

☒ Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575) 393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.

   a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
   b. When the operator proposes to set surface casing with Spudder Rig
      - Notify the BLM when moving in and removing the Spudder Rig.
      - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
      - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.

2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.

3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing intergrity test can be done (prior to the cement setting up) immediately after bumping the plug.

4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.

5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.

7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.

3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.

4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:

    a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
    b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
    c. Manufacturer representative shall install the test plug for the initial BOP test.
    d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
    e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

    a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).

c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.

e. The results of the test shall be reported to the appropriate BLM office.

f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.

g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.