

**Mobil Federal 9
OXY USA Inc.
November 12, 2011
Conditions of Approval**

- 1. Surface disturbance beyond the originally approved pad must have prior approval.**
- 2. Closed loop system required.**
- 3. Operator to have H2S monitoring equipment on location.**
- 4. A minimum of a 3000 (3M) BOP to be used. All blowout preventer (BOP) and related equipment (BOPE) shall comply with reasonable well control requirements. A two ram system with a blind ram and a pipe ram designed for the size of the work string shall be adequate. Tapered work strings will require an additional pipe ram. The manifold shall comply with Onshore Oil and Gas Order #2 Attachment I (3M Diagrams of Choke Manifold Equipment). The accumulator system shall have an immediately available power source to close the rams and retain 200 psi above pre-charge. The pre-charge test shall follow requirements in Onshore Order #2.**
- 5. All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of work over operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area. Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.**
- 6. Operator limited to 3700 psi on the frac down the casing. This is based on 70% of the 5.5" 17# J-55 casing's burst rating.**
- 7. Operator to submit a subsequent sundry with details of work performed including a new well test. Due to classification as one pool under order R-10086, no completion report is required.**

WWI 111211