

RECEIVED
MAR 11 2013
NMOCD ARTESIA

Form 3160-3
(April 2004)

Operator Copy

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0137
Expires March 31, 2007

5. Lease Serial No.
S-Fee BH-NMNM/088138 *TES*

6. If Indian, Allottee or Tribe Name
3/13/2013

1a. Type of work: DRILL REENTER

7. If Unit or CA Agreement, Name and No.

1b. Type of Well: Oil Well Gas Well Other Single Zone Multiple Zone

8. Lease Name and Well No.
Cedar Canyon 23 #2H *<39437>*

2. Name of Operator
OXY USA Inc. *< 16696 >*

9. API Well No.
30-015- *41194*

3a. Address
P.O. Box 50250
Midland, TX 79710

3b. Phone No. (include area code)
432-685-5717

10. Field and Pool, or Exploratory
Corral Draw Bone Spring *<96238>*

4. Location of Well (Report location clearly and in accordance with any State requirements.)
At surface 660 FSL 660 FWL SWSW(M)
At proposed prod. zone 660 FSL 380 FEL SESE(P)

11. Sec., T. R. M. or Blk. and Survey or Area
Sec 23 T24S R29E

14. Distance in miles and direction from nearest town or post office*
6 miles northeast from Loving, NM

12. County or Parish
Eddy

13. State
NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 380'

16. No. of acres in lease
1280

17. Spacing Unit dedicated to this well
160

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 2558'

19. Proposed Depth
11574'M 7911'V

20. BLM/BIA Bond No. on file
NMB000862 - ESB00226 - 022032304

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
2927' GL

22. Approximate date work will start*
03/01/2013

23. Estimated duration
45 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature *[Signature]*

Name (Printed/Typed)
David Stewart

Date
11/19/12

Title
Regulatory Advisor

david_stewart@oxy.com

Approved by (Signature) *[Signature]*

Name (Printed/Typed)

Date
2/13/13

Title
FIELD MANAGER

Office
CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on page 2)

Carlsbad Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached

Operator must be in compliance with NMOCD Rule 5.9 prior to producing well

**SEE ATTACHED FOR
CONDITIONS OF APPROVAL**

*TES
3/12/2013*

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720

DISTRICT II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720

DISTRICT III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number 30-015-41194	Pool Code 96238-50371	Pool Name Pierce Crossing Carrot Draw Base Springs
Property Code 39439	Property Name CEDAR CANYON 23	Well Number 2H
OGRID No. 16694	Operator Name OXY U.S.A. INC.	Elevation 2927'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	23	24-S	29-E		660	SOUTH	660	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	23	24-S	29-E		660	SOUTH	380	EAST	EDDY


Dedicated Acres 160	Joint or Infill N	Consolidation Code	Order No.
-------------------------------	-----------------------------	--------------------	-----------

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>DETAIL</p> <p>2931.5' 600' 600' 2919.2' 2922.3'</p> <p>GEODETIC COORDINATES NAD 27 NME</p> <p>SURFACE LOCATION Y=435711.6 N X=615130.7 E</p> <p>LAT.=32.197340° N LONG.=103.961139° W</p> <p>BOTTOM HOLE LOCATION Y=435743.8 N X=619390.9 E</p> <p>LAT.=32.197388° N LONG.=103.947367° W</p> <p>CORNER COORDINATES</p> <p>(A) - Y=436373.2 N, X=614469.0 E (B) - Y=436411.1 N, X=619767.4 E (C) - Y=435046.6 N, X=614472.5 E (D) - Y=435086.9 N, X=619774.1 E</p> <p>PROJECT AREA</p> <p>PRODUCING AREA GRID AZ.=89°33'59" HORIZ. DIST.=4261.3'</p> <p>S.L. SEE DETAIL 660' 660' 660' 660'</p>	<p>OPERATOR CERTIFICATION</p> <p>I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or undivided mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>David Stewart</i> 11/19/12 Signature Date</p> <p>David Stewart P.O. Ado. Printed Name</p> <p>David.Stewart@oxy.com E-mail Address</p>
	<p>SURVEYOR CERTIFICATION</p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p>AUGUST 11, 2011</p> <p>Date of Survey</p> <p>Signature & Seal of Professional Surveyor:</p> <p></p> <p>Ronald J. Eidson 8/13/2012 Signature</p> <p>3239 Ronald J. Eidson 12641 Ronald J. Eidson 3239 Certificate Number</p> <p>DSS/DSM REG. W.C. 12.13.1053</p>

OPERATOR CERTIFICATION

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 19th day of Nov., 2012.



Name: Peter Lawrence
Position: Reservoir Management Team Leader
Address: 5 Greenway Plaza, Suite 110, Houston, TX 77046
Telephone: 713-215-7644
E-mail: (optional): peter_lawrence@oxy.com
Company: OXY USA Inc.
Field Representative (if not above signatory): Dusty Weaver
Address (if different from above): P.O. Box 50250 Midland, TX 79710
Telephone (if different from above): 432-685-5723
E-mail (if different from above): calvin_weaver@oxy.com

DRILLING PROGRAM

Operator Name/Number:	OXY USA Inc.	16696
Lease Name/Number:	Cedar Canyon 23 #2H	39439
Pool Name/Number:	Corral Draw Bone Spring	96238
Surface Location:	660 FSL 660 FWL SWSW(M) Sec 23 T24S R29E	Fee
Bottom Hole Location:	660 FSL 660 FEL SESE(P) Sec 23 T24S R29E	Federal Lease No. NMNM088138

Proposed TD:	7911' TVD	11574' TMD	Elevation: 2927' GL
SL - Lat: 32.197340	Long: 103.961139	X= 615130.7	Y= 435711.6
BH - Lat: 32.197388	Long: 103.947367	X= 619390.9	Y= 435743.8
			NAD - 1927
			NAD - 1927

1. Geologic Name of Surface Formation:

a. Permian

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

Geological Marker	Depth	Type
a. Rustler	400'	Formation
b. Top Salt	506'	Formation
c. Base Salt	2784'	Formation
d. Anhydrite	3024'	Oil
e. Bell Canyon	3074'	Oil
f. Cherry Canyon	3919'	Oil
g. Brushy Canyon	5219'	Oil
h. Bone Spring	6794'	Oil
i. 1st Bone Spring	7794'	Oil

Fresh water may be encountered above the Rustler formation. Surface casing will be set below the top of the Rustler to protect it. Per State Engineer website, fresh water has been found in the area as deep as 212'.

3. Casing Program:

Hole Size	Interval	OD Csg	Weight	Collar	Grade	Condition	Collapse Design Factor	Burst Design Factor	Tension Design Factor
17-1/2"	0-435'	13-3/8"	48	ST&C	H-40	New	4.31	9.34	12.33
				Hole filled with 8.9# Mud			770#	1730#	
12-1/4"	0-3150'	9-5/8"	40	LT&C	J-55	New	1.94	7	4.13
	3030			Hole filled with 10# Mud			2570#	3950#	
8-3/4"	0-11574'	5-1/2"	17	LT&C	L-80	New	2.32	2.83	1.78
	DVT @ 7000'			Hole filled with 9.2# Mud			6290#	7740#	

Collapse and burst loads calculated using Stress Check with anticipated loads

4. Cement Program

- a. 13-3/8" Surface Circulate cement to surface w/ 420sx PP cmt w/ 4% Bentonite + .125#/sx Poly-E-Flake + 2% CaCl₂, 13.5ppg 1.75 yield 589# 24hr CS 165% Excess followed by 200sx PP cmt w/ 2% CaCl₂, 14.8ppg 1.35 yield 1608# 24hr CS 165% Excess.
- b. 9-5/8" Intermediate Circulate cement to surface w/ 890sx HES light PP cmt w/ 5% Salt + .125#/sx Poly-E-Flake + 3#/sx Kol Seal, 12.9ppg 1.87 yield 840# 24hs CS 105% Excess followed by 200sx PP cmt w/ 1% CaCl₂, 14.8ppg 1.34 yield 2125# 24hr CS 105% Excess.

See COA

- c. 5-1/2" Production Cement 1st stage w/ 110sx HES light PP cmt w/ 3#/sx Kol Seal + 3#/sx salt + .3% HR-601, 12.4ppg 2.08 yield 460# 24hr CS 135% Excess followed by 1600sx Super H w/ 1#/sx salt .5% Halad-344 + .125#/sx Poly-E-Flake + 3#/sx Kol-Seal + .3% HR-601, 13.2ppg 1.61 yield 1372# 24hr CS 135% Excess, Calc TOC-6995'
- Cement 2nd stage w/ 1550sx HES light PP cmt w/ 3#/sx Kol Seal + 3#/sx salt, 12.4ppg 2.07 yield 610# 24hr CS 200% Excess followed by 100sx PP cmt w/ 1% CaCl₂, 14.8ppg 1.34 yield 1372# 24hr CS 200% Excess, Calc TOC-2600'

Description of Cement Additives: Calcium Chloride, Salt (Accelerator), Bentonite (Light Weight Additive), Kol-Seal, Poly-E-Flake (Lost Circulation Additive), Halad-344 (Low Fluid Loss Control), HR-601 (Retarder)

5. Pressure Control Equipment:

Surface: None

Intermediate/Production: 13-5/8" 10M three ram stack w/ 5M annular preventer, 5M Choke Manifold

All BOP's and associated equipment will be tested in accordance with Onshore Order #2 (250/5000 psi on rams for 10 minutes each and 250/3500 for 10 minutes for annular preventer, equal to 70% of working pressure) with a third party BOP testing service before drilling out the 13-3/8" casing shoe. Wellhead pressure rating will support this test and 13-3/8" casing will be protected from high pressure. Since the wellhead system is a multibowl design, this initial test will cover the requirements prior to drilling out the 9-5/8" casing shoe. *See COA - second test required.*

Pipe Rams will be operated and checked each 24-hour period and each time the drill pipe is out of the hole. These functional tests will be documented on the daily driller's log. A 2" kill line and 3" choke line will be accommodated on the drilling spool below the ram-type BOP. Other accessory BOP equipment will include a Kelly cock, floor safety valve, choke lines and choke manifold having a 5000 psi WP rating. OXY requests that the entire system be tested as a 5000psi WP rating.

OXY also requests a variance to connect the BOP outlet to the choke manifold using a co-flex hose that is manufactured by Contitech Rubber Industrial KFT. It is a 3" ID X 35' flexible hose rated to 10000psi working pressure. It has been tested to 15000psi and is built to API Spec 16C. Once the flex line is installed, it will be tied down with safety clamps, see attached for certifications.

6. Proposed Mud Circulation System

<u>Depth</u>	<u>Mud Wt.</u> ppg	<u>Visc</u> sec	<u>Fluid</u> <u>Loss</u>	<u>Type System</u>
0 - 435'	8.4-8.9	32-34	NC	Fresh Water/Spud Mud
435 - 3150 3030	9.8-10.0	28-29	NC	Brine Water
3150 - 7000'	8.6-8.8	28-29	NC	Fresh Water
7000 - TD'	9.0-9.2	40-50	8-15	LSND

Pump high viscosity sweeps as needed for hole cleaning. The mud system will be monitored visually/manually as well as with an electronic PVT. The necessary mud products for additional weight and fluid loss control will be on location at all times. Appropriately weighted mud will be used to isolate potential gas, oil, and water zones until such time as casing can be cemented into place for zonal isolation.

7. Auxiliary Well Control and Monitoring Equipment:

- A Kelly cock will be in the drill string at all times.
- A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor unobstructed and readily accessible at all times.

- c. Hydrogen Sulfide detection equipment will be in operation after drilling out the surface casing shoe until the production casing is cemented. Breathing equipment will be on location upon drilling the surface casing shoe until total depth is reached. If Hydrogen Sulfide is encountered, measured amounts and formations will be reported to the BLM.

8. Logging, Coring and Testing Program: *See COA*

- a. Drill stem tests are not anticipated but if done will be based on geological sample shows.
- b. The open hole electrical logging program will consist of a Triple Combo from build section to base of intermediate. MWD-GR from kick-off point to TD.
- c. No coring program is planned but if done will be sidewall rotary cores.
- d. Mud logging will be initiated from the base of intermediate casing to TD.

9. Potential Hazards:

No abnormal pressures, temperatures or H₂S gas are expected. The highest anticipated pressure gradient would be 0.47psi/ft. The bottomhole pressure is anticipated to be between 3700-3800psi. If H₂S is encountered the operator will comply with the provisions of Onshore Oil & Gas Order No.6.

All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well.

Adequate flare lines will be installed off the mud/gas separator where gas may be flared safely.

10. Anticipated Starting Date and Duration of Operations:

Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 35 days. If production casing is run, then an additional 30 days will be needed to complete the well and construct surface facilities and/or lay flow lines in order to place well on production.



Taylor Cann, RPL
Land Negotiator

OXY USA Inc.
Box 4294, Houston, TX 77210-4294

Phone (713) 366-5119
Cell (832) 291-9168
Fax (713) 985-1859
Taylor_Cann@oxy.com

United States Department of the Interior
Bureau of Land Management
Carlsbad Field Office
620 East Greene Street
Carlsbad, New Mexico 88220

Attention: Linda Denniston

RE: Cedar Canyon 23 2H

Eddy County, New Mexico

STATEMENT ACCEPTING RESPONSIBILITY FOR OPERATIONS

OPERATOR NAME: OXY USA Inc.
ADDRESS: P.O. Box 4294
Houston, Texas 77210-4294

The undersigned accepts all applicable terms, conditions, stipulations, and restrictions concerning operations conducted on the leased land or portion thereof, as described below:

LEASE NO.:	NMNM 88138 & NMNM 81586
LEGAL DESCRIPTION:	
Surface Location:	660' FSL & 660' FWL
Bottom Hole Location:	660' FSL & 380' FEL
	Section 23 T24S-R29E
	Eddy County, New Mexico
FORMATIONS:	Second Bone Spring
BOND COVERAGE:	Nationwide
BLM BOND FILE NO.:	Individual: NMB000862
	Nationwide: 022032304
	BLM: ESB00226

AUTHORIZED SIGNATURE:
OXY USA Inc.

Taylor Cann

TITLE: Land Negotiator

DATE: September 26, 2012

cc: David Stewart



New Mexico Office of the State Engineer Water Column/Average Depth to Water

No records found.

PLSS Search:

Section(s): 13, 14, 15, 22, Township: 24S
23, 24, 25, 26,
27

Range: 29E

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.



Cedar Canyon 23 #2H
Eddy Co, New Mexico




SECTION DETAILS										
Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.00	0.00	89.57	0.00	0.00	0.00	0.00	0.00	0.00	
2	7266.17	0.00	89.57	7266.17	0.00	0.00	0.00	0.00	0.00	
3	8154.10	88.79	89.57	7839.00	4.24	560.88	10.00	89.57	560.90	
4	11574.28	88.79	89.57	7911.00	30.10	3980.20	0.00	0.00	3980.31	Pbhl

SITE DETAILS	
Cedar Canyon 23 #2H	
Site Centre Northing:	435711.60
Easting:	615130.70
Ground Level:	2927.00
Positional Uncertainty:	0.00
Convergence:	0.20

WELL DETAILS							
Name	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
Cedar Canyon 23 #2H	0.00	0.00	435711.60	615130.70	32°11'50.426N	103°57'40.102W	N/A

TARGET DETAILS						
Name	TVD	+N/-S	+E/-W	Northing	Easting	Shape
Pbhl	7911.00	30.10	3980.20	435741.70	619110.90	Point

Azimuths to Grid North
Magnetic Declination: 7.68
Grid Convergence: .20
Total Correction: 7.48
Mag Model: BGGM2012
Total Correction to Grid North: 7.48°



Vertical Section at 89.57° [500ft/in]





Weatherford International Ltd.

WFT Plan Report - X & Y's



Weatherford

DP-2

Company: Occidental Permian Ltd	Date: 9/14/2012	Time: 08:00:35	Page: 1
Field: Eddy Co. NM (Nad 27)	Co-ordinate (NE) Reference: Well: Cedar Canyon 23 #2H Grid: North		
Site: Cedar Canyon 23 #2H	Vertical (TVD) Reference: SITE: 2951.0		
Well: Cedar Canyon 23 #2H	Section (VS) Reference: Well: (0.00N, 0.00E; 89.57Azi)		
Wellpath: 1	Survey Calculation Method: Minimum Curvature	Db: Sybase	

Plan: Plan #4	Date Composed: 9/14/2012
Principal: Yes	Version: 1
	Tied-to: From Surface

Site: Cedar Canyon 23 #2H			
Site Position:	Northing: 435711.60 ft	Latitude: 32 11 50.426 N	
From: Map	Easting: 615130.70 ft	Longitude: 103 57 40.102 W	
Position Uncertainty: 0.00 ft		North Reference: Grid	
Ground Level: 2927.00 ft		Grid Convergence: 0.20 deg	

Well: Cedar Canyon 23 #2H		Slot Name:	
Well Position: +N-S 0.00 ft	Northing: 435711.60 ft	Latitude: 32 11 50.426 N	
+E-W 0.00 ft	Easting: 615130.70 ft	Longitude: 103 57 40.102 W	
Position Uncertainty: 0.00 ft			

Wellpath: 1		Drilled From: Surface	
Current Datum: SITE	Height: 2951.00 ft	Tie-on Depth: 0.00 ft	
Magnetic Data: 1/1/2013		Above System Datum: Mean Sea Level	
Field Strength: 48407 nT		Declination: 7.68 deg	
Vertical Section: Depth From (TVD)	+N-S	Mag Dip Angle: 60.01 deg	
ft	ft	+E-W	Direction
		ft	deg
0.00	0.00	0.00	89.57

Plan Section Information

MD	Incl	Azim	TVD	+N-S	+E-W	DLS	Build	Turn	TFO	Target
ft	deg	deg	ft	ft	ft	deg/100ft	deg/100ft	deg/100ft	deg	
0.00	0.00	89.57	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7266.17	0.00	89.57	7266.17	0.00	0.00	0.00	0.00	0.00	0.00	
8154.10	88.79	89.57	7839.00	4.24	560.88	10.00	10.00	0.00	89.57	
11574.28	88.79	89.57	7911.00	30.10	3980.20	0.00	0.00	0.00	0.00	Pbhl

Survey

MD	Incl	Azim	TVD	N/S	E/W	VS	DLS	MapN	MapE	Comment
ft	deg	deg	ft	ft	ft	ft	deg/100ft	ft	ft	
7200.00	0.00	89.57	7200.00	0.00	0.00	0.00	0.00	435711.60	615130.70	
7266.17	0.00	89.57	7266.17	0.00	0.00	0.00	0.00	435711.60	615130.70	KOP
7300.00	3.38	89.57	7299.98	0.01	1.00	1.00	10.00	435711.61	615131.70	
7350.00	8.38	89.57	7349.70	0.05	6.12	6.12	10.00	435711.65	615136.82	
7400.00	13.38	89.57	7398.79	0.12	15.56	15.56	10.00	435711.72	615146.26	
7450.00	18.38	89.57	7446.86	0.22	29.24	29.24	10.00	435711.82	615159.94	
7500.00	23.38	89.57	7493.56	0.36	47.06	47.06	10.00	435711.96	615177.76	
7550.00	28.38	89.57	7538.53	0.52	68.88	68.88	10.00	435712.12	615199.58	
7600.00	33.38	89.57	7581.43	0.71	94.53	94.53	10.00	435712.31	615225.23	
7650.00	38.38	89.57	7621.93	0.94	123.83	123.83	10.00	435712.54	615254.53	
7700.00	43.38	89.57	7659.72	1.18	156.54	156.55	10.00	435712.78	615287.24	
7749.23	48.31	89.57	7694.00	1.45	191.85	191.86	10.00	435713.05	615322.55	
7750.00	48.38	89.57	7694.51	1.46	192.43	192.43	10.00	435713.06	615323.13	1st Bone Spring Sa
7800.00	53.38	89.57	7726.05	1.75	231.21	231.21	10.00	435713.35	615361.91	
7850.00	58.38	89.57	7754.08	2.06	272.59	272.59	10.00	435713.66	615403.29	
7900.00	63.38	89.57	7778.40	2.39	316.25	316.26	10.00	435713.99	615446.95	
7950.00	68.38	89.57	7798.83	2.74	361.87	361.88	10.00	435714.34	615492.57	
8000.00	73.38	89.57	7815.20	3.09	409.10	409.11	10.00	435714.69	615539.80	
8050.00	78.38	89.57	7827.39	3.46	457.57	457.59	10.00	435715.06	615588.27	
8100.00	83.38	89.57	7835.31	3.83	506.92	506.94	10.00	435715.43	615637.62	
8154.10	88.79	89.57	7839.00	4.24	560.88	560.90	10.00	435715.84	615691.58	LP
8200.00	88.79	89.57	7839.96	4.59	606.76	606.78	0.00	435716.19	615737.46	
8300.00	88.79	89.57	7842.07	5.34	706.74	706.76	0.00	435716.94	615837.44	



Weatherford International Ltd.

WFT Plan Report - X & Y's



Weatherford

DP-3

Company: Occidental Permin Ltd.	Date: 9/14/2012	Time: 08:00:35	Page: 2
Field: Eddy Co. NM (Nad 27)	Co-ordinate(NE) Reference: Well: Cedar Canyon 23 #2H, Grid North	Vertical (TVD) Reference: SITE 2951.0	
Site: Cedar Canyon 23 #2H	Section (VS) Reference: Well: (0.00N,0.00E,89.57Azi)	Survey Calculation Method: Minimum Curvature	Db: Sybase
Well: Cedar Canyon 23 #2H			
Wellpath: 1			

Survey

MD ft	Incl deg	Azim deg	TVD ft	N/S ft	E/W ft	VS ft	DLS deg/100ft	MapN ft	MapE ft	Comment
8400.00	88.79	89.57	7844.17	6.10	806.71	806.74	0.00	435717.70	615937.41	
8500.00	88.79	89.57	7846.28	6.86	906.69	906.72	0.00	435718.46	616037.39	
8600.00	88.79	89.57	7848.38	7.61	1006.66	1006.69	0.00	435719.21	616137.36	
8700.00	88.79	89.57	7850.49	8.37	1106.64	1106.67	0.00	435719.97	616237.34	
8800.00	88.79	89.57	7852.59	9.12	1206.61	1206.65	0.00	435720.72	616337.31	
8900.00	88.79	89.57	7854.70	9.88	1306.59	1306.63	0.00	435721.48	616437.29	
9000.00	88.79	89.57	7856.81	10.64	1406.56	1406.60	0.00	435722.24	616537.26	
9100.00	88.79	89.57	7858.91	11.39	1506.54	1506.58	0.00	435722.99	616637.24	
9200.00	88.79	89.57	7861.02	12.15	1606.51	1606.56	0.00	435723.75	616737.21	
9300.00	88.79	89.57	7863.12	12.91	1706.49	1706.54	0.00	435724.51	616837.19	
9400.00	88.79	89.57	7865.23	13.66	1806.46	1806.52	0.00	435725.26	616937.16	
9500.00	88.79	89.57	7867.33	14.42	1906.44	1906.49	0.00	435726.02	617037.14	
9600.00	88.79	89.57	7869.44	15.17	2006.41	2006.47	0.00	435726.77	617137.11	
9700.00	88.79	89.57	7871.54	15.93	2106.39	2106.45	0.00	435727.53	617237.09	
9800.00	88.79	89.57	7873.65	16.69	2206.36	2206.43	0.00	435728.29	617337.06	
9900.00	88.79	89.57	7875.75	17.44	2306.34	2306.41	0.00	435729.04	617437.04	
10000.00	88.79	89.57	7877.86	18.20	2406.31	2406.38	0.00	435729.80	617537.01	
10100.00	88.79	89.57	7879.96	18.95	2506.29	2506.36	0.00	435730.55	617636.99	
10200.00	88.79	89.57	7882.07	19.71	2606.26	2606.34	0.00	435731.31	617736.96	
10300.00	88.79	89.57	7884.17	20.47	2706.24	2706.32	0.00	435732.07	617836.94	
10400.00	88.79	89.57	7886.28	21.22	2806.21	2806.29	0.00	435732.82	617936.91	
10500.00	88.79	89.57	7888.38	21.98	2906.19	2906.27	0.00	435733.58	618036.89	
10600.00	88.79	89.57	7890.49	22.73	3006.16	3006.25	0.00	435734.33	618136.86	
10700.00	88.79	89.57	7892.59	23.49	3106.14	3106.23	0.00	435735.09	618236.84	
10800.00	88.79	89.57	7894.70	24.25	3206.11	3206.21	0.00	435735.85	618336.81	
10900.00	88.79	89.57	7896.80	25.00	3306.09	3306.18	0.00	435736.60	618436.79	
11000.00	88.79	89.57	7898.91	25.76	3406.06	3406.16	0.00	435737.36	618536.76	
11100.00	88.79	89.57	7901.02	26.51	3506.04	3506.14	0.00	435738.11	618636.74	
11200.00	88.79	89.57	7903.12	27.27	3606.01	3606.12	0.00	435738.87	618736.71	
11300.00	88.79	89.57	7905.23	28.03	3705.99	3706.10	0.00	435739.63	618836.69	
11400.00	88.79	89.57	7907.33	28.78	3805.96	3806.07	0.00	435740.38	618936.66	
11500.00	88.79	89.57	7909.44	29.54	3905.94	3906.05	0.00	435741.14	619036.64	
11574.28	88.79	89.57	7911.00	30.10	3980.20	3980.31	0.00	435741.70	619110.90	Pbhl

Targets

Name	Description Dip.	Dir.	TVD ft	+N/S ft	+E/W ft	Map Northing ft	Map Easting ft	Latitude		Longitude					
								Deg	Min	Sec	Deg	Min	Sec		
Pbhl			7911.00	30.10	3980.20	435741.70	619110.90	32	11	50.585	N	103	56	53.780	W

Casing Points

MD ft	TVD ft	Diameter in	Hole Size in	Name
470.00	470.00	0.000	0.000	Srfc. Csg.
3000.00	3000.00	0.000	0.000	Int. Csg.



Weatherford International Ltd.

WFT Plan Report - X & Y's



Weatherford

DP-4

Company: Occidental Permian Ltd.	Date: 9/14/2012	Time: 08:00:35	Page: 3
Field: Eddy Co, NM (Nad 27)	Co-ordinate(NE) Reference:	Well: Cedar Canyon 23 #2H Grid North	
Site: Cedar Canyon 23 #2H	Vertical (TVD) Reference:	SITE: 2951.0	
Well: Cedar Canyon 23 #2H	Section (VS) Reference:	Well: (0.00N; 0.00E; 89.57Azi)	
Wellpath: 1	Survey Calculation Method:	Minimum Curvature	Db: Sybase

Annotation

MD ft	TVD ft	Description
7266.17	7266.17	KOP
8154.10	7839.00	LP
11574.27	7911.00	PBHL

Formations


MD ft	TVD ft	Formations	Lithology	Dip Angle deg	Dip Direction deg
7749.23	7694.00	1st Bone Spring Sand		0.00	0.00

Field: Eddy Co, NM (Nad 27)

Map System: US State Plane Coordinate System 1927
Geo Datum: NAD27 (Clarke 1866)
Sys Datum: Mean Sea Level

Map Zone: New Mexico, Eastern Zone
Coordinate System: Well Centre
Geomagnetic Model: IGRF2010

BOP



- ① - 13 5/8" - 10M FLANGED END GATE VALVE
- ② - 13 5/8" - 10M FLANGED END GATE VALVE WITH DOUBLE ACTING HYDRAULIC ACTUATOR
- ③ - 13 5/8" - 10M FLANGED END GATE VALVE
- ④ - 13 5/8" - 10M FLANGED END GATE VALVE
- ⑤ - DOUBLE BEADED ADAPTER


SEE LIFT LING DETAIL

SHAFTER BULB-TYPE SPHERICAL ANNULAR PREVENTER (API 10A MICROGRAINED, 13 5/8" - 10M), 10M BOTTOM FLANGE - 10" STUCCO TOP (WEIGHT = 14,500 LBS WITH SHAFTER AND 100 NET OIL RESISTANT ADJUSTABLE ELEMENT)

CAMERON CHOKER REV-TYPE PREVENTER (API 10A MICROGRAINED, 13 5/8" - 10M) WITH 5" CAMERON PIPE RAMS (CAMERON FRONT PACKERS & TOP SEALS) IN TOP CHAMBER AND CAMERON CHOKER SHEARING PUNCH IN BOTTOM CHAMBER. BOTTOM FLANGE & STUCCO TOP (WEIGHT = 21,100 LBS WITH RAMS)


13 5/8" - 10M WP CAMERON DRILLING SPOOL (API 10A MICROGRAINED), STUCCO TOP & FLANGED BOTTOM WITH 4 1/2" - 10M WP FLANGED OUTLETS (WEIGHT APPROXIMATELY 6,000 LBS)

CAMERON LW SINGLE RAM-TYPE PREVENTER (API 10A MICROGRAINED, 13 5/8" - 10M) WITH 5" CAMERON PIPE RAMS (CAMERON FRONT PACKERS & TOP SEALS) BOTTOM FLANGE & STUCCO TOP (WEIGHT = 10,900 LBS)



H&P FURNISHED
 13 5/8" - 10M x 13 5/8" - 5M
 ADAPTER SPOOL 2' - 0" LONG

**13 5/8" - 10M BOP STACK
 WITH 13 5/8" - 5M ANNULAR**



ISSUED FOR FABRICATION
 December-18-2007
 DRAFTSMAN _____
 ENGINEER _____

API 10A MICROGRAINED CAMERON CHOKER AND KILL AND VALVE ASSEMBLIES ARE NOT SHOWN FOR CLARITY
 WEIGHTS DO NOT INCLUDE HOSES, ADAPTER SPOOLS OR QUICK CONNECT FITTINGS

PROPRIETARY
 THIS DRAWING AND THE IDEAS AND INFORMATION CONTAINED IN THIS DRAWING ARE PROPRIETARY AND ARE NOT TO BE REPRODUCED, COPIED, OR DISCLOSED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF A DULY AUTHORIZED OFFICER OF HELMERICH & PAYNE INT'L DRILLING CO.


HELMERICH & PAYNE
 INTERNATIONAL DRILLING CO.

ENGINEERING APPROVAL	DATE	TITLE
12/18/07	ADDED SHEET 03	13 5/8" - 10M BOP 3 RAM STACK FLEXRIGS
1-10-07	CHOKER AND KILL VALVE ASSEMBLIES ARE NOT SHOWN FOR CLARITY	
4-24-07	ADDED TO SPACER ADAPTER SPOOL	
11-07-07	ADDED ADAPTER SPOOL	
08-15-08	CORRECTED BOP STACK	
REV	DATE	DESCRIPTION


CUSTOMER FILE # _____
 PROJECT FLEXRIGS
 DRAWN: MTR DATE 6-2-02 DWG. NO.: _____
 SCALE 3/4" = 1' SHEET 1 OF 7 210-P1-07 E

CW-2


10M REMOTE KILL LINE SCHEMATIC



Choke Manifold - Gas Separator (Top View)




Choke Manifold - Gas Separator (Side View)



CM-4

Gas Separator Routing Flex III Rigs





CERTIFICATE OF CONFORMITY

Supplier : CONTITECH RUBBER INDUSTRIAL KFT.
Equipment : 6 pcs. Choke and Kill Hose with installed couplings
Type : 3" x 10,67 m WP: 10000 psi
Supplier File Number : 412638
Date of Shipment : April. 2008
Customer : Phoenix Beattie Co.
Customer P.o. : 002491
Referenced Standards
/ Codes / Specifications : API Spec 16 C
Serial No.: 52754,52755,52776,52777,52778,52782

STATEMENT OF CONFORMITY

We hereby certify that the above items/equipment supplied by us are in conformity with the terms, conditions and specifications of the above Purchaser Order and that these items/equipment were fabricated inspected and tested in accordance with the referenced standards, codes and specifications and meet the relevant acceptance criteria and design requirements.

COUNTRY OF ORIGIN HUNGARY/EU

Signed : 

Position: Q.C. Manager

ContiTech Rubber
 Industrial Kft.
 Quality Control Dept.
 01

Date: 04. April. 2008

Coflex Hose Certification

FH-4

Form No 100/12



Phoenix Beattie Corp

11535 Brittonmoore Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0148
E-mail: mail@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	1
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IDC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
1	HP10CK3A-35-4F1 3" 10K 16C C&K HOSE x 35ft OAL CW 4.1/16" API SPEC FLANGE E/ End 1: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End 2: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange c/w BX155 Standard ring groove at each end Suitable for H2S Service Working pressure: 10,000psi Test pressure: 15,000psi Standard: API 16C Full specification Armor Guarding: Included Fire Rating: Not Included Temperature rating: -20 Deg C to +100 Deg C	1	1	0
2	SECK3-HPF3 LIFTING & SAFETY EQUIPMENT TO SUIT HP10CK3-35-F1 2 x 160mm ID Safety Clamps 2 x 244mm ID Lifting Collars & element C's 2 x 7ft Stainless Steel wire rope 3/4" OD 4 x 7.75t Shackles	1	1	0
3	SC725-200CS SAFETY CLAMP 200MM 7.25T C/S GALVANISED	1	1	0

Continued...

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days. Returns may be subject to a handling charge.



Fluid Technology
Quality Document

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 746	
PURCHASER: Phoenix Beattie Co.			P.O. N°: 002491		
CONTITECH ORDER N°: 412838		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 52777		NOMINAL / ACTUAL LENGTH: 10,67 m			
W.P. 68,96 MPa	10000	psi	T.P. 103,4 MPa	15000	psi
		Duration: 60 ~ min.			
Pressure test with water at ambient temperature See attachment. (1 page)					
↑ 10 mm = 10 Min. → 10 mm = 25 MPa					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	917	913	AISI 4130	T7998A	
			AISI 4130	26984	
INFOCHIP INSTALLED			API Spec 16 C Temperature rate: "B"		
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:	Inspector		Quality Control		
04. April. 2008			Contitech Rubber Industrial KIL Quality Control Dept. (1)		

Coflex Hose Certification

FH-6

Form No 100/12



Phoenix Beattie Corp

11535 Brittainore Park Drive
Houston, TX 77041
Tel: (832) 327-0141
Fax: (832) 327-0149
E-mail: mail@phoenixbeattie.com
www.phoenixbeattie.com

Delivery Note

Customer Order Number	370-369-001	Delivery Note Number	003078	Page	2
Customer / Invoice Address HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119		Delivery / Address HELMERICH & PAYNE IOC ATTN: JOE STEPHENSON - RIG 370 13609 INDUSTRIAL ROAD HOUSTON, TX 77015			

Customer Acc No	Phoenix Beattie Contract Manager	Phoenix Beattie Reference	Date
H01	JJL	006330	05/23/2008

Item No	Beattie Part Number / Description	Qty Ordered	Qty Sent	Qty To Follow
4	SC725-132CS SAFETY CLAMP 132MM 7.25T C/S GALVANIZED C/W BOLTS	1	1	0
5	00CERT-HYDRO HYDROSTATIC PRESSURE TEST CERTIFICATE	1	1	0
6	00CERT-LOAD LOAD TEST CERTIFICATES	1	1	0
7	00FREIGHT INBOUND / OUTBOUND FREIGHT PRE-PAY & ADD TO FINAL INVOICE NOTE: MATERIAL MUST BE ACCOMPANIED BY PAPERWORK INCLUDING THE PURCHASE ORDER, RIG NUMBER TO ENSURE PROPER PAYMENT	1	1	0

Phoenix Beattie Inspection Signature :

Received In Good Condition : Signature

Print Name

Date

All goods remain the property of Phoenix Beattie until paid for in full. Any damage or shortage on this delivery must be advised within 5 days. Returns may be subject to a handling charge.

SWA-5


STATE OF TEXAS §
COUNTY OF HARRIS §

This instrument was acknowledged before me on this 26 day of MARCH 2012, by **Stephen S. Flynn**, Attorney-in-Fact of OXY USA Inc., a Delaware Corporation.

Candace Young
Notary Public



COUNTY OF Eddy §
STATE OF New Mexico §




This instrument was acknowledged before me this 23 day of March 2012, by **Tyson Mahaffey and Leslie Mahaffey**, Managers of Mahaffey Ranch.

My Commission Expires: 9-9-13

Caryn Pond
NOTARY PUBLIC,
STATE OF New Mexico


600x600

SECTION 23, TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M.
EDDY COUNTY NEW MEXICO



DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF CO. RD. 720 (DUARTE RD.) AND CO. RD. 746 (McDONALD RD.), GO SOUTH ON CO. RD. 746 APPROX. 5.6 MILES. TURN LEFT AND GO EAST, THEN NORTH APPROX. 1.3 MILES TO THE EXISTING OXY U. S. A. INC., VORTEC 22 #1 WELL. FROM THE NORTHEAST CORNER OF THE PAD, FOLLOW PROPOSED ROAD SURVEY STAKES NORTH, THEN EAST APPROX. 684 FEET TO THIS LOCATION.



OXY U.S.A. INC.


CEDAR CANYON 23 #2H WELL
LOCATED 660 FEET FROM THE SOUTH LINE
AND 660 FEET FROM THE WEST LINE OF SECTION 23,
TOWNSHIP 24 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

Survey Date: 8/11/11	Sheet 1 of 1 Sheets
W.O. Number: 11.11.1662	Dr. By: DSS
Date: 8/17/11	Rel. W.O.: 11111662
	Scale: 1"=100'

PROVIDING SURVEYING SERVICES SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117

LUM

LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL:
PIERCE CANYON, N.M. - 10'

SEC. 23 TWP. 24-S RGE. 29-E

SURVEY N.M.P.M.

COUNTY EDDY STATE NEW MEXICO

DESCRIPTION 660' FSL & 660' FWL

ELEVATION 2927'

OPERATOR OXY U.S.A. INC.


LEASE CEDAR CANYON 23

U.S.G.S. TOPOGRAPHIC MAP
PIERCE CANYON, N.M.

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117

UM

VICINITY MAP




SCALE: 1" = 2 MILES

SEC. 23 TWP. 24-S RGE. 29-E
 SURVEY N.M.P.M.
 COUNTY EDDY STATE NEW MEXICO
 DESCRIPTION 660' FSL & 660' FWL
 ELEVATION 2927'
 OPERATOR OXY U.S.A. INC.
 LEASE CEDAR CANYON 23



PROVIDING SURVEYING SERVICES
 SINCE 1946
JOHN WEST SURVEYING COMPANY
 412 N. DAL PASO
 HOBBS, N.M. 88240
 (575) 393-3117


BLM-9500-PLAT



Flex 3 Rig - V-Door Southeast


Cedar Canyon 23 #2H

Wellsite layout



If the road comes into the Southwest corner of the pad, Oxy will pick up 80' on the West side and 50' on the North side

Facility layout




REVISION BLOCK						ENGINEERING RECORD	
NO.	DATE	DESCRIPTION	BY	CHK	APP	BY	DATE
A	11/11/12	Plot Plan for Permilting	RJG			RJG	7/18/2012

PRODUCTION FACILITY LAYOUT
Cedar Canyon 23-2

CL-1

ITEM	QTY	DESCRIPTION	LENGTH	WIDTH
------	-----	-------------	--------	-------



NO.	REV.	DATE	BY	CHKD.	APP.

1. ALL STRUCTURAL MATERIAL SHALL BE ASTM - A36
 2. ALL PIPING SHALL BE ASTM A106 Gr. B
 3. ALL FLANGES SHALL BE SPIR 150# 4 MATERIAL SA 105
 4. ALL FITTINGS SHALL BE ASTM A105 2 1/2" GR. WHP
 5. TANK FABRICATION SHALL BE IN ACCORDANCE WITH API-650

The entire information and drawings are the property of Scomi International Limited and are not to be reproduced in whole or in part by any means, in any form, or transmitted, or divulged to any person in any language or used for manufacture or other purposes without the written permission of Scomi International Limited. In receipt of such permission, safety and security for the purposes concerned. The drawings and any copies shall be returned to Scomi International Limited when required.


PROJECT: CLOSED LOOP SYSTEM
 BASIC LAYOUT AND TIE IN
 OXY - H&P - FLEX RIGS / PG 1 OF 2

DESIGNED BY: SCA
 CHECKED BY: SPC
 DATE: 10/30/06
 SCALE: NTS
 ADO INCH: D

Scomi

5457 W. Main Street, Calgary, Alberta, Canada T2C 1K9
 PHONE: (403) 243-8228 FAX: (403) 243-8229

JOB NO. 521S-014
 REV. A



Closed Loop System

Dewat

DE 1000

DE 1000

27'-0\"/>

VARIABLE FREQUENCY DRIVE HOUSE

30'-0\"/>

30'-0\"/>

30'-0\"/>

35'-0\"/>

40'-0\"/>

40'-0\"/>


END OF BOOBY GUIDE

MAST IN HORIZONTAL POSITION

CL-4


OXY FLEX III PAD (SCOMI Closed Loop System)

Level Area-No Caliche-For Offices and Living Quarters



Notes for Rotating Mouse hole for a FlexRig3 & 25' Substructure:

- 1) 70' of mouse hole below ground level
- 2) If conductor pipe is less than 85' below ground level, recommend cement mouse hole in place in order to prevent break thru & circulation / washout thru mouse hole.
- 3) Use 14" (mini. Nominal size) pipe. This can be spiral weld or low pressure pipe, 10 3/4" is used in some applications but due to inaccuracies in location of mouse hole & potential out of alignment or centered in hole, 14" pipe recommended.
- 4) Cement mouse hole in 16 1/2" or 18 3/4" hole.
- 5) Cellar will need to be oblong in order to accommodate mouse hole (i.e. 5' x 10', 6' x 10',) Operator decision



**Permian Drilling
Hydrogen Sulfide Drilling Operations Plan
Cedar Canyon 23 ~~XXXXXX~~ #2H**

Open drill site. No homes or buildings are near the proposed location.

1. Escape

Personnel shall escape upwind of wellbore in the event of an emergency gas release. Escape can take place through the lease road on the West side of the location. Personnel need to move to a safe distance and block the entrance to location. If the primary route is not an option due to the wind direction, then a secondary egress route should be taken.

 H2S Detectors. At least three detectors will be installed: bell nipple, rig floor and Shakers.

 Briefing Areas. At least two briefing areas will be placed, 90 deg off.


 Wind direction indicators. Visible from rig floor and from the mud pits area.

A gas buster is connected to both the choke manifold and flowline outlets.

Rig Layout

Secondary Egress 

Primary Briefing Area 



WIND: Prevailing winds are from the Southwest 



Permian Drilling Hydrogen Sulfide Drilling Operations Plan New Mexico

Scope

This contingency plan establishes guidelines for the public, all company employees, and contract employees who's work activities may involve exposure to hydrogen sulfide (H₂S) gas.

While drilling this well, it is possible to encounter H₂S bearing formations. At all times, the first barrier to control H₂S emissions will be the drilling fluid, which will have a density high enough to control influx.

Objective

1. Provide an immediate and predetermined response plan to any condition when H₂S is detected. All H₂S detections in excess of 10 parts per million (ppm) concentration are considered an Emergency.
2. Prevent any and all accidents, and prevent the uncontrolled release of hydrogen sulfide into the atmosphere.
3. Provide proper evacuation procedures to cope with emergencies.
4. Provide immediate and adequate medical attention should an injury occur.

Discussion

Implementation:	This plan with all details is to be fully implemented before drilling to <u>commence</u> .
Emergency response Procedure:	This section outlines the conditions and denotes steps to be taken in the event of an emergency.
Emergency equipment Procedure:	This section outlines the safety and emergency equipment that will be required for the drilling of this well.
Training provisions:	This section outlines the training provisions that must be adhered to prior to drilling.
Drilling emergency call lists:	Included are the telephone numbers of all persons to be contacted should an emergency exist.
Briefing:	This section deals with the briefing of all people involved in the drilling operation.
Public safety:	Public safety personnel will be made aware of any potential evacuation and any additional support needed.
Check lists:	Status check lists and procedural check lists have been included to insure adherence to the plan.
General information:	A general information section has been included to supply support information.

Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on the well:

1. The hazards and characteristics of H₂S.
2. Proper use and maintenance of personal protective equipment and life support systems.
3. H₂S detection.
4. Proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures and prevailing winds.
5. Proper techniques for first aid and rescue procedures.
6. Physical effects of hydrogen sulfide on the human body.
7. Toxicity of hydrogen sulfide and sulfur dioxide.
8. Use of SCBA and supplied air equipment.
9. First aid and artificial respiration.
10. Emergency rescue.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S on metal components. If high tensile strength tubular is to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling a well, blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan.

H₂S training refresher must have been taken within one year prior to drilling the well. Specifics on the well to be drilled will be discussed during the pre-spud meeting. H₂S and well control (choke) drills will be performed while drilling the well, at least on a weekly basis. This plan shall be available in the well site. All personnel will be required to carry the documentation proving that the H₂S training has been taken.

Service company and visiting personnel

- A. Each service company that will be on this well will be notified if the zone contains H₂S.
- B. Each service company must provide for the training and equipment of their employees before they arrive at the well site.
- C. Each service company will be expected to attend a well site briefing

Emergency Equipment Requirements

1. Well control equipment

The well shall have hydraulic BOP equipment for the anticipated pressures. Equipment is to be tested on installation and follow Oxy Well Control standard, as well as BLM Onshore Order #2.

Special control equipment:

- A. Hydraulic BOP equipment with remote control on ground.
- B. Rotating head
- C. Gas buster equipment shall be installed before drilling out of surface pipe.

2. Protective equipment for personnel

- A. Four (4) 30-minute positive pressure air packs (2 at each briefing area) on location.
- B. Adequate fire extinguishers shall be located at strategic locations.
- C. Radio / cell telephone communication will be available at the rig.
 - Rig floor and trailers.
 - Vehicle.

3. Hydrogen sulfide sensors and alarms

- A. H₂S sensor with alarms will be located on the rig floor, at the bell nipple, and at the flow line. These monitors will be set to alarm at 10 ppm with strobe light, and audible alarm.
- B. Hand operated detectors with tubes.
- C. H₂S monitor tester (to be provided by contract Safety Company.)
- D. There shall be one combustible gas detector on location at all times.

4. Visual Warning Systems

- A. One sign located at each location entrance with the following language:

**Caution – potential poison gas
Hydrogen sulfide
No admittance without authorization**

Wind sock – wind streamers:

- A. One 36" (in length) wind sock located at protection center, at height visible from rig floor.
- B. One 36" (in length) wind sock located at height visible from pit areas.

Condition flags

- A. One each condition flag to be displayed to denote conditions.

green – normal conditions

yellow – potential danger

red – danger, H₂S present

- B. Condition flag shall be posted at each location sign entrance.

5. Mud Program

The mud program is designed to minimize the risk of having H₂S and other formation fluids at surface. Proper mud weight and safe drilling practices will be applied. H₂S scavengers will be used to minimize the hazards while drilling. Below is a summary of the drilling program.

Mud inspection devices:

Garrett gas train or hatch tester for inspection of sulfide concentration in mud system.

6. Metallurgy

- A. Drill string, casing, tubing, wellhead, blowout preventers, drilling spools or adapters, kill lines, choke manifold, lines and valves shall be suitable for the H₂S service.
- B. All the elastomers, packing, seals and ring gaskets shall be suitable for H₂S service.

7. Well Testing

No drill stem test will be performed on this well.

8. Evacuation plan

Evacuation routes should be established prior to well spud for each well and discussed with all rig personnel.

9. Designated area

- A. Parking and visitor area: all vehicles are to be parked at a predetermined safe distance from the wellhead.
- B. There will be a designated smoking area.
- C. Two briefing areas on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds perpendicularly, or at a 45-degree angle if wind direction tends to shift in the area.

Emergency procedures

- A. In the event of any evidence of H₂S level above 10 ppm, take the following steps:
 - 1. The Driller will pick up off bottom, shut down the pumps, slow down the pipe rotation.
 - 2. Secure and don escape breathing equipment, report to the upwind designated safe briefing / muster area.
 - 3. All personnel on location will be accounted for and emergency search should begin for any missing, the Buddy System will be implemented.
 - 4. Order non-essential personnel to leave the well site, order all essential personnel out of the danger zone and upwind to the nearest designated safe briefing / muster area.
 - 5. Entrance to the location will be secured to a higher level than our usual "Meet and Greet" requirement, and the proper condition flag will be displayed at the entrance to the location.
 - 6. Take steps to determine if the H₂S level can be corrected or suppressed and, if so, proceed as required.
- B. If uncontrollable conditions occur:
 - 1. Take steps to protect and/or remove any public in the down-wind area from the rig – partial evacuation and isolation. Notify necessary public safety personnel and appropriate regulatory entities (i.e. BLM) of the situation.

2. Remove all personnel to the nearest upwind designated safe briefing / muster area or off location.
3. Notify public safety personnel of safe briefing / muster area.
4. An assigned crew member will blockade the entrance to the location. No unauthorized personnel will be allowed entry to the location.
5. Proceed with best plan (at the time) to regain control of the well. Maintain tight security and safety procedures.

C. Responsibility:

1. Designated personnel.
 - a. Shall be responsible for the total implementation of this plan.
 - b. Shall be in complete command during any emergency.
 - c. Shall designate a back-up.

- All personnel:
1. On alarm, don escape unit and report to the nearest upwind designated safe briefing / muster area upw
 2. Check status of personnel (buddy system).
 3. Secure breathing equipment.
 4. Await orders from supervisor.

- Drill site manager:
1. Don escape unit if necessary and report to nearest upwind designated safe briefing / muster area.
 2. Coordinate preparations of individuals to return to point of release with tool pusher and driller (using the buddy system).
 3. Determine H₂S concentrations.
 4. Assess situation and take control measures.

- Tool pusher:
1. Don escape unit Report to up nearest upwind designated safe briefing / muster area.
 2. Coordinate preparation of individuals to return to point of release with tool pusher drill site manager (using the buddy system).
 3. Determine H₂S concentration.
 4. Assess situation and take control measures.

- Driller:
1. Don escape unit, shut down pumps, continue rotating DP.

- 2. Check monitor for point of release.
- 3. Report to nearest upwind designated safe briefing / muster area.
- 4. Check status of personnel (in an attempt to rescue, use the buddy system).
- 5. Assigns least essential person to notify Drill Site Manager and tool pusher by quickest means in case of their absence.
- 6. Assumes the responsibilities of the Drill Site Manager and tool pusher until they arrive should they be absent.

Derrick man
 Floor man #1
 Floor man #2

- 1. Will remain in briefing / muster area until instructed by supervisor.

Mud engineer:

- 1. Report to nearest upwind designated safe briefing / muster area.
- 2. When instructed, begin check of mud for ph and H2S level. (Garett gas train.)

Safety personnel:

- 1. Mask up and check status of all personnel and secure operations as instructed by drill site manager.

Taking a kick

When taking a kick during an H2S emergency, all personnel will follow standard Well control procedures after reporting to briefing area and masking up.

Open-hole logging

All unnecessary personnel off floor. Drill Site Manager and safety personnel should monitor condition, advise status and determine need for use of air equipment.

Running casing or plugging

Following the same "tripping" procedure as above. Drill Site Manager and safety personnel should determine if all personnel have access to protective equipment.

Ignition procedures

The decision to ignite the well is the responsibility of the operator (Oxy Drilling Management). The decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope controlling the blowout under the prevailing conditions at the well.

Instructions for igniting the well

1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man (tool pusher or safety engineer) will check the atmosphere for explosive gases with the gas monitor. The other man is responsible for igniting the well.
2. Primary method to ignite: 25 mm flare gun with range of approximately 500 feet.
3. Ignite upwind and do not approach any closer than is warranted.
4. Select the ignition site best for protection, and which offers an easy escape route.
5. Before firing, check for presence of combustible gas.
6. After lighting, continue emergency action and procedure as before.
7. All unassigned personnel will remain in briefing area until instructed by supervisor or directed by the Drill Site Manager.

Remember: After well is ignited, burning hydrogen sulfide will convert to sulfur dioxide, which is also highly toxic. **Do not assume the area is safe after the well is ignited.**

Status check list

Note: All items on this list must be completed before drilling to production casing point.

1. H₂S sign at location entrance.
2. Two (2) wind socks located as required.
3. Four (4) 30-minute positive pressure air packs (2 at each Briefing area) on location for all rig personnel and mud loggers.
4. Air packs inspected and ready for use.
5. Cascade system and hose line hook-up as needed.
6. Cascade system for refilling air bottles as needed.
7. Condition flag on location and ready for use.
8. H₂S detection system hooked up and tested.
9. H₂S alarm system hooked up and tested.
10. Hand operated H₂S detector with tubes on location.
11. 1 - 100' length of nylon rope on location.
12. All rig crew and supervisors trained as required.
13. All outside service contractors advised of potential H₂S hazard on well.
14. No smoking sign posted and a designated smoking area identified.
15. Calibration of all H₂S equipment shall be noted on the IADC report.

Checked by: _____ Date: _____

Procedural check list during H₂S events

Perform each tour:

1. Check fire extinguishers to see that they have the proper charge.
2. Check breathing equipment to ensure that it is in proper working order.
3. Make sure all the H₂S detection system is operative.

Perform each week:

1. Check each piece of breathing equipment to make sure that demand or forced air regulator is working. This requires that the bottle be opened and the mask assembly be put on tight enough so that when you inhale, you receive air or feel air flow.
2. BOP skills (well control drills).
3. Check supply pressure on BOP accumulator stand by source.
4. Check breathing equipment mask assembly to see that straps are loosened and turned back, ready to put on.
5. Check pressure on breathing equipment air bottles to make sure they are charged to full volume. (Air quality checked for proper air grade "D" before bringing to location)
6. Confirm pressure on all supply air bottles.
7. Perform breathing equipment drills with on-site personnel.
8. Check the following supplies for availability.
 - A. Emergency telephone list.
 - B. Hand operated H₂S detectors and tubes.

General evacuation plan

1. When the company approved supervisor (Drill Site Manager, consultant, rig pusher, or driller) determines the H₂S gas cannot be limited to the well location and the public will be involved, he will activate the evacuation plan.
2. Drill Site Manager or designee will notify local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company or contractor safety personnel that have been trained in the use of H₂S detection equipment and self-contained breathing equipment will monitor H₂S concentrations, wind directions, and area of exposure. They will delineate the outer perimeter of the hazardous gas area. Extension to the evacuation area will be determined from information gathered.
4. Law enforcement personnel (state police, police dept., fire dept., and sheriff's dept.) Will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.
5. After the discharge of gas has been controlled, company safety personnel will determine when the area is safe for re-entry.

Important: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

Emergency actions**Well blowout – if emergency**

1. Evacuate all personnel to “Safe Briefing/ Muster Areas” or off location if needed.
2. If sour gas – evacuate rig personnel.
3. If sour gas – evacuate public within 3000 ft radius of exposure.
4. Don SCBA and shut well in if possible using the buddy system.
5. Notify Drilling Superintendent and call 911 for emergency help (fire dept and ambulance) if needed.
6. Implement the Blowout Contingency Plan, and Drilling Emergency Action Plan.
6. Give first aid as needed.

Person down location/facility

1. If immediately possible, contact 911. Give location and wait for confirmation.
2. Don SCBA and perform rescue operation using buddy system.

Toxic effects of hydrogen sulfide

Hydrogen sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 ppm, which is .001% by volume. Hydrogen sulfide is heavier than air (specific gravity – 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in table i. Physical effects at various hydrogen sulfide exposure levels are shown in table ii.

Table i
Toxicity of various gases

Common name	Chemical formula	Specific gravity (sc=1)	Threshold limit (1)	Hazardous limit (2)	Lethal concentration (3)
Hydrogen Cyanide	Hcn	0.94	10 ppm	150 ppm/hr	300 ppm
Hydrogen Sulfide	H ₂ S	1.18	10 ppm	250 ppm/hr	600 ppm
Sulfur Dioxide	So ₂	2.21	5 ppm	-	1000 ppm
Chlorine	Cl ₂	2.45	1 ppm	4 ppm/hr	1000 ppm
Carbon Monoxide	Co	0.97	50 ppm	400 ppm/hr	1000 ppm
Carbon Dioxide	Co ₂	1.52	5000 ppm	5%	10%
Methane	Ch ₄	0.55	90,000 ppm	Combustible above 5% in air	

- 1) threshold limit – concentration at which it is believed that all workers may be repeatedly exposed day after day without adverse effects.
- 2) hazardous limit – concentration that will cause death with short-term exposure.
- 3) lethal concentration – concentration that will cause death with short-term exposure.

Toxic effects of hydrogen sulfide

Table ii
Physical effects of hydrogen sulfide

Percent (%)	Ppm	Concentration Grains 100 std. Ft ³ *	Physical effects
0.001	<10	00.65	Obvious and unpleasant odor.

H₂S-17

0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kill smell in 3 - 15 minutes. May sting eyes and throat.
0.020	200	12.96	Kills smell shortly; stings eyes and throat.
0.050	500	32.96	Dizziness; breathing ceases in a few minutes; needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; followed by death within minutes.

*at 15.00 psia and 60'f.

Use of self-contained breathing equipment (SCBA)

1. Written procedures shall be prepared covering safe use of SCBA's in dangerous atmosphere, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available SCBA.
2. SCBA's shall be inspected frequently at random to insure that they are properly used, cleaned, and maintained.
3. Anyone who may use the SCBA's shall be trained in how to insure proper face-piece to face-seal. They shall wear SCBA's in normal air and then wear them in a test atmosphere. (note: such items as facial hair {beard or sideburns} and eyeglasses will not allow proper seal.) Anyone that may be reasonably expected to wear SCBA's should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses or contact lenses.
4. Maintenance and care of SCBA's:
 - a. A program for maintenance and care of SCBA's shall include the following:
 1. Inspection for defects, including leak checks.
 2. Cleaning and disinfecting.
 3. Repair.
 4. Storage.
 - b. Inspection, self-contained breathing apparatus for emergency use shall be inspected monthly.
 1. Fully charged cylinders.
 2. Regulator and warning device operation.
 3. Condition of face piece and connections.
 4. Rubber parts shall be maintained to keep them pliable and prevent deterioration.
 - c. Routinely used SCBA's shall be collected, cleaned and disinfected as frequently as necessary to insure proper protection is provided.
5. Persons assigned tasks that requires use of self-contained breathing equipment shall be certified physically fit (medically cleared) for breathing equipment usage at least annually.
6. SCBA's should be worn when:
 - A. Any employee works near the top or on top of any tank unless test reveals less than 10 ppm of H2S.

- B. When breaking out any line where H2S can reasonably be expected.
- C. When sampling air in areas to determine if toxic concentrations of H2S exists.
- D. When working in areas where over 10 ppm H2S has been detected.
- E. At any time there is a doubt as to the H2S level in the area to be entered.

Rescue
First aid for H2S poisoning

Do not panic!

Remain calm – think!

1. Don SCBA breathing equipment.
2. Remove victim(s) utilizing buddy system to fresh air as quickly as possible. (go up-wind from source or at right angle to the wind. Not down wind.)
3. Briefly apply chest pressure – arm lift method of artificial respiration to clean the victim's lungs and to avoid inhaling any toxic gas directly from the victim's lungs.
4. Provide for prompt transportation to the hospital, and continue giving artificial respiration if needed.
5. Hospital(s) or medical facilities need to be informed, before-hand, of the possibility of H2S gas poisoning – no matter how remote the possibility is.
6. Notify emergency room personnel that the victim(s) has been exposed to H2S gas.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration.

Revised CM 6/27/2012

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	OXY USA INC.
LEASE NO.:	NM88138
WELL NAME & NO.:	2H-CEDAR CANYON 23
SURFACE HOLE FOOTAGE:	660'/S. & 660'/W.
BOTTOM HOLE FOOTAGE:	660'/S. & 380'/E.
LOCATION:	Section 23, T. 24 S., R. 29 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Contact private land owner
 - Well Pad Construction
 - Visual Resource Management
 - Communitization Agreement
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Drilling**
 - Logging requirements
 - Medium cave/karst
 - Casing depth
 - Waste Material and Fluids
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Contact private land owner

Contact land owner prior to construction in order to determine reroute for fence.
Tyson Mahaffey 575-361-1133

Well Pad Construction:

- The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.
- Any water erosion that may occur due to the construction of the well pad during the life of the well will be quickly corrected and proper measures will be taken to prevent future erosion.
- Stockpiling of topsoil is required. The top soil shall be stockpiled in an appropriate location to prevent loss of soil due to water or wind erosion and not used for berming or erosion control.

Tank Battery COAs Only:

- Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.
- Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

Surface Pipeline COAs Only:

A leak detection plan will be submitted to the BLM Carlsbad Field Office for approval prior to pipeline installation. The method could incorporate gauges to detect pressure drops, situating valves and lines so they can be visually inspected periodically or installing electronic sensors to alarm when a leak is present. The leak detection plan will incorporate an automatic shut off system that will be installed for proposed pipelines to minimize the effects of an undesirable event.

VISUAL RESOURCE MANAGEMENT

- The proposed construction will be limited to approved pad size.
- All above-ground tanks, facilities, structures, appurtenances, and pipelines will be low-profile (less than 8 feet in height).
- Above-ground structures including meter housing that are not subject to safety requirements are painted a flat non-reflective paint color Shale Green, Munsell Soil Color No. 5Y 4/2"

- **Minimize the number and width of roads. Plan roads to reduce mileage and build only the roads necessary for development. Locate pipelines in or adjacent to roads where possible. Road construction should conform to the natural landscape – meandering, not straight, and out of site when possible. Meandering roads make a slight turn and seem to disappear. Straight roads draw the viewer’s eye to the disturbance in the natural landscape. Locate roads to avoid hill tops, and minimize road cuts. Build around obstacles, not over them.**
- **Avoid prominent placement on hills or mountains. Use natural contours of the land or vegetation to screen operations from the casual viewer when possible. Consider the line, form, color and texture of the surrounding landscape during pad location and placement of equipment.**
- **After final abandonment and reclamation, the pads, roads and associated infrastructure will be removed, reclaimed, re-contoured and re-vegetated, thereby eliminating visual impacts.**

Communitization Agreement

A Communitization Agreement (CA) covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

Operator shall change the name of the well to include “Com”.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 4 inches in depth. The topsoil will be used for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty (20) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out-sloping and in-sloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Although Hydrogen Sulfide has not been reported in the area, it is always a potential hazard. If Hydrogen Sulfide is encountered, please report measured amounts and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium cave/karst.

Possible lost circulation in the Delaware and Bone Spring formations.

1. The 13-3/8 inch surface casing shall be set at approximately 435 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If the salt is penetrated, casing shall be set 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is: **(Ensure casing is set in the Lamar at approximately 3030')**
 - Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
 - a. First stage to DV tool:
 - Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. **Operator has proposed a multi-bowl wellhead assembly. The installation of this assembly does not eliminate the testing of the BOP/BOPE for the successive casing strings. A seal is broken when the lock screws are used and when the observation port is opened. There is no guarantee that when these are tightened that a pressure seal exists without performing another test is performed on this segment of the BOP/BOPE.**

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **5000 (5M) psi. 5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**
 - c. The results of the test shall be reported to the appropriate BLM office.
 - d. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
 - e. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

CRW 021213

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

VRM Facility Requirement

Low-profile tanks not greater than eight-feet-high shall be used.

B. PIPELINES (not applied for in APD)

C. ELECTRIC LINES (not applied for in APD)

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 1, for Loamy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass (<i>Eragrostis intermedia</i>)	0.5
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sideoats grama (<i>Bouteloua curtipendula</i>)	5.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed