,			OCE	) Artesia	) -	3-1313
	(August 2007) UNITED STATES DEPARTMENT OF THE INTERIOR				FORM APPROVED OMB NO. 1004-0135 Expires: July 31, 2010	
	BUREAU OF LAND MANAGEMENT SUNDRY NOTICES AND REPORTS ON WELLS				5. Lease Serial No. NMNM120349	
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.				6. If Indian, Allottee or Tribe Name		
SUBMIT IN TRIPLICATE - Other instructions on reverse side.				7. If Unit or CA/Agreement, Name and/or No.		
1. Type of Well ☑ Oil Well □ Gas Well □ Other					8. Well Name and No. FROSTY FEDERAL COM 2H	
2. Name of Operator Contact: CINDY COTTRELL MURCHISON OIL & GAS INC E-Mail: ccottrell@jdmii.com					9. API Well No. 30-015-38531	
3a. Address 1100 MIRA VISTA BLVD PLANO, TX 75093-4698	1100 MIRA VISTA BLVD		3b. Phone No. (include area code) Ph: 972-931-0700 Ext: 109		10. Field and Pool, or Exploratory EMPIRE; WOLFCAMP, NW	
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)					11. County or Parish, and State	
Sec 26 T16S R27E Mer NMP NENE 950FNL 250FEL					EDDY COUNTY, NM	
12. CHECK APPRO	PRIATE BOX(ES) TO	D INDICATE	NATURE OF N	NOTICE, RE	PORT, OR OTHER	DATA
TYPE OF SUBMISSION	TYPE OF ACTION					
Notice of Intent	<ul> <li>Acidize</li> <li>Alter Casing</li> </ul>	Deep	en 1re Treat	Production Reclamation	on (Start/Resume)	U Water Shut-Off
Subsequent Report	Casing Repair	—	Construction	Recompl		U Well Integrity
Final Abandonment Notice	Change Plans Plug and Abandon Tempo		-	orarily Abandon		
Attach the Bond under which the work w following completion of the involved op testing has been completed. Final Aband determined that the site is ready for final Murchison Oil & Gas, Inc. respect	perations. If the operation re- donment Notices shall be file	sults in a multiple ed only after all re	completion or reco quirements, includ	ompletion in a ne ling reclamation,	ew interval, a Form 3160	4 shall be filed once
Mulchison On a Gas, inc. respec			son or one (a).	yre <u>a</u> i.		
Accepted for record	JUL 12	2013		APPROVE	DFORZEMONT	TH PERIOD
Engineering	Revers t	new	COA	-civat	tid-JA/	n 05/30/13
14. Indeby certify that the foregoing s tru E Name(Printed/Typed) CINDY COT	lectronic Submission # For MURCHIS Committed to AFMSS f	ON OIL & GAS or processing I	INC, sent to the by KURT SIMMO	e Carlsbad	2013 ()	
	· · · 、					
Signature (Electronic Sub	THIS SPACE FC		Date 01/30/2		E	
9 Max	Janer	·	For F		NACED	7/10/13
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease					11220013131	Date
	ble title to those rights in the		Office	CADI CDA	D FIELD OFFICE	

.

,

\*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\* OPERATOR-SUBMITTED \*\*

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Murchison Oil & Gas, Inc.
LEASE NO.:	NM-114347
WELL NAME & NO.:	Frosty Federal Com #2H
SURFACE HOLE FOOTAGE:	0950' FNL & 0250' FEL
BOTTOM HOLE FOOTAGE	0990' FNL & 0330' FWL
LOCATION:	Section 26, T.16 S., R. 27 E., NMPM
COUNTY:	Eddy County, New Mexico

The standard Conditions of Approval (COA) that were approved with the APD on 02/16/2011 apply to this APD extension. The following conditions apply to the APD extension as well.

Special Requirements

Communitization Agreement

# Drilling

7

Logging Requirements High Cave/Karst Waste Material and Fluids

# I. SPECIAL REQUIREMENT(S)

### **Communitization Agreement**

A Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

# II. DRILLING

7

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

# 1. Although Hydrogen Sulfide has not been reported in this section, it is always a potential hazard. If Hydrogen Sulfide is encountered, please report measured amounts and formations to the BLM.

- Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If

available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

#### B. CASING

ï

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

HIGH CAVE/KARST – A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE IS REQUIRED IN HIGH CAVE/KARST AREAS. THE CEMENT MUST BE IN A SOLID SHEATH. THEREFORE, ONE INCH OPERATIONS WILL NOT BE PERMITTED AND DV TOOLS MAY BE NEEDED TO MEET THE SOLID SHEATH REQUIREMENT ON EACH CASING STRING.

Possible lost circulation in the Grayburg and San Andres formations.

- 1. The 9-5/8 inch surface casing shall be set at approximately 1400 feet (within a competent bed in the Grayburg) and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 7 inch production casing is:

Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

An isolation packer shall be set 375' off of the east line to make the producing area orthodox. In addition, this packer also isolates the Abo and Wolfcamp formations to eliminate the possibility of downhole commingle behind pipe.

3. The minimum required fill of cement behind the 4-1/2 inch production liner is:

Cement not required – Port packer system to be used.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

# C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M)** psi.
  - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- 3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after

installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

### D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

# E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

### JAM 053013

.

ì