Form 3160-3
(March 2012)

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

UNITED STATES
DEPARTMENT OF THE INTERIOR SECRETARY'S POTASH
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

5. Lease Serial No. NMNM 0006748 (BHL)	TES 11/14/2013
6. If Indian, Allotee or Tribe Name	
7. If Unit or CA Agreement, Name and No. Big Eddy Unit NM68294X	
8. Lease Name and Well No. Bid Eddy Unit 254 1H <305860>	
9. API Well No. 30-015-41798	
10. Field and Pool, or Exploratory ~~WC-William Sink (Bone Spring)~~ 98053	
11. Sec., T. R. M. or Blk. and Survey or Area Section 15, T21S-R29E	
12. County or Parish Eddy	13. State NM

1a. Type of work: ☑ DRILL ☐ REENTER

1b. Type of Well: ☑ Oil Well ☐ Gas Well ☐ Other ☑ Single Zone ☐ Multiple Zone

2. Name of Operator BOPCO L.P. <260737>

3a. Address PO Box 2760, Midland, TX 79702

3b. Phone No. *(include area code)* 432-683-2277

4. Location of Well *(Report location clearly and in accordance with any State requirements.*)*

At surface NWNW, UL D, 1000' FNL & 1249' FWL, Lat:N32.483825, Long:W103.976444

At proposed prod. zone 1980' FNL,330' FEL,Sec 13,T21S-R29E,Lat:N32.41081,Long:W103.9302

WC-015 G-08 S212915D; Bone Spring

14. Distance in miles and direction from nearest town or post office*
15 miles northeast of Carlsbad, NM

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 330'	16. No. of acres in lease 1280	17. Spacing Unit dedicated to this well 440
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 3,740'	19. Proposed Depth Pilot Hole- 11,493' TVD Lat- 23,271' MD/9,258' TVD	20. BLM/BIA Bond No. on file COB 000050
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3,447' GL	22. Approximate date work will start* 11/21/2013	23. Estimated duration 35 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the BLM.

25. Signature Courtney Lockhart	Name *(Printed/Typed)* Courtney Lockhart	Date 10-25-13
Title		
Approved by *(Signature)* Jesse J. Juen	Name *(Printed/Typed)* Jesse J. Juen	Date 11/13/13
Title NM STATE OFFICE	Office STATE DIRECTOR	

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

Carlsbad Controlled Water Basin

RECEIVED
NOV 14 2013
NMOCD ARTESIA

Approval Subject to General Requirements & Special Stipulations Attached

SEE ATTACHED FOR CONDITIONS OF APPROVAL

October 28, 2013

OPERATORS'S CERTIFICATION

APPLICATION FOR PERMIT TO DRILL
BIG EDDY UNIT #254
1000' FNL & 1249' FWL, Sec. 15, T21S, R29E, Eddy County, NM

In reference to the above captioned well, I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 25th day of October, 2013.

If you have any questions regarding the accuracy of the plan provided herein, please do not hesitate to contact me at (432) 683-2277.

Courtney Lockhart
Regulatory Analyst

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
DISTRICT II
1301 W. Grand Avenue, Artesia, NM 88210
DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410
DISTRICT IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

Form C-102
Revised July 16, 2010

Submit one copy to appropriate District Office

☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

API Number	Pool Code	Pool Name
30-015-41798	~~97650~~ 98053 (see below)	~~WC WILLIAM SINK (BONE SPRING)~~ *

Property Code	Property Name	Well Number
305860	BIG EDDY UNIT	254H
OGRID No.	**Operator Name**	**Elevation**
260737	BOPCO, L.P.	3447'

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
D	15	21 S	29 E		1000	NORTH	1249	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
H	13	21 S	29 E		1980	NORTH	330	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
440			

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

*WC-015 G-08 S212915D; Bone Spring



SURFACE LOCATION
Lat - N 32°29'01.77"
Long - W 103°58'35.20"
NMSPCE- N 539913.2
E 610048.9
(NAD-27)

PROPOSED BOTTOM HOLE LOCATION
Lat - N 32°28'51.89"
Long - W 103°55'48.74"
NMSPCE- N 538965.4
E 624310.7
(NAD-27)

SCALE 1"-3000'

OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Courtney Lockhart 10-28-13
Signature Date

Courtney Lockhart
Printed Name

clockhart@basspet.com
Email Address

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervison, and that the same is true and correct to the best of my belief.

AUGUST 08, 2013
Date Surveyed

Signature & Seal of Professional Surveyor

GARY L. JONES NEW MEXICO 7977 REGISTERED PROFESSIONAL LAND SURVEYOR

Certificate No. Gary L. Jones 7977

BASIN SURVEYS 29160

SECTION 15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M.,

EDDY COUNTY, WELL PAD LAYOUT **NEW MEXICO.**



NOTE: WELL IS LOCATED ABOUT 15 MILES EAST, NORTHEAST OF CARLSBAD NM.

200 0 200 400 FEET

SCALE: 1" = 200'

Directions to Location:

FROM MILE MARKER 52, GO EAST 0.4 MILES TURNING SOUTH 1.0 MILES TO BOPCO MONITOR WARNING SIGN, CONTINUE SOUTH 2.9 MILES TURNING EAST 1.7 MILES TO LEASE ROAD, GO NORTH 0.2 MILES TURNING EAST AGAIN FOR 0.4 MILES TO THE BEU 220, DRILLING ISLAND IS LOCATED 1.0 MILES SOUTHEAST OF LOCATION FOLLOWING PROPOSED LEASE ROAD.

BASIN SURVEYS P.O. BOX 1786 - HOBBS, NEW MEXICO

BOPCO, L.P.

REF: BIG EDDY UNIT #254H / WELL PAD TOPO

THE BIG EDDY UNIT #254H LOCATED 1000' FROM THE NORTH LINE AND 1249' FROM THE WEST LINE OF SECTION 15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 29160	Drawn By: DAJ/JMS
Date: 08-06-2013	Disk: JMS 29160
Survey Date: 08-06-2013	Sheet 1 of 6 Sheets



BIG EDDY UNIT #254H
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: JMS 29160
Survey Date: 08-06-2013
Scale: 1" = 2000'
Date: 08-06-2013

N

BOPCO, L.P.



BIG EDDY UNIT #254H
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: JMS 29160
Survey Date: 08-06-2013
Scale: 1" = 2 Miles
Date: 08-06-2013

N

BOPCO, L.P.



BIG EDDY UNIT #254H
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

basin surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: JMS 29160

Scale: 1" = 2000'

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT #254H
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: JMS 29160

Scale: None

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.



BIG EDDY UNIT #254H (BOTTOM HOLE MAP)
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

basin surveys
focused on excellence in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. Number: JMS 29160

Scale: None

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND
NATURAL COLOR - FEE LAND

N

BOPCO, L.P.

5 6

SECTION 15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M.,

EDDY COUNTY, WELL PAD LAYOUT **NEW MEXICO.**



BOPCO, L.P.
BIG EDDY UNIT #254 1H
ELEV. - 3447'

Lat - N 32°29'01.77"
Long - W 103°58'35.20"
NMSPCE- N 539913.2
E 610048.9
(NAD-27)

NOTE: WELL IS LOCATED ABOUT 15 MILES EAST, NORTHEAST OF CARLSBAD NM.

200 0 200 400 FEET

SCALE: 1" = 200'

Directions to Location:

FROM MILE MARKER 52, GO EAST 0.4 MILES TURNING SOUTH 1.0 MILES TO BOPCO MONITOR WARNING SIGN, CONTINUE SOUTH 2.9 MILES TURNING EAST 1.7 MILES TO LEASE ROAD, GO NORTH 0.2 MILES TURNING EAST AGAIN FOR 0.4 MILES TO THE BEU 220, DRILLING ISLAND IS LOCATED 1.0 MILES SOUTHEAST OF LOCATION FOLLOWING PROPOSED LEASE ROAD.

BASIN SURVEYS P.O. BOX 1786 - HOBBS, NEW MEXICO

W.O. Number: 29160	Drawn By: DAJ/JMS
Date: 08-06-2013	Disk: JMS 29160

BOPCO, L.P.

REF: BIG EDDY UNIT #254 1H / WELL PAD TOPO

THE BIG EDDY UNIT #254 1H LOCATED 1000' FROM THE NORTH LINE AND 1249' FROM THE WEST LINE OF SECTION 15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 08-06-2013 | Sheet 1 of 6 Sheets

SECTIONS 10&15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, Proposed Road Diagram 1of2 NEW MEXICO.



LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTIONS 10&15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

SECTION 10	73.9 FEET	= 0.01 MILES	= 4.48 RODS	= 0.05 ACRES
SECTION 15	737.8 FEET	= 0.14 MILES	= 44.71 RODS	= 0.51 ACRES
TOTAL	811.7 FEET	= 0.15 MILES	= 49.19 RODS	= 0.56 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

GARY L. JONES, NEW MEXICO No. 7977
TEXAS P.L.S. No. 5074

1000 0 1000 2000 FEET

BOPCO, L.P.

REF: PROPOSED LEASE ROAD

A LEASE ROAD CROSSING USA LAND IN SECTIONS 10&15, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., LEA COUNTY, NEW MEXICO.

BASIN SURVEYS P.O. BOX 1786 – HOBBS, NEW MEXICO

W.O. Number: 28825	Drawn By: J. GOAD		
Date: 6-26-2013	Disk: JG – 28825	Survey Date: 6-17-2013	Sheet 1 of 2 Sheets

SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

Proposed Road Diagram 2 of 2



LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

2349.8 FEET = 0.45 MILES = 142.41 RODS = 1.62 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

GARY L. JONES, N.M. No. 7977
TEXAS P.L.S. No. 5074

1000 0 1000 2000 FEET

BASIN SURVEYS P.O. BOX 1786 – HOBBS, NEW MEXICO

BOPCO, L.P.

REF: PROPOSED LEASE ROAD

A LEASE ROAD CROSSING USA LAND IN SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., LEA COUNTY, NEW MEXICO.

W.O. Number: 28825	Drawn By: J. GOAD		
Date: 6-26-2013	Disk: JG – 28825	Survey Date: 6-17-2013	Sheet 2 of 2 Sheets

SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M.,
EDDY COUNTY, Production facility-New Disturbance NEW MEXICO.



LEGAL DESCRIPTION

A TRACT OF LAND LOCATED IN SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS.

BEGINNING AT A POINT WHICH LIES N0°03'45"W., 890.8 FEET AND N89°55'24"W., 1829.5 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION 9; THENCE N89°55'24"W., 300.0 FEET; THENCE N0°05'42"E., 300.0 FEET; THENCE S89°55'24"E., 300.0 FEET; THENCE S0°05'42"W., 300.0 FEET TO THE POINT OF BEGINNING. SAID TRACT OF LAND CONTAINING 2.0661 ACRES, MORE OR LESS.

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS THE REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

GARY L. JONES, N.M. P.S. No. 7977
No. 5074

GARY L. JONES NEW MEXICO 7977 REGISTERED PROFESSIONAL LAND SURVEYOR

1000 0 1000 2000 FEET

BASIN SURVEYS P.O. BOX 1786 – HOBBS, NEW MEXICO

BOPCO, L.P.

REF: PROPOSED FACILITY TRACT

A TRACT OF LAND IN
SECTION 9, TOWNSHIP 21 SOUTH, RANGE 29 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 28825	Drawn By: J. GOAD		
Date: 6-26-2013	Disk: JG – 28825	Survey Date: 6-17-2013	Sheet 1 of 1 Sheets

Surface casing is to be set into the Rustler below all fresh water sands at an approximate depth of 915' and cement circulated to surface.

7" casing will be set at approximately 13,771' MD, 9,150' TVD (Through Curve) and cemented in two stages with DV Tool set at approximately 5,000'. Cement will be circulated to surface.

Drilling procedure, BOP diagram, and anticipated tops are attached.

This well is located inside the R111 Potash area and Secretary's Potash area.

The surface location is nonstandard and located inside the Big Eddy Unit.

The bottom hole location is nonstandard and located inside the Big Eddy Unit.

Surface Lease Numbers: NMLC 0062940

Bottom Hole Lease Numbers: NMNM 006748, NMNM 006749, NMNM 006750

Fee Lease Numbers: TDY Industries

State Lease: E-5233

BOPCO, L.P., at P. O. Box 2760, Midland, TX, 79702 is a subsidiary of BOPCO, L.P., 201 Main Street, Ft. Worth, TX, 76102. Bond No. COB000050 (Nationwide).

EIGHT POINT DRILLING PROGRAM
BOPCO, L.P.

NAME OF WELL: Big Eddy Unit #254H
LEGAL DESCRIPTION - SURFACE: 1000' FNL, 1249' FWL, Section 15, T21S, R29E, Eddy County, NM.
BHL: 1980' FNL, 330' FEL, Section 13, T21S, R29E, Eddy County, New Mexico.

POINT 1: ESTIMATED FORMATION TOPS (See No. 2 Below)

POINT 2: WATER, OIL, GAS AND/OR MINERAL BEARING FORMATIONS

Anticipated Formation Tops: KB 3476' (estimated)
GL 3447'

Formation Description	Est from KB (TVD)	Est (MD)	SUB-SEA TOP	BEARING
T/Fresh Water	130'	130'	+ 3,346'	Fresh Water
T/Rustler Anhydrite	825'	825'	+ 2,651'	Barren
T/Salt	935'	935'	+ 2,541'	Barren
B/Salt	2,868'	2,868'	+ 578'	Barren
T/Delaware Mtn Group	3,273'	3,273'	+ 203'	Oil/Gas
T/Bone Spring Lime	6,999'	6,999'	- 3,523'	Oil/Gas
T/1st Bone Spring Sand	8,086'	8,086'	- 4,610'	Oil/Gas
B/1st Bone Spring Sand	8,335'	8,335'	- 4,859'	Oil/Gas
T/2nd Bone Spring "A" Sand	8,816'	8,816'	- 5,340'	Oil/Gas
B/2nd Bone Spring "A" Sand	8,992'	8,992'	- 5,516'	Oil/Gas
T/2nd Bone Spring "B" Sand	9,041'	9,041'	- 5,565'	Oil/Gas
B/2nd Bone Spring "B" Sand	9,200'	9,200'	- 5,724'	Oil/Gas
T/Wolfcamp	10,106'	10,106'	-6,630'	Oil/Gas
TD Pilot Hole Wolfcamp	11,493'	11,493'	- 8,017'	Oil/Gas

FORMATION (LATERAL HOLE)	TOP EST FROM KB (TVD)	MD	SUB-SEA TOP	BEARING
Est. KOP	7,948'	7,948'	- 4,472'	Oil/Gas
2nd Bone Spring A Sand	8,816'	9,031'	- 5,340'	Oil/Gas
2nd Bone Spring B Sand	9,041'	9,615'	- 5,565'	Oil/Gas
EOC	9,108'	10,090'	- 5,632'	Oil/Gas
Lateral Target #1	9,108'	10,129'	- 5,632'	Oil/Gas
TD Horizontal Hole	9,258'	23,271'	- 5,815'	Oil/Gas

See COA

POINT 3: CASING PROGRAM

TYPE	INTERVAL MD	HOLE SIZE	PURPOSE	INSTALLATION TYPE
20"	0' – 120'	30"	Conductor	Contractor Discretion
13-3/8", 48 ppf, H-40, or 54.5#, J-55 8rd, ST&C*	0' – ~~915'~~ 700'	17-1/2"	Surface	New
9-5/8", 40 ppf, N-80, 8rd, LT&C or 9-5/8" 40 ppf, J-55, 8rd, LT&C*	0' – ~~4,330'~~ 3900'	12-1/4"	Intermediate	New
7", 26 ppf, HCP-110, Buttress or 8rd LTC*	0' – 13,771'	8-3/4"	Production	New
Completion System				
4-1/2", 11.6 ppf, HCP-110 8rd LT&C, BTC	~~13,721'~~ – 23,271' Okay	6-1/8"	Completion System	New

*** Depending on availability.**

CASING DESIGN SAFETY FACTORS:

TYPE	TENSION	COLLAPSE	BURST
13-3/8", 48 ppf, H-40, 8rd, ST&C*	8.53	1.62	1.12
13-3/8", 54.5 ppf, J-55, 8rd, STC*	19.90	2.54	1.77
9-5/8", 40 ppf, N-80, 8rd, LT&C*	5.04	1.23	2.38
9-5/8", 40 ppf, J-55, 8rd, LT&C*	4.31	1.12	1.63
7", 26 ppf, HCP-110, Buttress or 8rd LTC*	3.38	1.56	1.95
Completion System			
4-1/2", 11.6 ppf, HCP-110 8rd. LT&C	3.01	1.65	2.07
4-1/2", 11.6 ppf, HCP-110 BTC	3.96	1.76	2.07

*** Depending on availability.**

DESIGN CRITERIA AND CASING LOADING ASSUMPTIONS:

SURFACE CASING - (13-3/8")

Tension — A 1.6 design factor utilizing the effects of buoyancy (9.2 ppg).

Collapse — A 1.0 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst — A 1.3 design factor with a surface pressure equal to the fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure a that depth. Backup pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a 1.0 psi/ft gradient. The effects of tension on burst will not be utilized.

PROTECTIVE CASING - (9-5/8")

Tension — A 1.6 design factor utilizing the effects of buoyancy (10.2 ppg).

Collapse — A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.52 psi/ft). The effects of axial load on collapse will be considered.

In the case of development drilling, collapse design should be analyzed using internal evacuation equal to 1/3 the proposed total depth of the well. This criterion will be used when there is absolutely no potential of the protective string being used as a production casing string.

Burst — A 1.0 surface design factor and a 1.3 downhole design factor with a surface pressure equivalent to the fracture gradient at setting depth less a gas gradient to the surface. Internal burst force at the shoe will be fracture pressure at that depth. Back pressure will be formation pore pressure. In all cases a conservative fracture pressure will be used such that it represents the upper limit of potential fracture resistance up to a 1.0 psi/ft gradient.

Production CASING - (7")

Tension — A 1.6 design factor utilizing the effects of buoyancy (9.0 ppg).

Collapse — A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst — A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

Completion System - (4-1/2")

Tension — A 1.6 design factor utilizing the effects of buoyancy (9.0 ppg).

Collapse — A 1.125 design factor with full internal evacuation and a collapse force equal to the mud gradient in which the casing will be run (0.48 psi/ft). The effects of axial load on collapse will be considered.

Burst — A 1.25 design factor with anticipated maximum tubing pressure (5000 psig) on top of the maximum anticipated packer fluid gradient. (0.433 psi/ft) Backup on production strings will be formation pore pressure. (0.433 psi/ft) The effects of tension on burst will not be utilized.

See COA

POINT 4: PRESSURE CONTROL EQUIPMENT (SEE ATTACHED DIAGRAMS A, B, C or D)

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed, used, maintained and tested as per Onshore Order 2. In addition to the high pressure test, a low pressure (250-300 psig) test will be performed.

After running the 9-5/8" intermediate casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the 9-5/8" intermediate casing spool (8-3/4" open hole), used, maintained and tested as per Onshore Order 2. In addition to the high pressure test, a low pressure (250-300 psig) test will be performed.

After running the 7" ~~intermediate~~ production casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the 9-5/8" intermediate casing spool (6-1/8" open hole), used, maintained and tested as per Onshore Order 2. In addition to the high pressure test, a low pressure (250-300 psig) test will be performed.

During the drilling of the pilot hole (8-3/4" hole section), BOPCO, L.P. will be utilizing and maintaining a 5M system. Once the pilot hole has been plugged back, we will return to the required 3M system. **(See Diagram D for 5M system)**

These tests will be performed:

a) Upon installation
b) After any component changes
c) Thirty days after a previous test
d) As required by well conditions
e) Any time a seal is broken within a system

A function test to insure that the preventers are operating correctly will be performed on each trip.

See COA

BOPCO, L.P. would like to request a variance to use an armored, 3", 5000 psi WP flex hose for the choke line in the drilling of the well if the rig is equip with hose. (See specification for hose that might be used, attached with APD exhibits). This is rig equipment and will help quicken nipple up time thus saving money without a safety problem. The hose itself is rated to 5000 psi ,and has 5000 psi flanges on each end. This well is to be drilled to 23,271' MD (9,258' TVD) and max surface pressure should be +/- 2295 psi as prescribed in onshore order #2 shown as max BHP minus 0.22 psi/ft. Thus, 3000 psi BOPE is all that is needed for this well. **Please refer to diagrams A, B, C or D for choke manifold and closed loop system layout. If an armored flex hose is utilized, the company man will have all of the proper certified paper work for that hose available on location.**

See COA

POINT 5: MUD PROGRAM

DEPTH	MUD TYPE	WEIGHT	FV	PV	YP	FL	Ph
0 - ~~915'~~ 700'	FW Spud Mud	8.5 – 9.2	38-70	NC	NC	NC	10.0	9.5 – 10.5
~~915'~~ – ~~4,330'~~ 3000'	Brine Water	9.8 – 10.2	28-30	NC	NC	NC	9.5 – 10.5	9.5 – 10.5
~~4,330'~~ – 13,771'	FW/Gel	8.7 – 9.0	28-36	NC	NC	NC	9.5 – 10.0	9.5 – 10.5
								Electrical stability

NOTE: May increase vis for logging purposes only.

See COA

MUD MONITORING SYSTEM

1. BOPCO L.P. plans to drill the proposed well with water and does not expect to mud up. In the event of abnormal pressures that require mudding up, BOPCO L.P will record slow pump rates on the daily drilling report on a daily basis.

2. Visual mud monitoring equipment will be installed to detect volume changes.

3. Pit volume totalizers are installed on rig before spud.

4. BOPCO L.P. has the drilling mud checked every 24 hrs., and the daily mud check will be posted in the company man's trailer.

5. BOPCO L.P will be using a 3M system so trip tanks will not be required per Onshore order #2.

6. Gas detections systems will be installed on exploratory wells per Onshore order #2. Please refer to section G under point 6 in the 8pt drilling program for H2S safety information.

BOPCO, L.P. will have auxiliary equipment in place and a 24 hour mud engineer during the drilling of the lateral to minimize the risk of an OBM spill. In the event of a spill while drilling OBM, BOPCO, L.P. has a spill contingency plan that is attached.

Sufficient mud materials will be kept at the well site to maintain mud properties and meet minimum lost circulation and weight increase requirements at all times (sack or bulk barite will not be on location until 500' above the top of the wolfcamp.)

POINT 6: TECHNICAL STAGES OF OPERATION

A) TESTING
None anticipated.

B) LOGGING

See COA

Run #1: GR with MWD during drilling of build and horizontal portions of 8-3/4" and 6-1/8" hole.

Run #2: Shuttle log w/GR, PE, Density, Neutron, Resistivity in lateral leg open hole.

Mud Logger: Rigged up at 100'

C) CONVENTIONAL CORING

None anticipated

Pilot Hole Plug Back Cement

INTERVAL	AMT SXS	FT OF FILL	TYPE	GAL/SX	PPG	FT³/SX
10,993' – 11,493'	370	500	Class H-50/50 POZ + 0.2 FL-52	5.74	14.8	1.26
10,006'-10,206'	170	200	Class H-50/50 POZ + 0.2 FL-52	5.74	14.8	1.26
7,548' – 8,048'	310	500	Class H + 1.2 CD-32 + 0.1 R3	2.93	18.0	0.89

INTERVAL	AMOUNT SXS	FT OF FILL	TYPE	GALS/SX	PPG	FT³/SX
SURFACE:						
Lead: 0' – 615'	490	615	Class C +2% CACL + 4% Bentonite + 0.25 LB/SK Cello Flake + 3 lb/sk LCM-1	8.69	13.50	1.75
Tail: 615' – 915'	340	300	Class C + 2% CACL + 0.25 LB/SK CF+ 4% Bentonite + 0.25LB/SK Cello Flake + 3 lb/sk LCM-1	6.35	14.80	1.35
INTERMEDIATE:						
Lead: 0' – 3,830'	850	3830	EconoCEM HLC + 5% CaCl + 5#/sk Gilsonite	9.32	12.90	1.85
Tail: 3,830' – 4,330'	190	500	HalCem C	6.34	14.80	1.33
Production						
Stage 1:						
Lead: 5,000' – 7,948'	260	2948	Tuned Light + 0.125 pps Poly-E-Flake	14.87	11.00	2.64
Tail: 7,948' – 13,771'	650	5823	Class "H" + 0.5% Halad-344 + 0.25% CFR-3 + 0.5% Econolite	11.41	12.00	2.03
DV Tool @ 5,000'						
Stage 2:						
See COA Lead: 0' – 5,000'	390	5000	Tuned Light + 0.125 pps Poly-E-Flake	11.70	11.00	2.35

BOPCO L.P plans to drill a pilot hole to a total depth of 11,493' (TVD). After drilling the pilot hole, BOPCO will set three cement plugs in order to plug back the pilot hole to a depth of 7,548'. The cement plug intervals will be a bottom plug from a depth of 11,493' TVD up to a depth of 10,993' TVD, an intermediate plug is to cover the Wolfcamp formation top from approximately 10,206' TVD to 10,006' TVD, followed by a top plug from a depth of 7,548' TVD to a depth of 8,048' TVD.

The cement excess pumped will be 30% above gauge hole.

CEMENT CONT'D...

Cement excesses will be as follows:

Surface – 100% excess above gauge hole with cement circulated to surface.

1st Intermediate – 30% excess above fluid caliper with cement circulated to surface.

Production – 50% excess above gauge hole or 30% above electric log caliper with cement circulated 500' up into the 9-5/8" 1st intermediate casing in areas outside the SOPA. Cement will be circulated to surface on areas inside the SOPA.
Cement volumes will be adjusted proportionately for depth changes of the multi stage tool.

E) COMPLETIONS SYSTEM

BOPCO, L.P. plans to plug and perforate the 7" casing. The top perforation will be located inside of the producing interval. A 4-1/2" completion system with open hole packers will be run in the producing lateral to a depth of 23,271'. The top of the completion system will be set at approximately 13,721', 50' inside the 7" casing. Cement will not be required for the 4-1/2" completion system.

F) DIRECTIONAL DRILLING

BOPCO, L.P. plans to drill out the 9-5/8" intermediate casing with a 8-3/4" bit to a TVD of approximately 7,948' at which point a directional hole will be kicked off of the pilot hole cement plug and drilled at an azimuth of 155.50 degrees, building angle at 6.00 deg/ 100' to a MD of 13,771'. At this depth 7", 26 ppf, HCP-110, Buttress or 8rd LTC* casing will be installed and cemented in two stages (DV Tool @ approximately 5000') with cement circulated to surface. A 6-1/8" open hole lateral will then be drilled out from 7" casing at an azimuth of 90.00 degrees, inclination of 89.34 degrees to a measured depth of 23'271', TVD 9,258'. At this depth a 4-1/2" Completion System with packers installed for zone isolation will be run into the producing lateral

G) H_2S SAFETY EQUIPMENT

H2S monitors shall be installed prior to drilling out the surface shoe. If H2S is encountered in quantities greater than 10 PPM, the well will be shut in and H2S equipment will be installed, including a flare line that will be extended pursuant to onshore oil and gas order #6. **(Please refer to diagram B or C for choke manifold and closed loop system layout when H2S is present) Please refer to H2S location diagram for location of important H2S safety items.**

See COA

H) CLOSED LOOP AND CHOKE MANIFLOLD

Please see diagram A, B, C or D depending on configuration.

POINT 7: ANTICIPATED RESERVOIR CONDITIONS

Normal pressures are anticipated throughout Delaware, Bone Spring and Wolfcamp sections. A BHP of 5378 psi (max) or MWE of 9.0 ppg is expected. Lost circulation may exist in the Delaware, Bone Spring and Wolfcamp sections from 3,240'-11,493' TVD.

See COA

POINT 8: OTHER PERTINENT INFORMATION

A) Auxiliary Equipment

Upper and lower kelly cocks. Full opening stab in valve on the rig floor.

B) Anticipated Starting Date

Upon approval

30 days drilling operations

14 days completion operations

Todd Carpenter

BOPCO, L.P.

Location: Eddy County, NM
Field: Big Eddy
Facility: Big Eddy Unit No.254H

Slot: No.254H SHL
Well: No.254H
Wellbore: No.254H PWB

BAKER HUGHES





BGGM (1945.0 to 2015.0) Dip: 60.29° Field: 48499.2 nT
Magnetic North is 7.64 degrees East of True North (at 08/07/2013)
Grid North is 0.19 degrees East of True North
To correct azimuth from True to Grid subtract 0.19 degrees
To correct azimuth from Magnetic to Grid add 7.45 degrees
For example: if the Magnetic North Azimuth = 90 degs, then the Grid North Azimuth = 90 + 7.45 = 97.45

Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	29.00	0.000	155.500	29.00	0.00	0.00	0.00	0.00
Est KOP	7948.00	0.000	155.500	7948.00	0.00	0.00	0.00	0.00
Curve 60°	8948.00	60.000	155.500	8774.99	-434.47	198.00	6.00	226.38
EOC	10090.93	89.348	90.000	9108.00	-947.65	1083.02	6.00	1143.47
TL	10090.96	89.348	90.001	9108.00	-947.65	1083.04	4.00	1143.50
No.254H PBHL	23271.69	89.348	90.001	9258.00	-947.87	14262.93	0.00	14294.39

Plot reference wellpath is Rev-C.0	
True vertical depths are referenced to Rig on No.254H SHL (KB)	Grid System: NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet
Measured depths are referenced to Rig on No.254H SHL (KB)	North Reference: Grid north
Rig on No.254H SHL (KB) to Mean Sea Level: 3475 feet	Scale: True distance
Mean Sea Level to Mud line (At Slot: No.254H SHL): 0 feet	Depths are in feet
Coordinates are in feet referenced to Slot	Created by: gentbry on 08/08/2013



Azimuth 93.80° with reference 0.00 N, 0.00 E

Rev-C.0

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	**BOPCO, L.P.**	Slot	**No.254H SHL**
Area	**Eddy County, NM**	Well	**No.254H**
Field	**Big Eddy**	Wellbore	**No.254H PWB**
Facility	**Big Eddy Unit No.254H**		

REPORT SETUP INFORMATION			
Projection System	**NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet**	Software System	**WellArchitect® 3.0.0**
North Reference	**Grid**	User	**Gentbry**
Scale	**0.999923**	Report Generated	**08/09/2013** at **10:22:15 AM**
Convergence at slot	**0.19° East**	Database/Source file	**WA Midland/No.254H_PWB.xml**

WELLPATH LOCATION	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	**East[ft]**	**Easting[US ft]**	**Northing[US ft]**	**Latitude**	**Longitude**
Slot Location	2257.78	-801.76	**610048.90**	**539913.20**	32°29'01.776"N	103°58'35.202"W
Facility Reference Pt			**610850.60**	**537655.60**	32°28'39.408"N	103°58'25.932"W
Field Reference Pt			**610823.03**	**524402.80**	32°26'28.262"N	103°58'26.774"W

WELLPATH DATUM			
Calculation method	**Minimum curvature**	Rig on No.254H SHL (KB) to Facility Vertical Datum	**3476.00ft**
Horizontal Reference Pt	**Slot**	Rig on No.254H SHL (KB) to Mean Sea Level	**3476.00ft**
Vertical Reference Pt	**Rig on No.254H SHL (KB)**	Rig on No.254H SHL (KB) to Mud Line at Slot (No.254H SHL)	**3476.00ft**
MD Reference Pt	**Rig on No.254H SHL (KB)**	Section Origin	**N 0.00, E 0.00 ft**
Field Vertical Reference	**Mean Sea Level**	Section Azimuth	**93.80°**

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	155.500	0.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
29.00	0.000	155.500	29.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	Tie On
129.00†	0.000	155.500	129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
229.00†	0.000	155.500	229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
329.00†	0.000	155.500	329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
429.00†	0.000	155.500	429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
529.00†	0.000	155.500	529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
629.00†	0.000	155.500	629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
729.00†	0.000	155.500	729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
825.00†	0.000	155.500	825.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	T/Rustle Anhydrite
829.00†	0.000	155.500	829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
929.00†	0.000	155.500	929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
935.00†	0.000	155.500	935.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	T/Salt
1029.00†	0.000	155.500	1029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1129.00†	0.000	155.500	1129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1229.00†	0.000	155.500	1229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1329.00†	0.000	155.500	1329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1429.00†	0.000	155.500	1429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1529.00†	0.000	155.500	1529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1629.00†	0.000	155.500	1629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1729.00†	0.000	155.500	1729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1829.00†	0.000	155.500	1829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
1929.00†	0.000	155.500	1929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2029.00†	0.000	155.500	2029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2129.00†	0.000	155.500	2129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2229.00†	0.000	155.500	2229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2329.00†	0.000	155.500	2329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2429.00†	0.000	155.500	2429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2529.00†	0.000	155.500	2529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2629.00†	0.000	155.500	2629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2729.00†	0.000	155.500	2729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2829.00†	0.000	155.500	2829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
2898.00†	0.000	155.500	2898.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	B/Salt
2929.00†	0.000	155.500	2929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3029.00†	0.000	155.500	3029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3129.00†	0.000	155.500	3129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3229.00†	0.000	155.500	3229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3273.00†	0.000	155.500	3273.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	T/Delaware Mtn Group
3329.00†	0.000	155.500	3329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3429.00†	0.000	155.500	3429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3529.00†	0.000	155.500	3529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3629.00†	0.000	155.500	3629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3729.00†	0.000	155.500	3729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3829.00†	0.000	155.500	3829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
3929.00†	0.000	155.500	3929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
4029.00†	0.000	155.500	4029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4129.00†	0.000	155.500	4129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4229.00†	0.000	155.500	4229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4329.00†	0.000	155.500	4329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4343.00†	0.000	155.500	4343.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	T/Lamar Lime
4429.00†	0.000	155.500	4429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4529.00†	0.000	155.500	4529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4629.00†	0.000	155.500	4629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4729.00†	0.000	155.500	4729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4829.00†	0.000	155.500	4829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
4929.00†	0.000	155.500	4929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5029.00†	0.000	155.500	5029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5129.00†	0.000	155.500	5129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5229.00†	0.000	155.500	5229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5329.00†	0.000	155.500	5329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5429.00†	0.000	155.500	5429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5529.00†	0.000	155.500	5529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5629.00†	0.000	155.500	5629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5729.00†	0.000	155.500	5729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5829.00†	0.000	155.500	5829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
5929.00†	0.000	155.500	5929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6029.00†	0.000	155.500	6029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6129.00†	0.000	155.500	6129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6229.00†	0.000	155.500	6229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6329.00†	0.000	155.500	6329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6429.00†	0.000	155.500	6429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6529.00†	0.000	155.500	6529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6629.00†	0.000	155.500	6629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6729.00†	0.000	155.500	6729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6829.00†	0.000	155.500	6829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6929.00†	0.000	155.500	6929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
6999.00†	0.000	155.500	6999.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	T/Bone Spring Lime
7029.00†	0.000	155.500	7029.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7129.00†	0.000	155.500	7129.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7229.00†	0.000	155.500	7229.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7329.00†	0.000	155.500	7329.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7429.00†	0.000	155.500	7429.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7529.00†	0.000	155.500	7529.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7629.00†	0.000	155.500	7629.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7729.00†	0.000	155.500	7729.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7829.00†	0.000	155.500	7829.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7929.00†	0.000	155.500	7929.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	
7948.00	0.000	155.500	7948.00	0.00	0.00	0.00	610048.90	539913.20	32°29'01.776"N	103°58'35.202"W	0.00	Est KOP
8029.00†	4.860	155.500	8028.90	1.63	-3.12	1.42	610050.32	539910.08	32°29'01.745"N	103°58'35.186"W	6.00	
8086.48†	8.309	155.500	8086.00	4.75	-9.12	4.16	610053.06	539904.08	32°29'01.685"N	103°58'35.154"W	6.00	T/1st Bone Spring Sand

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
8129.00†	10.860	155.500	8127.92	8.11	-15.56	7.09	610055.99	539897.64	32°29'01.622"N	103°58'35.120"W	6.00	
8229.00†	16.860	155.500	8224.96	19.46	-37.35	17.02	610065.92	539875.85	32°29'01.406"N	103°58'35.005"W	6.00	
8329.00†	22.860	155.500	8318.97	35.56	-68.25	31.10	610080.00	539844.96	32°29'01.099"N	103°58'34.842"W	6.00	
8346.46†	23.908	155.500	8335.00	38.85	-74.56	33.98	610082.87	539838.65	32°29'01.037"N	103°58'34.809"W	6.00	B/1st Bone Spring Sand
8429.00†	28.860	155.500	8408.92	56.23	-107.92	49.18	610098.08	539805.29	32°29'00.706"N	103°58'34.632"W	6.00	
8529.00†	34.860	155.500	8493.81	81.25	-155.93	71.06	610119.96	539757.28	32°29'00.230"N	103°58'34.379"W	6.00	
8629.00†	40.860	155.500	8572.73	110.33	-211.75	96.50	610145.39	539701.46	32°28'59.677"N	103°58'34.084"W	6.00	
8729.00†	46.860	155.500	8644.80	143.17	-274.78	125.22	610174.11	539638.45	32°28'59.053"N	103°58'33.751"W	6.00	
8829.00†	52.860	155.500	8709.23	179.40	-344.31	156.91	610205.80	539568.92	32°28'58.364"N	103°58'33.384"W	6.00	
8929.00†	58.860	155.500	8765.33	218.62	-419.59	191.22	610240.10	539493.64	32°28'57.618"N	103°58'32.986"W	6.00	
8948.00	60.000	155.500	8774.99	226.38	-434.47	198.00	610246.89	539478.76	32°28'57.470"N	103°58'32.908"W	6.00	Curve 60°
9029.00†	61.143	150.073	8814.81	262.72	-497.17	230.26	610279.14	539416.07	32°28'56.849"N	103°58'32.534"W	6.00	
9031.46†	61.181	149.911	8816.00	263.92	-499.03	231.34	610280.22	539414.20	32°28'56.830"N	103°58'32.521"W	6.00	T/2nd Bone Spring "A" Sand
9129.00†	62.844	143.552	8861.81	315.83	-570.98	278.58	610327.46	539342.27	32°28'56.117"N	103°58'31.973"W	6.00	
9229.00†	64.837	137.243	8905.93	377.49	-640.05	335.79	610384.66	539273.20	32°28'55.431"N	103°58'31.307"W	6.00	
9329.00†	67.088	131.149	8946.69	447.03	-703.64	401.25	610450.12	539209.61	32°28'54.800"N	103°58'30.546"W	6.00	
9429.00†	69.564	125.264	8983.65	523.68	-761.05	474.25	610523.12	539152.21	32°28'54.229"N	103°58'29.696"W	6.00	
9453.27†	70.195	123.865	8992.00	543.26	-773.98	493.02	610541.88	539139.28	32°28'54.101"N	103°58'29.477"W	6.00	B/2nd Bone Spring "A" Sand
9529.00†	72.231	119.572	9016.40	606.60	-811.65	553.99	610602.85	539101.62	32°28'53.726"N	103°58'28.767"W	6.00	
9615.31†	74.662	114.799	9041.00	682.52	-849.41	627.57	610676.42	539063.85	32°28'53.350"N	103°58'27.910"W	6.00	T/2nd Bone Spring "B" Sand
9629.00†	75.057	114.053	9044.57	694.88	-854.88	639.60	610688.45	539058.39	32°28'53.296"N	103°58'27.769"W	6.00	
9729.00†	78.013	108.679	9067.87	787.56	-890.26	730.13	610778.97	539023.01	32°28'52.942"N	103°58'26.714"W	6.00	
9829.00†	81.068	103.425	9086.04	883.61	-917.42	824.59	610873.43	538995.85	32°28'52.671"N	103°58'25.612"W	6.00	
9929.00†	84.196	98.258	9098.87	982.00	-936.05	921.96	610970.78	538977.22	32°28'52.483"N	103°58'24.477"W	6.00	
10029.00†	87.370	93.149	9106.23	1081.62	-945.95	1021.15	611069.96	538967.33	32°28'52.382"N	103°58'23.319"W	6.00	
10090.93	89.348	90.000	9108.00	1143.47	-947.65	1083.02	611131.83	538965.63	32°28'52.363"N	103°58'22.597"W	6.00	EOC
10090.96	89.348	90.001	9108.00	1143.50	-947.65	1083.04	611131.86	538965.63	32°28'52.363"N	103°58'22.597"W	4.00	TL
10129.00†	89.348	90.001	9108.43	1181.46	-947.65	1121.08	611169.89	538965.63	32°28'52.362"N	103°58'22.152"W	0.00	
10229.00†	89.348	90.001	9109.57	1281.23	-947.65	1221.08	611269.88	538965.63	32°28'52.358"N	103°58'20.985"W	0.00	
10329.00†	89.348	90.001	9110.71	1381.00	-947.65	1321.07	611369.87	538965.62	32°28'52.355"N	103°58'19.818"W	0.00	
10429.00†	89.348	90.001	9111.85	1480.78	-947.65	1421.06	611469.85	538965.62	32°28'52.351"N	103°58'18.651"W	0.00	
10529.00†	89.348	90.001	9112.99	1580.55	-947.65	1521.06	611569.84	538965.62	32°28'52.348"N	103°58'17.483"W	0.00	
10629.00†	89.348	90.001	9114.12	1680.32	-947.66	1621.05	611669.82	538965.62	32°28'52.345"N	103°58'16.316"W	0.00	
10729.00†	89.348	90.001	9115.26	1780.10	-947.66	1721.04	611769.81	538965.62	32°28'52.341"N	103°58'15.149"W	0.00	
10829.00†	89.348	90.001	9116.40	1879.87	-947.66	1821.04	611869.79	538965.62	32°28'52.338"N	103°58'13.982"W	0.00	
10929.00†	89.348	90.001	9117.54	1979.64	-947.66	1921.03	611969.78	538965.61	32°28'52.335"N	103°58'12.814"W	0.00	
11029.00†	89.348	90.001	9118.68	2079.42	-947.66	2021.03	612069.77	538965.61	32°28'52.331"N	103°58'11.647"W	0.00	
11129.00†	89.348	90.001	9119.81	2179.19	-947.66	2121.02	612169.75	538965.61	32°28'52.328"N	103°58'10.480"W	0.00	
11229.00†	89.348	90.001	9120.95	2278.96	-947.67	2221.01	612269.74	538965.61	32°28'52.324"N	103°58'09.313"W	0.00	
11329.00†	89.348	90.001	9122.09	2378.74	-947.67	2321.01	612369.72	538965.61	32°28'52.321"N	103°58'08.145"W	0.00	
11429.00†	89.348	90.001	9123.23	2478.51	-947.67	2421.00	612469.71	538965.60	32°28'52.318"N	103°58'06.978"W	0.00	
11529.00†	89.348	90.001	9124.37	2578.29	-947.67	2520.99	612569.69	538965.60	32°28'52.314"N	103°58'05.811"W	0.00	
11629.00†	89.348	90.001	9125.50	2678.06	-947.67	2620.99	612669.68	538965.60	32°28'52.311"N	103°58'04.644"W	0.00	
11729.00†	89.348	90.001	9126.64	2777.83	-947.68	2720.98	612769.66	538965.60	32°28'52.307"N	103°58'03.476"W	0.00	
11829.00†	89.348	90.001	9127.78	2877.61	-947.68	2820.97	612869.65	538965.60	32°28'52.304"N	103°58'02.309"W	0.00	

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
11929.00†	89.348	90.001	9128.92	2977.38	-947.68	2920.97	612969.64	538965.60	32°28'52.301"N	103°58'01.142"W	0.00	
12029.00†	89.348	90.001	9130.06	3077.15	-947.68	3020.96	613069.62	538965.59	32°28'52.297"N	103°57'59.975"W	0.00	
12129.00†	89.348	90.001	9131.19	3176.93	-947.68	3120.95	613169.61	538965.59	32°28'52.294"N	103°57'58.807"W	0.00	
12229.00†	89.348	90.001	9132.33	3276.70	-947.68	3220.95	613269.59	538965.59	32°28'52.290"N	103°57'57.640"W	0.00	
12329.00†	89.348	90.001	9133.47	3376.47	-947.69	3320.94	613369.58	538965.59	32°28'52.287"N	103°57'56.473"W	0.00	
12429.00†	89.348	90.001	9134.61	3476.25	-947.69	3420.93	613469.56	538965.59	32°28'52.283"N	103°57'55.306"W	0.00	
12529.00†	89.348	90.001	9135.75	3576.02	-947.69	3520.93	613569.55	538965.59	32°28'52.280"N	103°57'54.138"W	0.00	
12629.00†	89.348	90.001	9136.88	3675.79	-947.69	3620.92	613669.54	538965.58	32°28'52.277"N	103°57'52.971"W	0.00	
12729.00†	89.348	90.001	9138.02	3775.57	-947.69	3720.92	613769.52	538965.58	32°28'52.273"N	103°57'51.804"W	0.00	
12829.00†	89.348	90.001	9139.16	3875.34	-947.69	3820.91	613869.51	538965.58	32°28'52.270"N	103°57'50.637"W	0.00	
12929.00†	89.348	90.001	9140.30	3975.12	-947.70	3920.90	613969.49	538965.58	32°28'52.266"N	103°57'49.469"W	0.00	
13029.00†	89.348	90.001	9141.44	4074.89	-947.70	4020.90	614069.48	538965.58	32°28'52.263"N	103°57'48.302"W	0.00	
13129.00†	89.348	90.001	9142.57	4174.66	-947.70	4120.89	614169.46	538965.58	32°28'52.259"N	103°57'47.135"W	0.00	
13229.00†	89.348	90.001	9143.71	4274.44	-947.70	4220.88	614269.45	538965.57	32°28'52.256"N	103°57'45.968"W	0.00	
13329.00†	89.348	90.001	9144.85	4374.21	-947.70	4320.88	614369.43	538965.57	32°28'52.252"N	103°57'44.800"W	0.00	
13429.00†	89.348	90.001	9145.99	4473.98	-947.70	4420.87	614469.42	538965.57	32°28'52.249"N	103°57'43.633"W	0.00	
13529.00†	89.348	90.001	9147.13	4573.76	-947.71	4520.86	614569.41	538965.57	32°28'52.246"N	103°57'42.466"W	0.00	
13629.00†	89.348	90.001	9148.26	4673.53	-947.71	4620.86	614669.39	538965.57	32°28'52.242"N	103°57'41.299"W	0.00	
13729.00†	89.348	90.001	9149.40	4773.30	-947.71	4720.85	614769.38	538965.57	32°28'52.239"N	103°57'40.131"W	0.00	
13829.00†	89.348	90.001	9150.54	4873.08	-947.71	4820.84	614869.36	538965.56	32°28'52.235"N	103°57'38.964"W	0.00	
13929.00†	89.348	90.001	9151.68	4972.85	-947.71	4920.84	614969.35	538965.56	32°28'52.232"N	103°57'37.797"W	0.00	
14029.00†	89.348	90.001	9152.82	5072.62	-947.72	5020.83	615069.33	538965.56	32°28'52.228"N	103°57'36.629"W	0.00	
14129.00†	89.348	90.001	9153.95	5172.40	-947.72	5120.82	615169.32	538965.56	32°28'52.225"N	103°57'35.462"W	0.00	
14229.00†	89.348	90.001	9155.09	5272.17	-947.72	5220.82	615269.31	538965.56	32°28'52.221"N	103°57'34.295"W	0.00	
14329.00†	89.348	90.001	9156.23	5371.94	-947.72	5320.81	615369.29	538965.55	32°28'52.218"N	103°57'33.128"W	0.00	
14429.00†	89.348	90.001	9157.37	5471.72	-947.72	5420.81	615469.28	538965.55	32°28'52.214"N	103°57'31.960"W	0.00	
14529.00†	89.348	90.001	9158.51	5571.49	-947.72	5520.80	615569.26	538965.55	32°28'52.211"N	103°57'30.793"W	0.00	
14629.00†	89.348	90.001	9159.64	5671.27	-947.73	5620.79	615669.25	538965.55	32°28'52.207"N	103°57'29.626"W	0.00	
14729.00†	89.348	90.001	9160.78	5771.04	-947.73	5720.79	615769.23	538965.55	32°28'52.204"N	103°57'28.459"W	0.00	
14829.00†	89.348	90.001	9161.92	5870.81	-947.73	5820.78	615869.22	538965.55	32°28'52.200"N	103°57'27.291"W	0.00	
14929.00†	89.348	90.001	9163.06	5970.59	-947.73	5920.77	615969.20	538965.54	32°28'52.197"N	103°57'26.124"W	0.00	
15029.00†	89.348	90.001	9164.20	6070.36	-947.73	6020.77	616069.19	538965.54	32°28'52.193"N	103°57'24.957"W	0.00	
15129.00†	89.348	90.001	9165.33	6170.13	-947.73	6120.76	616169.18	538965.54	32°28'52.190"N	103°57'23.790"W	0.00	
15229.00†	89.348	90.001	9166.47	6269.91	-947.74	6220.75	616269.16	538965.54	32°28'52.186"N	103°57'22.622"W	0.00	
15329.00†	89.348	90.001	9167.61	6369.68	-947.74	6320.75	616369.15	538965.54	32°28'52.183"N	103°57'21.455"W	0.00	
15429.00†	89.348	90.001	9168.75	6469.45	-947.74	6420.74	616469.13	538965.54	32°28'52.179"N	103°57'20.288"W	0.00	
15529.00†	89.348	90.001	9169.89	6569.23	-947.74	6520.73	616569.12	538965.53	32°28'52.176"N	103°57'19.121"W	0.00	
15629.00†	89.348	90.001	9171.02	6669.00	-947.74	6620.73	616669.10	538965.53	32°28'52.172"N	103°57'17.953"W	0.00	
15729.00†	89.348	90.001	9172.16	6768.77	-947.74	6720.72	616769.09	538965.53	32°28'52.169"N	103°57'16.786"W	0.00	
15829.00†	89.348	90.001	9173.30	6868.55	-947.75	6820.71	616869.08	538965.53	32°28'52.165"N	103°57'15.619"W	0.00	
15929.00†	89.348	90.001	9174.44	6968.32	-947.75	6920.71	616969.06	538965.53	32°28'52.162"N	103°57'14.452"W	0.00	
16029.00†	89.348	90.001	9175.58	7068.10	-947.75	7020.70	617069.05	538965.53	32°28'52.158"N	103°57'13.284"W	0.00	
16129.00†	89.348	90.001	9176.71	7167.87	-947.75	7120.70	617169.03	538965.52	32°28'52.154"N	103°57'12.117"W	0.00	
16229.00†	89.348	90.001	9177.85	7267.64	-947.75	7220.69	617269.02	538965.52	32°28'52.151"N	103°57'10.950"W	0.00	
16329.00†	89.348	90.001	9178.99	7367.42	-947.75	7320.68	617369.00	538965.52	32°28'52.147"N	103°57'09.783"W	0.00	

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS °/100ft	Comments
16429.00†	89.348	90.001	9180.13	7467.19	-947.76	7420.68	617468.99	538965.52	32°28'52.144"N	103°57'08.615"W	0.00	
16529.00†	89.348	90.001	9181.27	7566.96	-947.76	7520.67	617568.97	538965.52	32°28'52.140"N	103°57'07.448"W	0.00	
16629.00†	89.348	90.001	9182.40	7666.74	-947.76	7620.66	617668.96	538965.51	32°28'52.137"N	103°57'06.281"W	0.00	
16729.00†	89.348	90.001	9183.54	7766.51	-947.76	7720.66	617768.95	538965.51	32°28'52.133"N	103°57'05.114"W	0.00	
16829.00†	89.348	90.001	9184.68	7866.28	-947.76	7820.65	617868.93	538965.51	32°28'52.130"N	103°57'03.946"W	0.00	
16929.00†	89.348	90.001	9185.82	7966.06	-947.77	7920.64	617968.92	538965.51	32°28'52.126"N	103°57'02.779"W	0.00	
17029.00†	89.348	90.001	9186.96	8065.83	-947.77	8020.64	618068.90	538965.51	32°28'52.122"N	103°57'01.612"W	0.00	
17129.00†	89.348	90.001	9188.09	8165.60	-947.77	8120.63	618168.89	538965.51	32°28'52.119"N	103°57'00.445"W	0.00	
17229.00†	89.348	90.001	9189.23	8265.38	-947.77	8220.62	618268.87	538965.50	32°28'52.115"N	103°56'59.277"W	0.00	
17329.00†	89.348	90.001	9190.37	8365.15	-947.77	8320.62	618368.86	538965.50	32°28'52.112"N	103°56'58.110"W	0.00	
17429.00†	89.348	90.001	9191.51	8464.92	-947.77	8420.61	618468.85	538965.50	32°28'52.108"N	103°56'56.943"W	0.00	
17529.00†	89.348	90.001	9192.65	8564.70	-947.78	8520.60	618568.83	538965.50	32°28'52.105"N	103°56'55.776"W	0.00	
17629.00†	89.348	90.001	9193.78	8664.47	-947.78	8620.60	618668.82	538965.50	32°28'52.101"N	103°56'54.608"W	0.00	
17729.00†	89.348	90.001	9194.92	8764.25	-947.78	8720.59	618768.80	538965.50	32°28'52.097"N	103°56'53.441"W	0.00	
17829.00†	89.348	90.001	9196.06	8864.02	-947.78	8820.58	618868.79	538965.49	32°28'52.094"N	103°56'52.274"W	0.00	
17929.00†	89.348	90.001	9197.20	8963.79	-947.78	8920.58	618968.77	538965.49	32°28'52.090"N	103°56'51.107"W	0.00	
18029.00†	89.348	90.001	9198.34	9063.57	-947.78	9020.57	619068.76	538965.49	32°28'52.087"N	103°56'49.939"W	0.00	
18129.00†	89.348	90.001	9199.47	9163.34	-947.79	9120.57	619168.74	538965.49	32°28'52.083"N	103°56'48.772"W	0.00	
18175.13†	89.348	90.001	9200.00	9209.37	-947.79	9166.70	619214.87	538965.49	32°28'52.081"N	103°56'48.234"W	0.00	B/2nd Bone Spring "B" Sand
18229.00†	89.348	90.001	9200.61	9263.11	-947.79	9220.56	619268.73	538965.49	32°28'52.079"N	103°56'47.605"W	0.00	
18329.00†	89.348	90.001	9201.75	9362.89	-947.79	9320.55	619368.72	538965.49	32°28'52.076"N	103°56'46.438"W	0.00	
18429.00†	89.348	90.001	9202.89	9462.66	-947.79	9420.55	619468.70	538965.48	32°28'52.072"N	103°56'45.270"W	0.00	
18529.00†	89.348	90.001	9204.03	9562.43	-947.79	9520.54	619568.69	538965.48	32°28'52.069"N	103°56'44.103"W	0.00	
18629.00†	89.348	90.001	9205.17	9662.21	-947.79	9620.53	619668.67	538965.48	32°28'52.065"N	103°56'42.936"W	0.00	
18729.00†	89.348	90.001	9206.30	9761.98	-947.80	9720.53	619768.66	538965.48	32°28'52.061"N	103°56'41.769"W	0.00	
18829.00†	89.348	90.001	9207.44	9861.75	-947.80	9820.52	619868.64	538965.48	32°28'52.058"N	103°56'40.601"W	0.00	
18929.00†	89.348	90.001	9208.58	9961.53	-947.80	9920.51	619968.63	538965.48	32°28'52.054"N	103°56'39.434"W	0.00	
19029.00†	89.348	90.001	9209.72	10061.30	-947.80	10020.51	620068.62	538965.47	32°28'52.051"N	103°56'38.267"W	0.00	
19129.00†	89.348	90.001	9210.86	10161.08	-947.80	10120.50	620168.60	538965.47	32°28'52.047"N	103°56'37.100"W	0.00	
19229.00†	89.348	90.001	9211.99	10260.85	-947.80	10220.49	620268.59	538965.47	32°28'52.043"N	103°56'35.932"W	0.00	
19329.00†	89.348	90.001	9213.13	10360.62	-947.81	10320.49	620368.57	538965.47	32°28'52.040"N	103°56'34.765"W	0.00	
19429.00†	89.348	90.001	9214.27	10460.40	-947.81	10420.48	620468.56	538965.47	32°28'52.036"N	103°56'33.598"W	0.00	
19529.00†	89.348	90.001	9215.41	10560.17	-947.81	10520.47	620568.54	538965.46	32°28'52.032"N	103°56'32.431"W	0.00	
19629.00†	89.348	90.001	9216.55	10659.94	-947.81	10620.47	620668.53	538965.46	32°28'52.029"N	103°56'31.263"W	0.00	
19729.00†	89.348	90.001	9217.68	10759.72	-947.81	10720.46	620768.51	538965.46	32°28'52.025"N	103°56'30.096"W	0.00	
19829.00†	89.348	90.001	9218.82	10859.49	-947.82	10820.46	620868.50	538965.46	32°28'52.021"N	103°56'28.929"W	0.00	
19929.00†	89.348	90.001	9219.96	10959.26	-947.82	10920.45	620968.49	538965.46	32°28'52.018"N	103°56'27.762"W	0.00	
20029.00†	89.348	90.001	9221.10	11059.04	-947.82	11020.44	621068.47	538965.46	32°28'52.014"N	103°56'26.594"W	0.00	
20129.00†	89.348	90.001	9222.24	11158.81	-947.82	11120.44	621168.46	538965.45	32°28'52.010"N	103°56'25.427"W	0.00	
20229.00†	89.348	90.001	9223.37	11258.58	-947.82	11220.43	621268.44	538965.45	32°28'52.007"N	103°56'24.260"W	0.00	
20329.00†	89.348	90.001	9224.51	11358.36	-947.82	11320.42	621368.43	538965.45	32°28'52.003"N	103°56'23.093"W	0.00	
20429.00†	89.348	90.001	9225.65	11458.13	-947.83	11420.42	621468.41	538965.45	32°28'51.999"N	103°56'21.925"W	0.00	
20529.00†	89.348	90.001	9226.79	11557.91	-947.83	11520.41	621568.40	538965.45	32°28'51.996"N	103°56'20.758"W	0.00	
20629.00†	89.348	90.001	9227.93	11657.68	-947.83	11620.40	621668.39	538965.45	32°28'51.992"N	103°56'19.591"W	0.00	
20729.00†	89.348	90.001	9229.06	11757.45	-947.83	11720.40	621768.37	538965.44	32°28'51.988"N	103°56'18.424"W	0.00	

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

WELLPATH DATA (251 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
20829.00†	89.348	90.001	9230.20	11857.23	-947.83	11820.39	621868.36	538965.44	32°28'51.985"N	103°56'17.256"W	0.00	
20929.00†	89.348	90.001	9231.34	11957.00	-947.83	11920.38	621968.34	538965.44	32°28'51.981"N	103°56'16.089"W	0.00	
21029.00†	89.348	90.001	9232.48	12056.77	-947.84	12020.38	622068.33	538965.44	32°28'51.977"N	103°56'14.922"W	0.00	
21129.00†	89.348	90.001	9233.62	12156.55	-947.84	12120.37	622168.31	538965.44	32°28'51.974"N	103°56'13.755"W	0.00	
21229.00†	89.348	90.001	9234.75	12256.32	-947.84	12220.36	622268.30	538965.44	32°28'51.970"N	103°56'12.587"W	0.00	
21329.00†	89.348	90.001	9235.89	12356.09	-947.84	12320.36	622368.28	538965.43	32°28'51.966"N	103°56'11.420"W	0.00	
21429.00†	89.348	90.001	9237.03	12455.87	-947.84	12420.35	622468.27	538965.43	32°28'51.963"N	103°56'10.253"W	0.00	
21529.00†	89.348	90.001	9238.17	12555.64	-947.84	12520.35	622568.26	538965.43	32°28'51.959"N	103°56'09.086"W	0.00	
21629.00†	89.348	90.001	9239.31	12655.41	-947.85	12620.34	622668.24	538965.43	32°28'51.955"N	103°56'07.918"W	0.00	
21729.00†	89.348	90.001	9240.44	12755.19	-947.85	12720.33	622768.23	538965.43	32°28'51.951"N	103°56'06.751"W	0.00	
21829.00†	89.348	90.001	9241.58	12854.96	-947.85	12820.33	622868.21	538965.42	32°28'51.948"N	103°56'05.584"W	0.00	
21929.00†	89.348	90.001	9242.72	12954.73	-947.85	12920.32	622968.20	538965.42	32°28'51.944"N	103°56'04.417"W	0.00	
22029.00†	89.348	90.001	9243.86	13054.51	-947.85	13020.31	623068.18	538965.42	32°28'51.940"N	103°56'03.249"W	0.00	
22129.00†	89.348	90.001	9245.00	13154.28	-947.86	13120.31	623168.17	538965.42	32°28'51.937"N	103°56'02.082"W	0.00	
22229.00†	89.348	90.001	9246.13	13254.06	-947.86	13220.30	623268.16	538965.42	32°28'51.933"N	103°56'00.915"W	0.00	
22329.00†	89.348	90.001	9247.27	13353.83	-947.86	13320.29	623368.14	538965.42	32°28'51.929"N	103°55'59.748"W	0.00	
22429.00†	89.348	90.001	9248.41	13453.60	-947.86	13420.29	623468.13	538965.41	32°28'51.925"N	103°55'58.580"W	0.00	
22529.00†	89.348	90.001	9249.55	13553.38	-947.86	13520.28	623568.11	538965.41	32°28'51.922"N	103°55'57.413"W	0.00	
22629.00†	89.348	90.001	9250.69	13653.15	-947.86	13620.27	623668.10	538965.41	32°28'51.918"N	103°55'56.246"W	0.00	
22729.00†	89.348	90.001	9251.82	13752.92	-947.87	13720.27	623768.08	538965.41	32°28'51.914"N	103°55'55.079"W	0.00	
22829.00†	89.348	90.001	9252.96	13852.70	-947.87	13820.26	623868.07	538965.41	32°28'51.910"N	103°55'53.911"W	0.00	
22929.00†	89.348	90.001	9254.10	13952.47	-947.87	13920.25	623968.05	538965.41	32°28'51.907"N	103°55'52.744"W	0.00	
23029.00†	89.348	90.001	9255.24	14052.24	-947.87	14020.25	624068.04	538965.40	32°28'51.903"N	103°55'51.577"W	0.00	
23129.00†	89.348	90.001	9256.38	14152.02	-947.87	14120.24	624168.03	538965.40	32°28'51.899"N	103°55'50.410"W	0.00	
23229.00†	89.348	90.001	9257.51	14251.79	-947.87	14220.24	624268.01	538965.40	32°28'51.895"N	103°55'49.242"W	0.00	
23271.69	89.348	90.001	9258.00	14294.39	-947.87	14262.93	624310.70	538965.40	32°28'51.894"N	103°55'48.744"W	0.00	No.254H PBHL

HOLE & CASING SECTIONS - Ref Wellbore: No.254H PWB Ref Wellpath: Rev-C.0

String/Diameter	Start MD [ft]	End MD [ft]	Interval [ft]	Start TVD [ft]	End TVD [ft]	Start N/S [ft]	Start E/W [ft]	End N/S [ft]	End E/W [ft]
7in Casing	29.00	13772.00	13743.00	29.00	9149.89	0.00	0.00	-947.71	4763.85

Planned Wellpath Report

Rev-C.0

BAKER HUGHES

REFERENCE WELLPATH IDENTIFICATION			
Operator	BOPCO, L.P.	Slot	No.254H SHL
Area	Eddy County, NM	Well	No.254H
Field	Big Eddy	Wellbore	No.254H PWB
Facility	Big Eddy Unit No.254H		

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) No.254H PBLH (Rev-1)	23271.69	9258.00	-947.87	14262.93	**624310.70**	**538965.40**	32°28'51.894"N	103°55'48.744"W	point
No.254H PBHL		9291.00	-948.17	14162.92	**624210.70**	**538965.10**	32°28'51.895"N	103°55'49.911"W	point

SURVEY PROGRAM - Ref Wellbore: No.254H PWB Ref Wellpath: Rev-C.0

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
3476.00	23271.69	NaviTrak (Standard)		No.254H PWB

Oil-Based Drilling Mud Contingency Plan
Latshaw Rig #18

This Site Specific Contingency Plan was developed to address the identified risks associated with BOPCO, LP's drilling and production operations. The plan discusses steps to be taken to minimize or prevent spills from occurring during drilling operations.

BOPCO is currently drilling with Latshaw Rig #18 and is requesting to use an oil-based mud to improve drilling efficiency in the curve and lateral. To ensure the oil based mud is completely contained while drilling these wells, BOPCO will employ a Zero Spill Technology which will ensure all oil based mud will be contained, captured, and introduced back into the circulating system. This technology will be provided by the company Katch Kan USA. The rig will employ the light weight Kelly Kan, which redirects all the drilling fluid down through a rotary table. This product comes equipped with seals to prevent the fluid from escaping from the top. The fluid is drained downward from the bottom of the Kelly Kan. A Katch Kan Splash Guard will also be used to prevent a fluid spill from the rotary table onto the rig floor. After draining through the rotary table, the fluid is directed to the Lo-Pro Containment system. The containment tank, which holds eight barrels, will be monitored regularly and the fluid will be pumped back into the active mud system when necessary. Katch Kan USA will also provide pipe trays for setback areas to collect all fluid that drains out of the drill string and line pipe trays for rig personnel to use to capture all the stray fluid produced while breaking mud, cement, or hydraulic lines during rig operations. A mud vacuum system will be rigged up to remove the oil-based mud from pipe trays and any other area where the mud accumulates. All rig personnel will be properly trained on how to use the Zero Spill System and all the system components by Katch Kan USA before the use of the system.





Zero Spill System Kelly Kan and Splash guard shown redirecting fluid through rotary table to be captured in Lo-Pro.





Lo-Pro with ACE mounted on BOP to collect oil-based mud redirected by Kelly Kan and any other that drains off rig floor.



Drill pipe trays to capture fluid in drill string during trips.

In addition to the Katch Kan USA Zero Spill Technology system, BOPCO will employ other preventative measures to minimize hazards to the environment and human health. The drill rig is positioned on matting boards and will have a tinhorn cellar with concrete bottom. A 20 mil HDPE liner will be positioned on top of matting boards under the rig floor area to collect all spilled material and direct it to the cellar to be returned back to the circulating system. The liner will be placed in a way that minimizes tripping and slipping hazards and will be bermed to provide adequate containment capacity for these potential releases and maintenance fluids.

All oil-based mud will be trucked in from the mud plant to site. A maximum of 500 bbl of diesel will be stored in a tank on site for use in mud maintenance as well as three 500 bbl frac tanks for mud storage. The frac tank area will have a berm surrounding the tanks to contain any spilled fluid. Spill trays will be used in both of these areas to contain any spilled liquid caused from utilized connections.



13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic
Diagram A

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.



13-5/8" X 3-M BOPE (2 Rams and Rotating Head) &
Closed Loop System Equipment Schematic
H2S contingency
Diagram B

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.



Latshaw 4 closed loop system, with Latshaw 18 addition "clouded."

Latshaw 13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic Diagram C

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.



Latshaw 4 closed loop system, with Latshaw 18 addition "clouded."

Latshaw 13-5/8" X 5-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic Diagram D

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.

MIDWEST

HOSE AND SPECIALTY INC.

INTERNAL HYDROSTATIC TEST REPORT		
Customer: LATSHAW DRILLING		**P.O. Number:** RIG#4
HOSE SPECIFICATIONS		
Type: CHOKE LINE		**Length:** 30'
I.D. 3" *INCHES*		**O.D.** 6" *INCHES*
WORKING PRESSURE 5,000 *PSI*	**TEST PRESSURE** 10,000 *PSI*	**BURST PRESSURE** *PSI*
COUPLINGS		
Type of End Fitting 4 1/16 5K FLANGE		
Type of Coupling: SWEDGED	**MANUFACTURED BY** MIDWEST HOSE & SPECIALTY	
PROCEDURE		
Hose assembly pressure tested with water at ambient temperature.		
TIME HELD AT TEST PRESSURE 1 *MIN.*	ACTUAL BURST PRESSURE: 0 *PSI*	
COMMENTS: SO#81610 Hose is covered with stainless steel armour cover and wraped with fire resistant vermiculite coated fiberglass insulation rated for 1500 degrees complete with lifting eyes		
Date: 3/2/2011	Tested By: BOBBY FINK	Approved: MENDI JACKSON

Midwest Hose & Specialty, Inc.

Internal Hydrostatic Test Graph

April 4, 2012

Customer: Latshaw

Pick Ticket #: 81610

Hose Specifications

Hose Type	Length
D	30'
I.D.	**O.D.**
3"	4 15/32
Working Pressure	**Burst Pressure**
5000 PSI	Standard Safety Multiplier Applies

Verification

Type of Fitting	Coupling Method
4 1/16 5K	Swage
Die Size	**Final O.D.**
5.12"	5.16"
Hose Serial #	**Hose Assembly Serial #**
6884	81610



Test Pressure	Time Held at Test Pressure	Actual Burst Pressure	Peak Pressure
10000 PSI	6 1/4 Minutes		10195 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: *Donnie Mclemore*

Approved By: *Bobby Fink*

RIG LAYOUT

Exhibit "D"

RIG LAYOUT SCHEMATIC
INCLUSIVE OF CLOSED-LOOP DESIGN PLAN

Solids Control Equipment Legend

1) Roll Off Bin
2) Steel Tank
3) Mud Cleaner
4) Shaker
5) Centrifuge
6) Dewatering Unit
7) Catch Tank
8) Choke Manifold
A) Bleed line from choke manifold



BIG EDDY UNIT #254H
Located 1000' FNL and 1249' FWL
Section 15, Township 21 South, Range 29 East,
N.M.P.M., Eddy County, New Mexico.

Basin Surveys
focused on excellence in the oilfield
P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 – Office
(575) 392-2206 – Fax
basinsurveys.com

W.O. Number: JMS 29160
Survey Date: 08-06-2013
Scale: 1" = 2000'
Date: 08-06-2013

N

BOPCO, L.P.

Sheet 6 of 6 Sheets

TABLE OF CONTENTS

H_2S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release, or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H_2S).

Objective:

Prevent any and all accidents, and prevent the uncontrolled release of H_2S into the atmosphere.

Provide proper evacuation procedures to cope with emergencies.

Provide immediate and adequate medical attention should an injury occur.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 500' above or three days prior to drilling into the first known sour zone

Emergency Response and Public Protection Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 500 feet above or three days prior to drilling into the first known sour zone.

Emergency call lists: Included are the telephone numbers of all persons that would need to be contacted should an H_2S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

EMERGENCY PROCEDURES AND PUBLIC PROTECTION SECTION

I. In the event of any evidence of H_2S levels above 10 ppm, take the following steps immediately:

A. Secure breathing apparatus.

B. Order non-essential personnel out of the danger zone.

C. Take steps to determine if the H_2S level can be corrected or suppressed, and if so, proceed with normal operations.

II. If uncontrollable conditions occur, proceed with the following:

A. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel and the New Mexico Oil & Gas of the situation.

B. Isolate area and prevent entry by unauthorized persons into the 100 ppm ROE.

C. Remove all personnel to the Safe Briefing Area.

D. Notify public safety personnel for help with maintaining roadblocks and implementing evacuation. Phone number list attached.

E. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.

III. Responsibility:

A. The Company Approved Supervisor shall be responsible for the total implementation of the plan.

B. The Company Approved Supervisor shall be in complete command during any emergency.

C. The Company Approved Supervisor shall designate a back up Supervisor in the event that he/she is not available.

EMERGENCY PROCEDURE IMPLEMENTATION

I. Drilling or Tripping

A. All Personnel

1. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
2. Check status of other personnel (buddy system).
3. Secure breathing apparatus.
4. Wait for orders from supervisor.

B. Drilling Foreman

1. Report to the upwind Safe Briefing Area.
2. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
3. Determine the concentration of H_2S.
4. Assess the situation and take appropriate control measures.

C. Tool Pusher

1. Report to the upwind Safe Briefing Area.
2. Don breathing apparatus and return to the point of release with the Drilling Foreman or the Driller (buddy system).
3. Determine the concentration.
4. Assess the situation and take appropriate control measures.

D. Driller

1. Check the status of other personnel (in a rescue attempt, always use the buddy system).
2. Assign the least essential person to notify the Drilling Foreman and Tool Pusher, in the event of their absence.

3. Assume the responsibility of the Drilling Foreman and the Tool Pusher until they arrive, in the event of their absence.

E. Derrick Man and Floor Hands

1. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

F. Mud Engineer

1. Report to the upwind Safe Briefing Area.

2. When instructed, begin check of mud for pH level and H_2S level.

G. On-site Safety Personnel

1. Don Breathing Apparatus.

2. Check status of all personnel.

3. Wait for instructions from Drilling Foreman or Tool Pusher.

II. Taking a Kick

A. All personnel report to the upwind Safe Briefing Area.

B. Follow standard BOP procedures.

III. Open Hole Logging

A. All unnecessary personnel should leave the rig floor.

B. Drilling Foreman and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

A. Follow "Drilling or Tripping" procedures.

B. Assure that all personnel have access to protective equipment.

SIMULATED BLOWOUT CONTROL DRILLS

All drills will be initiated by activating alarm devices (air horn). Use one long blast on the air horn for ACTUAL and SIMULATED Blowout Control Drills. This operation will be performed by the Drilling Foreman or Tool Pusher at least one time per week for each of the following conditions, with each crew:

Drill # 1 Bottom Drilling

Drill # 2 Tripping Drill Pipe

In each of these drills, the initial reaction time to shutting in the well shall be timed as well as the total time for the crew to complete its entire pit drill assignment. The times must be recorded on the IADC Driller's Log as "Blowout Control Drill".

Drill No.:		
Reaction Time to Shut-In:	minutes,	seconds.
Total Time to Complete Assignment:	minutes,	seconds.

I. Drill Overviews

A. Drill No. 1- Bottom Drilling

1. Sound the alarm immediately.
2. Stop the rotary and hoist kelly joint above the rotary table.
3. Stop the circulatory pump.
4. Close the drill pipe rams.
5. Record casing and drill pipe shut-in pressures and pit volume increases.

B. Drill No. 2 – Tripping Drill Pipe

1. Sound the alarm immediately.
2. Position the upper tool joint just above the rotary table and set the slips.

3. Install a full opening valve or inside blowout preventor tool in order to close the drill pipe.

4. Close the drill pipe rams.

5. Record the shut-in annular pressure.

II. Crew Assignments

A. Drill No. 1 – Bottom Drilling

1. Driller

   a) Stop the rotary and hoist kelly joint above the rotary table.

   b) Stop the circulatory pump.

   c) Check flow.

   d) If flowing, sound the alarm immediately.

   e) Record the shut-in drill pipe pressure.

   f) Determine the mud weight increase needed or other courses of action.

2. Derrickman

   a) Open choke line valve at BOP.

   b) Signal Floor Man # 1 at accumulator that choke line is open.

   c) Close choke and upstream valve after pipe tams have been closed.

   d) Read the shut-in annular pressure and report readings to Driller.

3. Floor Man # 1

   a) Close the pipe rams after receiving the signal from the Derrickman.

   b) Report to Driller for further instructions.

4. Floor Man # 2

   a) Notify the Tool Pusher and Operator Representative of the H_2S alarms.

   b) Check for open fires and, if safe to do so, extinguish them.

   c) Stop all welding operations.

   d) Turn-off all non-explosion proof lights and instruments.

   e) Report to Driller for further instructions.

5. Tool Pusher

   a) Report to the rig floor.

   b) Have a meeting with all crews.

   c) Compile and summarize all information.

   d) Calculate the proper kill weight.

   e) Ensure that proper well procedures are put into action.

6. Operator Representative

   a) Notify the Drilling Superintendent.

   b) Determine if an emergency exists and if so, activate the contingency plan.

B. Drill No. 2 – Tripping Pipe

1. Driller

   a) Sound the alarm immediately when mud volume increase has been detected.

   b) Position the upper tool joint just above the rotary table and set slips.

   c) Install a full opening valve or inside blowout preventor tool to close the drill pipe.

   d) Check flow.

e) Record all data reported by the crew.

f) Determine the course of action.

2. Derrickman

a) Come down out of derrick.

b) Notify Tool Pusher and Operator Representative.

c) Check for open fires and, if safe to do so, extinguish them.

d) Stop all welding operations.

e) Report to Driller for further instructions.

3. Floor Man # 1

a) Pick up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 2).

b) Tighten valve with back-up tongs.

c) Close pipe rams after signal from Floor Man # 2.

d) Read accumulator pressure and check for possible high pressure fluid leaks in valves or piping.

e) Report to Driller for further instructions.

4. Floor Man # 2

a) Pick-up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 1).

b) Position back-up tongs on drill pipe.

c) Open choke line valve at BOP.

d) Signal Floor Man # 1 at accumulator that choke line is open.

e) Close choke and upstream valve after pipe rams have been closed.

f) Check for leaks on BOP stack and choke manifold.

IGNITION PROCEDURES

Responsibility:

The decision to ignite the well is the responsibility of the DRILLING FOREMAN in concurrence with the STATE POLICE. The State Police shall be the Incident Command on the scene of any major release. Intentional ignition must be coordinated with the NMOCD and local officials. In the event the Drilling Foreman is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.

2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Foreman is responsible for igniting the well.

2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.

3. Ignite from upwind and do not approach any closer than is warranted.

4. Select the ignition site best suited for protection and which offers an easy escape route.

5. Before igniting, check for the presence of combustible gases.

6. After igniting, continue emergency actions and procedures as before.

7. All unassigned personnel will limit their actions to those directed by the Drilling Foreman.

NOTE: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide (SO_2), which is also highly toxic. Do not assume the area is safe after the well is ignited.

TRAINING REQUIREMENTS

When working in an area where Hydrogen Sulfide (H_2S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel at the well site, whether regularly assigned, contracted, or employed on an unscheduled basis, have had adequate training by a qualified instructor in the following:

1. Hazards and Characteristics of Hydrogen Sulfide and Sulfur Dioxide.
2. Physicals effects of Hydrogen Sulfide on the human body.
3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
4. H_2S detection, emergency alarm and sensor location.
5. Emergency rescue.
6. First aid and artificial resuscitation.
7. The effects of Hydrogen Sulfide on metals.
8. Location safety.

In addition, Supervisory Personnel will be trained in the following areas:

1. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well as well as blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Contingency Plan and the Public Protection Plan.

Service company personnel and visiting personnel must be notified if the zone contains H_2S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

EMERGENCY EQUIPMENT

As stated in the BLM Onshore Order 6, for wells located in a known H_2S areas, H_2S equipment will be rigged up after setting surface casing. For wells located inside known H_2S areas, the flare pit will be located 150' from the location and for wells located outside known H_2S areas, the flare pit will be located 100' away from the location. (See page 6 of Survey plat package and diagram B, C or D)

It is not anticipated that any H_2S is in the area, however in the event that H_2S is encountered, the attached H_2S Contingency Plan will be implemented. (Please refer to diagrams B, C or D for choke manifold and closed loop system layout.) See H_2S location layout diagram for location of all H_2S equipment on location.

All H_2S safety equipment and systems will be installed, tested and be operational when drilling reaches a depth of 500' above, or three days prior to penetrating a known formation containing H_2S.

Lease Entrance Sign:

Caution signs should be located at all roads providing direct access to the location. Signs shall have a yellow background with black lettering and contain the words "CAUTION" and "POISON GAS" that is legible from a distance of at least 50 feet.

LEASE NAME
CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION

Windsocks or Wind Streamers:

- A minimum of two 10" windsocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location)

Hydrogen Sulfide Detector and Alarms:

- H_2S monitors with alarms will be located on the rig floor, at the cellar, and at the mud pits. These monitors will be set to alarm at 10 PPM with a red light and to alarm at 15 PPM with a red light and audible alarm.

Well Condition Flags:

The Well Condition flags should be located at all roads providing direct access to the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions
YELLOW – Potential Danger
RED – Danger, H_2S Gas Present

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the company supervision trailer and the safe briefing areas and should include the following:
  - A minimum of two SCBA's at each briefing area and the supervisor company supervision trailer.
  - Enough air line units to operate safely, anytime the H_2S concentration reaches the IDLH level (100 PPM).
  - Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Mud Program:

The mud program has been designed to minimize the volume of H_2S circulated to the surface. Proper mud weight, safe drilling practices and the use of H_2S scavengers will minimize hazards when penetrating H_2S bearing zones.

Metallurgy:

All drill strings, casing, tubing, wellhead; blowout preventer, drilling spools, kill lines, choke manifold and lines, and valves shall be suitable for H_2S service.

Well Control Equipment:

- Flare Line (See page 6 of survey plat package for flare line reference).
- Choke manifold (See diagram B or C and refer to H2S location diagram for location of important H2S safety items).
- Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing units.
- Auxiliary equipment may include, if applicable, annular preventer & rotating head.

Communication Equipment:

- Proper communication equipment such as cell phones or 2 – way radios should be available for communication between the company man's trailer, rig floor and tool pusher's trailer.

Well Testing:

- There will be no drill stem testing.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:

Parking and Visitor area:

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- A smoking area will be designated at a pre-determined safe distance from the wellhead and any other possible flammable areas.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds or they are at a 180 degree angle if wind directions tend to shift in the area.

- Personal protective equipment should be stored at both briefing areas or if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

NOTE:

- Additional equipment will be available at Indian Fire and Safety in Hobbs, NM or at Total Safety in Hobbs, NM.

EVACUATION PLAN

General Plan

The direct lines of action to protect the public from hazardous gas situations are as follows:

1. When the company approved supervisor (Drilling Foremen, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the Area Map.

2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists and evacuation needs to be implemented.

3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.

4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, Company approved safety personnel will determine when the area is safe for re-entry.

See Emergency Action Plan

Contacting Authorities

BOPCO L.P. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H_2S CONTINGENCY PLAN EMERGENCY CONTACTS

BOPCO L.P. Midland Office 432-683-2277

Key Personnel

Name	Title	Cell Phone Number
Stephen Martinez	Drilling & Completions Manager	432-556-0262
Charles Warne	Engineer	432-312-4431
Chris Giese	Engineer	432-661-7328
Leo Bojorquez	Area Drilling Superintendent	702-280-4424
Brian Braun	Engineer	210-683-9849
Chris Volek	Engineer	785-979-2643

Artesia

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

Carlsbad

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
24 Hour	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635
National Emergency Response Center (Washington, DC)	800-424-8802

Other

Wild Well Control	432-550-6202 (Permian Basin)
Cudd PressureControl	432-580-3544 or 432-570-5300 (Permian Basin)
Flight For Life – 4000 24th St. Lubbock, Texas	806-743-9911
Aerocare – R3, Box 49F, Lubbock, Texas	806-747-8923
Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuq., NM	505-842-4433
S B Air Med Service – 2505 Clark Carr Loop SE, Albuq., NM	505-842-4949
Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM	575-393-3093
Total Safety – 3229 Industrial Dr., Hobbs, NM	575-392-2973

TOXIC EFFECTS OF HYDROGEN SULFIDE

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity = 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in Table I. Physical effects at various Hydrogen Sulfide exposure levels are shown in Table II.

Table I - TOXICITY OF VARIOUS GASES

Common Name	Chemical Formula	Specific Gravity (SC=1)	Threshold Limit (1)	Hazardous Limit (2)	Lethal Concentration (3)
Hydrogen Cyanide	HCN	0.94	10 PPM	150 PPM/HR	300 PPM
Hydrogen Sulfide	H2S	1.18	10 PPM	250 PPM/HR	600 PPM
Sulfur Dioxide	SO2	2.21	5 PPM	--	1000 PPM
Chlorine	CL2	2.45	1 PPM	4 PPM/HR	1000 PPM
Carbon Monoxide	CO	0.97	50 PPM	400 PPM/HR	1000 PPM
Carbon Dioxide	CO2	1.52	5000 PPM	5%	10%
Methane	CH4	0.55	90,000 PPM	Combustible in air	Above 5%

1) **Threshold Limit – Concentration at which it is believed that all worker may be repeatedly exposed day after day without adverse effects.**

2) **Hazardous Limit – Concentration that will cause death with short-term exposure.**

3) **Lethal Concentration – Concentration that will cause death with short-term exposure.**

Table II – PHYSICAL EFFECTS OF HYDROGEN SULFIDE

Percent (%)	PPM	Concentration Grains 100 STD. FT3*	Physical Effects
0.001	< 10	00.65	Obvious & unpleasant odor.
0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kills smell in 3-15 minutes. May sting eyes & throat.
0.020	200	12.96	Kills smell shortly; stings eyes & throat.
0.050	500	32.96	Dizziness; Breathing ceases in a few minutes. Needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; Death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; Followed by death within minutes.

- At 15.00 PSIA and 60° F.

USE OF SELF-CONTAINED BREATHING APPARATUS

1. Anyone who uses an SCBA shall: Be approved by a physician or licensed health care practitioner; Pass a fit test; Be trained in donning and doffing, proper use, including how to ensure a proper face seal, conducting an inspection of the SCBA, and conduct proper maintenance.

2. Such items as facial hair (beard or sideburns) and eyeglasses will not allow a proper face mask seal.

3. Anyone reasonably expected to wear SCBA's shall have these items removed before entering a toxic atmosphere.

4. A special mask with a mount for prescription glasses must be obtained for anyone who must wear eyeglasses in order to see while using an SCBA.

5. SCBA's should be worn in H_2S concentrations above 10 PPM.

RESCUE & FIRST AID FOR H_2S POISONING

DO NOT PANIC – REMAIN CALM – THINK

1. Hold your breath – do not inhale first.

2. Put on SCBA.

3. Remove victim(s) to fresh air as quickly as possible. Go upwind from source or at right angle to the wind. Do not go downwind.

4. Briefly apply chest pressure – using arm lift method of artificial respiration to clean victim's lungs and to avoid inhaling any toxic gas directly from victim's lungs.

5. Provide artificial respiration if needed.

6. Provide for prompt transportation to the hospital and continue giving artificial respiration if needed.

7. Inform hospital/medical facilities of the possibility of H2S gas poisoning before they treat.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration and CPR, as well as first aid for eyes and skin contact with liquid H_2S.

Exhibit "D"

RIG LAYOUT SCHEMATIC

INCLUSIVE OF CLOSED-LOOP DESIGN PLAN



Proposed H2S Safety Schematic

1) Location of windsocks.
2) Location of H2S alarms.
3) Location of briefing areas.
4) Terrain of surrounding area (Please refer to page 2 of survey plat package also see point 11 of multisurface use plan)
5) Location of flare line(s) and pit(s) (Please refer to page 6 of survey plat package and diagram)
6) Location of caution and/or danger signs.
(7) Location of Breathing Equipment



Access Road Diagram



Location On-Site Notes

Location on-site conducted by Cecil Watkins, Todd Carpenter, Chris Boyd & David Corgill -BOPCO L.P., Jim Rutley, Amanda Lynch & trainee, John Chopp-BLM, and Robert Gomez & crew-Basin Survey on 06/10/2013. A suitable location to place a ten acre drilling island at approximately 750' FNL & 1000' FWL, Sec 15-T21S-R29E (center of pad). All parties agreed on this location, with the stipulation that we would utilize water diverting berms on the eastern side of the pad upon construction. The facilities for this Drilling Island will be placed on the north side of the BEU 220 well pad. The access road for this Drilling Island will run from the facilities pad. The Big Eddy Unit #254 1H has been assigned a slot on the pad with footage calls of 1000' FNL & 1249' FWL of Section 15, T21S-R29E. Location layout is as follows: v-door will face the east, frac pad will be on north/northwest corner, access road will enter location from the north/northwest corner and topsoil will be stockpiled to the east side of location.

MULTI-POINT SURFACE USE PLAN

NAME OF WELL: BIG EDDY UNIT #254H

LEGAL DESCRIPTION - SURFACE: 1000' FNL & 1249' FWL, Section 15, T21S-R29E, Eddy County, NM.
BHL: 1980' FNL & 330' FEL, Section 13, T21S- R29E, Eddy County, New Mexico.

POINT 1: EXISTING ROADS

A) Proposed Well Site Location:

See Form C-102 (Survey Plat).

B) Existing Roads:

From mile marker 52, go east 0.4 miles turning south 1.0 miles to BOPCO monitor warning sign. Continue south 2.9 miles then turn east for 1.7 miles to lease road. Go north 0.2 miles, turning east again for 0.4 miles to the Big Eddy Unit #220. Drilling island is located 1.0 miles southeast of location following proposed lease road.

C) Existing Road Maintenance or Improvement Plan:

Existing roads will be maintained and kept in the same or better condition than before operations began. See the Well Pad Layout and Topo Map of the survey plat (Sheet 1 and 2 of plat package)

POINT 2: NEW PLANNED ACCESS ROUTE

A) Route Location:

Approximately 789' of new lease road will be built. (See the Well Pad Layout of the survey plat (Sheet 1 of plat package).

B) Width

14' wide

C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

D) Turnout Ditches

As required by BLM stipulations

E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

POINT 3: LOCATION OF EXISTING WELLS

The following wells are located within a one-mile radius of the location site. See the One-Mile Radius Map (Sheet 5 of the plat package).

Existing wells..... 6 (Six)
Water wells..... 0 (Zero)

POINT 4: LOCATION OF EXISTING OR PROPOSED FACILITIES

A) The BEU Battery 220 is within a (1) mile radius.

B) New Facilities in the Event of Production:

New production facilities will be built at BEU Battery 220. A new separator, heater treater, water and oil tanks and possibly a FWKO will be set at BEU Battery 220. A 2-7/8" or 3-1/2" in diameter steel flowline is to be run above ground, approx. 1 mile in length. The flowline is expected to carrying oil, water, and gas from the proposed well to BEU Battery 220. Power will be supplied by a Genset until adequate power can be supplied from the utility company.

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Please see Point 10

C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Please see Point 10

POINT 5: LOCATION AND TYPE OF WATER SUPPLY

A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities.

B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

POINT 6: SOURCE OF CONSTRUCTION MATERIALS

A) Materials

On-site caliche will be used. If this is not sufficient, caliche will be hauled from a BLM approved pit.

B) Land Ownership

Federally Owned, State Owned and Fee Lease

C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site

D) Access Roads

See the Well Pad Layout and Aerial Map of the survey plat (Sheet 1 and 4 of plat package)

POINT 7: METHODS FOR HANDLING WASTE MATERIAL

A) Cuttings

Cuttings will be contained in the roll off bins and disposed at R360 Environmental Solutions located in Lea County, NM.

B) Drilling Fluids

Drilling fluids will be contained in the steel pits, frac tanks and disposed at licensed disposal sites.

C) Produced Fluids

Water production will be contained in the steel pits.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. Reasonable cleanup will be performed prior to the final restoration of the site.

POINT 8: ANCILLARY FACILITIES

None required.

POINT 9: WELL SITE LAYOUT

A) Rig Orientation and Layout

The "Rig Layout Schematic" (Sheet 6 of plat package) shows the dimensions of the well pad, closed loop system, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary. **The V-Door will be on the east side, the top soil will be stockpiled on the north side and the Frac pad to the north northwest corner of the location.**

B) Locations of Access Road

See the Well Pad Layout, Topo Map, and Vicinity Map of the survey plat (Sheet 1, 2, and 3 of plat package).

C) Lining of the Pits

No reserve pits - closed loop system.

POINT 10: PLANS FOR RESTORATION OF THE SURFACE

A) Reserve Pit Cleanup - Not applicable. Closed loop drilling fluid system will be used

The pits will be fenced immediately after construction and shall be maintained until they are backfilled. Previous to backfill operations, any hydrocarbon material on the pits' surfaces shall be removed. The fluids and solids contained in the pits shall be backfilled with soil excavated from the site and soil adjacent to the reserve pits. The restored surface of the pits shall be contoured to prevent impoundment of surface water flow. Water-bars will be constructed as needed to prevent excessive erosion. Topsoil, as available, shall be placed over the restored surface in a uniform layer. The area will be seeded according to the Bureau of Land Management stipulations during the appropriate season following restoration.

B) Restoration Plans - Production Developed

BOPCO, L.P. has no plans of interim reclamation to allow for additional wells to be drilled on this pad.

C) Restoration Plans - No Production Developed

BOPCO, L.P. has no plans of interim reclamation to allow for additional wells to be drilled on this pad.

D) Rehabilitation's Timetable

Upon completion of drilling operations, the initial cleanup of the site will be performed as soon as weather and site conditions allow economic execution of the work.

POINT 11: OTHER INFORMATION

A) On-Site

Location on-site conducted by Cecil Watkins, Todd Carpenter, Chris Boyd & David Corgill -BOPCO L.P., Jim Rutley, Amanda Lynch & trainee, John Chopp-BLM, and Robert Gomez & crew-Basin Survey on 06/10/2013. A suitable location to place a ten acre drilling island at approximately 750' FNL & 1000' FWL, Sec 15-T21S-R29E (center of pad). All parties agreed on this location, with the stipulation that we would utilize water diverting berms on the eastern side of the pad upon construction. The facilities for this Drilling Island will be placed on the north side of the BEU 220 well pad. The access road for this

Drilling Island will run from the facilities pad. The Big Eddy Unit #254 has been assigned a slot on the pad with footage calls of 1000' FNL & 1249' FWL of Section 15, T21S-R29E. Location layout is as follows: v-door will face the east, frac pad will be on north/northwest corner, access road will enter location from the north/northwest corner and topsoil will be stockpiled to the east side of location.

B) Soil

Caliche and sand.

C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

POINT 11: OTHER INFORMATION – cont'd...

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There are no water wells located within a 1 mile radius of the proposed location.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

No independent archeological survey has been done. This well location is located in the area covered by Memorandum of Agreement – Permian Basin. A Payment of $1507.00 fee for this project is included in this application. Any location or construction conflicts will be resolved before construction begins. Please see diagram 4 for flowline route.

J) Surface Ownership

The well site is on federally owned land. There will be 789' of new access roads required for this location.

K) Well signs will be posted at the drilling site.

L) Open Pits

No open pits will be used for drilling or production. Any open top tanks will be netted.

M) Terrain

Slightly rolling hills.

POINT 12: OPERATOR'S FIELD REPRESENTATIVE

(Field personnel responsible for compliance with development plan for surface use).

DRILLING
Stephen Martinez
Box 2760
Midland, Texas 79702
(432) 683-2277

PRODUCTION
Gary Fletcher
3104 East Green Street
Carlsbad, New Mexico 88220
(575) 887-7329

F.R. "Fritz" Schoch
Box 2760
Midland, Texas 79702
(432) 683-227

CJL/wbm

PECOS DISTRICT
CONDITIONS OF APPROVAL

OPERATOR'S NAME:	**BOPCO, L.P.**
LEASE NO.:	**NMNM-06748**
WELL NAME & NO.:	**Big Eddy Unit 254H**
SURFACE HOLE FOOTAGE:	**1000' FNL & 1249' FWL**
BOTTOM HOLE FOOTAGE	**1980' FNL & 0330' FEL Sec. 13, T. 21 S., R 29 E.**
LOCATION:	**Section 15, T. 21 S., R 29 E., NMPM**
COUNTY:	**Eddy County, New Mexico**

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Commercial Well Determination
A commercial well determination shall be submitted after production has been established for at least six months.

Unit Wells
The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing
The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width
The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing
Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning
Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching
Ditching shall be required on both sides of the road.

Turnouts
Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage
Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: $\frac{400'}{4\%} + 100' = 200'$ lead-off ditch interval

Culvert Installations
Appropriately sized culverts shall be installed at deep waterway channel flow crossings through the road.

Cattleguards
An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings.

Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access
Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road
3. Redistribute topsoil
4. Revegetate slopes



Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

a. Spudding well (minimum of 24 hours)
b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

1. **Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is encountered in quantities greater than 10 PPM the well shall be shut in and H2S equipment shall be installed and flare line must be extended pursuant to Onshore Oil and Gas Order #6. After detection, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items.**

2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a "Major" violation.**

3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Secretary's Potash
Medium Cave/Karst
Possibility of water flows in the Salado, Castile, and Delaware.
Possibility of lost circulation in the Rustler, Delaware, and Bone Spring.
Abnormal pressures may be encountered in the 3rd Bone Spring Sand formation and Wolfcamp formation.

1. The **13-3/8** inch surface casing shall be set at approximately **700** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If Rustler is not reached and surface casing set point is expected to be deepened, operator is to contact BLM and submit a sundry indicating that a mud logger is on site and will set casing in a competent bed above the salt.**

    a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

    b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.

c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

d. If cement falls back, remedial cementing will be done prior to drilling out that string.

2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing, which shall be set at **3200** feet (set casing in the base of the limestone member), is:

☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst and potash.**

Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

Pilot hole plugging procedure approved as written. Tag the bottom hole plug (a minimum of 210') and Wolfcamp plug (a minimum of 200').

3. The minimum required fill of cement behind the **7** inch production casing is:

Operator has proposed DV tool at depth of 5000', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

a. First stage to DV tool:

☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve approved top of cement on the next stage.

b. Second stage above DV tool:

☒ Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Excess calculates to 18% - Additional cement may be required. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to potash.**

4. Cement not required on the **4-1/2"** casing. **Packer system being used.**

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M)** psi.

    a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** intermediate casing shoe shall be **5000 (5M)** psi. **5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**

Operator may return to a 3M BOP system after pilot hole is plugged.

5. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **7** production casing shoe shall be **3000 (3M)** psi.

6. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.

   a. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.

   b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

   c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock.

   d. The results of the test shall be reported to the appropriate BLM office.

   e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**

   f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

   g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

D. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the **Wolfcamp** formation, and shall be used until production casing is run and cemented. Operator shall report any mud spill to the BLM within 12 hours of the spill.

Proposed mud weight may not be adequate for drilling through Wolfcamp.

E. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

F. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 110613

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities
Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)
Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening
The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures
The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures
Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement
All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent

provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
b. Activities of other parties including, but not limited to:
    (1) Land clearing.
    (2) Earth-disturbing and earth-moving work.
    (3) Blasting.
    (4) Vandalism and sabotage.
c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars ($1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of **20** feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize

suspension of the pipeline across low areas in the terrain. In hummocky of duney areas, the pipeline will be "snaked" around hummocks and dunes rather then suspended across these features.

9. The pipeline shall be buried with a minimum of **24** inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

C. ELECTRIC LINES (Not applied for in APD)

IX. INTERIM RECLAMATION

Since it is expected that multiple wells will be drilled from this location in the future, no interim reclamation will be required. However, during the life of the development, all disturbed areas not needed for future wells or active support of production operations should undergo reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

Species	lb/acre
Sand dropseed (Sporobolus cryptandrus)	1.0
Sand love grass (Eragrostis trichodes)	1.0
Plains bristlegrass (Setaria macrostachya)	2.0

*Pounds of pure live seed:

Pounds of seed **x** percent purity **x** percent germination = pounds pure live seed