

Ocp Artesia

13-1162

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

TS  
2-11-2014

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. <del>N/A</del> <b>LL029420 B</b>
1b. Type of Well: <input type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other (SWD) <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator Burnett Oil Co., Inc.		7. If Unit or CA Agreement, Name and No.
3a. Address 801 Cherry Street, Suite 1500 Fort Worth, Texas 76102		8. Lease Name and Well No. Burnett 33 Federal 1 SWD <b>2328707</b>
3b. Phone No. (include area code) 817-332-5108 x6326		9. API Well No. <b>30-D15-42060</b>
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 360' FNL & 2050' FWL, Unit C At proposed prod. zone		10. Field and Pool, or Exploratory SWD: Wolfcamp Reef <b>&lt; 96135 &gt;</b>
14. Distance in miles and direction from nearest town or post office* Approximately 4 Miles South East of Loco Hills, NM		11. Sec., T. R. M. or Blk. and Survey or Area Section 33, T. 17S, R. 31E
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) N/A	16. No. of acres in lease Not in a lease <b>720 acres</b> <b>LL029420 B</b>	17. Spacing Unit dedicated to this well N/A
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. N/A	19. Proposed Depth 9700' TVD 9700' MD	20. BLM/BIA Bond No. on file NM-B000197 & NM-B000699 & New SWD Bond in process.
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3761' GL	22. Approximate date work will start* 09/30/2013	23. Estimated duration 30 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- |  |   |
|--|---|
| 1. Well plat certified by a registered surveyor.   | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan.  | 5. Operator certification   |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM.             |

25. Signature <i>Leslie M. Garvis</i>	Name (Printed/Typed) Leslie M. Garvis	Date 10/03/2013
--	--	--------------------

Title Regulatory Coordinator

Approved by (Signature) <b>ISI STEPHEN J. CAFFEY</b>	Name (Printed/Typed)	Date <b>FEB 10 2014</b>
---	----------------------	----------------------------

Title FIELD MANAGER Office CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.


**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

Roswell Controlled Water Basin



Approval Subject to General Requirements & Special Stipulations Attached

SEE ATTACHED FOR CONDITIONS OF APPROVAL



**BURNETT OIL Co., INC.**

**FINAL CERTIFICATION MEMO**

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that Burnett Oil Co. Inc. is responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 26<sup>th</sup> day of August 2013.

Signed: Mark A. Jacoby

Printed Name: Mark A. Jacoby  
Position: Engineering Manager  
Company: Burnett Oil Co., Inc.  
Address: 801 Cherry Street, Suite 1500, Unit #9, Fort Worth, Texas 76108  
Telephone: 817.332.5108  
Email: [mjacob@burnettoil.com](mailto:mjacoby@burnettoil.com)

**BURNETT OIL CO.**

June 2013

---


RE: Burnett 33 Fed #1  
Unit C, Section 33, Tws. 17 S., Rng. 31 E.  
Eddy Co., NM

Dear Sir:

In accordance with the Rules and Regulations of the Oil Conservation Division of the State of New Mexico, you are being provided a copy of the C-108, Application for Authorization to Inject in to the above captioned well.

Any questions about the permit can be directed to Eddie W. Seay, (575)392-2236. Any objections or request for hearing must be filed with the Oil Conservation Division within fifteen (15) days from the date received. The OCD address is 1220 S. Saint Francis Drive, Santa Fe, NM 87504, (505)476-3440.

Thank You,



Eddie W. Seay, Agent  
Eddie Seay Consulting  
601 W. Illinois  
Hobbs, NM 88242  
575-392-2236  
seay04@leaco.net

DISTRICT I  
1625 N. French Dr., Hobbs, NM 88240  
Phone (575) 393-6161 Fax: (575) 393-0720

DISTRICT II  
811 S. First St., Artesia, NM 88210  
Phone (575) 748-1263 Fax: (575) 748-0720

DISTRICT III  
1000 Rio Brazos Rd., Aztec, NM 87410  
Phone (505) 334-6178 Fax: (505) 334-6170

DISTRICT IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505  
Phone (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals and Natural Resources Department

Form C-102  
Revised August 1, 2011

Submit one copy to appropriate  
District Office

**OIL CONSERVATION DIVISION**  
1220 South St. Francis Dr.  
Santa Fe, New Mexico 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT

AMENDED REPORT

API Number <b>30-015-4200</b>	Pool Code <b>96435</b>	Pool Name <b>(SWD); WOLF CAMP REEF</b>
Property Code <b>32870 40288</b>	Property Name <b>BURNETT 33 FEDERAL</b>	Well Number <b>1SWD</b>
OGRID No. <b>03080</b>	Operator Name <b>BURNETT OIL COMPANY, INC.</b>	Elevation <b>3761'</b>

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	33	17 S	31 E		360	NORTH	2050	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County

Dedicated Acres <b>0</b>	Joint or Infill	Consolidation Code	Order No.
-----------------------------	-----------------	--------------------	-----------


NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

<p>N.: 654340.6 E.: 638486.2 NAD 27</p> <p>2050'</p> <p>3750.5'</p> <p>3759.7'</p> <p>360'</p> <p>3756.9'</p> <p>3756.8'</p>	<p><b>SURFACE LOCATION</b></p> <p>Lat - N 32.797120536 Long - W 103.875986591 NMSPC - N 654007.3 E 640535.5 (NAD-27)</p>		<p>N.: 654408.9 E.: 643752.1 NAD 27</p>	<p><b>OPERATOR CERTIFICATION</b></p> <p>I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.</p> <p><i>Leslie Garvis</i> 6-28-13 Signature Date Leslie Garvis Printed Name leslie.garvis@burnettoil.com Email Address</p>
	<p>N.: 651732.7 E.: 638485.4 NAD 27</p>	<p><b>SURVEYOR CERTIFICATION</b></p> <p>I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.</p> <p><i>Gary L. Jones</i> 6-28-13 Date Surveyed Signature Seal of Professional Surveyor 7877 Certificate No. Gary L. Jones 7977</p>		
<p>N.: 649092.7 E.: 638500.8 NAD 27</p>	<p>N.: 649128.4 E.: 643782.2 NAD 27</p>	<p>Certificate No. Gary L. Jones 7977</p> <p><b>Basin Surveys 28897</b></p>		

# EXHIBIT A

**SECTION 33, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.**

**BURNETT OIL COMPANY, INC.**  
**BURNETT-33 FEDERAL #1 SWD**  
**ELEV. - 3761'**  
 Lat - N 32.797120536  
 Long - W 103.875986591  
 NMSPE - N 654007.3  
           E 640535.5  
 (NAD-27)



LOCO HILLS, NM IS ±6 MILES TO THE NORTHWEST OF LOCATION.  
 200                      0                      200                      400 FEET  
  
 SCALE: 1" = 200'

Directions to Location:

FROM HIGHWAY 82 AND COUNTY ROAD 222  
 (SHUGART ROAD) GO SOUTH 1.2 MILES TURN EAST  
 GO 0.4 MILES TO PROPOSED ROAD TO LOCATION.

## BURNETT OIL COMPANY, INC.

REF: BURNETT 33 FEDERAL #1 SWD / WELL PAD TOPO

THE BURNETT 33 FEDERAL #1 SWD LOCATED 360'  
 FROM THE NORTH LINE AND 2050' FROM THE WEST LINE OF  
 SECTION 33, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
 N.M.P.M., EDDY COUNTY, NEW MEXICO.


**BASIN SURVEYS** P.O. BOX 1786 - HOBBS, NEW MEXICO

W.O. Number: 28897                      Drawn By: J. GOAD

Date: 6-25-2013                      Disk: JG - 28897

Survey Date: 6-20-2013                      Sheet 1 of 1 Sheets

# EXHIBIT B



**BURNETT 33 FEDERAL #1 SWD**  
 Located 360' FNL and 2050' FWL  
 Section 33, Township 17 South, Range 31 East,  
 N.M.P.M., Eddy County, New Mexico.

**basin  
surveys**

focused on excellence  
in the oilfield

P.O. Box 1786  
 1120 N. West County Rd.  
 Hobbs, New Mexico 88241  
 (575) 393-7316 - Office  
 (575) 392-2206 - Fax  
 basinsurveys.com

W.O. Number: JG - 28897.


Survey Date: 6-20-2013

Scale: 1" = 2000'


Date: 6-25-2013

**BURNETT OIL  
COMPANY, INC.**

# EXHIBIT C



**BURNETT 33 FEDERAL #1 SWD**  
 Located 360' FNL and 2050' FWL  
 Section 33, Township 17 South, Range 31 East,  
 N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786  
 1120 N. West County Rd.  
 Hobbs, New Mexico 88241  
 (575) 393-7316 - Office  
 (575) 392-2206 - Fax  
 basinsurveys.com

W.O. Number: JG - 28897


Survey Date: 6-20-2013

Scale: 1" = 2 Miles


Date: 6-25-2013

**BURNETT OIL  
 COMPANY, INC.**

EXHIBIT D



BURNETT 33 FEDERAL #1 SWD  
Located 360' FNL and 2050' FWL  
Section 33, Township 17 South, Range 31 East,  
N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786  
1120 N. West County Rd.  
Hobbs, New Mexico 88241  
(575) 393-7316 - Office  
(575) 392-2206 - Fax  
basinsurveys.com

W.O. Number: JG - 28897


Scale: 1" = 2000'

YELLOW TINT - USA LAND  
BLUE TINT - STATE LAND  
NATURAL COLOR - FEE LAND

BURNETT OIL  
COMPANY, INC.

EXHIBIT E

SECTION 12, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



LEGAL DESCRIPTION


A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 12, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

1108.0 FEET = 67.15 RODS = 0.21 MILES = 0.76 ACRES

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

**GARY L. JONES**  
PROFESSIONAL LAND SURVEYOR  
NEW MEXICO  
1977

GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 12, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013


Disk: JG - 28797

Survey Date: 6-1-2013

Sheet 1 of 8 Sheets

EXHIBIT F

SECTION 13, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



11+08 SECTION LINE  
15+25 OVERHEAD ELECTRIC  
15+85 LEASE ROAD  
17+35.1 PI 7°42'06\" LT  
18+16 LEASE ROAD

28+21.3 PI 50°46'10\" LT  
28+40 2-4\" FLOW LINES  
28+45 LEASE ROAD  
28+50 2-4\" FLOW LINE  
28+87.5 PI 34°28'12\" LT  
34+50 OVERHEAD ELECTRIC  
36+65.6 PI 41\" RT  
37+58.2 PI 9°04'57\" RT  
39+52.3 PI 25°06'41\" LT

OWNER: USA  
LESSEE: CASWELL RANCHES

57+93.5 PI 38°44'35\" RT  
58+80.6 PI 39°17'30\" RT  
60+87.7 PI 21°24'38\" LT

68+50.3 PI 35°04'25\" LT  
69+00 RIPPLE ROAD

74+59.5 SECTION LINE

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 13, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

6351.5 FEET = 384.94 RODS = 1.20 MILES = 4.37 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

**GARY L. JONES**  
PROFESSIONAL LAND SURVEYOR  
NEW MEXICO  
7877

GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL


A PIPELINE CROSSING USA LAND IN  
SECTION 13, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

W.O. Number: 28797	Drawn By: J. GOAD
Date: 7-1-2013	Disk: JG - 28797
Survey Date: 6-1-2013	Sheet 2 of 8 Sheets

**BASIN SURVEYS** P.O. BOX 1786 - HOBBS, NEW MEXICO

# EXHIBIT G

## SECTION 24, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.




### LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 24, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

5404.2 FEET = 327.53 RODS = 1.02 MILES = 3.72 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF A CADASTRAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074

1000 0 1000 2000 FEET

### BURNETT OIL COMPANY, INC.

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 24, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786-HOBBS, NEW MEXICO


W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013 Disk: JG - 28797

Survey Date: 6-1-2013 Sheet 3 of 8 Sheets

# EXHIBIT H

**SECTION 25, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.**



**OWNER: USA  
LESSEE: CASWELL RANCHES**


**R-31-E  
R-32-E**

**LEGAL DESCRIPTION**

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 25, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

4612.6 FEET = 279.55 RODS = 0.87 MILES = 3.18 ACRES

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED FROM FIELD NOTES OF AN ORIGINAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 25, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786 - HOBBS, NEW MEXICO


W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013 Disk: JG - 28797

Survey Date: 6-1-2013 Sheet 4 of 8 Sheets

# EXHIBIT I


**SECTION 26, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.**



**LEGAL DESCRIPTION**

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 26, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

5282.2 FEET = 320.13 RODS = 1.00 MILES = 3.64 ACRES



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED FROM FIELD NOTES OF AN ORIGINAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.

GARY L. JONES, Surveyor, No. 7977, Texas P.L.S., No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 26, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786 - HOBBS, NEW MEXICO

W.O. Number: 28797      Drawn By: J. GOAD

Date: 7-1-2013


Disk: JG - 28797

Survey Date: 6-1-2013

Sheet 5 of 8 Sheets

# EXHIBIT J

**SECTION 27, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.**




**OWNER: USA  
LESSEE: ROSS OR JILL CAVINESS**

**LEGAL DESCRIPTION**

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 27, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

5281.9 FEET = 320.11 RODS = 1.00 MILES = 3.64 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY HIS STATE.



GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD. WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 27, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013


Disk: JG - 28797

Survey Date: 6-1-2013

Sheet 6 of 8 Sheets

EXHIBIT K

SECTION 28, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



OWNER: USA  
LESSEE: ROSS OR JILL CAVINESS

280+40.4 SECTION LINE  
286+84.2 PI 6°24'00" RT  
298+56 BPL  
298+80 ROAD  
299+13.8 PI 46°21'40" LT  
299+56.2 PI 45°00'09" LT  
300+15 BPL  
300+45 OVERHEAD ELECTRIC  
300+86 OVERHEAD ELECTRIC

319+15 PI 44°59'59" RT

332+95.6 SECTION LINE

28

S85°13'51"W  
643.8'

N00°04'44"W  
316.6'

N88°21'58"W  
1229.6'

S45°16'21"W  
42.4'

S00°16'13"W  
1958.8'

S45°16'12"W  
1380.6'

S89°31'28"W  
259.5'

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 28, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

5255.2 FEET = 318.50 RODS = 0.99 MILES = 3.62 ACRES

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 28, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**BASIN SURVEYS** P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013


Disk: JG - 28797

Survey Date: 6-1-2013

Sheet 7 of 8 Sheets

EXHIBIT L

SECTION 33, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M.,  
EDDY COUNTY, NEW MEXICO.



OWNER: USA  
LESSEE: ROSS OR JILL CAVINESS

332+95.6 SECTION LINE  
335+98.4 END OF SURVEY AT  
NORTHEAST CORNER  
OF PAD  
N32°47'51.54" W103°52'34.07"

33


T-17-S  
T-18-S

LEGAL DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE, LOCATED IN SECTION 33, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

302.8 FEET = 18.35 RODS = 0.06 MILES = 0.21 ACRES

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY AND MEETS OR EXCEEDS ALL REQUIREMENTS FOR LAND SURVEYS AS SPECIFIED BY THIS STATE.



GARY L. JONES N.M.P.S. No. 7977  
TEXAS P.L.S. No. 5074



**BURNETT OIL COMPANY, INC.**

REF: SWD PIPELINE FOR SWD WELL

A PIPELINE CROSSING USA LAND IN  
SECTION 33, TOWNSHIP 17 SOUTH, RANGE 31 EAST,  
N.M.P.M., EDDY COUNTY, NEW MEXICO.


**BASIN SURVEYS** P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 28797 Drawn By: J. GOAD

Date: 7-1-2013 Disk: JG - 28797

Survey Date: 6-1-2013 Sheet 8 of 8 Sheets

# EXHIBIT M



**SWD PIPELINE FOR SWD WELL**  
*Sections 12,13,24&25, Township 17 South, Range 31 East,  
N.M.P.M., Eddy County, New Mexico.*

**basin**  
**surveys**  
focused on excellence  
in the oilfield

P.O. Box 1786  
1120 N. West County Rd.  
Hobbs, New Mexico 88241  
(575) 393-7316 - Office  
(575) 392-2206 - Fax  
basinsurveys.com

W.O. Number: JG - 28797


Survey Date: 6-1-2013

Scale: 1" = 2000'

Date: 7-1-2013

**BURNETT OIL  
COMPANY, INC.**

EXHIBIT N



**SWD PIPELINE FOR SWD WELL**  
Sections 26,27,28&33, Township 17 South, Range 31 East,  
N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786  
1120 N. West County Rd.  
Hobbs, New Mexico 88241  
(575) 393-7316 - Office  
(575) 392-2206 - Fax  
basinsurveys.com

W.O. Number: JG - 28797


Survey Date: 6-1-2013

Scale: 1" = 2000'

Date: 7-1-2013


**BURNETT OIL  
COMPANY, INC.**

# EXHIBIT O-1




	Carrier Pipe	Casing Pipe	CROSSING OF HIGHWAY 82 (LOVINGTON HIGHWAY)
Contents			<b>BURNETT OIL COMPANY, INC.</b>
O.D.			REF: SWD PIPELINE FOR SWD WELL
I.D.			A ROAD CROSSING IN SECTION 13, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO.
Material			
W.T.			
Grade			

# EXHIBIT O-2




	Carrier Pipe	Casing Pipe	CROSSING OF RIPPLE ROAD
Contents			<b>BURNETT OIL COMPANY, INC.</b>
O.D.			REF: SWD PIPELINE FOR SWD WELL
I.D.			A ROAD CROSSING IN SECTION 13, TOWNSHIP 17 SOUTH, RANGE 31 EAST, N.M.P.M. EDDY COUNTY, NEW MEXICO.
Material			
W.T.			
Grade			

# EXHIBIT O-3



	Carrier Pipe	Casing Pipe	CROSSING OF HIGHWAY 529
Contents			<b>BURNETT OIL COMPANY, INC.</b>
O.D.			REF: SWD PIPELINE FOR SWD WELL
I.D.			
Material			A ROAD CROSSING IN
W.T.			SECTION 28, TOWNSHIP 17 SOUTH, RANGE 31 EAST,
Grade			N.M.P.M. EDDY COUNTY, NEW MEXICO.

EXHIBIT P



1250 0 1250 2500 3750 ft

1 inch = 1250 feet



Well Status

-  INA-GAS
-  INA-OIL
-  GAS
-  SWD

**Burnett 33 Fed 1**

**T17S, R31E, Sect 33, Unit B**  
**SHL: 380' FNL, 2510' FEL**  
**Lat/Long: 32.797081, -103.873627**

<b>Burnett Oil Co., Inc.</b> 6666	
Burnett 33 Federal 1 SWD Maljamar Area	
Author: GR	Date: 5/23/2013



**BURNETT OIL CO., INC.**

**DRILLING PLAN  
Burnett 33 Federal 1  
SWD WELL**

**1. Geological Name of Surface Formation with Estimated Depth:**

<u>Geological Name</u>	<u>Estimate Top</u>	<u>Anticipated Fresh Water, Oil or Gas</u>
a. Quaternary	Surface	Fresh Water, Sand
b. Rustler	616'	
c. Salt	795'	
d. Base Salt	1727'	
e. Yates	1915'	
f. Seven Rivers	2246'	
g. Queen	2913'	
h. Grayburg	3261'	Oil/Gas
i. San Andres	3741'	Oil/Gas
j. Glorieta	5129'	
k. ABO	7770'	
l. Wolfcamp	8338'	
m. Wolfcamp Reef	8941'	
n. Cisco	9768'	
o. Pennsylvanian	9989'	
p. Total Depth	Refer to Form 3160-3	

No other formations are expected to yield oil, gas or fresh water in measurable volumes. No interval expected of producing fresh water at any point in the well. We will set 13 3/8" casing @ approx. +/- 750' in the Rustler, above the salt and circulate cement to surface.

Any salt and/or hydrocarbons bearing intervals will be protected by setting 9 5/8" casing to 4500' and circulating cement back to surface. All other zones above TD will be cased with 7" casing and cement circulated to surface.

**2. Casing Program: (ALL CASING WILL BE NEW API APPROVED MATERIAL.)**

**(MW = 10 PPG IN DESIGN FACTOR CALCULATIONS.)**

## DRILLING PLAN SWD WELL

a. Design Safety Factor Minimums:

<u>Type</u>	<u>Hole Size</u>	<u>Interval</u>	<u>OD Csg</u>	<u>Weight</u>	<u>Collar</u>	<u>Grade</u>	<u>Collapse Design Factor</u>	<u>Burst Design Factor</u>	<u>Tension Design Factor</u>	<u>Joint String</u>
Conductor	24"	0'-40'	20"	Contractor Discretion			---	---	---	
Surface	17 1/2"	0' - 750'	13 3/8"	48#	ST & C	H40	1.125	1.00	2.00	1.80
Intermediate	12 1/4"	0' - 4500'	9 5/8"	3400' of 36.00#	ST & C	J55	1.125	1.00	2.00	1.80
				1100' of 40.00#						
Production	8-3/4"	0' - 9700'	7"	26.00#	LT & C	N80	*1.125	1.00	2.00	1.80

b. Surface Casing Info

The proposed casing setting depth is 750' based on cross sections which show the estimated top of the rustler and top of salt. Drilling times will be plotted to find the hard section just above the salt. If salt is penetrated, it will be obvious by the sudden increase in water salinity and surface casing will then be set above the top of salt. Our highly experienced drilling personnel has drilled many wells in this area and is able to easily identify the hard streak on the top of the salt.

### 3. Cementing Program (Note Yields and DV Tool Depth if Multiple Stage.)

**BLM to be notified prior to all cementing and tag operations in order to observe the operation if desired.**

a. **13 3/8" Surface (0-750')** Cement to surface

- Pump 20 bbl Fresh Water with Rhodamine red dye (0.1lbm/bbl). Lead with 460 sx Extendacem CZ System cement with Poly-E-Flake (0.125 lbm/sx) , 13.5 ppg, 1.75 CF/sx Yield.
- Tail with 240 sxs HalCem-C + 2% CaCl.-Flake, 14.8 ppg, 1.35 CF/sx yield. TOC Surface. Excess cement 100%.

**If cement does not circulate to surface, BLM will be notified of same, plus the plans to bring the cement to surface so BLM may witness tagging and cementing. If surface pressures when circulating indicate cement is low in the annulus, temperature survey results will be reviewed with BLM representative to determine the remediation needed.**

b. **9 5/8" Intermediate Casing (0-4500')**

- Pump 20 bbl WG-19 Gel Spacer (2.5 lbm/bbl) w/Rhodamine Red Dye (0.1 lbm/bbl). Lead with 1,230 sxs EconoCem HLC system cement w/5% Salt, Kol-Seal (5 lbm/sx) and Poly-E-Flake (0.125 lbm/sx) , 12.9 ppg, 1.88 CF/sx Yield.
- Tail with 300 sxs HalCem System cement, 14.8 ppg, 1.32 CF/sx yield. TOC Surface. Excess cement 50%.

## DRILLING PLAN SWD WELL

### c. 7" Production Casing (0-9700')

- Pump 40 bbl Fresh Water then pump 500 gallons (11.9 bbls) Super Flush 102, followed by pumping 20 bbls WC-19 Gel Spacer (2.5 lbm/bbl) with Rhodamine Red Dye (0.1 lbm/bbl). Lead with 480 sx Ecnocem H System Cement w/ .5% Halad -322, Kol-Seal (3lbm/sx), Poly-E-Flake (0.125 lbm/sx) and D-AIR 5000 (.25 lbm/sx) , 11.9 ppg, 2.47 CF/sx Yield.
- Tail with 630 sxs VersaCem H + 0.4% LAP-1, 0.3% CFR-3, Kol-Seal (3 lbm/sx), Poly-E-Flake (0.125 lbm/sx) and D-AIR 5000 (0.25 lbm/sx). 14.2 ppg, Yield 1.28 CF/sx. , TOC Surface. 35% excess cement.

The above cement volumes may be revised pending the caliper measurement from the open hole logs. **Casing/cementing design is to bring cement to the surface.**

### 4. Pressure Control Equipment:

*See COA*  
The blowout prevention equipment (BOPE) will be as described below. The surface casing will have a 13 3/8", 2,000 PSI Hydril (annular) BOP. A 13 3/8" drilling (rotating) head will be applied up on top of the Hydril.

The intermediate and production casings will include a rotating head plus both annular and double ram BOPs. A 10 3/4" rotating head will be used on both strings. Both intermediate and production strings will include 10 3/4", 5000 PSI Hydril and Double Ram Type BOPs.

*See COA*  
The BOPE will comply with on shore order #2. The annular will be tested at 50% and the double ram BOP will be tested at 100% of rated working pressure (RWP), and maintained at least 10 minutes. An independent testing company will be used for the testing. Other accessory BOPE will include a Kelly cock, floor safety valve, choke lines and choke manifold having 5000 PSI WP rating (Exhibits Q,R, & S).

Below are notes regarding the BOPE:

- a. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
- b. Wear ring will be properly installed in head.
- c. Blowout preventer and all associated fittings will be in operable condition to withstand a minimum 5,000 psi working pressure.
- d. All fittings will be flanged.
- e. A full bore safety valve tested to a minimum 5,000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
- f. All choke lines will be anchored to prevent movement.
- g. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
- h. Will maintain a Kelly cock attached to the Kelly.
- i. Hand wheels and wrenches will be properly installed and tested for safe operation.
- j. Hydraulic floor control for blowout preventer will be located as near in proximity to driller's controls as possible.

## DRILLING PLAN SWD WELL

- k. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.

### 5. Auxiliary Well Control and Monitoring Equipment:

- a. A Kelly cock will be in the drill string at all times.
- b. A full opening drill pipe stabbing valve with the appropriate connections on the rig floor at all times.
- c. Hydrogen Sulfide detection and breathing equipment will be installed and in operation at drilling depth of 1800' (which is more than 500' above top of Grayburg) until 7" casing is cemented.
- d. An H2S compliance package will be on all sites while drilling.

### 6. Proposed Mud Circulation System

<u>Depth</u>	<u>Mud Wt</u>	<u>Visc</u>	<u>Fluid Loss</u>	<u>Type System</u>	<u>Max Volume</u>
0' - 750'	8.6 - 9.5	34	N.C.	Fresh Water	
750' - 4500'	10.6	30	N.C.	Saturated Water	
4500' - 9700'	9.2	28	12 to log	Cut Brine	

The necessary mud products for weight addition and fluid loss control will be on location at all times.

Pason equipment will be used to monitor the mud system.

### 7. Logging, Coring and Testing program:

- a. Drill stem tests not anticipated.
- b. The open hole electrical logging program will be:
  1. Logging expected to be Dual Laterolog-Micro Laterolog, Dual Spaced Neutron, Spectral Density log, Spectral Gamma Ray and Caliper and CSNG will be run from TD to 9 5/8 casing shoe and GR from 9 5/8' to 13 3/8' shoe.
  2. No coring program is anticipated.
  3. Zones considered for injection will be perforated and acidized.

### 8. Potential Hazards:

*add  
CSA*  
No abnormal pressures or temperatures are expected. All personnel will be familiar with the safe operation of the equipment being used to drill this well. The maximum anticipated bottom hole pressure is 4317#. This is based upon the following formula of .445 x BH ft. estimate. The anticipated bottom hole temperature is 140°F. This is based upon logs of drilled wells surrounding this well

There is known H2S in this area. The attached H2S plan will be implemented when drilling below the Grayburg. The Mud/Gas Separator will be connected for the Intermediate and Production Casing and a remote choke will be installed as required in Onshore Order 6. Refer to the attached H2S plan for details as well as Exhibit R.


## **DRILLING PLAN SWD WELL**

### **9. Anticipated Start Date and Duration of Operation**

Road and location construction will begin after BLM has approved the APD and has approved the start of the location work. Anticipated spud date will be as soon as the location building work has been completed and the drilling rig is available to move to the location. Move in and drilling is expected to take approximately 15 days. When production casing is run, an additional 60 days would be required to complete the well and install the necessary surface equipment to place the well on injection.


## BURNETT 33 FEDERAL 1 - EXHIBIT Q - SURFACE CASING

NOTE: ALL VALVES AND  
PIPE ON CHOKE MANIFOLD  
ARE TO BE 2"



EPS PROJECT NUMBER = 10-028  
DATE: JANUARY 29, 2010  
REVISION DATE: FEBRUARY 23, 2010  
REVISION DATE: MAY 9, 2011  
REVISION DATE (LG): AUGUST 28, 2013  
REVISION DATE (LG): SEPTEMBER 30, 2013

## EXHIBIT R - INTERMEDIATE & PRODUCTION




### BURNETT OIL COMPANY, INC. BLOWOUT PREVENTER & CHOKE MANIFOLD DIAGRAM 5000 PSI WORKING PRESSURE

EPS PROJECT NUMBER = 10-028  
 DATE: JANUARY 29, 2010  
 REVISION DATE: MAY 9, 2011  
 REVISION DATE (LG): AUGUST 28, 2013  
 REVISION DATE (LG): OCTOBER 3, 2013



**BURNETT OIL CO., INC.**  
**EXHIBIT S**



**OPERATIONS & MAINTENANCE**

Drilling Fluids from the wellbore will go through the flow line across the shale shaker. Solids will drop into roll off containers with baffles as drawn above. Baffles slow fluid velocity to allow solids to fall down through 6" air actuated valves into roll off containers. Clean water goes back out to the drilling fluid steel pits. Solids and any leftover liquid will be hauled to disposal.

**INSPECTION**

The closed loop equipment will be inspected daily by each tour and any necessary maintenance performed. Any leak in the system will be repaired and .or contained immediately. OCD will be notified within 48 hours. Remediation process started.

**CLOSURE PLAN**

During drilling operations, all liquids, drilling fluids and cutting will b e hauled off via CRO (Controlled Recovery Incorporated Permit R-9166)





## BURNETT OIL Co., INC.

### HYDROGEN SULFIDE (H<sub>2</sub>S) PLAN & TRAINING

This plan was developed in accordance with 43 CFR 3162.3-1, section III.C, Onshore Oil and Gas Operations Order No. 6.

Based on our area testing H<sub>2</sub>S at 100 PPM has a radius of 139' and does not get off our well sites. There are no schools, residences, churches, parks, public buildings, recreation area or public within 2+ miles of our area.

---

#### A. Training

##### 1. Training of Personnel

**All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in accordance with 43 CFR 3162.3-1, section III.C.3.a. Training will be given in the following areas prior to commencing drilling operations on each well:**

- a. The hazards and characteristics of Hydrogen Sulfide (H<sub>2</sub>S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures and the prevailing wind.
- d. The proper techniques for first aid and rescue procedures.
- e. **ATTACHED HYDROGEN SULFIDE (H<sub>2</sub>S) CONTINGENCY PLAN DRILLING EXHIBIT K.**
- f. **ATTACHED EMERGENCY CALL LIST FOR ANY ON SITE EMERGENCY DRILLING EXHIBIT L.**

##### 2. Training of Supervisory Personnel

**In addition to the training above, supervisory personnel will also be trained in the following areas:**

- a. The effects of H<sub>2</sub>S on metal components. If high tensile tubulars are to be used, personnel will be trained in special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well, blowout prevention and well control procedures.
- c. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan (if applicable.)

##### 3. Initial and Ongoing Training

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan (if applicable). This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

## **B. H2S Drilling Operations Plan**

### **1. Well Control Equipment**

- a. Flare line(s) and means of ignition
- b. Remote control choke
- c. Flare gun/flares
- d. Mud-gas separator

### **2. Protective equipment for essential personnel:**

- a. Mark II Surviveair (or equivalent) 30 minute units located in the dog house and at the primary briefing area (to be determined.)
- b. Means of communication when using protective breathing apparatus.

### **3. H2S detection and monitoring equipment:**

- a. Three (3) portable H2S monitors positioned on location for best coverage and response. These units have warning lights at 10 PPM and warning lights and audible sirens when H2S levels of 15 PPM is reached. A digital display inside the doghouse shows current H2S levels at all three (3) locations.
- b. An H2S Safety compliance set up is on location during all operations.
- c. We will monitor and start fans at 1- ppm or less, an increase over 10 ppm results in the shutdown and installation of the mud/gas separator.
- d. Portable H2S and SO2 monitor(s).

### **4. Visual warning systems:**

- a. Wind direction indicators will be positioned for maximum visibility.
- b. Caution/Danger signs will be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

### **5. Mud program:**

- a. The mud program has been designed to minimize the volume of H2S circulated to the surface. Proper mud weight, safe drilling practices and the use of H2S scavengers will minimize hazards when penetrating H2S bearing zones.

### **6. Metallurgy:**

- a. All drill strings, casings, tubing, wellheads, Hydril BOPS, drilling spools, kill lines, choke manifold, valves and lines will be suitable for H2S service.
- b. All elastomers used for packing and seals shall be H2S trim.

**7. Communication:**

- a. Cellular Telephone and/or 2-way radio will be provided at well site.
  - b. Landline telephone is located in our field office.
-



## BURNETT OIL Co., INC.

### EXHIBIT U - HYDROGEN SULFIDE (H2S) CONTIGENCY PLAN

#### A. Emergency Procedures

In the event of a release of gas containing H2S, the first responder(s) must

1. Isolate the area and prevent entry by other persons into the 100 PPM ROE. Assumed 100PPM ROE = 3000'.
2. Evacuate any public places encompassed by 100 PPM ROE.
3. ~~Be equipped with H2S monitors and air packs in order to control release.~~
4. Use the "buddy system" to ensure no injuries occur during the response.
5. Take precautions to avoid personal injury during this operation.
6. Have received training in the following:
  - a. H2S detection
  - b. Measures for protection against this gas
  - c. Equipment used for protection and emergency response.

#### B. Ignition of Gas Source

Should control of the well be considered lost and ignition considered, care will be taken to protect against exposure to Sulfur Dioxide (SO2). Intentional ignition will be coordinated with the NMOCD and local officials. Additionally, the New Mexico State Police may become involved. NM State Police shall be the incident command on scene of any major release. Care will be taken to protect downwind whenever there is an ignition of gas.

#### C. Characteristics of H2S and SO2

<u>Common Name</u>	<u>Chemical Formula</u>	<u>Specific Gravity</u>	<u>Threshold Limit</u>	<u>Hazardous Limit</u>	<u>Lethal Concentration</u>
Hydrogen Sulfide	H2S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO2	2.21 Air = 1	2 ppm	NA	1000 ppm

#### **D. Contacting Authorities**

Burnett Oil Co., Inc. personnel will liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD will be notified of the release as soon as possible but no later than four (4) hours after the incident. Agencies will ask for information such as type and volume of release, wind and direction, location of release, etc. Be sure all is written down and ready to give to contact list attached. Burnett's response must be in coordination with the State of New Mexico's Hazardous Materials Emergency Response Plan.

Directions to the site are as follows:

Burnett Office  
87 Square Lake Road (CR #220)  
Loco Hills, NM 88255

Loco Hills, New Mexico (2 miles East of Loco Hills on US Hwy 82 to C #220. Then North on CR #220 approximately one (1) mile to office.

---



## BURNETT OIL CO., INC.

### EXHIBIT V - EMERGENCY NOTIFICATION LIST

#### BURNETT CONTACTS

**Burnett's New Mexico Office** 575.677.2313  
87 Square Lake Road (CR #220) Loco Hills, New Mexico 88255  
Directions: Loco Hills, NM – 2 miles east of Loco Hills on US Hwy 82 to CR#220. Then  
North on CR #220 approximately one (1) mile to office.

**Belton Mathews – BOCI District Superintendent (NM)** Cell - 575.703.9601

---

**Burnett Oil Home Office** 817.332.5108  
Burnett Plaza – Suite 1500 | 801 Cherry Street – Unit #9| Fort Worth, Texas 76102

Mark Jacoby – BOCI Engineering Manager (TX) Cell – 817-312-2751

#### SHERIFF/POLICE CONTACTS

Eddy County Sheriff 911 or 575.677.2313  
New Mexico State Police 575.746.2701

#### FIRE DEPARTMENT

Loco Hills Fire Department (VOLUNTEER ONLY) 911 or 575.677.2349  
For Medical and Fire (Artesia) 575.746.2701

#### AIR AMBULANCE

Flight for Life Air Ambulance	(Lubbock)	806.743.9911
Aerocare Air Ambulance	(Lubbock)	806.747.8923
Med Flight Air Ambulance	(Albuq)	505.842.4433
S B Med Svc Air Ambulance	(Albuq)	505.842.4949

#### FEDERAL AND STATE

US Bureau of Land Management (Carlsbad)	575.361.2822	575.234.5972
New Mexico Oil Conservation Division (Artesia)		575.748.1283
New Mexico Emergency Response Commission (24 hour)		575.827.9126
Local Emergency Planning Operation Center (Artesia)		505.842.4949
National Emergency Response Center (Washington, DC)		800.424.8802

#### OTHER IMPORTANT NUMBERS

Boots & Coots IWC		800.256.9688
Cudd Pressure Control		432.570.5300
Halliburton Services		575.746.2757
BJ Service		575.746.2293

**THIS MUST BE POSTED AT THE RIG WHILE ON LOCATION**

# EXHIBIT W


## BURNETT OIL CO., INC.

INTERIM RECLAMATION PLAT

BURNETT 33 FEDERAL #

2050' FWL, 360' FNL

SEC 33, T17S, R31E




✚ ANCHOR 75' FROM WELLHEAD TO ANCHORS

● WELLHEAD

NOT TO SCALE

# EXHIBIT X



ENTRY

**BURNETT OIL COMPANY**  
**BURNETT 33 FEDERAL 1 SWD**

PREPARED BY:  
**ENGINEERED PIPELINE SYSTEMS, INC.**  
P.O. BOX 14989  
ODESSA, TEXAS 79768

PHONE: 432/367-1955  
DATE: NOVEMBER 9, 2010


FAX: 432/367-1957  
E.P.S. DRAWING NO. 10-118-CP

\*Not to Scale

# EXHIBIT Y-1

BURNETT OIL CO., INC.  
 EDDY COUNTY, NM  
 NOSLER FEDERAL BATTERY  
 SEC 12, T 17S, R 30E

- SITE LEGEND**
-  500 BBL STEEL OIL SALES TANK #
  -  500 BBL STEEL OIL SALES TANK #
  -  500 BBL STEEL OIL SALES TANK #
  -  500 BBL FIBERGLASS WATER TANK
  -  500 BBL FIBERGLASS WATER TANK
  -  750 BBL FIBERGLASS GUN BARREL
  -  FENCED FIREWALL



**VALVE SEALED YES/NO**

VALVE LEGEND	TANK BEING HAULED	TANK BEING PRODUCED	EXCEPTIONS:
 LOAD LINE VALVE	YES	YES	
 FILL LINE VALVE	YES	NO	
 EQUALIZER LINE	YES	NO	
 CIRC LINE VALVE	YES	YES	SEAL OFF WHILE CIRCULATING PRODUCING TANK; SEAL ON AFTER CIRCULATING COMPLETE
 BS&W LOAD LINE	YES	YES	SEAL OFF WHILE CLEANING TANKS; SEAL ON AFTER TANKS ARE CLEAN
 WATER LINE VALVE	NO	NO	

**NOTE:**  
 PRODUCED WATER IS TRUCK HAULED TO PUBLIC DISPOSAL  
 WATER PUMPS ARE SET, BUT NOT IN USE

**NOSLER FEDERAL BATTERY (NOSLER #1 ACTIVE WELL)**

3 – 500 BBL Oil Tanks – No tank numbers yet or strappings – waiting on Holly

1 – 210 BBL Skim Tank

2 – 500 BBL Water Tanks

1 - 750 BBL Fiberglass Gun Barrel

1 – FWKO

1 – DCP Gas Sales Meter (Digital) 727033.00

1 – Gas Production Check Meter (Digital) 74633010

1 – Gas Test Meter (Digital) T122887100

1 - Production Water Meter – Digital

1 – Test Water Meter - Digital

1 – Production Heater Treater 8 x 20

1 – Test Heater Treater 4 x 20



Add Heater Calc

# EXHIBIT Y-2

BURNETT OIL CO., INC.  
 EDDY COUNTY, NM  
 PARTITION FEDERAL BATTERY

SEC 24, T 17S, R 30E

INCOMING FLOWLINES - PARTITION 1, NOSLER 2  
 NOSLER #3, FUTURE WELLS



**NOTE:**  
 PRODUCED WATER IS TRUCK HAULED TO PUBLIC DISPOSAL  
 WATER PUMPS ARE SET, BUT NOT IN USE

**GAS METERS:**  
 Partition Battery Test Meter 1 - 746-49003  
 Partition Battery Test Meter 2 - T091108660  
 Partition Battery Check Meter 3 - 746-33011  
 Partition Battery DCP Sales Meter - 727032-00

ENTRANCE/EXIT MAIN LEASE

ENTRANCE/EXIT MAIN LEASE ROAD

### SITE LEGEND

- |  |                                      |  |                               |  |                 |
|--|--------------------------------------|--|-------------------------------|--|-----------------|
|  | 500 BBL STEEL OIL SALES TANK # 67677 |  | 500 BBL FIBERGLASS WATER TANK |  | FWKO            |
|  | 500 BBL STEEL OIL SALES TANK # 67678 |  | 500 BBL FIBERGLASS WATER TANK |  | HEATER TREATER  |
|  | 500 BBL STEEL OIL SALES TANK # 67679 |  | 750 BBL FIBERGLASS GUN BARREL |  | WATER LINE      |
|  | 210 BBL STEEL SKIM TANK              |  |                               |  | OIL LINE        |
|  |                                      |  |                               |  | GAS LINE        |
|  |                                      |  |                               |  | FENCED FIREWALL |

### VALVE LEGEND

- |  |                      |  |                      |
|--|----------------------|--|----------------------|
|  | LOAD LINE VALVE      |  | CIRC LINE VALVE      |
|  | FILL LINE VALVE      |  | BS&W LOAD LINE VALVE |
|  | EQUALIZER LINE VALVE |  | WATER LINE VALVE     |

BURNETT OIL CO., INC.  
 EDDY COUNTY, NM  
 PARTITION FEDERAL BATTERY  
 SEC 24, T 17S, R 30E

**ATTACHMENT TO SITE FACILITY DIAGRAM**

General sealing of valves, sales by tank guage

**Production Phase:**

Load Line Valves sealed closed. Fill valve to tank that is in production will be open.  
 Equalizer valve to tank that is in production will be open. Circulation valves will be opened as necessary, then resealed.  
 BS&W Load Line valve will be sealed at all times, unless cleaning tanks, then resealed once tank maintenance is complete.

**Sales Phase:**

The tank from which sales are being made will be isolated by sealing closed the fill line valve, circulating valve, and the equalizer valve during sales and opening the sales valve. Upon completion of the sale, the sales valve will be resealed.  
 Sales by truck will be by tank gauge.

	<u>VALVE</u>	<u>PRODUCTION PHASE</u>	<u>SALES PHASE</u>	<u>CIRCULATING</u>	<u>NOTE</u>
	LOAD LINE VALVE	CLOSED	OPEN	CLOSED	
	PRODUCTION FILL LINE VALVE	OPEN OR CLOSED	CLOSED	CLOSED OR OPEN	
3	EQUALIZER LINE VALVE	OPEN	CLOSED	CLOSED OR OPEN	
	CIRCULATING LINE VALVE	OPEN OR CLOSED	CLOSED	OPEN	RE-SEALED ONCE CIRCULATING IS COMPLETE
5	BS&W LOAD LINE VALVE	CLOSED	CLOSED	CLOSED	OPEN FOR TANK MAINTENANCE, RESEALED ONCE MAINTENANCE IS COMPLETE
6	WATER LINE VALVE	OPEN	NA	NA	WATER TANKS ARE ISOLATED FROM OIL PRODUCTION TANKS WATER IS TRUCK HAULED FROM FORWARD LOAD LINES



## BURNETT OIL Co., INC.

### SURFACE USE PLAN

#### 1. Existing Roads:

- a. All roads into the location are shown on the Vicinity Map (**Exhibit C**).
- b. Directions to location: From Highway 82 and County Road 222 (Shugart Road), Go South 1.2 miles. Turning East, Go 0.4 mile to Proposed Road to location. (**Exhibit A**)

---

- c. In preparation for the new well site, water and a road grader is used to smooth nearby roads and patch holes. This is standard procedure used for the maintenance of existing roads. Existing roads will be improved and maintained according to the standards set forth in section 2 below.

#### 2. New or Reconstructed Access Roads:

- a. The well site layout, Form C-102 and **Exhibit A** show the proposed road which will be utilized. **Exhibit C** shows the existing roads surrounding the location.
- b. The new road will be 1138.9 ft. long and will enter the well site from the South side..
- c. All new roads will be constructed and all existing roads maintained according to the standards below:
  1. Approximately six (6) inches of top soil will be stripped from the proposed access road in preparation for construction. The removed top soil will be spread along the edge of the road and the ditch and will be seeded with the BLM approved seed mix.
  2. All construction material will be native caliche. The driving surface will be made of 6" rolled and compacted caliche. It may be available at the proposed location. If unavailable on location or road, caliche will be hauled from nearest BLM approved caliche pit.
  3. All access roads will not exceed fourteen (14) feet in width and will disturb as little surface as possible. The maximum width of disturbance during construction shall not exceed twenty (20) feet. Where possible, no improvements will be made on un-surfaced access roads other than to remove vegetation, road irregularities, safety issues or to fill low areas to prevent standing water.
  4. Crowning shall be done on the access road driving surface and shall have an approximate grade of 2% from the tip of the crown to the edge of the driving surface.
  5. Ditching will be done on both sides of the road the entire length of the road to control drainage. The ditch will have a minimum depth of one (1) foot below and a down sloping berm of six (6) inches above the ground level. All ditching will be completed as per BLM requirements.
  6. Vehicle turnouts will be constructed on the road with an interval spacing distance less than 1,000 feet. Turnouts will be constructed on all blind curves and shall conform to with BLM standards.
  7. The access road will be constructed and maintained in a way that will prevent soil erosion and accommodate all weather traffic in accordance with BLM guidelines.

## SURFACE USE PLAN

8. Fence Cuts: No; Cattle guards : No; Culverts: No; Cuts and Fills: Not significant.

### 3. Location of existing wells:

Please refer to **Exhibit P** for the location of all wells within a one (1) mile radius of the proposed well site.

### 4. Location of existing and/or proposed production facilities:

- a. Facilities will be located on the location. See **Exhibit X** for layout of the tanks on the well location.
- b. Flowline from the new well pad site is on Federal land that is outside the current Burnett Lease and is not under lease. The required flowline will be laid above ground and along existing lease road and right of way from the Nosler Battery (**Exhibit Y-1**) to the Partition Battery (**Exhibit Y-2**), leases-NMLC-029415A-and-NMLC-029415B, to the Burnett 33 Federal 1 SWD (~~Refer to Exhibits L & X~~). The flowline(s) will be 8" poly pipe, 33,598.4 ft. in length (**Refer to Exhibits E thru L**) and will transport produced water to the water tanks on the well pad (**Refer Exhibit X**). All flowlines will be low pressure 8" SDR-11 HDPE poly pipe with a typical working pressure of 75 psi. The SDR-11 HDPE poly pipe has a maximum pressure rating of 200 psi.

### c. Operational Control Philosophy

Incoming water will be transferred through an 8" SDR-11 HDPE pipeline to two (2) each 750 bbl fiberglass water tanks. Each water tank level will be monitored by a pressure transducer, T1 and T2, shown on **Exhibit X** which will allow for high level and low level shut down and alarm.

The water disposal pump will be 100 hp single stage centrifugal with a design rating of 10,000 bbl/day at 250 psi. Pump discharge pressure will be monitored by a pressure transducer labeled P1 as on **Exhibit X**. This pressure transducer will allow for shut down of the system based on a high or low pump discharge pressure. The shut off head of this pump is 275 psi.

The casing will be fitted with a pressure transducer labeled C1 on **Exhibit X**. This transducer will have the ability to shut in and alarm the system if the casing pressure exceeds 50 psi.

### 5. Location and Type of Water Supply:

All water to be used in drilling this well will be brine or fresh water transported by truck over existing and above proposed lease road from Loco Hills, New Mexico or produced water furnished from our existing waterflood facilities in the area. We may install a pump and lay a **temporary 2"** poly line on the lease from the battery to the rig for this drilling water.

### 6. Construction Materials:

All construction material for the roadway and drilling pad will be native caliche from the nearest BLM approved pit or from existing available deposits found on the location. All will be in accordance with the drilling stipulations for this well. If caliche is flipped on location, the following process will be followed:

- a. A caliche permit will be obtained from BLM by the dirtworks vendor prior to pushing up any caliche.
- b. The top 6" of top soil will be pushed off and stockpiled on the East side the location. Once the well is drilled the stock piled top soil will be used for interim reclamation and spread along the areas where the caliche is picked up and the location size is reduced. Neither caliche nor top soil

## SURFACE USE PLAN

will be piled outside the well pad. Top soil will be stockpiled along the edge of the pad as depicted in the attached well diagram (**Exhibit W**).

- c. An area approximately 120'x120' is used within the proposed site to remove caliche.
- d. Subsoil is removed and piled alongside the 120' x120' area within the pad and then pushed back once the caliche has been removed.
- e. When caliche is found, material will be stock piled within the pad site to build the location and road.

### 7. Methods of Handling Waste Disposal:

- a. Drill cuttings will be disposed of in a closed loop system using steel haul off tanks. All drilling Fluids will be hauled off location to a contracted off lease disposal location.
- b. Trash, waste paper, garbage and junk will be placed in a portable, screened trash container on location. All trash and debris will be transported to an authorized off-lease disposal station within thirty (30) days following the completion activities.
- c. A properly maintained Porto-john will be provided for the crews during drilling and completion operations. All will be removed after all completion operations have ended.
- d. Oil produced during testing will be put into steel storage tank for later sales.
- e. Water produced during testing operations will be put in the steel frac tanks pit until well is turned to the lease tank battery. All produced water will be disposed of through one of our approved disposal methods.

### 8. Ancillary Facilities:

There are no planned ancillary facilities for this well.

### 9. Well Site Layout:

- a. **Exhibit T** shows the relative location and dimensions of the drilling pad and related components. The pad size will be 300 ft.x 250 ft. Only minor differences, if any, in length and/or width of the drilling pad are anticipated, depending on which drilling contractor is selected to drill the well. Only minor leveling of the drilling site is anticipated.
- b. The V-Door will be East. Entry will be on the South side of the location to the Main Lease Road. Topsoil stockpile to the North side of the pad.
- c. On site was approved on 19 June 2013.
- d. All power for the well site is provided and handled by CBE.
- e. Refer to **Exhibit X** for location and description of water tanks to be located on well pad after drilling has been completed.

### 10. Plans for surface Reclamation:

- a. After drilling and successful completion operations are finished, all equipment and other materials not required for normal production operation will be removed. (**Refer to Exhibit W**)
- b. **Burnett Oil respectfully requests two (2) years to downsize the drilling location in order to have room for equipment to fracture stimulate three (3) to four (4) intervals. Each one**

## SURFACE USE PLAN

requires a large volume fracture treatment with several pumps, a large sand mover, several frac tans, a treatment can and various other vehicles and equipment. Burnett will, if all fracs are completed before the two (2) years, contact BLM to downsize the location.

Refer to attached **Exhibit W** which shows resulting location after downsizing and showing the sides of location where the caliche would be left for use of kill trucks, hot oil trucks, foam units or whatever is needed to service unit, which is what has to happen if the location is reclaimed on all four (4) sides to the safety anchors.

- c. The pad size will be reduced to the amount required for normal operation of the producing well. This reduced portion will be restored to the BLM stipulations. **(See Exhibit W)**
- d. If a well is abandoned, the surface location and unneeded road will be restored according to BLM stipulations within ninety (90) days of final abandon and sit re-seeded with BLM (#2) seed mix.

---

### 11. Surface ownership:

All lands are owned by the U.S. Government and administered by the Bureau of Land Management. The surface is multiple use with the primary use of the region for the production of oil and gas and the grazing of livestock.

### 12. Other information:

- a. The area surrounding the well site is a sandy dunal featured area. The area is relatively flat with small hills and sand dunes. The topsoil is fine, deep sand underlain by caliche. Vegetation cover is generally sparse and consists of mesquite, yucca, shinnery oak and sparse native grasses. Wildlife in the area includes deer, coyotes, rabbits, rodents, reptiles, dove and quail.
- b. No permanent or live water is found in the general proximity of this area.
- c. No dwellings are found within two (2) miles of this location.
- d. There is intermittent cattle grazing and hunting in the area; however, the principal land use is for oil and gas production.

### 13. Bond Coverage:

Current Bonds are BLM Bond # NMB000197. The Surety Bond is #B000863. New SWD Bond #B008175 was submitted to the BLM on 8/29/13. Awaiting NM Bond #.

Both the BLM Bond #NMB000197 and the Surety Bond # B000863 are effective May 21, 2004 and remain in place.

## SURFACE USE PLAN

The Burnett Oil Co., Inc. representatives responsible for ensuring compliance of the surface use plan are listed below:

### Regulatory

Leslie M. Garvis  
Regulatory Coordinator  
Burnett Oil Co. Inc.  
Burnett Plaza – Suite 1500  
801 Cherry Street – Unit #9  
Fort Worth, Texas 76102-5108  
817.332.5108 (office)  
713.819.4371 (cell)  
[lgarvis@burnettoil.com](mailto:lgarvis@burnettoil.com)

### Drilling & Production/Field Representative

Belton Matthews  
District Superintendent  
Burnett Oil Co. Inc.  
P.O. Box 188  
Loco Hills, New Mexico 88255  
575.677.2313 (office)  
575.703.9601 (cell)  
[bmathews@burnettoil.com](mailto:bmathews@burnettoil.com)

---

# EXHIBIT Z

DATE IN	SUSPENSE	ENGINEER	LOGGED IN	TYPE	APP NO.
---------	----------	----------	-----------	------	---------

ABOVE THIS LINE FOR DIVISION USE ONLY

**NEW MEXICO OIL CONSERVATION DIVISION**  
 - Engineering Bureau -  
 1220 South St. Francis Drive, Santa Fe, NM 87505



## ADMINISTRATIVE APPLICATION CHECKLIST

THIS CHECKLIST IS MANDATORY FOR ALL ADMINISTRATIVE APPLICATIONS FOR EXCEPTIONS TO DIVISION RULES AND REGULATIONS WHICH REQUIRE PROCESSING AT THE DIVISION LEVEL IN SANTA FE

**Application Acronyms:**

- [NSL-Non-Standard Location] [NSP-Non-Standard Proration Unit] [SD-Simultaneous Dedication]**  
**[DHC-Downhole Commingling] [CTB-Lease Commingling] [PLC-Pool/Lease Commingling]**  
**[PC-Pool Commingling] [OLS - Off-Lease Storage] [OLM-Off-Lease Measurement]**  
**[WFX-Waterflood Expansion] [PMX-Pressure Maintenance Expansion]**  
**[SWD-Salt Water Disposal] [IPI-Injection Pressure Increase]**  
**[EOR-Qualified Enhanced Oil Recovery Certification] [PPR-Positive Production Response]**

**[1] TYPE OF APPLICATION - Check Those Which Apply for [A]**

- [A] Location - Spacing Unit - Simultaneous Dedication  
 NSL  NSP  SD

Check One Only for [B] or [C]

- [B] Commingling - Storage - Measurement  
 DHC  CTB  PLC  PC  OLS  OLM

- [C] Injection - Disposal - Pressure Increase - Enhanced Oil Recovery  
 WFX  PMX  SWD  IPI  EOR  PPR

- [D] Other: Specify \_\_\_\_\_

**[2] NOTIFICATION REQUIRED TO: - Check Those Which Apply, or Does Not Apply**

- [A]  Working, Royalty or Overriding Royalty Interest Owners
- [B]  Offset Operators, Leaseholders or Surface Owner
- [C]  Application is One Which Requires Published Legal Notice
- [D]  Notification and/or Concurrent Approval by BLM or SLO  
U.S. Bureau of Land Management - Commissioner of Public Lands, State Land Office
- [E]  For all of the above, Proof of Notification or Publication is Attached, and/or,
- [F]  Waivers are Attached


**[3] SUBMIT ACCURATE AND COMPLETE INFORMATION REQUIRED TO PROCESS THE TYPE OF APPLICATION INDICATED ABOVE.**

**[4] CERTIFICATION:** I hereby certify that the information submitted with this application for administrative approval is accurate and complete to the best of my knowledge. I also understand that no action will be taken on this application until the required information and notifications are submitted to the Division.

Note: Statement must be completed by an individual with managerial and/or supervisory capacity.

Eddie W Seay Eddie W Seay Agent 4/21/2013  
Print or Type Name Signature Title Date  
seay\_04@leaco.net  
e-mail Address

**APPLICATION FOR AUTHORIZATION TO INJECT**

- I. PURPOSE: \_\_\_\_\_ Secondary Recovery \_\_\_\_\_ Pressure Maintenance  Disposal \_\_\_\_\_ Storage  
Application qualifies for administrative approval? \_\_\_\_\_ Yes \_\_\_\_\_ No
- II. OPERATOR: Burnett Oil Co., Inc.  
ADDRESS: 801 Cherry St., Suite 1500 Ft. Worth, TX 76102  
CONTACT PARTY: Mark Jacoby PHONE: 817-332-5108
- III. WELL DATA: Complete the data required on the reverse side of this form for each well proposed for injection.  
Additional sheets may be attached if necessary.
- IV. Is this an expansion of an existing project? \_\_\_\_\_ Yes  No  
If yes, give the Division order number authorizing the project: \_\_\_\_\_
- V. Attach a map that identifies all wells and leases within two miles of any proposed injection well with a one-half mile radius circle drawn around each proposed injection well. This circle identifies the well's area of review.
- VI. Attach a tabulation of data on all wells of public record within the area of review which penetrate the proposed injection zone. Such data shall include a description of each well's type, construction, date drilled, location, depth, record of completion, and a schematic of any plugged well illustrating all plugging detail.
- VII. Attach data on the proposed operation, including:
1. Proposed average and maximum daily rate and volume of fluids to be injected;
  2. Whether the system is open or closed;
  3. Proposed average and maximum injection pressure;
  4. Sources and an appropriate analysis of injection fluid and compatibility with the receiving formation if other than reinjected produced water; and
  5. If injection is for disposal purposes into a zone not productive of oil or gas at or within one mile of the proposed well, attach a chemical analysis of the disposal zone formation water (may be measured or inferred from existing literature, studies, nearby wells, etc.).
- \*VIII. Attach appropriate geologic data on the injection zone including appropriate lithologic detail, geologic name, thickness, and depth. Give the geologic name, and depth to bottom of all underground sources of drinking water (aquifers containing waters with total dissolved solids concentrations of 10,000 mg/l or less) overlying the proposed injection zone as well as any such sources known to be immediately underlying the injection interval.
- IX. Describe the proposed stimulation program, if any.
- \*X. Attach appropriate logging and test data on the well. (If well logs have been filed with the Division, they need not be resubmitted).
- \*XI. Attach a chemical analysis of fresh water from two or more fresh water wells (if available and producing) within one mile of any injection or disposal well showing location of wells and dates samples were taken.
- XII. Applicants for disposal wells must make an affirmative statement that they have examined available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zone and any underground sources of drinking water.
- XIII. Applicants must complete the "Proof of Notice" section on the reverse side of this form.
- XIV. Certification: I hereby certify that the information submitted with this application is true and correct to the best of my knowledge and belief.
- NAME: Mark Jacoby TITLE: VP Production  
SIGNATURE:  DATE: 6/21/2013  
E-MAIL ADDRESS: mjacoby@burnettoil.com
- \* If the information required under Sections VI, VIII, X, and XI above has been previously submitted, it need not be resubmitted. Please show the date and circumstances of the earlier submittal: will submit after drilling
- DISTRIBUTION: Original and one copy to Santa Fe with one copy to the appropriate District Office



## ATTACHMENT TO APPLICATION C-108

Burnett 33 Fed. #1 SWD (API to be assigned)  
Unit C, Sect. 33, Tws. 17 S., Rng. 31 E.  
Eddy Co., NM

### III. WELL DATA

- 
- A.
    - 1) See injection well data sheets and attached schematics.
    - 2) See injection well data sheets and attached schematics.
    - 3) 4 1/2" plastic coated tubing.
    - 4) Baker Lock Set with on/off tool.
  
  - B.
    - 1) Injection formation is the Wolfcamp Reef.
    - 2) Injection interval from 8900' to 9500'.
    - 3) This will new a new drill as a SWD.
    - 4) The next higher producing zone is the Abo Reef at approximately 8400'.  
The next lower producing zone is the Penn at approximately 10,000'.

### IV. NO.

### V. MAP ATTACHED.

### VI. LIST OF WELLS AND DATA ATTACHED.

VII. Burnett proposes and is filing APD to drill a new well for disposal, in the Wolfcamp Reef, with perforations from 8900' to 9500'. Plan to set 4 1/2" coated tubing and packer in 7" casing at approximately 8800' or 100' above upper most perms. Acidize as needed, run MIT as required and put on injection.

- 1) Plan to inject approximately 8000 bpd of produced water from Burnetts own operation.
- 2) Closed system.
- 3) Average injection pressure should be approximately 1600# or whatever limit OCD allows.
- 4) Produced water analysis.
- 5) Water from Burnetts offset production from San Andres, Yeso, and Grayburg.

**VIII.** The proposed disposal formation is interbedded shale and limestone. The primary geologic formations are the Wolfcamp Reef from 8900' to 9500'.

The fresh water formation in the area is the Ogallala, which if existed, would be in excess of 300 ft.

**IX. ACIDIZE AS NEEDED.**

**X. LOGS WILL BE SUBMITTED AFTER DRILLING.**

**XI. NO WATER FOUND OR NOTED BY STATE ENGINEERS SITE. MAP AND DATA ATTACHED.**

---

**XII.** I, Eddie W. Seay, have examined all available geologic and engineering data and find no evidence of open faults or any other hydrologic connection between the disposal zones and any underground source of drinking water pertaining to this well.

**XIII. ATTACHED.**



INJECTION WELL DATA SHEET

Tubing Size: 4 1/2 Lining Material: Plastic Coated  
Type of Packer: Baker loc set  
Packer Setting Depth: Approx. 8800  
Other Type of Tubing/Casing Seal (if applicable): NONE

Additional Data

1. Is this a new well drilled for injection?  Yes  No  
If no, for what purpose was the well originally drilled? SWD

2. Name of the Injection Formation: Wolfcamp Reef

3. Name of Field or Pool (if applicable): NA

4. Has the well ever been perforated in any other zone(s)? List all such perforated intervals and give plugging detail, i.e. sacks of cement or plug(s) used.  
NONE

5. Give the name and depths of any oil or gas zones underlying or overlying the proposed injection zone in this area:  
overlying formation - Abu Reef 8400  
underlying formation Penn 10,000

## DISPOSAL WELL

30-015-	BURNETT 33 FEDERAL SWD	1	BURNETT OIL COMPANY		I	N	Eddy	F	C	33	17	S	31	E	360	N	2050	W
---------	------------------------	---	---------------------	--	---	---	------	---	---	----	----	---	----	---	-----	---	------	---


Wells within 1/2 mile not penetrating proposed disposal interval.

API #	PROPERTY NAME	#	OPERATOR	TD	TYPE	STATUS	CO	LAND	U/L	SEC	TWN	RNG			EW		Dist		
30-015-05440	SKELLY UNIT	98	WISER OIL CO (THE)	3810	O	P	EDDY	F	J	28	17	S	31	E	1980	S	1980	E	2652
30-015-04829	SKELLY UNIT	99	TEXACO PRODUCING INC	3780	O	P	EDDY	F	K	28	17	S	31	E	1980	S	1980	W	2341
30-015-22533	SKELLY UNIT	155	TEXACO PRODUCING INC	2680	O	P	EDDY	F	K	28	17	S	31	E	2130	S	1980	W	2490

Wells within 1/2 mile penetrating proposed disposal interval.

API #	PROPERTY NAME	#	OPERATOR	TD	TYPE	STATUS	CO	LAND	U/L	SEC	TWN	RNG			EW		Dist		
30-015-28140	SKELLY UNIT	161	WISER OIL CO (THE)	12080	G	P	EDDY	F	K	28	17	S	31	E	1650	S	2310	W	2026
30-015-28676	DOW B 28 FEDERAL	1	JUDAH OIL LLC	12725	S	A	EDDY	F	P	28	17	S	31	E	1028	S	1227	E	2436
30-015-27675	DOW B 33 FEDERAL	2	V-F PETROLEUM INC	12100	G	A	EDDY	F	C	33	17	S	31	E	660	N	2310	W	396
30-015-31723	DENALI 33 FEDERAL	1	EOG RESOURCES INC	11925	G	P	EDDY	F	E	33	17	S	31	E	1980	N	660	W	2134
30-015-32164	DENALI 33 FEDERAL	2	V-F PETROLEUM INC	11950	O	A	EDDY	F	E	33	17	S	31	E	1580	N	760	W	1775

**PROPOSED NEW DRILL WELLBORE SCHEMATIC**




**COMPLETION SCHEMATIC**

APINUM: 30-015-			
OPERATOR: BURNETT OIL CO.			
LEASENAME: BURNETT 33 FEDERAL SWD			WELL NO. 1
SURF.LOC:	UL: C	SEC: 33	TWN: 17S
	360 FNL		2050 FWL
BH.LOC:	UL: C	SEC: 33	TWN: 17S
	360 FNL		2050 FWL
MD 9900	TVD 9900	KB	DF
	GL		
POOL	SWD;WOLFCAMP		Perf. 8900-9600.
POOL:			Perf.
POOL			Perf.

CASING RECORD					
	SIZE	DEPTH	CMT	HOLE SIZE	TOC
SURF.	13.375	500	TBD sxs	17 1/2	0' Circ
INTM1	9.625	4500	TBD sxs	12 1/4	0' Circ
PROD	7	9900	TBD sxs	7.875	4000'

# WELLBORE SCHEMATIC AND HISTORY




PREPARED BY:

UPDATED

06/20/13

# WELLBORE SCHEMATIC AND HISTORY




PREPARED BY:

UPDATED:

06/20/13

# WELLBORE SCHEMATIC AND HISTORY




PREPARED BY:

UPDATED:

06/20/13



## WELLBORE SCHEMATIC AND HISTORY




CASING RECORD					
	SIZE	DEPTH	CMT	HOLE SIZE	TOC
SURF	13.375	675	760 sxs	17-1/2	0' Circ
INTM1	8.625	4614	1700 sxs	12 1/4	0' Circ
PROD	5.5	11950	300 sxs	7.875	4445 CBL

SPUD: 03/12/2002  
 COMP: 06/26/2002

Water Sample Analysis

Pool	Location			Chlorides
	Section	Township	Range	
North Justis Montoya	2	25S	37E	45440
North Justis McKee	2	25S	37E	58220
North Justis Fusselman	2	25S	37E	68533
North Justis Ellenburger	2	25S	37E	34151
Fowler Blinbry	22	24S	37E	116085
Skaggs Grayburg	18	20S	38E	84845
Warren McKee	18	20S	38E	85910
Warren Abo	19	20S	39E	91600
DK Drinkard	30	20S	39E	108855
Littman San Andres	8	21S	38E	38895
East Hobbs grayburg	29	18S	39E	6481
Halfway Yates	16	20S	32E	14768
Arkansas Junction San Andres	12	18S	36E	7171
Pearl Queen	28	19S	35E	114310
Midway Abo	17	17S	37E	38494
Lovinton Abo	31	16S	37E	22933
Lovington San Andres	3	16S	37E	4899
Lovington Paddock	31	16S	37E	93720
Mesa Queen	17	16S	32E	172530
Kemnitz Wolfcamp	27	16S	34E	49345
Hume Queen	9	16S	34E	124980
Anderson Ranch Wolfcamp	2	16S	32E	11040
Anderson Ranch Devonian	11	16S	32E	25702
Anderson Ranch Unit	11	16S	32E	23788
Caudill Devonian	9	15S	38E	20874
Townsend Wolfcamp	6	16S	38E	38695
Dean Permio Perin	5	16S	37E	44730
Dean Devonian	35	15S	38E	19525
South Denton Wolfcamp	28	15S	37E	54315
South Denton Devonian	38	15S	37E	34080
Medicine Rock Devonian	15	15S	38E	39760
Little Lucky Lake Devonian	29	15S	30E	23288
Wanz Abo	28	21S	37E	132770
Crosby Devonian	18	25S	37E	58220
Scarborough Yates Seven Rivers	7	26S	37E	3443(Reef)
Teague Simpson	34	23S	37E	114665
Teague Ellenburger	34	23S	37E	120345
Rhodes Yates 7 Rivers	27	26S	37E	144485
House SA	11	20S	38E	93385
House Drinkard	12	20S	38E	49700
South Leonard Queen	24	28S	37E	115375
Elliot Abo	2	21S	38E	55380
Scharb Bone Springs	5	19S	36E	30801
EK Queen	13	18S	34E	41860
East EK Queen	22	18S	34E	178630
Mallamar Grayburg SA	22	17S	32E	46079
Mallamar Paddock	27	17S	32E	115375
Mallamar Devonian	22	17S	32E	25418



Groundwater Map

Records of wells from Eddy County, New Mexico

Location	Well Status	Altitude (feet)	Depth of Well(ft.)	Depth to Water(ft.)	Aquifer	Date of Measurement	Remarks
17.28.14.220	Stock/domestic			80	Dckm ?		
19.200	Stock			224.3	Ckbf/Rslr	Dec.2,1948	
22.230	Abandoned stock			45.5	Rslr/Dckm	Dec.1,1948	
24.224	Stock	3565	33.88	24.2		Oct.14,1977	
17.29. 8.231	Stock	3617	92.7	90.13		Oct.14,1977	
<i>No water listed</i>							
22.110	Stock	3550		79.7	Dckm ?	Nov.29,1948	
<i>No water</i> 29.400	Stock			210	Dckm ?	Dec.3,1948	
17.31.34.000	Stock			271+	Dckm	Dec.6,1948	
18.27. 8.240	Unused	3505		181.40		Jan.9,1964	
8.244	Industrial	3513	381	325 ?		Apr.,1951	Oil test
10.200	Unused	3470		46.92		Jan.9,1964	
10.214	Industrial	3493	130	50		Jul.,1958	Oil test
28.13	Domestic/stock	3377	120	100		May,1960	
28.140	Unused	3415		91.37		Jan.9,1964	
33.42	Stock	3447	90	49.3		Sep.,1969	
18.28. 8.330	Stock			81.6	Ckbf/Rslr	Dec.3,1948	
30.110	Stock/domestic	3560		137.1	Ckbf ?	Dec.2,1948	
18.29.24.142	Windmill	3436		156.44		Oct.18,1977	S.C.2600; 21°C
24.23311	Windmill	3436		160.20	Trsc	Apr.8,1971	
24.300	Stock	3430		158.3	Dckm	Apr.28,1950	
34.324	Stock	3440	250	230		Mar.,1960	Yield: 63gpm
18.30.21.4200	Open cased hole	3495		266.48	Trcl	Dec.9,1965	
22.2220	Open cased hole	3430		239.26	Trcl	Apr.8,1971	
26.4140	Stock	3430	223.0	201.67	Trcl	Dec.14,1977	S.C. 1100
31.323	Observation	3370	161.0	157.80		Nov.18,1977	
32.32422	Windmill	3380		161.28	Trcl	Apr.8,1971	
32.413	Abandoned windmill	3370	266	158.77		Oct.18,1977	
18.31. 1.44432	Windmill	3797		460.42	Trcl	Apr.7,1971	
12.223	Stock	3795	480+	453.39		Oct.18,1977	
12.23144	Stock	3775	600	435.34	Trcl	Apr.7,1971	

## **OFFSETS AND MINERAL NOTICES**

### **LAND OWNER & MINERAL OWNER FOR APR AND LEASE**

BLM - US Minerals and Surface Owner  
620 E. Green St.  
Carlsbad, NM 88220

---

### **OFFSETS OPERATORS AND MINERAL LEASEES**

State Land Office  
310 Old Santa Fe Trail  
Box 1148  
Santa Fe, NM 87504-1148

Oxy USA, Inc.  
Box 4294  
Houston, TX 77210

EOG Resources, Inc.  
Box 2267  
Midland, TX 79702

V.F. Petroleum  
Box 1889  
Midland, TX 79702


Chevron Corp.  
15 Smith Rd.  
Midland, TX 79705

Judah Oil, LLC  
Box 568  
Artesia, NM 88215

The Wiser Oil Co.  
Box 2568  
Hobbs, NM 88240



Federal Minerals



7012 3050 0000 7665 3261

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$ 7.37



Sent To  
**BLM**  
 Street, Apt. No., or PO Box No.  
**620 E. Green St.**  
 City, State, ZIP+4  
**Carlsbad, NM 88220**

PS Form 3800, August 2006 See Reverse for Instructions


452E 599L 0000 7665 3247

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**State Land Office**  
 Street, Apt. No., or PO Box No.  
**310 Old Santa Fe Trail**  
 City, State, ZIP+4  
**Box 1148**  
**Santa Fe, NM 87504-1148**

PS Form 3800, August 2006 See Reverse for Instructions

7012 3050 0000 7665 3230

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**EOG Resources, Inc.**  
 Street, Apt. No., or PO Box No.  
**Box 2267**  
 City, State, ZIP+4  
**Midland, TX 79702**

PS Form 3800, August 2006 See Reverse for Instructions


42E 599L 0000 7665 3247

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**Oxy USA, Inc.**  
 Street, Apt. No., or PO Box No.  
**Box 4294**  
 City, State, ZIP+4  
**Houston, TX 77210**

PS Form 3800, August 2006 See Reverse for Instructions


7012 3050 0000 7665 3223

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**V.F. Petroleum**  
 Street, Apt. No., or PO Box No.  
**Box 1889**  
 City, State, ZIP+4  
**Midland, TX 79702**

PS Form 3800, August 2006 See Reverse for Instructions

42E 599L 0000 7665 3192

U.S. Postal Service  
**CERTIFIED MAIL™ RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**The Wiser Oil Co.**  
 Street, Apt. No., or PO Box No.  
**Box 2568**  
 City, State, ZIP+4  
**Hobbs, NM 88240**

PS Form 3800, August 2006 See Reverse for Instructions


7012 3050 0000 7665 3216

U.S. Postal Service<sup>™</sup>  
**CERTIFIED MAIL<sup>™</sup> RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**Chevron Corp.**  
 Street, Apt. No.,  
 or PO Box No. **15 Smith Rd.**  
 City, State, ZIP+4<sup>®</sup>  
**Midland, TX 79705**

PS Form 3800, August 2006 See Reverse for Instructions

7012 3050 0000 7665 3209

U.S. Postal Service<sup>™</sup>  
**CERTIFIED MAIL<sup>™</sup> RECEIPT**  
(Domestic Mail Only; No Insurance Coverage Provided)

For delivery information visit our website at [www.usps.com](http://www.usps.com)

**OFFICIAL USE**

Postage	\$
Certified Fee	
Return Receipt Fee (Endorsement Required)	
Restricted Delivery Fee (Endorsement Required)	
Total Postage & Fees	\$



Sent To  
**Judah Oil, LLC**  
 Street, Apt. No.,  
 or PO Box No. **Box 568**  
 City, State, ZIP+4<sup>®</sup>  
**Artesia, NM 88215**

PS Form 3800, August 2006 See Reverse for Instructions

## LEGAL NOTICE

Pursuant to the rules and regulations of the Oil Conservation Division of the State of New Mexico, Burnett Oil Co. Inc., Burnett Plaza, Suite 1500, 801 Cherry St. Unit #9, Ft. Worth, Texas 76102, is filing a C-108, Application for Salt Water Disposal. The well being applied for is a new drill for SWD, the Burnett 33 Fed #1, located in Unit C, Section 33, Township 17 South, Range 31 East, Eddy Co., NM. The injection formation is the Wolfcamp Reef from 8900' to 9500' below surface. Expected maximum injection rate is 8000 bpd., and the expected maximum injection pressure is 1600 psi or what the OCD allows. Any questions about the application can be directed to Eddie W. Seay, (575)392-2236, or any objection or request for hearing must be directed to the Oil Conservation Division, (505)476-3440, 1220 South Saint Francis Drive, Santa Fe, NM 87504, within fifteen (15) days.

# Affidavit of Publication

NO. 22628

STATE OF NEW MEXICO

County of Eddy:

Danny Scott

being duly sworn, says that he is the Publisher

of the Artesia Daily Press, a daily newspaper of general circulation, published in English at Artesia, said county and state, and that the hereto attached

### Legal Notice

was published in a regular and entire issue of the said Artesia Daily Press, a daily newspaper duly qualified for that purpose within the meaning of Chapter 167 of the 1937 Session Laws of the state of New Mexico for

1 Consecutive weeks/days on the same

day as follows:

First Publication	<u>June 23, 2013</u>
Second Publication	
Third Publication	
Fourth Publication	
Fifth Publication	

Subscribed and sworn to before me this

24th day of June 2013



OFFICIAL SEAL  
Latisha Romine  
NOTARY PUBLIC-STATE OF NEW MEXICO

My commission expires: 5/12/2015

Latisha Romine  
Notary Public, Eddy County, New Mexico

# Copy of Publication:

## LEGAL NOTICE

Pursuant to the rules and regulations of the Oil Conservation Division of the state of New Mexico, Burnett Oil Co. Inc. Burnett Plaza Suite 1500 801 Cherry St Unit #9 Ft. Worth, Texas 76102, is filing a G-108 application for Salt Water Disposal. The well being applied for is a new drill for SWD the Burnett 33 Fed #1 located in Unit C Section 33 Township 17 South Range 31 East Eddy Co. NM. The injection formation is the Wolfcamp Reef from 8900 to 9500 below surface. Expected maximum injection rate is 8000 bpd and the expected maximum injection pressure is 1600 psi or what the OCD allows. Any questions about the application can be directed to Eddie Seay (575) 392-2236 or any objection or request for hearing must be directed to the Oil Conservation Division (505) 476-3400 1200 South Saint Francis Drive Santa Fe, NM 87504 within fifteen (15) days. Published in the Artesia Daily Press, Artesia, N.M. June 23, 2013. Legal No 22628.

**PECOS DISTRICT  
CONDITIONS OF APPROVAL**

<b>OPERATOR'S NAME:</b>	<b>Burnett Oil Co., Inc.</b>
<b>LEASE NO.:</b>	<b>NMLC-029420B</b>
<b>WELL NAME &amp; NO.:</b>	<b>Burnett 33 Federal SWD 1</b>
<b>SURFACE HOLE FOOTAGE:</b>	<b>0360' FNL &amp; 2050' FWL</b>
<b>LOCATION:</b>	<b>Section 33, T. 17 S., R 31 E., NMPM</b>
<b>COUNTY:</b>	<b>Eddy County, New Mexico</b>

**TABLE OF CONTENTS**

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
  - Dunes Sagebrush Lizard Trench Stipulation (for row pipeline)
- Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- Road Section Diagram**
- Drilling**
  - Cement Requirements
  - H2S Requirements
  - Logging Requirements
  - Waste Material and Fluids
- Production (Post Drilling)**
  - Well Structures & Facilities
  - Pipelines
- Interim Reclamation**
- Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## V. SPECIAL REQUIREMENT(S)

### **Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

**Ground-level Abandoned Well Marker to avoid raptor perching:** Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

### **Dunes Sagebrush Lizard Trench Stipulation (applies to row pipeline)**

- Pre-construction contact with a BLM wildlife biologist is required before any ground disturbing activities associated with the project occurs.
- Successful completion of the BLM Trench Stipulation Workshop is required for a non-agency person to be approved as a monitor.
- Any trench left open for (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, an agency approved monitor shall walk the entire length of the open trench and remove all trapped vertebrates. The bottom surface of the trench will be disturbed a minimum of 2 inches in order to arouse any buried vertebrates. All vertebrates will be released a minimum of 100 yards from the trench.
- For trenches left open for eight (8) hours or more the following requirements apply:
  - Earthen escape ramps and/or structures (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench. Metal structures will not be authorized. Options will be discussed in detail at the required Trench Stipulation Workshop.
  - One approved monitor shall be required to survey up to three miles of trench between the hours of 11 AM-2 PM. A daily report (consolidate if

there is more than one monitor) on the vertebrates found and removed from the trench shall be provided to the BLM (email/fax is acceptable) the following morning.

- Prior to backfilling of the trench all structures used as escape ramps will be removed and the bottom surface of the trench will be disturbed a minimum of 2 inches in order to arouse any buried vertebrates. All vertebrates will be released a minimum of 100 yards from the trench.
  
- This stipulation shall apply to the entire length of the project in the DSL habitat polygon regardless of land ownership or CCA/CCAA enrollment status.
  
- A project closeout will be required within three business days of the completion of the project.

## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

## **F. EXCLOSURE FENCING (CELLARS & PITS)**

### **Exclosure Fencing**

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

## **G. ON LEASE ACCESS ROADS**

### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### **Crowning**

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### **Ditching**

Ditching shall be required on both sides of the road.

### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

## Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

### Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

### Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

## Culvert Installations

Appropriately sized culverts shall be installed at deep waterway channel flow crossings through the road.

## Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings.

Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

**Fence Requirement**

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

**Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

**Construction Steps**

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

## VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

**Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated 500 feet prior to drilling into the Grayburg formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

### B. CASING

**Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).**

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

**Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

**Possibility of water flows in the Salado and Artesia Group.**

**Possibility of lost circulation in the Rustler, Artesia Group, San Andres, and Grayburg.**

**Abnormal pressures may be encountered within the Wolfcamp formation.**

1. The 13-3/8 inch surface casing shall be set at approximately 750 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

**Intermediate casing shall be kept fluid filled while running into hole to meet BLM minimum collapse requirements.**

2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:

Cement to surface. If cement does not circulate see B.1.a, c-d above.

**Formation below the 9-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole. Report results to BLM office.**

3. The minimum required fill of cement behind the 7 inch production casing is:

Cement to surface. If cement does not circulate, contact the appropriate BLM office.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### **C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

2. **In the case where the only BOP installed is an annular preventer, it shall be tested to a minimum of 2000 psi (which may require upgrading to 3M or 5M annular).**

3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M) psi.**

4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 9-5/8 intermediate casing shoe shall be **5000 (5M) psi. 5M system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.**

5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**.
  - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
  - d. The results of the test shall be reported to the appropriate BLM office.
  - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
  - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
  - g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the **Wolfcamp** formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

## **E. WELL COMPLETION**

**A NOI sundry with the completion procedure for this well shall be submitted and approved prior to commencing completion work. The procedure will be reviewed to verify that the completion proposal will allow the operator to:**

- 1. Properly evaluate the injection zone utilizing open hole logs, swab testing and/or any other method to confirm that hydrocarbons cannot be produced in paying quantities. This evaluation shall be reviewed by the BLM prior to injection commencing.**
- 2. Restrict the injection fluid to the approved formation.**

**If off-lease water will be disposed in this well, the operator shall provide proof of right-of-way approval.**

## **F. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JAM 020714**

## VIII. PRODUCTION (POST DRILLING)

### A. WELL STRUCTURES & FACILITIES

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Exclosure Netting (Open-top Tanks)**

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

#### **Chemical and Fuel Secondary Containment and Exclosure Screening**

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

#### **Open-Vent Exhaust Stack Exclosures**

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

#### **Containment Structures**

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

## **B. PIPELINES**

### **STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES**

**A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.**

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. The holder shall be liable for damage or injury to the United States to the extent

provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
  - (1) Land clearing.
  - (2) Earth-disturbing and earth-moving work.
  - (3) Blasting.
  - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize

suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

#### BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
  - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
  - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
  - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- |  |  |
|--|--|
| <input type="checkbox"/> seed mixture 1                | <input type="checkbox"/> seed mixture 3          |
| <input type="checkbox"/> seed mixture 2                | <input type="checkbox"/> seed mixture 4          |
| <input checked="" type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates “Standard Environmental Colors” – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder’s name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Dunes Sagebrush Lizard Trench Stipulation (see special stipulation section above)

## **IX. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **X. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory

revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

## Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed