		OCD	Artesia			
Form 3160-5 (August 2007) UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT SUNDRY NOTICES AND REPORTS ON WE					FORM APPROVED OMB NO. 1004-0135 Expires: July 31, 2010 5. Lease Serial No. NMNM83066	
Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.					6. If Indian, Allottee or Tribe Name	
SUBMIT IN TRIPLICATE - Other instructions on reverse side.					7. If Unit or CA/Agr	cement, Name and/or No.
1. Type of Well S Oil Well Gas Well Other					8. Well Name and No. CROW FLATS 26 IL FEDERAL 1H	
2. Name of Operator Contact: JACKIE LATHAN MEWBOURNE OIL COMPANY E-Mail: jlathan@mewbourne.com					9. API Well No. 30-015-41155-00-X1	
3a. Address P O BOX 5270 HOBBS, NM 88241	3b. Phone No. (include area code) Ph: 575-393-5905			10. Field and Pool, or Exploratory DOG CANYON		
4. Location of Well (Footage, Sec., T., R., M., or Survey Description) Sec 26 T16S R28E NESE 1890FSL 330FEL					11. County or Parish, and State EDDY COUNTY, NM	
· · · · · · · · · · · · · · · · · · ·	·		•			
· · · · · · · · · · · · · · · · · · ·	ROPRIATE BOX(ES) TO) INDICATE			EPORT, OR OTHE	ER DATA
TYPE OF SUBMISSION	TYPE OF ACTION					
 Notice of Intent Subsequent Report Final Abandonment Notice 	 Acidize Alter Casing Casing Repair Change Plans Convert to Injection 	Alter Casing Fracture Treat Casing Repair New Construction		 Production (Start/Resume) Water Shut-Off Reclamation Well Integrity Recomplete Other Temporarily Abandon Water Disposal 		
Attach the Bond under which the wo following completion of the involved testing has been completed. Final A determined that the site is ready for f Mewbourne Oil Company has 02/21/15. We would like to ex	d operations. If the operation re bandonment Notices shall be fil inal inspection.)	sults in a multipl ed only after all above captic	e completion or reco requirements, includ	mpletion in a ing reclamatic	new interval, a Form 31 in, have been completed NM OII	60-4 shall be filed once
If you have any questions, ple SubCace: Cel				2 cteri SEE CON	ATTACHE	AN 26 2015 DFOR FAPPEROVAL
Accepted to nec	4/15		Jen		OVED FOR <u>24</u>	_MONTH PERIOD
14. Thereby certify that the foregoing is	<u>15/15-JA</u>	<u>M- r</u>	en Cé	5/ENDI	0 A I)
Com	Electronic Submission # For MEWBOU mitted to AFMSS for proce	RNE OIL COM	PANY, sent to th NFER MASON on	e Carlsbad 01/05/2015	(15JAM0157SE)	· · · · ·
Name(Printed/Typed) JACKIE L				PRESENTATIVE		
Signature (Electronic	THIS SPACE FO		Date 12/03/2			
lin lit	Ephy J Palti		FOR FIEL			1/201
Conditions of approval, if any, are attached certify that the applicant holds legal or eq	one of approval, if any, are attached. Approval of this notice does not warrant or hat the applicant holds legal or equitable title to those rights in the subject lease would entitle the applicant to conduct operations thereon.			Office CARLSBAD FIELD OFFICE		
Title 18 U.S.C. Section 1001 and Title 43 States any false, fictitious or fraudulent	U.S.C. Section 1212, make it a			willfully to n	ake to any department c	or agency of the United.
** BLM REV	ISED ** BLM REVISE	Ö ** BLM RI	EVISED ** BLN	A REVISE	D ** BLM REVISE	ED **

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Mewbourne Oil Co
LEASE NO.:	NM83066
WELL NAME & NO.:	1H Crow Flats 26 IL Federal
SURFACE HOLE FOOTAGE:	1890'/ FSL & 330'/ FEL
BOTTOM HOLE FOOTAGE	1980'/ FSL & 330'/ FWL
LOCATION:	Section 26, T.16 S., R.28 E., NMPM
COUNTY:	Eddy County, New Mexico
API:	30-015-41155

The original COAs still stand with the following drilling modifications:

I. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Although Hydrogen Sulfide has not been reported in the area, it is always a potential hazard. If Hydrogen Sulfide is encountered, report measured amounts and formations to the BLM.
- Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. If the drilling rig is removed without approval an Incident of Non-Compliance will be written and will be a "Major" violation.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.

4. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The top and bottom of Salt are to be recorded on the Completion Report.

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Medium Cave/Karst

Possible lost circulation in the Grayburg and San Andres formations.

- 1. The 13-3/8 inch surface casing shall be set at approximately 250 feet (a minimum of 25 feet above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.

- b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Contingency 9-5/8" Casing:

2. The minimum required fill of cement behind the **9-5/8** inch intermediate contingency casing is:

Centralizers required through the curve and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7 inch production casing is:

Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

4. The minimum required fill of cement behind the 4-1/2 inch production liner is:

 \bigotimes Cement not required – packer system to be used.

5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.

Cement to surface. If cement does not circulate see B.1.a, c-d above. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst.

- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
 - a. For surface casing only: If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
- Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 7 inch intermediate casing shoe shall be 3000 (3M) psi.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips or where the float does not hold, the minimum wait time before cut-off is eight hours after bumping the plug or when the cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. BOP/BOPE testing can begin after the above conditions are satisfied.
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
 - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
 - d. The results of the test shall be reported to the appropriate BLM office.
 - e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.

f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 011515