

Marathon Oil Permian, LLC

Eddy County, NM (NAD27)

Squirrel Master Fee 23-28-5

WXY #3H

30-015-44873

OH

NM OIL CONSERVATION
ARTESIA DISTRICT

APR 10 2018

RECEIVED

Plan: Plan #1

Standard Planning Report

05 April, 2018



www.scientificdrilling.com

Planning Report

Database:	Midland District	Local Co-ordinate Reference:	Well WXY #3H
Company:	Marathon Oil Permian, LLC	TVD Reference:	KB = 26.5' @ 3056.50usft (Rig TBD)
Project:	Eddy County, NM (NAD27)	MD Reference:	KB = 26.5' @ 3056.50usft (Rig TBD)
Site:	Squirrel Master Fee 23-28-5	North Reference:	Grid
Well:	WXY #3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Project	Eddy County, NM (NAD27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	New Mexico East 3001		Using geodetic scale factor

Site		Squirrel Master Fee 23-28-5			
Site Position:		Northing:	486,529.83 usft	Latitude:	32° 20' 14.665 N
From:	Map	Easting:	565,703.16 usft	Longitude:	104° 7' 14.166 W
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.11

Well	WXY #3H					
Well Position	+N/-S	-0.01 usft	Northing:	486,529.82 usft	Latitude:	32° 20' 14.665 N
	+E/-W	30.00 usft	Easting:	565,733.16 usft	Longitude:	104° 7' 13.816 W
Position Uncertainty		0.00 usft	Wellhead Elevation:	0.00 usft	Ground Level:	3,030.00 usft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	4/5/2018	7.28	60.12	48,033

Design	Plan #1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (bearing)
	0.00	0.00	0.00	90.00

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
4,500.00	10.00	120.00	4,497.47	-21.76	37.69	2.00	2.00	0.00	120.00	
8,250.00	10.00	120.00	8,190.49	-347.35	601.63	0.00	0.00	0.00	0.00	
8,750.00	0.00	0.00	8,687.96	-369.11	639.32	2.00	-2.00	0.00	180.00	
8,912.04	0.00	0.00	8,850.00	-369.11	639.32	0.00	0.00	0.00	0.00	
9,801.04	88.90	110.00	9,422.85	-561.31	1,167.39	10.00	10.00	0.00	110.00	
9,848.04	88.90	110.00	9,423.75	-577.39	1,211.55	0.00	0.00	0.00	0.00	
10,848.35	88.90	89.99	9,443.16	-750.09	2,191.50	2.00	0.00	-2.00	-90.19	
14,586.84	88.90	89.99	9,515.00	-749.29	5,929.29	0.00	0.00	0.00	-117.84	BHL[SM\WXY#3H]
14,631.84	88.90	89.99	9,515.87	-749.28	5,974.28	0.00	0.00	0.00	0.00	

Planning Report

Database: Midland District
 Company: Marathon Oil Permian, LLC
 Project: Eddy County, NM (NAD27)
 Site: Squirrel Master Fee 23-28-5
 Well: WXY #3H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference: Well WXY #3H
 TVD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 MD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
461.00	0.00	0.00	461.00	0.00	0.00	0.00	0.00	0.00	0.00
Salado/Castile									
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,411.00	0.00	0.00	2,411.00	0.00	0.00	0.00	0.00	0.00	0.00
Lamar									
2,472.00	0.00	0.00	2,472.00	0.00	0.00	0.00	0.00	0.00	0.00
Bell Canyon									
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,267.00	0.00	0.00	3,267.00	0.00	0.00	0.00	0.00	0.00	0.00
Cherry Canyon									
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
KOP - Build 2.0° / 100									
4,100.00	2.00	120.00	4,099.98	-0.87	1.51	1.51	2.00	2.00	0.00
4,200.00	4.00	120.00	4,199.84	-3.49	6.04	6.04	2.00	2.00	0.00
4,300.00	6.00	120.00	4,299.45	-7.85	13.59	13.59	2.00	2.00	0.00
4,400.00	8.00	120.00	4,398.70	-13.94	24.14	24.14	2.00	2.00	0.00

Planning Report

Database: Midland District
 Company: Marathon Oil Permian, LLC
 Project: Eddy County, NM (NAD27)
 Site: Squirrel Master Fee 23-28-5
 Well: WXY #3H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference: Well WXY #3H
 TVD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 MD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N-S (usft)	+E-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Bulld Rate (°/100usft)	Turn Rate (°/100usft)
4,489.38	9.79	120.00	4,487.00	-20.85	36.11	36.11	2.00	2.00	0.00
Brushy Canyon									
4,500.00	10.00	120.00	4,497.47	-21.76	37.69	37.69	2.00	2.00	0.00
EOB - HOLD									
4,600.00	10.00	120.00	4,595.95	-30.44	52.73	52.73	0.00	0.00	0.00
4,700.00	10.00	120.00	4,694.43	-39.13	67.77	67.77	0.00	0.00	0.00
4,800.00	10.00	120.00	4,792.91	-47.81	82.81	82.81	0.00	0.00	0.00
4,900.00	10.00	120.00	4,891.39	-56.49	97.85	97.85	0.00	0.00	0.00
5,000.00	10.00	120.00	4,989.87	-65.17	112.88	112.88	0.00	0.00	0.00
5,100.00	10.00	120.00	5,088.35	-73.86	127.92	127.92	0.00	0.00	0.00
5,200.00	10.00	120.00	5,186.83	-82.54	142.96	142.96	0.00	0.00	0.00
5,300.00	10.00	120.00	5,285.31	-91.22	158.00	158.00	0.00	0.00	0.00
5,400.00	10.00	120.00	5,383.79	-99.90	173.04	173.04	0.00	0.00	0.00
5,500.00	10.00	120.00	5,482.27	-108.59	188.08	188.08	0.00	0.00	0.00
5,600.00	10.00	120.00	5,580.75	-117.27	203.11	203.11	0.00	0.00	0.00
5,700.00	10.00	120.00	5,679.23	-125.95	218.15	218.15	0.00	0.00	0.00
5,800.00	10.00	120.00	5,777.72	-134.63	233.19	233.19	0.00	0.00	0.00
5,900.00	10.00	120.00	5,876.20	-143.32	248.23	248.23	0.00	0.00	0.00
5,939.40	10.00	120.00	5,915.00	-146.74	254.15	254.15	0.00	0.00	0.00
Bone Spring									
6,000.00	10.00	120.00	5,974.68	-152.00	263.27	263.27	0.00	0.00	0.00
6,100.00	10.00	120.00	6,073.16	-160.68	278.31	278.31	0.00	0.00	0.00
6,200.00	10.00	120.00	6,171.64	-169.36	293.34	293.34	0.00	0.00	0.00
6,300.00	10.00	120.00	6,270.12	-178.04	308.38	308.38	0.00	0.00	0.00
6,400.00	10.00	120.00	6,368.60	-186.73	323.42	323.42	0.00	0.00	0.00
6,500.00	10.00	120.00	6,467.08	-195.41	338.46	338.46	0.00	0.00	0.00
6,600.00	10.00	120.00	6,565.56	-204.09	353.50	353.50	0.00	0.00	0.00
6,700.00	10.00	120.00	6,664.04	-212.77	368.54	368.54	0.00	0.00	0.00
6,800.00	10.00	120.00	6,762.52	-221.46	383.57	383.57	0.00	0.00	0.00
6,900.00	10.00	120.00	6,861.00	-230.14	398.61	398.61	0.00	0.00	0.00
6,938.58	10.00	120.00	6,899.00	-233.49	404.41	404.41	0.00	0.00	0.00
1st Bone Spring Sand									
7,000.00	10.00	120.00	6,959.48	-238.82	413.65	413.65	0.00	0.00	0.00
7,100.00	10.00	120.00	7,057.97	-247.50	428.69	428.69	0.00	0.00	0.00
7,200.00	10.00	120.00	7,156.45	-256.19	443.73	443.73	0.00	0.00	0.00
7,300.00	10.00	120.00	7,254.93	-264.87	458.77	458.77	0.00	0.00	0.00
7,400.00	10.00	120.00	7,353.41	-273.55	473.80	473.80	0.00	0.00	0.00
7,500.00	10.00	120.00	7,451.89	-282.23	488.84	488.84	0.00	0.00	0.00
7,600.00	10.00	120.00	7,550.37	-290.92	503.88	503.88	0.00	0.00	0.00
7,700.00	10.00	120.00	7,648.85	-299.60	518.92	518.92	0.00	0.00	0.00
7,750.92	10.00	120.00	7,699.00	-304.02	526.58	526.58	0.00	0.00	0.00
2nd Bone Spring Sand									
7,800.00	10.00	120.00	7,747.33	-308.28	533.96	533.96	0.00	0.00	0.00
7,900.00	10.00	120.00	7,845.81	-316.96	549.00	549.00	0.00	0.00	0.00
8,000.00	10.00	120.00	7,944.29	-325.65	564.03	564.03	0.00	0.00	0.00
8,100.00	10.00	120.00	8,042.77	-334.33	579.07	579.07	0.00	0.00	0.00
8,200.00	10.00	120.00	8,141.25	-343.01	594.11	594.11	0.00	0.00	0.00
8,250.00	10.00	120.00	8,190.49	-347.35	601.63	601.63	0.00	0.00	0.00
DROP 2.0° / 100									
8,300.00	9.00	120.00	8,239.81	-351.48	608.78	608.78	2.00	-2.00	0.00
8,400.00	7.00	120.00	8,338.83	-358.44	620.83	620.83	2.00	-2.00	0.00
8,500.00	5.00	120.00	8,438.28	-363.66	629.88	629.88	2.00	-2.00	0.00
8,600.00	3.00	120.00	8,538.03	-367.15	635.92	635.92	2.00	-2.00	0.00

Planning Report

Database: Midland District
 Company: Marathon Oil Permian, LLC
 Project: Eddy County, NM (NAD27)
 Site: Squirrel Master Fee 23-28-5
 Well: WXY #3H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference: Well WXY #3H
 TVD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 MD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,700.00	1.00	120.00	8,637.96	-368.89	638.94	638.94	2.00	-2.00	0.00
8,750.00	0.00	0.00	8,687.96	-369.11	639.32	639.32	2.00	-2.00	0.00
EOD - HOLD									
8,800.00	0.00	0.00	8,737.96	-369.11	639.32	639.32	0.00	0.00	0.00
8,900.00	0.00	0.00	8,837.96	-369.11	639.32	639.32	0.00	0.00	0.00
8,912.04	0.00	0.00	8,850.00	-369.11	639.32	639.32	0.00	0.00	0.00
Curve KOP - Build 10.0° / 100									
8,950.00	3.80	110.00	8,887.93	-369.54	640.50	640.50	10.00	10.00	0.00
9,000.00	8.80	110.00	8,937.61	-371.42	645.65	645.65	10.00	10.00	0.00
9,016.62	10.46	110.00	8,954.00	-372.37	648.27	648.27	10.00	10.00	0.00
3rd Bone Spring Sand									
9,050.00	13.80	110.00	8,986.63	-374.77	654.85	654.85	10.00	10.00	0.00
9,100.00	18.80	110.00	9,034.61	-379.56	668.03	668.03	10.00	10.00	0.00
9,150.00	23.80	110.00	9,081.18	-385.77	685.09	685.09	10.00	10.00	0.00
9,200.00	28.80	110.00	9,125.99	-393.35	705.90	705.90	10.00	10.00	0.00
9,250.00	33.80	110.00	9,168.70	-402.23	730.30	730.30	10.00	10.00	0.00
9,300.00	38.80	110.00	9,208.99	-412.35	758.10	758.10	10.00	10.00	0.00
9,350.00	43.80	110.00	9,246.54	-423.63	789.10	789.10	10.00	10.00	0.00
9,400.00	48.80	110.00	9,281.08	-435.99	823.08	823.08	10.00	10.00	0.00
9,418.44	50.64	110.00	9,293.00	-440.80	836.28	836.28	10.00	10.00	0.00
Wolfcamp									
9,450.00	53.80	110.00	9,312.33	-449.33	859.71	859.71	10.00	10.00	0.00
9,500.00	58.80	110.00	9,340.07	-463.55	898.79	898.79	10.00	10.00	0.00
9,550.00	63.80	110.00	9,364.07	-478.54	939.98	939.98	10.00	10.00	0.00
9,600.00	68.80	110.00	9,384.17	-494.20	982.99	982.99	10.00	10.00	0.00
9,650.00	73.80	110.00	9,400.20	-510.39	1,027.48	1,027.48	10.00	10.00	0.00
9,700.00	78.80	110.00	9,412.04	-527.00	1,073.11	1,073.11	10.00	10.00	0.00
9,750.00	83.80	110.00	9,419.60	-543.90	1,119.54	1,119.54	10.00	10.00	0.00
9,801.04	88.90	110.00	9,422.85	-561.31	1,167.39	1,167.39	10.00	10.00	0.00
EOC - HOLD									
9,848.04	88.90	110.00	9,423.75	-577.39	1,211.55	1,211.55	0.00	0.00	0.00
TURN									
9,900.00	88.90	108.96	9,424.75	-594.71	1,260.52	1,260.52	2.00	-0.01	-2.00
9,982.51	88.89	107.31	9,426.35	-620.39	1,338.92	1,338.92	2.00	-0.01	-2.00
FTP(SMWXY#3H)									
10,000.00	88.89	106.96	9,426.68	-625.54	1,355.63	1,355.63	2.00	0.00	-2.00
10,100.00	88.89	104.96	9,428.62	-653.03	1,451.75	1,451.75	2.00	0.00	-2.00
10,119.42	88.89	104.57	9,429.00	-657.98	1,470.53	1,470.53	2.00	0.00	-2.00
Wolfcamp A									
10,200.00	88.88	102.96	9,430.57	-677.15	1,548.77	1,548.77	2.00	0.00	-2.00
10,300.00	88.88	100.96	9,432.52	-697.86	1,646.58	1,646.58	2.00	0.00	-2.00
10,400.00	88.88	98.96	9,434.46	-715.15	1,745.05	1,745.05	2.00	0.00	-2.00
10,500.00	88.88	96.96	9,436.41	-729.00	1,844.06	1,844.06	2.00	0.00	-2.00
10,600.00	88.89	94.96	9,438.36	-739.37	1,943.50	1,943.50	2.00	0.00	-2.00
10,700.00	88.89	92.96	9,440.30	-746.27	2,043.24	2,043.24	2.00	0.00	-2.00
10,800.00	88.90	90.96	9,442.23	-749.69	2,143.15	2,143.15	2.00	0.01	-2.00
10,848.35	88.90	89.99	9,443.16	-750.09	2,191.50	2,191.50	2.00	0.01	-2.00
HOLD									
10,900.00	88.90	89.99	9,444.15	-750.08	2,243.13	2,243.13	0.00	0.00	0.00
11,000.00	88.90	89.99	9,446.07	-750.06	2,343.11	2,343.11	0.00	0.00	0.00
11,100.00	88.90	89.99	9,447.99	-750.04	2,443.10	2,443.10	0.00	0.00	0.00
11,200.00	88.90	89.99	9,449.91	-750.03	2,543.08	2,543.08	0.00	0.00	0.00
11,300.00	88.90	89.99	9,451.83	-750.01	2,643.06	2,643.06	0.00	0.00	0.00

Planning Report

Database: Midland District
 Company: Marathon Oil Permian, LLC
 Project: Eddy County, NM (NAD27)
 Site: Squirrel Master Fee 23-28-5
 Well: WXY #3H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference: Well WXY #3H
 TVD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 MD Reference: KB = 26.5' @ 3056.50usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (bearing)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
11,400.00	88.90	89.99	9,453.75	-749.99	2,743.04	2,743.04	0.00	0.00	0.00
11,500.00	88.90	89.99	9,455.67	-749.97	2,843.02	2,843.02	0.00	0.00	0.00
11,600.00	88.90	89.99	9,457.59	-749.95	2,943.00	2,943.00	0.00	0.00	0.00
11,700.00	88.90	89.99	9,459.51	-749.93	3,042.99	3,042.99	0.00	0.00	0.00
11,800.00	88.90	89.99	9,461.43	-749.91	3,142.97	3,142.97	0.00	0.00	0.00
11,900.00	88.90	89.99	9,463.35	-749.89	3,242.95	3,242.95	0.00	0.00	0.00
12,000.00	88.90	89.99	9,465.27	-749.87	3,342.93	3,342.93	0.00	0.00	0.00
12,100.00	88.90	89.99	9,467.19	-749.85	3,442.91	3,442.91	0.00	0.00	0.00
12,200.00	88.90	89.99	9,469.11	-749.83	3,542.89	3,542.89	0.00	0.00	0.00
12,300.00	88.90	89.99	9,471.03	-749.81	3,642.88	3,642.88	0.00	0.00	0.00
12,400.00	88.90	89.99	9,472.96	-749.79	3,742.86	3,742.86	0.00	0.00	0.00
12,500.00	88.90	89.99	9,474.88	-749.77	3,842.84	3,842.84	0.00	0.00	0.00
12,600.00	88.90	89.99	9,476.80	-749.75	3,942.82	3,942.82	0.00	0.00	0.00
12,700.00	88.90	89.99	9,478.72	-749.73	4,042.80	4,042.80	0.00	0.00	0.00
12,800.00	88.90	89.99	9,480.64	-749.71	4,142.78	4,142.78	0.00	0.00	0.00
12,900.00	88.90	89.99	9,482.56	-749.69	4,242.76	4,242.76	0.00	0.00	0.00
13,000.00	88.90	89.99	9,484.49	-749.67	4,342.75	4,342.75	0.00	0.00	0.00
13,100.00	88.90	89.99	9,486.41	-749.64	4,442.73	4,442.73	0.00	0.00	0.00
13,200.00	88.90	89.99	9,488.33	-749.62	4,542.71	4,542.71	0.00	0.00	0.00
13,300.00	88.90	89.99	9,490.25	-749.60	4,642.69	4,642.69	0.00	0.00	0.00
13,400.00	88.90	89.99	9,492.18	-749.58	4,742.67	4,742.67	0.00	0.00	0.00
13,500.00	88.90	89.99	9,494.10	-749.55	4,842.65	4,842.65	0.00	0.00	0.00
13,600.00	88.90	89.99	9,496.02	-749.53	4,942.63	4,942.63	0.00	0.00	0.00
13,700.00	88.90	89.99	9,497.94	-749.51	5,042.62	5,042.62	0.00	0.00	0.00
13,800.00	88.90	89.99	9,499.87	-749.49	5,142.60	5,142.60	0.00	0.00	0.00
13,900.00	88.90	89.99	9,501.79	-749.46	5,242.58	5,242.58	0.00	0.00	0.00
14,000.00	88.90	89.99	9,503.71	-749.44	5,342.56	5,342.56	0.00	0.00	0.00
14,100.00	88.90	89.99	9,505.64	-749.41	5,442.54	5,442.54	0.00	0.00	0.00
14,200.00	88.90	89.99	9,507.56	-749.39	5,542.52	5,542.52	0.00	0.00	0.00
14,300.00	88.90	89.99	9,509.48	-749.37	5,642.51	5,642.51	0.00	0.00	0.00
14,400.00	88.90	89.99	9,511.41	-749.34	5,742.49	5,742.49	0.00	0.00	0.00
14,500.00	88.90	89.99	9,513.33	-749.32	5,842.47	5,842.47	0.00	0.00	0.00
14,586.84	88.90	89.99	9,515.00	-749.29	5,929.29	5,929.29	0.00	0.00	0.00
TD at 14586.84 - BHL[SMWXY#3H]									
14,600.00	88.90	89.99	9,515.25	-749.29	5,942.45	5,942.45	0.00	0.00	0.00
14,631.84	88.90	89.99	9,515.87	-749.28	5,974.28	5,974.28	0.00	0.00	0.00
TD + 45' VS									

Design Targets

Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (bearing)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
FTP[SMWXY#3H] - plan misses target center by 191.31usft at 9982.51usft MD (9426.35 TVD, -620.39 N, 1338.92 E) - Point	0.00	0.00	9,291.00	-749.78	1,299.72	485,780.10	567,032.77	32° 20' 7.219 N	104° 6' 58.685 W
BHL[SMWXY#3H] - plan hits target center - Point	0.00	0.00	9,515.00	-749.29	5,929.29	485,780.59	571,661.94	32° 20' 7.128 N	104° 6' 4.730 W

Planning Report

Database:	Midland District	Local Co-ordinate Reference:	Well WXY #3H
Company:	Marathon Oil Permian, LLC	TVD Reference:	KB = 26.5' @ 3056.50usft (Rig TBD)
Project:	Eddy County, NM (NAD27)	MD Reference:	KB = 26.5' @ 3056.50usft (Rig TBD)
Site:	Squirrel Master Fee 23-28-5	North Reference:	Grid
Well:	WXY #3H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #1		

Formations					
Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (bearing)
461.00	461.00	Salado/Castile			
2,411.00	2,411.00	Lamar			
2,472.00	2,472.00	Bell Canyon			
3,267.00	3,267.00	Cherry Canyon			
4,489.38	4,487.00	Brushy Canyon			
5,939.40	5,915.00	Bone Spring			
6,938.58	6,899.00	1st Bone Spring Sand			
7,750.92	7,699.00	2nd Bone Spring Sand			
9,016.62	8,954.00	3rd Bone Spring Sand			
9,418.44	9,293.00	Wolfcamp			
10,119.42	9,429.00	Wolfcamp A			

Plan Annotations					
Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates			
		+N/-S (usft)	+E/-W (usft)	Comment	
4,000.00	4,000.00	0.00	0.00	KOP - Build 2.0° / 100	
4,500.00	4,497.47	-21.76	37.69	EOB - HOLD	
8,250.00	8,190.49	-347.35	601.63	DROP 2.0° / 100	
8,750.00	8,687.96	-369.11	639.32	EOD - HOLD	
8,912.04	8,850.00	-369.11	639.32	Curve KOP - Build 10.0° / 100	
9,801.04	9,422.85	-561.31	1,167.39	EOC - HOLD	
9,848.04	9,423.75	-577.39	1,211.55	TURN	
10,848.35	9,443.16	-750.09	2,191.50	HOLD	
14,586.84	9,515.00	-749.29	5,929.29	TD at 14586.84	
14,631.84	9,515.87	-749.28	5,974.28	TD + 45' VS	

Marathon Oil Corporation

EDDY COUNTY, NM (NAD27)
SQUIRREL MASTER FEE 23-28-5
WXY #3H

PLAN #1
RIG TBD

WELL DETAILS:

Ground Level: 3030.00
+N-S 0.00 +E-W 0.00
Northing 486529.82 Easting 565733.18 32° 20' 14.685 N 104° 7' 13.816 W

SECTION DETAILS

MD	INC	AZI	TVD	+N-S	+E-W	DLEG	TFACE	YSECT	TARGET
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
4000.00	0.00	0.00	4000.00	0.00	0.00	0.00	0.00	0.00	
4500.00	10.00	120.00	4497.47	-21.76	37.69	2.00	120.00	37.69	
8250.00	10.00	120.00	8190.49	-347.35	601.63	0.00	0.00	601.63	
8750.00	0.00	0.00	8687.96	-369.11	639.32	2.00	180.00	639.32	
8912.04	0.00	0.00	8850.00	-369.11	639.32	0.00	0.00	639.32	
9801.04	88.90	110.00	9422.85	-591.31	1167.39	10.00	110.00	1167.39	
9848.04	88.90	110.00	9423.75	-577.39	1211.55	0.00	0.00	1211.55	
10848.35	88.90	89.99	9443.16	-750.09	2191.50	2.00	-90.19	2191.50	
14586.84	88.90	89.99	9515.00	-749.29	5929.29	0.00	-117.84	5929.29	BHL[SMWXY#3H]
14631.84	88.90	89.99	9515.87	-749.28	5974.28	0.00	0.00	5974.28	

DESIGN TARGET DETAILS

Name	TVD	+N-S	+E-W	Northing	Easting
FTP[SMWXY#3H]	9443.00	-748.78	1299.72	485780.10	567032.77
BHL[SMWXY#3H]	9515.00	-749.29	5929.29	485780.59	571861.94



To convert Magnetic North to Grid, Add 7.17°
To convert True North to Grid, Subtract 0.11°

Azimuths to Grid North
True North: -0.11°
Magnetic North: 7.17°
Magnetic Field
Strength: 48033.1nT
Dip Angle: 60.12°
Date: 4/5/2018
Model: HDGM

FORMATION TOP DETAILS

TVD PATH	MD PATH	FORMATION
461.00	461.00	SALADO/CASTILE
2411.00	2411.00	LAMAR
2472.00	2472.00	BELL CANYON
3267.00	3267.00	CHERRY CANYON
4487.00	4489.38	BRUSHY CANYON
5915.00	5939.40	BONE SPRING
6899.00	6938.58	1ST BONE SPRING SAND
7699.00	7750.92	2ND BONE SPRING SAND
8954.00	9016.62	3RD BONE SPRING SAND
9293.00	9418.44	WOLFCAMP
9429.00	10119.42	WOLFCAMP A

SITE DETAILS: Squirrel Master Fee 23-28-5
Site Centre Northing: 486529.83
Easting: 565703.18

Positional Uncertainty: 0.00
Convergence: 0.11
Local North: Grid

Map System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone Name: New Mexico East 3001
Local Origin: Well WXY #3H, Grid North
Latitude: 32° 20' 14.685 N
Longitude: 104° 7' 13.816 W
Grid East: 565733.18
Grid North: 486529.82
Scale Factor: 1.000

Geomagnetic Model: HDGM
Sample Date: 05-Apr-18
Magnetic Declination: 7.28°
Dip Angle from Horizontal: 60.12°
Magnetic Field Strength: 48033

To convert Magnetic North to Grid, Add 7.17°
To convert Magnetic North to True, Add 7.28° East
To convert True North to Grid, Subtract 0.11°

PROJECT DETAILS: Eddy County, NM (NAD27)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level

DRILLING TARGET: 9401 'TVD @ OVS // 88.9° INC.

WINDOW: 10' U // 10' D // 30' L // 30' R

NM OIL CONSERVATION
ARTESIA DISTRICT

APR 10 2018

RECEIVED

