

District I - (575) 393-6161
1625 N. French Dr., Hobbs, NM 88240
District II - (575) 748-1283
811 S. First St., Artesia, NM 88210
District III - (505) 334-6178
1000 Rio Brazos Rd., Aztec, NM 87410
District IV - (505) 476-3460
1220 S. St. Francis Dr., Santa Fe, NM 87505

RECEIVED

JAN 21 2020

Energy, Minerals and Natural Resources

OIL CONSERVATION DIVISION

1220 South St. Francis Dr.

Santa Fe, NM 87505

EMMRD-OCD ARTESIA

WELL API NO. 30-015-46600
5. Indicate Type of Lease STATE [X] FEE []
6. State Oil & Gas Lease No.

SUNDRY NOTICES AND REPORTS ON WELLS
1. Type of Well: Oil Well [X] Gas Well [] Other []
2. Name of Operator COG Operating LLC
3. Address of Operator 600 W. Illinois Ave., Midland, TX 79701
4. Well Location Unit Letter A : 245 feet from the North line and 955 feet from the East line
Section 28 Township 25S Range 28E NMPM County Eddy
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 2958' GR

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

- PERFORM REMEDIAL WORK [] PLUG AND ABANDON []
TEMPORARILY ABANDON [] CHANGE PLANS [X]
PULL OR ALTER CASING [] MULTIPLE COMPL []
DOWNHOLE COMMINGLE []
CLOSED-LOOP SYSTEM []
OTHER: []

SUBSEQUENT REPORT OF:

- REMEDIAL WORK [] ALTERING CASING []
COMMENCE DRILLING OPNS. [] P AND A []
CASING/CEMENT JOB []
OTHER: []

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

COG Operating LLC respectfully requests to make the following changes to the Drilling plan:

Table with 7 columns: TYPE, HOLE SIZE, CASING SIZE, CASING WT., SETTING DEPTH, SACKS OF CEMENT, ESTIMATED TOC. Rows include SURF, INT 1, and PROD.

COG proposes to drill 14-3/4" hole to ~675' w/ fresh water. Run 10-3/4" 45.5# J-55 BTC casing to TD and cement to surface in one stage. Drill 9-7/8" hole to ~8,800' with cut brine emulsion. Run 7-5/8 29.7# L-80 BTC to TD and cement to surface in one stage. Drill 6-3/4" vertical hole, curve & lateral to 20,132' with OBM. Run 5-1/2" 20# P110 CDC HTQ from surfaced to 8,700' and TLW casing from 8,700' to TD and cement to 8,200' in one stage.

Spud Date: []

Rig Release Date: []

I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE [Signature] TITLE Sr Regulatory Analyst DATE 01/17/2020
Type or print name Robyn M. Russell E-mail address: Rrussell@concho.com PHONE: (432) 685-4385

For State Use Only

APPROVED BY [Signature] TITLE Geologist DATE 2-12-2020
Conditions of Approval (if any):