SEP -8 2008

OCD-ARTESIA

UNITED STATES DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT

Form 3160-3 (February 2005) OCD-ARTESIA

1163

FORM APPROVED OMB No 1004-0137 Expires March 31, 2007

LC048468(SL);NM063472 (BL)

6 If Indian, Allotee or Tribe Name

| APPLICATION FOR PERMIT TO | DRILL OR | REENTER | | o n mann, money or | | |
|--|-----------------------------|--|---------------------------------------|---|------------------------------------|--|
| la. Type of work DRILL REENT | ER | | · · · · · · · · · · · · · · · · · · · | 7 If Unit or CA Agreement, Name and No | | |
| lb Type of Well. Oll Well Gas Well Other | Sın | gle ZoneMultı | ole Zone | 8. Lease Name and We SAND TANK 18 | | |
| 2. Name of Operator EOG Resources, Inc. | | | | 9 API Well No. 30-015-36 | 617 | |
| 3a Address P.O. Box 2267 Midland, TX 79702 | 3b Phone No. 432-686 | (include area code) 5-3642 | | 10 Field and Pool, or Exp Sand Tank; Bon | , | |
| 4 Location of Well (Report location clearly and in accordance with a At surface 1880' FSL & 2310' FEL (U/L J); S At proposed prod zone 1980' FSL & 2310' FWL (U/L K); | ec 18, T18S-R | 30E | | 11. Sec., T R M or Blk. Section 18, T18S | and Survey or Area -R30E, N.M.P.M. | |
| 14 Distance in miles and direction from nearest town or post office: | | | | 12 County or Parish | 13 State | |
| Approx 5 miles SW from Loco Hills, NM Capita | n Control | ed Water Bas | sin | Eddy | NM | |
| 15 Distance from proposed* location to nearest property or lease line, ft (Also to nearest drig unit line, if any) | 16 No of ac | res in lease | | g Unit dedicated to this wel E/4 (18); N/2 SW/4 (17) | | |
| 18 Distance from proposed location* | 19 Proposed | Depth | 20 BLM/I | VBIA Bond No on file | | |
| to nearest well, drilling, completed, applied for, on this lease, ft | ' | D; 12,492'TMD | NM23 | 98 | | |
| 21 Elevations (Show whether DF, KDB, RT, GL, etc.) GL 3513 | 22. Approxim | ate date work will sta 09/30/2008 | rt* | 23 Estimated duration 30 days | | |
| | 24. Attac | nments | | | | |
| The following, completed in accordance with the requirements of Onshe | ore Oil and Gas (| Order No I, must be a | tached to the | s form | | |
| Well plat certified by a registered surveyor A Drilling Plan A Surface Use Plan (if the location is on National Forest System SUPO must be filed with the appropriate Forest Service Office) | n Lands, the | Item 20 above) 5 Operator certific | cation | ns unless covered by an ex ormation and/or plans as in | · · | |
| 25 Signature Jy J. Must | 4 | Printed Typed) Donny G. Glanton | | D | o7/17/2008 | |
| Title Sr. Lease Operations ROW Representative | | | | | | |
| Approved by (Signature) /S/ DAVID D. EVANS | | Printed Typed) /S/ DAVIE | D. EV | AND L | *SEP - 4 2008 | |
| Title FIELD MANAGER | Office | CARLS | BAD | FIELD OFFI | CE | |
| Application approval does not warrant or certify that the applicant hol conduct operations thereon Conditions of approval, if any, are attached | ds legal or equit | | ts in the sub | | tle the applicant to | |
| Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a States any false, fictitious or fraudulent statements or representations as | crime for any pe | rson knowingly and thin its jurisdiction | willfully to n | nake to any department or | agency of the United | |

*(Instructions on page 2)

SEE ATTACHED FOR CONDITIONS OF APPROVAL APPROVAL SUBJECT TO GENERAL REQUIREMENTS AND SPECIAL STIPULATIONS **ATTACHED**

District 1

1625 N. French Dr., Hobbs, NM 88240

District II

-1301 W. Grand Avenue, Artesia, NM 88210

District III

1000 Rio Brazos Rd., Aztec, NM 87410

District IV

1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico

Energy, Minerals & Natural Resources Department

OIL CONSERVATION DIVISION

1220 South St. Francis Dr. Santa Fe. NM 87505

Form C-102

Revised October 12, 2005

Submit to Appropriate District Office

State Lease- 4 Copies


Fee Lease-3 Copies

AMENDED REPORT


WELL LOCATION AND ACREAGE DEDICATION PLAT API Number Pool Code 30-015-96832 Sand Tank; Bone Spring Property Name Property Code Well Number SAND TANK 18 FED. COM 4H1095 Operator Name Elevation 1317 EOG RESOURCES, INC. *3513.5* [']

Surface Location UL or lot no. Section Lot Idn Feet from the North/South line Township Range Feet from the East/West line County 18 18 SOUTH 30 EAST, N.M.P.M. 1880' SOUTH 2310' EAST **EDDY** Bottom Hole Location If Different From Surface Township Lot Idn Feet from the North/South line Feet from the Ut or lot no Section East/West line County K 18 SOUTH 30 EAST, N.M.P.M. 17 1980' **SOUTH** WEST **EDDY** 2310 Dedicated Acres Joint or Infill Consolidation Code Order No. 160

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the



LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL: 10'

SEC. 18 TWP. 18—S RGE. 30—E

SURVEY N.M.P.M.

COUNTY EDDY

DESCRIPTION 1880' FSL & 2310' FEL

ELEVATION 3513.5'

OPERATOR EOG RESOURCES INC.

LEASE SAND TANK 18 FED. COM #4H

U.S.G.S. TOPOGRAPHIC MAP


ILLINOIS CAMP NE, N.M.

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR
HOBBS, NEW MEXICO - 575-393-9146



VICINITY MAP



номян

 SEC. 18 TWP. 18-S RGE. 30-E

 SURVEY N.M.P.M.


 COUNTY EDDY

 DESCRIPTION 1880' FSL & 2310' FEL

ELEVATION 3513.5'


OPERATOR EOG RESOURCES INC.

Asel Surveying





LEASE SAND TANK 18 FED. COM #4H
DIRECTIONS BEGINNING IN LOCO HILLS AT THE INTERSECTION OF U.S. HWY. #82 AND EDDY CO. ROAD
#217, GO SOUTH SOUTHWEST ON EDDY CO. ROAD #217 FOR 3.0 MILES, TURN LEFT ON EDDY CO.
ROAD #216 (GENERAL AMERICAN ROAD) AND GO SOUTH FOR 1.9 MILES, TURN LEFT ON LEASE ROAD
FOR 0.1 MILES, TURN RIGHT ON LEASE ROAD FOR 0.2 MILES, TURN LEFT ON LEASE ROAD AND GO
EAST FOR 0.5 MILES, TURN RIGHT AND GO SOUTH FOR 0.1 MILES, TURN RIGHT AND GO WEST ON
LEASE ROAD FOR 0.2 MILES, TURN LEFT AND GO SOUTH FOR 0.3 MILES TO PROPOSED NEW ROAD,
GO EAST FOR 0.1 MILES, TURN SOUTH FOR 0.3 MILES TO LOCATION.



DESCRIPTION

A STRIP OF LAND 30.0 FEET WIDE AND 2913.1 FEET OR 0.552 MILES IN LENGTH CROSSING U.S.A. LAND IN SECTION 18, TOWNSHIP 18 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 15.0 FEET LEFT AND 15.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.



SURVEYORS CERTIFICATE

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMIUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.

Jeny J. Agel N.M. R.P.S. No. 15079

Asel Surveying

P.O. BOX 393 - 310 W. TAYLOR HOBBS, NEW MEXICO - 505-393-9146

LEGEND

● - DENOTES FOUND MONUMENT AS NOTED

1000' 0 1000' 2000' FEET

SCALE: 1"=1000'


EOG RESOURCES, INC.


SURVEY FOR A ROAD EASEMENT CROSSING U.S.A. LAND IN SECTION 18, TOWNSHIP 18 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

| Survey Date: 07/05/08 | Sheet 1 of 1 Sheets |
|------------------------------|-------------------------------|
| W.O. Number: 080705RD | Drawn By: JL |
| Date: 07/08/08 | 080705RD.DWG Scale:1"=1000' |

SECTIONS 18 & 17, TOWNSHIP 18 SOUTH, RANGE 30 EAST, N.M.P.M., EDDY COUNTY

EXAMPLE 26





DRIVING DIRECTIONS:
BEGINNING IN LOCO HILLS AT THE INTERSECTION OF
U.S. HWY. #82 AND EDDY COUNTY ROAD #217
(HAGERMAN CUTOFF ROAD), GO SOUTH SOUTHWEST
ON EDDY CO. ROAD #217 FOR 3.0 MILES, TURN
LEFT ON EDDY COUNTY ROAD #216 (GENERAL
AMERICAN ROAD) AND GO SOUTH FOR 1.9 MILES,
TURN LEFT ON LEASE ROAD FOR 0.1 MILES, TURN
RIGHT ON LEASE ROAD FOR 0.2 MILES, TURN LEFT
ON LEASE ROAD AND GO EAST FOR 0.5 MILES,
TURN RIGHT AND GO SOUTH FOR 0.1 MILES, TURN
RIGHT AND GO WEST ON LEASE ROAD FOR 0.2
MILES, TURN LEFT AND GO SOUTH FOR 0.3 MILES
TO PROPOSED NEW ROAD, GO EAST FOR 0.1 MILES,
TURN SOUTH FOR 0.3 MILES TO LOCATION.

SCALE-1'=200'




SURVEYORS CERTIFICATE

of Bearings t Zone (83)

I, TERRY J. ASEL, NEW MEXICO PROFESSIONAL SURVEYOR NO. 15079, DO HEREBY CERTIFY THAT I CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND MEETS THE "MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO" AS ADOPTED BY THE NEW MEXICO STATE BOARD OF REGISTRATION FOR PROFESSIONAL ENGINEERS AND SURVEYORS.




Asel Surveying



LEGEND

DENOTES FOUND MONUMENT AS NOTED



EOG RESOURCES, INC.

SAND TANK 18 FED. COM #4H
IN SECTIONS 18 & 17, TOWNSHIP 18 SOUTH,
RANGE 30 EAST, N.M.P.M., EDDY COUNTY,
NEW MEXICO

| Survey Date: 07/02/08 | Sheet 1 o | f 1 Sheets |
|-------------------------|--------------|----------------|
| W.O. Number: 080702WL-a | Drawn By: KA | Rev: |
| Date: 07/07/08 | 080702WL-a | Scale:1"=1000' |

| The state of the s | 0 157 0 107 225 0 157 0 107 225 0 157 0 107 225 0 157 0 107 225 0 157 0 158 | 152 145 145 0 17 17 6 17 6 17 6 17 6 17 6 17 6 17 6 | The mirrolles was a comment of the second of | |
|--|--|--|--|---|
| EXHIBIT 3 | 156 156 156 156 156 156 156 155 1 | 159 JS JO JS Ger Amarica (1981) | Garage Control | Feet de Word Parent Co. WI Par |
| Soul T V V | '5 184 20 100) 6004 | 197 (A) 188 199 A O 1690 PARCO 9191 E | Pecce Processing 19 10 10 10 10 10 10 10 10 10 10 10 10 10 | AROC AROC AROC AROC AROC AROC AROC AROC |
| Sand Tank 18 Fed lom 4H | (88) Gray 99 (850) 4955 501 89) 197 (196 | (Pro) (Gen Amer) (Pro) (Grop Beer) Marthon (Grop Beer) Marthon (Grop Beer) Marthon (Grop Beer) (Grop B | AROZ ZE ZE TO | O ZOSO "MA" BI BINI |
| SHL: 1880' FSL : 2310' FEL | 7197 096 WI 71901 097 097 Am | 137 67 CRS Oper S/R | 1936 23 BWI 1703712 | Mogoren 13th mas SO 151 1/2 |
| Section 18, T185-1230 E | ST 1150 Sowers | "L" Sony 10 40 37 24 0 | 1 8 4 108 MOORES | (Pecos Prad) |
| BHL: 1980 FSL : 2310 FWL | COG 54 con 50 COG 54 3 20 54 5 | 15° 65 67 68 65° 65° 65° 65° 65° 65° 65° 65° 65° 65° | Pet p Madge" | Pecos Prod HOP 055 9581 |
| Section 17, 7188 - R30 E | 9 2023 9 7 | Dhillios walcas sia lyates of | Alem Competet 14 p Baston Ben | D/A6 -3 48 |
| ard and | No Loco" 1 * (Beinorth) Now Novelly i | P 6 2 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 | Sand Laure Offi | 053: 0579 Solwest Ener Prod Big Tank Fed |
| ************************************** | 12 A Socialist A Socialist A Socialist A Socialist A Socialist Rough of the Control of the Contr | Free Joy Jan Spran 3 5 5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 | School Manual 1 OXY 10 280 CHS Variable County 6 2190 School Principle 6 80 | Beason 1-X Beason 1-X 103464-64 |
| Eddy County, New Mexico | I ALNU . | 1326A 4 3 3000 3 30 81 2 3076 1 | 38.75 439.95 340.07 240.21 1 00 Newmont Yates Pt. Franklin | 14035 140 9 140 40 140 4 Franklin Astan, Fair Noison - Feo. |
| r (| Newmorth 3 Ballard | 3 de folce du p | to Del, base 102905 etal Ne son | 1 L 1 L 1 L 1 L 1 L 1 L 1 L 1 L 1 L 1 L |
| д 3 <u>Гонеци 22 2 - 24 - 24 - 24 - 24 - 24 - 24 - 2</u> | Votes Pet 1505 Hand | Yates Per 546 15 14 514 55 16 6 049947 172 14 14 15 14 15 16 16 16 16 16 16 16 16 16 16 16 16 16 | to Eog Res Formation Company C | Mandemon A |
| Some So | ates Pet ps | (Newmoot) | EOG Res, 046256 | (Franklin Aston (, Fairl Edg Res FAF Fed (55 Roy) (0.12545 Fed (55 Roy) (0.12545 Fed (55 Roy) (1.12545 Fed (55 |
| Parine saying | No. | | 医春 经产品通过 人名马姆伊克 | The Diwon of Ped |
| 1 | Yates JF 4 Fer. 828772 | 5 EGG U S Franklin, etal 15 EGG W S Franklin, etal 16 Fred Genyates , 102872 1784 1 2 H EGG Res | OZHA OBHL 3H A | |
| Yate (Pot etal./2) | 1050904 6 BAR | EDG GESTEIL (Tom Boudelet, S/R) Sond Gesteil 1 2.4 EDG Res BHL Miss Discrete G. D/R) | 767 F.OG Res 0 300557 | EDG RES -X |
| Spet, WEST LOCOHILL STERRE IN TO ALL STE | - A Eugen (wei) 1 (2. | 2 (Newmont)) 5 W 047269 to TomBoud | (Burlington) (So Roy) (Holly-Fed (P/B) (Morr plac) | x |
| 8-3 Costilla Tr 13-3 Tr 4-1 | 7 ates Pet. | 937 93 31 SDX Res | EOG Res H (So Rout) (IA) Yate Hally Fed Har | es Yey ocog Res. |
| TTIN # US TO 2671 Knot Newmont Mewberrie | Yates Sand Tank Fed | ode co caston | Mostella - EOG Res No | rvey etal H.E. Yorkes HBP |
| 1580 State 4 Bearings Brainerd 4 State To 050229 | us Ir 6 | 4 22 18 Tr. 2-A BHL | BHL + TVS ZAS - OBHL + 123 | Bn Spr Dnsc Fi30 |
| emport of the state of the stat | Tates Pet. | Mastellar ISO Tinion | Hoperies B EOGRES B HOP MOSTELLE C South of the state C Sou | CUG OEG OXY, (1/ 1 2008 E06 1 1 2008 Res 842 66 27276 |
| Fig.) Tr. 8-B underwood (same to the control of the | Tr. 7:A | | A J Smith Fed Sorpson Res 4 8 Smith T0 214 A 2005 Franklin etal Sagar lank T0 2003 Major lank T0 2003 Major lank | Southwest |
| Loco-Guy Registration of Thunderbott Yates Fet. Enron Thunderbott Yates Fet. | -13 and | 7:18-7:5 Res. Res. Tr.218-7:50 1049528 00497521 | TO 2868 November 17 To 2868 November 17 To 2868 November 17 To 2868 November 18 To 286 | Res EOG Res |
| 1 ARUN 96220 0437524 # 1 ARUN 96694 06 694 | 437,522 | SAITH-Fed | Confield Somson Res | 9262 1830 SOEG EOG RES 95639 |
| 29 "Boulter Fed" 8 65 10 047 311 | | 0437523 U.S OG Res. 10 OG | Violence - V 1 11.1 | 1206 HBP £ 1262 25000 |
| Ji Tr 99 COG Martin Yates III Waring Vates Petral Cock Prolifer Services Petral Prolifer Petral Prolifer Services Petral Prolifer Services Petral | HBP: 0427523 | Martab) | EOG Res. (Flag. HBP Reffern Client | Teroco, etal McCour texoco |
| 10 10 10 10 10 10 10 10 10 10 10 10 10 1 | Marbab 2009 | Margarian EGG AGGERTA 1013-19-JEWDOUTRE POLES COMPTED 020186 | File of the state | Redfern, 0283'9 |
| Mossie 22 meriner 0 431524 Mossie 23 Morbob One 2 | 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 18 25 F EOG | Mewbourne Ar | ioina of Manning |
| Mostin 2 - Fed Wishing 2 5 Morbob 00 94 TR. Track Ind. Track Ind. Track Track Ind. Track | Yote Bros MI J D Graham | Notes Chip of 020186 Bros. MI Lom | 93478 | IĀRĒNĀ ? |
| FPO 1 21 2011 K 3'91 COLA | VL 10 5857 | 94.2004 FIDO OF FS302 | Mayybourne Pet Res et al 9 2004 Elliot Oil 93478 HBP 6309 U.S. 27279 | RES |
| SDG. So Rey Ventographic Migro Ind Control Con | F(3) 25 EOG 04) 1575 6 1 2000 1 0 2 1100050 | (Fliott Oil) (he apeake | Mewbourne Dil F w Energy R.W. 2 (E 1:0+1 Oil) Smith Ellinterin Webb | Raptor Appen |
| Osijaz Propostava Posijaz Propostava Osajase O46256 (Vales Petr) Potoni Svilege, JKMEnor 2-A A-A TriggSPRA I Trigg | EOG Res ,etal | Fed Com Mewhourne Santo Nino | | (Acacha) (7/43270) N |
| Contons Embre 300132 Value E Turkey Fed 26 ates Petr etai (Come | 25 Oreo Fed Com." | Perform Fed 122 F245 Olman 132 Olm | SUPSTITUTE TO SUPSTITUTE TO SUPSTITUTE TO SUPSTITUTE TO SUPSTITUTE | NOTICE OF S |
| Der tan Fed Store Tomber Tombe | P O-A Fed Com | (Manzana) 6 (Manzana) 100 (Man | Per of the state o | BENSON 86 W. J. |
| DINNER MEKAR Food Feed Track-Feet / 15 11 (FO | $G_*D(R)$ | 38 33 7 Selliott-Fed 1 9 Hanagan | HBD A Sortion C C Connected Williams | |
| Plans Prod Wasses 3 56 10 3 5 11 5 11 5 11 5 11 5 11 5 11 5 11 | Ind OE,C) Yesu Euer | 38 37 / Morexco 1060402' (Sunshine Roy) 30 | Simms Reesel | - O(WO) THE APPROACES TO 3500 |
| Hete 06009 18 Hete 10009 1000 1000 1000 1000 1000 1000 10 | E 1819 | Gass Standagon | W 1 Temporaty (03085) | 'Yotes Peth Top 9 33 6 7 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 |
| Treater 3624 Muco MBC 2 Delh Webo 1 180 (185) | State 150 | Startell Fed Sunshing | 1 3161 - 100 (100 100 100 100 100 100 100 100 10 | Author Design of the Control of the |
| more to CCH Server by the server before the server by a server by the se | Myco and Col 4171 | 18 24 3 Snow | Morbob Walking Of Street Street Co. 2 Perm Description of Street C | 703030 /s.m. 2 06 7013 |
| The state of the s | GC/L+SF Brodey-SF ST FING JL Myco,e+o | 7 8 18 React et al | 13665 12 P. P. P. P. P. P. P. P | MUNCU Virtea B Ree HKSC 1801 HISPERSON G-WAS WITE WCClose 10 person G-WAS 271 T09388 HKSC 10 person G-WAS 271 |
| 9 John 1 of 1 200 | 1 6.6811 18 E811 | 10 05 1 40 06 1 40 06 1 40 05 | 1 926. Stott. Heypost. 1 | 76 Cray 76 10 36 10 |
| Dominion Piana Prod (NICON) 38 12 17 324 5 | Silfina OEC. | HBP Yates Personal States | 01144 | #10 43 \$1439 \$14036 \$10 #10 43 \$1439 \$14036 \$10 #10 Blanca Co 6 1 2 2015 1 3 2015 1 5 2000 |
| Off O INI Cluses Canada Masterdard Edistra | indigit of [18] | (C Morgan, D/R O' Edga Par O' Edga Par | 43 AO Yotos otal | Flag Redfern Vites Pet (45) Ge 18 Edge Fet (15) 10 0/4 |
| | | | ے خان ہ | L |

1. GEOLOGIC NAME OF SURFACE FORMATION:

Permian

2. ESTIMATED TOPS OF IMPORTANT GEOLOGICAL MARKERS:

| Rustler | 320' |
|-----------------------------|--------|
| San Andres | 3,150' |
| 1 st Bone Spring | 7,000' |
| 2 nd Bone Spring | 7,775' |

3. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL OR GAS:

| Upper Permian Sands | 0-200' | Fresh Water |
|-----------------------------|--------|-------------|
| Grayburg/ San Andres | 3,150' | Oil |
| 1 st Bone Spring | 7,000' | Oil |
| 2 nd Bone Spring | 7,775' | Oil |

No other Formations are expected to give up oil, gas or fresh water in measurable quantities. Surface fresh water sands will be protected by setting 11.75" casing at 350' and circulating cement back to surface.

4. CASING PROGRAM-NEW

| | | | | | | Collapse | <u>Burst</u> | Tension |
|-----------------|-----------------|--------|-----|------|------|---------------|---------------|----------------|
| | | | | | | <u>Design</u> | <u>Design</u> | <u>Design</u> |
| | <u>Interval</u> | | | | | | | |
| 1 4.750" | 0-350' | 11.75" | 42# | H-40 | ST&C | 6.36 | 1.96 | 6.32 |
| 11.00" | 0-3,300' | 8.625" | 32# | J-55 | LT&C | 1.70 | 1.94 | 4.01 |
| 7.875" | 0-12,492' | 5.5" | 17# | N-80 | LT&C | 1.52 | 1.09 | 2.25 |

Cementing Program:

11.75" Surface Casing:

Cement to surface, 500 sx Premium Plus C + 0.005 pps Static Free + 2% CaCl2 + 0.25 pps CelloFlake + 0.005 gps FP-6L, 14.8 ppg, 1.35 yield

8.625" Intermediate Casing: Cement to surface, Lead: 555 sx 50:50 Poz C + 0.005

pps Static Free + 5% NaCl + 0.25 pps CelloFlake + 5 pps LCM-1 + 0.005 gps FP-6L + 10% Bentonite, 11.8

ppg, 2.45 yield

Tail: 200 sx Prem Plus C + 0.25 pps CelloFlake + 0.005 FP-6L + 1% CaCl₂, 14.8 ppg, 1.34 yield

5.50" Production Casing: Cement to 2,700', Lead: 750 sx 50:50 Poz C + 0.005

pps Static Free + 5% NaCl + 0.25 pps CelloFlake + 5

1.

pps LCM-1 + 0.005 gps FP-6L + 10% Bentonite, 11.8 ppg, 2.29 yield
Tail: 750 sx 50:50 Poz H + 2% Bentonite + 0.005 gps FP-6L + 0.005 pps Static Free + 5% NaCl + 0.1% R-3 + 0.2% CD-32 + 0.3% FL-52A, 14.2 ppg, 1.30 yield

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

(SEE EXHIBIT #1)

The blowout preventer equipment (BOP) shown in Exhibit #1 will consist of a double ram-type (5000 psi WP) preventer and an annular preventer (5000-psi WP). Units will be hydraulically operated and the ram-type will be equipped with blind rams on bottom and drill pipe rams on top. All BOP's and accessory equipment will be tested in accordance with Onshore Oil & Gas order No. 2. for a 2M system prior to drilling out of the surface casing shoe and while drilling the intermediate section. Before drilling out of the intermediate casing, the ram- type BOP and accessory equipment will be tested to 5000/ 250 psig and the annulur preventer to 3500/ 250 psig.

Pipe rams will be operationally checked each 24-hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets.

Hydraulically operated choke will not be installed prior to the setting and cementing of the intermediate casing string, but will be installed prior to drilling out of the intermediate casing shoe.

6. TYPES AND CHARACTERISTICS OF THE PROPOSED MUD SYSTEM:

The well will be drilled to TD with a combination of brine, cut brine, and polymer mud system. The applicable depths and properties of this system are as follows:

| | • | • • • | | • | |
|----|------------------------|-------------------|--------------|--------------|-------------|
| | | | Wt | Viscosity | Waterloss |
| | <u>Depth</u> | Type | <u>(PPG)</u> | <u>(sec)</u> | <u>(cc)</u> |
| -1 | 10-350° 350°-3,300° | Fresh – Gel | 8.6-8.8 | 28-34 | N/c |
| | 350'-3,300' | Brine | 10.0-10.2 | 28-34 | N/c |
| | 3,300'-7,000' | Fresh water | 8.4-8.6 | 28-34 | N/c |
| | 7,000'-7,500' | Cut Brine | 8.8-9.6 | 28-34 | N/c |
| | 7,500'-8,200' | Cut Brine | 8.8-9.6 | 28-34 | 10-15 |
| | 7,593'-12,492' | Polymer (Lateral) | 8.8-9.6 | 40-45 | 10-25 |
| | | | | | |

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept at the wellsite at all times.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

- (A) A kelly cock will be kept in the drill string at all times.
- (B) A full opening drill pipe-stabbing valve (inside BOP) with proper drill pipe connections will be on the rig floor at all times.

8. LOGGING, TESTING AND CORING PROGRAM:

Electric logging will consist of GR-Dual Laterlog and GR-Compensated Density-Neutron from TD to surface casing with a GR- Compensated Neutron run from surface casing to surface and a borehole sonic and HRLA from TD to surface.

Electric logging will consist of GR-Dual Laterlog and GR-Compensated Density-Neutron from TD to intermediate casing with a GR- Compensated Neutron run from intermediate casing to surface and a borehole sonic from TD to intermediate casing.

Possible sidewall cores based on shows. Possible FMI.

9. ABNORMAL CONDITIONS, PRESSURES, TEMPERATURES AND POTENTIAL HAZARDS:

The estimated bottom hole temperature (BHT) at TD is 165 degrees F with an estimated maximum bottom-hole pressure (BHP) at TD of 3500 psig. No hydrogen sulfide or other hazardous gases or fluids have been encountered, reported or are known to exist at this depth in this area. No major loss circulation zones have been reported in offsetting wells.

10. ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:

The drilling operation should be finished in approximately one month. If the well is productive, an additional 30-60 days will be required for completion and testing before a decision is made to install permanent facilities.

Permit Information:

Well Name: Sand Tank 18 Fed Com #4H

Location:

SL 1880' FSL & 2310' FEL, Section 18, T-18-S, R-30-E, Eddy Co., N.M.

BHL 1980' FSL & 2310' FWL, Section 17, T-18-S, R-30-E, Eddy Co., N.M.

Casing Program:

| Casing | Setting Depth | Hole Size | Casing Size | Casing Weight | Casing Grade | Desired TOC |
|--------------|------------------|--------------|----------------|------------------|-----------------|----------------|
| Surface | 350' | 14-3/4" | 11-3/4" | 42# | H-40 | Surface |
| Intermediate | 3,300' | 11" | 8-5/8" | 32# | J-55 | Surface |
| Production | 12,492' | 7-7/8" | 5 1/2" | 17# | N-80 | -Surface- |

2700

Cement Program:

| Depth | No. | Slurries: |
|---------|-------|---|
| | Sacks | |
| 350' | 500 | Premium Plus C + 0.005 pps Static Free + 2% CaCl2 + 0.25 pps CelloFlake + 0.005 gps FP-6L |
| 3,300' | 555 | Lead: 50:50 Poz C + 0.005 pps Static Free + 5% NaCl + 0.25 pps CelloFlake + 5 pps LCM-1 + 0.005 gps FP-6L + 10% Bentonite |
| | 200 | Tail: Premium Plus C + 0.005 pps Static Free + 1% CaCl2 + 0.25 pps CelloFlake + 0.005 gps FP-6L |
| 12,492' | 750 | Lead: 50:50 Poz C + 0.005 pps Static Free + 5% NaCl + 0.25 pps CelloFlake + 5 pps LCM-1 + 0.005 gps FP-6L + 10% Bentonite |
| | 750 | Tail: 50:50 Poz H + 2% Bentonite + 0.005 gps FP-6L + 0.005 pps Static Free + 5% NaCl + 0.1% R-3 + 0.2% CD-32 + 0.3% FL-52A |

Mud Program:

| Trida I Togram: | | | | |
|------------------|-------------------|--------------|-----------|------------|
| Depth | Type | Weight (ppg) | Viscosity | Water Loss |
| 0 – 350' | Fresh - Gel | 8.6-8.8 | 28-34 | N/c |
| 350' – 3,300' | Brine | 10.0-10.2 | 28-34 | N/c |
| 3,300' - 7,000' | Fresh Water | 8.4 – 8.6 | 28-34 | N/c |
| 7,000' - 7,500' | Cut Brine | 8.8-9.6 | 28-34 | N/c |
| 7,500' - 8,200' | Cut Brine | 8.8-9.6 | 28-34 | 10-15 |
| 7,593' – 12,492' | Cut Brine/ | 8.8-9.6 | 40-45 | 10-25 |
| | Polymer (Lateral) | | | |

EOG Resources Inc

Planning Report

EDM Database: Company:

Midland - New Mexico Sand Tank (Bone Spring)

Project: Site: Well: Sand Tank 18 Fed Com #4H Sand Tank 18 Fed Com #4H

Sand Tank 18 Fed Com #4H Wellbore:⊩

Original Plan Design:

Local Co-ordinate Reference

TVD Reference: MD Reference:

Well Sand Tank 18 Fed Com #4H

WELL @ 3532 50ft (Original Well Elev) WELL @ 3532 50ft (Original Well Elev)

North Reference: Grid

Survey Calculation Method: Mınımum Curvature

Sand Tank (Bone Spring), Eddy County, NM

Map System: Geo Datum:

US State Plane 1927 (Exact solution)

NAD 1927 (NADCON CONUS)

New Mexico East 3001 Map Zone:

System Datum:

Mean Sea Level

Sand Tank 18 Fed Com #4H Site

Site Position:

Well

Map

Northing:

635,008 90ft

Latitude:

32° 44' 43.138 N 104° 0' 35.013 W

0 18 ?

Easting: 599,496 90ft From: Longitude: 0 00 ft **Position Uncertainty:** Slot Radius: **Grid Convergence:**

Sand Tank 18 Fed Com #4H

+N/-S **Well Position**

0.00 ft

Northing:

635,008.90 ft 599,496.90 ft

Latitude:

32° 44' 43.138 N

Position Uncertainty

0.00 ft 0.00 ft Easting: Wellhead Elevation: Longitude: **Ground Level:** 104° 0' 35.013 W 3,513.50ft

Sand Tank 18 Fed Com #4H

+E/-W

Magnetics Model Name Sample Date Declination Field Strength **IGRF2000** 12/31/2004 8 81 49,685 60.84

Original Plan Design

Audit Notes:

Version:

Phase:

PROTOTYPE

Tie On Depth:

0.00

Vertical Section: Depth From (TVD) +N/-S Direction ्र (ft) (?) 8,220.00 0.00 0.00 88 69

| Plan Sectio | ns 🖫 📗 | | | | | | Cafet vecion | | | |
|-------------------|--|----------------|---------------|---------------|---------------|--------------------|----------------|-------------------|---------|-----------------|
| Measured | Section of the property of the control of the contr | | Vertical - | | | Dogleg | Build' | Turn | | |
| ⊒ Depth ≿ (ft) | inclination (?) | Azimuth (?) | Depth (ft) | +N/-S (ft) | +E/-W (ft) | Rate: (?/100ft) | Rate (?/100ft) | Rate (?/100ft) | TFO (?) | Target |
| SEEKAR! | | | | | | | eavena | | | |
| 0.0 | | | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 7,593.0 | 0.00 | 0.00 | 7,593.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 8,333.7 | '5 88.00 | 88 70 | 8,075.00 | 10.56 | 465.34 | 11.88 | 11.88 | 0.00 | 88.70 | |
| 8,333 9 | 7 88.00 | 88.69 | 8,075 01 | 10 57 | 465.56 | 3 00 | 0.68 | -2 92 | -76.98 | |
| 12,491.5 | 60 88 00 | 88.69 | 8,220.00 | 105.30 | 4,619.48 | 0 00 | 0 00 | 0.00 | 0.00 | |
| 12,491 6 | 3 88.00 | 88.69 | 8,220 00 | 105.30 | 4,619.61 | 3.00 | -1.15 | -2.77 | -112.63 | BHL (ST 18 #4H) |

EOG Resources Inc

Planning Report

Database:

Design:

EDM

Database
Company:
Project:
Site
Sand Tank (Bo
Sand Tank 18
Well:
Wellbore:
Design:
Sand Tank 18
Original Plan Midland - New Mexico Sand Tank (Bone Spring) Sand Tank 18 Fed Com.#4H Sand Tank 18 Fed Com #4H Sand Tank 18 Fed Com #4H Original Plan

| Local Co-ordinate Reference | Well Sand Tank 18 Fed Com #4H |
| TVD Reference | WELL @ 3532.50ft (Original Well Elev) |
| MD Reference | WELL @ 3532.50ft (Original Well Elev) |
| North Reference | Grid |
| Survey Calculation Method | Minimum Curvature

THE CONTROL OF THE CO

| | | ev.* | |
|--|--|------|--|
| | | | |
| | | | |
| | | | |

| | | entarpotesta. | | deting leekenings | accompleanments. | and the state of t | | all the second s | hat he will be the state of the |
|---|---------------------------------------|----------------------|-------------------------------------|--|---|--|---|--|--|
| Planned Survey *** | ACTIVITIES TO MAKE | enter annier meeter. | المراجع والمنافعة المنافعة المنافعة | attentile makiki jeng saidi Tani San | | <u>a erángun millera</u> ni | | a la la partir de la partir del | and sometiments on the Water to |
| Planned Survey | e negrative true t | ero. Issaelena e | PAR SHEEKERSHING KA | no retrinore causas | ir markatika k | | rranerisi matura | ou mai ir maio co | |
| | 多种的 的表现 | 1.445 | | | Transay. | | | | |
| Measured | | | Vertical | | V | ertical 🖖 🔆 | Dogleg | Build | Turn |
| THE THE THE COURT OF THE PARTY | | | Depth | A NUCOS STATE | | W W. In & 2+4778 TO 71230110 | Rate | Rate | Rate |
| Depth : Inc | The Tall of the State of the State of | imuth | Mr. The Strain Strain | 展"如你·如果"一种"是"的一个概念 | 2702 Opt (1) (1) 11 12 12 12 12 12 12 12 12 12 12 12 12 | Land Committee C | The second section in the second section in | STATE OF THE PARTY | The was been a little of the second |
| (ft) | ·(?);(**±*; | (2) | (ft) | (ft) | (ft) | √(ft);- (| ?/100ft), 📜 (' | ?/100ft) | (?/100ft)# |
| | AND ALL PLANT OF MICH. | | | ACCOMPANIES DE COMPANIES DE COM | | | | 0.00 | |
| 0 00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 100 00 | 0.00 | 0.00 | 100 00 | 0.00 | 0 00 | 0 00 | 0 00 | 0.00 | 0 00 |
| 200 00 | 0.00 | 0 00 | 200.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 300.00 | 0.00 | 0 00 | 300 00 | 0 00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 400 00 | 0.00 | 0 00 | 400 00 | 0 00 | 0.00 | 0 00 | 0.00 | 0.00 | 0 00 |
| | | | | | | | | | |
| 500 00 | 0 00 | 0.00 | 500 00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 600 00 | 0 00 | 0.00 | 600.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 700.00 | 0 00 | 0 00 | 700.00 | 0 00 | 0.00 | 0 00 | 0.00 | 0 00 | 0 00 |
| 800 00 | 0.00 | 0.00 | 800 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 900.00 | 0.00 | 0.00 | 900.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0 00 | 0 00 |
| 300.00 | 0.00 | 0 00 | 300.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0 00 | 0 00 |
| 1,000.00 | 0.00 | 0 00 | 1,000.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1,100.00 | 0 00 | 0.00 | 1,100 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 1,200 00 | 0.00 | 0.00 | 1,200.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 1,300 00 | 0.00 | 0.00 | 1,300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| · · · · · · · · · · · · · · · · · · · | | | 1,300.00 | | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 1,400.00 | 0 00 | 0.00 | 1,400.00 | 0.00 | 0 00 | 0 00 | 0.00 | 0 00 | 0.00 |
| 1,500.00 | 0.00 | 0 00 | 1.500.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 1,600.00 | 0.00 | 0.00 | 1,600.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 | 0.00 |
| 1,700 00 | 0.00 | 0.00 | 1,700.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| · | | | • | | | | | | |
| 1,800.00 | 0.00 | 0.00 | 1,800 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1,900.00 | 0.00 | 0.00 | 1,900.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 | 0 00 |
| 2,000.00 | 0.00 | 0 00 | 2,000.00 | 0.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| · | | | | | | | | 0.00 | 0.00 |
| 2,100 00 | 0.00 | 0.00 | 2,100.00 | 0.00 | 0.00 | 0.00 | 0.00 | | |
| 2,200 00 | 0 00 | 0.00 | 2,200.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2,300.00 | 0.00 | 0 00 | 2,300.00 | 0 00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 2,400 00 | 0.00 | 0.00 | 2,400.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 | 0 00 |
| 2 500 00 | 0.00 | 0.00 | 0.500.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2,500.00 | 0.00 | 0.00 | 2,500.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 | |
| 2,600.00 | 0 00 | 0.00 | 2,600.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2,700.00 | 0 00 | 0 00 | 2,700.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 2,800.00 | 0.00 | 0 00 | 2,800.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 |
| 2,900.00 | 0.00 | 0.00 | 2,900.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0 00 | 0.00 |
| , | | | • | | | | | | |
| 3,000 00 | 0.00 | 0.00 | 3,000.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 3,100.00 | 0.00 | 0.00 | 3,100 00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 | 0.00 |
| 3,200.00 | 0.00 | 0 00 | 3,200.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 |
| 3,300.00 | 0.00 | 0 00 | 3,300.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 3,400.00 | 0.00 | 0.00 | 3,400 00 | 0.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| | | | • | | | | | | |
| 3,500.00 | 0 00 | 0.00 | 3,500.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 3,600 00 | 0.00 | 0 00 | 3,600.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 3,700.00 | 0.00 | 0.00 | 3,700.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 3,800.00 | 0.00 | 0.00 | 3,800.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 3.900.00 | 0.00 | 0.00 | 3,900.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| -, - | | | • | | | | | | |
| 4,000 00 | 0.00 | 0 00 | 4,000.00 | 0 00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 4,100.00 | 0.00 | 0 00 | 4,100 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 4,200 00 | 0.00 | 0.00 | 4,200 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 4,300.00 | 0.00 | 0.00 | 4,300.00 | 0 00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 4,400 00 | 0.00 | 0.00 | 4,400.00 | 0.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 |
| | | | | | | | | | |
| 4,500.00 | 0.00 | 0.00 | 4,500.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0 00 | 0.00 |
| 4,600.00 | 0.00 | 0 00 | 4,600.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 |
| 4,700.00 | 0.00 | 0 00 | 4,700.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| | 0.00 | 0.00 | 4,800 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 4,800.00 | | | | | | | | | |
| 4,900.00 | 0.00 | 0.00 | 4,900.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 |
| 5,000.00 | 0.00 | 0 00 | 5,000.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 5,100.00 | 0.00 | 0.00 | 5,000.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 5,100.00 | | | | 0 00 | 0.00 | 0.00 | | 0.00 | 0.00 |
| 5 200 00 | | | | | | | | | |
| 5,300.00 | 0.00 0.00 | 0.00 0.00 | 5,200.00 5,300.00 | 0 00 | 0.00 | 0.00 | 0 00 0 00 | 0 00 | 0.00 |

EOG Resources Inc

Planning Report

THE PROPERTY OF THE PROPERTY O

Database EDM
Company Midland - New Mexico
Project Sand Tank (Bone Spring)
Site Sand Tank 18 Fed Com #4H
Wellbore Sand Tank 18 Fed Com #4H
Original Plan

88.00

88.00

88 00

88.00

10,000.00

10,100.00

10,200 00

10,300.00

88.69

88 69

88.69

88.69

8,133.11

8,136 60

8,140.08

8,143.57

Localico-ordinate Reference TVD Reference MD Reference North Reference: Survey Calculation Man

Survey Calculation Method:

Well Sand Tank 18 Fed Com #4H WELL @ 3532.50ft (Original Well Elev) WELL @ 3532 50ft (Original Well Elev)

Grid

Minimum Curvature

| Design: Chgii | | | | | | remarn. | ne i szertenevski | ncientrinia de la composición de la co | erent jū prainti ili i |
|----------------------|--|--------------------|--|----------------------|---|----------------------|-------------------|--|------------------------------|
| Planned Survey | | NAME AND ASSESSED. | ELECTRONICAL SECTION S | | araining kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang ka Kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang kanggarang k | - | neminenterije | sustantining appari | SERVICE AND SERVICE SERVICES |
| | | | | | | | | | |
| Measured | | | Vertical | | | Vertical | Dogleg | Build * * | Turn 👾 📜 |
| | A STATE OF THE PARTY OF THE PAR | Azimuth: | Depth | , ∓N/ ^L S | +E/-W | Section | Rate | Rate | Rate |
| (ft) | (?) | (?) | (ft) | (ft) | (ft)*\ | (ft)- | (?/100ft); | (?/100ft) | /(?/100ft) |
| 5,400.00 | 0.00 | 0.00 | 5,400.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0 00 |
| 5,500 00 | 0.00 | 0 00 | 5,500 00 | 0.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0 00 |
| 5,600 00 | 0.00 | 0 00 | 5,600.00 | 0 00 , | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 5,700 00 | 0.00 | 0.00 | 5,700.00 | 0 00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 |
| 5,800.00 5,900 00 | 0 00 0 00 | 0.00 0.00 | 5,800.00 5,900 00 | 0 00 0.00 | 0.00 0.00 | 0 00 · 0 00 | 0 00 0 00 | 0.00 0 00 | 0 00 0.00 |
| • | 0.00 | 0.00 | 6,000 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 6,000 00 6,100.00 | 0.00 | 0.00 | 6,000 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 6,200.00 | 0.00 | 0.00 | 6,200 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 6,300.00 | 0.00 | 0.00 | 6,300 00 | 0.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0 00 |
| 6,400.00 | 0.00 | 0.00 | 6,400 00 | 0.00 | 0.00 | 0 00 | 0 00 | 0 00 | 0 00 |
| 6,500.00 | 0.00 | 0.00 | 6,500.00 | 0 00 | 0.00 | 0.00 | 0 00 | 0.00 | 0 00 |
| 6,600 00 | 0 00 | 0 00 | 6,600 00 | 0 00 | 0 00 | 0.00 | 0.00 | 0 00 | 0.00 |
| 6,700.00 6,800.00 | 0.00 0.00 | 0.00 0.00 | 6,700.00 6,800.00 | 0 00 0 00 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 6,900.00 | 0.00 | 0.00 | 6,900 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 7,000 00 | 0.00 | 0.00 | 7,000.00 | 0.00 | 0.00 | 0.00 | 0 00 | 0.00 | 0 00 |
| 7,100 00 | 0.00 | 0.00 | 7,100.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 7,200 00 | 0 00 | 0.00 | 7,200.00 | 0.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0 00 |
| 7,300.00 | 0.00 | 0.00 | 7,300.00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 7,400 00 | 0 00 | 0.00 | 7,400.00 | 0 00 | 0 00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 7,500 00 | 0.00 0.00 | 0.00 0 00 | 7,500.00 7,593.00 | 0 00 0 00 | 0 00 0,00 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 | 0.00 0.00 |
| 7,593 00 7,600.00 | 0 00 | 88.70 | 7,593 00 7,600 00 | 0.00 | 0.00 | 0.00 0.05 | 0.00 11 88 | 0.00 11.88 | 0.00 |
| 7,700.00 | 12.71 | 88.70 | 7,699.12 | 0.27 | 11.82 | 11.82 | 11.88 | 11.88 | 0.00 |
| 7,800.00 | 24 59 | 88 70 | 7,793.70 | 0.99 | 43.73 | 43.74 | 11.88 | 11 88 | 0.00 |
| 7,900.00 | 36 47 | 88 70 | 7,879 68 | 2.14 | 94.43 | 94.45 | 11.88 | 11 88 | 0.00 |
| 8,000 00 | 48.35 | 88.70 | 7,953 38 | 3.67 | 161 74 | 161.78 | 11.88 | 11.88 | 0.00 |
| 8,100.00 8,200.00 | 60.23 72 11 | 88.70 88.70 | 8,011 65 8,051.98 | 5.51 7.58 | 242.77 334 06 | 242.83 334.14 | 11.88 11.88 | 11.88 11.88 | 0.00 0.00 |
| 8,300 00 | 83.99 | 88.70 | 8,072.64 | 9 80 | 431.69 | 431.80 | 11.88 | 11.88 | 0.00 |
| 8,333.75 | 88.00 | 88.70 | 8,075.00 | 10 56 | 465 34 | 465 46 | 11.88 | 11.88 | 0.00 |
| 8,333.97 | 88.00 | 88.69 | 8,075.01 | 10.57 | 465 56 | 465.68 | 3 00 | 0.68 | -2.92 |
| 8,400.00 | 88.00 | 88.69 | 8,077.31 | 12 07 | 531.53 | 531 67 | 0.00 | 0.00 | 0.00 |
| 8,500.00 | 00.88 | 88.69 | 8,080 80 | 14.35 | 631 45 | 631.61 | 0.00 | 0 00 | 0.00 |
| 8,600.00 | 88.00 | 88.69 | 8,084.29 | 16.63 | 731.36 | 731.55 | 0.00 | 0.00 | 0 00 |
| 8,700.00 8,800.00 | 88.00 88.00 | 88.69 88.69 | 8,087.77 8,091.26 | 18.91 21.18 | 831 27 931.19 | 831.49 931.43 | 0.00 0.00 | 0.00 0.00 | 0 00 0.00 |
| 8,800 00 8,900.00 | 88.00 | 88.69 | 8,091.26 8,094.75 | 23.46 | 1,031.19 | 1,031.37 | 0.00 | 0.00 | 0.00 |
| 9,000.00 | 88 00 | 88.69 | 8,098.23 | 25.74 | 1,131 01 | 1,131.31 | 0.00 | 0 00 | 0 00 |
| 9,100.00 | 88 00 | 88.69 | 8,101.72 | 28.02 | 1,230.93 | 1,231.25 | 0.00 | 0.00 | 0.00 |
| 9,200.00 | 88 00 | 88.69 | 8,105 21 | 30.30 | 1,330.84 | 1,331 18 | 0 00 | 0.00 | 0.00 |
| 9,300.00 | 88.00 | 88 69 | 8,108 70 | 32.58 | 1,430.75 | 1,431.12 | 0 00 | 0.00 | 0.00 |
| 9,400.00 9,500.00 | 88.00 88.00 | 88.69 | 8,112.18 8 115.67 | 34 86 37 13 | 1,530 67 | 1,531 06 | 0.00 | 0.00 | 0.00 0.00 |
| 9,600.00 | 88 00 | 88 69 88.69 | 8,115.67 8,119.16 | 37.13 39.41 | 1,630.58 1,730.49 | 1,631.00 1,730.94 | 0.00 0.00 | 0.00 0 00 | 0.00 |
| • | 88.00 | | | | | | | | 0.00 |
| 9,700.00 9,800.00 | 88.00 | 88.69 88.69 | 8,122.65 8,126.13 | 41.69 43.97 | 1,830 41 1,930.32 | 1,830.88 1,930.82 | 0.00 0.00 | 0 00 0 00 | 0.00 |
| 9,900.00 | 88 00 | 88.69 | 8,129.62 | 46.25 | 2,030.32 | 2,030.76 | 0.00 | 0 00 | 0.00 |
| 10,000,00 | 88.00 | 88.69 | 8 133 11 | 48 53 | 2 130 15 | 2.130.70 | 0.00 | 0.00 | 0.00 |

48 53

50 81

53.08

55.36

2,130.15

2,230.06

2,329.97

2,429.89

2,130.70

2,230 64

2,330 58

2,430.52

0.00

0.00

0.00

0.00

0.00

0.00

0 00

0.00

0.00

0.00

0 00

0.00

EOG Resources Inc.

Planning Report

Database EDM
Company Midland - New
Project Sand Tank (B Site Sand Tank 18
Well: Sand Tank 18
Wellibore: Sand Tank 18
Original Plan Midland - New Mexico Sand Tank (Bone Spring)

Sand Tank 18 Fed Com #4H Sand Tank 18 Fed Com #4H Sand Tank 18 Fed Com #4H

Eocal Co-ordinate Reference: TVD)Reference: MD:Reference:

North Reference: Survey Calculation Method:

Well Sand Tank 18 Fed Com #4H

WELL @ 3532 50ft (Original Well Elev) WELL @ 3532.50ft (Original Well Elev)


Grid .

Minimum Curvature

| 1. 10. 25. 高点的是实现。 (1. 1. 2. 2. 2. 4. 4. 2. 2. 4. 4. 2. 2. 4. 4. 2. 2. 4. 4. 4. 2. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. 4. | 200 V 7 7 W 3. 2 12 1 46 1 | zimuth. | Vërtical Depth | +N/-S | #E/= W | Vertical Section | Rate : | Build Rate | Rate |
|---|----------------------------|---------|-------------------|--------|---------------|---------------------|-------------|---------------|-----------|
| (ft). | (?) | (?) | (ft) | (ft) | (ft) | シ。 (ft) デキサム | (?/100ft) (| ?/100ft) | (?/100ft) |
| 10.400.00 | 88 00 | 88.69 | 8,147.06 | 57.64 | 2,529 80 | 2,530.46 | 0.00 | 0 00 | 0.00 |
| 10.500 00 | 88 00 | 88.69 | 8,150.54 | 59.92 | 2,629.71 | 2,630.39 | 0.00 | 0 00 | 0.00 |
| 10,600 00 | 88 00 | 88.69 | 8,154 03 | 62.20 | 2,729 62 | 2,730 33 | 0.00 | 0.00 | 0 00 |
| 10,700 00 | 88 00 | 88.69 | 8,157.52 | 64.48 | 2,829 54 | 2,830.27 | 0.00 | 0 00 | 0.00 |
| 10,800.00 | 88 00 | 88.69 | 8,161.01 | 66.76 | 2,929 45 | 2,930.21 | 0 00 | 0 00 | 0 00 |
| 10,900 00 | 88 00 | 88.69 | 8,164.49 | 69.03 | 3,029.36 | 3,030.15 | 0 00 | 0 00 | 0 00 |
| 11,000.00 | 88.00 | 88.69 | 8,167 98 | 71.31 | 3,129.28 | 3,130.09 | 0.00 | 0.00 | 0 00 |
| 11,100.00 | 88 00 | 88 69 | 8,171.47 | 73.59 | 3,229.19 | 3,230.03 | 0.00 | 0 00 | 0.00 |
| 11,200.00 | 88 00 | 88.69 | 8,174 96 | 75 87 | 3,329 10 | 3,329 97 | 0.00 | 0.00 | 0.00 |
| 11,300.00 | 88.00 | 88.69 | 8,178.44 | 78.15 | 3,429 02 | 3,429.91 | 0.00 | 0.00 | 0 00 |
| 11,400.00 | 88.00 | 88.69 | 8,181 93 | 80.43 | 3,528.93 | 3,529.85 | 0.00 | 0 00 | 0.00 |
| 11,500.00 | 88.00 | 88 69 | 8,185.42 | 82.71 | 3,628 84 | 3,629.79 | 0.00 | 0 00 | 0.00 |
| 11,600.00 | 88.00 | 88.69 | 8,188.91 | 84.98 | 3,728 76 | 3,729.73 | 0 00 | 0.00 | 0 00 |
| 11,700 00 | 88 00 | 88.69 | 8,192.39 | 87.26 | 3,828.67 | 3,829.66 | 0.00 | 0 00 | 0 00 |
| 11,800.00 | 88 00 | 88.69 | 8,195.88 | 89.54 | 3,928.58 | 3,929.60 | 0.00 | 0.00 | 0 00 |
| 11,900 00 | 88.00 | 88.69 | 8,199 37 | 91.82 | 4,028.50 | 4,029.54 | 0.00 | 0.00 | 0.00 |
| 12,000.00 | 88.00 | 88.69 | 8,202 86 | 94.10 | 4,128 41 | 4,129 48 | 0.00 | 0.00 | 0.00 |
| 12,100.00 | 88 00 | 88.69 | 8,206.34 | 96 38 | 4,228.32 | 4,229.42 | 0 00 | 0.00 | 0 00 |
| 12,200 00 | 88.00 | 88.69 | 8,209.83 | 98.66 | 4,328.24 | 4,329.36 | 0.00 | 0.00 | 0.00 |
| 12,300 00 | 88 00 | 88.69 | 8,213.32 | 100.93 | 4,428.15 | 4,429.30 | 0.00 | 0.00 | 0.00 |
| 12,400.00 | 88.00 | 88.69 | 8,216 80 | 103 21 | 4,528.06 | 4,529 24 | 0 00 | 0.00 | 0 00 |
| 12,491.50 | 88.00 | 88.69 | 8,220 00 | 105.30 | 4,619 48 | 4,620.68 | 0.00 | 0.00 | 0.00 |
| 12,491.63 | 88 00 | 88 69 | 8,220.00 | 105.30 | 4,619 61 | 4,620 81 | 3 00 | -1 15 | -2.77 |
| BHL (ST 18 #4 | IH) | | | | | | | . : | • |

| THE ST SAME OFF AS IN THE PER TWO DESIGNATION THAT | | Market Ash | many water an expense property age | ب كار | early sales above to a secretary species who | AND A SHIRLING STREET, | wife will the rest of the property of the same | Lincon International Control of | وينجان والمناورة والمناورة والمناورة | las, tecentricalizationalisticas, papita estatituido est | Seminary and Seminary |
|--|--|--|------------------------------------|---|--|--|--|---|--|--|--|
| Targets | 4 | | | , | | | , | ` , | | | 3 |
| Talyets | | | | | | | | | | minter confidence and an an | There are no server |
| 10 10 10 10 10 10 10 10 10 10 10 10 10 1 | | THE STATE OF THE S | | | | | | and the second | | active services | A STATE OF THE STA |
| THE RESERVE OF THE PARTY OF THE | THE STATE OF THE S | 100 | | ALCOHOL: WATER TO THE | | and the second of the second | | 的有权为2000年1000年1000年1000年 | 11 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 以,用数据的特别的 | CTA ALM I |
| THE COURSE OF THE PROPERTY OF THE PARTY OF T | | 304 775 | | Application of the second second | | | 中国工程,这种工程,不是一种工程的 | Short of the state of | COLUMN TO THE REAL PROPERTY. | | 2.50 |
| Target Name | | | | | "我们就是这个的," | WATER WATER TO A COLUMN | | CONTRACTOR OF THE PARTY OF THE | A VISSAL WALL | THE RESERVE OF THE PARTY OF THE | 10 P. C. C. |
| The state of the s | 10 A 10 P 20 P 10 P 10 P 10 P 10 P 10 P 10 P | R 2000 E | The company of the same | THE PERSON NAMED IN | 。""···································· | | AND THE RESERVE THE THE | Commence of the second | Maria Artista | | A 10 10 10 10 10 10 10 10 10 10 10 10 10 |
| - hit/miss target Dip A | nale. Din | Dir | | +N/-S+X- | *+F/-W | Northing | Easting | 2 3 2 2 2 X | X Drive Market Sec. | CARLETT NO. 12 YEAR | A State of |
| The Marine of the Control of the Con | 20 S 10 S | 14. | | Secure of the second | Street And Street Printers | Service Co. Service Service | New March 1988 Co. L. C. | THE STATE OF THE | AGE OF CA | | AND |
| Shape | 30 A T A T A T A T A T A T A T A T A T A | 113000 | (ft) | (ft). | 267/44\2 ft 2013 | 600 7 301641 | (ft) | The second second second | and the second | AN A TAN BE TO LE | では、大学の |
| E STOLIANE SELECTION OF STATE | 1. 建建筑、建建设、1 | 100000 | 公路(IL)后来第二条 | 那些(IL)多多数使品数 | は後しいたの機構 | 被决定的[[[]] | 35.00 (15/4) W. W. S. S. S. S. | Latitu | de | Lonaituc | PACE AND A |
| The state of the s | | A PARTY | A STATE OF THE SECOND | and the second | | | The state of the s | the fire man comment | and the same | Brail warmen - market | |
| 30, | | | | | | | | | | | ľ |
| THE COT 40 ((41)) | 0.00 | 0.00 | 0.000.00 | 405.00 | 4 040 04 | 005 444 00 | 004 440 50 | 000 441 4 | 4 007 N | 4000 501 40 4 | 141 000 |
| BHL (ST 18 #4H) | 0.00 | 0.00 | 8.220.00 | 105.30 | 4.619 61 | 635,114,20 | 604,116.50 | 32 44 4 | 4.037 N | 103° 59' 40.9 | 320 VV |
| | | | -, | | -,- | , | | | | | |
| plan hits target center | | | | | | | | | | | Y |
| | | | | | | | | | | | |
| - Point | | | | | | | | | | | |
| - I Olin | | | | | | | | | | | - 1 |
| | | | | | | | | | | | |


| • | +N/-S 0.00 | +E/- 0. | -W 00 | North 635008 | ing | ound Level: Easting 599496.90 | : 3513 La 32° 44' 43 | atittude | Lon 104° 0' 35.0 | gitude)13 W | Slo | 01 |
|-------|---|-------------------------|---|---|--|---|---|--|---------------------|---|-----|---------------------------------------|
| | | | | | | SECTION | DETAILS | | | | | |
| | Sec 1 2 759 3 833 4 833 51249 61249 | 33.75 33.97 91.50 | Inc 0.00 0.00 88.00 88.00 88.00 88.00 | Azi 0.00 0.00 88.70 88.69 88.69 88.69 | TVD 0.00 7593.00 8075.00 8075.01 8220.00 8220.00 | +N/-S 0.00 0.00 10.56 10.57 105.30 105.30 | +E/-W 0.00 0.00 465.34 465.56 4619.48 4619.61 | DLeg 0.00 0.00 11.88 3.00 0.00 3. B 0 L | 88.70 -76.98 | 0.00 0.00 465.46 465.68 4620.68 | | |
| 0- | 1 | ı | , , | | | s 4 | | T out many | 1 | | | |
| 750 | | ! | 9 | | | | 4500 | Section dates a section of the secti | | | | |
| 1500 | | ; | | | | | 3750 | | 1 | , | | 1 |
| 3000 | | | | | t. | 1 . | 3000 — | | 1 | ! | , | |
| 3750 | - | | | | | | 1500 | 5 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | | ; | 1 | ; ; 1 |
| 4500 | | | 1 5 1 1 1 1 1 | | • | | (1500 ft/in) | | | | | |
| 5250 | | | ; | | | | South(-)/North(+) | | | | | |
| 6000 | in the second second | ţ | 1 | | • | | South -420 | | | 1 | | |
| 6750 | : | , | 1 | | | | -1500 — - - | 1 1 1 1 | i | , | | |
| 7500 | | , | ! | | | | -2250 | 1 | | , | • | |
| 8250 | | | 1 | | , | | -3000 | | : | 1 | | |
| 9000- | - | | , | | | | -3750 | 1 4 | | e e | | |
| 9750 | i | | ; | | | | -4500 - - - | : | | | | , , , , , , , , , , , , , , , , , , , |



WELL NAME: Sand Tax 18 Fed Com 4H

CLOSED LOOP EQUIPMENT

Closed Loop EQUIPMENT



11 70 1 1 2 1 1. Separator 1 1 2. Heater

3. 0:1 TLK


4. Water Tank

"NOT TO SCALE"

E

ATTACHMENT TO EXHIBIT #1

- 1. Wear ring to be properly installed in head.
- 2. Blow out preventer and all fittings must be in good condition, 5000 psi W.P. minimum. Exhibit #1.
- 3. All fittings to be flanged
- 4. Safety valve must be available on rig floor at all times with proper connections, valve to be full bore 5000 psi W.P. minimum.
- 5. All choke and fill lines to be securely anchored especially ends of choke lines.
- 6. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
- 7. Kelly cock on kelly.
- 8. Extension wrenches and hand wheels to be properly installed.
- 9. Blow out preventer control to be located as close to driller's position as feasible.
- 10. Blow out preventer closing equipment to include minimum 40-gallon accumulator, two independent sources of pump power on each closing unit installation, and meet all API specifications.




5M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

Although not required for any of the choke manifold systems, buffer tanks are sometimes installed downstream of the choke assemblies for the purpose of manifolding the bleed lines together. When buffer tanks are employed, valves shall be installed upstream to isolate a failure or malfunction without interrupting flow control. Though not shown on 2M, 3M, 10M, OR 15M drawings, it would also be applicable to those situations.

[54 FR 39528, Sept. 27, 1989]

EOG Resources, Inc.

Sand Tank 18 Fed Com 4H




EOG Resources, Inc.

Legals:
Sand Tank 18 Fed Com #4H
1880' FSL & 2310' FEL
Section 18
T-18-S, R-30-E
Eddy Co. New Mexico

H₂S

"Contingency Plan"





Safety Solutions, LLC 3222 Commercial Dr. Midland, TX 79701 (432) 686-8555 CAPLISAD FIELD OFFICE

2008 JUL 29 PM 3: 00

Table of Contents

I. H₂S Contingency Plan

- a. Scope
- b. Objective
- c. Discussion of Plan

II. Emergency Procedures

- a. Emergency Procedures
- b. Emergency Reaction Steps
- c. Simulated Blowout Control Drills

III. Ignition Procedures

- a. Responsibility
- b. Instructions
- IV. Training Requirements
- V. Emergency Equipment
- **VI. Check Lists**
 - a. Status Check List
 - b. Procedural Check List

VII. Briefing Procedures

VIII. Evacuation Plan

- a. General Plan
- b. Emergency Phone Lists

IX. Maps and Plats

- a. Location Plat
- b. Map to Location
- c. Radius of Exposure

X. General Information

- a. Drilling/Re-entry Permits
- b. H-9 Permit
- c. H₂S Permissible Limits
- d. Toxicity Table
- e. Physical Properties
- f. Respirator Use
- g. Emergency Rescue

H₂S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release, or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H₂S).

Objective:

Prevent any and all accidents, and prevent the uncontrolled release of H₂S into the atmosphere.

Provide proper evacuation procedures to cope with emergencies.

Provide immediate and adequate medical attention should an injury occur.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 1000' before drilling into the first sour zone. **Emergency Response Procedure:** This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 1000' before drilling into the first sour zone.

Emergency call list: Included are the telephone numbers of all persons that would need to be contacted, should an H₂S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

Check Lists: Status check lists and procedural check lists have been included to ensure adherence to the plan.

General Information: A general information section has been included to supply support information.

EMERGENCY PROCEDURES SECTION

- I. In the event of any evidence of H₂S level above 10ppm, take the following steps immediately:
 - a. Secure breathing apparatus.
 - b. Order non-essential personnel out of the danger zone.
 - c. Take steps to determine if the H₂S level can be corrected or suppressed, and if so, proceed with normal operations.
- II. If uncontrollable conditions occur, proceed with the following:
 - a. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel and the New Mexico Oil Conservation Division of the situation.
 - b. Remove all personnel to the Safe Briefing Area.
 - c. Notify public safety personnel for help with maintaining roadblocks and implementing evacuation.
 - d. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.

III. Responsibility:

- a. The Company Approved Supervisor shall be responsible for the total implementation of the plan.
- b. The Company Approved Supervisor shall be in complete command during any emergency.
- c. The Company Approved Supervisor shall designate a back up Supervisor in the event that he/she is not available.

EMERGENCY PROCEDURE IMPLEMENTATION

I. Drilling or Tripping

a. All Personnel

- i. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
- ii. Check status of other personnel (buddy system).
- iii. Secure breathing apparatus.
- iv. Wait for orders from supervisor.

b. Drilling Foreman

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

c. Tool Pusher

- i. Report to the upwind Safe Briefing Area.
- ii. Don Breathing Apparatus and return to the point of release with the Drilling Foreman or the Driller (buddy system).
- iii. Determine the concentration of H₂S.
- iv. Assess the situation and take appropriate control measures.

d. Driller

- i. Check the status of other personnel (in a rescue attempt, always use the buddy system).
- ii. Assign the least essential person to notify the Drilling Foreman and Tool Pusher, in the event of their absence.
- **iii.** Assume the responsibility of the Drilling Foreman and the Tool Pusher until they arrive, in the event of their absence.

e. Derrick Man and Floor Hands

i. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

f. Mud Engineer

- i. Report to the upwind Safe Briefing Area.
- ii. When instructed, begin check of mud for pH level and H₂S level.

g. Safety Personnel

- i. Don Breathing Apparatus.
- ii. Check status of personnel.
- iii. Wait for instructions from Drilling Foreman or Tool Pusher.

II. Taking a Kick

- a. All Personnel report to the upwind Safe Briefing Area.
- b. Follow standard BOP procedures.

III. Open Hole Logging

- **a.** All unnecessary personnel should leave the rig floor.
- **b.** Drilling Foreman and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

- a. Follow "Drilling or Tripping" procedures.
- b. Assure that all personnel have access to protective equipment.

SIMULATED BLOWOUT CONTROL DRILLS

All drills will be initiated by activating alarm devices (air horn). One long blast, on the air horn, for ACTUAL and SIMULATED Blowout Control Drills. This operation will be performed by the Drilling Foreman or Tool Pusher at least one time per week for each of the following conditions, with each crew:

Drill #1 Bottom Drilling
Drill #2 Tripping Drill Pipe

In each of these drills, the initial reaction time to shutting in the well shall be timed as well as the total time for the crew to complete its entire pit drill assignment. The times must be recorded on the IADC Driller's Log as "Blowout Control Drill".

Drill No .:

Reaction Time to Shut-In: minutes, seconds.

Total Time to Complete Assignment: minutes, seconds.

I. Drill Overviews

- a. Drill No. 1 Bottom Drilling
 - i. Sound the alarm immediately.
 - ii. Stop the rotary and hoist Kelly joint above the rotary table.
 - iii. Stop the circulatory pump.
 - iv. Close the drill pipe rams.
 - v. Record casing and drill pipe shut-in pressures and pit volume increases.
- b. Drill No. 2 Tripping Drill Pipe
 - i. Sound the alarm immediately.
 - ii. Position the upper tool joint just above the rotary table and set the slips.
 - iii. Install a full opening valve or inside blowout preventer tool in order to close the drill pipe.
 - iv. Close the drill pipe rams.
 - v. Record the shut-in annular pressure.

II. Crew Assignments

a. Drill No. 1 - Bottom Drilling

i. Driller

- 1. Stop the rotary and hoist Kelly joint above the rotary table.
- 2. Stop the circulatory pump.
- 3. Check Flow.
- 4. If flowing, sound the alarm immediately
- 5. Record the shit-in drill pipe pressure
- 6. Determine the mud weight increase needed or other courses of action.

ii. Derrickman

- Open choke line valve at BOP.
- 2. Signal Floor Man #1 at accumulator that choke line is open.
- 3. Close choke and upstream valve after pipe tam have been closed.
- 4. Read the shut-in annular pressure and report readings to Driller.

iii. Floor Man #1

- 1. Close the pipe rams after receiving the signal from the Derrickman.
- 2. Report to Driller for further instructions.

iv. Floor Man #2

- 1. Notify the Tool Pusher and Operator representative of the H₂S alarms.
- 2. Check for open fires and, if safe to do so, extinguish them.
- 3. Stop all welding operations.
- 4. Turn-off all non-explosions proof lights and instruments.
- 5. Report to Driller for further instructions.

v. Tool Pusher

- 1. Report to the rig floor.
- 2. Have a meeting with all crews.
- 3. Compile and summarize all information.
- 4. Calculate the proper kill weight.
- 5. Ensure that proper well procedures are put into action.

vi. Operator Representative

- 1. Notify the Drilling Superintendent.
- 2. Determine if an emergency exists and if so, activate the contingency plan.

b. Drill No. 2 - Tripping Pipe

i. Driller

- 1. Sound the alarm immediately when mud volume increase has been detected.
- 2. Position the upper tool joint just above the rotary table and set slips.
- 3. Install a full opening valve or inside blowout preventer tool to close the drill pipe.
- 4. Check flow.
- 5. Record all data reported by the crew.
- 6. Determine the course of action.

ii. Derrickman

- 1. Come down out of derrick.
- 2. Notify Tool Pusher and Operator Representative.
- 3. Check for open fires and, if safe to do so, extinguish them.
- 4. Stop all welding operations.
- 5. Report to Driller for further instructions.

iii. Floor Man #1

- 1. Pick up full opening valve or inside blowout preventer tool and stab into tool joint above rotary table (with Floor Man #2).
- 2. Tighten valve with back-up tongs.
- 3. Close pipe rams after signal from Floor Man #2.
- 4. Read accumulator pressure and check for possible high pressure fluid leaks in valves or piping.
- 5. Report to Driller for further instructions.

iv. Floor Man #2

- 1. Pick-up full opening valve or inside blowout preventer tool and stab into tool joint above rotary table (with Floor Man #1).
- 2. Position back-up tongs on drill pipe.
- 3. Open choke line valve at BOP.
- 4. Signal Floor Man #1 at accumulator that choke line is open.
- 5. Close choke and upstream valve after pipe rams have been closed.
- 6. Check for leaks on BOP stack and choke manifold.
- 7. Read annular pressure.
- 8. Report readings to the Driller.

v. Tool Pusher

- 1. Report to the rig floor.
- 2. Have a meeting with all of the crews.
- 3. Compile and summarize all information.
- 4. See that proper well kill procedures are put into action.

vi. Operator Representative

- 1. Notify Drilling Superintendent
 - 2. Determine if an emergency exists, and if so, activate the contingency plan.

IGNITION PROCEDURES

Responsibility:

The decision to ignite the well is the responsibility of the DRILLING FOREMAN in concurrence with the STATE POLICE. In the event the Drilling Foreman is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

- 1. Human life and property are endangered.
- 2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

- 1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Foreman is responsible for igniting the well.
- 2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.
- 3. Ignite from upwind and do not approach any closer than is warranted.
- 4. Select the ignition site best suited for protection and which offers an easy escape route.
- 5. Before igniting, check for the presence of combustible gases.
- 6. After igniting, continue emergency actions and procedures as before.
- 7. All unassigned personnel will limit their actions to those directed by the Drilling Foreman.

Note: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide, which is also highly toxic. Do not assume the area is safe after the well is ignited.

TRAINING PROGRAM

When working in an area where Hydrogen Sulfide (H_2S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel, at the well site, have had adequate training in the following:

1. Hazards and characteristics of Hydrogen Sulfide.

- 2. Physicals effects of Hydrogen Sulfide on the human body.
- 3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
- 4. H₂S detection, Emergency alarm and sensor location.
- 5. Emergency rescue.
- 6. Resuscitators.
- 7. First aid and artificial resuscitation.
- 8. The effects of Hydrogen Sulfide on metals.
- 9. Location safety.

Service company personnel and visiting personnel must be notified if the zone contains H₂S, and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

EMERGENCY EQUIPMENT REQUIREMENTS

Lease Entrance Sign:

Should be located at the lease entrance with the following information:

CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the safe briefing areas and should include the following:
- Two SCBA's at each briefing area.
- Enough air line units to operate safely, anytime the H₂S concentration reaches the IDLH level (100 ppm).
- Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Windsocks or Wind Streamers:

- A minimum of two 10" windsocks located at strategic locations so that they may be seen from any point on location
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location).

Hydrogen Sulfide Detector and Alarms:

- 1 Four channel H₂S monitor with alarms.
- Four (4) sensors located as follows: #1 Rig Floor, #2 Bell Nipple, #3 Shale Shaker, #4 Mud Pits.
- Gastec or Draeger pump with tubes.
- Sensor test gas.

Well Condition Sign and Flags:

The Well Condition Sign w/flags should be placed a minimum of 150' before you enter the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions YELLOW – Potential Danger RED – Danger, H₂S Gas Present

Auxiliary Rescue Equipment:

- Stretcher
- 2 100' Rescue lines.

First Aid Kit properly stocked.

Mud Inspection Equipment:

Garret Gas Train or Hach Tester for inspection of Hydrogen Sulfide in the drilling mud system.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Blowout Preventer:

- The well shall have hydraulic BOP equipment for the anticipated BHP.
- The BOP should be tested upon installation.
- BOP, Choke Line and Kill Line will be tested as specified by Operator.

Confined Space Monitor:

There should be a portable multi-gas monitor with at least 3 sensors (O_2 , LEL H_2S). This instrument should be used to test the atmosphere of any confined space before entering. It should also be used for atmospheric testing for LEL gas before beginning any type of Hot Work. Proper calibration documentation will need to be provided.

Communication Equipment:

- Proper communication equipment such as cell phones or 2-way radios should be available at the rig.
- Radio communication shall be available for communication between the company man's trailer, rig floor and the tool pusher's trailer.
- Communication equipment shall be available on the vehicles.

Special Control Equipment:

- Hydraulic BOP equipment with remote control on the ground.
- Rotating head at the surface casing point.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:

Parking and Visitor area:

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- Designated smoking area.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds or they are at a 180 degree angle if wind directions tend to shift in the area.
- Personal protective equipment should be stored at both briefing areas or if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

Note:

- Additional equipment will be available at the Safety Solutions, LLC office.
- Additional personal H₂S monitors are available for all employees on location.
- Automatic Flare Igniters are recommended for installation on the rig.

CHECK LISTS

Note: Date each item as they are implemented.

| 1. | Sign at location entrance. | |
|-----|--|--|
| 2. | Two (2) wind socks (in required locations). | |
| 3. | Wind Streamers (if required). | |
| 4. | SCBA's on location for all rig personnel and mud loggers. | |
| 5. | Air packs, inspected and ready for use. | |
| 6. | Spare bottles for each air pack (if required). | |
| 7. | Cascade system for refilling air bottles. | |
| 8. | Cascade system and hose line hook up. | |
| 9. | Choke manifold hooked-up and tested. | |
| | (before drilling out surface casing.) | |
| 10. | Remote Hydraulic BOP control (hooked-up and tested before | |
| | drilling out surface casing). | |
| 11. | BOP tested (before drilling out surface casing). | |
| | Mud engineer on location with equipment to test mud for H ₂ S. | |
| 13. | Safe Briefing Areas set-up | |
| 14. | Well Condition sign and flags on location and ready. | |
| 15. | Hydrogen Sulfide detection system hooked -up & tested. | |
| 16. | Hydrogen Sulfide alarm system hooked-up & tested. | |
| 17. | Stretcher on location at Safe Briefing Area. | |
| 18. | 2 – 100' Life Lines on location. | |
| 19. | 1 – 20# Fire Extinguisher in safety trailer. | |
| 20. | Confined Space Monitor on location and tested. | |
| 21. | All rig crews and supervisor trained (as required). | |
| 22. | Access restricted for unauthorized personnel. | |
| 23. | Drills on H₂S and well control procedures. | |
| 24. | All outside service contractors advised of potential H ₂ S on the well. | |
| 25. | NO SMOKNG sign posted. | |
| 26. | H_2S Detector Pump w/tubes on location. | |
| 27. | 25mm Flare Gun on location w/flares. | |
| 28. | Automatic Flare Igniter installed on rig. | |
| | | |
| | | |

Procedural Check List

Perform the following on each tour:

- 1. Check fire extinguishers to see that they have the proper charge.
- 2. Check breathing equipment to insure that they have not been tampered with.
- 3. Check pressure on the supply air bottles to make sure they are capable of recharging.
- 4. Make sure all of the Hydrogen Sulfide detection systems are operative.

Perform the following each week:

- 1. Check each piece of breathing equipment to make sure that they are fully charged and operational. This requires that the air cylinder be opened and the mask assembly be put on and tested to make sure that the regulators and masks are properly working. Negative and Positive pressure should be conducted on all masks.
- 2. BOP skills.
- 3. Check supply pressure on BOP accumulator stand-by source.
- 4. Check all breathing air mask assemblies to see that straps are loosened and turned back, ready for use.
- 5. Check pressure on cascade air cylinders to make sure they are fully charged and ready to use for refill purposes if necessary.
- 6. Check all cascade system regulators to make sure they work properly.
- 7. Perform breathing drills with on-site personnel.
- 8. Check the following supplies for availability:
 - Stretcher

- Safety Belts and Ropes
- Spare air Bottles
- Spare Oxygen Bottles (if resuscitator required)
- Gas Detector Pump and Tubes
- Emergency telephone lists
- 9. Test the Confined Space Monitor to verify the batteries are good

BRIEFING PROCEDURES

DUBLIC CAESTV.

The following scheduled briefings will be held to ensure the effective drilling and operation of this project:

Pre-Spud Meeting

Date: Prior to spudding the well.

Attendance: Drilling Supervisor
Drilling Engineer
Drilling Foreman
Rig Tool Pushers
Rig Drillers
Mud Engineer

Key Service Company Personnel

All Safety Personnel

Purpose: Review and discuss the well program, step-by-step, to insure complete understanding of assignments

and responsibilities.

EVACUATION PLAN

General Plan

The direct lines of action prepared by SAFETY SOLUTIONS, LLC to protect the public from hazardous gas situations are as follows:

- 1. When the company approved supervisor (Drilling Foreman, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the area map.
- 2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists and evacuation needs to be implemented.
- 3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.
- 4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, "Company" safety personnel will determine when the area is safe for re-entry.

See Emergency Action Plan Emergency Assistance Telephone List

011 or

| PUBLIC SAFETT: | 311 01 |
|----------------------------------|----------------|
| Eddy County Sheriff's Department | (575) 887-7551 |
| Kent Waller | |
| Fire Department: | |
| Carlsbad | (575) 885-3125 |
| Artesia | (575) 746-5050 |
| Hospitals: | |

| Carlsbad | | (575) 887-4121 |
|---------------------------------|--------|----------------|
| Artesia | | (575) 748-3333 |
| Hobbs | | (575) 392-1979 |
| Dept. of Public Safety/Carlsbad | | (575) 748-9718 |
| Highway Department | | (575) 885-3281 |
| New Mexico Oil Conservation | | (575) 476-3440 |
| U.S. Dept. of Labor | | (575) 887-1174 |
| EOG Resources, Inc. | | |
| EOG / Midland | | |
| Company Drilling Consultants: | | |
| Wayne Helms | Cell | (432) 894-3416 |
| Will Henderson | | |
| Drilling Engineer | | |
| Jason La Grega | | |
| Drilling Manager | | |
| Drilling Superintendent | | |
| Ron Welch | Office | (432) 686-3695 |
| | Cell | (432) 386-0592 |
| McVay Drilling / Hobbs | Office | (575) 397-3311 |
| McVay Drilling Rig #8 | Rig | (575) 631-0794 |
| Tool Pusher: | | |
| Rick Massey | Cell | (575) 390-3313 |
| Melvin Koons | Cell | (575) 631-9225 |

MAPS AND PLATS (Maps & Plats Attached)

Affected Notification List

(within a 65' radius of exposure @100ppm)

The geologic zones that will be encountered during drilling are known to contain hazardous quantities of H_2S . The accompanying map illustrates the affected areas of the community. The residents within this radius will be notified via a hand delivered written notice describing the activities, potential hazards, conditions of evacuation, evacuation drill siren alarms and other precautionary measures.

Evacuee Description:

Residents: THERE ARE NO RESIDENTS WITHIN 3000' ROE.

Notification Process:

A continuous siren audible to all residence will be activated, signaling evacuation of previously notified and informed residents.

Evacuation Plan:

All evacuees will migrate lateral to the wind direction.

The Oil Company will identify all home bound or highly susceptible individuals and make special evacuation preparations, interfacing with the local and emergency medical service as necessary.

Toxic Effects of H₂S Poisoning

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity -1.192) and is colorless and transparent. Hydrogen Sulfide is almost as toxic as Hydrogen Cyanide and is 5-6 times more toxic than Carbon Monoxide. Occupational exposure limits for Hydrogen Sulfide and other gases are compared below in Table 1. Toxicity table for H_2S and physical effects are shown in Table 2.

Table 1
Permissible Exposure Limits of Various Gases

| Common Name | Symbol | Sp. Gravity | TLV | STEL | IDLH |
|------------------|------------------|-------------|----------|------------|---------|
| Hydrogen Cyanide | HCN | .94 | 4.7 ppm | С | |
| Hydrogen Sulfide | H ₂ S | 1.192 | 10 ppm | 15 ppm | 100 ppm |
| Sulfide Dioxide | SO ₂ | 2.21 | 2 ppm | 5 ppm | |
| Chlorine | CL | 2.45 | .5 ppm | 1 ppm | |
| Carbon Monoxide | CO | .97 | 25 ppm | 200 ppm | |
| Carbon Dioxide | CO ₂ | 1.52 | 5000 ppm | 30,000 ppm | |
| Methane | CH ₄ | .55 | 4.7% LEL | 14% UEL | |

Definitions

- A. TLV Threshold Limit Value is the concentration employees may be exposed based on a TWA (time weighted average) for eight (8) hours in one day for 40 hours in one (1) week. This is set by ACGIH (American Conference of Governmental Hygienists) and regulated by OSHA.
- B. STEL Short Term Exposure Limit is the 15 minute average concentration an employee may be exposed to providing that the highest exposure never exceeds the OEL (Occupational Exposure Limit). The OEL for H₂S is 19 PPM.
- C. IDLH Immediately Dangerous to Life and Health is the concentration that has been determined by the ACGIH to cause serious health problems or death if exposed to this level. The IDLH for H_2S is 100 PPM.
- D. TWA Time Weighted Average is the average concentration of any chemical or gas for an eight (8) hour period. This is the concentration that any employee may be exposed based on an TWA.

TABLE 2

| Percent % | PPM | Physical Effects |
|-----------|------|---|
| .0001 | 1 | Can smell less than 1 ppm. |
| .001 | 10 | TLV for 8 hours of exposure. |
| .0015 | 15 | STEL for 15 minutes of exposure. |
| .01 | 100 | Immediately Dangerous to Life & Health. |
| | | Kills sense of smell in 3 to 5 minutes. |
| .02 | 200 | Kills sense of smell quickly, may burn eyes and throat. |
| .05 | 500 | Dizziness, cessation of breathing begins in a few minutes. |
| .07 | 700 | Unconscious quickly, death will result if not rescued promptly. |
| .10 | 1000 | Death will result unless rescued promptly. Artificial resuscitation |
| | | may be necessary. |

PHYSICAL PROPERTIES OF H₂S

The properties of all gases are usually described in the context of seven major categories:

COLOR

ODOR

VAPOR DENSITY

EXPLOSIVE LIMITS

FLAMMABILITY

SOLUBILITY (IN WATER)

BOILING POINT

Hydrogen Sulfide is no exception. Information from these categories should be considered in order to provide a fairly complete picture of the properties of the gas.

COLOR -- TRANSPARENT

Hydrogen Sulfide is colorless so it is invisible. This fact simply means that you can't rely on your eyes to detect its presence. In fact that makes this gas extremely dangerous to be around.

ODOR - ROTTEN EGGS

Hydrogen Sulfide has a distinctive offensive smell, similar to "rotten eggs". For this reason it earned its common name "sour gas". However, H₂S, even in low concentrations, is so toxic that it attacks and quickly impairs a victim's sense of smell, so it could be fatal to rely on your nose as a detection device.

VAPOR DENSITY – SPECIFIC GRAVITY OF 1.192

Hydrogen Sulfide is heavier than air so it tends to settle in low-lying areas like pits, cellars or tanks. If you find yourself in a location where H_2S is known to exist, protect yourself. Whenever possible, work in an area upwind and keep to higher ground.

EXPLOSIVE LIMITS - 4.3% TO 46%

Mixed with the right proportion of air or oxygen, H₂S will ignite and burn or explode, producing another alarming element of danger besides poisoning.

FLAMMABILITY

Hydrogen Sulfide will burn readily with a distinctive clear blue flame, producing Sulfur Dioxide (SO₂), another hazardous gas that irritates the eyes and lungs.

SOLUBILITY - 4 TO 1 RATIO WITH WATER

Hydrogen Sulfide can be dissolved in liquids, which means that it can be present in any container or vessel used to carry or hold well fluids including oil, water, emulsion and sludge. The solubility of H_2S is dependent on temperature and pressure, but if conditions are right, simply agitating a fluid containing H_2S may release the gas into the air.

BOILING POINT – (-76 degrees Fahrenheit)

Liquefied Hydrogen Sulfide boils at a very low temperature, so it is usually found as a gas.

RESPIRATOR USE

The Occupational Safety and Health Administration (OSHA) regulate the use of respiratory protection to protect the health of employees. OSHA's requirements are written in the Code of Federal Regulations, Title 29, Part 1910, Section 134, Respiratory Protection. This regulation requires that all employees who might be required to wear respirators, shall complete a OSHA mandated medical evaluation questionnaire. The employee then should be fit tested prior to wearing any respirator while being exposed to hazardous gases.

Written procedures shall be prepared covering safe use of respirators in dangerous atmospheric situations, which might be encountered in normal operations or in emergencies. Personnel shall be familiar with these procedures and the available respirators.

Respirators shall be inspected prior to and after each use to make sure that the respirator has been properly cleaned, disinfected and that the respirator works properly. The unit should be fully charged prior to being used.

Anyone who may use respirators shall be properly trained in how to properly seal the face piece. They shall wear respirators in normal air and then in a test atmosphere. (Note: Such items as facial hair (beard or sideburns) and eyeglass temple pieces will not allow a proper seal.) Anyone that may be expected to wear respirators should have these items removed before entering a toxic atmosphere. A special mask must be obtained for anyone who must wear eyeglasses. Contact lenses should not be allowed.

Respirators shall be worn during the following conditions:

- A. Any employee who works near the top or on the top of any tank unless tests reveal less than 20 ppm of H₂S.
- B. When breaking out any line where H₂S can reasonably be expected.
- C. When sampling air in areas where H₂S may be present.
- D. When working in areas where the concentration of H₂S exceeds the Threshold Limit Value for H₂S (10 ppm).
- E. At any time where there is a doubt as to the H₂S level in the area to be entered.

EMERGENCY RESCUE PROCEDURES DO NOT PANIC!!! Remain Calm — Think

- 1. Before attempting any rescue you must first get out of the hazardous area yourself. Go to a safe briefing area.
- 2. Sound alarm and activate the 911 system.
- 3. Put on breathing apparatus. At least two persons should do this, when available use the buddy system.
- 4. Rescue the victim and return them to a safe briefing area.
- 5. Perform an initial assessment and begin proper First Aid/CPR procedures.
- 6. Keep victim lying down with a blanket or coat, etc.., under the shoulders to keep airway open. Conserve body heat and do not leave unattended.
- 7. If the eyes are affected by H₂S, wash them thoroughly with potable water. For slight irritation, cold compresses are helpful.
- 8. In case a person has only minor exposure and does not lose consciousness totally, it's best if he doesn't return to work until the following day.
- 9. Any personnel overcome by H₂S should always be examined by medical personnel. They should always be transported to a hospital or doctor.

EOG RESOURCES, INC. Sand Tank 18 Fed Com 4H

SURFACE USE PLAN OF OPERATION

SHL: 1880' FSL & 2310' FEL, Unit J, Section 18, T18S-R30E, N.M.P.M., Eddy, NM BHL: 1980' FSL & 2310' FWL, Unit K, Section 17, T18S-R30E, N.M.P.M., Eddy, NM

1. EXISTING ROADS:

- a. The well site and elevation plat for the proposed well are reflected on the well site layout; Form C-102. The well was staked by Terry Asel, RPL 15079.
- b. All roads into the location are depicted on Exhibit 2 & 2a. Operator will amend RW120717 to include roadway described on Exhibit 2a.
- c. <u>Directions to Locations:</u> Beginning in Loco Hills, NM, From Jct. of Hwy 82 & Co. Road 217, Go Southwest on CR 217 for 3 miles, turn left on CR 216 and go south for 1.9 miles, turn left on lease road for 0.1 miles, turn right on lease road for 0.2 miles, turn left lease road for 0.5 miles, turn right and go south for 0.1 miles, turn right and go west on lease road for 0.2 miles, turn left and go south for 0.3 miles, turn left for 0.1 miles, turn south for 0.3 miles to location.

2. NEW OR RECONSTRUCTED ACCESS ROAD:

- a. The well site layout, Exhibit 2b shows the layout. The proposed access road begins off an existing lease road and trends SSW to the W side of well pad. (See 1c above for driving directions).
- b. The maximum width of the road will be 20'. It will be crowned and made of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent soil erosion.
- c. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 1%.
- d. No cattleguards, gates or fence cuts will be required. No turnouts are planned.

3. LOCATION OF EXISTING WELLS:

Exhibit #3 shows all existing wells within a one-mile radius of this well.

4. LOCATION OF EXISTING AND/OR PROPOSED PRODUCTION FACILITIES:

- a. In the event the well is found to be productive, the Sand Tank 18 Fed Com 4H battery would be utilized and the necessary production equipment will be installed at the well site. See Production Facilities Layout diagram.
- b. As a proposed oil well, operator shall construct a powerline to the well location alongside existing lease roads as described on Exhibit 5. A separate powerline grant will be secured prior to construction.

EOG RESOURCES, INC. Sand Tank 18 Fed Com 4H

- c. All flow lines will adhere to API standards. A separate pipeline grant will be secured prior to construction.
- d. Refer to b above.
- e. If the well is productive, rehabilitation plans are as follows:
 - i. Within 60 days after drilling and completion of the well, the location shall be reduced as determined by operator to the minimum area necessary to safely and effectively operate the well.
 - ii. The original topsoil from the well site will be returned to the location. The location will be contoured as close as possible to the original state.

5. LOCATION AND TYPE OF WATER SUPPLY:

This location will be drilled using a combination of water mud systems (outlined in the drilling program). The water will be obtained from commercial water stations in the area and hauled to location by transport truck using existing and proposed roads shown in Exhibit 2 & 2a. On occasion, water will be obtained from existing water wells. In these cases where a poly pipeline is used to transport water for drilling purposes, proper authorizations shall be secured. If poly pipeline is used to transport fresh water to the location, proper authorization shall be secured by the contractor.

6. CONSTRUCTION MATERIALS

All caliche utilized for the drilling pad and proposed access road shall be obtained from an existing BLM approved pit or from prevailing deposits found under the location. All roads shall be constructed of rolled and compacted caliche. Operator will use BLM recommended use of extra caliche from other locations close by roads, if available.

7. METHODS OF HANDLING WASTE MATERIALS

- a. Drill cuttings shall be disposed of in a steel cuttings bin (catch tanks) on the drilling pad (behind the steel mud tanks). The bin and cuttings shall be hauled to an approved cuttings dumpsite.
 - At the site, the cuttings shall be removed from the bin & the bin shall be returned to the drilling site for reuse.
- b. All trash, junk, and other waste material shall be contained in trash cages or trash bins to prevent scattering. When a job is completed, all contents shall be removed and disposed of in an approved landfill.
- c. The supplier, including broken sacks, shall pick up salts remaining after completion of well.
- d. If necessary, a porto-john shall be provided for the rig crews. This equipment shall be properly maintained during the drilling and completion operations and shall be removed when all operations are complete.
- e. Remaining drilling fluids shall be hauled off by transports to a state approved disposal site. Water produced during completion shall be put in storage tanks

EOG RESOURCES, INC. Sand Tank 18 Fed Com 4H

and disposed of in a state approved disposal. Oil and condensate produced shall be put in a storage tank and sold.

- f. Disposal of fluids to be transported by the following companies:
 - i. RGB TRUCKING
 - ii. LOBO TRUCKING
 - iii. I & W TRUCKING
 - iv. CRANE HOT OIL & TRANSPORT
 - v. JWS
 - vi. QUALITY TRUCKING

8. ANCILLARY FACILITIES:

a. No airstrip, campsite, or other facilities will be built.

9. WELL SITE LAYOUT:

- a. Exhibit 4 shows the proposed well site layout with dimensions of the pad layout.
- b. Exhibit 4 shows proposed location living facilities.
- c. Mud pits in the active circulating system shall be steel pits and the catch tanks shall be steel tanks set in shallow sumps behind the steel circulating tanks and sumps.
- d. The area where the catch tanks are placed shall be reclaimed and seeded per BLM requirements.

10. PLANS FOR SURFACE RECLAMATION:

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche shall be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road shall be reclaimed as directed by the BLM. The catch tank area shall be broken out and leveled after drying to a condition where these are feasible. The original topsoil shall again be returned to the pad and contoured, as close as possible, to the original topography.
- b. The location and road shall be reclaimed as recommended by the BLM.
- c. If the well is deemed commercially productive, the catch tank area shall be restored as described in 10(a) within 120 days subsequent to the completion date. Caliche from areas of the pad site not required for operations shall be reclaimed. The original top soil shall be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad shall be contoured, as close as possible, to match the original topography.

EOG RESOURCES, INC. Sand Tank 18 Fed Com 4H

11. SURFACE OWNERSHIP

The surface is owned by the Bureau of Land Management (BLM). The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas. The proposed road routes and surface location will be restored as directed by the BLM.

12. OTHER INFORMATION:

- a. The area surrounding the well is grassland. The topsoil is sandy in nature. The vegetation is moderately sparse with native prairie grass, cactus and shinnery oak. No wildlife was observed but it is likely that deer, rabbits, coyotes, birds and rodents transverse the area.
- b. There are not dwellings within 2 miles of location.
- c. There is no permanent or live water within 1 mile of the location.
- d. EOG will participate in the Permian Basin Memorandum of Agreement (MOA) signed by SHPO and the ACHP to use as an option for archaeological clearance.

13. BOND COVERAGE:

a. Bond Coverage is Nationwide; Bond No. NM 2308

EOG RESOURCES, INC. Sand Tank 18 Fed Com 4H

COMPANY REPRESENTATIVES:

Representatives responsible for ensuring compliance of the surface use plan are listed below:

Permitting & Land

Mr. Donny G. Glanton Senior Lease Operations ROW Representative EOG Resources, Inc. P.O. Box 2267 Midland, TX 79702 (432) 686-3642 Office (432) 770-0602 Cell

Drilling

Operations

| Mr. Jason LaGrega | Mr. Howard Kemp |
|----------------------------|-----------------------|
| Division Drilling Engineer | Production Manager |
| EOG Resources, Inc. | EOG Resources, Inc |
| P.O. Box 2267 | P.O. Box 2267 |
| Midland, TX 79702 | Midland, TX 79702 |
| (432) 686-3633 Office | (432) 686-3704 Office |
| (432) 894-1217 Cell | (432) 634-1001 Cell |

OPERATOR CERTIFICATION

I certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal Laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true, and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 11th day of July 2008.

Name: Donny G. Glanton

Position: Sr. Lease Operations ROW Representative

Address: P.O. Box 2267 Midland, TX 79705

Telephone: <u>432-686-3642</u>

Email: donny glanton@eogresources.com

Signed: Jm J. MM

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME: LEASE NO.: NM063472 BHL
WELL NAME & NO.: 4H-Sand Tank 18 Fed Com
SURFACE HOLE FOOTAGE: 1880' FSL & 2310' FEL
BOTTOM HOLE FOOTAGE 1980' FSL & 2310' FWL
LOCATION: Section 18, T. 18 S., R 30 E., NMPM
COUNTY: Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

| General Provisions |
|---|
| Permit Expiration |
| Archaeology, Paleontology, and Historical Sites |
| Noxious Weeds |
| Special Requirements |
| Lesser Prairie Chicken |
| ☐ Construction |
| Notification |
| Topsoil |
| Reserve Pit |
| Federal Mineral Material Pits |
| Well Pads |
| Roads |
| Road Section Diagram |
| ☑ Drilling |
| Production (Post Drilling) |
| Well Structures & Facilities |
| Pipelines |
| Electric Lines |
| Interim Reclamation |
| Final Ahandanment/Parlametian |

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken: Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (505) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil of the well pad. The topsoil to be stripped is approximately 8 inches in depth. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

C. RESERVE PITS

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (505) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.


Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:

Standard Turnout – Plan View




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope:
$$\frac{400'}{4\%}$$
 + 100' = 200' lead-off ditch interval

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 - Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. Hydrogen Sulfide has been reported as a hazard, but no measurements have been recorded. It is recommended that monitoring equipment be onsite for potential Hydrogen Sulfide. If Hydrogen Sulfide is encountered, please report measurements and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possible water flows in the Salado Group and Premier member of the Grayburg formation.

- 1. The 11-3/4 inch surface casing shall be set at approximately 385 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. Fresh water mud to be used to setting depth.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
 - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
- 2. The minimum required fill of cement behind the 8-5/8 inch intermediate casing is:

Formation below the 8-5/8" shoe to be tested according to Onshore Order 2.III.B.1.i. Test to be done as a mud equivalency test using the mud weight necessary for the pore pressure of the formation below the shoe (not the mud weight required to prevent dissolving the salt formation) and the mud weight for the bottom of the hole.

- 3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
 - Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
- 3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the 8-5/8" intermediate casing shoe shall be 5000 (5M) psi.
- 4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. The tests shall be done by an independent service company.
 - b. The results of the test shall be reported to the appropriate BLM office.
 - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
 - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.

WWI 090108

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Containment Structures

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

IX. INTERIM RECLAMATION & RESERVE PIT CLOSURE

A. INTERIM RECLAMATION

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

The operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

| Species | <u>lb/acre</u> | |
|-------------------|----------------|--------|
| Plains Bristlegra | SS | 5lbs/A |
| Sand Bluestem | | 5lbs/A |
| Little Bluestem | | 3lbs/A |
| Big Bluestem | | 6lbs/A |
| Plains Coreopsis | • | 2lbs/A |
| Sand Dropseed | | 1lbs/A |
| | | |

^{*} This can be used around well pads and other areas where caliche cannot be removed.

5lbs/A

**Four-winged Saltbush

Pounds of seed x percent purity x percent germination = pounds pure live seed (Insert Seed Mixture Here)

^{*}Pounds of pure live seed:

X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface land owner agreement.