

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OCD-ARTESIA

MAR 10 2009

FORM APPROVED
OMB No 1004-0137
Expires, July 31, 2010**SUNDRY NOTICES AND REPORTS ON WELLS**
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

NMLC070938

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2.

1. Type of Well

☒ Oil Well☐ Gas Well☐ Other

2. Name of Operator

BP America Production Company

3a. Address

P. O. Box 1089 Eunice, New Mexico 88231

3b. Phone No. (include area code)

575 / 394-1650

4. Location of Well (Footage, Sec, T, R, M., or Survey Description)

660' FSL & 1980' FWL Unit Letter "N"
Section 9 - T18S - R27E

7. If Unit of CA/Agreement, Name and/or No.

NMNM70945X

8. Well Name and No

Empire Abo Unit "P" #6

9. API Well No.

30-015-00837

10. Field and Pool or Exploratory Area

Empire Abo

11. Country or Parish, State

Eddy County, New Mexico

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input checked="" type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation. Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

BP America Production Company proposes to plug and abandon this well as follows:

1. MIRU PU. POH with rods & pump, install BOP & POH w/ tbg.
2. Set CIBP on tbg @ approx 5430' = 60' above top perf, load hole with water and test casing and CIBP to 500 psi.
3. Run GR-CBL and evaluate bond across top of Glorieta @ 2995' and surface casing shoe @ 1497'. Discuss results with BLM representative and obtain approval for any needed revisions to these procedures before proceeding with abandonment.
4. Spot 25 sx Class "C" cement on top of CIBP @ 5430' (top of cement plug estimated @ 5070') and circulate hole with 9.0 ppg mud laden fluid.
5. Spot 25 sx Class "C" cement from 3600' - 3960' across remedial cementing perfs @ 3880'.
6. Spot 25 sx Class "C" cement from 2690' - 3050' across top of Glorieta @ 2995' and across old casing leaks between 2823' to 2854'.
7. Spot 25 sx Class "C" cement from 1190' - 1550' across the 8 5/8" surface casing shoe @ 1497'. WOC & tag plug to confirm proper placement.
8. Spot 25 sx Class "C" cement from 0' - 360', which provides a plug across the top of Yates (if zone is present in this area) and sets the top plug.
9. RD PU. Cut-off wellhead equipment, casings and anchors to 3' below ground level and install regulation Dry Hole Marker.
10. Reclaim and prepare location location for BLM inspection.

See attached well bore schematic for additional information. Operations will commence after approval of this "Notice of Intent" and the starting date will be dependent on the availability of equipment and services. It is expected that downhole operations will require approximately seven days to complete.

**SEE ATTACHED FOR
CONDITIONS OF APPROVAL**

14. I hereby certify that the foregoing is true and correct Name (Printed/Typed)

M. D. Westmoreland

Title Wells Operations Superintendent

Signature

Date 03/04/2009

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Office

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

APPROVED


MAR 8 2009

JAMES A. AMOS

(Originally drilled by Humble O&R as the Chalk Bluff Draw Unit #3)

Present Status

RKB	15'
GL	3493'



Empire Abo Unit "P" #6


Empire Abo Field
(Federal Lease No. NMLC070938)

API No. 30-015-00837

660' FSL & 1980' FWL
Section 9 - T18S - R27E
Eddy County, New Mexico

(Originally drilled by Humble O&R as the
Abo Chalk Bluff Draw Unit #3)

Proposed P&A



BUREAU OF LAND MANAGEMENT
Carlsbad Field Office
620 East Greene Street
Carlsbad, New Mexico 88220
575-234-5972

Permanent Abandonment of Federal Wells
Conditions of Approval

Failure to comply with the following Conditions of Approval may result in a Notice of Incidents of Noncompliance (INC) in accordance with 43 CFR 3163.1.

1. Plugging operations shall commence within ninety (90) days from the approval date of this Notice of Intent to Abandon.

If you are unable to plug the well by the 90th day provide this office, prior to the 90th day, with the reason for not meeting the deadline and a date when we can expect the well to be plugged. Failure to do so will result in enforcement action.

2. **Notification:** Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Chaves and Roosevelt County, call 575-627-0272; Eddy County, call 575-361-2822; Lea County, call 575-393-3612.

3. **Blowout Preventers:** A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.

4. **Mud Requirement:** Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of water. Minimum nine (9) pounds per gallon.

5. **Cement Requirement:** Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final. Unless specific approval is received, no plug except the surface plug shall be less than 25 sacks of cement. In lieu of a cement plug in a cased hole, a bridge plug set within 50 feet to 100 feet above the perforations shall be capped with 25 sacks of cement. If a bailer is used to cap this plug, 35 feet of cement shall be sufficient.

Unless otherwise specified in the approved procedure, the cement plug shall consist of either Neat Class "C", for up to 7,500 feet of depth or Neat Class "H", for deeper than 7,500 feet plugs.

6. **Dry Hole Marker:** All casing shall be cut-off at the base of the cellar or 3 feet below final restored ground level (whichever is deeper). The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement. The following information shall be permanently inscribed on the dry hole marker: well name and number, name of the operator, lease serial number, surveyed location (quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer such as metes and bounds).

7. **Subsequent Plugging Reporting:** Within 30 days after plugging work is completed, file one original and five copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. **Show date well was plugged.**

8. **Trash:** All trash, junk and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on site is not permitted.

Following the submission and approval of the Subsequent Report of Abandonment, surface restoration conditions of approval will be developed and furnished to you.