# OCD-ARTESIA

Form 3160-3 (April 2004)							
	UNITED ST	ATES			5. Lease Serial No.		<del></del>
DEPA	ARTMENT OF T				NMNM-17574		
BURE	AU OF LAND N	MANAGEMENT	`		6. If Indian, Allotee or	6. If Indian, Allotee or Tribe Name	
APPLICATION	N FOR PERMIT T	O DRILL OR RE	ENTER	_			
1a. Type of Work: DRILL	RE	ENTER			7. If Unit or CA Agree	ment, Name and No	
					8 Lease Name and W	all No	
1b. Type of Well. Oil Well Gas W	ell Other	Singl	e Zone Multipl	le Zone	Grynberg 11 Fed		
2. Name of Operator		- Liveria			9. API Well No	ETALINO. O	
Cimarex Energy Co. of Colorado					30-015- 37.3	474	
3a. Address		3b Phone No (ir	clude area code)		10. Field and Pool, or	Exploratory	
5215 N. O'Connor Bvd., Ste. 1500; Irvin	g. TX 75039	972-401-311	1		Cottonwood Dra	w; Delaware, Nor	th
Location of Well (Report location clearly     At Surface 2460 FSL &	and in accordance	vith any State requ	rements.*)	ΩX	11. Sec., T. R. M. or Blk.		
At Surface 2460 FSL &	330 FEL	UN	ORIHUL				
A			LOCATIO	N	11-25S-26E		
At proposed prod. Zone 330 FSL & 2		Horizontal De	OCATIO Elaware Test		_	13. State	
14 Distance in miles and direction from nea	itest town or post of	iice*			12. County or Parish		
15.72		16 No efermi	- 1	17 Sman	Eddy ng Unit dedicated to this w	NM	
15 Distance from proposed* location to nearest	ľ	16. No of acres i	n lease	17. Spaci	ng Unit dedicated to this w	eli	
property or lease line, ft.							
(Also to nearest drig unit line if	180	1	60		E2SE 80 a	croc	
any) 18 Distance from proposed location*	180	19. Proposed De		20. BLM	BIA Bond No. on File	162	
to nearest well, drilling, completed,		Vertic	al 3400'				
applied for, on this lease, ft.	N/A		 133' TVD 3093'	1	NM-257	5	
21 Elevations (Show whether DF, KDB, RT	·	22. Approximate	date work will start	*	23. Estimated duration		
, ,	, ,	••					
3339' GR		09	.15.09		20-25	days	
•		24. Att	achments				
The following, completed in accordance with t	he requirements of (	Onshore Oil and Ga	s Order No. 1, shall l	be attached to	this form:		
Well plat certified by a registered surveyor		ı	4. Bond to cover	the operatio	ns unless covered by an exi	sting bond on file (se	ee
2. A Drilling Plan			Item 20 above	e).			•
3. A Surface Use Plan (if the location is on N SUPO shall be filed with the appropriate F			<ol> <li>Operator Cert</li> <li>Such other sit</li> </ol>		ormation and/or plans as m	ay be required by the	•
	orest berviec Office,		authorized off	-			
25. Signature	r	Name (Pri	nted/Typed)			Date	
Zeno Fa	w	Zeno F	arris			08.1	12.09
Title							
Manager Operations Administration	1						
Approved By (Signature)	7.	Name (Pri	nted/Typed)			Date	
5/ Jeanette ma	luce	Jea	nette	MA	etines	SEP 2 ?	<u> 20</u> 0
Title Low FIELD MANAGER		1 000	ARLSBAD FIELI	V			
Application approval does not warrant or certify that conduct operations thereon.	the applicant holds leg	al or equitable title to	those rights in the subj	ect lease which	would entitle the applicant to	OD TIVIO VE	ARS
		-	•		APPROVAL F	AU INA IF	,rti tO
Conditions of approval, if any, are attached.  Title 18 U.S.S. Section 1001 and Title 43 U.S.C. Sec	tion 1212, make it a cr	me for any person kno	owingly and willfully to	make to any	lepartment or agency of the I in	ited	
States any false, fictitious, or fraudulent statements of					or agency of the Off	· · · · ·	
* (Instructions on page 2)						1 1	

Carlsbad Controlled Water Basin

SEE ATTACHED FOR CONDITIONS OF APPROVAL

Approval Subject to General Requirements & Special Stipulations Attached DISTRICT I 1825 N. French Dr., Hobbs, NM 88240

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102 Revised October 12, 2005

Submit to Appropriate District Office

₱ DISTRICT II

1301 W. Grand Avenue, Artesia, NM 88210

DISTRICT IV

DISTRICT III 1000 Rio Brazos Rd., Aztec, NM 87410

1220 S. St. Francis Dr., Santa Fe, NM 87505

OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, New Mexico 87505

AMENDED REPORT

State Lease - 4 Copies

Fee Lease - 3 Copies

WELL LOCATION AND ACREAGE DEDICATION PLAT

30 · Olfo- 30	Pool Code Pool Cettonwood Draw	Name Sulphalli Delauture, SU 7: Delaware, North
Property Code	Property Name GRYNBERG "11' FEDERAL	Well Number 6
оскій мо. 162683	Operator Name CIMAREX ENERGY CO. OF COLORADO	Elevation 3339'


#### Surface Location


	UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
j	1	11	25 S	26 E		2460	SOUTH	330	EAST	EDDY

#### Bottom Hole Location If Different From Surface

ſ	UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
	Р	11	25 S	26 E		330	SOUTH	430	EAST	EDDY
Dedicated Acres Joint or Infill Consolidation Code Order No.										
	80				NS	L Pending				

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION





GRYNBERG "11' FEDERAL #6 Located 2460' FSL and 330' FEL Section 11, Township 25 South, Range 26 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786 1120 N. West County Rd. Hobbs, New Mexico 88241 (575) 393-7316 — Office (575) 392-2206 — Fax basinsurveys.com


W.O. Nurnber: JMS 21539

Survey Date: 07-14-2009

Scale: 1" = 2000'

Date: 07-15-2009

CIMAREX ENERGY CO. OF COLORADO




GRYNBERG "11' FEDERAL #6 Located 2460' FSL and 330' FEL Section 11, Township 25 South, Range 26 East, N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

W.O. N	umber.	JMS	21539	
Survey	Date:	07-	14-2009	
Scale:	1" = 2	Miles		
Date:	07-15-	2009		

CIMAREX ENERGY CO. OF COLORADO SECTION 11, TOWNSHIP 25 SOUTH, RANGE 26 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO.



Directions to Location:

FROM THE JUNCTION OF BLACK RIVER VILLAGE AND JOHN D FOREHAND, GO SOUTH ON JOHN D FOREHAND FOR 7.1 MILES TO LEASE ROAD, ON LEASE ROAD GO WEST WINDING NORTH FOR 1.7 MILES TO LEASE ROAD, ON LEASE ROAD GO WEST WINDING NORTHWESTERLY FOR 0.2 MILES TO PROPOSED LEASE ROAD.

BASIN SURVEYS P.O. BOX 1786-HOBBS, NEW MEXICO

W.O. Number: 21539 | Drawn By: J. SMALL

Date: 07-15-2009 | Disk: JMS 21539

# CIMAREX ENERGY CO. OF COLORADO

REF: GRYNBERG "11' FEDERAL #6 / WELL PAD TOPO


THE GRYNBERG "11' FEDERAL #6 LOCATED 2460'

FROM THE SOUTH LINE AND 330' FROM THE EAST LINE OF SECTION 11, TOWNSHIP 25 SOUTH, RANGE 26 EAST.

N.M.P.M., EDDY COUNTY, NEW MEXICO.

Survey Date: 07-14-2009 Sheet

eet 1 of 1 Sheets



# Application to Drill Grynberg 11 Federal No. 6

# Cimarex Energy Co. of Colorado Unit I, Section 11

T25S-R26E, Eddy County, NM

In response to questions asked under Section II B of Bulletin NTL-6, the following information is provided for your consideration:

1. Location:

SHL

2460 FSL & 330 FEL

BHL

330 FSL & 430 FEL

2. Elevation above sea level:

3339' GR

3. Geologic name of surface formation:

**Quaternery Alluvium Deposits** 

4. Drilling tools and associated equipment:

Conventional rotary drilling rig using fluid as a circulating

medium for solids removal.

5. Proposed drilling depth:

Vertical 3400'

Lateral MD 5133' TVD 3093'

## 6. Estimated tops of geological markers:

Top Salt	1179'	Cherry Canyon M3	3058'
Base Salt	1759'	M3 TVD Target	3083'
Bell Canyon	1969'	Cherry Canyon L	3204'
Cherry Canyon	2920'	Cherry Canyon K	3264'
Cherry Canyon M	2984'		

#### 7. Possible mineral bearing formations:

Bell Canyon	Oil
Cherry Canyon	Oil

## 8. Proposed drilling Plan

After drilling and setting surface casing, drill to vertical TD 3400' and log. Set 5%" casing to 2830' and cross over to 2%" 2000 psi IJ fiberglass tubing underneath and cement in place. Drill out of the bottom of the 5%" with a 4%" bit and through cement and fiberglass tubing to KOP @ 2892' and kick off to drill the lateral. The fiberglass tubing effectively circulates cement to surface and plugs back the open hole.

Kick off 4¾" hole @ 2892.' Drill to TD 5133' MD. Run 2¾" PEAK liner from RSB packer @ 2792' to TD @ 5133.' Frac through PEAK completion liner.

# Application to Drill Grynberg 11 Federal No. 6

# Cimarex Energy Co. of Colorado Unit I, Section 11

T25S-R26E, Eddy County, NM

9. Mud Circulating System:

Dèpth			Mud Wt	Visc	Fluid Loss	Type Mud
0,	to	440'	8.4 - 8.6	30-32	NC	FW spud mud. Add FW to control weight & viscosity and paper to prevent seepage.
440'	to	2,830'	9.9 - 10.0	28-29	NC	Saturated Brine. Sweep as needed to clean hole.
2,892'	to	5,133'	9.5 - 9.8	28-30	NC	Cut brine. Sweep as needed to clean hole.

> see COA

Sufficient mud materials will be kept on location at all times in order to combat lost circulation or unexpected kicks. In order to run DSTs, open hole logs, and casing, the viscosity and water loss may have to be adjusted in order to meet these needs.

10. Casing Program:

Hole Size			Depth			Casing OD		Weight Collar	
Surface	12¼"	0'	to	440'	New	8%"	24#	STC	J-55
Production	7%"	0'	to	2830'	New	5½"	17#	J-55	LTC
Fiberglass tbg	7%"	2830'	to	3400'	New	2%"	2.18#	Fiberglass	IJ
Lateral	434" 273	1 2192	to	5133'	New	21/8"	6.5#	EUE	L-80

COR.

11. Cementing Prog	ram: C-see COA
Surface Casing	<u>Lead:</u> 150 sx 10:2 RFC (Class A) + 4 pps D24 + 0.125 pps D130, 14.20 ppg, 1.62 cuft/sx, 7.5 gps.
	<i>Tail</i> : 150 sx Class C + 2% S1 + 0.125 pps D130, 14.80 ppg, 1.34 cuft/sx, 6.29 gps.
	TOC Surface
Production casing	<u>Lead:</u> 550 sx 50:50 Poz:Class H + 5% D44 (bwow) + 6% D20 + 0.2% D46 + 0.125 pps D130, 11.90
and Fiberglass	ppg, 2.38 cuft/sx, 13.68 gps.
tubing	Tail: 400 sx TXI Lightweight + 1.33% D44 (bwow) + 0.1% D167 + 0.1% D65 + 0.1% D13, 13.00 ppg,
	1.40 cuft/sx, 7.24 gps.
	TOC Surface
Lateral	PEAK completion assembly will be used, so no cement is required.

Fresh water zones will be protected by setting 8%" casing at 440' and cementing to surface. Hydrocarbon zones will be protected by setting 5½" casing at 2830' and 2½" fiberglass tubing at 3400' and cementing to surface.

Collapse Factor	<b>Burst Factor</b>	<u>Tension Factor</u>
1.125	1.125	1.6

# Application to Drill Grynberg 11 Federal No. 6

Cimarex Energy Co. of Colorado Unit I, Section 11 T25S-R26E, Eddy County, NM

## 12. Pressure control Equipment:

Exhibit "E". A 12½" 5000 PSI working pressure B.O.P. consisting of one set of blind rams and one set of pipe rams and a 5000 # annular type preventer. A choke manifold and 120 gallon accumulator with floor and remote operating stations and auxiliary power system. Rotating head below 440.' A kelly cock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

BOP unit will be hydraulically operated. BOP will be nippled up and operated at least once a day while drilling and the blind rams will be operated when out of hole during trips. No abnormal pressure or temperature is expected while drilling. From the base of the surface pipe through the running of production casing, the well will be equipped with a 5000 psi BOP system.

We are requesting a variance for testing the 8%" surface casing from Onshore Order No. 2, which states that all casing strings below the conductor shall be pressure tested to 0.22 psi per foot or 1500 psi, whichever is greater, but not to exceed 70% of the manufacturer's stated maximum internal yield. We are requesting to test the 8%" casing to 1000 psi using rig pumps. The BOP will be tested to 3000 psi by an independent service company.

# 13. Testing, Logging and Coring Program:

L See-COA

- A. Mud logging program: No mud logging program.
- B. Electric logging program: CNL / LDT / CAL / GR, DLL / CAL / GR
- C. No DSTs or cores are planned at this time.

#### 14. Potential Hazards:

No abnormal pressures or temperatures are expected. In accordance with Onshore Order 6, Cimarex has encountered H<sub>2</sub>S in a one-time encounter in an Intra-salt Pocket and while drilling and completing wells in the Delaware Mountain Group. In this regard, attached is an H<sub>2</sub>S Drilling Operations Plan. The ROEs encountered do not meet the BLM's minimum requirements for the submission of a "Public Protection Plan" for the drilling and completion of this well. Adequate flare lines will be installed off the mud / gas separator where gas may be flared safely. All personnel will be familiar with all aspects of safe operation of equipment being used.

Estimated BHP 2300 psi Estimated BHT 110°

15. Road and location construction will begin after BLM approval of APD. Anticipated spud date as soon as approved.

Drilling expected to take 10-15 days


If production casing is run an additional 30 days will be required to complete and construct surface facilities.

# 16. Other Facets of Operations:

After running casing, cased hole gamma ray neutron collar logs will be run from total depth over possible pay intervals.

<u>Delaware</u> pay will be perforated and stimulated.


The proposed well will be tested and potentialed as an oil well.




Wind Direction Indicators (wind sock or streamers)

- △ H2S Monitors (alarms at bell nipple and shale shaker)
- O Briefing Areas
- O Remote BOP Closing Unit

Exhibit D – Rig Diagram
Grynberg 11 Federal No. 6
Cimarex Energy Co. of Colorado
11-25S-26E
SHL 2460 FSL & 330 FEL
BHL 330 FSL & 430 FEL
Eddy County, NM





# Cimarex Energy Co.

Eddy County (NM83E) Sec 11-25S-26E Grynberg 11 Federal #6

Wellbore #1

Plan: Plan #1 8-10-09

# **Standard Planning Report**

10 August, 2009

# **Great White Directional Services**

Planning Report

EDM 5000.1 Single User Db Well Grynberg 11 Federal #6 Database: Local Co-ordinate Reference: Cimarex Energy Co. WELL @ 3339.0usft (Original Well Elev) Company: **TVD Reference:** Project: Eddy County (NM83E) WELL @ 3339.0usft (Original Well Elev) MD Reference:

Sec 11-25S-26E Site: North Reference:

Minimum Curvature Grynberg 11 Federal #6 **Survey Calculation Method:** Well: Wellbore: Wellbore #1 Plan #1 8-10-09 Design:

Eddy County (NM83E) Pröject

Map System: US State Plane 1983 System Datum: Mean Sea Level North American Datum 1983 Geo Datum:

Map Zone: New Mexico Eastern Zone

Sec 11-25S-26E Site Northing: 413,975.80 usft 32° 8′ 17.095 N Site Position: Latitude: 561,186.90 usft 104° 16' 9.135 W From: Мар Easting: Longitude: Position Uncertainty: 0.0 usft Slot Radius: 13-3/16 " **Grid Convergence:** 0.03

Grynberg 11 Federal #6 Well Well Position 2.158.6 usft 416.134.40 usft Latitude: 32° 8' 38.431 N +N/-S Northing: Easting: +E/-W 4,017.5 usft 565,204.40 usft Longitude: 104° 15' 22.391 W Wellhead Elevation: **Ground Level:** 3,339.0 usft 0.0 usft **Position Uncertainty** 

Wellbore #1 Wellbore Magnetics Model Name Sample Date Declination Dip Angle Field Strength (nT) (°) (°) IGRF200510 8/10/2009 60.05 48,705 8.10

Design	Plan #1 8-10-0	9	manufacturing at any day of an arranged manufacturing			and the second second
Audit Notes:						
Version:		Phase:	PLAN	Tie On Depth:	0.0	
Vertical Section:	-	Depth From (TVD)	+N/-S	+E/-W	Direction	annamin'nykyyjää aivaksi misämääninen 1915 ettään j
		(usft)	(usft)	(usft)	(°)	
Annual Water Print and who should be been been	THE PARTY OF THE P	0.0	0.0	0.0	181.79	The second secon

Measured Depth (usft)	Inclination (°)	Azimuth	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Ţarget
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	Controlled particular or all or the second of the second
2,892.0	0.00	0.00	2,892.0	0.0	0.0	0.00	0.00	0.00	0.00	
3,191.1	89.71	181.79	3,083.0	-189.9	-5.9	30.00	30.00	0.00	181.79	
5,133.0	89.70	181.80	3,093.0	-2,130.9	-66.8	0.00	0.00	0.00	133.52	Grynberg 11 Fede

8/10/2009 2.42 26PM COMPASS 5000.1 Build 27 Page 2

# **Great White Directional Services**

Planning Report

Database: Company: Project:

EDM 5000.1 Single User Db Cimarex Energy Co. Eddy County (NM83E) Sec 11-25S-26E

TVD Reference: MD Reference: North Reference:

Well Grynberg 11 Federal #6 WELL @ 3339.0usft (Original Well Elev) WELL @ 3339.0usft (Original Well Elev)

Well: Wellbore: Design:

Site:

Grynberg 11 Federal #6 Wellbore #1 Plan #1 8-10-09

Survey Calculation Method:

Local Co-ordinate Reference:

Minimum Curvature

nned Survey Measured		and the second of the second o	Vertical	ali order ranga, an agence and occasions	again of minimum and minimum a	Vertical	Dogleg	Build	Turn
Depth (usft)	Inclination (°)	Azimuth (°)	Depth (usft)	+N/-S (usft)	+E/-W (usft)	Section (usft)	Rate (°/100ft)	Rate (°/100ft)	Rate (°/100ft)~
2,892.0 <b>KÕP - 30</b> °	0.00 DLS, 181.79°	0.00 <b>AZI</b>	2,892.0	0.0	0.0	0.0	0.00	0.00	0.00
2.900.0	2.40	181.79	2,900.0	-0.2	0.0	0.2	30.00	30.00	0.00
2,910.0	5.40	181.79	2,910.0	-0.8	0.0	0.8	30.00	30.00	0.00
2,920.0	8.40	181.79	2,919.9	-2.0	-0.1	2.0	30.00	30.00	0.00
2,930.0	11.40	181.79	2,919.5	-3.8	-0.1 -0.1	3.8	30.00	30.00	0.00
2,940.0	14.40	181.79	2,929.7	-3.0 -6.0	-0.1	6.0	30.00	30.00	0.00
•									
2,950.0	17.40	181.79	2,949.1	-8.7	-0.3	8.7	30.00	30.00	0.00
2,960.0	20.40	181.79	2,958.6	-12.0	-0.4	12.0	30.00	30.00	0.00
2,970.0	23.40	181.79	2,967.8	-15.7	-0.5	15.7	30.00	30.00	0.00
2,980.0	26.40	181.79	2,976.9	-19.9	-0.6	19.9	30.00	30.00	0.00
2,990.0	29.40	181.79	2,985.8	-24.6	-0.8	24.6	30.00	30.00	0.00
3,000.0	32.40	181.79	2,994.3	-29.7	-0.9	29.7	30.00	30.00	0.00
3,010.0	35.40	181.79	3,002.6	-35.3	-1.1	35.3	30.00	30.00	0.00
3,020.0	38.40	181.79	3,010.6	-33.3 -41.3	-1.3	41.3	30.00	30.00	0.00
3,030.0	41.40	181.79	3,010.6	-41.3 -47.7	-1.5 -1.5	41.3 47.7	30.00	30.00	0.00
3,040.0	44.40	181.79	3,025.6	-47.7 -54.5	-1.5 -1.7	54.5	30.00	30.00	0.00
•									
3,050.0	47.40	181.79	3,032.6	-61.7	-1.9	61.7	30.00	30.00	0.00
3,060.0	50.40	181.79	3,039.2	-69.2	-2.2	69.2	30.00	30.00	0.00
3,070.0	53.40	181.79	3,045.3	-77.1	-2.4	77.1	30.00	30.00	0.00
3,080.0	56.40	181.79	3,051.1	-85.2	-2.7	85.3	30.00	30.00	0.00
3,090.0	59.39	181.79	3,056.4	-93.7	-2.9	93.8	30.00	30.00	0.00
•									
3,100.0	62.39	181.79	3,061.3	-102.4	-3.2	102.5	30.00	30.00	0.00
3,110.0	65.39	181.79	3,065.7	-111.4	-3.5	111.5	30.00	30.00	0.00
3,120.0	68.39	181.79	3,069.6	-120.6	-3.8	120.7	30.00	30.00	0.00
3,130.0	71.39	181.79	3,073.0	-130.0	-4.1	130.1	30.00	30.00	0.00
3,140.0	74.39	181.79	3,076.0	-139.5	-4.4	139.6	30.00	30.00	0.00
3,150.0	77.39	181.79	3,078.4	-149.2	-4.7	149,3	30.00	30.00	0.00
3,160.0		181.79	3,080.3	-159.0	-5.0	159.1	30.00	30.00	0.00
3,170.0		181.79	3,081.7	-168.9	-5.3	169.0	30.00	30.00	0.00
3,180.0	86.39	181.79	3,082.6	-178.9	-5.6	179.0	30.00	30.00	0.00
3,190.0		181.79	3,083.0	-188.9	-5.9	189.0	30.00	30.00	0.00
3,191.1 EOC - Ho		** ,	3,083.0	-189.9	-5.9	190.0	30.00	30.00	0.00
3,200.0	89.71	181.79	3,083.0	-198.9	-6.2	199.0	0.00	0.00	0.00
3,300.0	89.71		3,083.6	-298.8	-9.3	299.0	0.00	0.00	0.00
3,400.0			3,084.1	-398.8	-12.5	399.0	0.00	0.00	0.00
3,500.0			3,084.6	-498.7	-15.6	499.0	0.00	0.00	0.00
3,600.0			3,085.1	-598.7	-18.7	599.0	0.00	0.00	0.00
	89.71 89.71				-18.7 -21.8	599.0 699.0		0.00	
3,700.0			3,085.6	-698.6 -798.6			0.00		0.00
3,800.0	89.71		3,086.1		-25.0 -28.1	799.0	0.00	0.00	0.00
3,900.0			3,086.6	-898.5		899.0	0.00	0.00	0.00
4,000.0	89.71		3,087.1	-998.5	-31.2	999.0	0.00	0.00	0.00
4,100.0			3,087.6	-1,098.4	-34.4	1,099.0	0.00	0.00	0.00
4,200.0	89.70	181.80	3,088.2	-1,198.4	-37.5	1,199.0	0.00	0.00	0.00
4,300.0	89.70	181.80	3,088.7	-1,298.3	-40.6	1,299.0	0.00	0.00	0.00
4,400.0	89.70	181.80	3,089.2	-1,398.3	-43.8	1,399.0	0.00	0.00	0.00
4,500.0			3,089.7	-1,498.2	-46.9	1,499.0	0.00	0.00	0.00
4,600.0		181.80	3,090.2	-1,598.2	-50.0	1,599.0	0.00	0.00	0.00
4,700.0			3,090.7	-1,698.1	-53.2	1,699.0	0.00	0.00	0.00
4,800.0		181.80	3,091.3	-1,798.1	-56.3	1,799.0	0.00	0.00	0.00
4,900.0			3,091.8	-1,898.0	-59.5	1,899.0	0.00	0.00	0.00
5.000.0	89.70	181,80	3,092.3	-1,998.0	-62.6	1,999.0	0.00	0.00	0.00

# **Great White Directional Services**

Planning Report

Well Grynberg 11 Federal #6 EDM 5000.1 Single User Db Database: Local Co-ordinate Reference: Company: Project: WELL @ 3339.0usft (Original Well Elev) WELL @ 3339.0usft (Original Well Elev) Cimarex Energy Co. TVD Reference: Eddy County (NM83E) MD Reference: Site: Sec 11-25S-26E North Reference: Well: Grynberg 11 Federal #6 Minimum Curvature Survey Calculation Method: Wellbore #1 Wellbore: Design: Plan #1 8-10-09

* *		*	. **	- 1	* '	•			
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Tùrn Rate (°/100ft)
5,100.0 5,133.0	89.70 89.70	181.80 181.80	3,092.8 3,093.0	-2,097.9 -2,130.9	-65.7 -66.8	2,099.0 2,131.9	0.00 0.00	0.00 0.00	0.00 0.00

Design Targets	and the massives			and the second	and the state of t	د در دو در	andred in the same design and the second section of the second section in the second section is a second section of the second section in the second section is a second section in the second section in the second section is a second section in the second section in the second section is a second section in the second section in the second section is a second section in the second section in the second section is a second section in the second section in the second section is a second section in the section is a second section in the section in the section is a second section in the section is a section in the section in the section is a section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section in the section in the section is a section in the section	enanthile enanthine and terrescotter mode and analysis of any con-	min i gu phemilip nikakhara sama kulubahara 
Target Name - hit/miss target - Shape	Dip Angle	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+Ē/-W (uṣft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Grynberg 11 Federal : - plan hits target co - Point		0.00	3,093.0	-2,130.9	-66.8	414,003.54	565,137.63	32° 8' 17.344 N	104° 15′ 23.185 W

Plan Annot	ations	ing and an expension and an expension and an expension and	a analysis in a section of the secti	and the second s	ett kantan samunian samunian Samunian samunian sa	e na se seu sano mener	and the second s	and the state of t
~	Measured	Vertical	Local Coor	dinates			Ÿ	•
ú	Depth (usft)	Depth (usft)	+N/-S (usft)	+Ė/-W (usft)	Comment		•	· ·
The productive arm and P.O. ago	2,892.0 3,191.1 5,133.0	2,892.0 3,083.0 3,093.0	0.0 -189.9 -2,130.9	0.0 -5.9 -66.8	KOP - 30° DLS, 181.7 EOC - Hold to TD TD at 5133.0' MD	79° AZI	- Marie Perma antido de se con contra los está Perma de Albi Perte, como	anne fantareasaith alleit Printegream sallane àirichthe de d'Alleithe

# Cimarex Energy Co.

Project Eddy County (NM83E)
Site Sec 11-25S-26E
Well Grynberg 11 Federal #6
Wellbore: Wellbore #1
Design: Plan #1 8-10-09

#### WELL DETAILS: Grynberg 11 Federal #6

+N/-S +E/-W Northing 0.0 0.0 416134.40 Ground Level: 3339.0 Easting Latittude Lonaitude 32° 8' 38.431 N104° 15' 22.391 W 565204.40

Slot

375

-375-



SHL: 2460' FSL / 330' FEL BHL: 330' FSL / 430' FEL



Azimuths to Grid North True North -0 04° Magnetic North 8 06°

Magnetic Field Strength 48704 7snT Dip Angle 60.05° Date 8/10/2009 Model IGRF200510

KOP - 30° DLS, 181.79° AZI

EOC - Hold to TD

# SECTION DETAILS


S	Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSect	Target
	1	0.0	0.00	0.00	0.0	0.0	0.0	$0.0\bar{0}$	0.00	0.0	
-	2	2892.0	0.00	0.00	2892.0	0.0	0.0	0.00	0.00	0.0	
	3	3191.1	89.71	181.79	3083.0	-189.9	-5.9		181.79	190.0	
	4	5133.0	89.70	181.80	3093.0	-2130.9	-66.8	0.00	133.52	2131.9	Grynberg 11 Federal #6 - BHL

#### **ANNOTATIONS**

TVD	MD	Inc	Azi	+N/-S	+E/-W	VSect D	Departure	Annotation
2892.0	2892.0	0.00	0.00	0.0	0.0	0.0	0.0	KOP - 30° DLS, 181.79° AZI
3083.0	3191.1	89.71	181.79	-189.9	-5.9	190.0	190.0	EOC - Hold to TD
3093.0	5133.0	89.70	181.80	-2130.9	-66.8	2131.9	2131.9	TD at 5133.0' MD

#### WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N/-S	+E/-W	Northing	Easting
Grynberg 11 Federal #6 - BHL	3093.0	-2130.9	-66.8	414003.54	565137.63



# Hydrogen Sulfide Drilling Operations Plan

# Grynberg 11 Federal No. 6

Cimarex Energy Co. of Colorado Unit I, Section 11 T25S-R26E, Eddy County, NM

H₂S equipment will be rigged up at Surface. The plan should be implemented before drilling out from the surface.

1. Due to a one-time encounter on a previous well, an Intra-salt Pocket was charged with H₂S and a burnable amount of hydrocarbons.

#### First Potential Problem Zone:

Initial suspected problem zone	Salt Zone @ 1,333'
Potential Open Flow Capacity	1 mcf
Expected H₂S Concentration	11,000 ppm
100' ROE	6'
500' ROE	3'

Cimarex will have 24-hour H₂S Safety Supervisors on location while drilling the first 2,000' on this well.

# 2. Second Potential Problem Zone:

Initial suspected problem zone	Delaware Mountain Group @ 1,800'
Potential Open Flow Capacity	100 mcf
Expected H₂S Concentration	1,000 ppm
100' ROE	241
500' ROE	11'

- 3. All Company and Contract personnel admitted on location must be trained by a qualified H<sub>2</sub>S safety instructor to the following:
  - A. Characteristics of H<sub>2</sub>S
  - B. Physical effects and hazards
  - C. Proper use of safety equipment and life support systems.
  - D. Principle and operation of H<sub>2</sub>S detectors, warning system and briefing areas.
  - E. Evacuation procedure, routes and first aid.
  - F. Proper use of 30 minute pressure demand air pack.

# 4. H<sub>2</sub>S Detection and Alarm Systems:

A. H<sub>2</sub>S detectors and audio alarm system to be located at bell nipple, end of flow line (mud pit) and on derrick floor or doghouse.

## 5. Windsock and/or wind streamers:

- A. Windsock at mudpit area should be high enough to be visible.
- B. Windsock at briefing area should be high enough to be visible.

# 6. Condition Flags and Signs:

- A. Warning sign on access road to location.
- B. Flags to be displayed on sign at entrance to location. Green flag indicates normal safe condition. Yellow flag indicates potential pressure and danger. Red flag indicates danger (H₂S present in dangerous concentration). Only emergency personnel admitted to location.

# Hydrogen Sulfide Drilling Operations Plan Grynberg 11 Federal No. 6 Cimarex Energy Co. of Colorado Unit I, Section 11 T25S-R26E, Eddy County, NM

# 7. Well control equipment:

A. See exhibit "E"

## 8. Communication:

- A. While working under masks chalkboards will be used for communication.
- B. Hand signals will be used where chalk board is inappropriate.
- C. Two way radio will be used to communicate off location in case of emergency help is required. In most cases cellular telephones will be available at most drilling foreman's trailer or living quarters.

# 9. <u>Drillstem Testing:</u>

No DSTs or cores are planned at this time.

- 10. Drilling contractor supervisor will be required to be familiar with the effects H₂S has on tubular goods and other mechanical equipment.
- 11. If H<sub>2</sub>S is encountered, mud system will be altered if necessary to maintain control of formation. A mud gas seperator will be brought into service along with H<sub>2</sub>S scavengers if necessary.

# H₂S Contingency Plan **Grynberg 11 Federal No. 6** Cimarex Energy Co. of Colorado Unit I, Section 11

T25S-R26E, Eddy County, NM

# **Emergency Procedures**

In the event of a release of gas containing H<sub>2</sub>S, the first responder(s) must:

- ★ Isolate the area and prevent entry by other persons into the 100 ppm ROE.
- ★ Evacuate any public places encompassed by the 100 ppm ROE.
- ★ Be equipped with H<sub>2</sub>S monitors and air packs in order to control the release.
- ★ Use the "buddy system" to ensure no injuries occur during the response.
- ★ Take precautions to avoid personal injury during this operation.
- ★ Contact operator and/or local officials to aid in operation. See list of phone numbers attached.
- ★ Have received training in the:
  - Detection of H₂S, and
  - Measures for protection against the gas,
  - Equipment used for protection and emergency response.

## **Ignition of Gas Source**

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO<sub>2</sub>). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally, the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas.

#### Characteristics of H<sub>2</sub>S and SO<sub>2</sub>

Common	Chemical	Specific	Threshold		Lethal
Name	Formula	Gravity	Limit	Hazardous Limit	Concentration
Hydrogen Sulfide	H <sub>2</sub> S	1.189 Air=1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO <sub>2</sub>	2.21 Air=1	2 ppm	N/A	1000 ppm

## **Contacting Authorities**

Cimarex Energy Co. of Colorado's personnel must liaise with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. Cimarex Energy Co. of Colorado's response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

# H₂S Contingency Plan Emergency Contacts Grynberg 11 Federal No. 6

Cimarex Energy Co. of Colorado Unit I, Section 11 T25S-R26E, Eddy County, NM

Cimarex Energy Co. of Colorado		800-969-4789		
Co. Office and After-Hours Menu				
Key Personnel		Off:		54-b-11-
Name	Title	Office		Mobile
Doug Park	Drilling Manager	972-443-6463		972-333-1407
Dee Smith	Drilling Super	972-443-6491		972-882-1010
Jim Evans	Drilling Super	972-443-6451		972-465-6564
Roy Shirley	Field Super			432-634-2136
PRINCE NO MARKET OF PRINCE	NOTICE OF LINES AS SECURE OF PRINCIPLE OF PRINCIPLE OF ANNUAL OR ANNUAL OR FORMAN OF ANNUAL OR COM-	· * ***** ** ***** ** ***** ** ***** **		4) Market de Serrie de Marche de Amble de de
				th statemen on woman in anyone the especial an a
<u>Artesia</u>				
Ambulance		911		
State Police		575-746-2703		
City Police		575-746-2703		
Sheriff's Office		575-746-9888		
Fire Department	Later	575-746-2701		
Local Emergency Planning Committ		575-746-2122		
New Mexico Oil Conservation Divisi	on	575-748-1283		
Carlsbad				
Ambulance		911		
State Police		575-885-3137		
City Police		575-885-2111		
Sheriff's Office		575-887-7551		
Fire Department		575-887-3798		
Local Emergency Planning Committ	ee	575-887-6544		
US Bureau of Land Management		575-887-6544		
P 1 - F-				
Santa Fe		FOF 47C 0C00		
New Mexico Emergency Response (		505-476-9600		
New Mexico Emergency Response (		505-827-9126		
New Mexico State Emergency Oper	ations Center	505-476-9635		
<u>National</u>	(W. Li	000 424 0002		
National Emergency Response Cent	er (washington, D.C.)	800-424-8802		
<u>Medical</u>				
<u>Iviedical</u> Flight for Life - 4000 24th St.; Lubbo	ock TV	206 742 0011		
Aerocare - R3, Box 49F; Lubbock, TX		806-743-9911 806-747-8923		
Med Flight Air Amb - 2301 Yale Blvd		505-842-4433		
SB Air Med Service - 2505 Clark Car	and the second s	505-842-4949		
35 All IVICA SELVICE - 2303 CIBIN CAL	Loop J.E., Albuque que, Min	303-042-4343		
<u>Other</u>				
Boots & Coots IWC		800-256-9688	or	281-931-8884
Cudd Pressure Control		432-699-0139	or	432-563-3356
Halliburton		575-746-2757		475-703-3330
B.J. Services		575-746-3569		
ס.ט. שכו VICES		2/2-/40-2205		

# Surface Use Plan

# Grynberg 11 Federal No. 6

Cimarex Energy Co. of Colorado Unit I, Section 11 T25S-R26E, Eddy County, NM

- 1. Existing Roads: Area maps, Exhibit "B" is a reproduction of Eddy Co. General Highway Map. Exhibit "C" is a reproduction of a USGS Topographic Map, showing existing roads and proposed roads. All existing roads will be maintained in a condition equal to or better than current conditions. Any new roads will be constructed to BLM specifications.
  - A. Exhibit "A" shows the proposed well site as staked.
  - B. From the junction of Black River Village and John D Forehand, go South on John D Forehand for
     7.1 miles to lease road. On lease road, go West winding North for 1.7 miles to lease road. On
     lease road, go West winding Northwesterly for 0.2 miles to proposed lease road.
- 2. Planned Access Roads: 160.1' of proposed newly constructed on-lease access road.
- 3. Location of Existing Wells in a One-Mile Radius Exhibit A

A. Water wells -

None known

B. Disposal wells -

None known

C. Drilling wells -

None known

D. Producing wells -

As shown on Exhibit "A"

E. Abandoned wells -

As shown on Exhibit "A"

- 4. If on completion this well is a producer, Cimarex Energy Co. of Colorado will furnish maps and/or plats showing on site facilities or off site facilities if needed. This will be accompanied by a Sundry Notice.
- 5. Location and Type of Water Supply:

Water will be purchased locally from a commercial source and trucked over the access roads or piped in flexible lines laid on top of the ground.

6. Source of Construction Material:

If possible, construction will be obtained from the excavation of drill site. If additional material is needed, it will be purchased from a local source and transported over the access route as shown on Exhibit "C".

# 7. Methods of Handling Waste Material:

- A. Drill cuttings will be seperated by a series of solids removal equipment and stored in steel containment pits and then hauled to a state-approved disposal facility.
- B. All trash, junk and other waste material will be contained in trash cages or bins to prevent scattering. When the job is completed all contents will be removed and disposed of in an approved sanitary land fill.
- C. Salts remaining after completion of well will be picked up by supplier including broken sacks.
- D. Sewage from living quarters will drain into holding tanks and be cleaned out periodically. A Porta-John will be provided for the rig crews. This equipment will be properly maintained during the drilling operations and removed upon completion of the well.
- E. Drilling fluids will be contained in steel pits in a closed circulating system. Fluids will be cleaned and reused. Water produced during testing will be contained in the steel pits and disposed of at a state approved disposal facility. Any oil or condensate produced will be stored in test tanks until sold and hauled from the site.

# Surface Use Plan Grynberg 11 Federal No. 6 Cimarex Energy Co. of Colorado Unit I, Section 11

T25S-R26E, Eddy County, NM

# 8. Ancillary Facilities:

A. No camps or airstrips to be constructed.

# 9. Well Site Layout:

- A. Exhibit "D" shows location and rig layout.
- C. Mud pits in the closed circulating system will be steel pits and the cuttings will be stored in steel containment pits.
- D. Cuttings will be stored in steel pits until they are hauled to a state-approved disposal facility.
- E. If the well is a producer, those areas of the location not essential to production facilities will be reclaimed and seeded per BLM requirements.

#### 10. Plans for Restoration of Surface:

Rehabilitation of the location will start in a timely manner after all drilling operations cease. The type of reclamation will depend on whether the well is a producer or a dry hole.

Drainage systems, if any, will be reshaped to the original configuration with provisions made to alleviate erosion. These may need to be modified in certain circumstances to prevent inundation of the location's pad and surface facilities. After the area has been shaped and contoured, topsoil from the spoil pile will be placed over the disturbed area to the extent possible. Revegetation procedures will comply with BLM standards.

If the well is a dry hole, the pad and road area will be recountoured to match the existing terrain. Topsoil will be spread to the extent possible. Revegetation will comply with BLM standards.

Should the well be a producer, the previously noted procedures will apply to those areas which are not required for production facilities.

# 11 Other Information

- A. Topography consists of a sloping plane with loose tan sands. Vegetation is mainly yucca, mesquite and shin oak.
- B. The wellsite is on surface owned by Department of the Interior, Bureau of Land Management. The land is used mainly for farming, cattle ranching, recreational use, and oil and gas production.
- C. An Archaeological survey will be conducted on the location and proposed roads, and this report will be filed with the Bureau of Land Management in the Carlsbad BLM office.
- D. There are no know dwellings within 1½ miles of this location.

Operator Certification Statement
Grynberg 11 Federal No. 6
Cimarex Energy Co. of Colorado
Unit I, Section 11
T25S-R26E, Eddy County, NM

Operator's Representative

Cimarex Energy Co. of Colorado 5215 N. O'Connor blvd ste 1500

Irving, TX 75039

Office Phone: (972) 443-6489

Zeno Farris

**CERTIFICATION:** I hereby certify that the statements and plans made in this APD are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Cimarex Energy Co. of Colorado and/or its contractors/subcontractors and is in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provision of U.S.C. 1001 for the filing of a false statement.

NAME:	Zono Fauch		
	Zeno Farris		
DATE:	August 12, 2009		
TITLE:	Manager Operations Administration		

# PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Cimarex Energy Co. of Colorado			
LEASE NO.:	NM17574			
WELL NAME & NO.:	Grynberg 11 Federal #6			
SURFACE HOLE FOOTAGE:	2460' FSL & 330' FEL			•
BOTTOM HOLE FOOTAGE	330' FSL & 430' FEL		•	
LOCATION:	Section 11, T. 25 S., R 26 E., NMPM	,		
COUNTY:	Eddy County, New Mexico			

# TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

General Provisions
Permit Expiration
Archaeology, Paleontology, and Historical Site
Noxious Weeds
Special Requirements
Cave/karst
<b>⊠</b> Construction
Notification
Topsoil
Closed Loop System
Federal Mineral Material Pits
Well Pads
Roads
<b>⊠</b> Road Section Diagram
<b>☑</b> Drilling
Logging requirements
High cave/karst – possible contingency
Onshore Order 6 – H2S requirements
☐ Production (Post Drilling)
Well Structures & Facilities
Pipelines
Electric Lines
☐ Closed Loop System/Interim Reclamation
Final Ahandonment/Peclamation

# I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

# II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

# III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

# IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

# V. SPECIAL REQUIREMENT(S)

# Cave and Karst

\*\* Depending on location, additional Drilling, Casing, and Cementing procedures may be required by engineering to protect critical karst groundwater recharge areas.

# Cave/Karst Surface Mitigation

The following stipulations will be applied to minimize impacts during construction, drilling and production.

## Construction:

In the advent that any underground voids are opened up during construction activities, construction activities will be halted and the BLM will be notified immediately.

# No Blasting:

No blasting will be utilized for pad construction. The pad will be constructed and leveled by adding the necessary fill and caliche.

# Pad Berming:

The pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the pad. All sides will be bermed.

# Tank Battery Liners and Berms:

Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.

# **Leak Detection System:**

A method of detecting leaks is required. The method could incorporate gauges to measure loss, situating values and lines so they can be visually inspected, or installing electronic sensors to alarm when a leak is present. Leak detection plan will be submitted to BLM for approval.

## **Automatic Shut-off Systems:**

Automatic shut off, check values, or similar systems will be installed for pipelines and tanks to minimize the effects of catastrophic line failures used in production or drilling.

# Cave/Karst Subsurface Mitigation

The following stipulations will be applied to protect cave/karst and ground water concerns:

# **Rotary Drilling with Fresh Water:**

Fresh water will be used as a circulating medium in zones where caves or karst features are expected. SEE ALSO: Drilling COAs for this well.

# **Directional Drilling:**

Kick off for directional drilling will occur at least 100 feet below the bottom of the cave occurrence zone. SEE ALSO: Drilling COAs for this well.

## Lost Circulation:

ALL lost circulation zones from the surface to the base of the cave occurrence zone will be logged and reported in the drilling report.

Regardless of the type of drilling machinery used, if a void of four feet or more and circulation losses greater than 70 percent occur simultaneously while drilling in any cavebearing zone, the BLM will be notified immediately by the operator. The BLM will assess the situation and work with the operator on corrective actions to resolve the problem.

# **Abandonment Cementing:**

Upon well abandonment in high cave karst areas additional plugging conditions of approval may be required. The BLM will assess the situation and work with the operator to ensure proper plugging of the wellbore.

# **Pressure Testing:**

Annual pressure monitoring will be performed by the operator on all casing annuli and reported in a sundry notice. If the test results indicated a casing failure has occurred, remedial action will be undertaken to correct the problem to the BLM's approval.

# VI. CONSTRUCTION

## A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5972 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

# B. TOPSOIL

The operator shall stockpile the topsoil of the well pad. The topsoil shall not be used to backfill the reserve pit and will be used for interim and final reclamation.

## C. CLOSED LOOP SYSTEM

Closed Loop System: v-door east

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

## D. FEDERAL MINERAL MATERIALS PIT

If the operator elects to surface the access road and/or well pad, mineral materials extracted during construction of the reserve pit may be used for surfacing the well pad and access road and other facilities on the lease.

Payment shall be made to the BLM prior to removal of any additional federal mineral materials from any site other than the reserve pit. Call the Carlsbad Field Office at (575) 234-5972.

# E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

# F. ON LEASE ACCESS ROADS

## Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed thirty (30) feet.

# Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

# Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.


# Ditching

Ditching shall be required on both sides of the road.

#### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:

## Standard Turnout - Plan View




# Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch

# **Cross Section Of Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

# Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

400 foot road with 4% road slope: 400'/4% + 100' = 200' lead-off ditch interval **Culvert Installations** 

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

## Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

## Fence Requirement

Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

# Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

ranshan
Intervisible numbers shall be considered on
of strigle lane sands on oil bind curves with
add hand tuncuts as needed to keep spacing
below 1000 feet Typical Turnout Plan embarkmeni slope Ç\* - 4° 3:1 **Embankment Section** 5pe earth surface 03 - .05 h/h 02 - .04 5/h agalegale systac paved surface .02 - .03 ft/ft Depth measured how the barrar of the ditch **Side Hill Section** fravel surface --[slope 2 - 4°---] Typical Outsloped Section Typical Inslope Section

Figure 1 – Cross Sections and Plans For Typical Road Sections

# VII. DRILLING.

# A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified a minimum of 4 hours in advance for a representative to witness:

- a. Spudding well
- b. Setting and/or Cementing of all casing strings
- c. BOPE tests

# **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220, (575) 361-2822

- 1. A Hydrogen Sulfide (H2S) Drilling Plan should be activated 500 feet prior to drilling into the Delaware formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.
- 2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
- 3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
- 4. The record of the drilling rate along with the CAL/GR/N well log run from TD to surface will be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

# B. CASING

Changes to the approved APD casing and cement program require submitting a sundry and receiving approval prior to work. Failure to obtain approval prior to work will result in an Incident of Non-Compliance being issued.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

HIGH CAVE/KARST – CONTINGENCY CASING WILL BE REQUIRED IF LOST CIRCULATION OCCURS WHILE DRILLING THE SURFACE HOLE. THE SURFACE HOLE WILL HAVE TO BE REAMED AND A LARGER CASING INSTALLED. IF LOST CIRCULATION OCCURS WHILE DRILLING THE 7-7/8" HOLE AND THE CONTINGENCY CASING HAS NOT BEEN SET, THE CEMENT PROGRAM FOR THE 5-1/2" CASING WILL NEED TO BE MODIFIED AND THE BLM IS TO BE CONTACTED. A MINIMUM OF TWO CASING STRINGS CEMENTED TO SURFACE ARE REQUIRED IN HIGH CAVE/KARST AREAS.

Possible lost circulation in the Delaware.

Salado at surface so brine water should be used for drilling the surface hole and fresh water or cut brine water for the intermediate hole.

- 1. The 8-5/8 inch surface casing shall be set at approximately 440 feet and cemented to the surface.
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with a surface log readout will be used or a cement bond log shall be run to verify the top of the cement.
  - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
  - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
  - d. If cement falls back, remedial cementing will be done prior to drilling out that string.

- 2. The minimum required fill of cement behind the 5-1/2 inch intermediate casing is:

  Cement to surface. If cement does not circulate see B.1.a, c-d above.

  Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst concerns.
- 3. The minimum required fill of cement behind the 2-7/8 inch production casing is:
  - Cement not required using Peak System completion assembly. Completion assembly to be set a minimum of 100' inside 5-1/2" casing.
- 4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

## C. PRESSURE CONTROL

- 1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
- 2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi. Operator installing 5M system and testing as 3M.
- 3. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
  - a. The tests shall be done by an independent service company.
  - b. The results of the test shall be reported to the appropriate BLM office.
  - c. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
  - d. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug.
  - e. Effective November 1, 2008, no variances will be granted on reduced pressure tests on the surface casing and BOP/BOPE. Onshore Order 2 requirements will be in effect.

# D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

WWI 091509

# VIII. PRODUCTION (POST DRILLING)

# A. WELL STRUCTURES & FACILITIES

# **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

# **Containment Structures**

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

# **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color Shale Green, Munsell Soil Color Chart # 5Y 4/2

# B. PIPELINES

# C. ELECTRIC LINES

# IX. INTERIM RECLAMATION & RESERVE PIT CLOSURE

## A. INTERIM RECLAMATION

If the well is a producer, interim reclamation shall be conducted on the well site in accordance with the orders of the Authorized Officer. The operator shall submit a Sundry Notices and Reports on Wells (Notice of Intent), Form 3160-5, prior to conducting interim reclamation.

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

The operators should work with BLM surface management specialists to devise the best strategies to reduce the size of the location. Any reductions should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

# Seed Mixture 1, for Loamy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be <u>no</u> primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (small/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains lovegrass (Eragrostis intermedia)	0.5
Sand dropseed (Sporobolus cryptandrus	1.0
Sideoats grama (Bouteloua curtipendula	5.0

<sup>\*</sup>Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

# X. FINAL ABANDONMENT & REHABILITATION REQUIREMENTS

Upon abandonment of the well and/or when the access road is no longer in service the Authorized Officer shall issue instructions and/or orders for surface reclamation and restoration of all disturbed areas.

On private surface/federal mineral estate land the reclamation procedures on the road and well pad shall be accomplished in accordance with the private surface land owner agreement.